Shoreline Stabilization Improvements

148 Brackett Road Portsmouth, New Hampshire

Assessor's Parcel 206 - 18 & 19 ISSUED FOR NHDES WETLANDS PERMIT/PORTSMOUTH C.U.P.

APPROVED BY THE PORTSMOUTH PLANNING BOAR

CHAIRMAN DATE


Plan Issue Date:

AUGUST 26, 2020

Owner / Applicant:

The Pamela N. Blalock
Trust Agreement
Pamela N. Blalock, Trustee
148 Brackett Road
Portsmouth, NH 03801

Civil Engineer:



Consultant:

Dr. David Burdick
University of New Hampshire
School of Marine Science and Ocean Engineering
Natural Resources & the Environment
James Hall Rm 266
Durham, NH 03824
Phone: (603) 862-5129

Sur veyor:


James Verra and Associates, Inc.

LAND SURVEYORS

101 SHATTUCK WAY - SUITE 8 NEWINGTON, N.H. 03801- 7876 603-436-3557

Wetland Scientist:


Joe Noel P.O. BOX 174 South Berwick, ME 03908 Phone: (207) 384-5587




LOCUS MAP
Not To Scale

Sheet Index Title	$Sheet \\ No.:$	Rev.	Date
Existing Conditions Plan	C-1	0	08/26/20
Grading, Drainage & Wetland Impact Plan	C-2	0	08/26/20
Planting Plan	C - 3	0	08/26/20
Detail Sheet	C - 4	0	08/26/20
Detail Sheet	C - 5	0	08/26/20

503






08/26/20

PAMELA N. BLALOCK, TRUSTEE

ASSESSOR'S PARCEL 206-19

ASSESSOR'S PARCEL 206-19



SEDIMENT AND EROSION CONTROL NOTES

PROJECT NAME AND LOCATION

148 BRACKETT ROAD PORTSMOUTH, NEW HAMPSHIRE TAX MAP 206 LOTS 18 & 19

LATITUDE: 43°04'05" N LONGITUDE: 70°45'04" W

OWNER/APPLICANT:

PAMELA N. BLALOCK TRUST AGREEMENT, PAMELA N. BLALOCK, TRUSTEE 148 BRACKETT ROAD PORTSMOUTH, NH 03801

DESCRIPTION

The project consists of the repair of an existing embankment and dock, installation of a raingarden and construction of seven restoration berms with associated planting.

DISTURBED AREA

The total area to be disturbed for the project is approximately $\pm 13,750$ S.F. (± 0.32 acres). USEPA NPDES Phase II compliance not required.

PROJECT PHASING

The proposed project will be completed in one phase.

NAME OF RECEIVING WATER

The site drains to Little Harbor (tidal waters).

SEQUENCE OF MAJOR ACTIVITIES

- 1. Install temporary erosion control measures, including perimeter controls, as noted on the plan. All temporary erosion control measures shall be maintained in good working condition for the duration of the project.
- Remove and store dock floats.
- . Remove landscaping, strip loam and stockpile. 4. Construct shoreline stabilization per details. This shall be performed in multiple phases in
- order to limit the area of unstabilized shoreline at any given time. 5. Repair dock footings.
- 6. Rough grade site including placement of borrow materials for restoration berms. 7. Construct drainage structure, piping and check valve.
- 8. Construct raingarden.
- 9. Loam (6" min) and seed all disturbed areas not otherwise stabilized.
- 10. Install plantings per Planting Plan.
- 11. When all construction activity is complete and site is stabilized, remove all temporary erosion control measures and any sediment that has been trapped by these devices.

TEMPORARY EROSION & SEDIMENT CONTROL AND STABILIZATION PRACTICES

All work shall be in accordance with state and local permits. Work shall conform to the practices described in the "New Hampshire Stormwater Manual, Volumes 1 - 3", issued December 2008, as amended. As indicated in the sequence of Major Activities, perimeter controls shall be installed prior to commencing any clearing or grading of the site. Structural controls shall be installed concurrently with the applicable activity. Once construction activity ceases permanently in an area and permanent measures are established, perimeter controls shall be removed.

During construction, runoff will be diverted around the site with stabilized channels where possible. Sheet runoff from the site shall be filtered through appropriate perimeter controls. All storm drain inlets shall be provided with inlet protection measures.

Temporary and permanent vegetation and mulching is an integral component of the erosion and sedimentation control plan. All areas shall be inspected and maintained until vegetative cover is established. These control measures are essential to erosion prevention and also reduce costly rework

Temporary vegetation shall be maintained in these areas until permanent seeding is applied. Additionally, erosion and sediment control measures shall be maintained until permanent vegetation is

INSTALLATION, MAINTENANCE AND INSPECTION PROCEDURES FOR TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES

A. GENERAL

These are general inspection and maintenance practices that shall be used to implement the

- 1. The smallest practical portion of the site shall be denuded at one time. 2. All control measures shall be inspected at least once each week and following any storm event
- of 0.5 inches or greater. 3. All measures shall be maintained in good working order; if a repair is necessary, it will be
- initiated within 24 hours. 4. Built-up sediment shall be removed from perimeter barriers when it has reached one-third the
- height of the barrier or when "bulges" occur. . All diversion dikes shall be inspected and any breaches promptly repaired.
- 6. Temporary seeding and planting shall be inspected for bare spots, washouts, and unhealthy
- 7. The owner's authorized engineer shall inspect the site on a periodic basis to review compliance
- with the Plans. 8. An area shall be considered stable if one of the following has occurred:
- a. Base coarse gravels have been installed in areas to be paved; b. A minimum of 85% vegetated growth as been established;
- c. A minimum of 3 inches of non-erosive material such as stone of riprap has been installed;
- d. Erosion control blankets have been properly installed. 9. The length of time of exposure of area disturbed during construction shall not exceed 45 days.

B. MULCHING

Mulch shall be used on highly erodible soils, on critically eroding areas, on areas where conservation of moisture will facilitate plant establishment, and where shown on the plans.

- 1. Timing In order for mulch to be effective, it must be in place prior to major storm events. There are two (2) types of standards which shall be used to assure this: a. Apply mulch prior to any storm event. This is applicable when working within 100 feet of
- wetlands. It will be necessary to closely monitor weather predictions, usually by contacting the National Weather Service in Concord, to have adequate warning of significant storms.
- b. Required Mulching within a specified time period. The time period can range from 21 to 28 days of inactivity on a area, the length of time varying with site conditions. Professional judgment shall be used to evaluate the interaction of site conditions (soil erodibility, season of year, extent of disturbance, proximity to sensitive resources, etc.) and the potential impact of erosion on adjacent areas to choose an appropriate time restriction.

INSTALLATION, MAINTENANCE AND INSPECTION PROCEDURES FOR TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES (CONTINUED)

2. Guidelines for Winter Mulch Application —

Rate per 1,000 s.f. <u>Use and Comments</u> Hay or Straw 70 to 90 lbs. Must be dry and free from mold. May be used with plantings. Wood Chips or 460 to 920 lbs. Used mostly with trees Bark Mulch and shrub plantings. Jute and Fibrous As per manufacturer Used in slope areas,

Blanket Crushed Stone Spread more than Effective in controlling wind and water erosion.

Specifications

1/4" to 1-1/2" dia. 1/2" thick Erosion Control Mix 2" thick (min) * The organic matter content is between 80 and 100%, dry weight basis.

> a 6"screen and a minimum of 70 %. maximum of 85%, passing a 0.75" screen. *The organic portion needs to be fibrous and elongated. *Large portions of silts, clays or fine sands are not acceptable in the mix. * Soluble salts content is less than 4.0 mmhos/cm. *The pH should fall between 5.0 and 8.0.

* Particle size by weight is 100% passina

water courses and other Control

- 3. Maintenance All mulches must be inspected periodically, in particular after rainstorms, to check for rill erosion. If less than 90% of the soil surface is covered by mulch, additional mulch shall be immediately applied.
- C. PERMANENT SEEDING -

Matting (Erosion

- 1. Bedding stones larger than $1\frac{1}{2}$, trash, roots, and other debris that will interfere with seeding and future maintenance of the area should be removed. Where feasible, the soil should be tilled to a depth of 5" to prepare a seedbed and mix fertilizer into the soil.
- 2. Fertilizer lime and fertilizer should be applied evenly over the area prior to or at the time of seeding and incorporated into the soil. Kinds and amounts of lime and fertilizer should be based on an evaluation of soil tests. When a soil test is not available, the following minimum amounts should be applied:

Agricultural Limestone @ 100 lbs. per 1,000 s.f. 10-20-20 fertilizer @ 12 lbs. per 1,000 s.f.


3. Seed Mixture (recommended)

Follow Planting Plan

4. Sodding shall not be permitted for this project.

WINTER CONSTRUCTION NOTES

- 1. All proposed vegetated areas which do not exhibit a minimum of 85% vegetative growth by October 15th, or which are disturbed after October 15th, shall be stabilized by seeding and installing erosion control blankets on slopes greater than 3:1, and elsewhere seeding and placing 3 to 4 tons of mulch per acre, secured with anchored netting. The installation of erosion control blankets or mulch and netting shall not occur over accumulated snow or on frozen ground and shall be completed in advance of thaw or spring melt events:
- 2. All ditches or swales which do not exhibit a minimum of 85% vegetative growth by October 15th, or which are disturbed after October 15th, shall be stabilized temporarily with stone or erosion control blankets appropriate for the design flow conditions; and
- 3. After November 15th, incomplete road or parking surfaces where work has stopped for the winter season shall be protected with a minimum of 3 inches of crushed gravel per NHDOT




NOTES:

TURBIDITY BARRIER TO BE SECURELY ANCHORED TO SHORE AT EACH END. TYPICAL SPECIFICATIONS -FABRIC: 20 MIL., 18 OZ. NOMINAL PVC-COVERED POLYESTER OR NYLON REINFORCED VINYL. ROPE: 5/8" POLY ROPE, 600# BREAK STRENGTH, WITH #5 BRASS OR STAINLESS STEEL GROMMETS. CABLE: 5/16" GALVANIZED STEEL 7x19 LOAD CABLE w/ PVC COATING, 9800# BREAK STRENGTH. BALLAST: 5/16" GALVANIZED CHAIN BALLAST IN BOTTOM OF CURTAIN. PLATES: ALUMINUM STRESS PLATES AT ALL CABLE AND CHAIN TERMINATIONS

FLOTATION: 8" CLOSED-CELL SOLID PLASTIC, 17 LB./FT MIN. BUOYANCY.

TURBIDITY BARRIER


NOT TO SCALE



- FOR EASIER INSTALLATION, LOWER WATER FROM LEVEL A TO LEVEL B BEFORE INSTALLATION OR WAIT FOR APPROPRIATE TIDAL CONDITIONS.
- PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.
- 3. BEGIN AT THE TOP OF THE SHORELINE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH WITH APPROXIMATELY 12" OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAKES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAKING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE BLANKET.
- 4. ROLL BLANKETS EITHER (A) DOWN THE SHORELINE FOR LONG BANKS (TOP TO BOTTOM) OR (B) HORIZONTALLY ACROSS THE SHORELINE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAKES IN APPROPRIATE LOCATIONS AS RECOMMENDED BY THE MANUFACTURER.
- 5. THE EDGES OF ALL HORIZONTAL AND VERTICAL BLANKET SEAMS MUST BE STAKED WITH APPROXIMATELY 2"-5" OVERLAP. TO ENSURE PROPER SEAM ALIGNMENT BETWEEN ADJACENT BLANKETS, PLACE THE EDGE OF THE OVERLAPPING BLANKET EVEN WITH THE SEAM STITCH ON THE PREVIOUSLY INSTALLED BLANKET. SECURE ALL OVERLAPS WITH STAKES SPACED 12" APART. NOTE: SEAM OVERLAP SHOULD BE SHINGLED WITH UPHILL BLANKETS OVERLAPPING DOWNHILL
- 6. THE EDGE OF THE BLANKET AT OR BELOW NORMAL WATER LEVEL MUST BE ANCHORED BY PLACING THE BLANKET IN A 12" DEEP BY 6" WIDE ANCHOR TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAKES SPACED APPROXIMATELY 12" APART IN THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAKING WITH STONE OR SOIL. NOTE: IN LOOSE SOIL CONDITIONS, THE USE OF STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY ANCHOR THE
- 7. ALL BLANKET FASTENERS SHALL BE BIODEGRADABLE.

EROSION CONTROL BLANKET

NOT TO SCALE




. SILTSOXX MAY BY USED IN PLACE OF SILT FENCE OR OTHER SEDIMENT BARRIERS. 2. ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.

3. SILTSOXX COMPOST/SOIL/ROCK/SEED FILL MATERIAL SHALL BE ADJUSTED AS NECESSARY TO MEET THE REQUIREMENTS OF THE SPECIFIC APPLICATION.

4. ALL SEDIMENT TRAPPED BY SILTSOXX SHALL BE DISPOSED OF PROPERLY.

TUBULAR SEDIMENT BARRIER

NOT TO SCALE



SLOPE AS NECESSARY TO APPROXIMATELY MATCH EXISTING EMBANKMENT GRADE (1:1.5 MAX.) ELEV. 1.0' MTL - 0.35'EXISTING GRADL ±2'-WIDE ROCK SILL

NOTES:

MLW - 4.66'

MLLW -5.00'


1. ON SITE ROCK SHALL BE USED TO THE GREATEST EXTENT POSSIBLE. WHERE REQUIRED, IMPORTED STONES SHALL GENERALLY BE LESS ANGULAR IN SHAPE -USE OF MANUFACTURED RIPRAP WILL NOT BE ACCEPTED.

BOTTOM ANCHORING


PER DETAILS

SHORELAND STABILIZATION

NOT TO SCALE



133 Court Street Portsmouth, NH 03801 (603) 433-2335 www.altus-eng.com



ISSUED FOR:

ISSUE DATE:

O INITIAL SUBMISSION

APPROVAL

AUGUST 26, 2020

REVISIONS DATE NO. DESCRIPTION

EBS

08/26/2

NOT FOR CONSTRUCTION

EBS DRAWN BY:. EDW APPROVED BY: 5033-SITE.DWG DRAWING FILE: __

SCALE:

 $22" \times 34" - 1" = 20"$ $11" \times 17" - 1" = 40"$

<u> OWNER/APPLICANT:</u>

PAMELA N. BLALOCK TRUST **AGREEMENT** PAMELA N. BLALOCK, TRUSTEE 148 BRACKETT ROAD PORTSMOUTH, N.H.

ASSESSOR'S PARCEL 206-18 ASSESSOR'S PARCEL 206-19

PROJECT:


SHORELAND **STABILIZATION**

148 BRACKETT ROAD PORTSMOUTH, N.H.

ASSESSOR'S PARCEL 206-18 ASSESSOR'S PARCEL 206-19

DETAIL SHEET

SHEET NUMBER:



5. THIS DETAIL IS SCHEMATIC IN NATURE AND IS INTENDED TO PROVIDE A


INTERPRETED AS A COMPLETE DEPICTION OF ALL MATERIALS OR WORK


REQUIRED TO COMPLETE CONSTRUCTION. THE CONTRACTOR SHALL BE

RECONSTRUCT THE EXISTING FACILITIES. IT SHALL IN NO WAY BE

GENERALIZED REPRESENTATION OF THE WORK REQUIRED TO REPAIR AND/OR


RESPONSIBLE FOR CONFORMING TO ALL APPLICABLE CODES AND STANDARDS.






TYPICAL RESTORATION BERM CROSS SECTION

NOT TO SCALE



]_	12" DOMED "BEEHIVE GRATE
INLET AND OUTLET PIPES PER PLANS		-	12" ADS DRAIN BASI (OR EQUAL)
	12" SUMP	12" MIN	١.
			3/4" CRUSHED STON BEDDING
	WIIN.		COMPACTED NATIVE SUBGRADE
NOTES:			



BACKFILL MATERIAL BELOW PAVED OR CONCRETE AREAS, BEDDING MATERIAL, AND SAND BLANKET SHALL
BE COMPACTED TO NOT LESS THAN 95% OF AASHTO T 99, METHOD C. SUITABLE BACKFILL MATERIAL
BELOW LOAM AREAS SHALL BE COMPACTED TO NOT LESS THAN 90% OF AASHTO T 99, METHOD C.

SAND E	BLANKET/BARRIER	CRUSHED	STONE BEDDING *
SIEVE SIZE	% FINER BY WEIGHT	SIEVE SIZE	% PASSING BY WEIGHT
1/2" 200	90 - 100 0 - 15	SIZE #67	100 90 - 100 20 - 55 0 - 10 0 - 5 IT TO STANDARD STONE - SECTION 703 OF ANDARD SPECIFICATIONS

DESIGN	REFERENCES

INVASIVE SPECIES.

UNH STORMWATER CENTER

MAINTENANCE REQUIREMENTS

BY SUCH INSPECTION.

. DOCK DIMENSIONS TO MATCH EXISTING WOOD STRUCTURES. THE

REQUIRED MEASUREMENTS AS NEEDED.

MANUFACTURERS SPECIFICATIONS.

DOCK REPAIR DETAIL

CONTRACTOR SHALL PERFORM THEIR OWN SITE INSPECTION AND TAKE ALL

ALL FASTENERS TO BE GALVANIZED OR STAINLESS STEEL AND INSTALLED

WHERE AND AS REQUIRED PER COMMON CONSTRUCTION PRACTICES AND THE

• EPA (1999A)

TYPICAL RAINGARDEN

NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 2, DECEMBER 2008 AS AMENDED.

TO REMOVAL OF ACCUMULATED SEDIMENTS OR RECONSTRUCTION OF THE FILTER MEDIA.

5. DO NOT TRAFFIC EXPOSED SURFACES OF RAINGARDEN WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE,

PERFORM EXCAVATION ACTIVITIES WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE BASIN.

SYSTEMS SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND FOLLOWING ANY RAINFALL EXCEEDING

PRETREATMENT MEASURES SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND CLEANED OF

ACCUMULATED SEDIMENT AS WARRANTED BY INSPECTION, BUT NO LESS THAN ONCE ANNUALLY.

AT LEAST ONCE ANNUALLY, SYSTEM SHOULD BE INSPECTED FOR DRAWDOWN TIME. IF BIORETENTION SYSTEM DOES NOT DRAIN WITHIN 72-HOURS FOLLOWING A RAINFALL EVENT, THEN A QUALIFIED.

VEGETATION SHOULD BE INSPECTED AT LEAST ANNUALLY, AND MAINTAINED IN HEALTHY CONDITION,

PROFESSIONAL SHOULD ASSESS THE CONDITION OF THE FACILITY TO DETERMINE MEASURES REQUIRED TO

RESTORE FILTRATION FUNCTION OR INFILTRATION FUNCTION (AS APPLICABLE), INCLUDING BUT NOT LIMITED

INCLUDING, PRUNING, REMOVAL, AND REPLACEMENT OF DEAD OR DISEASED VEGETATION, AND REMOVAL OF

2.5 INCHES IN A 24-HOUR PERIOD, WITH MAINTENANCE OR REHABILITATION CONDUCTED AS A WARRANTED

	Percent of	Gradation of material	
Component Material	Mixture by Volume	Sieve No.	Percent by Weight Passing Standard Sieve
F	ilter Media Opt	ion A	
ASTM C-33 concrete sand	50 to 55		
Loamy sand topsoil, with fines as indicated	20 to 30	200	15 to 25
Moderately fine shredded bark or wood fiber mulch, with fines as indicated	20 to 30	200	< 5
F	ilter Media Opt	ion B	
Moderately fine shredded bark or wood fiber mulch, with fines as indicated	20 to 30	200	< 5
Loamy coarse sand	70 to 80	10	85 to 100
		20	70 to 100
		60	15 to 40
		200	8 to 15

FILTER MEDIA MIXTURES

COMPASUBGR

15 to 25

NOTES:

1. FRAMES AND GRATES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05.
2. DRAIN BASIN TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN AND DETAILS.

3. DRAINAGE CONNECTION STUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D3212 FOR CORRUGATED HDPE, N-12HP AND PVC SEWER.

4. INLINE DRAIN TO BE PVC DIAMETER AS SPECIFIED AND AS MANUFACTURED BY ADS OR APPROVED EQUAL.

5. THE CONTRACTOR SHALL INSTALL THE DRAIN BASIN PER THE MANUFACTURER'S RECOMMENDATIONS AND AS SHOWN ON THE DRAWINGS.

NOT TO SCALE

NOT TO SCALE

YARD DRAIN AND GRATE

NOT TO SCALE


DRAINAGE TRENCH SECTION

NOT TO SCALE

ALTUS
NGINEERING, INC.

Court Street Portsmouth, NH 03801

133 Court Street Portsmouth, NH 03801 (603) 433-2335 www.altus-eng.com



ISSUED FOR:

APPROVAL

SSUE DATE:

AUGUST 26, 2020

REVISIONS
NO. DESCRIPTION

O INITIAL SUBMISSION

EBS

08/26/2

NOT FOR CONSTRUCTION

DRAWN BY: ______EBS

APPROVED BY: ______EDW

DRAWING FILE: _____5033-SITE.DWG

SCALE:

<u>OWNER/APPLICANT:</u>

PAMELA N. BLALOCK TRUST
AGREEMENT
PAMELA N. BLALOCK, TRUSTEE
148 BRACKETT ROAD
PORTSMOUTH, N.H.

ASSESSOR'S PARCEL 206-18 ASSESSOR'S PARCEL 206-19

PROJECT:

SHORELAND STABILIZATION

148 BRACKETT ROAD PORTSMOUTH, N.H.

ASSESSOR'S PARCEL 206-18

ASSESSOR'S PARCEL 206-19

TITLE:

DETAIL SHEET

SHEET NUMBER:

C-5