



**Civil  
Site Planning  
Environmental  
Engineering**

133 Court Street  
Portsmouth, NH  
03801-4413

February 16, 2021

Juliet T. H. Walker, Planning Director  
City of Portsmouth Municipal Complex  
1 Junkins Avenue  
Portsmouth, New Hampshire 03801

**Re: Application for Subdivision  
"Watson's Landing"  
Assessor's Map 209, Lot 33  
1 Clark Drive  
Altus Project No. 5090**

Dear Juliet,

Enclosed please find revised application materials for the March 2, 2021 TAC hearing. Pursuant to comments received at the February 2, 2021 TAC hearing, the applicant has decided to continue with the project as a private subdivision. This will require that a homeowner's association be formed to handle maintenance of the roadway and stormwater facilities. In the intervening time, we have also met with the Trees and Greenery Committee and the Conservation Commission and have incorporated their comments as well.

Please call me if you have any questions or need any additional information.

Sincerely,

**ALTUS ENGINEERING, INC.**

A handwritten signature in red ink, appearing to read "EBS: [Signature]", is written over a dashed line.

Erik B. Saari  
Vice President

ebs/5090-APP-PB-CovLtr-021621

Enclosures

eCopy: Robert Watson  
Eric Reuter

# WATSON'S LANDING Residential Subdivision

**Owner/Applicant:**

FREDERICK W. WATSON REVOCABLE TRUST  
Robert D. Watson, Trustee

53 Sleepy Hollow Drive  
Greenland, NH 03840  
(603) 501-0966

**Civil Engineer:**



133 Court Street  
(603) 433-2335  
Portsmouth, NH 03801  
www.altus-eng.com

**Surveyor:**

KNIGHT HILL LAND SURVEYING SERVICES, INC.  
c/o David Hislop, LLS

34 Old Post Road  
Newington, NH 03801  
(603) 436-1330

**Soil Scientist/Wetland Scientist:**

MICHAEL CUOMO, CWS

6 York Pond Road  
York, ME 03909  
(207) 363-4532

**Acoustics Consultant:**

REUTER ASSOCIATES, LLC  
Eric L. Reuter, FASA, INCE Bd. Cert., Principal

10 Vaughan Mall, Suite 201A  
Portsmouth, NH 03801  
(603) 430-2081


1 Clark Drive  
Portsmouth, New Hampshire

Assessor's Parcel 209, Lot 33

ISSUED FOR TAC

Plan Issue Date:

DECEMBER 1, 2020	TAC WORK SESSION
JANUARY 18, 2021	TAC
FEBRUARY 16, 2021	TAC



LOCUS NOT TO SCALE

**Sheet Index**

Title	Sheet No.:	Rev.	Date
Topo/Boundary Worksheet (by KHLSS)	1 of 1	0	11/04/20
Demolition Plan	C-1	2	02/16/21
Subdivision Plan	C-2	2	02/16/21
Roadway Plan & Profile	C-3	2	02/16/21
Stormwater Management Plan	C-4	2	02/16/21
Utility Plan	C-5	2	02/16/21
Conditional Use Permit Plan	C-6	1	02/16/21
Planting Plan	C-7	0	02/16/21
Detail Sheet	D-1	2	02/16/21
Detail Sheet	D-2	2	02/16/21
Detail Sheet	D-3	2	02/16/21
Detail Sheet	D-4	1	01/18/21

**Permit Summary:**


	Submitted	Received
NHDES Wetlands Permit	January 27, 2021	
NHDES Shoreland Permit	January 27, 2021	
Notice of Intent	By Contractor	

CURVE TABLE					
CURVE	LENGTH	RADIUS	DELTA	CHORD	CHORD BEARING
C1	31.94'	25.00'	73°12'04"	29.81'	N25°06'34"E
C2	66.34'	50.00'	76°01'12"	61.58'	N26°31'08"E
C3	28.81'	750.00'	2°12'03"	28.81'	S68°24'50"W
C4	106.40'	180.00'	33°52'00"	104.85'	S52°34'52"W
C5	39.27'	25.00'	90°00'01"	35.36'	S09°21'09"E
C6	135.95'	230.00'	33°52'00"	133.98'	N52°34'52"E
C7	95.35'	700.00'	7°48'16"	95.28'	N65°36'44"E

LINE TABLE		
LINE	LENGTH	BEARING
L1	12.71'	N25°29'20"W
L2	17.51'	S35°38'52"W
L3	42.51'	N35°38'52"E
L4	7.86'	N69°30'52"E
L5	7.86'	S69°30'52"W

- GENERAL NOTES:**
- 1.) THE EXISTING DETAILS SHOWN WERE LOCATED BY KNIGHT HILL LAND SURVEYING SERVICES, INC. IN OCTOBER 2020.
  - 2.) ELEVATION DATUM NAVD88 ESTABLISHED FROM CUTTS STREET RECONSTRUCTION BENCH MARK SPIKES FOUND IN POLES ACROSS FROM SUBJECT PROPERTY AS LABELED.
  - 3.) OWNER OF RECORD: FREDERICK W. WATSON REVOCABLE TRUST OF 1998. TAX MAP 209 LOT 33. RECORD DEED: RCRD BOOK 5200 PG. 1329. LOT AREA TO SALT MARSH: 3.1± ACRES.
  - 4.) SUBJECT LOT SUBJECT TO AND BENEFITS FROM AN ELECTRIC AND COMMUNICATIONS SERVICE & MAINTENANCE EASEMENT TO NH ELECTRIC CO. & NEW ENGLAND TELEPHONE & TELEGRAPH CO. PER 1957 DEED BK. 1447 PG. 227. THE DEED HAS NO EASEMENT WIDTH DETAILS.
  - 5.) SUBJECT LOT SUBJECT TO RIGHTS TO THE STATE OF NH TO MAINTAIN SLOPES AND EMBANKMENTS PER 1969 DEED BK. 1957 PG. 146. SEE STATE PLANS PER PLAN REFERENCE 1.


- PLAN REFERENCES:**
- 1.) "STATE OF NH DPW FEDERAL AID PROJECT I-95-(24)14 RIGHT OF WAY PLANS" NH PROJ. P-3875E, NH PROJ. P-3875H-1, NH PROJ. P-3875I, NH PROJ. P-5875B, NH PROJ. P-5875B(2) & NH PROJ. 5875B(3).
  - 2.) "PLAN OF LOTS PORTSMOUTH, NH FOR HERBERT W. POPE" BY JOHN W. DURGIN, REVISED JAN. 1974, RCRD PLAN D-4261.
  - 3.) "LOT LINE REVISION PORTSMOUTH NH FOR HERBERT W. POPE" BY JOHN W. DURGIN ASSOC., DATED JUNE 12, 1979, RCRD PLAN C-8792.
  - 4.) "EASEMENT PLAN OF LAND IN PORTSMOUTH, NH" BY WHITMAN & HOWARD, INC., DATED APRIL 4, 1985, RCRD PLAN D-13793.
  - 5.) "SUBDIVISION PLAN OF LAND IN PORTSMOUTH, NH" BY WHITMAN & HOWARD, INC., DATED OCT. 15, 1985, RCRD PLAN B-14767.
  - 6.) "LOT LINE ADJUSTMENT PLAN 200 CHASE DR. & 373 CUTTS AVE." BY JAMES VERA & ASSOC., DATED 5-23-2013, RCRD PLAN D-38287.
  - 7.) "PLAN OF BERSUM GARDENS FOR MARGO CONST. CO., PORTSMOUTH, NH" BY JOHN W. DURGIN, DATED OCT. 1955, RCRD PLAN 02178.
  - 8.) "PLAN OF LAND PORTSMOUTH NH FOR JOSEPH LAMB" BY JOHN W. DURGIN, DATED DEC. 1968, RCRD PLAN 1303.
  - 9.) "IMPROVEMENTS TO MAPLEWOOD AVE. UTILITY PLAN & PROFILE - CENTRAL & CUTTS FOR PORTSMOUTH DPW" BY GPI, CERTIFIED 1-18-18, SHEETS 52 & 53 OF 184.




TOPO/BOUNDARY WORKSHEET  
 1 CLARK DRIVE (PRIVATE)  
 TAX MAP 209 LOT 33  
 PORTSMOUTH, NEW HAMPSHIRE  
 COUNTY OF ROCKINGHAM  
 NOV. 4, 2020 SCALE 1" = 40' PROJECT # 2222PNTS

PREPARED FOR:  
 ALTUS ENGINEERING, INC.  
 ATTN: ERIK SARRI, PE.  
 133 COURT STREET  
 PORTSMOUTH, NH, 03801  
 esaari@altus-eng.com  
 603-433-2335

PREPARED BY:  
 KNIGHT HILL LAND SURVEYING  
 SERVICES, INC.  
 C/O DAVID HISLOP, LLS  
 34 OLD POST RD.  
 NEWINGTON, NH, 03801  
 dave@khlandsurveying.com  
 603-436-1330





REVISION 11-5-2020 CHANGE ELEVATION DATUM FROM NAVD29 TO NAVD88



**DEMOLITION NOTES**

1. CITY DEMOLITION PERMIT REQUIRED PRIOR TO ANY DEMOLITION ACTIVITIES. CONTRACTOR IS NOTIFIED THAT THIS PERMIT PROCESS MAY REQUIRE A 30-DAY LEAD TIME.
2. CONTRACTOR SHALL PRESERVE AND PROTECT ALL EXISTING UTILITIES SCHEDULED TO REMAIN.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE TIMELY NOTIFICATION OF ALL PARTIES, CORPORATIONS, COMPANIES, INDIVIDUALS AND STATE AND LOCAL AUTHORITIES OWNING AND/OR HAVING JURISDICTION OVER ANY UTILITIES RUNNING TO, THROUGH OR ACROSS AREAS TO BE DISTURBED BY DEMOLITION AND/OR CONSTRUCTION ACTIVITIES WHETHER OR NOT SAID UTILITIES ARE SUBJECT TO DEMOLITION, RELOCATION, MODIFICATION AND/OR CONSTRUCTION.
4. ALL UTILITY DISCONNECTIONS/DEMOLITIONS/RELOCATIONS SHALL BE COORDINATED BETWEEN THE CONTRACTOR, ALL APPROPRIATE UTILITY COMPANIES, PORTSMOUTH DPW AND ABUTTING PROPERTY OWNERS. UNLESS OTHERWISE SPECIFIED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL RELATED EXCAVATION, TRENCHING AND BACKFILLING.
5. WHERE SPECIFIED TO REMAIN, MANHOLE RIMS, CATCH BASIN GRATES, VALVE COVERS, HANDHOLES, ETC. SHALL BE ADJUSTED TO FINISH GRADE UNLESS OTHERWISE SPECIFIED.
6. SEE EROSION CONTROL PLANS FOR EROSION AND SEDIMENT CONTROL MEASURES THAT SHALL BE IN PLACE PRIOR TO DEMOLITION ACTIVITIES.
7. ALL MATERIALS SCHEDULED FOR DEMOLITION OR REMOVAL ON PRIVATE PROPERTY SHALL BECOME THE PROPERTY OF THE CONTRACTOR UNLESS OTHERWISE SPECIFIED.
8. ALL MATERIAL SCHEDULED TO BE REMOVED SHALL BE LEGALLY DISPOSED OF IN ACCORDANCE WITH ALL LOCAL, STATE AND FEDERAL REGULATIONS/CODES.
9. WATER: PORTSMOUTH DPW WATER DIVISION, JIM TOW, (603) 427-1530.
10. SEWER: PORTSMOUTH DPW SEWER DIVISION, JIM TOW, (603) 427-1530.
11. TELECOMMUNICATIONS: CONSOLIDATED, JOE COSIDINE, (603) 427-5525.
12. CABLE: COMCAST, MIKE COLLINS, (603) 679-5695, EXT. 1037.
13. ELECTRICAL: EVERSOURCE, MICHAEL BUSBY, (603) 332-4227, EXT. 5555334.
14. GAS: UNITIL, DAVID BEAULIEU, (603) 294-5144.
15. CONTRACTOR TO CONTACT PORTSMOUTH DPW A MINIMUM OF TWO WEEKS PRIOR TO ANY DEMOLITION TO COORDINATE ALL WORK CONCERNING DISCONNECTION/DEMOLITION OF ANY PROPOSED WATER AND SEWER LINE IMPROVEMENTS.
16. ALL WATER MAIN AND SERVICE DISCONNECTIONS SHALL CONFORM TO PORTSMOUTH DPW STANDARDS.
17. NO BURNING SHALL BE PERMITTED PER LOCAL REGULATIONS.
18. HAZARDOUS MATERIALS ENCOUNTERED DURING DEMOLITION AND CONSTRUCTION ACTIVITIES SHALL BE ABATED IN STRICT ACCORDANCE WITH ALL APPLICABLE STATE AND LOCAL REGULATIONS.
19. AT NO TIME SHALL ANY UTILITY SERVICE OR VEHICULAR ACCESS TO ADJOINING PROPERTIES BE COMPLETELY INTERRUPTED UNLESS A FULL SHUTDOWN IS COORDINATED WITH ALL AFFECTED PARTIES AND UTILITY PROVIDER(S).
20. SHOULD GROUNDWATER BE ENCOUNTERED DURING EXCAVATION, APPROPRIATE BEST MANAGEMENT PRACTICES SHALL BE EMPLOYED TO ENSURE SEDIMENT LADEN WATER IS NOT DISCHARGED INTO THE CITY DRAINAGE SYSTEM. A DISCHARGE PERMIT SHALL BE OBTAINED PRIOR TO DISCHARGING GROUNDWATER.
21. EXISTING HOUSE IS SERVICED BY AN INTERNAL HEATING OIL TANK. REMOVAL AND DISPOSAL OF TANK SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE REGULATIONS.
22. THIS PLAN IS INTENDED TO PROVIDE MINIMUM GUIDELINES FOR THE DEMOLITION OF EXISTING SITE FEATURES. UNLESS OTHERWISE NOTED TO REMAIN, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL BUILDINGS, PAVEMENT, CONCRETE, CURBING, SIGNS, POLES, UTILITIES, FENCES, VEGETATION AND OTHER EXISTING FEATURES AS NECESSARY TO FULLY CONSTRUCT THE PROJECT.
23. EXISTING SEWER SERVICE LOCATION IS APPROXIMATE. CONTRACTOR SHALL PERFORM TEST PITS AND OTHER WORK AS NECESSARY TO LOCATE LINE. SERVICE SHALL BE TERMINATED AT THE MAIN IN ACCORDANCE WITH DPW STANDARDS AND THE LINE ABANDONED.



133 Court Street Portsmouth, NH 03801  
(603) 433-2335 www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

NO.	DESCRIPTION	BY	DATE
0	TAC WORK SESSION	EBS	12/01/20
1	TAC	EBS	01/18/21
2	TAC	EBS	02/16/21

DRAWN BY: EBS  
APPROVED BY: EDW  
DRAWING FILE: 5090-SITE.dwg

SCALE:  
22" x 34" 1" = 30'  
11" x 17" 1" = 60'

OWNER:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

APPLICANT:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

PROJECT:  
**WATSON'S LANDING  
TAX MAP 209, LOT 33  
1 CLARK DRIVE  
PORTSMOUTH, NH 03801**

TITLE:  
**DEMOLITION PLAN**


SHEET NUMBER:  
**C-1**

PROPOSED CURVE TABLE			
CURVE	LENGTH	RADIUS	DELTA
C8	34.44'	25.00'	78°55'33"
C9	102.80'	63.00'	93°29'17"
C10	100.00'	63.00'	90°56'33"
C11	89.06'	63.00'	80°59'39"
C12	10.94'	700.00'	0°53'43"
C13	20.33'	63.00'	18°29'23"
C14	10.00'	63.00'	9°05'41"
C15	56.04'	63.00'	50°57'51"
C16	68.91'	55.00'	71°50'59"
C17	94.05'	75.00'	71°50'59"
C18	45.01'	157.00'	16°25'37"
C19	53.45'	184.00'	16°38'43"
C20	49.94'	209.00'	13°41'28"

PERIMETER CURVE TABLE			
CURVE	LENGTH	RADIUS	DELTA
C1	31.94'	25.00'	73°12'04"
C2	66.34'	50.00'	76°01'12"
C3	28.81'	750.00'	2°12'03"
C4	106.40'	180.00'	33°52'00"
C5	39.27'	25.00'	90°00'01"
C6	135.95'	230.00'	33°52'00"
C7	95.35'	700.00'	7°48'16"

PERIMETER LINE TABLE		
LINE	LENGTH	BEARING
L1	12.71'	N25°29'20"W
L2	17.51'	S35°38'52"W
L3	42.51'	N35°38'52"E
L4	7.86'	N69°30'52"E
L5	7.86'	S69°30'52"W

PROPOSED LINE TABLE		
LINE	LENGTH	BEARING
L6	4.20'	N51°48'32"E
L7	84.93'	S50°22'44"E
L8	98.89'	S50°22'44"E
L9	10.08'	S32°22'09"W
L10	100.16'	N50°22'44"W
L11	10.00'	N39°37'15"E
L12	10.08'	S32°22'09"W
L13	31.50'	S50°22'44"E
L14	10.00'	N39°37'15"E
L15	9.04'	N79°01'34"E
L16	206.39'	S50°22'44"E
L17	10.08'	S32°22'09"W
L18	136.39'	N50°22'44"W
L19	9.41'	S79°01'34"W
L20	10.08'	S32°22'09"W
L21	146.57'	S50°22'44"E
L22	12.94'	N79°01'34"E
L23	53.59'	S78°55'54"E
L24	8.10'	N11°04'05"E
L25	24.70'	N66°41'02"W
L26	10.03'	S18°55'08"W
L27	55.25'	N66°41'02"W
L28	47.14'	S78°55'54"E
L29	60.83'	S66°41'02"W
L30	10.03'	S18°55'08"E
L31	54.69'	S66°41'02"E
L32	20.00'	N23°18'57"E
L33	10.65'	S80°27'15"W
L34	5.86'	S0°18'19"E
L35	98.72'	S72°09'18"E
L36	20.00'	N18°55'08"E
L37	98.34'	N72°09'18"W
L38	2.61'	N0°18'19"W
L39	20.26'	N80°27'15"E
L40	21.75'	S72°09'18"E
L41	60.20'	N44°16'30"E
L42	37.65'	N21°42'25"E
L43	81.09'	N21°42'25"E
L44	15.03'	S72°09'18"E
L45	30.07'	S21°42'25"W
L46	12.03'	S72°09'18"E
L47	53.60'	S21°42'25"E
L48	24.43'	S66°41'03"E
L49	25.40'	N66°41'02"E
L50	36.89'	S21°42'25"W
L51	23.33'	S50°22'44"E
L52	26.51'	N50°22'44"W
L53	60.20'	S44°16'30"W
L54	39.03'	S50°22'44"E
L55	17.66'	S26°20'00"E
L56	54.81'	N38°09'39"E
L57	54.81'	N38°09'39"E




**SUBDIVISION NOTES**

- DESIGN INTENT - THIS PLAN IS INTENDED TO DEPICT A SINGLE-FAMILY RESIDENTIAL SUBDIVISION ON A PRIVATE ROAD.
- THE BASE PLAN USED HERE WAS DEVELOPED FROM "TOPO/ BOUNDARY, WORKSHEET, 1 CLARK DRIVE (PRIVATE)" DATED NOV. 4, 2020 BY KNIGHT HILL LAND SURVEYING SERVICES, INC.
- PROJECT PARCEL: MAP 209 LOT 33, 135,176 S.F (3.10 ACRES) TO HIGHEST OBSERVABLE TIDE LINE (HOTL).
- ZONE: SRB (SINGLE RESIDENCE B)  
OVERLAY: FLOOD PLAIN DISTRICT OVERLAY  
HIGHWAY NOISE OVERLAY DISTRICT
- DIMENSIONAL REQUIREMENTS:**

LOT AREA:	15,000 SF
LOT FRONTAGE:	100'
LOT DEPTH:	100'
FRONT YARD:	30'
SIDE YARD:	10'
REAR YARD:	30'
MAX. BUILDING HEIGHT:	35' (SLOPED ROOF)
MAX. BUILDING COVERAGE:	20%
MIN. OPEN SPACE:	40%
WETLAND BUFFER:	100'
WETLAND LIMITED CUT:	50'
WETLAND NO-CUT:	25'
- PARKING REQUIREMENTS: NR (NO REQUIREMENT)
- PORTIONS OF THE SITE ARE IN FLOOD HAZARD ZONE AE PER FLOOD INSURANCE RATE MAP (FIRM), ROCKINGHAM COUNTY, NEW HAMPSHIRE, PANEL 259 OF 681, MAP 33015C0259E DATED MAY 17, 2005 (ELEVATION 9') AND PRELIMINARY MAP 33015C0259F DATED JANUARY 29, 2021 (ELEVATION 8').
- WETLANDS WERE DELINEATED BY MICHAEL CUOMO, NH CERTIFIED SOILS SCIENTIST #006 AND NH CERTIFIED WETLANDS SCIENTIST #004, ON SEPTEMBER 15, 2020.
- WAIVERS REQUIRED:
  - SUBDIVISION REGULATION "RESIDENTIAL STREET MINIMUM STANDARDS" DIAGRAM TO ALLOW 20' AND 24' OF ROAD WIDTH WHERE 32' IS REQUIRED.
  - SUBDIVISION REGULATION VI.2.A REQUIRED FOR LOT ARRANGEMENT.
- ZONING SECTION 10.1016 - CONDITIONAL USE PERMIT REQUIRED FOR WORK IN THE CITY WETLAND BUFFER.
- ZONING SECTION 10.674 - CONDITIONAL USE PERMIT REQUIRED FOR USES WITHIN THE HIGHWAY NOISE OVERLAY DISTRICT.
- AREA OF DISTURBANCE EXCEEDS 43,560 S.F., COVERAGE UNDER EPA NPDES PHASE II CONSTRUCTION GENERAL PERMIT REQUIRED.
- AREA OF DISTURBANCE UNDER 50,000 S.F., NHDES ALTERATION OF TERRAIN PERMIT NOT REQUIRED.
- PORTIONS OF THE SITE ARE IN THE 250' NHDES SHORELAND ZONE. NHDES SHORELAND PERMIT REQUIRED.
- PORTIONS OF THE SITE ARE IN THE 100' NHDES TIDAL BUFFER. NHDES WETLANDS PERMIT REQUIRED.
- A HOMEOWNER'S ASSOCIATION SHALL BE REQUIRED FOR THE PERPETUAL MAINTENANCE OF PRIVATE ROADWAY, UTILITY AND STORMWATER INFRASTRUCTURE. SIDEWALK MAINTENANCE SHALL REMAIN THE RESPONSIBILITY OF THE CITY OF PORTSMOUTH.
- ALL LOTS SHALL BE SUBJECT TO A DEED RESTRICTION MANDATING ORGANIC LAWN AND LANDSCAPE CARE METHODS AS SPECIFIED IN THE NOFA ORGANIC STANDARDS LAND CARE.

APPROVED BY THE PORTSMOUTH PLANNING BOARD

CHAIRMAN \_\_\_\_\_ DATE \_\_\_\_\_



133 Court Street Portsmouth, NH 03801  
(603) 433-2335 www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

NO.	DESCRIPTION	BY	DATE
0	TAC WORK SESSION	EBS	12/01/20
1	TAC	EBS	01/18/21
2	TAC	EBS	02/16/21

DRAWN BY: EBS  
APPROVED BY: EDW  
DRAWING FILE: 5090-SITE.dwg

SCALE: 22" x 34" 1" = 30'  
11" x 17" 1" = 60'

OWNER:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

APPLICANT:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

PROJECT:  
**WATSON'S LANDING  
TAX MAP 209, LOT 33  
1 CLARK DRIVE  
PORTSMOUTH, NH 03801**


TITLE:

SUBDIVISION PLAN

SHEET NUMBER:

C-2


P5090



### LEGEND

	PROPERTY LINE
	EASEMENT LINE
	BUILDING SETBACK
	100' CITY WETLAND SETBACK
	50' CITY WETLAND SETBACK (LIMITED CUT)
	25' CITY WETLAND SETBACK (NO-CUT)
	100' STATE TIDAL BUFFER
	STATE SHORELAND SETBACKS
	FRESHWATER WETLAND BOUNDARY
	TIDAL WETLAND BOUNDARY
	FLOODPLAIN
	EXISTING PAVEMENT/CURB
	PROP. PAVEMENT/VERTICAL OR SLOPED GRANITE CURB
	EXISTING/PROPOSED GUARDRAIL
	EXISTING/PROPOSED STOCKADE FENCE
	EXISTING/PROPOSED CHAINLINK FENCE
	EXISTING CONTOUR
	PROPOSED CONTOUR/INTERMEDIATE CONTOUR
	PROPOSED SPOT GRADE/TOP & BOTTOM OF WALL
	PROPOSED RETAINING WALL
	EXISTING WATER/CURB STOP/VALVE/HYDRANT
	EXISTING SEWER/MANHOLE
	EXISTING GAS/VALVE
	EXIST. OVERHEAD/UNDERGROUND UTILITIES/POLE
	EXISTING DRAINAGE/CB/DMH
	PROPOSED THRUST BLOCK/CURB STOP/VALVE/HYDRANT
	PROPOSED DOMESTIC/FIRE WATER SERVICE LINE
	PROPOSED SEWER/MANHOLE/CLEANOUT
	PROPOSED SEWER FORCEMAIN
	PROPOSED GAS
	PROPOSED OVERHEAD UTILITIES/UTILITY POLE
	PROPOSED UNDERGROUND ELECTRIC/PHONE/TV
	PROPOSED DRAINAGE (HARD PIPE)/CB/DCB/DMH/FES
	PROPOSED DRAINAGE (PERFORATED PIPE)/CLEANOUT
	CORRUGATED PLASTIC PIPE/FLARED END SECTION/HEADWALL
	PROPOSED GROUND SLOPE/APPROX. GRADE/STONE CHECK DAM
	SILTFENCE/SEDIMENT BARRIER/CONST. FENCE
	STABILIZED CONSTRUCTION EXIT
	PROPOSED SAWCUT
	EXISTING TREE LINE/BRUSH LINE
	PROPOSED EROSION CONTROL BLANKET
	PROPOSED RIPRAP
	PROPOSED RAINGARDEN
	PROPOSED DISTURBANCE IN WETLAND SETBACK
	FRESHWATER WETLAND
	SALTMARSH


ROADWAY PLAN



ROADWAY PROFILE

**NOTES:**

- SEE SHEET C-4 FOR DRAINAGE STRUCTURE AND PIPING TABLE.
- SEE SHEET C-5 FOR 8" WATER MAIN LAYOUT
- SEE UTILITY NOTE #17 FOR INSULATION AT WATER AND DRAINAGE CROSSINGS.



133 Court Street  
(603) 433-2335  
Portsmouth, NH 03801  
www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

**REVISIONS**

NO.	DESCRIPTION	BY	DATE
0	TAC WORK SESSION	EBS	12/01/20
1	TAC	EBS	01/18/21
2	TAC	EBS	02/16/21

DRAWN BY: EBS  
APPROVED BY: EDW  
DRAWING FILE: 5090-SITE.dwg

**SCALE:**  
22" x 34" 1" = 30'  
11" x 17" 1" = 60'

**OWNER:**  
**FREDERICK W. WATSON REVOCABLE TRUST, ROBERT D. WATSON, TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

**APPLICANT:**  
**FREDERICK W. WATSON REVOCABLE TRUST, ROBERT D. WATSON, TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

**PROJECT:**  
**WATSON'S LANDING**  
TAX MAP 209, LOT 33  
1 CLARK DRIVE  
PORTSMOUTH, NH 03801


**TITLE:**  
**ROADWAY PLAN AND PROFILE**

**SHEET NUMBER:**  
**C-3**

P5090


**DRAINAGE SCHEDULE**

- PCB #10  
RIM: 29.55  
OUT: 26.05 [PDMH #12]  
12" CPP L=8'± S=0.0050'/'
- PCB #11  
RIM: 29.55  
OUT: 26.05 [PDMH #12]  
12" CPP L=8'± S=0.0050'/'
- PDMH #12  
RIM: 29.70  
IN: 26.01 [PCB #10]  
IN: 26.01 [PCB #11]  
OUT: 25.91  
12" CPP L=155'± S=0.0050'/'
- PCB #13  
RIM: 31.10  
OUT: 27.10 [PDMH #15]  
12" CPP L=5'± S=0.0100'/'
- PCB #14  
RIM: 31.10  
OUT: 27.10 [PDMH #15]  
12" CPP L=5'± S=0.0100'/'
- PDMH #15  
RIM: 31.25  
IN: 25.14 [PDMH #12]  
IN: 27.05 [PCB #13]  
IN: 27.05 [PCB #14]  
OUT: 25.04 [PDMH #17]  
12" CPP L=67'± S=0.0050'/'
- PCB #16  
RIM: 30.50  
OUT: 26.50 [PDMH #17]  
12" CPP L=5'± S=0.0100'/'
- PDMH #17  
RIM: 30.75  
IN: 24.70 [PDMH #15]  
IN: 26.45 [PCB #16]  
OUT: 24.60 [PDMH #18]  
12" CPP L=84'± S=0.005'/'
- PDMH #18  
OUT: 30.00  
IN: 24.18 [PCB #17]  
OUT: 24.08 [OUTFALL]  
12" CPP L=117'± S=0.0605'/'  
DAYLIGHT ELEV. 17.00



**STORMWATER MANAGEMENT NOTES**

1. TOTAL AREA OF PROJECT DISTURBANCE: ±47,550 S.F.
2. DO NOT BEGIN CONSTRUCTION UNTIL ALL STATE AND LOCAL PERMITS HAVE BEEN APPLIED FOR AND RECEIVED.
3. CONTRACTOR SHALL OBTAIN A "DIGSAFE" NUMBER AT LEAST 72 HOURS PRIOR TO COMMENCING CONSTRUCTION.
4. ALL CONSTRUCTION SHALL MEET THE MINIMUM CONSTRUCTION STANDARDS OF THE CITY OF PORTSMOUTH AND NHDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION. THE MORE STRINGENT SPECIFICATION SHALL GOVERN.
5. ALL BENCHMARKS AND TOPOGRAPHY SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO INITIATING CONSTRUCTION.
6. UNLESS OTHERWISE AGREED IN WRITING, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING AND MAINTAINING TEMPORARY BENCHMARKS (TBM) AND PERFORMING ALL CONSTRUCTION SURVEY LAYOUT.
7. PRIOR TO CONSTRUCTION, FIELD VERIFY JUNCTIONS, LOCATIONS AND ELEVATIONS/INVERTS OF ALL EXISTING STORMWATER AND UTILITY LINES. PRESERVE AND PROTECT LINES TO BE RETAINED.
8. TEMPORARY INLET PROTECTION MEASURES SHALL BE INSTALLED IN ALL EXISTING AND PROPOSED CATCH BASINS WITHIN 100' OF THE PROJECT SITE WHEN SITE WORK WITHIN CONTRIBUTING AREAS IS ACTIVE OR SAID AREAS HAVE NOT BEEN STABILIZED.
9. PROTECTION OF SUBGRADE: THE CONTRACTOR SHALL BE REQUIRED TO MAINTAIN STABLE, DEWATERED SUBGRADES FOR FOUNDATIONS, PAVEMENT AREAS, UTILITY TRENCHES, AND OTHER AREAS DURING CONSTRUCTION. SUBGRADE DISTURBANCE MAY BE INFLUENCED BY EXCAVATION METHODS, MOISTURE, PRECIPITATION, GROUNDWATER CONTROL, AND CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL TAKE PRECAUTIONS TO PREVENT SUBGRADE DISTURBANCE. SUCH PRECAUTIONS MAY INCLUDE DIVERTING STORMWATER RUNOFF AWAY FROM CONSTRUCTION AREAS, REDUCING TRAFFIC IN SENSITIVE AREAS, AND MAINTAINING AN EFFECTIVE DEWATERING PROGRAM. SOILS EXHIBITING HEAVING OR INSTABILITY SHALL BE OVER EXCAVATED TO MORE COMPETENT BEARING SOIL AND REPLACED WITH FREE DRAINING STRUCTURAL FILL. IF THE EARTHWORK IS PERFORMED DURING FREEZING WEATHER, EXPOSED SUBGRADES ARE SUSCEPTIBLE TO FROST. NO FILL OR UTILITIES SHALL BE PLACED ON FROZEN GROUND. THIS WILL LIKELY REQUIRE REMOVAL OF A FROZEN SOIL CRUST AT THE COMMENCEMENT OF EACH DAY'S OPERATIONS. THE FINAL SUBGRADE ELEVATION WOULD ALSO REQUIRE AN APPROPRIATE DEGREE OF INSULATION AGAINST FREEZING.
10. IF SUITABLE, EXCAVATED MATERIALS SHALL BE PLACED AS FILL WITHIN UPLAND AREAS ONLY AND SHALL NOT BE PLACED WITHIN WETLANDS. PLACEMENT OF BORROW MATERIALS SHALL BE PERFORMED IN A MANNER THAT PREVENTS LONG TERM DIFFERENTIAL SETTLEMENT. EXCESSIVELY WET MATERIALS SHALL BE STOCKPILED AND ALLOWED TO DRAIN BEFORE PLACEMENT. FROZEN MATERIAL SHALL NOT BE USED FOR CONSTRUCTION.
11. ALL CATCH BASIN, MANHOLE AND OTHER DRAINAGE RIMS SHALL BE SET FLUSH WITH OR NO LESS THAN 0.1' BELOW FINISH GRADE. ANY RIM ABOVE SURROUNDING FINISH GRADE SHALL NOT BE ACCEPTED.
12. IN ORDER TO PROVIDE VISUAL CLARITY ON THE PLANS, DRAINAGE AND OTHER UTILITY STRUCTURES MAY NOT BE DRAWN TO SCALE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER SIZING AND LOCATION OF ALL STRUCTURES AND IS DIRECTED TO RESOLVE ANY POTENTIAL DISCREPANCY WITH THE ENGINEER PRIOR TO CONSTRUCTION.
13. ALL CPP PIPE SHALL BE ADS N-12 OR APPROVED EQUAL.
14. PROJECT SUBJECT TO EPA NPDES PHASE II. CONTRACTOR SHALL BE RESPONSIBLE FOR REQUIRED NOI, SWPPP AND MINIMUM WEEKLY INSPECTIONS.
15. NO EARTHWORK, STUMPING OR GRUBBING SHALL COMMENCE UNTIL ALL APPROPRIATE SEDIMENT AND EROSION CONTROL MEASURES HAVE BEEN INSTALLED. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE PROPERLY MAINTAINED IN GOOD WORKING ORDER FOR THE DURATION OF CONSTRUCTION AND THE SITE IS STABILIZED.
16. SEE DETAIL SHEETS FOR PERTINENT SEDIMENT AND EROSION CONTROL DETAILS AND ADDITIONAL NOTES.
17. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH THE DESIGN STANDARDS AND SPECIFICATIONS SET FORTH IN THE NHDES NH STORMWATER MANUALS, VOL. 1-3, DATED DECEMBER 2008 AS AMENDED.
18. CONTRACTOR SHALL CONTROL DUST BY SPRAYING WATER, SWEEPING PAVED SURFACES, PROVIDING TEMPORARY VEGETATION, AND/OR MULCHING EXPOSED AREAS AND STOCKPILES.
19. THE CONTRACTOR SHALL TAKE WHATEVER MEANS NECESSARY TO PREVENT EROSION, PREVENT SEDIMENT FROM LEAVING THE SITE AND/OR ENTERING WETLANDS AND ENSURE PERMANENT SOIL STABILIZATION.
20. ALL EROSION CONTROL BLANKETS AND FASTENERS SHALL BE BIODEGRADABLE.
21. ALL SWALES AND DETENTION PONDS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
22. ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED SHALL RECEIVE SIX (6") INCHES OF COMPACTED LOAM, LIMESTONE, ORGANIC FERTILIZER, SEED, AND MULCH USING APPROPRIATE SOIL STABILIZATION TECHNIQUES.
23. UPON COMPLETION OF CONSTRUCTION, ALL DRAINAGE INFRASTRUCTURE SHALL BE CLEANED OF ALL DEBRIS AND SEDIMENT AND ALL TEMPORARY EROSION AND SEDIMENT CONTROLS REMOVED AND ANY AREAS DISTURBED BY THE REMOVAL SMOOTHED AND REVEGETATED.



133 Court Street Portsmouth, NH 03801  
(603) 433-2335 www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

NO.	DESCRIPTION	BY	DATE
0	TAC WORK SESSION	EBS	12/01/20
1	TAC	EBS	01/18/21
2	TAC	EBS	02/16/21

DRAWN BY: EBS  
APPROVED BY: EDW  
DRAWING FILE: 5090-SITE.dwg

SCALE:  
22" x 34" 1" = 30'  
11" x 17" 1" = 60'


OWNER:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840


APPLICANT:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

PROJECT:  
**WATSON'S LANDING  
TAX MAP 209, LOT 33  
1 CLARK DRIVE  
PORTSMOUTH, NH 03801**

TITLE:  
**STORMWATER  
MANAGEMENT PLAN**


SHEET NUMBER:  
**C-4**





**UTILITY NOTES**

1. THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES SHOWN HEREON ARE APPROXIMATE AND ARE BASED UPON THE FIELD LOCATION OF ALL VISIBLE STRUCTURES (IE. CATCH BASINS, MANHOLES, WATER GATES, ETC.) AND INFORMATION COMPILED FROM PLANS PROVIDED BY UTILITY PROVIDERS AND GOVERNMENTAL AGENCIES. AS SUCH, THEY ARE NOT INCLUSIVE AS OTHER UTILITIES AND UNDERGROUND STRUCTURES THAT ARE NOT SHOWN ON THE PLANS MAY EXIST. THE ENGINEER, SURVEYOR AND OWNER ACCEPT NO RESPONSIBILITY FOR POTENTIAL INACCURACIES IN THE PLAN AND/OR UNFORESEEN CONDITIONS. THE CONTRACTOR SHALL NOTIFY, IN WRITING, SAID AGENCIES, UTILITY PROVIDERS, CITY OF PORTSMOUTH DPW AND OWNER'S AUTHORIZED REPRESENTATIVE AND CALL DIG SAFE AT 1 (800) DIG-SAFE AT LEAST SEVENTY-TWO (72) HOURS PRIOR TO ANY EXCAVATION WORK.
2. PRIOR TO CONSTRUCTION, IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE AND FIELD VERIFY JUNCTIONS, LOCATIONS AND ELEVATIONS/INVERTS OF ALL EXISTING AND PROPOSED STORMWATER AND UTILITY LINES. CONFLICTS SHALL BE ANTICIPATED AND ALL EXISTING LINES TO BE RETAINED SHALL BE PROTECTED. ANY DAMAGE DONE TO EXISTING UTILITIES SHALL BE REPAIRED AND, IF NECESSARY, EXISTING UTILITIES SHALL BE RELOCATED AT NO EXTRA COST TO THE OWNER. ALL CONFLICTS SHALL BE RESOLVED WITH THE INVOLVEMENT OF THE ENGINEER, DPW AND APPROPRIATE UTILITIES.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE POSTING OF ALL BONDS AND PAYMENT OF ALL TAP, TIE-IN AND CONNECTION FEES.
4. ALL ROAD/LANE CLOSURES OR OTHER TRAFFIC INTERRUPTIONS SHALL BE COORDINATED WITH THE PORTSMOUTH POLICE DEPARTMENT AND DPW AT LEAST TWO WEEKS PRIOR TO COMMENCING RELATED CONSTRUCTION.
5. ALL CONSTRUCTION SHALL MEET THE MINIMUM CONSTRUCTION STANDARDS OF THE CITY OF PORTSMOUTH AND NHDOT STANDARD SPECIFICATIONS FOR ROADS AND BRIDGES, LATEST EDITION. THE MORE STRINGENT SPECIFICATION SHALL GOVERN.
6. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRENCHING, BEDDING, BACKFILL & COMPACTION FOR ALL UTILITY TRENCHING IN ADDITION TO ALL CONDUIT INSTALLATION AND COORDINATION OF ALL REQUIRED INSPECTIONS.
7. ALL TRENCHING, PIPE LAYING AND BACKFILLING SHALL CONFORM TO FEDERAL OSHA AND CITY REGULATIONS.
8. FINAL UTILITY LOCATIONS TO BE COORDINATED BETWEEN THE ARCHITECT, CONTRACTOR, APPROPRIATE UTILITY COMPANIES AND THE PORTSMOUTH DPW.
9. WATER: PORTSMOUTH DPW WATER DIVISION, JIM TOW, (603) 427-1530.
10. SEWER: PORTSMOUTH DPW SEWER DIVISION, JIM TOW, (603) 427-1530.
11. TELECOMMUNICATIONS: CONSOLIDATED, JOE CONSIDINE, (603) 427-5525.
12. CABLE: COMCAST, MIKE COLLINS, (603) 679-5695, EXT. 1037.
13. ELECTRICAL: EVERSOURCE, MICHAEL BUSBY, (603) 332-4227, EXT. 5555334. ALL ELECTRIC CONDUIT INSTALLATION SHALL BE INSPECTED BY EVERSOURCE PRIOR TO BACKFILL, 48-HOUR MINIMUM NOTICE REQUIRED.
14. GAS: UNITIL, DAVID BEAULIEU, (603) 294-5144.
15. DETECTABLE WARNING TAPE SHALL BE PLACED OVER THE ENTIRE LENGTH OF ALL BURIED UTILITIES, COLORS PER THE RESPECTIVE UTILITY PROVIDERS.
16. ALL WATER MAIN AND SERVICE INSTALLATIONS SHALL BE CONSTRUCTED AND TESTED PER PORTSMOUTH DPW STANDARDS AND SPECIFICATIONS. ALL OTHER UTILITIES SHALL BE TO THE STANDARDS AND SPECIFICATIONS OF THE RESPECTIVE UTILITY PROVIDERS.
17. WHERE WATER LINES CROSS, RUN ADJACENT TO OR ARE WITHIN 5' OF STORM DRAINAGE PIPES OR STRUCTURES, 2"-THICK CLOSED CELL RIGID BOARD INSULATION SHALL BE INSTALLED FOR FROST PROTECTION.
18. PER PORTSMOUTH DPW SPECIFICATIONS, ALL NEW DUCTILE IRON WATERLINES SHALL BE WRAPPED WITH A WATER TIGHT POLYETHYLENE WRAPPING FOR THEIR FULL LENGTH, ALL DOMESTIC WATER SERVICES SHALL BE PROVIDED WITH BACKFLOW PREVENTERS AND ALL JOINTS SHALL HAVE THREE (3) WEDGES PER JOINT.
19. WATER AND SANITARY SEWER LINES SHALL BE LOCATED AT LEAST 10' HORIZONTALLY FROM EACH OTHER. WHERE CROSSING, 18" MINIMUM VERTICAL CLEARANCE SHALL BE PROVIDED WITH WATER INSTALLED OVER SEWER.
20. CONTRACTOR SHALL PROVIDE DPW WITH DETAILS OF TEMPORARY & PERMANENT GROUNDWATER DEWATERING DESIGN IF NECESSARY.
21. THE APPLICANT OR ASSIGNS SHALL AGREE TO PAY FOR THE SERVICES OF A THIRD-PARTY OVERSIGHT ENGINEER, TO BE SELECTED BY THE CITY, TO MONITOR THE INSTALLATION OF UTILITIES INCLUDING SEWER, WATER AND DRAINAGE.
22. THE ENGINEER OF RECORD SHALL SUBMIT A WRITTEN REPORT WITH PHOTOGRAPHS AND ENGINEERS STAMP CERTIFYING THAT THE STORMWATER INFRASTRUCTURE WAS CONSTRUCTED TO THE APPROVED PLANS AND WILL MEET THE DESIGN PERFORMANCE.
23. RESIDENTIAL HOUSES SHALL BE EQUIPPED WITH NFPA 13D-COMPLIANT SPRINKLER SYSTEMS IF THEIR FRONT DOORS ARE LOCATED GREATER THAN 50' FROM THE EDGE OF ROADWAY PAVEMENT.



133 Court Street  
(603) 433-2335  
Portsmouth, NH 03801  
www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

NO.	DESCRIPTION	BY	DATE
0	TAC WORK SESSION	EBS	12/01/20
1	TAC	EBS	1/18/21
2	TAC	EBS	02/16/21

DRAWN BY: EBS  
APPROVED BY: EDW  
DRAWING FILE: 5090-SITE.dwg

SCALE:  
22" x 34" 1" = 30'  
11" x 17" 1" = 60'

OWNER:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

APPLICANT:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

PROJECT:  
**WATSON'S LANDING  
TAX MAP 209, LOT 33  
1 CLARK DRIVE  
PORTSMOUTH, NH 03801**


TITLE:

UTILITY PLAN

SHEET NUMBER:


C-5

P5090



**CONDITIONAL USE PERMIT NOTES**

- ZONING SECTION 10.1016 – CONDITIONAL USE PERMIT REQUIRED FOR EARTH DISTURBANCE IN THE 100' CITY WETLAND BUFFER.
- PROJECT PARCEL: MAP 209 LOT 33, 135,176 S.F. (3.10 ACRES) TO HIGHEST OBSERVABLE TIDE LINE (HOTL).
- WETLAND AREA ON LOT: ±16,397 S.F. (±0.38 ACRES)
- 100' WETLAND BUFFER ANALYSIS (EXISTING CONDITIONS):  
 LAWN: ±23,540 S.F.  
 BRUSH/WOODLAND: ±20,735 S.F.  
 IMPERVIOUS: ±3,326 S.F.  
 TOTAL BUFFER: ±47,601 S.F. (±1.09 ACRES)
- AREA OF 100' WETLAND BUFFER IMPACT:  
 ONSITE: ±15,125 S.F.  
 OFFSITE: ±375 S.F. (MARKET STREET RIGHT OF WAY)  
 TOTAL: ±15,500 S.F. (±0.36 ACRES)
- AREA OF TREE/BRUSH REMOVAL IN BUFFER:  
 0-25': ±501 S.F. (FOR SEWER AND DPW ACCESSWAY ONLY)  
 25'-50': ±252 S.F. (FOR SEWER AND DPW ACCESSWAY ONLY)  
 50'-100': ±756 S.F.  
 TOTAL: ±1,509 S.F.
- PROPOSED IMPERVIOUS SURFACES IN BUFFER: 0 S.F.
- PROPOSED WETLAND IMPACT: 0 S.F.
- WETLANDS WERE DELINEATED BY MICHAEL CUOMO, NH CERTIFIED SOILS SCIENTIST #006 AND NH CERTIFIED WETLANDS SCIENTIST #004, ON SEPTEMBER 15, 2020.
- CONSTRUCTION ACTIVITIES SHALL BE MANAGED IN STRICT ACCORDANCE WITH NH RSA 430:53 AND AGR 3800 RELATIVE TO INVASIVE SPECIES. NO INVASIVE SPECIES SHALL BE INSTALLED ON THE PROJECT SITE FOR ANY REASON.



133 Court Street Portsmouth, NH 03801  
 (603) 433-2335 www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

NO.	DESCRIPTION	BY	DATE
0	TAC	EBS	01/18/21
1	TAC	EBS	02/16/21

DRAWN BY: EBS  
 APPROVED BY: EDW  
 DRAWING FILE: 5090-SITE.dwg

SCALE:  
 22" x 34" 1" = 30'  
 11" x 17" 1" = 60'

OWNER:  
**FREDERICK W. WATSON  
 REVOCABLE TRUST,  
 ROBERT D. WATSON,  
 TRUSTEE**  
 53 SLEEPY HOLLOW DRIVE  
 GREENLAND, NH 03840

APPLICANT:  
**FREDERICK W. WATSON  
 REVOCABLE TRUST,  
 ROBERT D. WATSON,  
 TRUSTEE**  
 53 SLEEPY HOLLOW DRIVE  
 GREENLAND, NH 03840


PROJECT:  
**WATSON'S LANDING**  
 TAX MAP 209, LOT 33  
 1 CLARK DRIVE  
 PORTSMOUTH, NH 03801

TITLE:  
**CONDITIONAL USE  
 PERMIT PLAN**

SHEET NUMBER:  
**C-6**

**LEGEND**


- — — — — PROPERTY LINE
- - - - - EASEMENT LINE
- - - - - 100' CITY WETLAND SETBACK
- - - - - 50' CITY WETLAND SETBACK (LIMITED CUT)
- - - - - 25' CITY WETLAND SETBACK (NO-CUT)
- - - - - 100' STATE TIDAL BUFFER
- - - - - FRESHWATER WETLAND BOUNDARY
- - - - - TIDAL WETLAND BOUNDARY
- — — — — VGC SGC EXISTING PAVEMENT/CURB
- (S) — (S) — EXISTING SEWER/MANHOLE
- x - x - SILTFENCE/SEDIMENT BARRIER/CONST. FENCE
- - - - - EXISTING TREE LINE/BRUSH LINE
- [Hatched Box] PROPOSED DISTURBANCE IN WETLAND BUFFER
- [Dotted Box] PROPOSED VEGETATION REMOVAL IN 25' NO-CUT ZONE
- [Stippled Box] FRESHWATER WETLAND
- [Wavy Box] SALTMARSH



PS090


**LEGEND**

- ⊗ BLU Highbush Blueberry (*Vaccinium corymbosum*)  
QTY.: 15 MIN. SPACING: 5'
  - ⊙ PLM Beach Plum (*Prunus maritima*)  
QTY.: 4 MIN. SPACING: 10'
  - ⊗ RSE Beach Rose (*Rosa rugosa*)  
QTY.: 12 MIN. SPACING: 3'-4'
  - ⊙ BAY Northern Bayberry (*Myrica pensylvanica*)  
QTY.: 12 MIN. SPACING: 4'-6'
  - ⊙ TBD 'STREET TREE' SPECIES TO BE DETERMINED - SEE NOTE 15  
QTY.: 12 MIN. SPACING: AS SHOWN
- NEW ENGLAND WILDFLOWER SEED MIX
  - NEW ENGLAND CONSERVATION SEED MIX
  - 50/50 NEW ENGLAND WETLAND AND WILDFLOWER SEED MIXES
  - EXISTING TREE LINE/BRUSH LINE



**PLANTING NOTES**

- THE CONTRACTOR SHALL LOCATE AND VERIFY THE EXISTENCE OF ALL UTILITIES PRIOR TO STARTING WORK.
- THE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTINGS SHOWN ON THE DRAWINGS.
- ALL MATERIAL SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY THE CURRENT AMERICAN STANDARD FOR NURSERY STOCK PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
- ALL PLANT MATERIALS SHALL BE EXACTLY AS SPECIFIED BY THE ENGINEER AND BEAR LEGIBLE TAGS INDICATING THEIR SPECIES. IF PLANT SPECIES CULTIVARS ARE FOUND TO VARY FROM THAT SPECIFIED AT ANY TIME DURING THE GUARANTEE PERIOD, THE ENGINEER RESERVES THE RIGHT TO HAVE THE CONTRACTOR REPLACE THAT PLANT MATERIAL. ALL PLANT AND SEED SUBSTITUTIONS MUST BE APPROVED BY THE ENGINEER.
- PLANTS SHALL BE SUBJECT TO INSPECTION AND APPROVAL AT THE PLACE OF GROWTH, UPON DELIVERY OR AT THE JOB SITE WHILE WORK IS ON-GOING TO CONFORMITY TO SPECIFIED QUALITY, SIZE AND VARIETY.
- PLANTS FURNISHED IN CONTAINERS SHALL HAVE THE ROOTS WELL ESTABLISHED IN THE SOIL MASS AND SHALL HAVE AT LEAST ONE (1) GROWING SEASON. ROOT-BOUND PLANTS OR INADEQUATELY SIZED CONTAINERS TO SUPPORT THE PLANT MAY BE DEEMED UNACCEPTABLE.
- NO PLANT SHALL BE PUT IN THE GROUND BEFORE GRADING HAS BEEN FINISHED AND APPROVED BY THE ENGINEER. ALL FINAL GRADES SHALL BE PER THE GRADING AND DRAINAGE PLAN.
- ALL PLANTS SHALL BE INSTALLED AND DETAILED AND ALL WORK DONE PER THE PROJECT SPECIFICATIONS.
- ALL PLANTS SHALL BE WATERED THOROUGHLY TWICE DURING THE FIRST 24-HOUR PERIOD AFTER PLANTING. ALL PLANTS SHALL BE WATERED WEEKLY, OR MORE OFTEN IF NECESSARY, DURING THE FIRST GROWING SEASON.
- ALL PLANTS SHALL BE GUARANTEED BY THE CONTRACTOR FOR NOT LESS THAN ONE FULL YEAR FROM THE TIME OF PROVISIONAL ACCEPTANCE. DURING THIS TIME, THE OWNER SHALL MAINTAIN ALL PLANT MATERIALS IN THE ABOVE MANNER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSPECT THE PLANTS TO ENSURE PROPER CARE. IF THE CONTRACTOR IS DISSATISFIED WITH THE CARE GIVEN, HE SHALL IMMEDIATELY, AND IN SUFFICIENT TIME TO PERMIT THE CONDITION TO BE RECTIFIED, NOTIFY THE ENGINEER IN WRITING OR OTHERWISE FORFEIT HIS CLAIM.
- FINAL ACCEPTANCE BY THE ENGINEER WILL BE MADE UPON THE CONTRACTOR'S REQUEST AFTER ALL CORRECTIVE WORK HAS BEEN COMPLETED.
- BY THE END OF THE GUARANTEE PERIOD, THE CONTRACTOR SHALL HAVE REPLACED ANY PLANT MATERIAL THAT IS MISSING, NOT TRUE TO SIZE AS SPECIFIED, THAT HAS DIED, THAT HAVE LOST IS NATURAL SHAPE DUE TO DEAD BRANCHES, EXCESSIVE PRUNING OR INADEQUATE OR IMPROPER CARE, OR IS, IN THE OPINION OF THE ENGINEER, IN UNHEALTHY OR UNSIGHTLY CONDITION.
- UNLESS OTHERWISE SPECIFIED BELOW, ALL DISTURBED AREAS SHALL BE SEEDED WITH THE SEED MIXTURES SHOWN ON SHEET D-1.
- SPECIALTY SEED MIXTURES AND SOME PLANTINGS ARE AVAILABLE FROM:  
NEW ENGLAND WETLAND PLANTS, INC., 820 WEST STREET, AMHERST, MA.  
THIS IS NOT INTENDED TO BE AN EXCLUSIVE SUPPLIER. THE CONTRACTOR MAY USE ANY SUPPLIER PROVIDED THAT THE PLANTS AND SEED MIXTURES MEET THE PROJECT SPECIFICATIONS. THE CONTRACTOR SHOULD NOTE THAT LOCAL SUPPLIERS ARE PREFERABLE.
- CONTRACTOR SHALL CONSULT WITH THE CITY TREES AND GREENERY COMMITTEE ONCE ROUGH ROADWAY GRADING IS COMPLETE IN ORDER TO COORDINATE STREET TREE SPECIES, LOCATIONS AND PLANTING SPECIFICATIONS.




- NOTES:**
- PLANT TREE SUCH THAT TOP OF ROOT BALL IS FLUSH WITH GRADE (1" - 2" HIGHER IN SLOW DRAINING SOIL). TRUNK FLARE MUST BE VISIBLE AT THE TOP OF THE ROOT BALL.
  - THREE FLAGGED GUY WIRES TO BE EQUALLY SPACED ABOUT TREE. WOODEN STAKES (24" LENGTH) MAY BE SUBSTITUTED FOR METAL ANCHORS. EITHER OPTION SHALL BE DRIVEN OUTSIDE THE ROOT BALL, PREFERABLY IN UNEXCAVATED SOIL AND REMOVED AT THE END OF THE FIRST GROWING SEASON OR WHEN TREE IS STABILIZED.
  - COORDINATE PRUNING WITH LANDSCAPE ARCHITECT WHEN POSSIBLE. DO NOT HEAVILY PRUNE THE TREE AT PLANTING. DO NOT REMOVE THE TERMINAL BUDS OF BRANCHES THAT EXTEND TO THE EDGE OF THE CROWN. PRUNING OF DEAD OR BROKEN BRANCHES OR CO-DOMINANT LEADERS IS PERMITTED.

**NOTES:**

- SHRUBS SHALL BE PLANTED SUCH THAT THE TRUNK FLARE IS A MINIMUM OF 1" & NO MORE THAN 2" ABOVE FINISH GRADE, DEPENDING UPON SITE CONDITIONS.
- ALL ROPE, TWINE, WIRE OR OTHER MATERIAL SHALL BE REMOVED FROM ROOT BALL. BURLAP SHALL BE REMOVED FROM THE TOP HALF OF THE ROOT BALL.

**SHRUB PLANTING NOT TO SCALE**

**DECIDUOUS TREE PLANTING NOT TO SCALE**



**ALTUS**  
ENGINEERING, INC.

133 Court Street  
(603) 433-2335

Portsmouth, NH 03801  
www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

REVISIONS

NO.	DESCRIPTION	BY	DATE
0	TAC	EBS	02/16/21

DRAWN BY: EBS  
APPROVED BY: EDW  
DRAWING FILE: 5090-SITE.dwg

SCALE:  
22" x 34" 1" = 30'  
11" x 17" 1" = 60'

OWNER:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

APPLICANT:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

PROJECT:  
**WATSON'S LANDING  
TAX MAP 209, LOT 33  
1 CLARK DRIVE  
PORTSMOUTH, NH 03801**

TITLE:  
**PLANTING PLAN**

SHEET NUMBER:  
**C-7**

PS090

# SEDIMENT AND EROSION CONTROL NOTES

## PROJECT NAME AND LOCATION

1 CLARK DRIVE  
PORTSMOUTH, NEW HAMPSHIRE  
TAX MAP 209 LOT 33

LATITUDE: 43.084° N  
LONGITUDE: 70.771° W

## OWNER/APPLICANT:

FREDERICK W. WATSON REVOCABLE TRUST, ROBERT D. WATSON, TRUSTEE  
53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

## DESCRIPTION

The project consists of the demolition of a single family residence and creation of a 4-lot subdivision along with a private cul-de-sac and associated site improvements.

## DISTURBED AREA

The total area to be disturbed for the development is approximately ±47,550 S.F. (±1.09 acres). USEPA NPDES Phase II compliance required.

## PROJECT PHASING

The proposed road and associated utilities will be completed in one phase. Construction of individual house lots to be done later at the owner's discretion.

## NAME OF RECEIVING WATER

The site drains over land to Inner Cutts Cove and eventually the Piscataqua River.

## SEQUENCE OF MAJOR ACTIVITIES

1. Install temporary erosion control measures including perimeter controls, stabilized construction entrance and inlet sediment filters as noted on the plan. All temporary erosion control measures shall be maintained in good working condition for the duration of the project.
2. Remove landscaping, strip loam and stockpile.
3. Demolish existing site features, single family residence, utilities, etc. as shown on Demolition Plan.
4. Rough grade site including placement of borrow materials.
5. Construct building and associated improvements.
6. Construct drainage structures, culverts, utilities & sidewalk base course materials.
7. Install base course paving & curbing.
8. Install top course paving and sidewalks.
9. Loam (6" min) and seed all disturbed areas not paved or otherwise stabilized.
10. When all construction activity is complete and site is stabilized, remove all temporary erosion control measures and any sediment that has been trapped by these devices.
11. House construction on individual lots will be done by others subsequent to roadway construction.

## TEMPORARY EROSION & SEDIMENT CONTROL AND STABILIZATION PRACTICES

All work shall be in accordance with state and local permits. Work shall conform to the practices described in the "New Hampshire Stormwater Manual, Volumes 1 - 3", issued December 2008, as amended. As indicated in the sequence of Major Activities, perimeter controls shall be installed prior to commencing any clearing or grading of the site. Structural controls shall be installed concurrently with the applicable activity. Once construction activity ceases permanently in an area and permanent measures are established, perimeter controls shall be removed.

During construction, runoff will be diverted around the site with stabilized channels where possible. Sheet runoff from the site shall be filtered through appropriate perimeter controls. All storm drain inlets shall be provided with inlet protection measures.

Temporary and permanent vegetation and mulching is an integral component of the erosion and sedimentation control plan. All areas shall be inspected and maintained until vegetative cover is established. These control measures are essential to erosion prevention and also reduce costly rework of graded and shaped areas.

Temporary vegetation shall be maintained in these areas until permanent seeding is applied. Additionally, erosion and sediment control measures shall be maintained until permanent vegetation is established.

## INSTALLATION, MAINTENANCE AND INSPECTION PROCEDURES FOR TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES

### A. GENERAL

These are general inspection and maintenance practices that shall be used to implement the plan:

1. The smallest practical portion of the site shall be denuded at one time.
2. All control measures shall be inspected at least once each week and following any storm event of 0.5 inches or greater.
3. All measures shall be maintained in good working order; if a repair is necessary, it will be initiated within 24 hours.
4. Built-up sediment shall be removed from perimeter barriers when it has reached one-third the height of the barrier or when "bulges" occur.
5. All diversion dikes shall be inspected and any breaches promptly repaired.
6. Temporary seeding and planting shall be inspected for bare spots, washouts, and unhealthy growth.
7. The owner's authorized engineer shall inspect the site on a periodic basis to review compliance with the Plans.
8. An area shall be considered stable if one of the following has occurred:
  - a. Base course gravels have been installed in areas to be paved;
  - b. A minimum of 85% vegetated growth as been established;
  - c. A minimum of 3 inches of non-erosive material such as stone or riprap has been installed; - or -
  - d. Erosion control blankets have been properly installed.
9. The length of time of exposure of area disturbed during construction shall not exceed 45 days.

### B. MULCHING

Mulch shall be used on highly erodible soils, on critically eroding areas, on areas where conservation of moisture will facilitate plant establishment, and where shown on the plans.

1. Timing - In order for mulch to be effective, it must be in place prior to major storm events. There are two (2) types of standards which shall be used to assure this:
  - a. Apply mulch prior to any storm event. This is applicable when working within 100 feet of wetlands. It will be necessary to closely monitor weather predictions, usually by contacting the National Weather Service in Concord, to have adequate warning of significant storms.
  - b. Required Mulching within a specified time period. The time period can range from 21 to 28 days of inactivity on an area, the length of time varying with site conditions. Professional judgment shall be used to evaluate the interaction of site conditions (soil erodibility, season of year, extent of disturbance, proximity to sensitive resources, etc.) and the potential impact of erosion on adjacent areas to choose an appropriate time restriction.
2. Guidelines for Winter Mulch Application -

Type	Rate per 1,000 s.f.	Use and Comments
Hay or Straw	70 to 90 lbs.	Must be dry and free from mold. May be used with plantings.
Wood Chips or Bark Mulch	460 to 920 lbs.	Used mostly with trees and shrub plantings.

## INSTALLATION, MAINTENANCE AND INSPECTION PROCEDURES FOR TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES (CONTINUED)

Jute and Fibrous Matting (Erosion Blanket) As per manufacturer Specifications Used in slope areas, water courses and other Control areas.

Crushed Stone 1/4" to 1-1/2" dia. Spread more than 1/2" thick Effective in controlling wind and water erosion.

Erosion Control Mix 2" thick (min)

- The organic matter content is between 80 and 100%, dry weight basis.
- Particle size by weight is 100% passing a 6" screen and a minimum of 70 % maximum of 85% passing a 0.75" screen.
- The organic portion needs to be fibrous and elongated.
- Large portions of silts, clays or fine sands are not acceptable in the mix.
- Soluble salts content is less than 4.0 mmhos/cm.
- The pH should fall between 5.0 and 8.0.

3. Maintenance - All mulches must be inspected periodically, in particular after rainstorms, to check for rill erosion. If less than 90% of the soil surface is covered by mulch, additional mulch shall be immediately applied.

### C. PERMANENT SEEDING -

1. Bedding - stones larger than 1 1/2", trash, roots, and other debris that will interfere with seeding and future maintenance of the area should be removed. Where feasible, the soil should be tilled to a depth of 5" to prepare a seedbed and mix fertilizer into the soil.
2. Fertilizer - lime and fertilizer should be applied evenly over the area prior to or at the time of seeding and incorporated into the soil. Kinds and amounts of lime and organic fertilizer should be based on an evaluation of soil tests. When a soil test is not available, the following minimum amounts should be applied:

Agricultural Limestone @ 100 lbs. per 1,000 s.f.  
10-20-20 organic fertilizer @ 12 lbs. per 1,000 s.f.

### 3. Seed Mixture (recommended):

Type	Lbs. / Acre	Lbs. / 1,000 sq
Tall Fescue	24	0.55
Creeping Red Fescue	24	0.55
Total	48	1.10

Seed Mixture (For slope embankments):  
Grass Seed: Provide fresh, clean, new-crop seed complying with tolerance for purity and germination established by Official Seed Analysts of North America. Provide seed mixture composed of grass species, proportions and minimum percentages of purity, germination, and maximum percentage of weed seed, as specified:


Type	Min. Purity (%)	Min. Germination (%)	Kg./Hectare (Lbs./Acres)
Creeping Red Fescue (c)	96	85	45 (40)
Perennial Rye Grass (a)	98	90	35 (30)
Redtop	95	80	5 (5)
Alsike Clover	97	90(e)	5 (5)
Total			90 (80)

- a. Ryegrass shall be a certified fine-textured variety such as Pennfine, Fiesta, Yorktown, Diplomat, or equal.
- b. Fescue varieties shall include - Creeping Red and/or Hard Reliant, Scaldis, Koket, or Jamestown.

4. Sodding - sodding is done where it is desirable to rapidly establish cover on a disturbed area. Sodding an area may be substituted for permanent seeding procedures anywhere on site. Bed preparation, fertilizing, and placement of sod shall be performed according to the S.C.S. Handbook. Sodding is recommended for steep sloped areas, areas immediately adjacent to sensitive water courses, easily erodible soils (fine sand/silt), etc.

## WINTER CONSTRUCTION NOTES


1. All proposed vegetated areas which do not exhibit a minimum of 85% vegetative growth by October 15th, or which are disturbed after October 15th, shall be stabilized by seeding and installing erosion control blankets on slopes greater than 3:1, and elsewhere seeding and placing 3 to 4 tons of mulch per acre, secured with anchored netting. The installation of erosion control blankets or mulch and netting shall not occur over accumulated snow or on frozen ground and shall be completed in advance of thaw or spring melt events;
2. All ditches or swales which do not exhibit a minimum of 85% vegetative growth by October 15th, or which are disturbed after October 15th, shall be stabilized temporarily with stone or erosion control blankets appropriate for the design flow conditions; and
3. After November 15th, incomplete road or parking surfaces where work has stopped for the winter season shall be protected with a minimum of 3 inches of crushed gravel per NHDOT Item 304.3.



## CONSTRUCTION SPECIFICATIONS

1. **STONE SIZE** - NHDOT STANDARD STONE SIZE #4 - SECTION 703 OF NHDOT STANDARD.
2. **LENGTH** - DETAILED ON PLANS (50 FOOT MINIMUM).
3. **THICKNESS** - SIX (6) INCHES (MINIMUM).
4. **WIDTH** - FULL DRIVE WIDTH UNLESS OTHERWISE SPECIFIED.
5. **FILTER FABRIC** - MIRAFI 600X OR EQUAL APPROVED BY ENGINEER.
6. **SURFACE WATER CONTROL** - ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE.
7. **MAINTENANCE** - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS WILL REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE OR ADDITIONAL LENGTH AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
8. **WHEELS SHALL BE CLEANED TO REMOVE MUD PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY.** WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
9. **STABILIZED CONSTRUCTION EXITS SHALL BE INSTALLED AT ALL ENTRANCES TO PUBLIC RIGHTS-OF-WAY, AT LOCATIONS SHOWN ON THE PLANS, AND/OR WHERE AS DIRECTED BY THE ENGINEER.**

## STABILIZED CONSTRUCTION EXIT NOT TO SCALE




### NOTES:

1. SILT-SOXX MAY BE USED IN PLACE OF SILT FENCE OR OTHER SEDIMENT BARRIERS.
2. ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
3. SILT-SOXX COMPOST/SOIL/ROCK/SEED FILL MATERIAL SHALL BE ADJUSTED AS NECESSARY TO MEET THE REQUIREMENTS OF THE SPECIFIC APPLICATION.
4. ALL SEDIMENT TRAPPED BY SILT-SOXX SHALL BE DISPOSED OF PROPERLY.


## TUBULAR SEDIMENT BARRIER NOT TO SCALE

### NOTES:

1. ALL TIDAL DATA FROM NOAA.
2. HOTL FROM WETLANDS MAPPING.
3. FUTURE SEA LEVEL RISE PER NH COASTAL FLOOD RISK STUDY.



## TYPICAL SHORELAND CROSS SECTION NOT TO SCALE



## INSTALLATION AND MAINTENANCE:


INSTALLATION: REMOVE THE GRATE FROM CATCH BASIN. IF USING OPTIONAL OIL ABSORBENTS; PLACE ABSORBENT PILLOW IN UNIT. STAND GRATE ON END. MOVE THE TOP LIFTING STRAPS OUT OF THE WAY AND PLACE THE GRATE INTO CATCH BASIN INSERT SO THE GRATE IS BELOW THE TOP STRAPS AND ABOVE THE LOWER STRAPS. HOLDING THE LIFTING DEVICES, INSERT THE GRATE INTO THE INLET.

MAINTENANCE: REMOVE ALL ACCUMULATED SEDIMENT AND DEBRIS FROM VICINITY OF THE UNIT AFTER EACH STORM EVENT. AFTER EACH STORM EVENT AND AT REGULAR INTERVALS, LOOK INTO THE CATCH BASIN INSERT. IF THE CONTAINMENT AREA IS MORE THAN 1/3 FULL OF SEDIMENT, THE UNIT MUST BE EMPTIED. TO EMPTY THE UNIT, LIFT THE UNIT OUT OF THE INLET USING THE LIFTING STRAPS AND REMOVE THE GRATE. IF USING OPTIONAL ABSORBENTS; REPLACE ABSORBENT WHEN NEAR SATURATION.

## UNACCEPTABLE INLET PROTECTION METHOD:

A SIMPLE SHEET OF GEOTEXTILE UNDER THE GRATE IS NOT ACCEPTABLE.

## STORM DRAIN INLET PROTECTION NOT TO SCALE



## MAINTENANCE

THE OUTLET PROTECTION SHOULD BE CHECKED AT LEAST ANNUALLY AND AFTER EVERY MAJOR STORM. IF THE RIPRAP HAS BEEN DISPLACED, UNDERMINED OR DAMAGED, IT SHOULD BE REPAIRED IMMEDIATELY. THE CHANNEL IMMEDIATELY BELOW THE OUTLET SHOULD BE CHECKED TO SEE THAT EROSION IS NOT OCCURRING. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS, AND SEDIMENT THAT COULD CHANGE FLOW PATTERNS AND/OR TAILWATER DEPTHS ON THE PIPES. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE OUTLET PROTECTION APRON.

## CONSTRUCTION SPECIFICATIONS

1. THE SUBGRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIPRAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS.
2. THE ROCK OR GRAVEL USED FOR FILTER OR RIPRAP SHALL CONFORM TO THE SPECIFIED GRADATION.
3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIPRAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
4. STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

## RIPRAP OUTLET PROTECTION NOT TO SCALE



133 Court Street  
(603) 433-2335  
Portsmouth, NH 03801  
www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

## REVISIONS

NO.	DESCRIPTION	BY	DATE
0	TAC WORK SESSION	EBS	12/01/20
1	TAC	EBS	01/18/21
1	TAC	EBS	02/16/21

DRAWN BY: EBS

APPROVED BY: EDW

DRAWING FILE: 5090-DETAILS.dwg

SCALE: 22" x 34" NOT TO SCALE

OWNER:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**

53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

APPLICANT:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**

53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840



## PROJECT:

**WATSON'S LANDING**  
**TAX MAP 209, LOT 33**  
**1 CLARK DRIVE**  
**PORTSMOUTH, NH 03801**

## TITLE:

## DETAIL SHEET

SHEET NUMBER: D-1



18"x18"x6" GRANITE OR CONCRETE EROSION STOP SET AT MID POINT OF WEIR ALONG BERM CENTERLINE

NON-WOVEN GEOTEXTILE (10 OZ/SY)


1'-DEEP RIPRAP ON BOTH SIDES OF EROSION STOP (SEE NOTE 3 BELOW)

- CONSTRUCT EMERGENCY OVERFLOW WEIR TO THE WIDTHS AND LENGTHS SHOWN ON THE PLAN.
- THE SUBGRADE FOR THE GEOTEXTILE FABRIC AND RIPRAP SHALL BE PREPARED TO LINES AND GRADES SHOWN ON THE PLAN.
- UNLESS OTHERWISE SPECIFIED OR DIRECTED, RIPRAP USED FOR THE EMERGENCY OVERFLOW WEIR SHALL MEET THE FOLLOWING GRADATION:

SIZE	PERCENT PASSING BY WEIGHT
4"	90-100
2"	0-15


- GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE EROSION STOP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 18 INCHES.
- THE EROSION STOP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

**RIPRAP SPILLWAY / OVERFLOW WEIR NOT TO SCALE**






- NOTES**
- THE FOUNDATION AREA OF THE SWALE SHALL BE CLEARED AND GRUBBED OF ALL TREES, BRUSH, STUMPS, AND OTHER OBJECTIONABLE MATERIAL.
  - THE SWALE SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE AND CROSS SECTION AS REQUIRED TO MEET THE DESIGN CRITERIA AND BE FREE OF IRREGULARITIES.
  - EARTH FILLS REQUIRED TO MEET SUBGRADE REQUIREMENTS BECAUSE OF OVER EXCAVATION OR TOPOGRAPHY SHALL BE COMPACTED TO THE SAME DENSITY AS THE SURROUNDING SOIL TO PREVENT UNEQUAL SETTLEMENT THAT COULD CAUSE DAMAGE TO THE COMPLETED SWALE.
  - VEGETATION SHALL BE ESTABLISHED IN THE SWALE OR AN EROSION CONTROL MATTING INSTALLED PRIOR TO DIRECTING STORMWATER TO IT.
  - MAINTENANCE OF THE VEGETATION IS EXTREMELY IMPORTANT IN ORDER TO PREVENT RILLING, EROSION, AND FAILURE OF THE SWALE. MOWING SHALL BE DONE FREQUENTLY ENOUGH TO CONTROL ENCROACHMENT OF WEEDS AND WOODY VEGETATION AND TO KEEP GRASSES IN A VIGOROUS CONDITION. THE VEGETATION SHALL NOT BE MOWED TOO CLOSELY SO AS TO REDUCE THE EROSION RESISTANCE IN THE SWALE.
  - THE SWALE SHOULD BE INSPECTED PERIODICALLY AND AFTER ANY STORM GREATER THAN 0.5" OF RAINFALL IN 24 HOURS TO DETERMINE ITS CONDITION. RILLS AND DAMAGED AREAS SHOULD BE PROMPTLY REPAIRED AND REVEGETATED AS NECESSARY TO PREVENT FURTHER DETERIORATION.

**VEGETATED SWALE NOT TO SCALE**







- NOTES**
- CONSTRUCT PLUNGE POOL TO THE WIDTHS AND LENGTHS SHOWN ON THE PLAN.
  - THE SUBGRADE FOR THE GEOTEXTILE FABRIC AND RIPRAP SHALL BE PREPARED TO ACCOUNT FOR THE DEPTH OF RIPRAP.
  - EROSION STOP USED FOR THE PLUNGE POOL SHALL MEET THE FOLLOWING GRADATION:
- | SIZE | PERCENT PASSING BY WEIGHT |
|------|---------------------------|
| 18"  | 100                       |
| 12"  | 90-100                    |
| 4"   | 0-15                      |
- GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE EROSION STOP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 18".
  - THE EROSION STOP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

**PLUNGE POOL NOT TO SCALE**




- NOTES**
- ALL SECTIONS SHALL BE CONCRETE CLASS AA (4000 PSI).
  - CIRCUMFERENTIAL REINFORCEMENT SHALL BE 0.12 SQ. IN. PER LINEAR FT. IN ALL SECTIONS AND SHALL BE PLACED IN THE CENTER THIRD OF THE WALL.
  - THE TONGUE OR GROOVE OF THE JOINT SHALL CONTAIN ONE LINE OF CIRCUMFERENTIAL REINFORCEMENT EQUAL TO 0.12 SQ. IN. PER LINEAR FT.
  - RISERS OF 1', 2', 3' & 4' CAN BE USED TO REACH DESIRED DEPTH.
  - THE STRUCTURES SHALL BE DESIGNED FOR H2O LOADING.
  - USE H2O LOADING SLAB TOP SECTION IN LIEU OF ECCENTRIC TOP WHERE PIPE INVERT IS WITHIN 4' OF FINISH GRADE.
  - FRAME AND GRATE DIMENSIONS ARE TYPICAL BUT MAY VARY BASED ON PRODUCT SELECTED OR EQUIVALENT APPROVED BY THE ENGINEER.

**DEEP SUMP CATCH BASIN NOT TO SCALE**



**CLEANOUT DETAIL NOT TO SCALE**



CRUSHED STONE BEDDING *		
SIEVE SIZE	% PASSING BY WEIGHT	
1"	100	
3/4"	90 - 100	
3/8"	20 - 55	
# 4	0 - 10	
# 8	0 - 5	

\* EQUIVALENT TO STANDARD STONE SIZE #67 - SECTION 703 OF NHDOT STANDARD SPECIFICATIONS

- NOTES**
- WHEN CONTRACTOR EXCAVATES RAIN GARDEN AREA TO SUBGRADE, DESIGN ENGINEER SHALL PERFORM SUBSURFACE EVALUATION PRIOR TO THE PLACEMENT OF ANY SELECT MATERIAL OR OTHER BACKFILL.
  - SOIL FILTER MEDIA SHALL EITHER OPTION A OR OPTION B AT CONTRACTOR'S DISCRETION.
  - DO NOT PLACE RAINGARDEN INTO SERVICE UNTIL IT HAS BEEN PLANTED AND ITS CONTRIBUTING AREAS STABILIZED.
  - DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES TO THE RAINGARDEN DURING ANY STAGE OF CONSTRUCTION.
  - DO NOT TRAFFIC EXPOSED SURFACES OF RAINGARDEN WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATION ACTIVITIES WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE BASIN.

**MAINTENANCE REQUIREMENTS**


- SYSTEMS SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND FOLLOWING ANY RAINFALL EXCEEDING 2.5 INCHES IN A 24-HOUR PERIOD, WITH MAINTENANCE OR REHABILITATION CONDUCTED AS A WARRANTED BY SUCH INSPECTION.
- PRETREATMENT MEASURES SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY, AND CLEANED OF ACCUMULATED SEDIMENT AS WARRANTED BY INSPECTION, BUT NO LESS THAN ONCE ANNUALLY.
- AT LEAST ONCE ANNUALLY, SYSTEM SHOULD BE INSPECTED FOR DRAWDOWN TIME. IF BIORETENTION SYSTEM DOES NOT DRAIN WITHIN 72-HOURS FOLLOWING A RAINFALL EVENT, THEN A QUALIFIED PROFESSIONAL SHOULD ASSESS THE CONDITION OF THE FACILITY TO DETERMINE MEASURES REQUIRED TO RESTORE FILTRATION FUNCTION OR INFILTRATION FUNCTION (AS APPLICABLE), INCLUDING BUT NOT LIMITED TO REMOVAL OF ACCUMULATED SEDIMENTS OR RECONSTRUCTION OF THE FILTER MEDIA.
- VEGETATION SHOULD BE INSPECTED AT LEAST ANNUALLY, AND MAINTAINED IN HEALTHY CONDITION, INCLUDING WEED WHACKING, REMOVAL, AND REPLACEMENT OF DEAD OR DISEASED VEGETATION, AND REMOVAL OF INVASIVE SPECIES.

**DESIGN REFERENCES**

- UNH STORMWATER CENTER
- EPA (1999A)
- NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 2, DECEMBER 2008 AS AMENDED.


**TYPICAL RAINGARDEN NOT TO SCALE**

FILTER MEDIA MIXTURES			
Component Material	Percent of Mixture by Volume	Gradation of material	
		Sieve No.	Percent by Weight Passing Standard Sieve
<b>Filter Media Option A</b>			
ASTM C-33 concrete sand	50 to 55		
Loamy sand topsoil, with fines as indicated	20 to 30	200	15 to 25
Moderately fine shredded bark or wood fiber mulch, with fines as indicated	20 to 30	200	< 5
<b>Filter Media Option B</b>			
Moderately fine shredded bark or wood fiber mulch, with fines as indicated	20 to 30	200	< 5
Loamy coarse sand	70 to 80	10	85 to 100
		20	70 to 100
		60	15 to 40
		200	8 to 15




- NOTES**
- ALL SECTIONS SHALL BE CONCRETE CLASS AA (4000 PSI).
  - CIRCUMFERENTIAL REINFORCEMENT SHALL BE 0.12 SQ. IN. PER LINEAR FT. IN ALL SECTIONS AND SHALL BE PLACED IN THE CENTER THIRD OF THE WALL.
  - THE TONGUE OR GROOVE OF THE JOINT SHALL CONTAIN ONE LINE OF CIRCUMFERENTIAL REINFORCEMENT EQUAL TO 0.12 SQ. IN. PER LINEAR FT.
  - RISERS OF 1', 2', 3' & 4' CAN BE USED TO REACH DESIRED DEPTH.
  - ALL MANHOLE STRUCTURES SHALL BE DESIGNED FOR H2O LOADING.
  - USE H-20 LOADING SLAB TOP SECTION IN LIEU OF ECCENTRIC TOP WHERE PIPE INVERT IS WITHIN 4 FT OF GRADE.
  - MANHOLE STEPS ARE NOT PERMITTED.

**DRAIN MANHOLE DETAIL (PDMH) NOT TO SCALE**



- NOTES:**
- CONSISTENT SLOPE TO GUTTER LINE TO BE MAINTAINED ALONG CURVES.
  - TO BE USED WHERE DRIVEWAYS INTERRUPT A CURBED GUTTER LINE

**DRIVEWAY & GUTTER SECTION NOT TO SCALE**



133 Court Street  
(603) 433-2335

Portsmouth, NH 03801  
www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

**REVISIONS**

NO.	DESCRIPTION	BY	DATE
0	TAC WORK SESSION	EBS	12/01/20
1	TAC	EBS	01/18/21
2	TAC	EBS	02/16/21

DRAWN BY: EBS

APPROVED BY: EDW

DRAWING FILE: 5090-DETAILS.dwg

SCALE: 22" x 34" NOT TO SCALE

**OWNER:**  
FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE

53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

**APPLICANT:**  
FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE

53 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840


**PROJECT:**  
WATSON'S LANDING  
TAX MAP 209, LOT 33  
1 CLARK DRIVE  
PORTSMOUTH, NH 03801

TITLE:

DETAIL SHEET


SHEET NUMBER:

D-2




- NOTES**
- EACH GRAVEL BASE COURSE TO BE CONSTRUCTED AT THE PAVEMENT CROSS SLOPE.
  - REMOVE LEDGE 18" BELOW LOWEST WORK BEING INSTALLED.
  - COMPACT ALL MATERIALS TO 95% STANDARD PROCTOR.
  - REMOVE ALL LOAM, CLAY, MUCK, ORGANIC, YIELDING OR OTHERWISE UNSTABLE MATERIAL TO A MINIMUM OF 20" BELOW THE FINISHED GRADE AND INSTALL COMPACTED SAND (OR GRAVEL BORROW APPROVED BY THE ENGINEER) TO SUBGRADE AS NECESSARY.
  - THE OVER-EXCAVATION OF UNSUITABLE MATERIAL BEYOND THAT SPECIFIED ABOVE, THE INSTALLATION OF UNDERDRAINAGE, AND/OR THE INSTALLATION OF GEOTEXTILE FABRIC SHALL BE PROVIDED UPON DETERMINATION OF THE DEPARTMENT OF PUBLIC WORKS.
  - SUBGRADE SHALL BE FREE OF VOIDS THAT ALLOW MOVEMENT AND/OR SETTLEMENT OF MATERIALS.
  - SUBGRADE SHALL BE PROOF-ROLLED WITH A FULLY LOADED DUMP TRUCK PRIOR TO PLACEMENT OF SELECT GRAVELS. PROOF-ROLLING SHALL BE WITNESSED AND APPROVED BY THE ENGINEER.

**TYPICAL ROADWAY CROSS SECTION** NOT TO SCALE




- NOTES**
- ALL SIGNS SHALL MEET THE REQUIREMENTS OF AND BE INSTALLED AS INDICATED IN THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION.
- LENGTH: AS REQUIRED  
 WEIGHT PER LINEAR FOOT: 2.50 LBS (MIN.)  
 HOLES: 3/8" DIAMETER, 1" C-C FULL LENGTH  
 STEEL: SHALL CONFORM TO ASTM A-499 (GRADE 60) OR ASTM A-576 (GRADE 1070 - 1080)

**SIGN DETAILS** NOT TO SCALE




- NOTES**
- ALL CONDUIT IS TO BE SCHEDULE 40 PVC, ELECTRICAL GRADE, GRAY IN COLOR AND INSTALLED PER THE MANUFACTURER'S RECOMMENDATIONS. A 10-FOOT HORIZONTAL SECTION OF RIGID GALVANIZED STEEL CONDUIT WILL BE REQUIRED AT EACH SWEEP, UNLESS IN THE OPINION OF THE SERVICE PROVIDER DESIGNER, THE SWEEP-PVC JOINT IS NOT SUBJECT TO FAILURE DURING PULLING OF THE CABLE. ALL JOINTS ARE TO BE WATERTIGHT.
  - ALL 90 DEGREE SWEEPS WILL BE MADE WITH RIGID GALVANIZED STEEL WITH A MINIMUM RADIUS OF 36 INCHES FOR PRIMARY CABLES AND 24 INCHES FOR SECONDARY CABLES.
  - BACKFILL MAY BE MADE WITH EXCAVATED MATERIAL OR COMPARABLE, UNLESS MATERIAL IS DEEMED UNSUITABLE BY SERVICE PROVIDER. BACKFILL SHALL BE FREE OF FROZEN LUMPS, ROCKS, DEBRIS, AND RUBBISH. ORGANIC MATERIAL SHALL NOT BE USED AS BACKFILL. BACKFILL SHALL BE IN 6-INCH LAYERS AND THOROUGHLY COMPACTED.
  - A SUITABLE PULLING STRING, CAPABLE OF 300 POUNDS OF PULL, MUST BE INSTALLED IN THE CONDUIT BEFORE SERVICE PROVIDER IS NOTIFIED TO INSTALL CABLE. THE STRING SHOULD BE BLOWN INTO THE CONDUIT AFTER THE RUN IS ASSEMBLED TO AVOID BONDING THE STRING TO THE CONDUIT. A MINIMUM OF TWENTY-FOUR (24") INCHES OF ROPE SLACK SHALL REMAIN AT THE END OF EACH DUCT. PULL ROPE SHALL BE INSTALLED IN ALL CONDUIT FOR FUTURE PULLS. PULL ROPE SHALL BE NYLON ROPE HAVING A MINIMUM TENSILE STRENGTH OF THREE HUNDRED (300#) LBS.
  - SERVICE PROVIDER SHALL BE GIVEN THE OPPORTUNITY TO INSPECT ALL CONDUIT PRIOR TO BACKFILL. THE CONTRACTOR IS RESPONSIBLE FOR ALL REPAIRS SHOULD SERVICE PROVIDER BE UNABLE TO INSTALL ITS CABLE IN A SUITABLE MANNER.
  - TYPICAL CONDUIT SIZES ARE 3-INCH FOR SINGLE PHASE PRIMARY AND SECONDARY VOLTAGE CABLES, 4-INCH FOR THREE PHASE SECONDARY, AND 5-INCH FOR THREE PHASE PRIMARY. HOWEVER, SERVICE PROVIDERS MAY REQUIRE DIFFERENT NUMBERS, TYPES AND SIZES OF CONDUIT THAN THOSE SHOWN HERE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL CONDUIT SIZES, TYPES AND NUMBERS WITH EACH SERVICE PROVIDER PRIOR TO ORDERING THEM.
  - ROUTING OF CONDUIT, LOCATION OF MANHOLES, TRANSFORMERS, CABINETS, HANDHOLES, ETC., SHALL BE DETERMINED BY SERVICE PROVIDER DESIGN PERSONNEL. THE CONTRACTOR SHALL COORDINATE WITH ALL SERVICE PROVIDERS PRIOR TO THE INSTALLATION OF ANY CONDUIT.
  - ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND WHERE APPLICABLE, THE NATIONAL ELECTRIC CODE. WHERE REQUIRED BY UTILITY PROVIDER, CONDUIT SHALL BE SUPPORTED IN PLACE USING PIPE STANCHIONS PLACED EVERY FIVE (5') FEET ALONG THE CONDUIT RUN.
  - UNDER A BUILDING SLAB THE CONDUIT SHALL BE ENCASED IN 8" OF CONCRETE ON ALL SIDES.
  - ALL CONDUIT TERMINATIONS SHALL BE CAPPED TO PREVENT DEBRIS FROM ENTERING CONDUIT.

**ELECTRIC / COMMUNICATION TRENCH** NOT TO SCALE




**REINFORCED GRASS ACCESSWAY** NOT TO SCALE



- NOTES:**
- SEE PLANS FOR CURB LOCATION.
  - ADJOINING STONES SHALL HAVE THE SAME OR APPROXIMATELY THE SAME LENGTH.
  - MINIMUM LENGTH OF CURB STONES = 3'
  - MAXIMUM LENGTH OF STRAIGHT CURB STONES LAID ON CURVES = 10'
  - MAXIMUM LENGTH OF STRAIGHT CURB STONES LAID ON CURVES - SEE CHART.
  - CURB ENDS TO ROUNDED AND BATTERED FACES TO BE CUT WHEN CALLED FOR ON THE PLANS.


RADIUS	MAX. LENGTH
21'	3'
22'-28'	4'
29'-35'	5'
36'-42'	6'
43'-49'	7'
50'-56'	8'
57'-60'	9'
OVER 60'	10'




- NOTES**
- SEE SITE PLAN FOR LIMITS OF CURBING
  - ADJOINING STONES OF STRAIGHT CURB LAID ON CURVES SHALL HAVE THE SAME OR APPROXIMATELY THE SAME LENGTH
  - MINIMUM LENGTH OF STRAIGHT CURB STONES = 18"
  - MAXIMUM LENGTH OF STRAIGHT CURB STONES = 8'
  - MAXIMUM LENGTH OF STRAIGHT CURB STONES LAID ON CURVES - SEE CHART

RADIUS FOR STONES WITH SQUARE JOINTS	MAXIMUM LENGTH
16'-28'	1'-6"
29'-41'	2'
42'-55'	3'
56'-68'	4'
69'-82'	5'
83'-96'	6'
97'-110'	7'
OVER 110'	8'

**SLOPED GRANITE CURB** NOT TO SCALE



**BITUMINOUS SIDEWALK** NOT TO SCALE



- NOTES:**
- THE MAXIMUM ALLOWABLE CROSS SLOPE OF AN ACCESSIBLE ROUTE (SIDEWALK) AND CURB SHALL BE 1.5%.
  - THE MAXIMUM ALLOWABLE SLOPE OF AN ACCESSIBLE ROUTE EXCLUDING CURB RAMPS SHALL BE 5%.
  - THE MAXIMUM ALLOWABLE SLOPE OF AN ACCESSIBLE ROUTE (SIDEWALK) CURB RAMP SHALL BE 8%.
  - CURB TREATMENT VARIES, SEE PLANS FOR CURB TYPE.
  - BASE OF RAMP SHALL BE GRADED TO PREVENT THE PONDING OF WATER.
  - SEE TYPICAL SIDEWALK SECTION FOR RAMP CONSTRUCTION.
  - ALL CURB RAMPS SHALL BE CONSTRUCTED IN ACCORDANCE WITH AMERICANS WITH DISABILITIES ACT (ADA) AND ALL APPLICABLE CODES.
  - FLUSH CURB SECTIONS SHALL HAVE A MAXIMUM LIP REVEAL OF 1/2" AT THE EDGE OF PAVEMENT.
  - EDGES OF SIDEWALK FOOTINGS ALONG FLUSH CURBS SHALL BE HAUNCHED SO AS TO EXTEND TO A MINIMUM DEPTH OF 1' BELOW FINISH GRADE.
  - NO RAMP SHALL BE LESS THAN 4' IN WIDTH.
  - DETECTABLE WARNING PANELS SHALL BE CAST IRON WITH NO SURFACE COATING AND SHALL BE ALLOWED TO TRANSITION TO THEIR NATURAL PATINA.

**CURB RAMP (TYPE 'G')** NOT TO SCALE

**ALTUS ENGINEERING, INC.**  
 133 Court Street  
 (603) 433-2335  
 Portsmouth, NH 03801  
 www.altus-eng.com

STATE OF NEW HAMPSHIRE  
 ERIC D. WEINRIEB  
 No. 7634  
 LICENSED PROFESSIONAL ENGINEER  
 2/11/21

NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: FEBRUARY 16, 2021

**REVISIONS**

NO.	DESCRIPTION	BY	DATE
0	TAC WORK SESSION	EBS	12/01/20
1	TAC	EBS	01/18/21
2	TAC	EBS	02/16/21

DRAWN BY: EBS  
 APPROVED BY: EDW  
 DRAWING FILE: 5090-DETAILS.dwg

SCALE: 22" x 34" NOT TO SCALE

**OWNER:**  
 FREDERICK W. WATSON  
 REVOCABLE TRUST,  
 ROBERT D. WATSON,  
 TRUSTEE  
 53 SLEEPY HOLLOW DRIVE  
 GREENLAND, NH 03840

**APPLICANT:**  
 FREDERICK W. WATSON  
 REVOCABLE TRUST,  
 ROBERT D. WATSON,  
 TRUSTEE  
 53 SLEEPY HOLLOW DRIVE  
 GREENLAND, NH 03840


**PROJECT:**  
 WATSON'S LANDING  
 TAX MAP 209, LOT 33  
 1 CLARK DRIVE  
 PORTSMOUTH, NH 03801

TITLE:

DETAIL SHEET

SHEET NUMBER:

D-3



- NOTES**
- BACKFILL MATERIAL BELOW PAVED OR CONCRETE AREAS, BEDDING MATERIAL, AND SAND BLANKET SHALL BE COMPACTED TO NOT LESS THAN 95% OF AASHTO T 99, METHOD C. SUITABLE BACKFILL MATERIAL BELOW LOAM AREAS SHALL BE COMPACTED TO NOT LESS THAN 90% OF AASHTO T 99, METHOD C.
  - INSULATE GRAVITY SEWER AND FORCEMAINS WHERE THERE IS LESS THAN 5'-0" OF COVER WITH 2" THICK CLOSED CELL RIGID BOARD INSULATION, 18" ON EACH SIDE OF PIPE.
  - MAINTAIN 12" MINIMUM HORIZONTAL SEPARATION AND WIDEN TRENCH ACCORDINGLY IF MULTIPLE PIPES ARE IN TRENCH.

SAND BLANKET/BARRIER		SCREENED GRAVEL OR CRUSHED STONE BEDDING*	
SIEVE SIZE	% FINER BY WEIGHT	SIEVE SIZE	% PASSING BY WEIGHT
1/2"	90 - 100	1"	100
200	0 - 15	3/4"	90 - 100
		3/8"	20 - 55
		# 4	0 - 10
		# 8	0 - 5


\* EQUIVALENT TO STANDARD STONE SIZE #67 - SECTION 703 OF NHDOT STANDARD SPECIFICATIONS

**STANDARD TRENCH NOTES**

- ORDERED EXCAVATION OF UNSUITABLE MATERIAL BELOW GRADE: BACKFILL AS STATED IN THE TECHNICAL SPECIFICATIONS OR AS SHOWN ON THE DRAWING.
- BEDDING: SCREENED GRAVEL AND/OR CRUSHED STONE FREE FROM CLAY, LOAM, ORGANIC MATTER AND MEETING THE GRADATION SHOWN IN THE TRENCH DETAIL. WHERE ORDERED BY THE ENGINEER TO STABILIZE THE BASE, SCREENED GRAVEL OR CRUSHED STONE 1-1/2 INCH TO 1/2 INCH SHALL BE USED.
- SAND BLANKET: CLEAN SAND FREE FROM ORGANIC MATTER MEETING THE GRADATION SHOWN IN THE TRENCH DETAIL. BLANKET MAY BE REPLACED WITH BEDDING MATERIAL FOR CAST-IRON, DUCTILE IRON, AND REINFORCED CONCRETE PIPE PROVIDED THAT NO STONE LARGER THAN 2" IS IN CONTACT WITH THE PIPE AND THE GEOTEXTILE IS RELOCATED ACCORDINGLY.
- SUITABLE MATERIAL: IN ROADS, ROAD SHOULDERS, WALKWAYS AND TRAVELED WAYS, SUITABLE MATERIAL FOR TRENCH BACKFILL SHALL BE THE NATURAL MATERIAL EXCAVATED DURING THE COURSE OF CONSTRUCTION, BUT SHALL EXCLUDE DEBRIS, PIECES OF PAVEMENT, ORGANIC MATTER, TOP SOIL, ALL WET OR SOFT MUCK, PEAT, OR CLAY, ALL EXCAVATED LEDGE MATERIAL, ALL ROCKS OVER 6 INCHES IN LARGEST DIMENSION, AND ANY MATERIAL WHICH, AS DETERMINED BY THE ENGINEER, WILL NOT PROVIDE SUFFICIENT SUPPORT OR MAINTAIN THE COMPLETED CONSTRUCTION IN A STABLE CONDITION. IN CROSS COUNTRY CONSTRUCTION, SUITABLE MATERIAL SHALL BE AS DESCRIBED ABOVE, EXCEPT THAT THE ENGINEER MAY PERMIT THE USE OF TOP SOIL, LOAM, MUCK, OR PEAT, IF SATISFIED THAT THE COMPLETED CONSTRUCTION WILL BE ENTIRELY STABLE AND PROVIDED THAT EASY ACCESS TO THE SEWER FOR MAINTENANCE AND POSSIBLE RECONSTRUCTION WILL BE PRESERVED.
- BASE COURSE AND PAVEMENT SHALL MEET THE REQUIREMENTS OF THE NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION'S LATEST EDITION OF THE STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES - DIVISIONS 300 AND 400 RESPECTIVELY.
- SHEETING, IF REQUIRED: WHERE SHEETING IS PLACED ALONGSIDE THE PIPE AND EXTENDS BELOW MID-DIAMETER, IT SHALL BE CUT OFF AND LEFT IN PLACE TO AN ELEVATION 1 FOOT ABOVE THE TOP OF PIPE. WHERE SHEETING IS ORDERED BY THE ENGINEER TO BE LEFT IN PLACE, IT SHALL BE CUT OFF AT LEAST 3 FEET BELOW FINISHED GRADE, BUT NOT LESS THAN 1 FOOT ABOVE THE TOP OF THE PIPE.
- W = MAXIMUM ALLOWABLE TRENCH WIDTH TO A PLANE 12 INCHES ABOVE THE PIPE. FOR PIPES 15 INCHES NOMINAL DIAMETER OR LESS, W SHALL BE NO MORE THAN 36 INCHES. FOR PIPES GREATER THAN 15 INCHES IN NOMINAL DIAMETER, W SHALL BE 24 INCHES PLUS PIPE OUTSIDE DIAMETER (O.D.) ALSO, W SHALL BE THE PAYMENT WIDTH FOR LEDGE EXCAVATION AND FOR ORDERED EXCAVATION BELOW GRADE.
- FOR CROSS COUNTRY CONSTRUCTION, BACKFILL, FILL AND/OR LOAM SHALL BE MOUND TO A HEIGHT OF 6 INCHES ABOVE THE ORIGINAL GROUND SURFACE.
- CONCRETE FOR ENCASEMENT SHALL CONFORM TO THE NEW HAMPSHIRE DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS STANDARD SPECIFICATION REQUIREMENTS FOR CLASS A (3000#) CONCRETE AS FOLLOWS:  
CEMENT: 6.0 BAGS PER CUBIC YARD  
WATER: 5.75 GALLONS PER BAG  
CEMENT MAXIMUM SIZE OF AGGREGATE: 1 INCH  
CONCRETE ENCASEMENT IS NOT ALLOWED FOR PVC PIPE.
- CONCRETE FULL ENCASEMENT: IF FULL ENCASEMENT IS UTILIZED, DEPTH OF CONCRETE BELOW PIPE SHALL BE 1/4 I.D. (4" MINIMUM). BLOCK SUPPORT SHALL BE SOLID CONCRETE BLOCKS.
- NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES DESIGN STANDARDS REQUIRE TEN FEET (10') SEPARATION BETWEEN WATER AND SEWER. REFER TO TOWN'S STANDARD SPECIFICATIONS FOR METHODS OF PROTECTION IN AREAS THAT CANNOT MEET THESE REQUIREMENTS.

**DRAINAGE, SEWER & FORCEMAIN TRENCH**

NOT TO SCALE



**DEEP SEWER SERVICE CONNECTION**


NOT TO SCALE

**THRUST BLOCKING**

NOT TO SCALE

- NOTES**
- POUR THRUST BLOCKS AGAINST UNDISTURBED MATERIAL. WHERE TRENCH WALL HAS BEEN DISTURBED, EXCAVATE LOOSE MATERIAL AND EXTEND THRUST BLOCK TO UNDISTURBED MATERIAL.
  - NO JOINTS SHALL BE COVERED WITH CONCRETE. POLYETHYLENE (6 MIL) SHALL BE PLACED AROUND FITTINGS PRIOR TO CONCRETE PLACEMENT.
  - ON BENDS AND TEES, EXTEND THRUST BLOCKS FULL LENGTH OF FITTING.
  - PLACE BOARD IN FRONT OF ALL PLUGS BEFORE POURING THRUST BLOCKS. WHERE M.J. PIPE IS USED, M.J. PLUG WITH RETAINER GLAND MAY BE SUBSTITUTED FOR END BLOCKINGS.

REACTION TYPE	PIPE SIZE				
	4"	6"	8"	10"	12"
A 90°	0.89	2.19	3.82	11.14	17.24
B 180°	0.65	1.55	2.78	8.38	12.00
C 45°	0.48	1.19	2.12	6.02	9.32
D 22-1/2°	0.25	0.60	1.06	3.08	4.74
E 11-1/4°	0.13	0.30	0.54	1.54	2.38




SAND BLANKET/BARRIER	
SIEVE SIZE	% FINER BY WEIGHT
1/2"	90 - 100
200	0 - 15

**NOTES**

- BACKFILL MATERIAL BELOW PAVED OR CONCRETE AREAS, BEDDING MATERIAL, AND SAND BLANKET SHALL BE COMPACTED TO NOT LESS THAN 95% OF AASHTO T 99, METHOD C. SUITABLE BACKFILL MATERIAL BELOW LOAM AREAS SHALL BE COMPACTED TO NOT LESS THAN 90% OF AASHTO T 99, METHOD C.
- DUCTILE IRON WATER MAINS SHALL BE POLY WRAPPED FOR THEIR ENTIRE LENGTH.
- WATER MAINS SHALL HAVE 3 WEDGES PER JOINT.

**WATER MAIN TRENCH**

NOT TO SCALE




**NOTES**


- HYDRANT INSTALLATION AND OPERATION TO CONFORM TO REGULATIONS OF THE CITY OF PORTSMOUTH WATER & FIRE DEPARTMENTS.
- GATE VALVES & HYDRANTS TO OPEN RIGHT (CLOCKWISE).

**FIRE HYDRANT**

NOT TO SCALE



NOTE: ALL MATERIALS AND SPECIFICATIONS SHALL CONFORM TO CITY OF PORTSMOUTH WATER DEPARTMENT STANDARDS AND REQUIREMENTS. VERIFY PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITIES.




**WATER SERVICE CONNECTION**

NOT TO SCALE


**TEE & GATE VALVE ASSEMBLY DETAIL**

NOT TO SCALE



**WATER VALVE DETAIL**

NOT TO SCALE




**WATER VALVE DETAIL**

NOT TO SCALE



133 Court Street  
(603) 433-2335  
Portsmouth, NH 03801  
www.altus-eng.com



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: JANUARY 18, 2021

NO.	REVISIONS DESCRIPTION	BY	DATE
0	TAC WORK SESSION	EBS	12/01/20
1	TAC	EBS	01/18/21

DRAWN BY: EBS

APPROVED BY: EDW

DRAWING FILE: 5090-DETAILS.dwg

SCALE: 22" x 34" NOT TO SCALE

OWNER: FREDERICK W. WATSON REVOCABLE TRUST, ROBERT D. WATSON, TRUSTEE

53 SLEEPY HOLLOW DRIVE GREENLAND, NH 03840

APPLICANT: FREDERICK W. WATSON REVOCABLE TRUST, ROBERT D. WATSON, TRUSTEE

53 SLEEPY HOLLOW DRIVE GREENLAND, NH 03840

PROJECT: WATSON'S LANDING

TAX MAP 209, LOT 33

1 CLARK DRIVE PORTSMOUTH, NH 03801

TITLE:

DETAIL SHEET

SHEET NUMBER: D-4

**DRAINAGE ANALYSIS**  
**FOR**  
**Site Development**  
**of**  
**Watson's Landing Residential Subdivision**

**1 Clark Drive**  
**Portsmouth, NH**

**Tax Map 209, Lot 33**

**January 18, 2021**  
**Revised February 16, 2021**

*Prepared For:*

**Frederick W. Watson Revocable Trust**  
**Robert D. Watson, Trustee**  
53 Sleepy Hollow Drive  
Greenland, NH 03840

*Prepared By:*

**ALTUS ENGINEERING, INC.**  
133 Court Street  
Portsmouth, NH 03801  
Phone: (603) 433-2335



# Table of Contents

Section 1	Narrative
	Project Description
	Site Overview
	Site Soils
	Proposed Site Design
	Calculation Methods
	Disclaimer
	Drainage Analysis
	Conclusions
Section 2	Aerial Photo and USGS Map
Section 3	Drainage Analysis, Pre-Development
Section 4	Drainage Analysis, Post-Development
Section 5	BMP and Riprap Calculations
Section 6	NRCC Extreme Precipitation Table (Rainfall Data)
Section 7	NRCS Soils Report
Section 8	Stormwater Operations and Maintenance Plan
Section 9	Watershed Plans
	Pre-Development Watershed Plan
	Post-Development Watershed Plan

# Section 1

## Narrative

## **PROJECT DESCRIPTION**

The Frederick W. Watson Revocable Trust is proposing to subdivide an existing residential lot located at 1 Clark Drive in Portsmouth, NH. The property is identified as Assessor's Map 209, Lot 33, is approximately 3.1 (+/-) acres in size and is located in the City's Single Residence B (SRB) district. The site currently has a single-family residence, pool, and private roadway surrounded by a large lawn area with limited woodlands.

The proposed project will raze the existing house, construct an approximately 325' long private cul-de-sac roadway and create four single-family residential lots serviced by municipal water and sewer.

Runoff from the development will be directed to a 170-foot long rain garden to provide stormwater treatment. The stormwater management system proposed for the site will reduce peak flows and treat site runoff prior to discharging to Inner Cutts Cove, a tidal water adjacent to the site.

### ***Site Soils***

The NRCS indicates that the subject property consists of several primary soil classifications:  
799 – Urban-Land-Canton complex, HSG C

### ***Pre-Development (Existing Conditions)***

The pre-development site conditions reflect the existing conditions of the site, which include the existing house, pool and private roadway. The current site primarily discharges radially to the east and southeast to Inner Cutts Cove, identified as Point of Analysis #1 (POA #1). The Pre-Development analysis models the existing site conditions for the point of analysis.

The grades and elevations shown on the plans are based on the site survey completed by Knight Hill Surveying Services, Inc. and included in the plan set as Topo/Boundary Worksheet. The study pre-development area was analyzed as one (1) watershed, which discharges to POA #1 as identified above.

### ***Post-Development (Proposed Site Design)***

The existing house, patio and pool will be razed and a new roadway with associated site improvements will be constructed. The remainder of the lot will be subdivided into four (4) single-family house lots to be developed by others. Significant impervious areas for conceptual houses and driveways were included in the analysis to simulate future lot development.

The proposed stormwater system is depicted on the attached Post-Development Watershed Plan. For the post development analysis, the site was divided into seven (7) watershed areas to more accurately

depict the post-development conditions. The same point of analysis used in the Pre-Development model (POA #1) was used for comparison of the Pre and Post development conditions.

The Post-Development Watershed Plan illustrates the proposed stormwater management system. Site topography, existing features, proposed site improvements, proposed grading, drainage and erosion control measures are shown on the accompanying plans. Recommended erosion control measures are based upon the December 2008 edition of the “*New Hampshire Stormwater Manual Volumes 1 through 3*” prepared by NHDES and Comprehensive Environmental, Inc. as amended.

## **CALCULATION METHODS**

The drainage study was completed using the USDA SCS TR-20 Method within the HydroCAD Stormwater Modeling System. Reservoir routing was performed with the Dynamic Storage Indication method with automated calculation of tailwater conditions. A Type III 24-hour rainfall distribution was utilized in analyzing the data for the 2, 10, 25 and 50 year - 24-hour storm events using rainfall data provided by the Northeast Regional Climate Center (NRCC). As the project site lies within a Coastal and Great Bay Community identified by NHDES Alteration of Terrain, all rainfall amounts were increased by 15% to account for potential future increases in rainfall due to climate change.

### ***Disclaimer***

Altus Engineering, Inc. notes that stormwater modeling is limited in its capacity to precisely predict peak rates of runoff and flood elevations. Results should not be considered to represent actual storm events due to the number of variables and assumptions involved in the modeling effort. Surface roughness coefficients ( $n$ ), entrance loss coefficients ( $k_e$ ), velocity factors ( $k_v$ ) and times of concentration ( $T_c$ ) are based on subjective field observations and engineering judgment using available data. For design purposes, curve numbers ( $C_n$ ) describe the average conditions. However, curve numbers will vary from storm to storm depending on the antecedent runoff conditions (ARC) including saturation and frozen ground. Also, higher water elevations than predicted by modeling could occur if drainage channels, closed drain systems or culverts are not maintained and/or become blocked by debris before and/or during a storm event as this will impact flow capacity of the structures. Structures should be re-evaluated if future changes occur within relevant drainage areas in order to assess any required design modifications.

## *Drainage Analysis*

A complete summary of the drainage model is included in the appendix of this report. The following table compares pre- and post-development peak rates at the Point of Analysis identified on the plans for the 2, 10, 25, and 50-year storm events:

**Stormwater Modeling Summary**  
**Peak Q (cfs) for Type III 24-Hour Storm Events**

*Rainfall Intensities Reflect 15% Increase per AoT	<b>2-Yr Storm (3.69 inch)</b>	<b>10-Yr Storm (5.60 inch)</b>	<b>25-Yr Storm (7.10 inch)</b>	<b>50-Yr Storm (8.50 inch)</b>
<b>POA #1</b>				
Pre	4.56	9.41	13.45	17.29
Post	4.27	8.97	12.73	16.31
<b>Change</b>	<b>-0.29</b>	<b>-0.44</b>	<b>-0.72</b>	<b>-0.98</b>

As the above table demonstrates, the proposed peak rates of runoff will be decreased from the existing conditions for all analyzed storm events.

## **CONCLUSION**


This proposed site development of Watson's Landing subdivision off of Clark Drive in Portsmouth, NH will have minimal adverse effect on abutting properties and infrastructure as a result of stormwater runoff or siltation. Post-construction peak rates of runoff from the site will be lower than the existing conditions for all analyzed storm events. The new stormwater management system will also provide appropriate treatment of runoff from the entirety of the proposed impervious area. Appropriate steps will be taken to properly mitigate erosion and sedimentation through the use of temporary and permanent Best Management Practices for sediment and erosion control, including deep sump catch basins with grease hoods, vegetated swales and a raingarden.

## Section 2

# Aerial Photo and USGS Map



# Map by NH GRANIT



## Legend


- State
- County
- City/Town

Map Scale  
1: 24,000



© NH GRANIT, www.granit.unh.edu  
Map Generated: 12/23/2020

## Notes



## Section 3

# Drainage Calculations

Pre-Development

2-Year, 24-Hour Summary

10-Year, 24-Hour Complete



25-Year, 24-Hour Summary

50-Year, 24-Hour Summary



POA #1

Project Site to POA #1



**5090 Pre**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

*Type III 24-hr 2-yr Rainfall=3.69"*

Printed 2/10/2021

Page 2

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: Project Site to POA #1** Runoff Area=151,238 sf 12.17% Impervious Runoff Depth=1.50"  
Flow Length=550' Tc=14.6 min CN=76 Runoff=4.56 cfs 0.435 af



**Reach 100R: POA #1** Avg. Flow Depth=0.22' Max Vel=1.65 fps Inflow=4.56 cfs 0.435 af  
n=0.025 L=1.0' S=0.0100 '/ Capacity=120.83 cfs Outflow=4.56 cfs 0.435 af

**Total Runoff Area = 3.472 ac Runoff Volume = 0.435 af Average Runoff Depth = 1.50"**  
**87.83% Pervious = 3.049 ac 12.17% Impervious = 0.422 ac**



POA #1

Project Site to POA #1



**5090 Pre**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Printed 2/10/2021

Page 2

**Area Listing (all nodes)**

Area (acres)	CN	Description (subcatchment-numbers)
2.116	74	>75% Grass cover, Good, HSG C (1S)
0.346	98	Paved parking, HSG C (1S)
0.076	98	Roofs, HSG C (1S)
0.933	70	Woods, Good, HSG C (1S)
<b>3.472</b>	<b>76</b>	<b>TOTAL AREA</b>

**5090 Pre**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Printed 2/10/2021

Page 3

**Soil Listing (all nodes)**

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
3.472	HSG C	1S
0.000	HSG D	
0.000	Other	
<b>3.472</b>		<b>TOTAL AREA</b>

**5090 Pre**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.60"

Printed 2/10/2021

Page 4

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: Project Site to POA #1** Runoff Area=151,238 sf 12.17% Impervious Runoff Depth=3.04"  
Flow Length=550' Tc=14.6 min CN=76 Runoff=9.41 cfs 0.879 af

**Reach 100R: POA #1**

Avg. Flow Depth=0.31' Max Vel=2.07 fps Inflow=9.41 cfs 0.879 af  
n=0.025 L=1.0' S=0.0100 '/ Capacity=120.83 cfs Outflow=9.41 cfs 0.879 af

**Total Runoff Area = 3.472 ac Runoff Volume = 0.879 af Average Runoff Depth = 3.04"**  
**87.83% Pervious = 3.049 ac 12.17% Impervious = 0.422 ac**

**Summary for Subcatchment 1S: Project Site to POA #1**

Runoff = 9.41 cfs @ 12.21 hrs, Volume= 0.879 af, Depth= 3.04"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-yr Rainfall=5.60"

Area (sf)	CN	Description
15,072	98	Paved parking, HSG C
3,330	98	Roofs, HSG C
40,658	70	Woods, Good, HSG C
92,178	74	>75% Grass cover, Good, HSG C
151,238	76	Weighted Average
132,836		87.83% Pervious Area
18,402		12.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.9	100	0.0400	0.24		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 3.69"
6.5	320	0.0030	0.82		<b>Shallow Concentrated Flow,</b> Grassed Waterway Kv= 15.0 fps
1.2	130	0.1400	1.87		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
14.6	550	Total			

**Subcatchment 1S: Project Site to POA #1**

Hydrograph




### Summary for Reach 100R: POA #1

Inflow Area = 3.472 ac, 12.17% Impervious, Inflow Depth = 3.04" for 10-yr event  
 Inflow = 9.41 cfs @ 12.21 hrs, Volume= 0.879 af  
 Outflow = 9.41 cfs @ 12.21 hrs, Volume= 0.879 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Max. Velocity= 2.07 fps, Min. Travel Time= 0.0 min  
 Avg. Velocity = 0.75 fps, Avg. Travel Time= 0.0 min


Peak Storage= 5 cf @ 12.21 hrs  
 Average Depth at Peak Storage= 0.31'  
 Bank-Full Depth= 1.00' Flow Area= 26.7 sf, Capacity= 120.83 cfs

40.00' x 1.00' deep Parabolic Channel, n= 0.025 Earth, clean & winding  
 Length= 1.0' Slope= 0.0100 '/'  
 Inlet Invert= 1.00', Outlet Invert= 0.99'



### Reach 100R: POA #1



Hydrograph





POA #1

Project Site to POA #1



**5090 Pre**

*Type III 24-hr 25-yr Rainfall=7.10"*

Prepared by Altus Engineering, Inc.

Printed 2/10/2021

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Page 3

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: Project Site to POA #1** Runoff Area=151,238 sf 12.17% Impervious Runoff Depth=4.35"  
Flow Length=550' Tc=14.6 min CN=76 Runoff=13.45 cfs 1.258 af

**Reach 100R: POA #1**



Avg. Flow Depth=0.36' Max Vel=2.31 fps Inflow=13.45 cfs 1.258 af  
n=0.025 L=1.0' S=0.0100 '/ Capacity=120.83 cfs Outflow=13.45 cfs 1.258 af

**Total Runoff Area = 3.472 ac Runoff Volume = 1.258 af Average Runoff Depth = 4.35"**  
**87.83% Pervious = 3.049 ac 12.17% Impervious = 0.422 ac**



POA #1

Project Site to POA #1



## Section 4

# Drainage Calculations



Post-Development

2-Year, 24-Hour Summary

10-Year, 24-Hour Complete

25-Year, 24-Hour Summary

50-Year, 24-Hour Summary



**5090 Post - Copy**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.69"

Printed 2/10/2021

Page 2

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

<b>Subcatchment 10S: Roadway</b>	Runoff Area=4,876 sf 59.56% Impervious Runoff Depth=2.44" Tc=6.0 min CN=88 Runoff=0.31 cfs 0.023 af
<b>Subcatchment 11S: Roadway</b>	Runoff Area=6,718 sf 62.13% Impervious Runoff Depth=2.53" Tc=6.0 min CN=89 Runoff=0.44 cfs 0.033 af
<b>Subcatchment 13S: Roadway</b>	Runoff Area=3,183 sf 56.17% Impervious Runoff Depth=2.35" Tc=6.0 min CN=87 Runoff=0.20 cfs 0.014 af
<b>Subcatchment 14S: Roadway</b>	Runoff Area=2,407 sf 100.00% Impervious Runoff Depth=3.46" Tc=6.0 min CN=98 Runoff=0.19 cfs 0.016 af
<b>Subcatchment 15S: 19S</b>	Runoff Area=77,120 sf 25.21% Impervious Runoff Depth=1.79" Flow Length=480' Tc=17.3 min CN=80 Runoff=2.63 cfs 0.264 af
<b>Subcatchment 16S: Cul-de-sac</b>	Runoff Area=4,819 sf 55.95% Impervious Runoff Depth=2.35" Tc=6.0 min CN=87 Runoff=0.30 cfs 0.022 af
<b>Subcatchment 20S: Remaining Land</b>	Runoff Area=52,115 sf 0.00% Impervious Runoff Depth=1.19" Flow Length=175' Tc=8.5 min CN=71 Runoff=1.41 cfs 0.118 af
<b>Reach 16R: Outfall</b>	Avg. Flow Depth=0.09' Max Vel=0.77 fps Inflow=0.11 cfs 0.134 af n=0.100 L=75.0' S=0.1200 '/' Capacity=4.89 cfs Outflow=0.11 cfs 0.134 af
<b>Reach 100R: POA #1</b>	Avg. Flow Depth=0.21' Max Vel=1.62 fps Inflow=4.27 cfs 0.466 af n=0.025 L=1.0' S=0.0100 '/' Capacity=120.83 cfs Outflow=4.27 cfs 0.466 af
<b>Pond 10P: PCB #10</b>	Peak Elev=26.39' Inflow=0.31 cfs 0.023 af 12.0" Round Culvert n=0.013 L=8.0' S=0.0050 '/' Outflow=0.31 cfs 0.023 af
<b>Pond 11P: PCB #11</b>	Peak Elev=26.46' Inflow=0.44 cfs 0.033 af 12.0" Round Culvert n=0.013 L=8.0' S=0.0050 '/' Outflow=0.44 cfs 0.033 af
<b>Pond 12P: PDMH #13</b>	Peak Elev=26.42' Inflow=0.75 cfs 0.055 af 12.0" Round Culvert n=0.013 L=155.0' S=0.0050 '/' Outflow=0.75 cfs 0.055 af
<b>Pond 13P: PCB #12</b>	Peak Elev=27.35' Inflow=0.20 cfs 0.014 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.20 cfs 0.014 af
<b>Pond 14P: PCB #13</b>	Peak Elev=27.35' Inflow=0.19 cfs 0.016 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.19 cfs 0.016 af
<b>Pond 15P: PDMH #15</b>	Peak Elev=25.69' Inflow=1.14 cfs 0.086 af 12.0" Round Culvert n=0.013 L=67.0' S=0.0051 '/' Outflow=1.14 cfs 0.086 af
<b>Pond 16P: PCB #14</b>	Peak Elev=26.81' Inflow=0.30 cfs 0.022 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.30 cfs 0.022 af

**5090 Post - Copy**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.69"

Printed 2/10/2021

Page 3

**Pond 17P: PDMH #17**

Peak Elev=25.35' Inflow=1.44 cfs 0.107 af  
12.0" Round Culvert n=0.013 L=84.0' S=0.0050 '/ Outflow=1.44 cfs 0.107 af




**Pond 18P: PDMH #15**

Peak Elev=24.72' Inflow=1.44 cfs 0.107 af  
12.0" Round Culvert n=0.013 L=117.0' S=0.0605 '/ Outflow=1.44 cfs 0.107 af

**Pond 19P: Raingarden #1**

Peak Elev=18.25' Storage=3,716 cf Inflow=3.39 cfs 0.371 af  
Primary=0.11 cfs 0.134 af Secondary=3.17 cfs 0.214 af Outflow=3.28 cfs 0.347 af

**Total Runoff Area = 3.472 ac Runoff Volume = 0.489 af Average Runoff Depth = 1.69"**  
**77.91% Pervious = 2.705 ac 22.09% Impervious = 0.767 ac**



**Routing Diagram for 5090 Post - Copy**  
 Prepared by Altus Engineering, Inc., Printed 2/10/2021  
 HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

## 5090 Post - Copy

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Printed 2/10/2021

Page 2

### Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
1.772	74	>75% Grass cover, Good, HSG C (10S, 11S, 13S, 15S, 16S, 20S)
0.427	98	Paved parking, HSG C (10S, 11S, 13S, 14S, 15S, 16S)
0.340	98	Roofs, HSG C (11S, 15S)
0.933	70	Woods, Good, HSG C (20S)
<b>3.472</b>	<b>78</b>	<b>TOTAL AREA</b>

**5090 Post - Copy**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Printed 2/10/2021

Page 3

**Soil Listing (all nodes)**

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
3.472	HSG C	10S, 11S, 13S, 14S, 15S, 16S, 20S
0.000	HSG D	
0.000	Other	
<b>3.472</b>		<b>TOTAL AREA</b>

## 5090 Post - Copy

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Printed 2/10/2021

Page 4

### Pipe Listing (all nodes)

Line#	Node Number	In-Invert (feet)	Out-Invert (feet)	Length (feet)	Slope (ft/ft)	n	Diam/Width (inches)	Height (inches)	Inside-Fill (inches)
1	10P	26.05	26.01	8.0	0.0050	0.013	12.0	0.0	0.0
2	11P	26.05	26.01	8.0	0.0050	0.013	12.0	0.0	0.0
3	12P	25.91	25.14	155.0	0.0050	0.013	12.0	0.0	0.0
4	13P	27.10	27.05	5.0	0.0100	0.013	12.0	0.0	0.0
5	14P	27.10	27.05	5.0	0.0100	0.013	12.0	0.0	0.0
6	15P	25.04	24.70	67.0	0.0051	0.013	12.0	0.0	0.0
7	16P	26.50	26.45	5.0	0.0100	0.013	12.0	0.0	0.0
8	17P	24.60	24.18	84.0	0.0050	0.013	12.0	0.0	0.0
9	18P	24.08	17.00	117.0	0.0605	0.013	12.0	0.0	0.0
10	19P	14.50	14.03	47.0	0.0100	0.012	6.0	0.0	0.0

**5090 Post - Copy**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.60"

Printed 2/10/2021

Page 5

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

<b>Subcatchment 10S: Roadway</b>	Runoff Area=4,876 sf 59.56% Impervious Runoff Depth=4.24" Tc=6.0 min CN=88 Runoff=0.53 cfs 0.040 af
<b>Subcatchment 11S: Roadway</b>	Runoff Area=6,718 sf 62.13% Impervious Runoff Depth=4.35" Tc=6.0 min CN=89 Runoff=0.74 cfs 0.056 af
<b>Subcatchment 13S: Roadway</b>	Runoff Area=3,183 sf 56.17% Impervious Runoff Depth=4.14" Tc=6.0 min CN=87 Runoff=0.34 cfs 0.025 af
<b>Subcatchment 14S: Roadway</b>	Runoff Area=2,407 sf 100.00% Impervious Runoff Depth=5.36" Tc=6.0 min CN=98 Runoff=0.30 cfs 0.025 af
<b>Subcatchment 15S: 19S</b>	Runoff Area=77,120 sf 25.21% Impervious Runoff Depth=3.42" Flow Length=480' Tc=17.3 min CN=80 Runoff=5.05 cfs 0.505 af
<b>Subcatchment 16S: Cul-de-sac</b>	Runoff Area=4,819 sf 55.95% Impervious Runoff Depth=4.14" Tc=6.0 min CN=87 Runoff=0.51 cfs 0.038 af
<b>Subcatchment 20S: Remaining Land</b>	Runoff Area=52,115 sf 0.00% Impervious Runoff Depth=2.58" Flow Length=175' Tc=8.5 min CN=71 Runoff=3.22 cfs 0.257 af
<b>Reach 16R: Outfall</b>	Avg. Flow Depth=0.09' Max Vel=0.80 fps Inflow=0.12 cfs 0.149 af n=0.100 L=75.0' S=0.1200 '/' Capacity=4.89 cfs Outflow=0.12 cfs 0.149 af
<b>Reach 100R: POA #1</b>	Avg. Flow Depth=0.30' Max Vel=2.03 fps Inflow=8.97 cfs 0.921 af n=0.025 L=1.0' S=0.0100 '/' Capacity=120.83 cfs Outflow=8.97 cfs 0.921 af
<b>Pond 10P: PCB #10</b>	Peak Elev=26.50' Inflow=0.53 cfs 0.040 af 12.0" Round Culvert n=0.013 L=8.0' S=0.0050 '/' Outflow=0.53 cfs 0.040 af
<b>Pond 11P: PCB #11</b>	Peak Elev=26.59' Inflow=0.74 cfs 0.056 af 12.0" Round Culvert n=0.013 L=8.0' S=0.0050 '/' Outflow=0.74 cfs 0.056 af
<b>Pond 12P: PDMH #13</b>	Peak Elev=26.60' Inflow=1.27 cfs 0.095 af 12.0" Round Culvert n=0.013 L=155.0' S=0.0050 '/' Outflow=1.27 cfs 0.095 af
<b>Pond 13P: PCB #12</b>	Peak Elev=27.44' Inflow=0.34 cfs 0.025 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.34 cfs 0.025 af
<b>Pond 14P: PCB #13</b>	Peak Elev=27.41' Inflow=0.30 cfs 0.025 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.30 cfs 0.025 af
<b>Pond 15P: PDMH #15</b>	Peak Elev=25.94' Inflow=1.90 cfs 0.145 af 12.0" Round Culvert n=0.013 L=67.0' S=0.0051 '/' Outflow=1.90 cfs 0.145 af
<b>Pond 16P: PCB #14</b>	Peak Elev=26.92' Inflow=0.51 cfs 0.038 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.51 cfs 0.038 af

**5090 Post - Copy**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.60"

Printed 2/10/2021

Page 6

**Pond 17P: PDMH #17**

Peak Elev=25.68' Inflow=2.41 cfs 0.183 af  
12.0" Round Culvert n=0.013 L=84.0' S=0.0050 '/ Outflow=2.41 cfs 0.183 af

**Pond 18P: PDMH #15**

Peak Elev=24.98' Inflow=2.41 cfs 0.183 af  
12.0" Round Culvert n=0.013 L=117.0' S=0.0605 '/ Outflow=2.41 cfs 0.183 af

**Pond 19P: Raingarden #1**

Peak Elev=18.39' Storage=4,173 cf Inflow=6.34 cfs 0.688 af  
Primary=0.12 cfs 0.149 af Secondary=6.13 cfs 0.515 af Outflow=6.25 cfs 0.664 af

**Total Runoff Area = 3.472 ac Runoff Volume = 0.946 af Average Runoff Depth = 3.27"**  
**77.91% Pervious = 2.705 ac 22.09% Impervious = 0.767 ac**

**Summary for Subcatchment 10S: Roadway**

Runoff = 0.53 cfs @ 12.09 hrs, Volume= 0.040 af, Depth= 4.24"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-yr Rainfall=5.60"

Area (sf)	CN	Description
2,904	98	Paved parking, HSG C
0	98	Roofs, HSG C
1,972	74	>75% Grass cover, Good, HSG C
4,876	88	Weighted Average
1,972		40.44% Pervious Area
2,904		59.56% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 10S: Roadway**

Hydrograph



**Summary for Subcatchment 11S: Roadway**

Runoff = 0.74 cfs @ 12.09 hrs, Volume= 0.056 af, Depth= 4.35"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-yr Rainfall=5.60"

Area (sf)	CN	Description
3,359	98	Paved parking, HSG C
815	98	Roofs, HSG C
2,544	74	>75% Grass cover, Good, HSG C
6,718	89	Weighted Average
2,544		37.87% Pervious Area
4,174		62.13% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 11S: Roadway**

Hydrograph



**Summary for Subcatchment 13S: Roadway**

Runoff = 0.34 cfs @ 12.09 hrs, Volume= 0.025 af, Depth= 4.14"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-yr Rainfall=5.60"

Area (sf)	CN	Description
1,788	98	Paved parking, HSG C
0	98	Roofs, HSG C
1,395	74	>75% Grass cover, Good, HSG C
3,183	87	Weighted Average
1,395		43.83% Pervious Area
1,788		56.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 13S: Roadway**

Hydrograph



**Summary for Subcatchment 14S: Roadway**

Runoff = 0.30 cfs @ 12.09 hrs, Volume= 0.025 af, Depth= 5.36"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-yr Rainfall=5.60"

Area (sf)	CN	Description
2,407	98	Paved parking, HSG C
0	98	Roofs, HSG C
0	74	>75% Grass cover, Good, HSG C
2,407	98	Weighted Average
2,407		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 14S: Roadway**

Hydrograph



**Summary for Subcatchment 15S: 19S**

Runoff = 5.05 cfs @ 12.24 hrs, Volume= 0.505 af, Depth= 3.42"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-yr Rainfall=5.60"

Area (sf)	CN	Description
5,444	98	Paved parking, HSG C
14,000	98	Roofs, HSG C
57,676	74	>75% Grass cover, Good, HSG C
77,120	80	Weighted Average
57,676		74.79% Pervious Area
19,444		25.21% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.2	100	0.0400	0.11		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.69"
2.0	315	0.0300	2.60		<b>Shallow Concentrated Flow,</b> Grassed Waterway Kv= 15.0 fps
0.1	65	0.0600	10.80	45.37	<b>Channel Flow,</b> Area= 4.2 sf Perim= 5.0' r= 0.84' n= 0.030 Earth, grassed & winding
17.3	480	Total			

**Subcatchment 15S: 19S**

Hydrograph



**Summary for Subcatchment 16S: Cul-de-sac**

Runoff = 0.51 cfs @ 12.09 hrs, Volume= 0.038 af, Depth= 4.14"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-yr Rainfall=5.60"

Area (sf)	CN	Description
2,696	98	Paved parking, HSG C
0	98	Roofs, HSG C
2,123	74	>75% Grass cover, Good, HSG C
4,819	87	Weighted Average
2,123		44.05% Pervious Area
2,696		55.95% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 16S: Cul-de-sac**

Hydrograph



**Summary for Subcatchment 20S: Remaining Land**

Runoff = 3.22 cfs @ 12.13 hrs, Volume= 0.257 af, Depth= 2.58"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-yr Rainfall=5.60"

Area (sf)	CN	Description
40,658	70	Woods, Good, HSG C
11,457	74	>75% Grass cover, Good, HSG C
52,115	71	Weighted Average
52,115		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.2	35	0.0850	0.26		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 3.69"
5.3	50	0.1400	0.16		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.69"
1.0	90	0.0900	1.50		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
8.5	175	Total			

**Subcatchment 20S: Remaining Land**

Hydrograph




**Summary for Reach 16R: Outfall**

Inflow Area = 2.276 ac, 33.71% Impervious, Inflow Depth > 0.78" for 10-yr event  
 Inflow = 0.12 cfs @ 12.24 hrs, Volume= 0.149 af  
 Outflow = 0.12 cfs @ 12.28 hrs, Volume= 0.149 af, Atten= 0%, Lag= 2.7 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Max. Velocity= 0.80 fps, Min. Travel Time= 1.6 min  
 Avg. Velocity = 0.64 fps, Avg. Travel Time= 1.9 min


Peak Storage= 12 cf @ 12.26 hrs  
 Average Depth at Peak Storage= 0.09'  
 Bank-Full Depth= 0.50' Flow Area= 2.0 sf, Capacity= 4.89 cfs

6.00' x 0.50' deep Parabolic Channel, n= 0.100 Earth, dense brush, high stage  
 Length= 75.0' Slope= 0.1200 '/'  
 Inlet Invert= 14.00', Outlet Invert= 5.00'



**Reach 16R: Outfall**

Hydrograph



**Summary for Reach 100R: POA #1**

Inflow Area = 3.472 ac, 22.09% Impervious, Inflow Depth > 3.18" for 10-yr event  
 Inflow = 8.97 cfs @ 12.17 hrs, Volume= 0.921 af  
 Outflow = 8.97 cfs @ 12.17 hrs, Volume= 0.921 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Max. Velocity= 2.03 fps, Min. Travel Time= 0.0 min  
 Avg. Velocity = 0.61 fps, Avg. Travel Time= 0.0 min


Peak Storage= 4 cf @ 12.17 hrs  
 Average Depth at Peak Storage= 0.30'  
 Bank-Full Depth= 1.00' Flow Area= 26.7 sf, Capacity= 120.83 cfs

40.00' x 1.00' deep Parabolic Channel, n= 0.025 Earth, clean & winding  
 Length= 1.0' Slope= 0.0100 '/'  
 Inlet Invert= 1.00', Outlet Invert= 0.99'



**Reach 100R: POA #1**

Hydrograph



**Summary for Pond 10P: PCB #10**

Inflow Area = 0.112 ac, 59.56% Impervious, Inflow Depth = 4.24" for 10-yr event  
 Inflow = 0.53 cfs @ 12.09 hrs, Volume= 0.040 af  
 Outflow = 0.53 cfs @ 12.09 hrs, Volume= 0.040 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.53 cfs @ 12.09 hrs, Volume= 0.040 af


Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 26.50' @ 12.09 hrs  
 Flood Elev= 29.55'

Device	Routing	Invert	Outlet Devices
#1	Primary	26.05'	<b>12.0" Round Culvert</b> L= 8.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 26.05' / 26.01' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.51 cfs @ 12.09 hrs HW=26.49' (Free Discharge)  
 ↳ **1=Culvert** (Barrel Controls 0.51 cfs @ 2.27 fps)

**Pond 10P: PCB #10**

Hydrograph



**Summary for Pond 11P: PCB #11**

Inflow Area = 0.154 ac, 62.13% Impervious, Inflow Depth = 4.35" for 10-yr event  
 Inflow = 0.74 cfs @ 12.09 hrs, Volume= 0.056 af  
 Outflow = 0.74 cfs @ 12.09 hrs, Volume= 0.056 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.74 cfs @ 12.09 hrs, Volume= 0.056 af


Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 26.59' @ 12.09 hrs  
 Flood Elev= 29.55'

Device	Routing	Invert	Outlet Devices
#1	Primary	26.05'	<b>12.0" Round Culvert</b> L= 8.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 26.05' / 26.01' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.72 cfs @ 12.09 hrs HW=26.58' (Free Discharge)  
 ←1=Culvert (Barrel Controls 0.72 cfs @ 2.48 fps)

**Pond 11P: PCB #11**

Hydrograph



**Summary for Pond 12P: PDMH #13**

Inflow Area = 0.266 ac, 61.05% Impervious, Inflow Depth = 4.30" for 10-yr event  
 Inflow = 1.27 cfs @ 12.09 hrs, Volume= 0.095 af  
 Outflow = 1.27 cfs @ 12.09 hrs, Volume= 0.095 af, Atten= 0%, Lag= 0.0 min  
 Primary = 1.27 cfs @ 12.09 hrs, Volume= 0.095 af


Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 26.60' @ 12.09 hrs  
 Flood Elev= 29.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	25.91'	<b>12.0" Round Culvert</b> L= 155.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 25.91' / 25.14' S= 0.0050 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.24 cfs @ 12.09 hrs HW=26.59' (Free Discharge)  
 ↳1=Culvert (Barrel Controls 1.24 cfs @ 3.10 fps)

**Pond 12P: PDMH #13**

Hydrograph



**Summary for Pond 13P: PCB #12**

Inflow Area = 0.073 ac, 56.17% Impervious, Inflow Depth = 4.14" for 10-yr event  
 Inflow = 0.34 cfs @ 12.09 hrs, Volume= 0.025 af  
 Outflow = 0.34 cfs @ 12.09 hrs, Volume= 0.025 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.34 cfs @ 12.09 hrs, Volume= 0.025 af


Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 27.44' @ 12.09 hrs  
 Flood Elev= 31.10'

Device	Routing	Invert	Outlet Devices
#1	Primary	27.10'	<b>12.0" Round Culvert</b> L= 5.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 27.10' / 27.05' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.33 cfs @ 12.09 hrs HW=27.43' (Free Discharge)  
 ↑ **1=Culvert** (Barrel Controls 0.33 cfs @ 2.17 fps)

**Pond 13P: PCB #12**

Hydrograph



**Summary for Pond 14P: PCB #13**

Inflow Area = 0.055 ac, 100.00% Impervious, Inflow Depth = 5.36" for 10-yr event  
 Inflow = 0.30 cfs @ 12.09 hrs, Volume= 0.025 af  
 Outflow = 0.30 cfs @ 12.09 hrs, Volume= 0.025 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.30 cfs @ 12.09 hrs, Volume= 0.025 af


Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 27.41' @ 12.09 hrs  
 Flood Elev= 31.10'

Device	Routing	Invert	Outlet Devices
#1	Primary	27.10'	<b>12.0" Round Culvert</b> L= 5.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 27.10' / 27.05' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.29 cfs @ 12.09 hrs HW=27.41' (Free Discharge)  
 ↳ **1=Culvert** (Barrel Controls 0.29 cfs @ 2.10 fps)

**Pond 14P: PCB #13**

Hydrograph



**Summary for Pond 15P: PDMH #15**

Inflow Area = 0.394 ac, 65.60% Impervious, Inflow Depth = 4.42" for 10-yr event  
 Inflow = 1.90 cfs @ 12.09 hrs, Volume= 0.145 af  
 Outflow = 1.90 cfs @ 12.09 hrs, Volume= 0.145 af, Atten= 0%, Lag= 0.0 min  
 Primary = 1.90 cfs @ 12.09 hrs, Volume= 0.145 af


Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 25.94' @ 12.09 hrs  
 Flood Elev= 31.25'

Device	Routing	Invert	Outlet Devices
#1	Primary	25.04'	<b>12.0" Round Culvert</b> L= 67.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 25.04' / 24.70' S= 0.0051 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.86 cfs @ 12.09 hrs HW=25.93' (Free Discharge)  
 ↳ **1=Culvert** (Barrel Controls 1.86 cfs @ 3.35 fps)

**Pond 15P: PDMH #15**

Hydrograph



**Summary for Pond 16P: PCB #14**

Inflow Area = 0.111 ac, 55.95% Impervious, Inflow Depth = 4.14" for 10-yr event  
 Inflow = 0.51 cfs @ 12.09 hrs, Volume= 0.038 af  
 Outflow = 0.51 cfs @ 12.09 hrs, Volume= 0.038 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.51 cfs @ 12.09 hrs, Volume= 0.038 af


Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 26.92' @ 12.09 hrs  
 Flood Elev= 30.50'

Device #	Routing	Invert	Outlet Devices
#1	Primary	26.50'	<b>12.0" Round Culvert</b> L= 5.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 26.50' / 26.45' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.50 cfs @ 12.09 hrs HW=26.92' (Free Discharge)  
 ←1=Culvert (Barrel Controls 0.50 cfs @ 2.38 fps)

**Pond 16P: PCB #14**

Hydrograph



**Summary for Pond 17P: PDMH #17**

Inflow Area = 0.505 ac, 63.49% Impervious, Inflow Depth = 4.36" for 10-yr event  
 Inflow = 2.41 cfs @ 12.09 hrs, Volume= 0.183 af  
 Outflow = 2.41 cfs @ 12.09 hrs, Volume= 0.183 af, Atten= 0%, Lag= 0.0 min  
 Primary = 2.41 cfs @ 12.09 hrs, Volume= 0.183 af


Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 25.68' @ 12.09 hrs  
 Flood Elev= 30.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	24.60'	<b>12.0" Round Culvert</b> L= 84.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 24.60' / 24.18' S= 0.0050 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.36 cfs @ 12.09 hrs HW=25.66' (Free Discharge)  
 ←1=Culvert (Barrel Controls 2.36 cfs @ 3.53 fps)

**Pond 17P: PDMH #17**

Hydrograph



**Summary for Pond 18P: PDMH #15**

Inflow Area = 0.505 ac, 63.49% Impervious, Inflow Depth = 4.36" for 10-yr event  
 Inflow = 2.41 cfs @ 12.09 hrs, Volume= 0.183 af  
 Outflow = 2.41 cfs @ 12.09 hrs, Volume= 0.183 af, Atten= 0%, Lag= 0.0 min  
 Primary = 2.41 cfs @ 12.09 hrs, Volume= 0.183 af


Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 24.98' @ 12.09 hrs  
 Flood Elev= 30.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	24.08'	<b>12.0" Round Culvert</b> L= 117.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 24.08' / 17.00' S= 0.0605 '/ Cc= 0.900 n= 0.013, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.36 cfs @ 12.09 hrs HW=24.97' (Free Discharge)  
 ↑1=Culvert (Inlet Controls 2.36 cfs @ 3.20 fps)

**Pond 18P: PDMH #15**

Hydrograph



**Summary for Pond 19P: Raingarden #1**

Inflow Area = 2.276 ac, 33.71% Impervious, Inflow Depth = 3.63" for 10-yr event  
 Inflow = 6.34 cfs @ 12.20 hrs, Volume= 0.688 af  
 Outflow = 6.25 cfs @ 12.24 hrs, Volume= 0.664 af, Atten= 1%, Lag= 2.5 min  
 Primary = 0.12 cfs @ 12.24 hrs, Volume= 0.149 af  
 Secondary = 6.13 cfs @ 12.24 hrs, Volume= 0.515 af

Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 18.39' @ 12.24 hrs Surf.Area= 3,517 sf Storage= 4,173 cf

Plug-Flow detention time= 102.7 min calculated for 0.663 af (96% of inflow)  
 Center-of-Mass det. time= 83.6 min ( 900.5 - 816.8 )

Volume	Invert	Avail.Storage	Storage Description	
#1	14.00'	6,640 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)	
Elevation (feet)	Surf.Area (sq-ft)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
14.00	1,288	0.0	0	0
15.25	1,288	40.0	644	644
15.50	1,288	33.0	106	750
17.00	1,288	5.0	97	847
18.00	2,892	100.0	2,090	2,937
19.00	4,514	100.0	3,703	6,640

Device	Routing	Invert	Outlet Devices
#1	Primary	14.50'	<b>6.0" Round Culvert</b> L= 47.0' Ke= 0.500 Inlet / Outlet Invert= 14.50' / 14.03' S= 0.0100 '/' Cc= 0.900 n= 0.012, Flow Area= 0.20 sf
#2	Device 1	17.00'	<b>2.410 in/hr Exfiltration over Surface area above 17.00'</b> Excluded Surface area = 1,288 sf
#3	Secondary	18.00'	<b>10.0' long x 10.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64

**Primary OutFlow** Max=0.12 cfs @ 12.24 hrs HW=18.38' (Free Discharge)


↑1=Culvert (Passes 0.12 cfs of 1.43 cfs potential flow)



↑2=Exfiltration (Exfiltration Controls 0.12 cfs)

**Secondary OutFlow** Max=6.09 cfs @ 12.24 hrs HW=18.38' (Free Discharge)

↑3=Broad-Crested Rectangular Weir (Weir Controls 6.09 cfs @ 1.58 fps)

### Pond 19P: Raingarden #1





**Routing Diagram for 5090 Post - Copy**  
 Prepared by Altus Engineering, Inc., Printed 2/10/2021  
 HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

**5090 Post - Copy**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.10"

Printed 2/10/2021

Page 2

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

<b>Subcatchment 10S: Roadway</b>	Runoff Area=4,876 sf 59.56% Impervious Runoff Depth=5.69" Tc=6.0 min CN=88 Runoff=0.70 cfs 0.053 af
<b>Subcatchment 11S: Roadway</b>	Runoff Area=6,718 sf 62.13% Impervious Runoff Depth=5.81" Tc=6.0 min CN=89 Runoff=0.97 cfs 0.075 af
<b>Subcatchment 13S: Roadway</b>	Runoff Area=3,183 sf 56.17% Impervious Runoff Depth=5.58" Tc=6.0 min CN=87 Runoff=0.45 cfs 0.034 af
<b>Subcatchment 14S: Roadway</b>	Runoff Area=2,407 sf 100.00% Impervious Runoff Depth=6.86" Tc=6.0 min CN=98 Runoff=0.38 cfs 0.032 af
<b>Subcatchment 15S: 19S</b>	Runoff Area=77,120 sf 25.21% Impervious Runoff Depth=4.79" Flow Length=480' Tc=17.3 min CN=80 Runoff=7.02 cfs 0.706 af
<b>Subcatchment 16S: Cul-de-sac</b>	Runoff Area=4,819 sf 55.95% Impervious Runoff Depth=5.58" Tc=6.0 min CN=87 Runoff=0.68 cfs 0.051 af
<b>Subcatchment 20S: Remaining Land</b>	Runoff Area=52,115 sf 0.00% Impervious Runoff Depth=3.81" Flow Length=175' Tc=8.5 min CN=71 Runoff=4.83 cfs 0.380 af
<b>Reach 16R: Outfall</b>	Avg. Flow Depth=0.09' Max Vel=0.81 fps Inflow=0.13 cfs 0.158 af n=0.100 L=75.0' S=0.1200 '/' Capacity=4.89 cfs Outflow=0.13 cfs 0.158 af
<b>Reach 100R: POA #1</b>	Avg. Flow Depth=0.35' Max Vel=2.27 fps Inflow=12.73 cfs 1.306 af n=0.025 L=1.0' S=0.0100 '/' Capacity=120.83 cfs Outflow=12.73 cfs 1.306 af
<b>Pond 10P: PCB #10</b>	Peak Elev=26.57' Inflow=0.70 cfs 0.053 af 12.0" Round Culvert n=0.013 L=8.0' S=0.0050 '/' Outflow=0.70 cfs 0.053 af
<b>Pond 11P: PCB #11</b>	Peak Elev=26.68' Inflow=0.97 cfs 0.075 af 12.0" Round Culvert n=0.013 L=8.0' S=0.0050 '/' Outflow=0.97 cfs 0.075 af
<b>Pond 12P: PDMH #13</b>	Peak Elev=26.72' Inflow=1.67 cfs 0.128 af 12.0" Round Culvert n=0.013 L=155.0' S=0.0050 '/' Outflow=1.67 cfs 0.128 af
<b>Pond 13P: PCB #12</b>	Peak Elev=27.49' Inflow=0.45 cfs 0.034 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.45 cfs 0.034 af
<b>Pond 14P: PCB #13</b>	Peak Elev=27.46' Inflow=0.38 cfs 0.032 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.38 cfs 0.032 af
<b>Pond 15P: PDMH #15</b>	Peak Elev=26.15' Inflow=2.50 cfs 0.193 af 12.0" Round Culvert n=0.013 L=67.0' S=0.0051 '/' Outflow=2.50 cfs 0.193 af
<b>Pond 16P: PCB #14</b>	Peak Elev=27.00' Inflow=0.68 cfs 0.051 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.68 cfs 0.051 af

**5090 Post - Copy**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.10"

Printed 2/10/2021

Page 3

**Pond 17P: PDMH #17**

Peak Elev=26.24' Inflow=3.18 cfs 0.245 af  
12.0" Round Culvert n=0.013 L=84.0' S=0.0050 '/ Outflow=3.18 cfs 0.245 af




**Pond 18P: PDMH #15**

Peak Elev=25.28' Inflow=3.18 cfs 0.245 af  
12.0" Round Culvert n=0.013 L=117.0' S=0.0605 '/ Outflow=3.18 cfs 0.245 af

**Pond 19P: Raingarden #1**

Peak Elev=18.47' Storage=4,485 cf Inflow=8.72 cfs 0.951 af  
Primary=0.13 cfs 0.158 af Secondary=8.50 cfs 0.769 af Outflow=8.63 cfs 0.926 af

**Total Runoff Area = 3.472 ac Runoff Volume = 1.331 af Average Runoff Depth = 4.60"**  
**77.91% Pervious = 2.705 ac 22.09% Impervious = 0.767 ac**



**Routing Diagram for 5090 Post - Copy**  
 Prepared by Altus Engineering, Inc., Printed 2/10/2021  
 HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

**5090 Post - Copy**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.50"

Printed 2/10/2021

Page 4

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

<b>Subcatchment 10S: Roadway</b>	Runoff Area=4,876 sf 59.56% Impervious Runoff Depth=7.06" Tc=6.0 min CN=88 Runoff=0.85 cfs 0.066 af
<b>Subcatchment 11S: Roadway</b>	Runoff Area=6,718 sf 62.13% Impervious Runoff Depth=7.18" Tc=6.0 min CN=89 Runoff=1.19 cfs 0.092 af
<b>Subcatchment 13S: Roadway</b>	Runoff Area=3,183 sf 56.17% Impervious Runoff Depth=6.94" Tc=6.0 min CN=87 Runoff=0.55 cfs 0.042 af
<b>Subcatchment 14S: Roadway</b>	Runoff Area=2,407 sf 100.00% Impervious Runoff Depth=8.26" Tc=6.0 min CN=98 Runoff=0.45 cfs 0.038 af
<b>Subcatchment 15S: 19S</b>	Runoff Area=77,120 sf 25.21% Impervious Runoff Depth=6.10" Flow Length=480' Tc=17.3 min CN=80 Runoff=8.87 cfs 0.899 af
<b>Subcatchment 16S: Cul-de-sac</b>	Runoff Area=4,819 sf 55.95% Impervious Runoff Depth=6.94" Tc=6.0 min CN=87 Runoff=0.84 cfs 0.064 af
<b>Subcatchment 20S: Remaining Land</b>	Runoff Area=52,115 sf 0.00% Impervious Runoff Depth=5.02" Flow Length=175' Tc=8.5 min CN=71 Runoff=6.36 cfs 0.500 af
<b>Reach 16R: Outfall</b>	Avg. Flow Depth=0.10' Max Vel=0.82 fps Inflow=0.14 cfs 0.165 af n=0.100 L=75.0' S=0.1200 '/' Capacity=4.89 cfs Outflow=0.14 cfs 0.165 af
<b>Reach 100R: POA #1</b>	Avg. Flow Depth=0.40' Max Vel=2.45 fps Inflow=16.31 cfs 1.677 af n=0.025 L=1.0' S=0.0100 '/' Capacity=120.83 cfs Outflow=16.31 cfs 1.677 af
<b>Pond 10P: PCB #10</b>	Peak Elev=26.63' Inflow=0.85 cfs 0.066 af 12.0" Round Culvert n=0.013 L=8.0' S=0.0050 '/' Outflow=0.85 cfs 0.066 af
<b>Pond 11P: PCB #11</b>	Peak Elev=26.75' Inflow=1.19 cfs 0.092 af 12.0" Round Culvert n=0.013 L=8.0' S=0.0050 '/' Outflow=1.19 cfs 0.092 af
<b>Pond 12P: PDMH #13</b>	Peak Elev=26.85' Inflow=2.04 cfs 0.158 af 12.0" Round Culvert n=0.013 L=155.0' S=0.0050 '/' Outflow=2.04 cfs 0.158 af
<b>Pond 13P: PCB #12</b>	Peak Elev=27.54' Inflow=0.55 cfs 0.042 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.55 cfs 0.042 af
<b>Pond 14P: PCB #13</b>	Peak Elev=27.49' Inflow=0.45 cfs 0.038 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.45 cfs 0.038 af
<b>Pond 15P: PDMH #15</b>	Peak Elev=26.55' Inflow=3.05 cfs 0.238 af 12.0" Round Culvert n=0.013 L=67.0' S=0.0051 '/' Outflow=3.05 cfs 0.238 af
<b>Pond 16P: PCB #14</b>	Peak Elev=27.06' Inflow=0.84 cfs 0.064 af 12.0" Round Culvert n=0.013 L=5.0' S=0.0100 '/' Outflow=0.84 cfs 0.064 af

**5090 Post - Copy**

Prepared by Altus Engineering, Inc.

HydroCAD® 10.00-25 s/n 01222 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.50"

Printed 2/10/2021

Page 5

**Pond 17P: PDMH #17**

Peak Elev=26.74' Inflow=3.88 cfs 0.302 af  
12.0" Round Culvert n=0.013 L=84.0' S=0.0050 '/ Outflow=3.88 cfs 0.302 af

**Pond 18P: PDMH #15**

Peak Elev=25.63' Inflow=3.88 cfs 0.302 af  
12.0" Round Culvert n=0.013 L=117.0' S=0.0605 '/ Outflow=3.88 cfs 0.302 af

**Pond 19P: Raingarden #1**

Peak Elev=18.54' Storage=4,754 cf Inflow=10.96 cfs 1.202 af  
Primary=0.14 cfs 0.165 af Secondary=10.71 cfs 1.012 af Outflow=10.85 cfs 1.177 af

**Total Runoff Area = 3.472 ac Runoff Volume = 1.702 af Average Runoff Depth = 5.88"**  
**77.91% Pervious = 2.705 ac 22.09% Impervious = 0.767 ac**

## Section 5

# BMP and Riprap Calculations



## FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

Type/Node Name: \_\_\_\_\_

**Pond 16P - Raingarden 1**

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable

Yes		Have you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a)?	
2.28	ac	A = Area draining to the practice	
0.77	ac	A <sub>I</sub> = Impervious area draining to the practice	
0.34	decimal	I = percent impervious area draining to the practice, in decimal form	
0.35	unitless	R <sub>v</sub> = Runoff coefficient = 0.05 + (0.9 x I)	
0.81	ac-in	WQV = 1" x R <sub>v</sub> x A	
2,929	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")	
732	cf	25% x WQV (check calc for sediment forebay volume)	
2,197	cf	75% x WQV (check calc for surface sand filter volume)	
Deep Sump CB		Method of Pretreatment? (not required for clean or roof runoff)	
	cf	V <sub>SED</sub> = sediment forebay volume, if used for pretreatment	← ≥ 25%WQV
1,288	sf	A <sub>SA</sub> = surface area of the practice	
-	iph	K <sub>sat</sub> DESIGN = design infiltration rate <sup>1</sup>	
Yes	Yes/No	If K <sub>sat</sub> (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?	
-	hours	T <sub>DRAIN</sub> = drain time = V / (A <sub>SA</sub> * I <sub>DESIGN</sub> )	← ≤ 72-hrs
15.50	feet	E <sub>FC</sub> = elevation of the bottom of the filter course material <sup>2</sup>	
14.50	feet	E <sub>UD</sub> = invert elevation of the underdrain (UD), if applicable	
12.00	feet	E <sub>SHWT</sub> = elevation of SHWT (if none found, enter the lowest elevation of the test pit)	
12.00	feet	E <sub>ROCK</sub> = elevation of bedrock (if none found, enter the lowest elevation of the test pit)	
1.00	feet	D <sub>FC to UD</sub> = depth to UD from the bottom of the filter course	← ≥ 1'
3.50	feet	D <sub>FC to ROCK</sub> = depth to bedrock from the bottom of the filter course	← ≥ 1'
3.50	feet	D <sub>FC to SHWT</sub> = depth to SHWT from the bottom of the filter course	← ≥ 1'
18.54	ft	Peak elevation of the 50-year storm event (infiltration can be used in analysis)	
19.00	ft	Elevation of the top of the practice	
YES		50 peak elevation ≤ Elevation of the top of the practice	← yes

**If a surface sand filter or underground sand filter is proposed:**

YES	ac	Drainage Area check.	← < 10 ac
	cf	V = volume of storage <sup>3</sup> (attach a stage-storage table)	← ≥ 75%WQV
	inches	D <sub>FC</sub> = filter course thickness	← 18", or 24" if within GPA
Sheet	_____	Note what sheet in the plan set contains the filter course specification	
Yes/No		Access grate provided?	← yes



## RIPRAP CALCULATIONS

**Location: PDMH #15 - 12" Culvert (HydroCAD Pond #15P)**

Date: 12/31/2020 By: EBS

La	Apron Length, Ft.	Calculated
Tw	Tailwater, Ft.	1.4
Q	Flow, 10 Yr Storm, CFS	2.41
D50	Median Stone Dia., Ft.	Calculated
D	Depth of Stone, In	Calculated
Do	Pipe Diameter, Ft	1.00
W1	Width @ Start, Ft.	Calculated
W2	Width @ End, Ft	Calculated
W	Width of Channel	5

W1: 3(Do)= 3 Ft.

**Width @ Start: 3 Ft.**

D50:  $0.02(Q)^{4/3}$  D50= 0.05 Ft.  
Tw(Do) or 0.6 In.

**Median Stone Size: 6 In.**

D: 2.25\*D50 **Depth of Riprap: 14 In.**

La: If Tw ≤ Do/2: Do/2= 0.5 Ft.  
Tw= 1.38 Ft.

and  $La = 1.8Q/Do^{3/2} + 7Do$   
W2=width of channel  
or  
W2=3Do+La

If Tw > Do/2:  
and  $La = 3Q/Do^{3/2} + 7Do$   
W2=width of channel  
or  
W2=3Do+0.4La

**Length of Apron: 15 Ft.**

**Width @ End: 5 Ft.**



## Section 6

# NRCC Extreme Precipitation Table

## Extreme Precipitation Tables

### Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

<b>Smoothing</b>	Yes
<b>State</b>	New Hampshire
<b>Location</b>	
<b>Longitude</b>	70.763 degrees West
<b>Latitude</b>	43.072 degrees North
<b>Elevation</b>	0 feet
<b>Date/Time</b>	Wed, 23 Dec 2020 12:00:25 -0500

### Extreme Precipitation Estimates

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	Add 15%	1day	2day	4day	7day	10day		
<b>1yr</b>	0.26	0.40	0.50	0.65	0.81	1.04	<b>1yr</b>	0.70	0.98	1.21	1.56	2.03	2.66	3.06	2.35	2.81	3.22	3.94	4.55	<b>1yr</b>	
<b>2yr</b>	0.32	0.50	0.62	0.81	1.02	1.30	<b>2yr</b>	0.88	1.18	1.52	1.94	2.49	3.21	3.69	2.84	3.43	3.94	4.68	5.33	<b>2yr</b>	
<b>5yr</b>	0.37	0.58	0.73	0.98	1.25	1.61	<b>5yr</b>	1.08	1.47	1.89	2.43	3.14	4.07	4.68	3.60	4.40	5.04	5.94	6.70	<b>5yr</b>	
<b>10yr</b>	0.41	0.65	0.82	1.12	1.45	1.89	<b>10yr</b>	1.25	1.73	2.23	2.89	3.75	4.87	5.60	4.31	5.32	6.09	7.11	7.98	<b>10yr</b>	
<b>25yr</b>	0.48	0.76	0.97	1.34	1.77	2.34	<b>25yr</b>	1.53	2.14	2.78	3.63	4.74	6.17	7.10	5.46	6.83	7.80	9.03	10.05	<b>25yr</b>	
<b>50yr</b>	0.54	0.86	1.10	1.54	2.07	2.76	<b>50yr</b>	1.79	2.53	3.29	4.32	5.66	7.39	8.50	6.54	8.25	9.42	10.81	11.98	<b>50yr</b>	
<b>100yr</b>	0.60	0.97	1.25	1.77	2.42	3.26	<b>100yr</b>	2.09	2.98	3.90	5.16	6.77	8.85	10.18	7.83	9.98	11.38	12.96	14.27	<b>100yr</b>	
<b>200yr</b>	0.67	1.10	1.43	2.05	2.82	3.83	<b>200yr</b>	2.44	3.52	4.62	6.13	8.08	10.61	12.55	<b>200yr</b>	9.39	12.07	13.76	15.55	17.02	<b>200yr</b>
<b>500yr</b>	0.80	1.31	1.71	2.48	3.48	4.76	<b>500yr</b>	3.00	4.38	5.76	7.70	10.22	13.48	16.14	<b>500yr</b>	11.93	15.52	17.67	19.78	21.49	<b>500yr</b>

### Lower Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
<b>1yr</b>	0.23	0.36	0.44	0.59	0.72	0.88	<b>1yr</b>	0.63	0.86	0.92	1.33	1.68	2.24	2.49	<b>1yr</b>	1.98	2.40	2.87	3.18	3.90	<b>1yr</b>
<b>2yr</b>	0.31	0.49	0.60	0.81	1.00	1.19	<b>2yr</b>	0.86	1.16	1.37	1.82	2.34	3.06	3.45	<b>2yr</b>	2.71	3.32	3.82	4.55	5.08	<b>2yr</b>
<b>5yr</b>	0.35	0.54	0.67	0.92	1.17	1.40	<b>5yr</b>	1.01	1.37	1.61	2.12	2.73	3.79	4.19	<b>5yr</b>	3.35	4.03	4.72	5.53	6.24	<b>5yr</b>
<b>10yr</b>	0.39	0.59	0.73	1.03	1.33	1.60	<b>10yr</b>	1.14	1.56	1.80	2.39	3.06	4.37	4.86	<b>10yr</b>	3.87	4.67	5.44	6.41	7.20	<b>10yr</b>
<b>25yr</b>	0.44	0.67	0.83	1.19	1.56	1.90	<b>25yr</b>	1.35	1.86	2.10	2.75	3.53	4.72	5.89	<b>25yr</b>	4.18	5.66	6.65	7.79	8.68	<b>25yr</b>
<b>50yr</b>	0.48	0.73	0.91	1.31	1.76	2.17	<b>50yr</b>	1.52	2.12	2.35	3.07	3.93	5.33	6.80	<b>50yr</b>	4.72	6.54	7.72	9.04	10.02	<b>50yr</b>
<b>100yr</b>	0.54	0.81	1.01	1.47	2.01	2.47	<b>100yr</b>	1.73	2.41	2.63	3.41	4.35	6.00	7.85	<b>100yr</b>	5.31	7.55	8.98	10.51	11.56	<b>100yr</b>
<b>200yr</b>	0.59	0.89	1.13	1.63	2.28	2.81	<b>200yr</b>	1.96	2.75	2.93	3.78	4.79	6.72	9.06	<b>200yr</b>	5.95	8.71	10.42	12.22	13.37	<b>200yr</b>
<b>500yr</b>	0.68	1.02	1.31	1.90	2.71	3.36	<b>500yr</b>	2.34	3.29	3.41	4.31	5.45	7.82	10.94	<b>500yr</b>	6.92	10.52	12.69	14.96	16.19	<b>500yr</b>

### Upper Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
<b>1yr</b>	0.28	0.44	0.54	0.72	0.89	1.08	<b>1yr</b>	0.77	1.06	1.26	1.74	2.21	2.98	3.16	<b>1yr</b>	2.64	3.04	3.58	4.37	5.04	<b>1yr</b>
<b>2yr</b>	0.34	0.52	0.64	0.86	1.07	1.27	<b>2yr</b>	0.92	1.24	1.48	1.96	2.51	3.42	3.70	<b>2yr</b>	3.03	3.56	4.09	4.84	5.63	<b>2yr</b>
<b>5yr</b>	0.40	0.62	0.77	1.05	1.34	1.62	<b>5yr</b>	1.15	1.58	1.88	2.53	3.25	4.34	4.96	<b>5yr</b>	3.84	4.77	5.38	6.37	7.16	<b>5yr</b>
<b>10yr</b>	0.47	0.72	0.89	1.25	1.61	1.98	<b>10yr</b>	1.39	1.93	2.28	3.11	3.95	5.34	6.20	<b>10yr</b>	4.72	5.96	6.82	7.84	8.75	<b>10yr</b>
<b>25yr</b>	0.58	0.88	1.09	1.56	2.05	2.57	<b>25yr</b>	1.77	2.51	2.95	4.07	5.15	7.78	8.34	<b>25yr</b>	6.88	8.02	9.15	10.34	11.41	<b>25yr</b>
<b>50yr</b>	0.67	1.02	1.27	1.83	2.46	3.13	<b>50yr</b>	2.12	3.06	3.60	5.00	6.32	9.74	10.46	<b>50yr</b>	8.62	10.06	11.44	12.72	13.96	<b>50yr</b>
<b>100yr</b>	0.79	1.19	1.49	2.16	2.96	3.81	<b>100yr</b>	2.55	3.72	4.37	6.16	7.76	12.18	13.10	<b>100yr</b>	10.78	12.60	14.31	15.69	17.09	<b>100yr</b>
<b>200yr</b>	0.92	1.39	1.76	2.55	3.56	4.65	<b>200yr</b>	3.07	4.55	5.34	7.58	9.54	15.28	16.44	<b>200yr</b>	13.53	15.81	17.92	19.35	20.92	<b>200yr</b>
<b>500yr</b>	1.15	1.71	2.19	3.19	4.53	6.04	<b>500yr</b>	3.91	5.90	6.93	10.02	12.56	20.65	22.20	<b>500yr</b>	18.27	21.34	24.13	25.51	27.34	<b>500yr</b>



# Section 7

## NRCS Soils Report



United States  
Department of  
Agriculture

**NRCS**

Natural  
Resources  
Conservation  
Service

A product of the National  
Cooperative Soil Survey,  
a joint effort of the United  
States Department of  
Agriculture and other  
Federal agencies, State  
agencies including the  
Agricultural Experiment  
Stations, and local  
participants

# Custom Soil Resource Report for Rockingham County, New Hampshire

## PROPOSED SUBDIVISION



# Preface

---

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist ([http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2\\_053951](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951)).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

# Contents

---

<b>Preface</b> .....	2
<b>How Soil Surveys Are Made</b> .....	5
<b>Soil Map</b> .....	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
Rockingham County, New Hampshire.....	13
799—Urban land-Canton complex, 3 to 15 percent slopes.....	13
W—Water.....	14
<b>References</b> .....	15

# How Soil Surveys Are Made

---

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

## Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

## Custom Soil Resource Report


identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

# Soil Map

---

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Soil Map—Rockingham County, New Hampshire



Map Scale: 1:2,160 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 19N WGS84



Natural Resources  
Conservation Service

Web Soil Survey  
National Cooperative Soil Survey

## MAP LEGEND

- Area of Interest (AOI)
- Soil Map Unit Polygons
- Soil Map Unit Lines
- Soil Map Unit Points
- Special Point Features**
  - Blowout
  - Borrow Pit
  - Clay Spot
  - Closed Depression
  - Gravel Pit
  - Gravelly Spot
  - Landfill
  - Lava Flow
  - Marsh or swamp
  - Mine or Quarry
  - Miscellaneous Water
  - Perennial Water
  - Rock Outcrop
  - Saline Spot
  - Sandy Spot
  - Severely Eroded Spot
  - Sinkhole
  - Slide or Slip
  - Sodic Spot
- Water Features**
  - Streams and Canals
- Transportation**
  - Rails
  - Interstate Highways
  - US Routes
  - Major Roads
  - Local Roads
- Background**
  - Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Rockingham County, New Hampshire  
 Survey Area Data: Version 22, May 29, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Dec 31, 2009—Sep 9, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
799	Urban land-Canton complex, 3 to 15 percent slopes	5.2	91.2%
W	Water	0.5	8.8%
<b>Totals for Area of Interest</b>		<b>5.7</b>	<b>100.0%</b>

## Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however,

## Custom Soil Resource Report

onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

## Rockingham County, New Hampshire

### 799—Urban land-Canton complex, 3 to 15 percent slopes

#### Map Unit Setting

*National map unit symbol:* 9cq0  
*Elevation:* 0 to 1,000 feet  
*Mean annual precipitation:* 42 to 46 inches  
*Mean annual air temperature:* 45 to 48 degrees F  
*Frost-free period:* 120 to 160 days  
*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Urban land:* 55 percent  
*Canton and similar soils:* 20 percent  
*Minor components:* 25 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Canton

##### Setting

*Parent material:* Till

##### Typical profile

*H1 - 0 to 5 inches:* gravelly fine sandy loam  
*H2 - 5 to 21 inches:* gravelly fine sandy loam  
*H3 - 21 to 60 inches:* loamy sand

##### Properties and qualities

*Slope:* 3 to 8 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Well drained  
*Runoff class:* Low  
*Capacity of the most limiting layer to transmit water (Ksat):* High (2.00 to 6.00 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Available water capacity:* Low (about 5.3 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 2e  
*Hydrologic Soil Group:* A  
*Ecological site:* F144AY034CT - Well Drained Till Uplands  
*Hydric soil rating:* No

#### Minor Components

##### Udorthents

*Percent of map unit:* 5 percent  
*Hydric soil rating:* No

##### Squamscott and scitico

*Percent of map unit:* 4 percent  
*Landform:* Marine terraces

## Custom Soil Resource Report

*Hydric soil rating: Yes*

### **Boxford and eldridge**

*Percent of map unit: 4 percent*

*Hydric soil rating: No*

### **Chatfield**

*Percent of map unit: 4 percent*

*Hydric soil rating: No*

### **Scituate and newfields**

*Percent of map unit: 4 percent*

*Hydric soil rating: No*

### **Walpole**

*Percent of map unit: 4 percent*

*Landform: Depressions*

*Hydric soil rating: Yes*

## **W—Water**

### **Map Unit Setting**

*National map unit symbol: 9cq3*

*Elevation: 200 to 2,610 feet*

*Farmland classification: Not prime farmland*

### **Map Unit Composition**

*Water: 100 percent*

*Estimates are based on observations, descriptions, and transects of the mapunit.*

# References

---

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_054262](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262)
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053577](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577)
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053580](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580)
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2\\_053374](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374)
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

## Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\\_054242](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242)

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053624](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624)

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. [http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_052290.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf)

## Section 8

# Stormwater Operations & Maintenance Plan

# STORMWATER INSPECTION AND MAINTENANCE MANUAL

## Watson's Landing Assessor's Map 209, Lot 33

**OWNER AT TIME OF SUBDIVISION APPROVAL:**  
**Frederick W. Watson Revocable Trust**  
**Robert D. Watson, Trustee**  
**53 Sleepy Hollow Drive**  
**Greenland, NH 03840**

Proper inspection, maintenance, and repair are key elements in maintaining a successful stormwater management program on a developed property. Routine inspections ensure permit compliance and reduce the potential for deterioration of infrastructure or reduced water quality. The following responsible parties shall be in charge of managing the stormwater facilities:

### **RESPONSIBLE PARTIES:**

**Owner:** Frederick D. Watson Revocable Trust or Assigns (603) 501-0966  
Name Company Phone

**Inspection:** Frederick D. Watson Revocable Trust or Assigns (603) 501-0966  
Name Company Phone

**Maintenance:** Frederick D. Watson Revocable Trust or Assigns (603) 501-0966  
Name Company Phone

**NOTE: Inspection and maintenance responsibilities shall transfer to any future property owner(s) and any related homeowner's association(s). This form shall be updated as needed to reflect these changes.**

## **RAINGARDENS**

---

*Function* – Raingardens and infiltration ponds provide treatment to runoff prior to directing it to stormwater systems by filtering sediment and suspended solids, trapping them in the bottom of the garden and in the filter media itself. Additional treatment is provided by the native water-tolerant vegetation which removes nutrients and other pollutants through bio-uptake. Stormwater detention and infiltration can also be provided as the filtering process slows runoff, decreases the peak rate of discharge and promotes groundwater recharge.

Detention ponds temporarily store runoff and allow for its controlled release during and after a storm event, decreasing peak rates of runoff and minimizing flooding.

Raingardens shall be managed (Per AGR 3800 and RSA 430:53) to: prevent and control the spread of invasive plant, insect, and fungal species; minimize the adverse environmental and economic effects invasive species cause to agriculture, forests, wetlands, wildlife, and other natural resources of the state; and protect the public from potential health problems attributed to certain invasive species.

### *Maintenance*

- Inspect annually and after significant rainfall event.
- If a raingarden does not completely drain within 72-hours following a rainfall event, then a qualified professional should assess the condition of the facility to determine measures required to restore its filtration and/or infiltration function(s), including but not limited to removal of accumulated sediments and/or replacement or reconstruction of the filter media.
- Replace any riprap dislodged from spillways, inlets and outlets.
- Remove any obstructions, litter and accumulated sediment or debris as warranted but no less than once a year.
- Mowing of any grassed area in or adjacent to a raingarden shall be performed at least twice per year (when areas are not inundated) to keep the vegetation in vigorous condition. The cut grass shall be removed to prevent the decaying organic litter from clogging the filter media or choking other vegetation.
- Select vegetation should be maintained in healthy condition. This may include pruning, removal and replacement of dead or diseased vegetation.
- Remove any invasive species, Per AGR 3800 and RSA 430:53.
- Remove any hard wood growth from raingardens.

## **CULVERTS AND DRAINAGE PIPES**

---

*Function* – Culverts and drainage pipes convey stormwater away from buildings, walkways, and parking areas and to surface waters or closed drainage systems.

### *Maintenance*

- Culverts and drainage pipes shall be inspected semi-annually, or more often as needed, for accumulation of debris and structural integrity. Leaves and other debris shall be removed from the inlet and outlet to insure the functionality of drainage structures. Debris shall be disposed of on site where it will not concentrate back at the drainage structures or at a solid waste disposal facility.
- Riprap Areas - Culvert outlets and inlets shall be inspected during annual maintenance and operations for erosion and scour. If scour or creek erosion is identified, the outlet owner shall take appropriate means to prevent further erosion. Increased lengths of riprap may require a NHDES Permit and/or local permit.

## **CATCH BASINS**

---

*Function* – Catch basins collect stormwater, primarily from paved surfaces and roofs. Stormwater from paved areas often contains sediment and contaminants. Catch basin sumps serve to trap sediment, trace metals, nutrients and debris. Hooded catch basins trap hydrocarbons and floating debris.

### *Maintenance*

- Remove leaves and debris from structure grates on an as-needed basis.
- Sumps shall be inspected and cleaned (as needed) on an annual basis to protect water quality and infiltration capacity. Catch basin debris shall be disposed of at a solid waste disposal facility.

## **LEVEL SPREADERS AND RIP RAP OUTLETS**

---

*Function* – Level spreaders and rip rap outlets covert concentrated stormwater flows into less-erosive sheet flow, minimizing erosion and maximizing the treatment capabilities of associated buffers. Vegetated buffers, either forested or meadow, slow runoff which promotes and reduces peak rates of runoff. The reduced velocities and the presence of vegetation encourage the filtration of sediment and the limited bio-uptake of nutrients.

### *Maintenance*

- Inspect level spreaders and buffers at least annually for signs of erosion, sediment buildup, or vegetation loss.
- Inspect level for signs of condensed flows. Level spreader and rip rap shall be maintained to disperse flows evenly over level spreader.
- If a meadow buffer, provide periodic mowing as needed to maintain a healthy stand of herbaceous vegetation.
- If a forested buffer, then the buffer should be maintained in an undisturbed condition, unless erosion occurs.
- If erosion of the buffer (forested or meadow) occurs, eroded areas should be repaired and replanted with vegetation similar to the remaining buffer. Corrective action should include eliminating the source of the erosion problem and may require retrofit or reconstruction of the level spreader.
- Remove debris and accumulated sediment and dispose of properly.

## **VEGETATIVE SWALES**

---

*Function* – Vegetative swales filter sediment from stormwater, promote infiltration, and the uptake of contaminants. They are designed to treat runoff and dispose of it safely into the natural drainage system.

### *Maintenance*

- Timely maintenance is important to keep a swale in good working condition. Mowing of grassed swales shall be monthly to keep the vegetation in vigorous condition. The cut vegetation shall be removed to prevent the decaying organic litter from adding pollutants to the discharge from the swale.
- Fertilizing shall be bi-annual or as recommended from soil testing.
- Inspect swales following significant rainfall events.
- Woody vegetation shall not be allowed to become established in the swales or rock riprap outlet protection and if present shall be removed.

- Accumulated debris disrupts flow and leads to clogging and erosion. Remove debris and litter as necessary.
- Inspect for eroded areas. Determine cause of erosion and correct deficiency as required. Monitor repaired areas.

### **LANDSCAPED AREAS - FERTILIZER MANAGEMENT**

---

*Function* – Fertilizer management involves controlling the rate, timing and method of fertilizer application so that the nutrients are taken up by the plants thereby reducing the chance of polluting the surface and ground waters. Fertilizer management can be effective in reducing the amounts of phosphorus and nitrogen in runoff from landscaped areas, particularly lawns.

#### *Maintenance*

- Have the soil tested by your landscaper or local Soil Conservation Service for nutrient requirements and follow the recommendations.
- Do not apply fertilizer to frozen ground.
- Clean up any fertilizer spills.
- Do not allow fertilizer to be broadcast into water bodies.
- When fertilizing a lawn, water thoroughly, but do not create a situation where water runs off the surface of the lawn.

### **LANDSCAPED AREAS - LITTER CONTROL**

---

*Function* – Landscaped areas tend to filter debris and contaminates that may block drainage systems and pollute the surface and ground waters.

#### *Maintenance*

- Litter Control and lawn maintenance involves removing litter such as trash, leaves, lawn clippings, pet wastes, oil and chemicals from streets, parking lots, and lawns before materials are transported into surface waters.
- Litter control shall be implemented as part of the grounds maintenance program.

### **DE-ICING CHEMICAL USE AND STORAGE**

---

*Function* – Sand and salt are used for de-icing of drives.

#### *Maintenance*

- Salt is highly water-soluble. Contamination of fresh water wetlands and other sensitive areas can occur when salt is stored in open areas. Salt piles shall be covered at all times if not stored in a shed. Runoff from stockpiles shall be contained to keep the runoff from entering the drainage system.
- When shared driveways and walks are free of snow and ice, they should be swept clean. Disposal shall be in a solid waste disposal facility.
- **Salt use shall be minimized.** Sand shall be used for de-icing activities when possible. Salt is highly water-soluble. Contamination of fresh water wetlands and other sensitive areas can occur when salt is stored in open areas. Owner shall not store salt piles on site.

## **CONTROL OF INVASIVE PLANTS**

---

*Function* – Invasive plants are introduced, alien, or non-native plants, which have been moved by people from their native habitat to a new area. Some exotic plants are imported for human use such as landscaping, erosion control, or food crops. They also can arrive as "hitchhikers" among shipments of other plants, seeds, packing materials, or fresh produce. Some exotic plants become invasive and cause harm by:

- becoming weedy and overgrown;
- killing established shade trees;
- obstructing pipes and drainage systems;
- forming dense beds in water;
- lowering water levels in lakes, streams, and wetlands;
- destroying natural communities;
- promoting erosion on stream banks and hillsides; and
- resisting control except by hazardous chemical.

### *Maintenance*

During maintenance activities, check for the presence of invasive plants and remove in a safe manner as described in the attached "Methods for Disposing Non-Native Invasive Plants" prepared by the UNH Cooperative Extension.

## **GENERAL CLEAN UP**

---

Upon completion of the project, the contractor shall remove all temporary stormwater structures (i.e., temporary stone check dams, silt fence, temporary diversion swales, catch basin inlet basket, etc.). Any sediment deposits remaining in place after the silt fence or filter barrier is no longer required shall be dressed to conform to the existing grade, prepared, and seeded. Remove any sediment in catch basins and clean drain pipes that may have accumulated during construction.

Once in operation, all paved areas of the site should be swept at least once annually, preferably at the end of winter prior to significant spring rains.

## **APPENDIX**

---

- A. Stormwater System Operations and Maintenance Report
- B. Site Grading and Drainage Plan

## STORM WATER SYSTEM OPERATION AND MAINTENANCE REPORT

General Information		
<b>Project Name</b>		
<b>Owner</b>		
<b>Inspector's Name(s)</b>		
<b>Inspector's Contact Information</b>		
<b>Date of Inspection</b>	<b>Start Time:</b>	<b>End Time:</b>
<b>Type of Inspection:</b> <input type="checkbox"/> Annual Report <input type="checkbox"/> Post-storm event <input type="checkbox"/> Due to a discharge of significant amounts of sediment		
<b>Notes:</b>		

General Site Questions and Discharges of Significant Amounts of Sediment			
Subject	Status	Notes	
<i>A discharge of significant amounts of sediment may be indicated by (but is not limited to) observations of the following. Note whether any are observed during this inspection:</i>			
<i>Notes/ Action taken:</i>			
1	Do the current site conditions reflect the attached site plan?	<input type="checkbox"/> Yes <input type="checkbox"/> No	
2	Is the site permanently stabilized, temporary erosion and sediment controls are removed, and stormwater discharges from construction activity are eliminated?	<input type="checkbox"/> Yes <input type="checkbox"/> No	
3	Is there evidence of the discharge of significant amounts of sediment to surface waters, or conveyance systems leading to surface waters?	<input type="checkbox"/> Yes <input type="checkbox"/> No	

Permit Coverage and Plans				
#	BMP/Facility	Inspected	Corrective Action Needed and Notes	Date Corrected
	Rain Garden	<input type="checkbox"/> Yes <input type="checkbox"/> No		
	Catch Basin	<input type="checkbox"/> Yes <input type="checkbox"/> No		
	Drainage Pipes	<input type="checkbox"/> Yes <input type="checkbox"/> No		
	Riprap Aprons	<input type="checkbox"/> Yes <input type="checkbox"/> No		
		<input type="checkbox"/> Yes <input type="checkbox"/> No		
		<input type="checkbox"/> Yes <input type="checkbox"/> No		



# Section 9

## Watershed Plans

Pre-Development Drainage Area Plan

Post-Development Drainage Area Plan

NOT FOR CONSTRUCTION

ISSUED FOR: **TAC**

ISSUE DATE: **JANUARY 18, 2021**

REVISIONS	NO.	DESCRIPTION	BY	DATE
0	TAC		EBS	01/18/21

DRAWN BY: \_\_\_\_\_ EBS  
APPROVED BY: \_\_\_\_\_ EDW  
DRAWING FILE: \_\_\_\_\_ 5090-SITE.dwg

SCALE:  
22" x 34" 1" = 30'  
11" x 17" 1" = 60'


OWNER:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
  
**63 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840**

APPLICANT:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
  
**63 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840**


PROJECT:  
**WATSON'S LANDING  
TAX MAP 209, LOT 33  
1 CLARK DRIVE  
PORTSMOUTH, NH 03801**

TITLE:  
**PRE-DEVELOPMENT  
WATERSHED PLAN**

SHEET NUMBER:  
**WS-1**



- LEGEND**
- — — — — PROPERTY LINE
  - · - · - · - WETLAND BOUNDARY
  - - - - - 60 - - - - - EXISTING CONTOUR
  - - - - - 60 - - - - - PROPOSED CONTOUR
  - - - - - WATERSHED BOUNDARY
  - - - - - Tc PATH
  - 1 1 1 SUBCATCHMENT/POND/REACH
  - POA POINT OF ANALYSIS



NOT FOR CONSTRUCTION

ISSUED FOR: TAC

ISSUE DATE: JANUARY 18, 2021

REVISIONS	NO.	DESCRIPTION	BY	DATE
0	TAC		EBS	01/18/21

DRAWN BY: EBS  
APPROVED BY: EDW  
DRAWING FILE: 5090-SITE.dwg

SCALE:  
22" x 34" 1" = 30'  
11" x 17" 1" = 60'


OWNER:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
  
63 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

APPLICANT:  
**FREDERICK W. WATSON  
REVOCABLE TRUST,  
ROBERT D. WATSON,  
TRUSTEE**  
  
63 SLEEPY HOLLOW DRIVE  
GREENLAND, NH 03840

PROJECT:  
**WATSON'S LANDING  
TAX MAP 209, LOT 33  
1 CLARK DRIVE  
PORTSMOUTH, NH 03801**

TITLE:  
POST-DEVELOPMENT  
WATERSHED PLAN

SHEET NUMBER:  
**WS-2**



- LEGEND**
- PROPERTY LINE
  - WETLAND BOUNDARY
  - EXISTING CONTOUR
  - PROPOSED CONTOUR
  - WATERSHED BOUNDARY
  - Tc PATH
  - REACH
  - SUBCATCHMENT/POND/REACH
  - POINT OF ANALYSIS

