

P-0766-006 December 9, 2021

Mr. Dexter Legg, Chair City of Portsmouth Planning Board 1 Junkins Avenue Portsmouth, New Hampshire 03801

Re: Wetland Conditional Use Permit Application

North Mill Pond Greenway Vaughan Street Portsmouth, New Hampshire

Dear Mr. Legg,

On behalf of The City of Portsmouth, we are pleased to submit the following information to support this request for a Wetland Conditional Use Permit for the above referenced project:

- One (1) full size of the Site Plan Set, last revised December 3, 2021.
- One copy of the Restoration and Buffer Impact Exhibit, last revised December 3, 2021.
- One (1) Copy of the Invasive Species Inventory Figure, dated November 5, 2018.
- One (1) copy of the Owner's Letter of Authorization.

Project Summary

The proposed project involves mitigating an existing neglected urban shoreline parcel with a public multi-use path and boardwalk. As a valuable open space and wildlife habitat, the proposed greenway is envisioned to create an ecologically healthy, socially vibrant and educational destination for residents and visitors alike. The approximately 1.1-acre parcel is located along Vaughan Street and is identified on the City of Portsmouth Tax Map 123 as Lot 15. Invasive plant species have occupied the area over a long period of neglect and abandonment. The site presents an opportunity to holistically restore the shoreline and adjacent upland areas. The proposed restoration will include invasive species control, adjacent upland native plantings, community engagement, and living shoreline restoration.

The Jurisdictional wetland boundaries were delineated by Marc Jacobs, Certified Wetlands Scientist, Number 090, in December of 2015 according to the Standard of The US Army Corps of Engineers – Wetland Delineation Manual, Technical Report T-87-1, January 1987; The Regional Supplement to the Corps of Engineers Wetland Delineation Manual; Northcentral and Northeast Region, Version 2.0, January 2012; NH RSA 482-A; The Code of Administrative Rules, NH Department of Environmental Services – Wetlands Bureau – Chapter Env-Wt 100-900; as well as the City of Portsmouth Zoning – Article 10, Section 10.1010, Wetlands Conservation District. Predominant Hydric Soils were identified utilizing the Field Indicators for Identifying Hydric Soils in New England, Version 3, April 2004 and The Field Indicators of Hydric Soils in the United States, Version 7. The indicator status of Hydrophytic Vegetation was determined according to the National List of Plant Species that Occur in Wetlands; Northeast Region, U.S. Fish and Wildlife Service.

Proposed permanent impacts associated with this project include the upland buffer restoration area, the reclaimed salt marsh area, the subtidal oyster bed, a porous pavement multi-use trail and a boardwalk. By nature of the restoration project type, the entirety of the parcel is



identified as permanent impacts and are summarized in the table below. These impacts are depicted on the Restoration and Buffer Impact Exhibit, enclosed herein.

Project Buffer Impact and Marsh Restoration Comparison				
Wetland and Buffer	Proposed	Proposed Impacts		
Setback Area	Restoration	Boardwalk	Porous Pave	
Mudflat	3,922 SF	0 SF	0 SF	
Jurisdictional Wetland	30,948 SF	206 SF	0 SF	
0 - 100 FT*	22,794 SF	126 SF	5,420 SF	
Sub Totals	57,664 SF	332 SF	5,420 SF	
Totals 57,664 SF 5,752 SF				
*Tidal Buffer Zone per RSA 482-A:4				

Living Shoreline

As the science and art of coastal zone protection and restoration advances in the wake of climate change and sea level rise, the accumulated tools that develop will make up a set of resilient strategies to assist communities during these changing times. Based on the current literature, constructed living shorelines should be included in this set of tools. Coastal shorelines are increasingly susceptible to storm damage and flooding from rising seas. Coastal New Hampshire is an area that has become dramatically impacted by these changing conditions. Specifically, the infilling of tidal rivers with sediment from eroded marsh habitats, loss of shellfish habitat, and the loss of associated ecological services such as diminished flood storage and storm damage prevention. Furthermore, the loss of portions of these resources have resulted in significant impairment of local estuaries and the loss of ecological services provided by these unique ecosystems. Utilizing green technology such as living shorelines in concert with thin layer deposition, eel grass beds, oyster and blue mussel beds, among other strategies, could serve to reduce the impacts of the adverse impacts of climate change and sea level rise.

The existing coastal bank at the project site presents various stages of erosion and impairment of the seaward mudflat. The existing bulkhead is damaged and in various states of decay. The intent of the project is to create a living shoreline and create approximately 4000 square feet of low marsh dominated bv Salt Marsh Cordgrass (Spartina alterniflora) plantings. Additionally, a coastal bluff planting area is proposed landward of the river-walk which will not only provide a visual barrier to the developed spaces of the site but also provide wildlife habitat benefits in the form of food, shelter, and overwintering habitat for wildlife.



1. View of eroded shoreline that is part of the North Mill Pond shoreline restoration project.

The project has elected to install a living shoreline in an effort to stabilize the existing eroding shoreline at the site. The options of more "gray" infrastructure in this area was rejected given that we do not expect severe scour or storm damage directly on the shoreline given its location within the riparian system associated with North Mill Pond. The benefits of a green infrastructure solution would provide additional ecological services and assist with ameliorating impacts from sea level rise and climate change.

The lower sill will be created by using salvaged rock and granite as well as living rock from the site to create a rocky intertidal shoreline. This structural shoreline will mimic the rocky coast of New Hampshire and Maine and create tide pool habitats for a multitude of vertebrate and invertebrate species including blue mussels, oysters, and nursery habitat for fisheries. The landward side of the rocky intertidal shoreline will be infilled with a blended soil of 2 parts sand and 1 part organic compost to create a growing media for the lower marsh consisting of salt marsh cordgrass Spartina alterniflora.

By using dense coir logs at the toe of the upper sill, a blended soil consisting of sand and organic compost can be utilized to stabilized on the landward side of the coil logs to support the growth of salt meadow grass (Spartina patens).

Additional plantings located on the up-gradient side of the shoreline, including seaside goldenrod, marsh elder and sea lavender will add additional ecological services



View of coir log installation on Neponset River held fast with Duck Bill Anchors. Photo taken after two growing seasons. Spartina alterniflora well established.

to the shoreline system including flowering plants for pollinators and additional root structure for stability of the shoreline. Duck bill anchors will be utilized to hold the coir log in place and further maintain its stability.

Construction Sequence

The proposed living shoreline will be constructed in a specific sequence that will terminate with the installation of salt marsh plantings that will stabilize the entire living shoreline and establish a densely vegetated salt marsh consisting principally of low marsh grass (Spartina alterniflora) and high marsh plant community dominated by salt meadow grass (Spartina patens). The following sequence outlines the principal construction elements of the project. Oversight by a restoration ecologist or professional wetland scientist would improve the success of the outcome. The establishment of accurate elevations of the planting shelves are important to improve the success of plant establishment.

-3-

4

- 1. Salvaged rock and existing living rock from the project site will be used to create a rocky intertidal shore consistent with the elevations on the design plans.
- 2. The created rocky intertidal shoreline will be created between approximately Elevation -2.0 to Elevation 2.0 (NGVD 1929).
- 3. The blended soil mix (2 parts sand, 1-part organic compost) will be used to infill the area landward of the installed salvaged rock and granite to create a planting shelf for the low marsh.
- 4. The low marsh shelf will be planted with plugs of salt marsh cord grass (Spartina alterniflora) on an 18 inch on center, configuration at approximately Elevation 2.0 (NGVD 1929).
- 5. The remaining bulkhead will be left in place and act as perches for birds and other wildlife.
- 6. The coir logs (24-inch Cocologix, or equal) will be installed along the proposed contour at approximately Elevation 2.0 to approximately Elevation 6.0 and secured with timber stakes or other suitable constraints (Duckbill Anchors, or equal).
- 7. The slope from approximately Elevation 6.0 to approximately Elevation 9.0 will be stabilized with coir mat and salt tolerant plantings (see plant list) to transition to the coastal bluff and North Mill Pond Greenway Trail.
- 8. Irrigation will be provided through the first growing season or until new plantings are established.
- 9. Monitoring will be conducted by faculty and graduate students of the Marine Science Center at Northeastern University and the University of New Hampshire.

Community Engagement

A main objective of the proposed project is to provide a desirable shoreline space that was once inaccessible for public recreational use. Providing this public area along the once degraded shoreline will provide educational opportunities. The site will feature interpretive signage with the goal to educate users on the importance of responsible shoreline rehabilitation and habitat restoration. Also, the community will be able to use the space as an outdoor classroom to give educators a visual tool for positive environmental restoration projects.

Invasive Species Control

We have identified the dominant invasive species within and adjacent to the project site including Norway maple (*Acer platanoides*), black locust (*Robinia pseudoacacia*), autumn olive (*Elaeagnus umbellata*), Japanese knotweed (*Polygonum cuspidatum*), Phragmites (*Phragmites australis*), and Asiatic bittersweet (*Celastrus orbiculatus*) (See Invasive Species Inventory figure). These species are the targeted plants for removal at the North Mill Pond Greenway site. The presence of invasive species has been identified throughout the understory and canopy of the site. The following is a description of the proposed methodology to remove the invasive plant species to substantially improve the function and value of the landscape.

Whole Plant Removal

The techniques of whole plant removal intend to remove the entire invasive plant including standing plant material as well as the roots and rhizomes of the invasive species. In this way,

the entire plant is removed, and re-colonization of the treatment area is substantially reduced. Simply cutting the standing vegetation will only stimulate recovery growth and a dense regrowth of the invasive species intended to be removed.

However, 100% removal is rarely achievable, even in an excavation effort with machinery and labor. Accordingly, professional judgment is necessary to determine when to cease removal activities in any particular project area. Typically, this work is conducted in the fall and winter, before the ground freezes, or in early spring. During the following spring and summer months additional hand pulling of newly sprouted seed material is required. Summer work can also be effective especially when the season is dry and reduced impact to soils is achievable.

Initial Removal with Equipment or Weed Wrench

Standing vegetation will be cut, removed, and stockpiled for burning or chipping for compost. A mini excavator will be used to remove the root balls of the targeted species. This will leave the exposed roots and stumps of the invasive species accessible for removal. The area can be cut with a machine as well during this phase of work. If heavy machinery is used for removal of root material, mats will be placed to minimize the disturbance of the soils by dispersing the weight of the equipment over a larger surface area, decreasing the compression of the soils. The entire restoration area will be cleared of the invasive woody species and maintained from the re-invasion of the targeted invasive plant species.

Removal of Root Ball and Trailing Roots and Rhizomes

Care must be used in pulling the root balls of invasive shrub species. The use of a mini excavator, described above, may facilitate the removal of the root balls of these species. Carefully lifting and shaking the root ball as it is extracted from the soil facilitates the removal of the trailing roots and rhizomes. The soil is then released from the root ball by gentle shaking of the bucket by the machine operator. In areas that are inaccessible by machine, the work will be completed with weed wrenches and by hand. If root balls are too large for extraction by weed wrenches, chains and straps will be lead out to the mini excavator, or in some cases we will use "come-alongs" and manually pull the root ball out of the soil. These root balls can be stockpiled and burned during the burning season. Ashes are a good amendment for fields and planting areas as they contain phosphorous and other nutrients. Alternatively, the root balls can be transported to an off-site facility for grinding and chipping and/or composting. Standing plant material is chipped separately for wood chips. This work is usually completed on site to reduce the volume of material that will need to be transported from the site.

Hand Clearing and Grubbing of Broken Roots and Rhizomes

Hand clearing and removal of broken root parts is important for invasive species management, as these shoots will re-sprout if any viable rootlets remain at the site. These collected roots can be stockpiled and burned during the local brush-burning season or composted off site for later use as a soil amendment. Our staff will follow the excavator operator and clear the restoration area of root fragments and rhizomes by hand. All collected roots are removed along with the collected root balls for off-site composting.

Stump Grinding

An arborist will come to the Site and mark the invasive, dead, and hazardous trees. The trees will be clearly marked by professional scientist and removed by appropriate machinery. The cut trees will be stump ground to prevent coppicing and re-growth.

Final Disposition of Removed Plant Material

Once the invasive plant material is harvested, we plan to either burn the material on site or to chip it and remove it from the site for composting. If the harvest occurs during the burning season there are several reasons to burn the majority of the material on site. Firstly, burning on site reduces costs of chipping and off-site transport of harvested material. Secondly, the

burning of woody material returns valuable nutrients to the soil structure, principally phosphorous, which in many systems has been depleted by plant growth and microbial activity. If possible, we prefer to burn the harvested material in small manageable brush piles to facilitate these benefits to the local ecosystem.

If the work is conducted out of the burning season the harvested material will be chipped on site and removed to an off-site composting operation for composting and subsequent use as a soil amendment. Chipping the plant material before it develops seeds or flowers renders the plant unviable, especially once the material has completely dried. Then, composting the chipped woody plants becomes a sustainable use for the harvested material. Once composted, this material will return valuable nutrients to the soil, which will eventually be used by other plants for growth.

Soil Augmentation, Grading, Seeding and Hay Mulch

The existing landscape will be augmented with compost and duff (decaying leaf mold) as needed, then re-graded to match the contours of the adjacent upland areas and gently sloped upward across the buffer zone. Of most importance is establishing a native plant community within the treated area, as discussed under the "Native Species Planting Plan" section below. Accordingly, any disturbed soils will be seeded, then hay mulched with salt marsh hay to quickly stabilize the disturbed soils. The areas will be maintained until native species have established.

Native Species Planting Plan

Subsequent planting of various plant species adapted to the local habitat will be installed according to the proposed Restoration Planting Plan (see attached). This planting palette includes native trees, shrubs, and herbaceous species that will create habitat value, as well as increase plant and wildlife diversity within the general area. Specific locations of these plantings will be chosen on site at the time of installation, but all will be within the designated restoration area. All plantings are to be installed by hand within the existing landscape to maintain soil stability unless otherwise noted. Plantings will be interspersed across the restoration area and not in a uniform "on-center" planting schedule (see attached). The following is a description of the proposed methodology to install native plant species to substantially improve the function and value of the landscape.

Canopy and Shrub Plantings

Red maple (*Acer rubrum*), will be installed as the canopy species within the restoration planting area and the buffer zone between the living shoreline and the North Mill Pond Greenway (see Site Plan, attached). Gator Bags or equivalent will be placed around the newly planted trees to ensure watering and establishment, as needed. A native shrub layer consisting of red cedar (*Juniperus virginiana*), beach plum (*Prunus maritima*), witch hazel (*Hamamelis virginiana*) and gray dogwood (*Cornus racemosa*) will be installed according to the proposed Restoration Planting Plan (see attached). These species will substantially improve the function and value of the landscape to provide wildlife habitat and ecological services to this degraded coastal ecosystem. These shrub species will be installed by hand in with at least three (3) gallon containerized nursery stock.

Herbaceous Plantings

The herbaceous plant community consists of a diversity of native grasses and flowering perennial plantings (see Restoration Planting Plan). These native plant species are adapted to wetland conditions and will add to the existing landscape. These species will be installed as one-gallon, containerized nursery stock. In addition, an herbaceous seed mix will be used in the wetland plant community. The ground plain seed mix that will be spread in the buffer zone includes coastal red fescue (Festuca rubra), switchgrass (Panicum virgatum), and little



bluestem (Schizachyrium scoparium). Seeding will occur after plantings have been installed, and the entire restoration area will be lightly raked to cover the seeds with soil.

This planting plan will improve the area's capacity to provide ecosystem functions including food, cover, and nest sites for wildlife species. All species to be installed are native to this region and are adapted to the surrounding soils and hydrology.

Aftercare and Maintenance

After the initial removal of the woody shrub and tree species, the restoration areas will be surveyed monthly to remove sprouting invasive species, since seed material is still present in the thatch and surface soils of the disturbed areas. Some of these seeds will germinate and sprout. It is very important to conduct these monthly surveys and to harvest by hand any sprouting invasive materials. During the first growing season, the majority of this material is handpicked. We typically use 5-gallon pails and fill them with new invasive seedlings for disposal. Each month there are fewer and fewer seedlings to harvest, and by the end of the first season the seeded area has become dense with new growth of desirable native species, and the invasive seedlings are practically eliminated. The second growing season will typically only require three (3) surveys, in the early spring, mid-summer, and mid-fall.

The living shoreline will be monitored for a minimum of two (2) years to maximum of five (5) years to ensure the grow in and establishment of the low marsh plantings (principally, Spartina alterniflora) and high marsh plantings (principally Spartina patens). The site will be visited quarterly and assessed for plant vigor, establishment, percent cover, and recommendations for replacement of plantings or substitutions for failed plantings. The salt marsh, living shoreline, and the coastal bluff plantings will be monitored in accordance with the requirements of the restoration planting plan. Annual reports will summarize the results of the monitoring efforts including photographs and lists of interventions that were undertaken, as needed. Annual reports will be submitted to the NH Department of Environmental Services and other applicable agencies.

Construction Oversight, Follow-up Observation, & Maintenance

Construction oversight, follow-up observations, and all plant installation work will be overseen in accordance with the NHDES monitoring protocol requirements. It is proposed that the restoration areas be reviewed prior to the issuance of a Certificate of Compliance and within the regulatory provision to ensure that wetland plant material has established itself as required by NHDES rules and regulations.



Conditional Use Permit

Jurisdictional wetland areas were delineated by Marc Jacobs, Certified Wetlands Scientist Number 090, in December of 2015. The functions and values associated with this parcel have been identified in Section 1 of the enclosed Wetland Application.

Based on the above described and enclosed materials, the following addresses how the proposed project warrants the granting of a Wetland Conditional Use Permit by satisfying the following six (6) criteria for approval in Section 10.1017.50 of the Zoning Ordinance:

- (1) The land is reasonably suited to the use, activity or alteration;
 - This land exhibits an eroding tidal shoreline adjacent to a buffer area impaired with invasive species and neglect. The proposed alterations intend to restore the shoreline and improve the function and value of the intertidal zone. Additionally, the project will provide public access to a desirable shoreline space that was once inaccessible for public recreational use.
- (2) There is no alternative location outside the wetland buffer that is feasible and reasonable for the proposed use, activity or alteration;

The placement of the pervious path and boardwalk provides enhanced functions and values to the site which offers opportunities for the public to responsibly interact with the delicate resource area and provide educational opportunities with interpretive signage along the proposed path and boardwalk. This site does not provide an alternative location outside of the wetland buffer that provides the same enhancements as described.

(3) There will be no adverse impact on the wetland functional values of the site or surrounding properties;

The proposed project is intended as a restoration project and will enhance the wetland functional values.

(4) Alteration of the natural vegetative state or managed woodland will occur only to the extent necessary to achieve construction goals; and

The proposed project will restore the area to a natural vegetative state with native plantings and invasive species control.

(5) The proposal is the alternative with the least adverse impact to areas and environments under the jurisdiction of this Section.

The permanent impacts, including the pervious pathway and boardwalk have been minimized to the maximum extent practical to be able to provide the proposed enhanced wetland functional values to the site.

(6) Any area within the vegetated buffer strip will be returned to a natural state to the extent feasible.

Proposed impacts to the vegetated buffer strip have been minimized to the maximum extent feasible. Additionally, the vegetated buffer strip will be restored from the existing neglect and abandonment to a proposed living shoreline and marsh area to enhance resiliency to the effect of sea level rise and provide desirable ecological services.

Conservation Commission Work Session Progress

This project was originally presented to the Conservation Commission at their October 13, 2021 meeting. The Commission voted to hold a work session for the project at their November 10, 2021 meeting to discuss potential improvements to the design. The enclosed plans have been updated to address improvements recommended by the Commission during the work session. The following is a summary of those revisions:

- 1. The boardwalk area has been reduced by 375 SF from the previous design. The location and size are shown on the enclosed Site Plan Set.
- 2. The 1-foot gravel shoulders have been eliminated on either side of the 10-foot porous pavement path.
- 3. Existing trees greater than 6-inch caliper will remain where possible.

At the Conservation Commission meeting on December 8, 2021, the commission voted to recommend that the Planning Board grant a Conditional Use Permit with stipulations that project agrees to incorporate into the design.

Conclusion

The proposed improvements intend to restore the impaired shoreline and improve the function and value of the intertidal zone. Moreover, the project will create greater coastal resiliency by creating a stable, living habitat to act as storm damage prevention to the upgradient buffer zone and developed areas. Habitat quality for wildlife will be significantly improved by providing food, cover, and overwintering areas for wildlife. The landward migration of salt marsh as a result of sea level rise will be able to progress into the buffer zone at the site given the gradual rise in elevation in these areas.

We respectfully request to be placed on the Planning Board meeting agenda for December 16, 2021. If you have any questions or need any additional information, please contact Patrick Crimmins by phone at (603) 433-8818 or by email at pmcrimmins@tighebond.com.

Sincerely,

TIGHE & BOND, INC.

Patrick M. Crimmins, PE Senior Project Manager

Enclosures

Cc: Peter Britz, City Environmental Planner & Interim Planning Director

Halvorson Tighe & Bond Studio Derosa Environmental Consulting




NORTH MILL POND GREENWAY AND COMMUNITY PARK - AREA 1

VAUGHAN STREET
PORTSMOUTH, NEW HAMPSHIRE
JULY 21, 2021
LAST REVISED: DECEMBER 3, 2021

LIST OF DRAWINGS				
SHEET NO.	SHEET TITLE	LAST REVISED		
	COVER SHEET	12/3/2021		
C-101	EXISTING CONDITIONS AND DEMOLITION PLAN	12/3/2021		
C-102	SITE PLAN	12/3/2021		
C-103	GRADING AND DRAINAGE PLAN	12/3/2021		
C-501	EROSION CONTROL NOTES AND DETAILS SHEET	7/21/2021		
C-502	DETAILS SHEET	7/21/2021		
C-503	BOARDWALK DETAILS SHEET	12/3/2021		
C-504	RESTORATION SECTION PLAN	7/21/2021		
L-101	RESTORATION PLANTING PLAN	12/3/2021		







LOCATION MAP
SCALE: 1" = 2,000'

PREPARED BY:

HALVORSON Tighe&Bond STUDIO

25 KINGSTON STREET
BOSTON, MASSACHUSETTS 02111-2200
617-536-0380

ENVIRONMENTAL CONSULTANT:

DEROSA ENVIRONMENTAL CONSULTING, INC.

167 MAIN STREET, PO BOX 716 ROWLEY, MASSACHUSETTS 01969

CIVIL CONSULTANT:

Tighe&Bond

177 CORPORATE DRIVE
PORTSMOUTH, NEW HAMPSHIRE 03801
603-433-8818

APPLICANT/OWNER:

CITY OF PORTSMOUTH

1 JUNKINS AVENUE, 3RD FLOOR PORTSMOUTH, NEW HAMPSHIRE 03801

SURVEYOR:

DOUCET SURVEY, LLC

192 KENT PLACE

NEWMARKET, NEW HAMPSHIRE 30857

t Saved: 7/21/2021 ted On:Dec 03, 2021-8:26am By: ASellar

EXISTING CONDITIONS PLAN NOTES:

- 1. EXISTING CONDITIONS ARE BASED ON A FIELD SURVEY BY DOUCET SURVEY INC, DATED FEBRUARY 3, 2016.
- 2. JURISDICTIONAL WETLANDS DELINEATED BY MARC JACOBS, IN DECEMBER 2015.
- 3. VERTICAL DATUM IS BASED ON NGVD29 PER DISK B2 1923

EXISTING UTILITIES REQUIRED TO COMPLETE THE WORK.

4. HORIZONTAL DATUM IS BASED ON NEW HAMPSHIRE STATE PLANE(2800) NAD83(2011) DERIVED FROM REDUNDANT GPS OBSERVATIONS UTILIZING THE KEYNET GPS VRS NETWORK.

REFERENCE PLANS:

- 1. "EXISTING CONDITIONS PLAN OF TAX MAP 123, LOT 15 & TAX MAP 124, LOTS 10 & 11" PREPARED BY DOUCET SURVEY INC, DATED FEBRUARY 3, 2016.
- "EXISTING CONDITIONS PLAN FOR TIGHE & BOND OF STONE CREEK REALTY" PREPARED BY DOUCET SURVEY LLC, DATED NOVEMBER 2019.

DEMOLITION NOTES:

- 1. THE LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND THE LOCATIONS ARE NOT GUARANTEED BY THE OWNER OR THE ENGINEER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES, ANTICIPATE CONFLICTS, REPAIR EXISTING UTILITIES AND RELOCATE
- 2. THE CONTRACTOR SHALL VERIFY LOCATION OF ALL EXISTING UTILITIES. CALL DIG SAFE AT LEAST 72 HOURS PRIOR TO THE COMMENCEMENT OF ANY DEMOLITION/CONSTRUCTION ACTIVITIES.
- 3. ALL MATERIALS SCHEDULED TO BE REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR UNLESS OTHERWISE SPECIFIED. THE CONTRACTOR SHALL DISPOSE OF ALL MATERIALS OFF-SITE IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS, ORDINANCES AND CODES.

- COORDINATE REMOVAL, RELOCATION, DISPOSAL OR SALVAGE OF UTILITIES WITH THE OWNER AND APPROPRIATE UTILITY COMPANY.
 ANY EXISTING WORK OR PROPERTY DAMAGED OR DISPUPED BY CONSTRUCTION/ DEMOLITION
- 5. ANY EXISTING WORK OR PROPERTY DAMAGED OR DISRUPTED BY CONSTRUCTION/ DEMOLITION ACTIVITIES SHALL BE REPLACED OR REPAIRED TO MATCH ORIGINAL EXISTING CONDITIONS BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- 6. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FAMILIARIZE THEMSELVES WITH THE CONDITIONS OF ALL OF THE PERMIT APPROVALS.
- 7. THE CONTRACTOR SHALL OBTAIN AND PAY FOR ADDITIONAL PERMITS, NOTICES AND FEES NECESSARY TO COMPLETE THE WORK AND ARRANGE FOR AND PAY FOR NECESSARY INSPECTIONS AND APPROVALS FROM THE AUTHORITIES HAVING JURISDICTION.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DEMOLITION AND OFF-SITE DISPOSAL OF MATERIALS REQUIRED TO COMPLETE THE WORK.
- 9. CONTRACTOR SHALL VERIFY ORIGIN OF ALL DRAINS AND UTILITIES PRIOR TO REMOVAL/TERMINATION TO DETERMINE IF DRAINS OR UTILITY IS ACTIVE, AND SERVICES ANY ON OR OFF-SITE STRUCTURE TO REMAIN. THE CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY SUCH UTILITY FOUND AND SHALL MAINTAIN THESE UTILITIES UNTIL
- PERMANENT SOLUTION IS IN PLACE.

 10. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL EXISTING STRUCTURES, CONCRETE PADS, UTILITIES AND PAVEMENT WITHIN THE WORK LIMITS SHOWN UNLESS SPECIFICALLY IDENTIFIED TO REMAIN. ITEMS TO BE REMOVED INCLUDE BUT ARE NOT LIMITED TO: ABANDONED RAIL ROAD TRACKS, CONCRETE, PAVEMENT, CURBS, UNDER GROUND PIPING,
- POLES, SIGNS, FENCES, TREES, LANDSCAPING AND DEBRIS.

 11. REMOVE TREES AND BRUSH AS REQUIRED FOR COMPLETION OF WORK. CONTRACTOR SHALL GRUB AND REMOVE ALL STUMPS WITHIN LIMITS OF WORK AND DISPOSE OF OFF SITE IN
- ACCORDANCE WITH FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS.


 12. CONTRACTOR SHALL PROTECT ALL PROPERTY MONUMENTATION THROUGHOUT DEMOLITION AND CONSTRUCTION OPERATIONS. SHOULD ANY MONUMENTATION BE DISTURBED BY THE CONTRACTOR, THE CONTRACTOR SHALL EMPLOY A NEW HAMPSHIRE LICENSED SURVEYOR TO REPLACE DISTURBED MONUMENTS.

13. PROVIDE INLET PROTECTION BARRIERS AT ALL CATCH BASINS/CURB INLETS WITHIN CONSTRUCTION LIMITS AS WELL AS CATCH BASINS/CURB INLETS THAT RECEIVE RUNOFF FROM CONSTRUCTION ACTIVITIES. INLET PROTECTION BARRIERS SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT. INLET PROTECTION BARRIERS SHALL BE "HIGH FLOW SILT SACK" BY ACF ENVIRONMENTAL OR EQUAL. INSPECT BARRIERS WEEKLY AND AFTER EACH RAIN EVENT OF 0.25 INCHES OR GREATER. CONTRACTOR SHALL COMPLETE A MAINTENANCE INSPECTION REPORT AFTER EACH INSPECTION. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT OR MORE OFTEN IF THE FABRIC BECOMES CLOGGED OR SEDIMENT HAS ACCUMULATED TO 1/3 THE DESIGN DEPTH OF THE BARRIER.

14. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE START OF ANY CLEARING OR DEMOLITION ACTIVITIES.

- 15. THE CONTRACTOR SHALL PAY ALL COSTS NECESSARY FOR TEMPORARY PARTITIONING, BARRICADING, FENCING, SECURITY AND SAFETY DEVICES REQUIRED FOR THE MAINTENANCE OF A CLEAN AND SAFE CONSTRUCTION SITE.
- 16. WATER BOUNDARIES ARE DYNAMIC IN NATURE AND ARE SUBJECT TO CHANGE DUE TO NATURAL CAUSES SUCH AS EROSION OR ACCRETION.
- 17. MEAN HIGH WATER (EL. 3.0' NGVD1929) AND HIGHEST OBSERVABLE TIDE (EL. 4.3' NGVD1929) ELEVATIONS PER "MAPLEWOOD AVENUE CULVERT REPALCEMENT AND NORTH MILL POND RESTORATION, WATERFRONT/STRUCTURAL BASIS OF DESIGN, BY WATERFRONT ENGINEERS,
- LLC, DATED DECEMBER 30, 2009".

 18. MANMADE AND NATURAL JURISDICTIONAL BOUNDARIES WERE DELINEATED BY MARC JACOBS, CERTIFIED WETLAND SCIENTIST NUMBER 090, IN 12/15 ACCORDING TO THE STANDARD OF THE US ARMY CORPS OF ENGINEERS WETLAND DELINEATION MANUAL, TECHNICAL REPORT T-87-1, JANUARY 1987; THE REGIONAL SUPPLEMENT TO THE CORPS OF ENGINEERS WETLAND DELINEATION MANUAL: NORTHCENTRAL AND NORTHEAST REGION, VERSION 2.0, JANUARY 2012; NH RSA 482-A:; THE CODE OF ADMINISTRATIVE RULES, NH DEPARTMENT OF ENVIRONMENTAL SERVICES-WETLANDS BUREAU CHAPTER ENV-WT 100-900; AS WELL AS THE CITY OF PORTSMOUTH ZONING ARTICAL 10, SECTION 10.1010, WETLANDS CONSERVATION DISTRICT. PREDOMINANT HYDRIV SOILS WERE IDENTIFIED UTILIZING THE FIELD INDICATORS FOR IDENTIFYING HYDRIC SOILS IN NEW ENGLAND, VERSION 3, APRIL 2004 AND THE FIELD INDICATORS OF HYDRIC SOILS IN THE IUNITED STATES, VERSION 7. THE INDICATOR STATUS OF HYDROPHYTIC VEGETATION WAS DETERMINED ACCORDING TO THE NATIONAL LIST OF PLANT SPECIES THAT OCCUR IN WETLANDS: NORTHEAST REGION, U.S. FISH AND WILDLIFE SERVICE.



Christian

Shore

Hampshire

nans Point

Bersum

PROJECT

Terrace

NORTH MILL POND GREENWAY AND COMMUNITY PARK - AREA 1

PORTSMOUTH, NE



MEZQUITA

0 20' 40'

GRAPHIC SCALE

CON COM WORK SESSION 12/3/202

PROJECT NO: P0766-006

DRAWN BY: AFS

CHECKED BY: PMC

SCALE: AS SHOWN


PERMIT SET
NOT FOR CONSTRUCTION


July 21, 2021


EXISTING CONDITIONS AND DEMOLITION PLAN

C-101

<u>LEGEND</u>







PROJECT OWNER: CITY OF PORTSMOUTH 1 JUNKINS AVENUE

PORTSMOUTH, NH 03801 PROJECT NAME: NORTH MILL POND GREENWAY AND COMMUNITY PARK - AREA 1

PROJECT ADDRESS: VAUGHAN STREET PORTSMOUTH, NH 03801 PROJECT MAP / LOT: MAP 123 / LOT 15

PROJECT LATITUDE: 43°-04'-49.95"N PROJECT LONGITUDE: 70°-45'-49.31"W

PROJECT DESCRIPTION

THE PROJECT CONSISTS OF CONSTRUCTION OF A PROPOSED GREENWAY PATH AND BOARDWALK ALONG THE NORTH MILL POND WATERFRONT INCLUDING WETLAND RESTORATION, INVASIVE SPECIES CONTROL, PROPOSED LIVING SHORELINE AND ADDITIONAL DRAINAGE IMPROVEMENTS.

THE TOTAL AREA TO BE DISTURBED IS APPROXIMATELY 1.25 ACRES.

BASED ON THE NRCS WEB SOIL SURVEY FOR ROCKINGHAM COUNTY - NEW HAMPSHIRE, THE SOILS ON SITE CONSIST OF URBAN LAND SOILS WITH NO HYDROLOGIC SOIL GROUP RATING PROVIDED.

NAME OF RECEIVING WATERS THE STORMWATER RUNOFF FROM THE SITE WILL BE DISCHARGED VIA OVERLAND FLOW OR COLLECTED THROUGH THE POROUS PAVEMENT UNDERDRAIN AND DISCHARGED TO THE NORTH MILL POND.

CONSTRUCTION SEQUENCE OF MAJOR ACTIVITIES:

CUT AND CLEAR VEGETATION.

- CONSTRUCT TEMPORARY AND PERMANENT SEDIMENT, EROSION AND DETENTION CONTROL FACILITIES. EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED PRIOR TO ANY EARTH MOVING OPERATIONS THAT WILL INFLUENCE STORMWATER RUNOFF SUCH AS:
- NEW CONSTRUCTION
- DEVELOPMENT OF BORROW PIT AREAS
- DISPOSAL OF SEDIMENT SPOIL, STUMP AND OTHER SOLID WASTE
- EXCAVATION WORK
- WETLAND MODIFICATIONS
- CONTROL OF DUST
- CONSTRUCTION OF ACCESS AND HAUL ROAD NEARNESS OF CONSTRUCTION SITE TO RECEIVING WATERS
- CONSTRUCTION DURING LATE WINTER AND EARLY SPRING
- . ALL PERMANENT DITCHES, SWALES, DETENTION, RETENTION AND SEDIMENTATION BASINS TO BE STABILIZED USING THE VEGETATIVE AND NON-STRUCTURAL BMPS PRIOR TO DIRECTING RUNOFF TO
- CLEAR AND DISPOSE OF DEBRIS.
- 5. CONSTRUCT TEMPORARY CULVERTS AND DIVERSION CHANNELS AS REQUIRED
- 6. CONSTRUCT AND STABILIZE LIVING SHORELINE AND HELICAL PILES FOR PROPOSED BOARDWALK. 7. GRADE AND GRAVEL PATH - AREA SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED 2. PERMANENT MEASURES AND PLANTINGS:
- 8. FINALIZE BOARDWALK CONSTRUCTION. 9. BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES SHALL BE
- SEEDED AND MULCHED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE. 10. DAILY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DRAINS, DITCHES, PERIMETER EROSION
- CONTROL MEASURES, SEDIMENT TRAPS, ETC., MULCH AND SEED AS REQUIRED 11. SEDIMENT TRAPS AND/OR BASINS SHALL BE USED AS NECESSARY TO CONTAIN RUNOFF UNTIL
- SOILS ARE STABILIZED. 12. FINISH PAVING PATH.
- 13. INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES
- 14. COMPLETE PERMANENT SEEDING AND LANDSCAPING
- 15. REMOVE TRAPPED SEDIMENTS FROM COLLECTOR DEVICES AS APPROPRIATE AND THEN REMOVE TEMPORARY EROSION CONTROL MEASURES.

SPECIAL CONSTRUCTION NOTES:

- 1. THE CONSTRUCTION SEQUENCE MUST LIMIT THE DURATION AND AREA OF DISTURBANCE.
- 2. THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES

- ALL EROSION CONTROL MEASURES AND PRACTICES SHALL CONFORM TO THE "NEW HAMPSHIRE TORMWATER MANUAL VOLUME 3: EROSION AND SEDIMENT CONTROLS DURING CONSTRUCTION"
- PREPARED BY THE NHDES THE PROJECT MUST BE CONDUCTED IN ACCORDANCE WITH THE "NEW HAMPSHIRE BEST MANAGEMENT PRACTICES FOR EROSION CONTROL DURING TRAIL MAINTENANCE AND
- CONSTRUCTION (TRAIL BMPS)" PREPARED BY THE NEW HAMPSHIRE BUREAU OF TRAILS PRIOR TO ANY WORK OR SOIL DISTURBANCE, CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR
- EROSION CONTROL MEASURES AS REQUIRED IN THE PROJECT MANUAL CONTRACTOR SHALL INSTALL TEMPORARY EROSION CONTROL BARRIERS, INCLUDING TURBIDITY CURTAINS, HAY BALES, SILT FENCES, MULCH BERMS, SILT SACKS AND SILT SOCKS AS SHOWN IN
- THESE DRAWINGS AS THE FIRST ORDER OF WORK. SILT SACK INLET PROTECTION SHALL BE INSTALLED IN ALL EXISTING AND PROPOSED CATCH BASIN
- INLETS WITHIN THE WORK LIMITS AND BE MAINTAINED FOR THE DURATION OF THE PROJECT. 7. PERIMETER CONTROLS INCLUDING TURBIDITY CURTAINS, SILT FENCES, MULCH BERM, SILT SOCK,
- AND/OR HAY BALE BARRIERS SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT UNTIL NON-PAVED AREAS HAVE BEEN STABILIZED. 8. THE CONTRACTOR SHALL REMOVE AND PROPERLY DISPOSE OF ALL TEMPORARY EROSION CONTROL
- DEVICES UPON COMPLETION OF CONSTRUCTION.
- 9. ALL DISTURBED AREAS NOT OTHERWISE BEING TREATED SHALL RECEIVE 6" LOAM, SEED AND FERTILIZER.
- 10. INSPECT ALL INLET PROTECTION AND PERIMETER CONTROLS WEEKLY AND AFTER EACH RAIN STORM OF 0.25 INCH OR GREATER. REPAIR/MODIFY PROTECTION AS NECESSARY TO MAXIMIZE EFFICIENCY OF FILTER. REPLACE ALL FILTERS WHEN SEDIMENT IS 1/3 THE FILTER HEIGHT.

- AN AREA SHALL BE CONSIDERED STABLE WHEN ONE OF THE FOLLOWING HAS OCCURRED: A. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED;
- B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;
- C. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN
- EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.;
- E. IN AREAS TO BE PAVED, "STABLE" MEANS THAT BASE COURSE GRAVELS MEETING THE REQUIREMENTS OF NHDOT STANDARD FOR ROAD AND BRIDGE CONSTRUCTION, 2016, ITEM
- 304.2 HAVE BEEN INSTALLED. 2. WINTER STABILIZATION PRACTICES:
- A. ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS;
- B. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS;
- AFTER OCTOBER 15, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3, OR IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON BE CLEARED OF ANY ACCUMULATED SNOW AFTER EACH STORM EVENT;
- 3. STABILIZATION SHALL BE INITIATED ON ALL LOAM STOCKPILES, AND DISTURBED AREAS, WHERE CONSTRUCTION ACTIVITY SHALL NOT OCCUR FOR MORE THAN TWENTY-ONE (21) CALENDAR DAYS BY THE FOURTEENTH (14TH) DAY AFTER CONSTRUCTION ACTIVITY HAS PERMANENTLY OR TEMPORARILY CEASED IN THAT AREA. STABILIZATION MEASURES TO BE USED INCLUDE:
- A. TEMPORARY SEEDING; B. MULCHING.
- 4. ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE
- WHEN CONSTRUCTION ACTIVITY PERMANENTLY OR TEMPORARILY CEASES WITHIN 100 FEET OF NEARBY SURFACE WATERS OR DELINEATED WETLANDS, THE AREA SHALL BE STABILIZED WITHIN SEVEN (7) DAYS OR PRIOR TO A RAIN EVENT. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN THESE AREAS, SILT FENCES, MULCH BERMS, HAY BALE BARRIERS AND ANY
- EARTH/DIKES SHALL BE REMOVED ONCE PERMANENT MEASURES ARE ESTABLISHED DURING CONSTRUCTION, RUNOFF WILL BE DIVERTED AROUND THE SITE WITH EARTH DIKES, PIPING

OR STABILIZED CHANNELS WHERE POSSIBLE. SHEET RUNOFF FROM THE SITE WILL BE FILTERED

THROUGH SILT FENCES, MULCH BERMS, HAY BALE BARRIERS, OR SILT SOCKS. ALL STORM DRAIN BASIN INLETS SHALL BE PROVIDED WITH FLARED END SECTIONS AND TRASH RACKS. THE SITE SHALL BE STABILIZED FOR THE WINTER BY OCTOBER 15.

- THE CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST THROUGHOUT THE CONSTRUCTION
- 2. DUST CONTROL METHODS SHALL INCLUDE, BUT BE NOT LIMITED TO SPRINKLING WATER ON
- EXPOSED AREAS, COVERING LOADED DUMP TRUCKS LEAVING THE SITE, AND TEMPORARY
- DUST CONTROL MEASURES SHALL BE UTILIZED SO AS TO PREVENT THE MIGRATION OF DUST FROM THE SITE TO ABUTTING AREAS.

LOCATE STOCKPILES A MINIMUM OF 50 FEET AWAY FROM SURFACE WATERS, CATCH BASINS,

OF THE BARRIER SHOULD BE INSPECTED AT THE END OF EACH WORKING DAY.

- ALL STOCKPILES SHOULD BE SURROUNDED WITH TEMPORARY EROSION CONTROL MEASURES PRIOR TO THE ONSET OF PRECIPITATION.
- PERIMETER BARRIERS SHOULD BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMMODATE THE DELIVERY AND REMOVAL OF MATERIALS FROM THE STOCKPILE. THE INTEGRITY
 - PROTECT ALL STOCKPILES FROM STORMWATER RUN-OFF USING TEMPORARY EROSION CONTROL MEASURES SUCH AS BERMS, SILT SOCK, OR OTHER APPROVED PRACTICE TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THE STOCKPILES.

OFF SITE VEHICLE TRACKING:

1. THE CONTRACTOR SHALL CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE(S) PRIOR TO ANY **EXCAVATION ACTIVITIES.**

- TEMPORARY GRASS COVER: A. SEEDBED PREPARATION
 - a. APPLY FERTILIZER AT THE RATE OF 600 POUNDS PER ACRE OF 10-10-10. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF THREE (3)
- a. UTILIZE ANNUAL RYE GRASS AT A RATE OF 40 LBS/ACRE; b. WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO
- A DEPTH OF TWO (2) INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED; c. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, OR HYDROSEEDER (SLURRY
- INCLUDING SEED AND FERTILIZER). HYDROSEEDINGS, WHICH INCLUDE MULCH, MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING;
- C. MAINTENANCE: a. TEMPORARY SEEDING SHALL BE PERIODICALLY INSPECTED. AT A MINIMUM, 95% OF THE SOIL SURFACE SHOULD BE COVERED BY VEGETATION. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHALL BE MADE AND OTHER TEMPORARY MEASURES USED IN THE INTERIM (MULCH, FILTER BARRIERS, CHECK DAMS, ETC.).
- A. SEE RESTORATION PLANTING PLAN (SHEET L-101).

ALLOWABLE NON-STORMWATER DISCHARGES:

- FIRE-FIGHTING ACTIVITIES;
- FIRE HYDRANT FLUSHING; WATERS USED TO WASH VEHICLES WHERE DETERGENTS ARE NOT USED;
- WATER USED TO CONTROL DUST;
- POTABLE WATER INCLUDING UNCONTAMINATED WATER LINE FLUSHING;
- ROUTINE EXTERNAL BUILDING WASH DOWN WHERE DETERGENTS ARE NOT USED;
- PAVEMENT WASH WATERS WHERE DETERGENTS ARE NOT USED;
- UNCONTAMINATED AIR CONDITIONING/COMPRESSOR CONDENSATION
- 9. UNCONTAMINATED GROUND WATER OR SPRING WATER; 10. FOUNDATION OR FOOTING DRAINS WHICH ARE UNCONTAMINATED;
- UNCONTAMINATED EXCAVATION DEWATERING; 12. LANDSCAPE IRRIGATION.

- ALL WASTE MATERIALS SHALL BE COLLECTED AND STORED IN SECURELY LIDDED RECEPTACLES. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE SHALL BE DEPOSITED IN A DUMPSTER:
- B. NO CONSTRUCTION WASTE MATERIALS SHALL BE BURIED ON SITE; C. ALL PERSONNEL SHALL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL BY THE SUPERINTENDENT.
- 2. HAZARDOUS WASTE: A. ALL HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER;
- B. SITE PERSONNEL SHALL BE INSTRUCTED IN THESE PRACTICES BY THE SUPERINTENDENT. 3. SANITARY WASTE:

A ROOF OR OTHER ENCLOSURE, ON AN IMPERVIOUS SURFACE;

A. ALL SANITARY WASTE SHALL BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF ONCE PER WEEK BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.

- CONTRACTOR SHALL BE FAMILIAR WITH SPILL PREVENTION MEASURES REQUIRED BY LOCAL, STATE AND FEDERAL AGENCIES. AT A MINIMUM, CONTRACTOR SHALL FOLLOW THE BEST MANAGEMENT SPILL PREVENTION PRACTICES OUTLINED BELOW
- THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT SHALL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES DURING CONSTRUCTION TO STORMWATER RUNOFF:
- A. GOOD HOUSEKEEPING THE FOLLOWING GOOD HOUSEKEEPING PRACTICE SHALL BE FOLLOWED ON SITE DURING CONSTRUCTION:
- a. ONLY SUFFICIENT AMOUNTS OF PRODUCTS TO DO THE JOB SHALL BE STORED ON SITE; b. ALL REGULATED MATERIALS STORED ON SITE SHALL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR PROPER (ORIGINAL IF POSSIBLE) CONTAINERS AND, IF POSSIBLE, UNDER
- c. MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL SHALL BE FOLLOWED; d. THE SITE SUPERINTENDENT SHALL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL
- e. SUBSTANCES SHALL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER; f. WHENEVER POSSIBLE ALL OF A PRODUCT SHALL BE USED UP BEFORE DISPOSING OF THE
- g. THE TRAINING OF ON-SITE EMPLOYEES AND THE ON-SITE POSTING OF RELEASE RESPONSE INFORMATION DESCRIBING WHAT TO DO IN THE EVENT OF A SPILL OF REGULATED
- B. HAZARDOUS PRODUCTS THE FOLLOWING PRACTICES SHALL BE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS: a. PRODUCTS SHALL BE KEPT IN THEIR ORIGINAL CONTAINERS UNLESS THEY ARE NOT
- b. ORIGINAL LABELS AND MATERIAL SAFETY DATA SHALL BE RETAINED FOR IMPORTANT PRODUCT INFORMATION:
- MANUFACTURER'S RECOMMENDED METHODS OF DISPOSAL C. PRODUCT SPECIFIC PRACTICES - THE FOLLOWING PRODUCT SPECIFIC PRACTICES SHALL BE

c. SURPLUS PRODUCT THAT MUST BE DISPOSED OF SHALL BE DISCARDED ACCORDING TO THE

FOLLOWED ON SITE: a. PETROLEUM PRODUCTS

OF MATERIALS;

- i. ALL ON SITE VEHICLES SHALL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE LEAKAGE;
- ii. PETROLEUM PRODUCTS SHALL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT BASED SUBSTANCES USED ON SITE SHALL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.
- iii. SECURE FUEL STORAGE AREAS AGAINST UNAUTHORIZED ENTRY; iv. INSPECT FUEL STORAGE AREAS WEEKLY;
- v. WHEREVER POSSIBLE, KEEP REGULATED CONTAINERS THAT ARE STORED OUTSIDE MORE THAN 50 FEET FROM SURFACE WATER AND STORM DRAINS, 75 FEET FROM PRIVATE WELLS, AND 400 FEET FROM PUBLIC WELLS; vi. COVER REGULATED CONTAINERS IN OUTSIDE STORAGE AREAS;

vii. SECONDARY CONTAINMENT IS REQUIRED FOR CONTAINERS CONTAINING REGULATED


ABOVEGROUND OR UNDERGROUND STORAGE TANKS OTHERWISE REGULATED. viii. THE FUEL HANDLING REQUIREMENTS SHALL INCLUDE: (1) EXCEPT WHEN IN USE, KEEP CONTAINERS CONTAINING REGULATED SUBSTANCES CLOSED AND SEALED;

SUBSTANCES STORED OUTSIDE, EXCEPT FOR ON PREMISE USE HEATING FUEL TANKS, OR


- (2) PLACE DRIP PANS UNDER SPIGOTS, VALVES, AND PUMPS;
- (3) HAVE SPILL CONTROL AND CONTAINMENT EQUIPMENT READILY AVAILABLE IN ALL
- (4) USE FUNNELS AND DRIP PANS WHEN TRANSFERRING REGULATED SUBSTANCES,
- (5) PERFORM TRANSFERS OF REGULATED SUBSTANCES OVER AN IMPERVIOUS SURFACE. ix. FUELING AND MAINTENANCE OF EXCAVATION, EARTHMOVING AND OTHER CONSTRUCTION RELATED EQUIPMENT SHALL COMPLY WITH THE REGULATIONS OF THE NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES THESE REQUIREMENTS ARE SUMMARIZED IN WD-DWGB-22-6 BEST MANAGEMENT PRACTICES FOR FUELING AND MAINTENANCE OF EXCAVATION AND EARTHMOVING EQUIPMENT, OR ITS SUCCESSOR DOCUMENT.
- i. FERTILIZERS USED SHALL BE APPLIED ONLY IN THE MINIMUM AMOUNTS DIRECTED BY THE SPECIFICATIONS;
- ii. ONCE APPLIED FERTILIZER SHALL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORMWATER;
- iii. STORAGE SHALL BE IN A COVERED SHED OR ENCLOSED TRAILERS. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER SHALL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS.
- c. PAINTS:
- ALL CONTAINERS SHALL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE; ii. EXCESS PAINT SHALL NOT BE DISCHARGED TO THE STORM SEWER SYSTEM;
- iii. EXCESS PAINT SHALL BE DISPOSED OF PROPERLY ACCORDING TO MANUFACTURER'S INSTRUCTIONS OR STATE AND LOCAL REGULATIONS. D. SPILL CONTROL PRACTICES - IN ADDITION TO GOOD HOUSEKEEPING AND MATERIAL
- MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTION, THE FOLLOWING PRACTICES SHALL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP: a. MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP SHALL BE CLEARLY POSTED AND SITE PERSONNEL SHALL BE MADE AWARE OF THE PROCEDURES AND THE
- LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES; b. MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP SHALL BE KEPT IN THE MATERIAL STORAGE AREA ON SITE. EQUIPMENT AND MATERIALS SHALL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUSTPANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND SAWDUST AND PLASTIC OR METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE; ALL SPILLS SHALL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY;
- d. THE SPILL AREA SHALL BE KEPT WELL VENTILATED AND PERSONNEL SHALL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE;
- e. SPILLS OF TOXIC OR HAZARDOUS MATERIAL SHALL BE REPORTED TO THE APPROPRIATE LOCAL, STATE OR FEDERAL AGENCIES AS REQUIRED; f. THE SITE SUPERINTENDENT RESPONSIBLE FOR DAY-TO-DAY SITE OPERATIONS SHALL BE
- THE SPILL PREVENTION AND CLEANUP COORDINATOR. E. VEHICLE FUELING AND MAINTENANCE PRACTICE:
- a. CONTRACTOR SHALL MAKE AN EFFORT TO PERFORM EQUIPMENT/VEHICLE FUELING AND MAINTENANCE AT AN OFF-SITE FACILITY; b. CONTRACTOR SHALL PROVIDE AN ON-SITE FUELING AND MAINTENANCE AREA THAT IS
- CLEAN AND DRY; c. IF POSSIBLE THE CONTRACTOR SHALL KEEP AREA COVERED
- d. CONTRACTOR SHALL KEEP A SPILL KIT AT THE FUELING AND MAINTENANCE AREA;
- e. CONTRACTOR SHALL REGULARLY INSPECT VEHICLES FOR LEAKS AND DAMAGE; f. CONTRACTOR SHALL USE DRIP PANS, DRIP CLOTHS, OR ABSORBENT PADS WHEN REPLACING SPENT FLUID.

EROSION CONTROL OBSERVATIONS AND MAINTENANCE PRACTICES

- THIS PROJECT EXCEEDS ONE (1) ACRE OF DISTURBANCE AND THUS REQUIRE A SWPPP. THE SWPPP SHALL BE PREPARED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE FAMILIAR WITH THE SWPPP AND KEEP AN UPDATED COPY OF THE SWPPP ONSITE AT ALL TIMES
- THE FOLLOWING REPRESENTS THE GENERAL OBSERVATION AND REPORTING PRACTICES THAT SHALL BE FOLLOWED AS PART OF THIS PROJECT: A. OBSERVATIONS OF THE PROJECT FOR COMPLIANCE WITH THE SWPPP SHALL BE MADE BY THE
- CONTRACTOR AT LEAST ONCE A WEEK OR WITHIN 24 HOURS OF A STORM 0.25 INCHES OR B. AN OBSERVATION REPORT SHALL BE MADE AFTER EACH OBSERVATION AND DISTRIBUTED TO
- THE ENGINEER, THE OWNER, AND THE CONTRACTOR; C. A REPRESENTATIVE OF THE SITE CONTRACTOR, SHALL BE RESPONSIBLE FOR MAINTENANCE AND REPAIR ACTIVITIES;
- D. IF A REPAIR IS NECESSARY, IT SHALL BE INITIATED WITHIN 24 HOURS OF REPORT.



FULL-DEPTH TURBIDITY CURTAIN



WATER FLOW


WORK AREA

- 1. SILT SOCK SHALL BE SILT SOXX BY FILTREXX OR APPROVED EQUAL.
- 2. SILT SOCK SHALL BE FILLED WITH AREA TO BE PROTECTED FILTERMEDIA BY FILTREXX OR APPROVED
 - 3. WHERE TWO SILT SOCKS ARE JOINED, A MINIMUM OF 2 FEET OF OVERLAP SHALL BE MAINTAINED.
 - 4. SILT SOCKS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS 5. CONTRACTOR TO INSTALL SILT SOCK IN


J-HOOK OR SMILE CONFIGURATION TO

LIMIT CONCENTRATION OF STORMWATER


RUNOFF AT A SINGLE DISCHARGE POINT.




STABILIZED CONSTRUCTION EXIT



DEGREES FAHRENHEIT.



MONTHS OF EXPECTED USABLE CONSTRUCTION LIFE AT A TEMPERATURE RANGE OF 0 DEGREES FAHRENHEIT TO 120



OND TY P,



PATRICK

REVISIONS

PROJECT NO: P0766-006 DRAWN BY: AFS

AS SHOWN

PERMIT SET NOT FOR CONSTRUCTION


> July 21, 2021 **EROSION CONTROL** NOTES AND

DETAILS SHEET



SILT SACK

NO SCALE



(SEE GRADING, DRAINAGE AND EROSION CONTROL PLAN FOR LOCATIONS AND SIZE)

SEE GRADING AND DRAINAGE PLAN FOR SLOPE AND CROSS-SLOPE.

- GRAVEL SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST SPECIFICATIONS FROM THE UNH STORMWATER CENTER FOR POROUS ASPHALT. FILTER COURSE TO BE INCREASED AS NECESSARY TO MEET PROPOSED GRADES.
- INSTALL FILTER COURSE AGGREGATE IN 8-INCH MAXIMUM LIFTS TO A MAXIMUM OF 95% STANDARD PROCTOR COMPACTION (ASTM D698 / AASHTO T99). INSTALL AGGREGATE TO GRADES INDICATED ON THE DRAWINGS. INSTALL CHOKER, GRAVEL, AND STONE BASE COURSE AGGREGATE TO A MAXIMUM OF 95% COMPACTION STANDARD PROCTOR (ASTM D698 / AASHTO T99), CHOKER SHOULD BE PLACED EVENLY OVER SURFACE OF
- ASPHALT BUT NO LESS THAN 6-INCHES IN DEPTH. THE DENSITY OF SUBBASE COURSES SHALL BE DETERMINED BY AASHTO T 191 (SAND-CONE METHOD), AASHTO T 204 (DRIVE CYLINDER METHOD), OR AASHTO T 238 (NUCLEAR METHODS), OR OTHER APPROVED METHODS AT THE DISCRETION OF THE SUPERVISING ENGINEER.

FILTER COURSE BED, SUFFICIENT TO ALLOW PLACEMENT OF PAVEMENT, AND NOTIFY ENGINEER FOR APPROVAL.

CHOKER BASE COURSE THICKNESS SHALL BE SUFFICIENT TO ALLOW FOR EVEN PLACEMENT OF THE POROUS

POROUS PAVEMENT SECTION NO SCALE

	AASHTO #3 STONE			
(RESERVO	(RESERVOIR COURSE)			
	% PASSING			
2-½ "	100			
2"	90-100			
$1-\frac{1}{2}$ "	35-70			
1"	0-15			
<u>1</u> "	0-5			
	AASHTO #8 STONE (PEA GRAVEL)			
	% PASSING			
<u>1</u> "	100			
<u>3</u> "	85-100			
#4	10-30			
#8	0-10			
#16	0-5			
_	MODIFIED NHDOT 304.1			
	% PASSING			
6"	100			
#4	70-100			
#200	0-6*			
(CRUS	NHDOT ITEM No. 304.3 (CRUSHED GRAVEL)			
CIEVE CIZE	0/2 DACCING			


55-85 27-52

STABLE VEGETATED UPLAND FLEXIBLE FASTENERS (2 FT. LONG) STREAM BED FLEXIBLE FASTENERS (2 FT. LONG) STREAM BED FLEXIBLE FASTENERS (2 FT. LONG) STREAM BED FLEXIBLE FASTENERS (2 FT. LONG)
TYPICAL COIR LOG USE FOR BANK STABILIZATION

NO SCALE

	MINAL SIZE I.D.*	0.0000	ERALL GTH**	NUMBER OF CLAMPS -	CUFF DEPTH		BACK PRESSURE RATING	
Inches	Millimeters	Inches	Millimeters	OI GENING	Inches	Millimeters	Feet	Meters
12	300	23	584	1	2	51	40	12


Mounting Styles and Configurations



Downstream Flanged


Flange shape and bolt pattern can be customized. Flangeless thimble inserts are available.


TYPICAL BACK FLOW PREVENTER NO SCALE



- 1. MANHOLE FRAME AND COVER SHALL BE 32" HINGED ERGO XL
- BY EJ CO. 2. ALL DIMENSIONS ARE NOMINAL.
- 3. FRAMES USING NARROWER DIMENSIONS FOR THICKNESS ARE ALLOWED PROVIDED:
- A. THE FRAMES MEET OR EXCEED THE SPECIFIED LOAD RATING. B. THE INTERIOR PERIMETER (SEAT AREA) DIMENSIONS OF THE FRAMES REMAIN THE SAME TO ALLOW CONTINUED USE OF EXISTING GRATES/COVERS AS THE EXISTING FRAMES ALLOW, WITHOUT SHIMS OR OTHER MODIFICATIONS OR ACCOMMODATIONS.
- C. ALL OTHER PERTINENT REQUIREMENTS OF THE
- SPECIFICATIONS ARE MET.
- 4. LABEL TYPE OF MANHOLE WITH 3" HIGH LETTERS IN HE CENTER OF THE COVER.


DRAIN MANHOLE FRAME & COVER





STORM DRAIN TRENCH

NO SCALE




1. ALL SECTIONS SHALL BE 4,000 PSI CONCRETE.

- 2. CIRCUMFERENTIAL REINFORCEMENT SHALL BE 0.12 SQUARE INCHES PER LINEAR FOOT IN ALL SECTIONS AND SHALL BE PLACED IN THE CENTER THIRD OF THE WALL.
- 3. THE TONGUE AND THE GROOVE OF THE JOINT SHALL CONTAIN ONE LINE OF CIRCUMFERENTIAL REINFORCEMENT EQUAL TO 0.12
- SQUARE INCHES PER LINEAR FOOT.
- 4. THE STRUCTURES SHALL BE DESIGNED FOR H20 LOADING. CONSTRUCT CRUSHED STONE BEDDING AND BACKFILL UNDER (6" MINIMUM THICKNESS)
- THE TONGUE AND GROOVE JOINT SHALL BE SEALED WITH ONE STRIP OF BUTYL RUBBER SEALANT.
- PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO PRECASTING.
- OUTSIDE EDGES OF PIPES SHALL PROJECT NO MORE THAN 3" BEYOND INSIDE WALL OF STRUCTURE. 9. PRECAST SECTIONS SHALL HAVE A TONGUE AND GROOVE JOINT 4" HIGH AT AN 11° ANGLE CENTERED IN THE WIDTH OF THE
- WALL AND SHALL BE ASSEMBLED USING AN APPROVED FLEXIBLE SEALANT IN JOINTS. 10. ALL STRUCTURES WITH MULTIPLE PIPES SHALL HAVE A MINIMUM OF 12" OF INSIDE SURFACE BETWEEN HOLES, NO MORE THAN
- 75% OF A HORIZNTAL CROSS SECTION SHALL BE HOLES, AND THERE SHALL BE NO HOLES CLOSER THAN 3" TO JOINTS. 13. THE INSIDE OF THE CONCRETE STRUCTURE SHALL BE TREATED WITH A SILOXANE COATING AND SHALL BE INSTALLED PER
 - MANUFACTURER'S RECOMMENDATIONS. SILOXANE COATING SHALL BE SIKAGARD-705L OR APPROVED EQUAL.

4' DIAMETER DRAIN MANHOLE

NO SCALE



HALVORSON

25 KINGSTON ST, BOSTON MA 02111-2200 (PHONE) 617.536.0380 WWW.HALVORSONDESIGN.COM

MILL POND






REVISIONS


PROJECT NO:	P0766 - 006
DRAWN BY:	AFS
CHECKED BY:	PMC
SCALE:	AS SHOWN

PERMIT SET NOT FOR CONSTRUCTION


July 21, 2021


DETAILS SHEET





GRAPHIC SCALE







HALVORSON Tighe&Bond STUDIO

25 KINGSTON ST, BOSTON MA 02111-2200 [PHONE] 617.536.03B0 WWW.HALVORSONDESIGN.COM

> NORTH MILL POND GREENWAY AND COMMUNITY PARK - AREA 1





CON COM WORK SESSION 12/3/2021
REVISIONS

PROJECT NO:	P0766-006
DRAWN BY:	AFS
CHECKED BY:	PMC
SCALE:	AS SHOWN


PERMIT SET


NOT FOR CONSTRUCTION


July 21, 2021


BOARDWALK DETAILS SHEET

C - 503










HALVORSON Tighe&Bond studio

NORTH MILL POND GREENWAY COMMUNITY PARK - AREA



REVISIONS

	PROJECT NO:	P0766-006
	DRAWN BY:	AFS
	CHECKED BY:	PMC
	SCALE:	AS SHOWN
- 1		

PERMIT SET NOT FOR CONSTRUCTION

July 21, 2021

RESTORATION SECTION PLAN

Planting Notes:

- 1. Invasive plant material will be removed using mechanical, whole plant removal strategies and chipped and composted at an appropriate facility or burned on site according to local fire department rules and regulations.
- 2. Disturbed soils within the upland buffer zone will be augmented as needed with a custom blended soil of one part loam, one part compost and one part clean sand.
- 3. Seeded areas are to be covered with salt marsh hay to retain soil moisture and protect against seed predation by birds and small mammals.

Common Name	Scientific Name	Indicator Status	Quantiy	Sizo
Buffer Zone Adjacent to Sal	t Marsh-Living Shoreline			
Red Maple	Acer rubrum	FAC	8	2.5
Red cedar	Juniperus virginiana	FACU	12	3 gall
Beach Plum	Prunus maritima	UPL	25	5 gallo
Witch Hazel	Hamamelis virginiana	FACU	25	5 gall
Gray Dogwood	Cornus racemosa	FAC	50	5 galle
Pearly Everlasting	Anaphalis margaritacea	FACU	50	1 galle
False Indigo (purple)	Asclepias syriaca	UPL	50	1 gallo
Black-eyed Susan	Rudbeckia hirta	FACU	100	1 galle
Coneflower	Rudbeckia lacinata	UPL	100	1 galle
Red Fescue	Festuca rubra	FACU-	100 pounds	seed
Indian Grass	Sorghastrum nutans	UPL	50	1 galle
Switchgrass	Panicum virgatum	FAC	50	1 gallo
Upland Bentgrass	Agrostis pernnans	FACU	50	1 galle
Little Bluestem	Schizachyrium scoparium	FACU-	100	1 gallo
NE Lupine	Lupinus perennis	UPL	200	1 gallo
New Jersey Tea	Ceanothus americanus	UPL	100	1 gallo
Living Shoreline Plant List				
Low Marsh				
Chordgrass	Spartina alterniflora	OBL	500	Plug
High Marsh				
High Marsh Grass	Spartina patens	FACW	50	Plug
Sea Lavender	Limonium carolinianum	OBL	50	1 gallo
Sea Side Goldenrod	Solidago maratima	UPL	100	1 gallo
Black Grass	Juncus gerardii	FACW	100	1 gallo

(1) Plant species with scientific names and quantities provided. Included in planting list.

(2) Source of planting materials or whether the plan relies on natural re-vegeta-

Source will be from local nurseries including by not limited to: Pierson Nursery, Biddeford Maine; Bigelow Nursery, Northborough MA.

(3) Plant stock size and zones of predicted plant occurrence; Included on planting list

(4) Plant survival goals;

Expect to achieve 75 % success on or before 3 years post installation

(5) The proposed locations of native plant stock and the rate and type of seed-

Included on planting plan but will be determined in the field at time of planting based on local microtopography and specific site conditions.

(6) When and where seeding or planting will take place; and

(d) Documentation of existing and proposed soils as follows:

(1) The existing soils on the proposed mitigation site;


Existing soils consist of fill materials and debris; gravel, brick, wood. These materials will be filled with blended soils as described below to elevations condusive to the establishment of the native plant species proposed for the different planting zones: low marsh, high marsh, upland buffer.

(2) The source of soils to be placed on the site;

Blended soils consisting of 2 parts sand and 1 part organic compost will be sourced from local venders and inspected before use in the project. Soils will be blended at the facility and delivered to the site in their final form.

(3) The likely seed bank composition of soils;

The seed bank of existing soils is likely composed of a variety of invasive species that currently occupy the site including black locust, Asiatic Bittersweet, Phragmites, privet, bush honeysuckle, and multiflora rose. The proposed invasive species management plan (see narrative) intends to manage the site for re-colonization of the site with these invasive species.



HALVORSON Tighe&Bond STUDIO

NEW HAMPSHIRE NORTH MILL POND GREENWAY
COMMUNITY PARK - AREA

Restoration

Planting Plan

North Mill Pond Greenway Portsmouth, NH

1. Base Plan prepared by Halvorson Tighe & Bond Studio, Project No. P7066-003.

2. Additional text added by DeRosa Environmental Consulting, Inc. April 16, 2021.



978.948.7717 Office

PWS No. 2250

CON COM WORK SESSION **REVISIONS**

PROJECT NO: P0766-006


AS SHOWN PERMIT SET

NOT FOR CONSTRUCTION

July 21, 2021

SITE PLAN






DEROSA Environmental Consulting, Inc.

Invasive Species Inventory

North Mill Pond Multi-use Trail | Portsmouth, NH



Asiatic Bittersweet

Autumn Olive

Norway Maple (canopy and saplings)

Autumn Olive

Asiatic Bittersweet Norway Maple Japanese Knotweed Phragmites

Black Locust (canopy and saplings)



MJD/aem November 5. 20







Owner's Letter of Authorization

I, Peter Britz , of <u>The City of Portsmouth</u> (Owner) hereby give <u>Tighe & Bond, Inc.</u> (site/civil Engineer) permission to be my agent in all site design and permitting matters for the proposed project located at 0 Vaughan Street in Portsmouth, New Hampshire on the parcel of land identified as Tax Map 123 Lot 15. This authorization shall include any required signatures for local, state and federal permit applications.					
Signature	Peter Britz Print Name	9-21-21 Date			
Witness	TZAK 6ilbo Print Name	9-21-21 Date			