

## ADDENDUM #1

Issued: April 4, 2018

### Bid #65-18 PHS – CTE MAKERSPACE

This Addendum forms part of the original document marked “**Bid 65-18 PHS-CTE Makerspace Project**”.

**The following questions have been asked and answered.**

- Wall paint specifications, Latex? **Yes latex paint will be used and color will be TBD once contract is awarded.**
- Floor paint specifications, Epoxy? **No, Latex floor paint will be used. Color to be TBD once contract is awarded.**
- Is a sprinkler head required in the new closet areas, if so will the school handle that directly? **School Department will be responsible for coordinating sprinkler needs once its determined if needed.**
- Height of the new doors. Schedule indicates 8'-0 high, floor plans indicate 6'-8". **Door height will be 6'-8".**
- Will the doors be painted or pre-finished clear? **All new door will be manufactured clear coated**
- Are the doors required to be 1 hour? **Yes.**
- Cove base states 6" in specifications and walk through determined 4". Please clarify. **4" cove base to be used and color to match existing base.**
- Do the existing holes in mason block need to be filled before painting? **Yes any existing hole will need to be filled and smooth before final painting.**
- Existing door and frames need to be painted? **Yes to existing doors. No for existing window frames.**

Bidders are to acknowledge Addendum 1 within their bid proposal. Failure to do so may subject a bidder to disqualification.

END OF ADDENDUM 1