



February 23, 2022

Barbara McMillan, Chair Portsmouth Conservation Commission 1 Junkins Ave, 3rd Floor Portsmouth, NH 03801

RE: Conservation Commission Submission for Wetland CUP & Rev 4 Plans 325 Little Harbor Road, Portsmouth, NH – Tax Map 205 Lot 2 Project #47099.01

Dear Ms. McMillan:

On behalf of our client, ADL 325 Little Harbor Road Trust, please find the recently updated plans, including revised utility design as part of the Wetland Conditional Use Permit (CUP) submission relative to the above-referenced project. The following materials have been submitted via ViewPoint and hard copies are also included in this submission:

- Wetland CUP Application (10 copies);
- Land Management Plan (10 copies); and
- Site Development Plans entitled "Site Development Plans, Tax Map 205 Lot 2, Lady Isle Site Renovations, 325 Little Harbor Road, Portsmouth New Hampshire", prepared by TFMoran, Inc., dated September 29, 2021, revised February 18, 2022 (1 copy at 22"x34"and 9 copies at 11"x17").

This project was reviewed by the Conservation Commission and approved in November 2021, however, will be returning to Conservation Commission for review since recent utility-related revisions to the original submission in September 2021. Also, although TAC review is not required for Single Family Residential Homes, we agreed to attend TAC, at the request of the Planning Department and DPW, to provide further details of the proposed utilities. These revised plans detail the utility runs to and from the island and their connection with utilities in Little Harbor Road and Sagamore Avenue.

Project Description

The project includes the replacement of a single-family residence on 325 Little Harbor Road. The existing property is approximately 12.3 acres and currently contains a 2-story house, guest cottage, carriage house, barn, horse barn, horse paddock, and shed. The site is an island within the Rural Zoning District and surrounded by the Piscataqua River.

Renovations are proposed within a previously disturbed area and will replace existing structures. The remaining half of the island, which is wooded, will be maintained or enhanced with natural vegetation.





Conservation Commission Submission for Wetland CUP & Rev 4 Plans 325 Little Harbor Road, Portsmouth, NH – Tax Map 205 Lot 2

February 23, 2022

No adverse impact on the wetland functional values of the site or surrounding properties are proposed. A Land Management Plan has been developed for the entire island to remove existing invasive species and restore the area, including the Buffer, with native species that will benefit the ecosystem around the Piscataqua River and enhance the existing ecology.

The project does not propose any permanent wetland impacts, only Tidal Wetland Buffer Impacts on the previously developed uplands of the island. Temporary impacts are proposed within the Tidal Piscataqua River to remove existing utilities, install utilities suspended beneath the bridge, and for temporary bridge reinforcement to allow construction vehicles to access the site.

The purpose of this proposal is to demolish the existing house, carriage house, and paddock and to construct a 2-story single-family home, garage, pool, pool cabana, playground, and utility connections via Little Harbor Road; renovate an existing barn and guest cottage; and replace an existing shed and barn with a new shed and barn. Associated improvements include and are not limited to access, grading, stormwater management systems, utilities, and landscaping. The project proposes a 6,227 SF main, housing footprint and total 34,700 SF of impervious area (7%) upon the island within the HOT (Highest Observable Tide) line. There is approximately 195,656 SF (58%) of impact area proposed within the 100' Tidal Wetland Buffer Zone of the island. Below is a table comparing existing and proposed coverages within both the Tidal Wetland Buffer Zone and Total Upland Area, within the lot area upon the island only:

TABLE 1 COVERAGE AREA (SF)							
	Exis	sting	Proposed				
	Tidal Wetland Buffer Zone	Total Island Area	Tidal Wetland Buffer Zone	Total Island Area			
Impervious Area	27,123 (8.0%)	51,371 (10.2%)	25,217 (7.5%)	34,700 (6.8%)			
Permeable Area	754 (0.3%)	754 (0.1%)	8,144 (2.4%)	13,224 (2.6%)			
Grass/Landscape Area	176,413 (52.3%)	245,920 (48.4%)	166,530 (49.4%)	254,665 (50.2%)			
Natural Woodland Area	132,911 (39.4%)	209,400 (41.3%)	137,310 (42.5%)	204,856 (40.4%)			
Total Area	337,201	507,445	337,201	507,445			
Impact Area			195,656 (58.0%)	289,971 (57.1%)			

Approximately half of the development is proposed within the 100' Tidal Wetland Buffer. The remaining half of the island is proposed to be left in its natural woodland state. Most of the impact area is in order to convert areas from pavement and grass, using mechanized equipment, to open space, such as landscape areas or drought-tolerant lawn, with the goal of establishing more vegetation. Alterations of woodland will occur only to the extent necessary to achieve construction goals.

The existing wetland buffer contains 132,911 SF (40%) of natural woodland area and will be enhanced to provide a total of 137,310 SF, accounting for 43% of the Buffer Zone. There will also be maintained landscaping added within the Buffer Zone, contributing 48,191 SF of landscape or meadow area that may have previously been grass or impervious surface, accounting for 14% of the Buffer Zone. All proposed landscape areas propose native vegetation within the Buffer. The combined woodland, lawn, landscaped, and permeable area accounts for 92% of the Buffer Area, permitting approximately 8% of the Buffer as impervious, primarily from roofs and the sea wall. The project includes a net removal of



Conservation Commission Submission for Wetland CUP & Rev 4 Plans 325 Little Harbor Road, Portsmouth, NH – Tax Map 205 Lot 2

February 23, 2022

16,671 SF of impervious surfaces, resulting in a net loss of impervious surface within a jurisdictional wetland buffer.

Utility Design

The existing utilities serving the residential island include water from Little Harbor Road via the Belle Isle Road, septic system, and overhead electric from Pleasant Point to the island. The intent is to remove the existing water, which is undersized for the proposed improvements and freezes likely due to improper insulation and burial depth. The septic system will be decommissioned and removed. Pending coordination with Eversource, the overhead electric utilities may be removed via Pleasant Point and replaced with underground.

All proposed utilities will be located along the existing driveway easement of Belle Isle Road, including 4" C900 PVC water service, 1.25" SDR 11 HDPE force main, 2" gas service, and underground electric/communication in 3" SCH40 PVC conduits. The utilities will conform to Portsmouth DPW and state standards. Proposed gas and sewer main utilities are available in Sagamore Avenue, and these services will be installed in either side of the grassed shoulder of Little Harbor Road. All impacts within the right of ways will be restored to original conditions.

Review and Approval

The project has been reviewed by TAC. The project will also be reviewed by Planning Board, NHDES Wetlands Bureau, NHDES Shoreland Program, NHDES Alteration of Terrain (AoT) Bureau, NH Fish & Game, NHDES Wastewater Bureau, and EPA's NOI for Construction General Permit.

We appreciate your consideration of these matters and look forward to presenting this project to you at the March 9^h Conservation Commission Meeting.

Respectfully, **TFMoran, Inc.**

Corey Colwell, LLC

Division Manager | Vice President

Hannah Giovannucci, PE Civil Project Manager

JCC/heg

cc: Anthony Dilorenzo, ADL 325 Little Harbor Road Trust (via e-mail)

Jim Youngblood, Youngblood Builders (via jim@youngbloodbuilders.com)

Bernie Lee, Severino Construction (via blee@severinotrucking.com)

Mickey Benson, GPSchafer (via mbenson@gpschafer.com)

Matthew Cunningham, MCLD (via matthew@matthew-cunningham.com)

Stephen Roberts, Hoefle, Phoenix, Gormley & Roberts (via sroberts@hpgrlaw.com)

2/23/2022

Conservation Commission & Planning Board Submission for Wetland CUP

Please revise the following to the form:

Land Use Application

LU-22-23

Your Submission

Attachments

Guests (0)

- Preliminary Application Review
- **⊘** Land Use Permit -- Planning Department Review and Fee Calculation
- Application Permit Fee

Land Use Code Review

Conservation Commission Review

Planning Board Conditional Use Permit (Wetlands) Approval

Land Use Conditions of Approval Review

Building Permit Issued

Your submission

Submitted Feb 15, 2022 at 4:45pm

Contact Information

Corey Colwell

Email address

ccolwell@tfmoran.com

Phone Number

603-431-2222

Mailing Address

170 Commerce Way, Portsmouth, NH 03801

Location

325 LITTLE HARBOR RD

Portsmouth, NH 03801



Applicant Information

Please indicate your relationship to this project * ?

B. Property Owner's Representative

Alternative Project Address

Alternative Project Address ?

--

Project Type

Addition or Renovation: any project (commercial or residential) that includes an ADDITION to an existing structure or a NEW structure on a property that already has structure(s) on it



New Construction: any project (commercial or residential) that involves adding a NEW structure on a parcel that is currently VACANT. If there are any existing structures on the property (even if you are planning to remove them), you should select Addition and Renovation above

--

Minor Renovation: for projects in the Historic District only that involve a minor exterior renovation or alteration that does not include a building addition or construction of a new structure

--

Home Occupation: residential home occupation established in an existing residential dwelling unit and regulated by the Zoning Ordinance. Home Occupations are not allowed in the following Zoning Districts: Waterfront Business, Office Research, Industrial, or Waterfront Industrial New Use/Change in Use: for a change of land use or an expansion to an existing use (e.g. addition of dwelling units) that includes no exterior work or site modifications Temporary Structure / Use: only for temporary uses (e.g. tents, exhibits, events) Demolition Only: only applicable for demolition projects that do not involve any other construction, renovation, or site work Subdivision or Lot Line Revision: for projects which involved a subdivision of land or an adjustment to an existing lot line Other Site Alteration requiring Site Plan Review Approval and/or Wetland Conditional Use Permit Approval Sign: Only applies to signs requiring approval from a land use board (e.g. Historic Commission, Zoning Board of Adjustment)

Request for Extension of Previously Granted Land Use Approval

--

Appeal of an Administrative Decision or Request for Equitable Waiver

--

Zoning Information

Base Zoning District

Rural Residential (R)

Base Zoning District 2 @

Historic District

Flood Plain District
Downtown Overlay District
Osprey Landing Overlay District
Airport Approach Overlay District
Waterfront Use Overlay District
Nauth Fad la cathius Overlay District
North End Incentive Overlay District
West End Incentive Overlay District
Highway Noise Overlay District
Application Type
Lot Line Revision (Planning Board)
Subdivision (Planning Board)

Amended Subdivision or Lot Line Revision Approval

--

Project Description

Equitable Waiver

Lot Area (s.f.)

535,990

Lot Area Source 2

__

Detailed Description of Proposed Work *

Replace an existing residential home; remove carriage house and paddock, construct new garage, pool, pool cabana, playground, utility connections; renovate existing barn and guest cottage, andreplace existing shed and barn. Assocaited improvements include and are not limited to access, grading, stormwater management systems, utilities, and landsaping improvements.

Brief Description of Existing Land Use * ? Residential

Land Use Application Fee Calculation

Area of disturbance in wetland or wetland buffer (s.f.)

--

Existing Buildings/Structures

Building / Structure Description	Total Gross Floor Area (s.f.)	Area of Footprint (s.f.)	
Residential Home	4,180	4,201	
Guest Cottage	2,056	1,300	
Barn	3,800	2,130	
Carriage House	1,982	1,982	
Horse Shed	467	467	
Shed	48	48	

Existing Yards, Coverage, Parking, and Wetlands

Principal Front Yard / Building Setback (ft) ?

--

Secondary Front Yard / Building Setback (ft) @

--

Rear Yard / Building Setback (ft) ?

Right Side Yard / Building Setback (ft) ?

Left Side Yard / Building Setback (ft) ?

Total # of Residential Units

Number of Parking Spaces

Number of Loading Spaces

--

Area of Surface Parking & Driveways (sq ft) 22,378 — 29,732

Other Impervious Surface Area (sq ft) ?

21,718 \(\)— 21,639


Is all or a portion of the property located in the wetland area and/or within 100' of the wetland boundary? $\ \ \ \ \$

 \mathbf{V}

Proposed Building/Structures (REQUIRED)

Building / Structure Description	Total Gross Floor Area (sq ft)	Area of Footprint (s.f.)	
Residential House	10,766	6,227	
Garage	2,212	1,475	
Guest Cottage	1,320	660	
Pool Cabana	368	368	
Shed	384	384	
Barn	3,882	2,806	

Building / Structure Description	Total Gross Floor Area (sq ft)	Area of Footprint (s.f.)	
Barn	722	722	
Additional Proposed Building In	formation		
Number of new hotel rooms			
 Total New Restaurant Use Gross F 	Floor Area		
Proposed Yards, Coverage, Park Principal Front Yard / Building Set		D)	
Secondary Front Yard / Building S 	Setback (ft) 3		
Rear Yard / Building Setback (ft) (•		
Right Side Yard / Building Setbac	ek (ft) 🛭		
Left Side Yard / Building Setback 	(ft) ?		
Total # of Residential Units ?			
Number of Parking Spaces ? 			
Number of Loading Spaces ?			



--

Tidal Wetland Total Area on Lot (Sq.Ft.) 389,213

Tidal Wetland Area to be Disturbed (Sq.Ft.) 195,656

Review by Independent Certified Wetland Scientist

I have read and understand the above information. I will pay any additional fees due as required.

--

Project Representatives

Relationship to Project	If you selected "Other", please state relationship to project.	Full Name (First and
Engineer		Hannah Giovannucci

Plan Submission

I understand that this application will not be considered complete until I have provided the required plans and any additional submission requirements. I also understand that any hard copies as required by the Planning Department are required to be submitted prior to the application deadline. (You will be prompted at the next screen to upload your plans.) *

 \mathbf{V}

I have reviewed the application requirements provided on the Planning Department's web page -- www.cityofportsmouth.com/planportsmouth/land-use-applications-forms-and-fees. *



Acknowledgement

I hereby certify that as the applicant for permit, I am * ?

Other

If you selected "Other" above, please explain your relationship to this project. Owner authorization is required.

Civil Engineer

I certify that the information given is true and correct to the best of my knowledge. *



I understand that I am responsible for paying any applicable application fees and that I will be invoiced separately for legal and abutter notification costs as well. *



Is this property under condominium ownership? ②

--

I understand that it is the obligation of the applicant to submit adequate documents, plans, and exhibits to demonstrate compliance with the Zoning Ordinance. *



By signing below, I agree that this is equivalent to a handwritten signature and is binding for all purposes related to this transaction. *

✓ Hannah Giovannucci Feb 15, 2022

INTERNAL USE -- Land Use Approvals Historic District Commission HDC Approval Granted Zoning Board of Adjustment **BOA Approval Granted** Zoning Relief Required **Conservation Commission Review** Conservation Commission Review Completed Conditional Use Permit (Wetlands) Wetland CUP Granted Conditional Use Permit (Other) Other CUP Granted

Design Review Phase

Prelim. Concept. Consultation

Prelim. Concept. Consultation Completed

Your Profile

Your Records (/dashboard/records)

Resources

Search for Records (/search)

Claim a Record (/claimRecord)

Employee Login (https://portsmouthnh.viewpointcloud.io)

Portal powered by **OpenGov**

Land Management Plan

A Narrative for Invasive Plant Management and Native Plant Restoration

325 Little Harbor Road, Portsmouth, NE

Fall 2021

PARTERRE ECOLOGICAL



Table of Contents

Introduction & Primary Goals	
Invasive Plant Inventory and Plan	2-5
Invasive Plant Management Techniques Descriptions of proposed Manual Removal and Herbicide Application Management Methods	6-8
Bittersweet and Vines Management Calendar	7 8
Native Plant Inventory and Restoration Inventory	9-11 9-10
Restoration planting plan Restoration strategies and species	11
Management and Maintenance Schedule	13
Invasive Species Descriptions	14-19
Identification and Qualifications of Applicant	20
Precedent Restoration Project Images	
	ję (

Introduction and Primary Goals

The Dilorenzo residence is located at 325 Little Harbor Road in Portsmouth. The 11-acre island lies near the mouth of the Piscataqua River and the majority of the site is within the 100' tidal river buffer. An inventory of existing native and invasive plant species can be found in this plan.

The primary goal of this plan is to seek approval from the Portsmouth Conservation Commission to offset home construction and landscape improvements within the 100' Tidal buffer. We propose to remove invasive species on site and to restore the area with native species that will benefit the ecosystem around Piscataqua Rive and reduce further incursion of invasive species on the island. An inventory of existing native and invasive plant species can be found in this plan.

We propose removing invasive species by low-impact manual hand methods and cut & dab herbicide application by licensed applicators. All invasive species greater than 1" in caliper will be cut and dabbed with herbicide to reduce the chance of erosion along the banks. All existing erosion will be stabilize and any soil disturbed during planting will be stabilized and seeded with native wildflower mix. Techniques are outlined in the report. After removal of invasive species we will restore with native shrubs and perennials that will help prevent resurgence of the invasive plants and enhance the existing ecology.



A mass of invasive Multiflora Rose along the edges of the horse paddock with maturing Black Swallowort pods hanging from the stem. The majority of the western portion of the island is healthy pine/oak forest, but invasives are dense in areas with historically high disturbance. We propose managing all invasive species and replacing with native alternatives.



325 Little Harbor Road Invasive Plant Inventory

Mature invasive species have developed isolated populations along the tidal river buffer and threaten to spread into an otherwise healthy native ecosystem. We propose controlling invasive plant species that have developed self sustaining populations on the Dilorenzo's property and restoring with native species. The physiology of the invasive plants has enabled them to out compete the native plant community and compromise the ecological value of the native plant community. The dominant invasive plants, including Multiflora Rose and Barberry, disrupt the formation of a native understory by filling ecological niches and resisting any browsing by native species. A very small Japanese Knotweed population exists near the southwestern corner of the paddock. It can spread quickly in coastal areas and should be managed before it can establish itself. All invasive perennials and shrubs with viable fruit will be removed from the site. Poison lvy is a native species with valuable ecological benefits. We propose control the and areas of human traffic.

Invasive Plant Species Identified:

Acer platanoides, Norway Maple
Alliaria petiolata, Garlic Mustard
Berberis thunbergii, Japanese Barberry
Celastrus orbiculatus, Asiatic Bittersweet
Cynanchum louiseae, Black Swallowort
Elaeagnus umbellata, Autumn Olive
Fallopia japonica, Japanese Knotweed
Frangula alnus, Glossy Buckthorn
Lonicera morrowii, Morrow's Honeysuckle
Rhamnus cathartica, Common Buckthorn
Rosa multiflora, Multiflora Rose

*Likely Invasive Plant Species Identified:

Artemisia vulgaris, Mugwort Deutzia scabra, Fuzzy Deutzia Ligustrum vulgaris, Common Privet Rhodotypos scandens, Jetbead Vitus sp., Grape (Native but control)

* While not listed as an Invasive Species by ISC (New Hampshire Invasive Species Committee) these species can dominate the shrub layer and crowd out native trees and shrubs. We recommend removal of along with listed invasive plant species in wetland buffers and replace with native shrubs and trees.



Black Swallowort releasing seedheads in the paddock. The majority of this area is a healthy goldenrod/blackberry meadow with patches of Milkweed, but Black Swallowort can establish itself quickly and releases compounds in the soil to limit its competitor. Without intervention there will likely be a large infestation.






MAP FOR REFERENCE ONLY NOT A LEGAL DOCUMENT

City of Portsmouth, NH makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented on this map.

Geometry updated 4/1/2019 Data updated 7/17/2019

Print map scale is approximate. Critical layout or measurement activities should not be done using this resource.







• • • Highest Observable tide line

Existing Pathways

325 Little Harbor Road Invasive Plant Images



Japanese Barberry with Deutzia and Black Swallowort at the edge of the forest



Garlic Mustard seedheads with Mugwort on the northern bank



Japanese Barberry with viable fruits



Autumn Olive in the open paddock



A single small population of Japanese Knotweed on site should be managed as soon as possible

325 Little Harbor Road

Invasive management techniques

We propose a combination of manual hand removal and cut & dab herbicide to control invasive plant species within the identified project areas over a phased time line. Once the initial identified invasive plant species have been removed by manual methods (described below), we propose seeding all exposed soil with native seed blend and begin planting identified tree, shrub and perennial plant species selected from the native plant community list that will increase the density and diversity of the existing wetland buffers.

Manual Hand Removal Methods:

Manual methods of invasive plant management will include hand pulling or cutting. To minimize soil disturbance, shallow-rooted invasive plants less than 1" in caliper will be hand pulled from the soil. Invasive plant species greater than 1" in diameter will be cut. All invasive plant material will be disposed of off site. Manual hand pulling and cutting will remove all invasive plants from the wetland buffer.

Cut and Dab and Foam application: All invasive plant species that have a base greater than 1" in caliper are proposed for herbicide application methods. Although invasive, the root systems of plants greater then 1" in caliper usually have extensive fibrous root systems, providing soil stabilization. So we propose a cut & dab method of application of a Triclopyr based herbicide (Garlon) or Glyphosate based herbicide approved for wetland use (trade name Rodeo) on individual cut stumps. Licensed Pesticide Applicators will complete all aspects of the proposed restoration. For treatment of perennial species that cannot be controlled with cut and dab or by manual methods should be treated by a foam based herbicide that is wiped onto the leaves using a cotton glove. This hyper-specific treatment limits any treatment of non-target plants. No treatment will occur in areas of standing water.



Qualified applicators with necessary Personal Protective Equipment paint the stems of invasive species after cutting



Proposed cut stump treatment (below) using hand tools and applying marking dye to eliminate possibility of treatment of stump twice, or missing stump entirely. (Above) Foam treatment allows highly specific placement of herbicide to remove invasive perennials that limits disturbance and protects surrounding species


325 Little Harbor Road Asiatic Bittersweet ID and Management


Invasive Bittersweet (*Celastrus orbiculatus*) have the capacity to girdle, weaken, and even kill mature canopy trees. Without some frequency of removal, they will eventually open large holes in the canopy while suppressing saplings from filling the holes. They readily resprout after being cut and can damage the aesthetic and ecological value of meadows.

Mature stems produce thousands of bright red berries that mature in late fall and are spread by birds.

Removing the entire vines from trees is often dangerous and unnecessary (unless it poses safety risk). Our team recommends making cuts at shoulder height followed by a cut at 12" and immediate herbicide treatment. Bittersweet aggressively suckers after cutting so it is important to cut and treat during or after its flowering period (late June to December).







325 Little Harbor Road Japanese Knotweed Management

Japanese Knotweed (Fallopia japonica) is one of the most difficult invasive species to control. Its main mode of spreading is through cut portions of its rhizomes or stem, which can actively resprout even when 1 inch in length. Growing 10-15' and shading out any competitors, Japanese Knotweed can quickly form a monoculture. It can take 2-5 seasons to fully contain through repeat herbicide treatments. It is at its weakest point during the flowering stage, when nutrients are flowing back into the roots (Aug, Sept.) Unfortunately, taproots can extend over 6' below the ground making organic eradication nearly impossible without excavation. There are two ways to approach treatment.

- Cut and treat: For smaller areas, involves cutting the stem between the 1st and 3rd node and adding a 66% solution of Aquaneat (glyphosate), generally 5 oz per treated stem. If density is less than 5 ft per plant treat every third stem. Do this for 2-5 seasons.
- Cut in May, wipe leaves in fall or apply to stem in fall: In this case, dense stands of Knotweed are mown in end of May so when they regrow they are at hip height by August. They can then be easily wiped with a 6.0% Aquaneat (glyphosate) solution





Identification: Herbaceous perennial, with long heart shaped leaves. Young sprouts can be red, rhubarb in nature. Extensive roots can spread and colonize quickly and can reach 15 ft. at maturity.








Japanese Knotweed cut in preparation for a fall herbicide foliar wipe treatment (top left). Treatment of Japanese Knotweed stems using a cut and fill method (above). A combination of cut and fill in the first season and foliar wipe in the second has shown to be effective. Foliar wipe can be accomplished by applying herbicide to a glove and wiping leaves or by utilizing a foaming agent to help herbicide stick to the leaves (left). It is a highly specific treatment with little risk of drift.

Management Calendar for Treatment and Planting

Task	March/ April	May	June	July	August	Sept.	Oct.	Nov.	Dec.
Remove Garlic Mustard and Lesser Celandine seedlings by hand or smothering									
Cutting of Japanese Knotweed									
Cut and dab of woody invasive species									
Treatment of Japanese Knotweed									
Invasive vine management and cut and dab treatment									
Restoration planting									
Treatment of Black Swallowort									
Mowing of meadows									






325 Little Harbor Road Native Plant Inventory

Within the tidal river buffer is a diverse native plant community dominated by mature Oaks and White Pines with Chokeberry, Black Cherry, Arrowood Viburnum, and lowbush Blueberry in the understory. In the sunnier areas is a wet meadow featuring Rough Goldenrod, Alleghaney Blackberry, Sumac, Common Rush and Elderberry. An occupied Belted Kingfisher nest was found during the site visits. We propose utilizing these existing native plant species as indicators of what naturally inhabits this plant community and propose additional planting of these species and diversifying with other native trees, shrubs and perennials.

Native Plant Species Identified:

Acer rubrum, Red Maple
Acer sacharinum, Sugar Maple
Aronia melanocarpa, Black Chokeberry
Betula populifolia, Gray Birch
Betula papyrifera, Paper Birch
Iva frutescens, Bigleaf Marsh-elder
Juncus tenuis, Path Rush
Juniperus virginiana, Eastern Red Cedar
Kalmia latifolia, Mountain Laurel
Myrica pensylvanica, Bayberry
Parthenocissus quinquefolia, Virginia Creeper
Pinus strobus, Eastern White Pine
Prunus virginana, Chokecherry

Toxicodendron radicans, Poison Ivy
Quercus alba, White Oak
Rosa virginiana, Virginia Rose
Rhus typhina, Staghorn Sumac
Rubus allegheniensis, Allegheny blackberry
Sambucus canadensis, Elderberry
Solidago bicolor, Silverrod
Solidago sempervirens, Sea-side Goldenrod
Solidago rugosa, Rough-leaved Goldenrod
Swida amonum, Silky Dogwood
Tilia americana, American Basswood
Vaccinium corymbosum, High-bush Blueberry
Viburnum dentatum, Arrowood Viburnum



Silverrod alongside Blue-stem Goldenrod and Carex. sp



Gray Birch along the bank

325 Little Harbor Road Invasive Plant Images





Staghorn Sumac along the banks with Arrowood Viburnum and Virginia Rose in the foreground




Marsh Elder along with Beechgrass line the western banks of the island












• • • • Highest Observable tide line









325 Little Harbor Road Native Restoration Strategies

After invasive plant species have been removed from the wetland buffer, the area will be planted with one to five gallon native conservation grade New England native trees, shrubs and perennials from local seed and cutting sources. It is proposed that native plants will have greater than 90% coverage by the conclusion of the 3 year Order of Conditions. Native plants proposed for installation will add diversity of existing native plants, provide habitat and forage for wildlife, and reduce storm water and sediment flow wetland areas. Plants proposed for installation include:

	Quantity	Size	Scientific name	Common name		
	4	3-4'	Amelanchier laevis	Shadblow Serviceberry		
	2	3-4'	Acer rubrum	Red Maple		
	12	3-4'	Aronia melanocarpa	Black Chokecherry		
	5	3-4'	Betula papyrifera [*]	Paper Birch		
	2	3-4'	Carpinus caroliniana	Ironwood		
Within 100'	44	3-4'	Clethra alnifolia	Summersweet		
	5	3-4'	Cornus amonum	Silky Dogwood		
Tidal River Buffer	12	3-4'	Cornus racemosa	Gray Dogwood		
	10	3-4'	Diervilla lonicera	Northern Bush Honeysuckle		
	18	3-4'	Hamamelis virginiana	Witchazel		
	9	3-4'	llex vertilicillata	Winterberry		
	2	3-4'	Juniperus virginiana	Eastern Red Cedar		
	24	3-4'	Myrica pennsylvatica	Bayberry		
	6	3-4'	Nyssa sylvatica	Black Tupelo		
	6	3-4'	Prunus virginiana	Chokecherry		
	3	3-4'	Prunus serotina	Black Cherry		
	7	3-4'	Quercus bicolor	Swamp White Oak		
	9	3-4'	Rhus typhina	Staghorn Sumac		
	16	3-4'	Rosa virginiana	Virginia Rose		

After planting the conservation grade native shrubs and trees and slope stabilizing perennials, we propose the area be seeded with a custom Dormant seed mix at recommended seeding rates. This dense seed mix will supply a matrix of vegetative growth to cover disturbed soils, and reduce recolonization of invasive plant species. These mixes include:

New England Showy New England Wildflower mix New England Understory Grass and Forb Mix



325 Little Harbor Road Maintenance Schedule

The recommendations for restoration take into consideration the long term health of the wetland. Once the invasive plant species have been managed in a locus area and any native plants installed, a long-term maintenance plan will be set in motion with the goal of continued control of invasive plant species on site, serve, and sustain native plant populations, and improve the native plant diversity and aesthetic beauty of the wetland.

Fall - Winter 2021

- Complete invasive species management of Buckthorn and woody invasive plant species by cut and dab methods
- Identify and manually hand-pull identified invasive shrubs and vines under 1' in caliper
- Cover all disturbed soil along with native seed mix

Winter 2021-Spring 2022

- Continue utilizing control methods of invasive plant management to exhaust seed bank
- Begin planting native plant species according to approved quantities and varieties
- Monitor plant response and continue hand pulling and herbicide application methods on re sprouting invasive plant species
- Cover exposed soils Conservation seed mix

Summer 2022

- Cut and dab/Foam application to Japanese Knotweed and remaining invasive shrub and tree species
- Continue utilizing control methods of invasive plant management to exhaust seed bank
- Continue planting native plant species according to approved quantities and varieties

Fall 2022 - Summer 2023

- Monitor plant response and continue hand pulling and herbicide application methods on re sprouting invasive plant species
- Followup treatment of Japanese Knotweed (Mowing in spring, treating in fall)
- Cover exposed soils Conservation seed mix
- Monitor native species for plant health

Ongoing Maintenance and Monitoring:

- After the treatments of fall 2023, the management plan should be re-evaluated. If
 management treatments have been successful, only monitoring and minimal hand removal
 should be required to keep invasive plant species from being reintroduced. Native trees,
 shrubs, and herbaceous forbs should dominate the wetland buffer.
- Implementation of the LMP should be completed by qualified professionals including:

NH Licensed pesticide applicator

Certified Massachusetts/NH Invasive Species Management

MCH Massachusetts Certified Horticulturist

 Monitoring reports shall be submitted to conservation at the end of each growing season indicating invasive species management efforts and establishment of the restoration plantings.







Bittersweet

Description:

Celastrus orbiculatus, Asiatic Bittersweet is a deciduous climbing vine common in areas of disturbance in our New England forests. It has glossy, rounded leaves that are alternate with finely toothed margins. The leaves turn yellow in the fall. The fruiting plants produce small greenish flower clusters from leaf axils that mature in fall to produce high numbers of fruiting seed. The seed are noticeably yellow, globular capsules that split open at maturity to reveal red-orange fruiting seeds. Roots are also distinctly orange.

Habitat:

Bittersweet spreads easily into forest edges, woodlands, unmanaged meadows and old fields. Most disturbed sites that are not being actively managed that receive full sun are susceptible. The vine can tolerate shade but is often found in more open, sunny areas.

Management:

Asiatic Bittersweet management is a combination of manual hand pulling with cut & dab herbicide treatments. For established plants, vines should be cut to ground to reduce mass. Persistent root infestations will require repeat cutting and treatments over several seasons. Rake any seeds present, bagging in plastic bags, tying, and disposing of correctly.

Celastrus orbiculatus, Asiatic Bittersweet





Honeysuckle

Description:

Lonicera morrowii, Morrow's honeysuckles are upright, deciduous shrubs that typically have a multi-stem mounding appearance. Oval leaves are opposite along the stem with smooth edges (no teeth or lobes) and hairy on the underside. Mature stems are often hollow on the interior and peeling on the outer bark. In the spring pairs of fragrant, tubular flowers less than an inch long are borne along the stem in the leaf axils. The fruits are red to orange, and fleshy.



Habitat:

Honeysuckles are relatively shadeintolerant and most often occur in forest edges, abandoned fields, and other open, upland habitats. Woodlands and open meadows, especially those that have been grazed or otherwise disturbed and are left unmanaged are also highly susceptible. Morrow's Honeysuckle have the greatest habitat diversity and are capable of invading wetland edges and other uncommon habitat types.



Management:

Morrows Honeysuckle management is a combination of mechanical mowing and manual hand pulling with cut and dab herbicide treatments. When feasible, the root system is generally shallow and plants can be uprooted easily. Persistent root re sprouting may require repeat cutting with herbicide application over several seasons to fully control.

Lonicera morrowii, Morrow's Honeysuckle









Buckthorn

Description:

Frangula alnus, Glossy Buckthorn is a deciduous shrub that grows up to 20 ft.. tall. The oblong leaves are up to 2" long, arranged alternately along the stem and are dark green on the surface, glossy above and slightly pubescent beneath. The leaves turn yellow in the fall, and remain on the plant when most other species have already lost their leaves. The yellow-green flowers are arranged in 1-8 flowered sessile, glabrous umbels. This plant flowers after the leaves expand, from May to September . The fruit ripen from red to black July to August.

Habitat:

Buckthorn thrives in early successional habitat. Abandoned agricultural or pasture lands, an opening in canopy within woodland, or unmanaged meadows are common areas. Buckthorn will also tolerate wetland soils where it can form dense stands that suppress the growth of native plant species. The seed is readily dispersed by birds, and the extended productivity of the fruit into winter allows the plant to be dispersed through the entire season.

Management:

Manual methods of hand-pulling seedlings is recommended. For larger saplings, a 'Weed Wrench' is effective. Mature Buckthorn can also be cut and the stump application of Triclopyr based herbicide. Rake any seeds present, bagging and disposing of correctly.

Frangula alnus, Glossy buckthorn





Multiflora Rose

Description:

Rosa multiflora, Multiflora Rose is a shrub with arching canes with a mounding shape in the landscape. The leaves are divided into five to eleven sharply toothed leaflets. The base of each leaf stalk has a pair of fringed bracts which is a key identifier of the plant from other wild rose. Beginning in early summer, clusters of showy white flowers appear. The flowers are followed by developing red fruit, or hips, during the summer that remain on the plant through the winter.



Habitat:

Multiflora Rose thrives in early successional habitat. The rose has a wide tolerance for various soil, moisture, and light conditions. It occurs in dense woods, along river banks and roadsides and in open unmanaged fields. It can form a dense understory that suppresses growth of native plant species. The seed is readily dispersed by birds, and the extended productivity of the fruit into winter months allows wide spread distribution of the plant.



Management:

Manual methods of hand-pulling seedlings is effective. For more established shrubs, a combination of pruning to reduce mass followed by cut & dab treatments with a Triclopyr based herbicide is recommended. Persistent root infestations may require repeat cutting over several seasons. Rake any seeds present, bagging and disposing of correctly.

Rosa multiflora, Multiflora rose



IDENTIFICATION AND QUALIFICATION OF APPLICANT

This plan has been developed by Miles H. Connors, Director of Ecological Services at Parterre Ecological, a division of Parterre Garden Services. Parterre Ecological Services provides Land Management Planning, expert Invasive Plant Management services, Native Plant Restoration strategies, and ongoing Maintenance and Monitoring in natural area restorations.

PLAN AUTHOR AND QUALIFICATIONS

Miles Hilton Connors Director of Ecological Services mconnors@parterreecological.com

Parterre Garden Services 67 Smith Place, unit 12A Cambridge MA 12138

Miles holds an Bachelor of Science degree in Environmental Planning and Policy and Biology, with a Masters of Science in Sustainable Landscape Planning and Design. Miles is also a Massachusetts Certified Horticulturist, holds an Invasive Plant Certification from UMASS Amherst and is a Licensed Pesticide Applicator.

Members of the Parterre Ecological team are licensed Massachusetts Pesticide Applicators, are Massachusetts Certified Horticulturists and hold an Invasive Plant Certification from UMASS Amherst.





1. Existing Conditions - Client under an enforcement order to restore buffer after tree & shrub removal and hydroseeding turf



2. After installation of sediment control, we mechanically mowed area and seeded with New England Conservation and Wildlife Seed Mix



3. Covered exposed loam with straw erosion control blanket: BioNet S75BN and staple into existing slope



4. Layout native plant species suitable for an Oak Hickory Forest plant community



5. Native plant species installed: Quercus rubra, Kalmia latifolia, Ostrya virginiana, Corylus americana, Betula lenta, Fagus grandiflora and Viburnum acerfolium



RESOURCE LIST

PORTSMOUTH, NH 03801

PLANNING/ZONING DEPARTMENT 1 JUNKINS AVENUE

PORTSMOUTH, NH 03801 603-610-7296 BEVERLY ZENDT, PLANNING DIRECTOR

BUILDING DEPARTMENT

I JUNKINS AVENUE PORTSMOUTH, NH 03801 603-610-7261 ROBERT MARSILIA, CHIEF BUILDING INSPECTOR

PUBLIC WORKS 680 PEVERLY HILL ROAD PORTSMOUTH, NH 03801 603-427-1530 PETER RICE,

DIRECTOR OF PUBLIC WORKS POLICE DEPARTMENT

3 JUNKINS AVENUE PORTSMOUTH, NH 03801 603-427-1500 MARK NEWPORT, INTERIM CHIEF

FIRE DEPARTMENT 170 COURT STREET PORTSMOUTH, NH 03801 603-427-1515 TODD GERMAIN, CHIEF

ASSOCIATED PROFESSIONALS

ARCHITECT G.P. SCHAFER ARCHITECT, PLLC 19 UNION SQUARE WEST, 4TH FLOOR NEW YORK CITY, NY 10003 212-965-1355 MICKEY BENSON, PRINCIPAL

ECOLOGICAL SERVICES PARTERRE ECOLOGICAL 67 SMITH PLACE, UNIT 12A CAMBRIDGE, MA 02138 617-482-2230 RYAN CORRIGAN, MSED, MCH

LANDSCAPE ARCHITECT MATTHEW CUNNINGHAM LANDSCAPE ARCHITECTURE DESIGN LLC 411 MAIN STREET STONEHAM, MA 02180 617-905-2246 MATTHEW CUNNINGHAM, PRINCIPAL

WETLAND SCIENTIST MARC JACOBS, CERTIFIED WETLAND SCIENTIST PO BOX 417 GREENLAND, NH 603-686-5097

WILDLIFE ASSESSOR GZA GEOENVIRONMENTAL, INC. 5 COMMERCE PARK NORTH BEDFORD, NH 03110 603-232-8739 TRACY TARR, ASSOCIATE PRINCIPAL

LADY ISLE SITE RENOVATIONS

325 LITTLE HARBOR ROAD PORTSMOUTH, NEW HAMPSHIRE

SEPTEMBER 29, 2021 REVISED FEBRUARY 18, 2022



NEW HAMPSHIRE FISH AND GAME AOT PERMIT CONDITIONS RELATED TO THREATENED AND ENDANGERED SPECIES

- ALL OBSERVATIONS OF THREATENED OR ENDANGERED SPECIES SHALL BE REPORTED IMMEDIATELY TO THE NEW HAMPSHIRE FISH AND GAME DEPARTMENT NONGAME AND ENDANGERED WILDLIFE ENVIRONMENTAL REVIEW PROGRAM BY PHONE AT 603-271-2461 AND BY EMAIL AT NHFGREVIEW@WILDLIFE.NH.GOV. EMAIL SUBJECT LINE: NHB21-3751, LADY ISLE SITE RENOVATIONS, WILDLIFE SPECIES OBSERVATION. PHOTOGRAPHS SHALL BE PROVIDED FOR VERIFICATION AS
- THE NEW HAMPSHIRE FISH AND GAME DEPARTMENT SHALL HAVE ACCESS TO THE PROPERTY
- DURING THE TERM OF THE PERMIT. ALL MANUFACTURED EROSION AND SEDIMENT CONTROL PRODUCTS, UTILIZED FOR, BUT NOT LIMITED TO SLOPE PROTECTION, RUNOFF DIVERSION, SLOPE INTERRUPTION, PERIMETER CONTROL, AND INLET PROTECTION, CHECK DAMS, SEDIMENT TRAPS, AND SILT FENCE INSTALLED IN ACCORDANCE WITH ENV-WQ 1506.04, SHALL NOT CONTAIN WELDED PLASTIC, PLASTIC, OR MULTI-FILAMENT OR MONOFILAMENT POLYPROPYLENE NETTING OR MESH.
- PRIOR TO CONSTRUCTION, MARSH ELDER SHALL BE IDENTIFIED, FLAGGED, AND SURROUNDED WITH ORANGE CONSTRUCTION FENCING WITH YELLOW CAUTION TAPE FOR PROTECTION OF THE SPECIES. DO NOT REMOVE, MOW, TRAMPLE, COVER, OR OTHERWISE HARM THE PLANT, REMOVE FLAGS AND CONSTRUCTION FENCING AND CAUTION TAPE AFTER CONSTRUCTION IS COMPLETED.



- SHRUBBY PERENNIAL HERB 2 TO 4 FT TALL, WITH THICKISH, OPPOSITE LEAVES AND SMALL GREENISH-WHITE CAPITULA, EACH WITH 5-6 MINUTE TUBULAR-SHAPED FLOWERS
- EACH CLUMP CONSISTS OF FROM 10 TO 100 OR MORE STEMS FROM A SINGLE WOODY BASE

OCCURS NEAR THE HIGH TIDE LINE IN A FEW SMALL, SCATTERED **MARSH ELDER** POPULATIONS.

Copyright 2022 ©TFMoran, Inc.

48 Constitution Drive, Bedford, N.H. 03110 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of homas F. Moran, Inc.

THESE PLANS ARE PERMIT DRAWINGS ONLY AND HAVE NOT BEEN DETAILED FOR CONSTRUCTION OR BIDDING.

INDEX OF CHEETS

	INDEX OF SHEETS
SHEET	SHEET TITLE
C-00	COVER
C-01	NOTES & LEGEND
S-01	EXISTING CONDITIONS PLAN
C-02	NHDES AMENDED SHORELANDS PERMIT IMPACT PLAN
C-03	NHDES AMENDED WETLANDS PERMIT IMPACT PLAN
C-04	WETLAND CONDITIONAL USE PERMIT PLAN
C-05	OVERLAY PLAN
C-06 TO C-07	SITE PREPARATION & DEMOLITION PLAN
C-08 TO C-09	SITE LAYOUT PLAN
C-10	GRADING & DRAINAGE PLAN
C-11 TO C-12	UTILITY PLAN
C-13 TO C-14	DRIVEWAY GRADING & PROFILE
C-15 TO C-17	SEWER PROFILE
C-18	EROSION CONTROL PLAN
C-19	EROSION CONTROL NOTES
C-20 TO C-26	DETAILS
REFERENCE PLANS BY	ASSOCIATED PROFESSIONALS
_	FLOOR & EXTERIOR ELEVATIONS PLANS BY G.P. SCHAFER
L1.0 TO L1.4	LANDSCAPE ARCHITECTURE PLANS BY MCLD

PERMITS/APPROVALS

	NUMBER	APPROVED	EXPIRES
PORTSMOUTH PLANNING BOARD & CONSERVATION COMMISSION WETLAND CUP	_	-	-
PORTSMOUTH PLANNING BOARD CUP FOR DADU	LU-21-220	1/27/2022	1/27/2023
NH FISH & GAME	_	_	-
NHDES WETLANDS & PERMIT AMENDMENT	2014-02662	2/15/2018 -	2/15/2023
NHDES SHORELAND & PERMIT AMENDMENT	2017-02665	2/26/2018 -	2/26/2023
NHDES ALTERATION OF TERRAIN	_	_	_
NHDES SEWER	_	_	_
EPA NPDES ENOI CGP & SWPPP	_	_	_

APPROVED BY THE CITY OF PORTSMOUTH PLANNING BOARD

BOARD MEMBER BOARD MEMBER

SITE DEVELOPMENT PLANS

TAX MAP 205 LOT 2

COVER

LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR

ADL 325 LITTLE HARBOR ROAD TRUST

SCALE: NTS

DR CK

3 2/15/2022 REVISED PER NHDES & UTILITIES PER TAC

1 | 11/23/2021 | REVISED PER NHDES & PROJECT COORDINATION | HEG JCC

DESCRIPTION

2 2/2/2022 REVISED PER NHDES & UPDATE SURVEY/UTILIT

REV. DATE


SEPTEMBER 29, 2021




Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects

| 170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com Scientists

DR HEG FB C - 00





BOTTOM OF SLOPE

CONDITIONAL USE PERMIT

DETACHED ACCESSORY DWELLING UNIT

All rights reserved. These plans and materials may not be copied,

without the prior written permission of Thomas F. Moran, Inc.

luplicated, replicated or otherwise reproduced in any form whatsoever

This plan is not effective unless signed by a duly authorized officer of

BOTTOM OF WALL

CONCRETE

48 Constitution Drive, Bedford, N.H. 03110

Copyright 2022 ©TFMoran, Inc.

homas F. Moran, Inc.

COORDINATE

BW

CONC

COORD

LENGTH

MAXIMUM

MINIMUM

LSA

MAX

LINEAR FEET

LANDSCAPE AREA

NOW OR FORMERLY

R&R

REM

RET

RIM

ROW

TYP

UG

REMOVE AND RESET

TEMPORARY BENCHMARK

RIM FI FVATION

RIGHT OF WAY

SQUARE FFF1

TOP OF CURB

TOP OF WALL

UNDERGROUND

SIDEWALK

TEST PIT

TYPICAL

WITH

REMOVE

RETAIN

SLOPE

F&G

FES

FΜ

HDPE

НН

HW

HYD

OCS

PVC

RCP

RD

SMH

SOS

TSV

FRAME AND GRATE

MECHANICAL JOINT

FORCE MAIN

HANDHOLE

HEADWALL

ROOF DRAIN

UTILITY POLF

SEWER MANHOLE

HYDRANT

FLARED END SECTION

HIGH DENSITY POLYETHYLENE PIPE

OUTLET CONTROL STRUCTURE

POLYVINYL CHLORIDE PIPE

SEDIMENT OIL SEPARATOR

TAPPING SLEEVE, VALVE, AND BOX

REINFORCED CONCRETE PIPE

GENERAL NOTES

- 1. THESE PLANS ARE PERMIT DRAWINGS ONLY AND HAVE NOT BEEN DETAILED FOR CONSTRUCTION OR BIDDING.
- 2. THESE PLANS WERE PREPARED UNDER THE SUPERVISION OF A LICENSED PROFESSIONAL ENGINEER. TFMORAN, INC. ASSUMES NO LIABILITY AS A RESULT OF ANY CHANGES OR NON-CONFORMANCE WITH THESE PLANS EXCEPT UPON THE WRITTEN APPROVAL OF THE
- 3. THE SITE LAYOUT PLAN SHALL BE RECORDED IN THE ROCKINGHAM COUNTY REGISTRY OF
- 4. ALL IMPROVEMENTS SHOWN ON THE SITE PLAN SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES SHALL BE MADE TO THIS SITE PLAN WITHOUT THE EXPRESS APPROVAL OF THE PORTSMOUTH PLANNING DIRECTOR.
- 5. ALL WORK SHALL CONFORM TO THE APPLICABLE REGULATIONS AND STANDARDS OF THE CITY OF PORTSMOUTH, AND SHALL BE BUILT IN A WORKMANLIKE MANNER IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. ALL WORK TO CONFORM TO CITY OF PORTSMOUTH DEPARTMENT OF PUBLIC WORKS STANDARD SPECIFICATIONS. ALL WORK WITHIN THE RIGHT-OF-WAY OF THE CITY AND/OR STATE SHALL COMPLY WITH APPLICABLE STANDARDS. COORDINATE ALL WORK WITHIN THE RIGHT-OF-WAY WITH APPROPRIATE CITY, COUNTY, AND/OR STATE AGENCY.
- 6. THE SITE CONTRACTOR SHALL ENSURE THAT ALL WORK IS PERFORMED IN ACCORDANCE WITH APPLICABLE SECTIONS OF ENV-WQ 1500. THE SITE CONTRACTOR SHALL NOTIFY THE ENGINEER IN ADVANCE OF CONSTRUCTION OF EACH STORMWATER FACILITY TO COORDINATE REQUIRED INSPECTIONS. THE CONTRACTOR SHALL TAKE PROGRESS PHOTOS DURING CONSTRUCTION OF ALL STORMWATER DRAINAGE COMPONENTS AND SEND TO THE ENGINEER.
- 7. SEE EXISTING CONDITIONS PLAN FOR THE HORIZONTAL AND VERTICAL DATUM.
- 8. SEE EXISTING CONDITIONS PLAN FOR BENCHMARK INFORMATION. VERIFY TBM ELEVATIONS PRIOR TO CONSTRUCTION.
- 9. CONTACT EASEMENT OWNERS PRIOR TO COMMENCING ANY WORK WITHIN THE EASEMENTS. 10. PRIOR TO COMMENCING ANY SITE WORK, ALL LIMITS OF WORK SHALL BE CLEARLY MARKED
- IN THE FIELD. 11. SITE WORK SHALL BE CONSTRUCTED FROM A COMPLETE SET OF PLANS, NOT ALL FEATURES
- ARE DETAILED ON EVERY PLAN. THE ENGINEER IS TO BE NOTIFIED OF ANY CONFLICT WITHIN
- 12. TFMORAN, INC. ASSUMES NO LIABILITY FOR WORK PERFORMED WITHOUT AN ACCEPTABLE PROGRAM OF TESTING AND INSPECTION AS APPROVED BY THE ENGINEER OF RECORD.
- 13. TEMPORARY FENCING SHALL BE PROVIDED AND COVERED WITH A FABRIC MATERIAL TO CONTROL DUST MITIGATION.
- 14. ALL DEMOLITION SHALL INSURE MINIMUM INTERFERENCE WITH ROADS, STREETS, WALKWAYS, AND ANY OTHER ADJACENT OPERATING FACILITIES. PRIOR WRITTEN PERMISSION FROM THE OWNER/DEVELOPER AND LOCAL PERMITTING AUTHORITY IS REQUIRED IF CLOSURE/OBSTRUCTIONS TO ROADS, STREET, WALKWAYS, AND OTHERS IS DEEMED NECESSARY. CONTRACTOR TO PROVIDE ALTERNATE ROUTES AROUND CLOSURES/OBSTRUCTIONS PER LOCAL/STATE/FEDERAL REGULATIONS.

15. ALL DEMOLITION AND RENOVATION OF STRUCTURES SHALL COMPLY WITH ENV-A 1800 FOR ASBESTOS MANAGEMENT AND CONTROL.

- 16. REFER TO ARCHITECTURAL PLANS FOR LAYOUT OF BUILDING FOUNDATIONS AND CONCRETE ELEMENTS WHICH ABUT THE BUILDING SUCH AS STAIRS, SIDEWALKS, LOADING DOCK RAMPS, PADS, AND COMPACTOR PADS. DO NOT USE SITE PLANS FOR LAYOUT OF FOUNDATIONS.
- 17. IN THE EVENT OF A CONFLICT BETWEEN PLANS, SPECIFICATIONS, AND DETAILS, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY FOR CLARIFICATION.
- 18. IF CONDITIONS AT THE SITE ARE DIFFERENT THAN SHOWN ON THE PLANS, THE ENGINEER SHALL BE NOTIFIED PRIOR TO PROCEEDING WITH THE AFFECTED WORK.
- 19. CONTRACTOR'S GENERAL RESPONSIBILITIES:
- A. BID AND PERFORM THE WORK IN ACCORDANCE WITH ALL LOCAL, STATE, AND NATIONAL CODES, SPECIFICATIONS, REGULATIONS, AND STANDARDS AND CONDITIONS OF ALL PROJECT-SPECIFIC PERMITS AND APPROVALS AS LISTED ON THE COVER SHEET TO THESE PLANS OR OTHERWISE REQUIRED.
- B. NOTIFY ENGINEER IN WRITING OF ANY DISCREPANCIES OF PROPOSED LAYOUT AND/OR EXISTING FEATURES.
- C. EMPLOY A LICENSED SURVEYOR TO DETERMINE ALL LINES AND GRADES AND LAYOUT OF SITE ELEMENTS AND BUILDINGS.
- D. THE CONTRACTOR SHALL BE RESPONSIBLE TO BECOME FAMILIAR WITH THE SITE AND ALL SURROUNDING CONDITIONS. THE CONTRACTOR SHALL ADVISE THE APPROPRIATE AUTHORITY OF INTENTIONS AT LEAST 48 HOURS IN ADVANCE.
- E. TAKE APPROPRIATE MEASURES TO REDUCE, TO THE FULLEST EXTENT POSSIBLE, NOISE, DUST, AND UNSIGHTLY DEBRIS. CONSTRUCTION ACTIVITIES SHALL BE CARRIED OUT BETWEEN THE HOURS IN ACCORDANCE WITH THE APPLICABLE MUNICIPAL ORDINANCES AND REGULATIONS OF THE CITY OF PORTSMOUTH.
- F. MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY WORK AT ALL TIMES.
- G. IN ACCORDANCE WITH RSA 430:53 AND AGR 3800, THE CONTRACTOR SHALL NOT TRANSPORT INVASIVE SPECIES OFF THE PROPERTY, AND SHALL DISPOSE OF INVASIVE SPECIES ON-SITE IN A LEGAL MANNER.
- H. COORDINATE WITH ALL UTILITY COMPANIES AND CONTACT DIGSAFE (811 OR 888-344-7233) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION.
- I. PROTECT NEW AND EXISTING BURIED UTILITIES DURING INSTALLATION OF ALL SITE ELEMENTS. DAMAGED UTILITIES SHALL BE REPAIRED OR REPLACED AT NO ADDITIONAL
- J. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MEANS AND METHODS OF CONSTRUCTION AND FOR CONDITIONS AT THE SITE. THESE PLANS, PREPARED BY TFMORAN, INC., DO NOT EXTEND TO OR INCLUDE SYSTEMS PERTAINING TO THE SAFETY OF THE CONSTRUCTION CONTRACTOR OR THEIR EMPLOYEES, AGENTS, OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE SEAL OF THE SURVEYOR OR ENGINEER HEREON DOES NOT EXTEND TO ANY SUCH SAFETY SYSTEMS THAT MAY NOW OR HEREAFTER BE INCORPORATED INTO THESE PLANS. THE CONSTRUCTION CONTRACTOR SHALL PREPARE OR OBTAIN THE APPROPRIATE SAFETY SYSTEMS WHICH MAY BE REQUIRED BY THE US OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) AND/OR LOCAL REGULATIONS.
- K. WRITTEN DIMENSIONS HAVE PRECEDENCE OVER SCALED DIMENSIONS. THE CONTRACTOR SHALL USE CAUTION WHEN SCALING REPRODUCED PLANS. IN CASE OF CONFLICT BETWEEN THIS PLAN SET AND ANY OTHER DRAWING AND/OR SPECIFICATION, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY FOR CLARIFICATIONS.
- L. VERIFY LAYOUT OF PROPOSED BUILDING FOUNDATIONS WITH ARCHITECT AND THAT PROPOSED FOUNDATION MEETS PROPERTY LINE AND WETLAND SETBACKS PRIOR TO COMMENCING ANY FOUNDATION CONSTRUCTION.
- M. PROVIDE AN AS-BUILT PLAN AT THE COMPLETION OF THE PROJECT TO THE PLANNING DIRECTOR AND PER CITY REGULATIONS.
- N. IF ANY DEVIATIONS FROM THE APPROVED PLANS AND SPECIFICATIONS HAVE BEEN MADE, THE SITE CONTRACTOR SHALL PROVIDE AS-BUILT DRAWINGS STAMPED BY A LICENSED SURVEYOR OR QUALIFIED ENGINEER ALONG WITH A LETTER STAMPED BY A QUALIFIED ENGINEER DESCRIBING ALL SUCH DEVIATIONS. AND BEAR ALL COSTS FOR PREPARING AND FILING ANY NEW PERMITS OR PERMIT AMENDMENTS THAT MAY BE

GENERAL NOTES (CONTINUED)

- 19. CONTRACTOR'S GENERAL RESPONSIBILITIES (CONTINUED):
- O. THIS PROJECT IS SUBJECT TO THE AOT PERMIT LISTED ON THE COVER SHEET. THE CONTRACTOR SHALL CONFORM TO ALL CONDITIONS OF THE PERMIT AND PROVIDE THE FOLLOWING DOCUMENTATION TO OWNER AND ENGINEER:
- 1) ADVANCE WRITTEN NOTICE AT LEAST ONE WEEK PRIOR TO COMMENCING ANY WORK UNDER THE PERMIT.
- 2) IF ANY UNDERGROUND DETENTION SYSTEMS, INFILTRATION SYSTEMS, OR FILTERING SYSTEMS WERE INSTALLED, FOR EACH SUCH SYSTEM:
 - A) REPRESENTATIVE PHOTOGRAPHS OF THE SYSTEM AFTER COMPLETION
 - BUT PRIOR TO BACKFILLING; AND B) A LETTER SIGNED BY A QUALIFIED ENGINEER WHO OBSERVED THE
- APPROVED PLANS AND SPECIFICATIONS. 3) UPON COMPLETION OF CONSTRUCTION, WRITTEN CERTIFICATION THAT:
 - A) ALL WORK UNDER THE PERMIT HAS BEEN CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS. B) IF ANY DEVIATIONS FROM THE APPROVED PLANS WERE MADE, WRITTEN

DESCRIPTIONS AND AS-BUILT DRAWINGS OF ALL SUCH DEVIATIONS,

SYSTEM PRIOR TO BACKFILLING, THAT THE SYSTEM CONFORMS TO THE

- STAMPED BY A QUALIFIED ENGINEER, SHALL BE PROVIDED. 20. PURSUANT TO PORTSMOUTH PLANNING BOARD DADU CUP APPROVAL ON 1/27/2022, THE
- APPROVED DADU SHALL BE THE ONLY ACCESSORY DWELLING UNIT ON THE PROPERTY. AN AFFIDAVIT STATING THIS HAS BEEN RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF

GRADING & DRAINAGE NOTES

CONSIDERED FOR PAYMENT AFTER EARTHWORK HAS COMMENCED.

AND LOCATION OF ALL BUILDING SERVICES.

- 1. THE CONTRACTOR SHALL ENSURE THAT ALL WORK IS PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF NHDES ENV-WQ 1500 AS APPLICABLE.
- 2. THE CONTRACTOR SHALL PREPARE, MAINTAIN, AND EXECUTE A S.W.P.P.P. IN ACCORDANCE
- WITH EPA REGULATIONS AND THE CONSTRUCTION GENERAL PERMIT.
- 3. THE CONTRACTOR SHALL COORDINATE WITH THE OWNER TO SUBMIT AN eNOI AT LEAST 14 DAYS IN ADVANCE OF ANY EARTHWORK ACTIVITIES AT THE SITE.
- 4. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CHECK THE ACCURACY OF THE TOPOGRAPHY AND REPORT ANY DISCREPANCIES TO THE ENGINEER PRIOR TO ANY EARTHWORK BEING PERFORMED ON THE SITE. NO CLAIM FOR EXTRA WORK WILL BE
- 5. THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR INFORMATION ABOUT SOIL AND GROUNDWATER CONDITIONS. THE CONTRACTOR SHALL FOLLOW THE GEOTECHNICAL ENGINEER'S RECOMMENDED METHODS TO ADDRESS ANY SOIL AND GROUNDWATER ISSUES THAT ARE FOUND ON SITE, INCLUDING AND NOT LIMITED TO DEWATERING METHODS, PERIMETER DRAINS AND TIE INTO STORMWATER MANAGEMENT SYSTEM, ETC.
- 6. COORDINATE WITH GEOTECHNICAL/STRUCTURAL PLANS FOR SITE PREPARATION AND OTHER BUILDING INFORMATION.
- 7. COORDINATE WITH ARCHITECTURAL PLANS FOR DETAILED GRADING AT BUILDING, AND SIZE
- 8. COORDINATE WITH MECHANICAL AND PLUMBING PLANS FOR ROOF DRAIN INFORMATION.
- 9. LIMITS OF WORK ARE SHOWN AS APPROXIMATE. THE CONTRACTOR SHALL COORDINATE ALL WORK TO PROVIDE SMOOTH TRANSITIONS. THIS INCLUDES GRADING, PAVEMENT, CURBING, SIDEWALKS, AND ALIGNMENTS.
- 10. THE CONTRACTOR SHALL PROVIDE A FINISH PAVEMENT SURFACE FREE OF LOW SPOTS AND PONDING AREAS. CRITICAL AREAS INCLUDE BUILDING ENTRANCE, RAMPS, AND LOADING
- 11. THE SITE SHALL BE GRADED SO ALL FINISHED PAVEMENT HAS POSITIVE DRAINAGE AND SHALL NOT POND WATER DEEPER THAN 1/4" FOR A PERIOD OF MORE THAN 15 MINUTES AFTER FLOODING.
- 12. ALL ELEVATIONS SHOWN AT CURB ARE TO THE BOTTOM OF CURB UNLESS OTHERWISE

NOTED. CURBS HAVE A 6" REVEAL UNLESS OTHERWISE NOTED.

- 13. ALL SIDEWALK AND OTHER CURB REVEALS SHALL BE 6" WITH A TOLERANCE OF PLUS OR MINUS 3/8". WHERE SIDEWALK IS TO BE FLUSH, THE PAVEMENT REVEAL SHALL BE 1/4" WITH A TOLERANCE OF 1/8".
- 14. THE FINISHED GRADE AT BOTTOM OF ALL ACCESSIBLE RAMPS SHALL BE FLUSH WITH PAVEMENT WITH A TOLERANCE OF PLUS OR MINUS 1/4".
- 15. ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE PRIOR TO INSTALLATION OF FINISHED PAVEMENT.
- 16. ROAD AND DRAINAGE CONSTRUCTION SHALL CONFORM TO THE TYPICAL SECTIONS AND DETAILS SHOWN ON THE PLANS AND SHALL MEET LOCAL STANDARDS AND THE REQUIREMENTS OF THE LATEST NHDOT STANDARD SPECIFICATIONS FOR ROADS AND BRIDGE CONSTRUCTION AND THE NHDOT STANDARD STRUCTURE DRAWINGS UNLESS OTHERWISE
- 17. STORMWATER DRAINAGE SYSTEM SHALL BE CONSTRUCTED TO LINE AND GRADE AS SHOWN ON THE PLANS. CONSTRUCTION METHODS SHALL CONFORM TO NHDOT STANDARD SPECIFICATIONS, SECTION 603. CATCH BASINS AND DRAIN MANHOLES SHALL CONFORM TO SECTION 604. ALL CATCH BASIN GRATES SHALL BE TYPE B AND CONFORM TO NHDOT STANDARDS AND SPECIFICATIONS UNLESS OTHERWISE NOTED.
- 18. NO FILL SHALL BE PLACED IN ANY WETLAND AREA.

REV. DATE

LOCATION

- 19. ALL EXCAVATIONS SHALL BE THOROUGHLY SECURED ON A DAILY BASIS BY THE CONTRACTOR AT THE COMPLETION OF CONSTRUCTION OPERATIONS IN THE IMMEDIATE AREA.
- 20. ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED SHALL RECEIVE 6" LOAM, SEED, FERTILIZER, AND MULCH.
- 21. DENSITY REQUIREMENTS: MINIMUM DENSITY*
 - 95% BELOW PAVED OR CONCRETE AREAS TRENCH BEDDING MATERIAL AND SAND BLANKET BACKFILL BELOW LOAM AND SEED AREAS 90%

3 2/15/2022 REVISED PER NHDES & UTILITIES PER TAC

1 | 11/23/2021 | REVISED PER NHDES & PROJECT COORDINATION | HEG JCC

DESCRIPTION

2 | 2/2/2022 | REVISED PER NHDES & UPDATE SURVEY/UTIL

*ALL PERCENTAGES OF COMPACTION SHALL BE OF THE MAXIMUM DRY DENSITY AT THE OPTIMUM MOISTURE CONTENT AS DETERMINED AND CONTROLLED IN ACCORDANCE WITH ASTM D-1557, METHOD C. FIELD DENSITY TESTS SHALL BE MADE IN ACCORDANCE WITH ASTM D-1556 OR ASTM D-6938.





DR CK

UTILITY NOTES

- 1. LENGTH OF PIPE IS FOR CONVENIENCE ONLY. ACTUAL PIPE LENGTH SHALL BE DETERMINED
- 2. ALL PROPOSED UTILITY WORK, INCLUDING MATERIAL, INSTALLATION, TERMINATION. EXCAVATION, BEDDING, BACKFILL, COMPACTION, TESTING, CONNECTIONS, AND CONSTRUCTION SHALL BE COORDINATED WITH AND COMPLETED IN ACCORDANCE WITH THE APPROPRIATE REQUIREMENTS, CODES, AND STANDARDS OF ALL CORRESPONDING UTILITY ENTITIES AND SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING AND DETERMINING THE LOCATION, SIZE, AND ELEVATION OF ALL EXISTING UTILITIES, SHOWN OR NOT SHOWN ON THESE PLANS, PRIOR TO THE START OF ANY CONSTRUCTION. THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY UTILITIES FOUND INTERFERING WITH THE PROPOSED CONSTRUCTION AND APPROPRIATE REMEDIAL ACTION BE AGREED TO BY THE ENGINEER BEFORE PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE TO CONTACT "DIGSAFE" (811) AT LEAST 72 HOURS BEFORE DIGGING.
- 4. COORDINATE ALL WORK ADJACENT TO PROPOSED BUILDINGS WITH ARCHITECTURAL BUILDING DRAWINGS. CONFIRM UTILITY PENETRATIONS AND INVERT ELEVATIONS ARE COORDINATED PRIOR TO INSTALLATION.
- 5. THE CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES OWNING UTILITIES, EITHER OVERHEAD OR UNDERGROUND, WITHIN THE CONSTRUCTION AREA AND SHALL COORDINATE AS NECESSARY WITH THE UTILITY COMPANIES OF SAID UTILITIES. THE PROTECTION OR RELOCATION OF UTILITIES IS ULTIMATELY THE RESPONSIBILITY OF THE CONTRACTOR.
- 6. THE EXACT LOCATION OF NEW UTILITY CONNECTIONS SHALL BE DETERMINED BY THE CONTRACTOR IN COORDINATION WITH UTILITY COMPANY, COUNTY AGENCY, AND/OR PRIVATE
- 7. THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL MANHOLES, BOXES, FITTINGS, CONNECTORS, COVER PLATES, AND OTHER MISCELLANEOUS ITEMS NOT NECESSARILY DETAILED ON THESE DRAWINGS TO RENDER THE UTILITY INSTALLATION COMPLETE AND
- 8. ALL UTILITY COMPANIES REQUIRE INDIVIDUAL CONDUITS. CONTRACTOR TO COORDINATE WITH TELEPHONE, CABLE, AND ELECTRIC COMPANIES REGARDING NUMBER, SIZE, AND TYPE OF

CONDUITS REQUIRED PRIOR TO INSTALLATION OF ANY CONDUIT.

- 9. SANITARY SEWER SHALL BE CONSTRUCTED TO THE STANDARDS AND SPECIFICATIONS AS SHOWN ON THESE PLANS. ALL SEWER MAINS AND FITTINGS SHALL BE PVC AND SHALL CONFORM TO ASTM F 679 (SDR 35 MINIMUM). FORCE MAINS AND FITTINGS SHALL CONFORM TO NH CODE OF ADMINISTRATIVE RULES ENV-WQ 700. ALL SEWER CONSTRUCTION SHALL BE IN ACCORDANCE WITH NH CODE OF ADMINISTRATIVE RULES ENV-WQ 700. SANITARY MANHOLES SHALL CONFORM TO NHDES WATER DIVISION WASTEWATER ENGINEERING BUREAU STANDARDS AND SPECIFICATIONS SHOWN HEREON.
- 10. ON-SITE WATER DISTRIBUTION SHALL BE TO CITY OF PORTSMOUTH STANDARDS AND SPECIFICATIONS. WATER MAINS SHALL HAVE A MINIMUM OF 5.5' COVER. WHERE WATER PIPES CROSS SEWER LINES A MINIMUM OF 18" VERTICAL SEPARATION BETWEEN THE TWO OUTSIDE PIPE WALLS SHALL BE OBSERVED. HORIZONTAL SEPARATION BETWEEN WATER AND SEWER SHALL BE 10' MINIMUM. WHERE A SANITARY LINE CROSSES A WATER LINE, SEWER LINE MUST BE CONSTRUCTED OF FORCE MAIN MATERIALS (PER ENV-WQ 704.08) FROM BUILDING OR MANHOLE TO MANHOLE, OR SUBSTITUTE RUBBER-GASKETED PRESSURE PIPE FOR THE SAME DISTANCE. WHEN SANITARY LINES PASS BELOW WATER LINES, LAY PIPE SO THAT NO JOINT IN THE SANITARY LINE WILL BE CLOSER THAN 6' HORIZONTALLY TO THE
- 11. THRUST BLOCKS SHALL BE PROVIDED AT ALL LOCATIONS WHERE WATER LINE CHANGES DIRECTIONS OR CONNECTS TO ANOTHER WATER LINE.
- 12. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CONDUIT AND WIRING TO ALL SIGNS AND LIGHTS. CONDUIT TO BE A MINIMUM OF 24" BELOW FINISH GRADE.
- 13. ALL PROPOSED UTILITIES SHALL BE UNDERGROUND. ALL UNDERGROUND CONDUITS SHALL HAVE NYLON PULL ROPES.
- 14. THE CONTRACTOR SHALL ARRANGE AND PAY FOR ALL INSPECTIONS, TESTING, AND RELATED SERVICES AND SUBMIT COPIES OF ACCEPTANCE TO THE OWNER, UNLESS OTHERWISE
- 15. PROVIDE PERMANENT PAVEMENT REPAIR FOR ALL UTILITY TRENCHES IN EXISTING ROAD OR PAVEMENT TO REMAIN. SAW CUT TRENCH, PAVEMENT, AND GRANULAR BASE THICKNESS TO
- MATCH EXISTING PAVEMENT. OBTAIN ALL PERMITS REQUIRED FOR TRENCHING. 16. UNLESS OTHERWISE SPECIFIED, ALL UNDERGROUND STRUCTURES, PIPES, CHAMBERS, ETC.
- SHALL BE COVERED WITH A MINIMUM OF 18" OF COMPACTED SOIL BEFORE EXPOSURE TO
- 17. THE PROPERTY WILL BE SERVICED BY THE FOLLOWING: DRAINAGE PRIVATE

MUNICIPA

WATER MUNICIPAL

ELECTRIC EVERSOURCE

COMCAST, CONSOLIDATED COMMUNICATIONS, ETC. TELEPHONE CABLE COMCAST

SITE DEVELOPMENT PLANS

TAX MAP 205 LOT 2

NOTES & LEGEND

LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR **ADL 325 LITTLE HARBOR ROAD TRUST**

SEPTEMBER 29, 2021




ivil Engineers Structural Engineers affic Engineers and Surveyors andscape Architects cientists


170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com


DR HEG FB CK JCC CADFILE 47099-01_NOTES-LEGEND_MAIN


C - 01



Eet 23 2022 - 2:21nm







CONSTRUCTION SEQUENCE NOTES CONSTRUCTION SEQUENCE NOTES (CONTINUED) CONSTRUCTION SEQUENCE NOTES CONSTRUCTION SEQUENCE NOTES (CONTINUED) (FOR ALTERATION OF TERRAIN) TO MINIMIZE EROSION AND SEDIMENTATION DUE TO CONSTRUCTION, CONSTRUCTION SHALL FOLLOW THIS 10. BEGIN PERMANENT AND TEMPORARY INSTALLATION OF SEED AND MULCH. DO NOT PLACE STORMWATER BMP'S INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY 11. PERFORM EARTHWORK NECESSARY TO ESTABLISH ROUGH GRADING AROUND PARKING FIELDS AND ACCESS DRIVES. MANAGE EXPOSED SOIL SURFACES TO AVOID TRANSPORTING SEDIMENTS INTO GENERAL CONSTRUCTION SEQUENCE. 1. DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNOFF, WATER FROM MODIFICATIONS TO THE SEQUENCE NECESSARY DUE TO THE CONTRACTOR'S SCHEDULE SHALL INCLUDE AFTER THE INFILTRATION SYSTEM IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR SHOULD BE WETLANDS. PARKING LOTS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE. EXCAVATIONS) TO BMP'S DURING ANY STAGE OF CONSTRUCTION. APPROPRIATE TEMPORARY AND PERMANENT EROSION AND SEDIMENTATION CONTROL MEASURES. DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE THE INFILTRATION RATES, FOLLOWED 12. INSTALL SUBSURFACE UTILITIES (WATER, SEWER, GAS, ELECTRIC, COMMUNICATIONS, DRAINAGE, BY A PASS WITH A LEVELING DRAG. DRAINAGE FACILITIES, ETC.). 2. DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM THE CONTRACTOR SHALL SCHEDULE WORK SUCH THAT ANY CONSTRUCTION AREA IS STABILIZED WITHIN 45 13. CONSTRUCT PROPOSED ROADWAY, RAIN GARDENS, GRAVEL WETLANDS AND DRAINAGE SWALES. ALL EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION COMPONENTS OF THE 1. NOTIFY EASEMENT OWNERS PRIOR TO COMMENCEMENT OF WORK. DAYS OF INITIAL DISTURBANCE EXCEPT AS NOTED BELOW. NO MORE THAN 5 ACRES OF DISTURBED LAND DITCHES, SWALES, AND GRAVEL WETLANDS SHALL BE FULLY STABILIZED PRIOR TO DIRECTING FLOW TO SHALL BE UNSTABILIZED AT ANY ONE TIME. 2. INSTALL ALL PERIMETER EROSION PROTECTION MEASURES AS INDICATED ON THE PLANS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. 3. AFTER INFILTRATION SYSTEMS ARE EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR SHOULD BE 14. COMPLETE BUILDING AND ALL OFF-SITE IMPROVEMENTS. STORMWATER TREATMENT PONDS AND SWALES SHALL BE INSTALLED BEFORE ROUGH GRADING THE SITE. THE PROJECT SHALL BE MANAGED SO THAT IT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 15. COMPLETE SEEDING AND MULCHING. SEED TO BE APPLIED WITH BROADCAST SPREADER OR BY DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE INFILTRATION RATES, FOLLOWED BY DURING CONSTRUCTION EVERY EFFORT SHALL BE MADE TO MANAGE SURFACE RUNOFF QUALITY. AND CHAPTER ARG 3800 RELATIVE TO INVASIVE SPECIES. HYDRO-SEEDING, THEN ROLLED, RAKED, OR DRAGGED TO ASSURE SEED/SOIL CONTACT. . DAILY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DRAINS, DITCHES, SILT BARRIERS, SEDIMENT 16. REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDED AREÁS HAVE BECOME FIRMLY DO NOT TRAFFIC EXPOSED SOIL SURFACE OF INFILTRATION SYSTEMS WITH CONSTRUCTION EQUIPMENT. IF TRAPS, ETC. MULCH AND SEED AS REQUIRED. (TEMPORARY SEED MIXTURE OF WINTER RYE APPLIED AT 4. DO NOT PLACE STORMWATER BMP'S INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY ESTABLISHED AND SITE IMPROVEMENTS ARE COMPLETE. FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION A RATE OF 2.5 LBS/1000 SF SHALL BE USED). 17. DURING THE COURSE OF THE WORK AND UPON COMPLETION, THE CONTRACTOR SHALL REMOVE ALL STABILIZED. 6. CONDUCT MAJOR EARTHWORK, INCLUDING CLEARING AND GRUBBING, WITHIN THE LIMITS OF WORK. ALL SEDIMENT DEPOSITS, EITHER ON OR OFF SITE, INCLUDING CATCH BASINS, AND SUMPS, DRAIN PIPES CUT AND FILL SLOPES SHALL BE SEEDED WITHIN 72 HOURS AFTER GRADING. AND DITCHES, CURB LINES, ALONG SILT BARRIERS, ETC. RESULTING FROM SOIL AND/OR CONSTRUCTION 5. DO NOT PLACE STORMWATER BMP'S INTO SERVICE UNTIL THE BMP HAS BEEN PLANTED, IF NECESSARY, DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNOFF, WATER FROM 7. ALL STRIPPED TOPSOIL AND OTHER EARTH MATERIALS SHALL BE STOCKPILED OUTSIDE THE IMMEDIATE AND ITS CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED. EXCAVATIONS) TO STORMWATER BMP'S. STORMWATER RUNOFF MUST BE DIRECTED TO TEMPORARY WORK AND WETLAND AREAS. A SILT BARRIER SHALL BE CONSTRUCTED AROUND THESE PILES IN A 18. SEE WINTER CONSTRUCTION SEQUENCE FOR WORK CONDUCTED AFTER OCTOBER 15TH MANNER TO PROVIDE ACCESS AND AVOID SEDIMENT OUTSIDE OF THE WORK AREA. PRACTICES UNTIL STORMWATER BMP'S ARE STABILIZED. PISCATAQUA / RIVER 8. CONSTRUCT BUILDING PAD AND COMMENCE NEW BUILDING CONSTRUCTION. REM EXIST (SEE NOTE 11) 9. CONSTRUCT TEMPORARY CULVERTS AND DIVERSIONS AS REQUIRED. (TIDAL) OVERHEAD UTILITIES -- REM EXIST UP (SEE NOTE 11) REM ALL EXIST ELEC FROM PLEASANT POINT (COORD W/ UTILITY COMPANIES) STRUCTURES & UG SERVICES (TYP) (SEE NOTE 11) -REM ALL EXIST ELEC STRUCTURES (COORD W/ UTILITY COMPANIES) & UG SERVICES (TYP) (SEE NOTE 10) PSC 248/10 (COORD W/ UTILITY COMPANIES) DEMO & RAZE -NET 72T/9 EXIST STRUCTURES - HIGHFST (DISCONNECT EXIST - OBSERVABLE UTILITIES PRIOR) TIDE LINE PROP TREE PROTECTION -(TYP) (REFER TO LANDSCAPE ARCHITECT PLANS FOR DETAIL) REM ALL EXIST ELEC -STRUCTURES & UG PROP LIMIT OF GRADING -FI DOD TONE XLLILLILLING SERVICES ON ISLAND (TYP) REM WOODED AREA BETWEEN -(SEE NOTE 11) (COORD W/ EXIST AND PROP TREELINE & UTILITY COMPANIES) PROP LIMIT - SALT MARSH OF DISTURBANCE HIGHEST . (SEE NOTE 2) (TYP) *OBSERVABLE* TIDE LINE REM TREES IF NECESSARY TTTT + 1 + 1 + 1 + 1 + 1 + 1 REM GRAVEL DRIVE REM EXIST R&R EXIST BARN (SEE SHEET C-08 REM EXIST FOR LOCATION) REM EXIST PAVE & REM EXIST GRAVEL LOCATE & PROTECT (TYP) MONITORING WELLS — (SEE NOTE 9) -REM SEWER & PIPES HIGHEST **OBSERVABLE** TIDE LINE REM EXIST MAP 205 LOT 2 535,990± S.F. STONE WALK GRANITE BLOCK (12.30± ACRES) (TO HIGH WATER) (TYP) ← PROP FILTREXX FILTERSOXX REM EXIST (DOUBLE ROW INSTALLATION) - GRANITE STEPS L DEMO & RAZE PORTION OF HOUSE 1/100' TIDAL BUFFER AND RISERS (TYP) (SEE DETAIL) (REFER TO ARCHITECTURAL PLANS) PROP TREELINE -PISCATAQUA RIVER (DISCONNECT EXIST UTILITIES PRIOR) C-08 FOR - DECOMMISSION & REM IRON ROD W/CAP LOCATION) -- PROP LIMIT OF DISTURBANCE EXIST SEPTIC SYSTEM | "CONTROL POINT" - REM TREES (SEE NOTE 2) (TYP) & CONNECTIONS -PROP LIMIT OF GRADING - PROP LIMIT OF GRADING $\,\,\,\,\,$ └─DEMO & RAZE EXIST STRUCTURES, (TYP) **NOTES** DECKS, & PATHWAYS - POTENTIAL ROCK BLASTING W/IN - REM EXIST WATER SERVICE (DISCONNECT EXIST UTILITIES PRIOR) LIMITS OF DISTURBANCE - PROP STOCKPILE AREA (SEE ROCK BLASTING & WATER SEE NOTES ON SHEET C-01. SURROUNDED BY SILT THE PROPOSED LIMIT OF DISTURBANCE INCLUDES THE LIMIT OF GRADING AND OTHER AREAS WHICH HIGHEST -QUALITY NOTES ON SHEET C-19) WILL BE BE LANDSCAPED WITH MECHANIZED EQUIPMENT, PER THE LANDSCAPE ARCHITECTURE PLANS. **OBSERVABLE** FENCE (SEE DETAIL) THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING AND DETERMINING THE LOCATIONS, SIZE, AND TIDE LINE AVOID & PROTECT SALT MARSH TO THE GREATEST ELEVATIONS OF ALL EXISTING UTILITIES, SHOWN OR NOT SHOWN ON THESE PLANS PRIOR TO THE START EXTENT PRACTICABLE & MINIMIZE IMPACTS PROP LIMIT OF DISTURBANCE -OF ANY DEMOLITION. THE LOCATIONS SHOWN ON THESE PLANS ARE NOT GUARANTEED BY THE OWNER (SEE NOTE 13) (TYP) (SEE NOTE 2) (TYP) OR THE ENGINEER. THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY UTILITIES INTERFERING WITH REM EXIST PAVE (TYP) THE PROPOSED DEMOLITION TO DETERMINE APPROPRIATE ACTION TO BE TAKEN BEFORE PROCEEDING PROP FILTREXX FILTERSOXX -WITH THE WORK. IT IS ALSO THE CONTRACTOR'S RESPONSIBILITY TO ANTICIPATE CONFLICTS AND REPAIR (DOUBLE ROW INSTALLATION) GRANITE BLOCK EXISTING UTILITIES AS NECESSARY TO COMPLETE THE WORK AT NO ADDITIONAL COST TO THE OWNER. (TYP) (SEE DETAIL) THE CONTRACTOR SHALL MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY WORK AT ALL PROP TREE PROTECTION -UT & CAP EXIST WATER SERVICE (TYP) (REFER TO LANDSCAPE THE CONTRACTOR SHALL VERIFY ALL SURVEY INFORMATION IN THE FIELD AND REPORT ANY PISCATAQUA RIVER DISCREPANCIES TO THE ENGINEER PRIOR TO THE START OF CONSTRUCTION. ARCHITECT PLANS FOR DETAIL) PROP STABILIZED EXISTING UTILITY SERVICES TO BE DISCONTINUED ARE TO BE CAPPED AS REQUIRED BY THE RESPECTIVE CONSTRUCTION ENTRANCE AVOID & PROTECT SALT MARSH TO THE GREATEST — EXTENT PRACTICABLE & MINIMIZE IMPACTS UTILITY COMPANIES. (TIDAL) (SEE DETAIL) SITE PREPARATION & DEMOLITION PLAN CONSTRUCTION DEBRIS AND INVASIVE SPECIES SHALL BE REMOVED FROM SITE AND DISPOSED OF IN A (SEE NOTE 13) (TYP) - PROP MARSH ELDER PROTECTION LEGAL MANNER. PRIOR TO THE START OF WORK, THE CONTRACTOR SHALL PLACE ORANGE CONSTRUCTION FENCING AROUND EACH TREE TO BE RETAINED THROUGHOUT CONSTRUCTION. NO STOCKPILES OF MATERIAL ARE (TYP) (SEE NOTE 12) PROP FILTREXX FILTERSOXX — (DOUBLE ROW INSTALLATION) PERMITTED WITHIN THE DRIP LINE OF THE TREES TO BE SAVED. (TYP) (SEE DETAIL) CONTACT THE LANDSCAPE ARCHITECT IMMEDIATELY IF ANY TREES ARE DAMAGED DURING CONTRACTOR IS REQUIRED TO LOCATE AND PROTECT MONITORING WELLS SHOWN AND NOT SHOWN ON THE PLAN PER NHDES SITE# 200409050, PROJECT# 38804, ACTIVITY# 206267. ANY MODIFICATIONS TO **ADL 325 LITTLE HARBOR ROAD TRUST** EXISTING MONITORING WELLS SHALL BE DOCUMENTED WITH THE NHDES WITH NOTIFICATION TO TEMORAN IT IS TO BE DETERMINED IF THE EXISTING OVERHEAD ELECTRIC UTILITIES FROM PLEASANT POINT WILL BE MAINTAINED OR PROPOSED UNDERGROUND ELECTRIC UTILITIES WILL BE PROVIDED TO THE PROPERTY TO CONSTRUCTION, MARSH ELDER SHALL BE IDENTIFIED, FLAGGED, AND SURROUNDED WITH 1"=120' (11"x17") ORANGE CONSTRUCTION FENCING WITH YELLOW CAUTION TAPE FOR PROTECTION OF THE SPECIES. DO SCALE: 1"=60' (22"x34") NOT REMOVE, MOW, TRAMPLE, COVER, OR OTHERWISE HARM THE PLANT. REMOVE FLAGS AND STRUCTION FENCING AND CAUTION TAPE AFTER CONSTRUCTION IS COMPLET TO THE GREATEST EXTENT PRACTICABLE, IMPACTS TO THE SALT MARSH SHALL BE MINIMIZED. EROSION CONTROLS SHALL BE INSTALLED, MONITORED, AND ADJUSTED AS REQUIRED THROUGHOUT THE DURATION OF THE PROJECT. UPON COMPLETION, DISTURBED AREAS SHALL BE REPLANTED WITH PLUGS OF

48 Constitution Drive, Bedford, N.H. 03110

Copyright 2022 ©TFMoran, Inc.

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

SALTMARSH CORDGRASS (SPARTINA ALTERNIFLORA).

This plan is not effective unless signed by a duly authorized officer of homas F. Moran, Inc.

3 2/15/2022 REVISED PER NHDES & UTILITIES PER TAC 2/2/2022 REVISED PER NHDES & UPDATE SURVEY/UTIL HORIZONTAL SCALE 1"=60' 1 | 11/23/2021 | REVISED PER NHDES & PROJECT COORDINATION | HEG JCC

DESCRIPTION

DR CK

REV. DATE

SITE DEVELOPMENT PLANS

CHISELED X

IN CONCRETE

- PROP INLET AF (EL.8)

- PROP LIMIT OF DISTURBANCE

(SEE NOTE 2) (TYP)

PROTECTION (SEE DETAIL)

*STEP ELEV.=*8.94

SALT MARSH

GRANITE BLOCK SEA WALL

PROP LIMIT OF GRADING

TAX MAP 205 LOT 2

LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR

SEPTEMBER 29, 2021





ivil Engineers Structural Engineers raffic Engineers and Surveyors andscape Architects cientists


170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com


DR HEG FB CK JCC CADFILE 47099-01_SITE PREP_MAIN


C - 06

















BELLE ISLE ROAD PROFILE


LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH


OWNED BY & PREPARED FOR **ADL 325 LITTLE HARBOR ROAD TRUST**

1"=120' (11"x17") SCALE: 1"=60' (22"x34")

SEPTEMBER 29, 2021

HORIZONTAL SCALE 1"=60' VERTICAL SCALE 1"=4'





170 Commerce Way, Suite 102 Civil Engineers Structural Engineers Portsmouth, NH 03801 Traffic Engineers Phone (603) 431-2222

Land Surveyors Fax (603) 431-0910 Landscape Architects www.tfmoran.com

47099.01 DR HEG FB - CK JCC CADFILE 47099-01_PROFILE_DRIVEWAY

duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc. This plan is not effective unless signed by a duly authorized officer of


All rights reserved. These plans and materials may not be copied,

Copyright 2022 ©TFMoran, Inc.

Thomas F. Moran, Inc.

48 Constitution Drive, Bedford, N.H. 03110

C - 13



Eah 23 2022 - 2:40nm

eb 23, 2022 - 2:11pm

THE TOTAL AREA TO BE DISTURBED IS APPROXIMATELY 367,073 SQUARE FEET ($8.4\pm$ ACRES). CONSTRUCTION SHALL BE PHASED TO LIMIT DISTURBED AREAS TO LESS THAN 5 ACRES.

CRITICAL NOTE: THIS DRAWING IS PROVIDED FOR GENERAL GUIDANCE, ALL SPECIAL EROSION CONTROL MEASURES MUST BE EXECUTED IN ACCORDANCE WITH APPLICABLE CURRENT STATE AND LOCAL REGULATIONS, APPROVED SWPPP, AND PERMIT REQUIREMENTS.

SEQUENCE OF MAJOR ACTIVITIES

- 1. INSTALL PERIMETER CONTROLS, STABILIZED CONSTRUCTION ENTRANCE, AND TEMPORARY EROSION CONTROL MEASURES PER APPROVED SITE DEVELOPMENT PLANS, PERMITS, OR SWPPP IF REQUIRED, PRIOR TO EARTH MOVING OPERATIONS.
- DEMOLISH EXISTING SITE WORK DESIGNATED FOR REMOVAL. INSTALL STORMWATER TREATMENT PONDS AND SWALES BEFORE ROUGH GRADING THE SITE.
- COMPLETE MAJOR GRADING OF SITE.
- 5. CONSTRUCT BUILDING PAD, STORMWATER SYSTEM, AND SITE UTILITIES. CONSTRUCT PARKING AREAS.
- WHEN ALL CONSTRUCTION ACTIVITY IS COMPLETE AND SITE IS STABILIZED, REMOVE ALL INLET PROTECTION, SILT BARRIERS, AND SEDIMENT THAT HAS BEEN TRAPPED BY THESE DEVICES.
- 8. CONSULT APPLICABLE REGULATIONS, PERMITS, CONDITIONS, AND APPROVED SWPPP FOR CONDITIONS RELATED TO NOTICE OF TERMINATION, IF REQUIRED.

EROSION AND SEDIMENT CONTROLS AND STABILIZATION PRACTICES

STABILIZATION SHALL BE INITIATED ON ALL LOAM STOCKPILES AND DISTURBED AREAS WHERE CONSTRUCTION ACTIVITY WILL NOT OCCUR FOR MORE THAN TWENTY ONE (21) CALENDAR DAYS BY THE FOURTEENTH (14TH) DAY AFTER CONSTRUCTION ACTIVITY HAS PERMANENTLY OR TEMPORARILY CEASED IN THAT AREA. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:

- 1. BASE COURSE GRAVELS, WHICH MEET THE REQUIREMENTS OF NHDOT STANDARD FOR ROAD AND BRIDGE CONSTRUCTION, 2016, ITEM 304.2, HAVE BEEN INSTALLED IN AREAS TO BE PAVED;
- 2. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; 3. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED; OR
- 4. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

DURING CONSTRUCTION, RUNOFF WILL BE DIVERTED AROUND THE SITE WITH EARTH DIKES, PIPING OR STABILIZED CHANNELS WHERE POSSIBLE. SHEET RUNOFF FROM THE SITE WILL BE FILTERED THROUGH SILT BARRIERS. ALL STORM DRAIN INLETS SHALL BE PROVIDED WITH BARRIER FILTERS. STONE RIPRAP SHALL BE PROVIDED AT THE OUTLETS OF DRAINAGE PIPES WHERE EROSIVE VELOCITIES ARE ENCOUNTERED.

OFF SITE VEHICLE TRACKING

STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED.

<u>INSTALLATION, MAINTENANCE, AND INSPECTION OF EROSION AND SEDIMENT CONTROLS</u>

THESE ARE THE GENERAL INSPECTION AND MAINTENANCE PRACTICES THAT WILL BE USED TO IMPLEMENT THE PLAN.

- 1. STABILIZATION OF ALL SWALES, DITCHES, AND PONDS IS REQUIRED PRIOR TO DIRECTING FLOW TO THEM.
- 2. THE SMALLEST PRACTICAL PORTION OF THE SITE WILL BE DENUDED AT ONE TIME. (5 AC MAX)
- 3. ALL CONTROL MEASURES WILL BE INSPECTED IN ACCORDANCE WITH APPLICABLE REGULATIONS, PERMITS, AND CONDITIONS AND FOR PROJECTS REQUIRING A NHDES AOT PERMIT AND NHPDES EPA GCP, DISCHARGING TO A NON-SENSITIVE WATERBODY, AT LEAST EVERY 7 DAYS AND AFTER A 0.5 INCH RAIN EVENT OR GREATER, AND INSPECTIONS SHALL BE CONDUCTED BY THE ENVIRONMENTAL MONITOR IF ONE IS REQUIRED, PURSUANT TO ENV-WQ 1505.03(B) OR FOR PROJECTS REQUIRING A NHDES AOT PERMIT AND NHPDES EPA GCP, DISCHARGING TO A SENSITIVE WATERBODY, AT LEAST EVERY 7 DAYS AND AFTER A 0.25 INCH RAIN EVENT OR GREATER, AND INSPECTIONS SHALL BE CONDUCTED BY THE ENVIRONMENTAL MONITOR IF ONE IS REQUIRED, PURSUANT TO ENV-WQ 1505.03(B).
- 4. ALL MEASURES WILL BE MAINTAINED IN GOOD WORKING ORDER. IF A REPAIR IS NECESSARY, IT WILL BE INITIATED WITHIN 24 HOURS OF REPORT.
- 5. BUILT UP SEDIMENT WILL BE REMOVED FROM SILT BARRIER WHEN IT HAS REACHED ONE THIRD THE HEIGHT OF THE BARRIER.
- 6. ALL DIVERSION DIKES WILL BE INSPECTED AND ANY BREACHES PROMPTLY REPAIRED.
- 7. TEMPORARY SEEDING AND PLANTING WILL BE INSPECTED FOR BARE SPOTS, WASHOUTS, AND UNHEALTHY
- 8. A MAINTENANCE INSPECTION REPORT WILL BE MADE AFTER EACH INSPECTION.
- 9. THE CONTRACTOR WILL BE RESPONSIBLE FOR ENSURING AN ENVIRONMENTAL MONITOR. IF ONE IS REQUIRED. PURSUANT TO ENV-WQ 1505.03(B), IS CONTRACTED.

FILTERS / BARRIERS

SILT SOCKS

A. KNOTTED MESH NETTING MATERIAL SHALL BE DELIVERED TO SITE IN A 5 MIL CONTINUOUS, TUBULAR, HDPE 3/8" MATERIAL, FILLED WITH COMPOST CONFORMING TO THE FOLLOWING REQUIREMENTS:

TEST REQUIREMENTS
TMECC 04.11-A 5.0 TO 8.0 PARTICLE SIZE TMECC 02.02-B 2" SIEVE AND MIN. 60% GREATER THAN THE 3" SIEVE

MOISTURE CONTENT MATERIAL SHALL BE RELATIVELY FREE OF INERT OR FOREIGN MAN-MADE MATERIALS

MATERIAL SHALL BE WEED FREE AND DERIVED FROM A WELL-DECOMPOSED SOURCE OF ORGANIC MATTER, FREE FROM ANY REFUSE, CONTAMINANTS OR OTHER MATERIALS TOXIC TO PLANT GROWTH.

STND TESTING < 60%

- B. SEDIMENT COLLECTED AT THE BASE OF THE SILT SOCK SHALL BE REMOVED ONCE IT HAS REACHED 1/3 OF THE EXPOSED HEIGHT OF THE SILT SOCK.
- C. SILT BARRIER SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREAS HAS BEEN PERMANENTLY STABILIZED.

2. SEQUENCE OF INSTALLATION

SEDIMENT BARRIERS SHALL BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE OF THE CONTRIBUTING DRAINAGE AREA ABOVE THEM.

3. MAINTENANCE

- A. SILT BARRIERS SHALL BE INSPECTED WEEKLY AND IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. THEY SHALL BE REPAIRED IF THERE ARE ANY SIGNS OF EROSION OR SEDIMENTATION BELOW THEM. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY. IF THERE ARE SIGNS OF UNDERCUTTING AT THE CENTER OR THE EDGES, OR IMPOUNDING OF LARGE VOLUMES OF WATER BEHIND THEM, SEDIMENT BARRIERS SHALL BE REPLACED WITH A TEMPORARY CHECK DAM.
- B. SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.

- C. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE THIRD (1/3) THE HEIGHT OF THE BARRIER.
- D. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFIRM WITH THE EXISTING GRADE, PREPARED AND SEEDED.

C. <u>MULCHING</u>

IN ORDER FOR MULCH TO BE EFFECTIVE, IT MUST BE IN PLACE PRIOR TO MAJOR STORM EVENTS. THERE ARE TWO (2) TYPES OF STANDARDS WHICH SHALL BE USED TO ASSURE THIS:

A. APPLY MULCH PRIOR TO ANY STORM EVENT.

THIS IS APPLICABLE WHEN WORKING WITHIN 100' OF WETLANDS. IT WILL BE NECESSARY TO CLOSELY MONITOR WEATHER PREDICTIONS, USUALLY BY CONTACTING THE NATIONAL WEATHER SERVICE, TO HAVE ADEQUATE WARNING OF SIGNIFICANT STORMS.

B. REQUIRED MULCHING WITHIN A SPECIFIED TIME PERIOD.

THE TIME PERIOD CAN RANGE FROM 14 TO 21 DAYS OF INACTIVITY ON AN AREA, WHERE THE LENGTH OF TIME VARIES WITH SITE CONDITIONS. PROFESSIONAL JUDGMENT SHALL BE USED TO EVALUATE THE INTERACTION OF SITE CONDITIONS (SOIL ERODIBILITY, SEASON OF YEAR, EXTENT OF DISTURBANCE, PROXIMITY TO SENSITIVE RESOURCES, ETC.) AND THE POTENTIAL IMPACT OF EROSION ON ADJACENT AREAS TO CHOOSE AN APPROPRIATE TIME RESTRICTION.

2. GUIDELINES FOR WINTER MULCH APPLICATION.

WHEN MULCH IS APPLIED TO PROVIDE PROTECTION OVER WINTER (PAST THE GROWING SEASON) IT SHALL BE AT A RATE OF 6,000 POUNDS OF HAY OR STRAW PER ACRE. A TACKIFIER MAY BE ADDED TO THE MULCH.

MAINTENANCE

ALL MULCHES MUST BE INSPECTED PERIODICALLY, IN PARTICULAR AFTER RAINSTORMS, TO CHECK FOR RILL EROSION. IF LESS THAN 90% OF THE SOIL SURFACE IS COVERED BY MULCH, ADDITIONAL MULCH SHALL BE IMMEDIATELY APPLIED.

D. VEGETATIVE PRACTICE

- 1. AFTER ROUGH GRADING OF THE SUBGRADE HAS BEEN COMPLETED AND APPROVED, THE SUB GRADE SURFACE SHALL BE SCARIFIED TO A DEPTH OF 4". THEN, FURNISH AND INSTALL A LAYER OF LOAM PROVIDING A ROLLED 3. SANITARY WASTE THICKNESS AS SPECIFIED IN THESE PLANS. ANY DEPRESSIONS WHICH MAY OCCUR DURING ROLLING SHALL BE FILLED WITH ADDITIONAL LOAM, REGRADED AND REROLLED UNTIL THE SURFACE IS TRUE TO THE FINISHED LINES AND GRADES. ALL LOAM NECESSARY TO COMPLETE THE WORK UNDER THIS SECTION SHALL BE SUPPLIED BY THE SITE SUBCONTRACTOR.
- 2. ALL LARGE STIFF CLODS, LUMPS, BRUSH, ROOTS, DEBRIS, GLASS, STUMPS, LITTER, AND OTHER FOREIGN MATERIAL, AS WELL AS STONES OVER 1" IN DIAMETER, SHALL BE REMOVED FROM THE LOAM AND DISPOSED OF 1. MATERIAL MANAGEMENT PRACTICES OFF SITE. THE LOAM SHALL BE RAKED SMOOTH AND EVEN.
- 3. THE LOAM SHALL BE PREPARED TO RECEIVE SEED BY REMOVING STONES, FOREIGN OBJECTS AND GRADING TO ELIMINATE WATER POCKETS AND IRREGULARITIES PRIOR TO PLACING SEED. FINISH GRADING SHALL RESULT IN STRAIGHT UNIFORM GRADES AND SMOOTH, EVEN SURFACES WITHOUT IRREGULARITIES TO LOW POINTS.
- 4. SHAPE THE AREAS TO THE LINES AND GRADES REQUIRED. THE SITE SUBCONTRACTOR'S ATTENTION IS DIRECTED TO THE SCHEDULING OF LOAMING AND SEEDING OF GRADED AREAS TO PERMIT SUFFICIENT TIME FOR THE STABILIZATION OF THESE AREAS. IT SHALL BE THE SITE SUBCONTRACTOR'S RESPONSIBILITY TO MAINTAIN THE AREAS DURING THE CONSTRUCTION PERIOD AND REGRADE, LOAM AND RESEED ANY DAMAGED AREAS.
- 5. ALL AREAS DISTURBED BY CONSTRUCTION WITHIN THE PROPERTY LINES AND NOT COVERED BY STRUCTURES, PAVEMENT, OR MULCH SHALL BE LOAMED AND SEEDED.
- 6. LIMESTONE SHALL BE THOROUGHLY INCORPORATED INTO THE LOAM LAYER AT A RATE OF 2 TONS PER ACRE IN ORDER TO PROVIDE A PH VALUE OF 5.5 TO 6.5.
- 7. IF PERMITTED PER LOCAL AND STATE REGULATIONS, FERTILIZER SHALL BE SPREAD ON THE TOP LAYER OF LOAM AND WORKED INTO THE SURFACE. FERTILIZER APPLICATION RATE SHALL BE 500 POUNDS PER ACRE OF
- 8. SOIL CONDITIONERS AND FERTILIZER SHALL BE APPLIED AT THE RECOMMENDED RATES AND SHALL BE THOROUGHLY WORKED INTO THE LOAM. LOAM SHALL BE RAKED UNTIL THE SURFACE IS FINELY PULVERIZED, SMOOTH AND EVEN, AND THEN COMPACTED TO AN EVEN SURFACE CONFORMING TO THE REQUIRED LINES AND GRADES WITH APPROVED ROLLERS WEIGHING BETWEEN 4 1/2 POUNDS AND 5 1/2 POUNDS PER INCH OF WIDTH.
- 9. SEED SHALL BE SOWN AT THE RATE SHOWN BELOW. SOWING SHALL BE DONE ON A CALM, DRY DAY, PREFERABLY BY MACHINE, BUT IF BY HAND, ONLY BY EXPERIENCED WORKMEN. IMMEDIATELY BEFORE SEEDING, THE SOIL SHALL BE LIGHTLY RAKED. ONE HALF THE SEED SHALL BE SOWN IN ONE DIRECTION AND THE OTHER HALF AT RIGHT ANGLES TO THE ORIGINAL DIRECTION. IT SHALL BE LIGHTLY RAKED INTO THE SOIL TO A DEPTH NOT OVER 1/4" AND ROLLED WITH A HAND ROLLER WEIGHING NOT OVER 100 POUNDS PER LINEAR FOOT OF
- 10. HAY MULCH SHALL BE APPLIED IMMEDIATELY AFTER SEEDING AT A RATE OF 1.5 TO 2 TONS PER ACRE. MULCH 2. PRODUCT SPECIFICATION PRACTICES TECHNIQUES FROM THE EROSION AND SEDIMENT CONTROL HANDBOOK.
- 11. THE SURFACE SHALL BE WATERED AND KEPT MOIST WITH A FINE SPRAY AS REQUIRED, WITHOUT WASHING AWAY THE SOIL, UNTIL THE GRASS IS WELL ESTABLISHED. ANY AREAS WHICH ARE NOT SATISFACTORILY COVERED WITH GRASS SHALL BE RESEEDED, AND ALL NOXIOUS WEEDS REMOVED.
- 12. THE SITE SUBCONTRACTOR SHALL PROTECT AND MAINTAIN THE SEEDED AREAS UNTIL ACCEPTED, INCLUDING CUTTING, AS SPECIFIED HEREIN AFTER UNDER MAINTENANCE AND PROTECTION.
- 13. UNLESS OTHERWISE APPROVED, SEEDING SHALL BE DONE DURING THE APPROXIMATE PERIODS OF EARLY SPRING TO SEPTEMBER 30, WHEN SOIL CONDITIONS AND WEATHER ARE SUITABLE FOR SUCH WORK. IN NO CASE SHALL THE WEED CONTENT EXCEED 1 PERCENT BY WEIGHT. ALL SEED SHALL COMPLY WITH STATE AND FEDERAL SEED LAWS. FOR TEMPORARY PLANTINGS AFTER SEPTEMBER 30, TO EARLY SPRING AND FOR TEMPORARY PROTECTION OF DISTURBED AREAS:
- A. FOLLOW ABOVE SLOPE, LOAM DEPTH AND GRADING REQUIREMENTS. B. FERTILIZER SHALL BE SPREAD AND WORKED INTO THE SURFACE AT A RATE OF 500 POUNDS PER ACRE.
- MULCHING AND SEEDING SHALL BE APPLIED AT THE FOLLOWING RATES: WINTER RYE (FALL SEEDING) 2.5 LBS/1,000 SF
- OATS (SPRING SEEDING) 2.0 LBS/1,000 SF 1.5 TONS/ACRE

E. CATCH BASIN INLET PROTECTION

- 1. INLET BASKET STRUCTURE
- A. INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY PRIOR TO DISTURBING PAVEMENT AND SHALL REMAIN IN PLACE AND MAINTAINED UNTIL PAVEMENT BINDER COURSE IS COMPLETE.
- B. MOLD 6X6, 42 LB. WIRE SUPPORT AROUND INLET FRAME AND GRATE AND EXTEND 6" BEYOND SIDES. SECURE FILTER FABRIC TO WIRE SUPPORT.
- C. THE FILTER FABRIC SHALL BE A GEOTEXTILE FABRIC; POLYESTER, POLYPROPYLENE, STABILIZED NYLON, POLYETHYLENE OR POLYVINYLIDENE CHLORIDE MEETING THE FOLLOWING SPECIFICATIONS:
 - GRAB STRENGTH: 45 LB. MINIMUM IN ANY PRINCIPAL DIRECTION (ASTM D1682) MULLEN BURST STRENGTH: MIN. 60PSI (ASTM D774)
- D. THE FABRIC SHALL HAVE AN OPENING NO GREATER THAN A NUMBER 20 U.S. STANDARD SIEVE AND A MINIMUM PERMEABILITY OF 120 GPM.
- E. THE INLET PROTECTION SHALL BE INSPECTED WITHIN 24 HOURS AFTER EACH RAINFALL OR DAILY DURING EXTENDED PERIODS OF PRECIPITATION. REPAIRS SHALL BE MADE IMMEDIATELY, AS NECESSARY, TO PREVENT PARTICLES FROM REACHING THE DRAINAGE SYSTEM AND/OR CAUSING SURFACE FLOODING.
- F. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT, OR MORE OFTEN IF THE FABRIC BECOMES CLOGGED.

F. <u>WINTER CONSTRUCTION SEQUENCE</u>

- ALL PROPOSED POST-DEVELOPMENT LANDSCAPED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1 AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE PLACEMENT OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENT.
- 2. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.
- 3. AFTER OCTOBER 15TH, INCOMPLETE PARKING AREAS WHERE ACTIVE CONSTRUCTION HAS STOPPED FOR THE WINTER, ALL TRAVEL SURFACES SHALL BE PROTECTED WITH A MINIMUM OF 3" OF CRUSHED GRAVEL PER NHDOT ITEM 304.3, OR IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON BE CLEARED OF ANY ACCUMULATED SNOWFALL AFTER EACH STORM EVENT.

TIMING OF CONTROLS/MEASURES

AS INDICATED IN THE SEQUENCE OF MAJOR ACTIVITIES, SILT BARRIERS SHALL BE INSTALLED PRIOR TO COMMENCING ANY CLEARING OR GRADING OF THE SITE. STRUCTURAL CONTROLS SHALL BE INSTALLED CONCURRENTLY WITH THE APPLICABLE ACTIVITY. AREAS WHERE CONSTRUCTION ACTIVITY TEMPORARILY CEASES FOR MORE THAN TWENTY ONE (21) DAYS WILL BE STABILIZED WITH A TEMPORARY SEED AND MULCH WITHIN FOURTEEN (14) DAYS OF THE LAST DISTURBANCE. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN AREA, SILT BARRIERS AND ANY EARTH/DIKES WILL BE REMOVED ONCE PERMANENT MEASURES ARE ESTABLISHED.

- WASTE MATERIALS ALL WASTE MATERIALS WILL BE COLLECTED AND STORED IN SECURELY LIDDED RECEPTACLES. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN A DUMPSTER. NO CONSTRUCTION WASTE MATERIALS WILL BE BURIED ON SITE. ALL PERSONNEL WILL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL BY THE SUPERINTENDENT.
- 2. HAZARDOUS WASTE ALL HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER. SITE PERSONNEL WILL BE INSTRUCTED IN THESE PRACTICES BY THE SUPERINTENDENT.
- ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF ONCE PER WEEK BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.

SPILL PREVENTION

HE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES DURING CONSTRUCTION TO STORMWATER RUNOFF

GOOD HOUSEKEEPING: THE FOLLOWING GOOD HOUSEKEEPING PRACTICES WILL BE FOLLOWED ON SITE DURING THE CONSTRUCTION

- A. AN EFFORT WILL BE MADE TO STORE ONLY SUFFICIENT AMOUNTS OF PRODUCTS TO DO THE JOB.
- B. ALL MATERIALS STORED ON SITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR PROPER (ORIGINAL IF POSSIBLE) CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE.
- C. MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED.
- D. THE SITE SUPERINTENDENT WILL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS.
- E. SUBSTANCES WILL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER. F. WHENEVER POSSIBLE ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER.
- HAZARDOUS PRODUCTS: THE FOLLOWING PRACTICES WILL BE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS:
- A. PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE.
- B. ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED FOR IMPORTANT PRODUCT
- C. SURPLUS PRODUCT THAT MUST BE DISPOSED OF WILL BE DISCARDED ACCORDING TO THE MANUFACTURER'S RECOMMENDED METHODS OF DISPOSAL.

THE FOLLOWING PRODUCT SPECIFIC PRACTICES WILL BE FOLLOWED ON SITE

INFORMATION.

ALL ON SITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE LEAKAGE. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT BASED SUBSTANCES USED ON SITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

FERTILIZERS USED WILL BE APPLIED ONLY IN THE MINIMUM AMOUNTS DIRECTED BY THE SPECIFICATIONS. ONCE APPLIED, FERTILIZER WILL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORMWATER. STORAGE WILL BE IN A COVERED SHED OR ENCLOSED TRAILERS. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER WILL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS.

ALL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT WILL NOT BE DISCHARGED TO THE STORM SEWER SYSTEM BUT WILL BE DISPOSED OF PROPERLY ACCORDING TO MANUFACTURER'S INSTRUCTIONS OR STATE AND LOCAL REGULATIONS.

3 2/15/2022 REVISED PER NHDES & UTILITIES PER TAC

1 | 11/23/2021 | REVISED PER NHDES & PROJECT COORDINATION | HEG JCC

DESCRIPTION

DR CK

> | 2/2/2022 | REVISED PER NHDES & UPDATE SURVEY/UTII

REV. DATE

CONCRETE TRUCKS WILL DISCHARGE AND WASH OUT SURPLUS CONCRETE OR DRUM WASH WATER IN A CONTAINED AREA DESIGNATED ON SITE.

SPILL CONTROL PRACTICES

CLEANUP SUPPLIES.

- IN ADDITION TO GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTION THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:
- A. MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND
- B. MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREA ON SITE. EQUIPMENT AND MATERIALS WILL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUSTPANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAWDUST, AND PLASTIC OR METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE.
- C. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY.
- D. THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE.
- E. SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF THE SIZE.
- F. THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM RECURRING AND HOW TO CLEANUP THE SPILL IF IT RECURS. A DESCRIPTION OF THE SPILL, ITS CAUSE, AND THE CLEANUP MEASURES WILL BE INCLUDED.
- G. THE SITE SUPERINTENDENT RESPONSIBLE FOR DAY-TO-DAY SITE OPERATIONS WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR.

DUST CONTROL

THE CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST THROUGHOUT THE CONSTRUCTION PERIOD. DUST CONTROL METHODS SHALL INCLUDE, BUT NOT LIMITED TO SPRINKLING WATER ON EXPOSED AREAS, COVERING LOADED DUMP TRUCKS LEAVING THE SITE, AND TEMPORARY MULCHING. DUST CONTROL MEASURES SHALL BE UTILIZED SO AS TO PREVENT THE MIGRATION OF DUST FROM THE SITE TO ABUTTING AREAS.

ROCK BLASTING & WATER QUALITY NOTES

- . IDENTIFY DRINKING WATER WELLS LOCATED WITHIN 2000 FEET OF THE PROPOSED BLASTING ACTIVITIES. DEVELOP A GROUNDWATER QUALITY SAMPLING PROGRAM TO MONITOR FOR NITRATE AND NITRITE EITHER IN THE DRINKING WATER SUPPLY WELLS OR IN OTHER WELLS THAT ARE REPRESENTATIVE OF THE DRINKING WATER SUPPLY WELLS IN THE AREA THE PLAN MUST INCLUDE PRE AND POST BLAST WATER QUALITY MONITORING AND BE APPROVED BY NHDES PRIOR TO INITIATING BLASTING. THE GROUNDWATER SAMPLING PROGRAM MUST BE IMPLEMENTED ONCE APPROVED BY NHDES.
- 2. ALL ACTIVITIES RELATED TO BLASTING SHALL FOLLOW BEST MANAGEMENT PRACTICES (BMPS) TO PREVENT CONTAMINATION OF GROUNDWATER INCLUDING PREPARING, REVIEWING, AND FOLLOWING AN APPROVED BLASTING PLAN; PROPER DRILLING, EXPLOSIVE HANDING AND LOADING PROCEDURES; OBSERVING THE ENTIRE BLASTING PROCEDURES; EVALUATING BLASTING PERFORMANCE; AND HANDLING AND STORAGE OF BLASTED ROCK.
- A. LOADING PRACTICES. THE FOLLOWING BLASTHOLE LOADING PRACTICES TO MINIMIZE ENVIRONMENTAL EFFECTS SHALL BE FOLLOWED:
- (1) DRILLING LOGS SHALL BE MAINTAINED BY THE DRILLER AND COMMUNICATED DIRECTLY TO THE BLASTER. THE LOGS SHALL INDICATE DEPTHS AND LENGTHS OF VOIDS, CAVITIES, AND FAULT ZONES OR OTHER WEAK ZONES ENCOUNTERED AS WELL AS GROUNDWATER CONDITIONS.
- (2) EXPLOSIVE PRODUCTS SHALL BE MANAGED ON SITE SO THAT THEY ARE EITHER USED IN THE BOREHOLE, RETURNED TO THE DELIVERY VEHICLE, OR PLACED IN SECURE CONTAINERS FOR OFF-SITE DISPOSAL. (3) SPILLAGE AROUND THE BOREHOLE SHALL EITHER BE PLACED IN THE BOREHOLE OR CLEANED UP AND
- RETURNED TO AN APPROPRIATE VEHICLE FOR HANDLING OR PLACEMENT IN SECURED CONTAINERS FOR OFF SITE DISPOSAL (4) LOADED EXPLOSIVES SHALL BE DETONATED AS SOON AS POSSIBLE AND SHALL NOT BE LEFT IN THE
- BLASTHOLES OVERNIGHT, UNLESS WEATHER OR OTHER SAFETY CONCERNS REASONABLY DICTATE THAT DETONATION SHOULD BE POSTPONED. (5) LOADING EQUIPMENT SHALL BE CLEANED IN AN AREA WHERE WASTEWATER CAN BE PROPERLY CONTAINED AND
- HANDLED IN A MANNER THAT PREVENTS RELEASE OF CONTAMINANTS TO THE ENVIRONMENT. (6) EXPLOSIVES SHALL BE LOADED TO MAINTAIN GOOD CONTINUITY IN THE COLUMN LOAD TO PROMOTE COMPLETE
- DETONATION. INDUSTRY ACCEPTED LOADING PRACTICES FOR PRIMING, STEMMING, DECKING, AND COLUMN RISE NEED TO BE ATTENDED TO. B. EXPLOSIVE SELECTION. THE FOLLOWING BMPS SHALL BE FOLLOWED TO REDUCE THE POTENTIAL FOR GROUNDWATER
- CONTAMINATION WHEN EXPLOSIVES ARE USED: (1) EXPLOSIVE PRODUCTS SHALL BE SELECTED THAT ARE APPROPRIATE FOR SITE CONDITIONS AND SAFE BLAST
- (2) EXPLOSIVE PRODUCTS SHALL BE SELECTED THAT HAVE THE APPROPRIATE WATER RESISTANCE FOR THE SITE CONDITIONS PRESENT TO MINIMIZE THE POTENTIAL FOR HAZARDOUS EFFECT OF THE PRODUCT UPON
- C. PREVENTION OF MISFIRES. APPROPRIATE PRACTICES SHALL BE DEVELOPED AND IMPLEMENTED TO PREVENT MISFIRES. D. MUCK PILE MANAGEMENT. MUCK PILES (THE BLASTED PIECES OF ROCK) AND ROCK PILES SHALL BE MANAGED IN A MANNER TO REDUCE THE POTENTIAL FOR CONTAMINATION BY IMPLEMENTING THE FOLLOWING MEASURES:
- (1) REMOVE THE MUCK PILE FROM THE BLAST AREA AS SOON AS REASONABLY POSSIBLE. (2) MANAGE THE INTERACTION OF BLASTED ROCK PILES AND STORMWATER TO PREVENT CONTAMINATION OF WATER SUPPLY WELLS OR SURFACE WATER.
- E. SPILL PREVENTION MEASURES AND SPILL MITIGATION. SPILL PREVENTION AND SPILL MITIGATION MEASURES SHALL BE IMPLEMENTED TO PREVENT THE RELEASE OF FUEL AND OTHER RELATED SUBSTANCES TO THE ENVIRONMENT. THE MEASURES SHALL INCLUDE AT A MINIMUM:
- (1) THE FUEL STORAGE REQUIREMENTS SHALL INCLUDE
- STORAGE OF REGULATED SUBSTANCES ON AN IMPERVIOUS SURFACE.
- SECURE STORAGE AREAS AGAINST UNAUTHORIZED ENTRY. • LABEL REGULATED CONTAINERS CLEARLY AND VISIBLY.
- INSPECT STORAGE AREAS WEEKLY. COVER REGULATED CONTAINERS IN OUTSIDE STORAGE AREAS.
 WHEREVER POSSIBLE, KEEP REGULATED CONTAINERS THAT ARE STORED OUTSIDE MORE THAN 50 FEET FROM
- SURFACE WATER AND STORM DRAINS, 75 FEET FROM PRIVATE WELLS, AND 400 FEET FROM PUBLIC WELLS. SECONDARY CONTAINMENT IS REQUIRED FOR CONTAINERS CONTAINING REGULATED SUBSTANCES STORED OUTSIDE, EXCEPT FOR ON PREMISE USE HEATING FUEL TANKS, OR ABOVEGROUND OR UNDERGROUND
- STORAGE TANKS OTHERWISE REGULATED. (2) THE FUEL HANDLING REQUIREMENTS SHALL INCLUDE:
- EXCEPT WHEN IN USE, KEEP CONTAINERS CONTAINING REGULATED SUBSTANCES CLOSED AND SEALED.
- PLACE DRIP PANS UNDER SPIGOTS, VALVES, AND PUMPS.
 HAVE SPILL CONTROL AND CONTAINMENT EQUIPMENT READILY AVAILABLE IN ALL WORK AREAS. USE FUNNELS AND DRIP PANS WHEN TRANSFERRING REGULATED SUBSTANCES.
- PERFORM TRANSFERS OF REGULATED SUBSTANCES OVER AN IMPERVIOUS SURFACE. (3) THE TRAINING OF ONSITE EMPLOYEES AND THE ON SITE POSTING OF RELEASE RESPONSE INFORMATION DESCRIBING WHAT TO DO IN THE EVENT OF A SPILL OF REGULATED SUBSTANCES.
- (4) FUELING AND MAINTENANCE OF EXCAVATION, EARTHMOVING, AND OTHER CONSTRUCTION RELATED EQUIPMENT WILL COMPLY WITH THE REGULATIONS OF NHDES (NOTE THESE REQUIREMENTS ARE SUMMARIZED IN WD DWGB 22 6: "BEST MANAGEMENT PRACTICES FOR FUELING AND MAINTENANCE OF EXCAVATION AND EARTHMOVING EQUIPMENT" OR ITS SUCCESSOR DOCUMENT).

SITE DEVELOPMENT PLANS

TAX MAP 205 LOT 2

EROSION CONTROL NOTES LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR ADL 325 LITTLE HARBOR ROAD TRUST

1"=80' (11"X17") SCALE: NTSO' (22"X34")

SEPTEMBER 29, 2021



ivil Engineers Structural Engineers raffic Engineers and Surveyors andscape Architects cientists

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com

DR HEG FB C - 19CK JCC CADFILE 47099-01_EROSION_MAIN

Copyright 2022 ©TFMoran, Inc. 48 Constitution Drive, Bedford, N.H. 03110 All rights reserved. These plans and materials may not be copied,


without the prior written permission of Thomas F. Moran. Inc. This plan is not effective unless signed by a duly authorized officer of homas F. Moran, Inc.

duplicated, replicated or otherwise reproduced in any form whatsoever

SECTION VIEW


- I. SILT SOCK SHALL BE FILTREXX $^{\mathsf{M}}$ SILTSOXX $^{\mathsf{M}}$ natural original or approved equivalent. ALL MATERIAL AND SIZES TO MEET FILTREXX SPECIFICATIONS.
- COMPOST MATERIAL SHALL BE DISPERSED ON SITE, AS DETERMINED BY THE ENGINEER. 4. SILT SOCK SHALL BE INSPECTED PERIODICALLY AND AFTER ALL STORM EVENTS, AND REPAIR OR REPLACEMENT SHALL BE PERFORMED AS NEEDED.

FILTREXX™ FILTERSOXX™ STAKING NOT TO SCALE



- 1. FILTER CLOTH WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE SURFACE
- 2. WATER ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
- 3. MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND OR CLEANOLIT OF ANY MEASURES LISED TO TRA SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE
- 4. WASHING WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- 5. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN STORM EVENT.


STABILIZED CONSTRUCTION **ENTRANCE** NOT TO SCALE



STONE CHECK DAM NOT TO SCALE

Copyright 2022 ©TFMoran, Inc. 48 Constitution Drive, Bedford, N.H. 03110 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever

without the prior written permission of Thomas F. Moran, Inc. This plan is not effective unless signed by a duly authorized officer of homas F. Moran, Inc.



- 1. INSTALL PER MANUFACTURER'S SPECIFICATIONS.
- INSPECTION SHOULD OCCUR FOLLOWING ANY RAIN EVENT $> \frac{1}{2}$ " . EMPTY THE SEDIMENT BAG PER MANUFACTURER'S SPECIFICATIONS. 4. REMOVED CAKED ON SILT FROM SEDIMENT BAG AND FLUSH WITH MEDIUM
- SPRAY WITH OPTIMAL FILTRATION. 5. REPLACE BAG IF TORN OR PUNCTURED TO $> \frac{1}{2}$ " DIAMETER ON LOWER

FLEXSTORM CATCH-IT FILTERS

ALL PRODUCTS MANUFACTURED BY INLET & PIPE PROTECTION, INC. A DIVISION OF ADS, INC WWW.INLETFILTERS.COM

(866) 287-8655 INFO@INLETFILTERS.COM

DIKE, IF NECESSARY, TO DIVERT FLOW INTO TRAP SECTION A-A


NOTES

- 1. SEDIMENT TRAP TO BE USED AS NECESSARY TO CONTAIN RUNOFF UNTIL BASINS/PONDS ARE STABILIZED. IF IT IS DETERMINED THAT CONSTRUCTION OF A SEDIMENT TRAP IS WARRANTED, CONSULT WITH ENGINEER TO DETERMINE APPROPRIATE NUMBER AND DIMENSIONS.
- 2. 3,600 CF OF BASIN STORAGE IS REQUIRED FOR EVERY ACRE OF CONTRIBUTING DRAINAGE AREA.

6 x DRAINAGE AREA (ACRES)


SEDIMENT TRAP - ISOMETRIC VIEW SEDIMENT TRAP

INLET PROTECTION



- 1. THE GEOTEXTILE FABRIC SHALL MEET THE DESIGN CRITERIA FOR BEST MANAGEMENT PRACTICE FOR SILT FENCES, OF THE NEW HAMPSHIRE STORMWATER MANUAL, DECEMBER 2008. THE HEIGHT OF THE BARRIER SHALL NOT EXCEED 36 INCHES.
- 3. WHEN JOINTS ARE NECESSARY, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH
- A MINIMUM 6-INCH OVERLAP, AND SECURELY SEALED. SEE MANUFACTURER'S RECOMMENDATIONS. 4. POSTS SHALL BE SPACED A MAXIMUM OF 10 FEET APART AT THE BARRIER LOCATION AND DRIVEN SECURELY INTO THE GROUND (MINIMUM OF 16 INCHES). WHEN EXTRA STRENGTH FABRIC IS USED WITHOUT THE WIRE
- SUPPORT FENCE, POST SPACING SHALL BE AS MANUFACTURER RECOMMENDS. 5. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 6 INCHES WIDE AND 6 INCHES DEEP ALONG THE LINE OF
- POSTS AND UPSLOPE FROM THE BARRIER IN ACCORDANCE WITH RECOMMENDATIONS. 6. THE FABRIC SHALL NOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE, AND WILL EXTEND TO A MINIMUM OF 8 INCHES INTO THE TRENCH. FILTER FABRIC SHALL NOT BE STAPLED INTO
- 7. THE TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE FILTER FABRIC. 8. FILTER BARRIERS SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE
- THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED. 9. FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL, AND AT LEAST DAILY DURING
- PROLONGED RAINFALL, ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY. 10. SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL BE NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY. 11. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE-THIRD THE HEIGHT OF THE
- 12. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED, SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.


SILT FENCE



NOTES

- 1. INSTALL AT DISTURBED LOCATIONS WITH 2:1 SLOPES OR GREATER AND AS INDICATED PER PLANS.
- 2. BEGIN AT THE TOP OF BLANKET INSTALLATION AREA BY ANCHORING BLANKET IN A 6" DEEP TRENCH. BACKFILL AND COMPACT TRENCH AFTER STAPLING.
- 3. ROLL THE BLANKET DOWN THE SLOPE OR SWALE IN THE DIRECTION OF THE WATER FLOW.
- 4. THE EDGES OF BLANKETS MUST BE STAPLED WITH APPROX. 4 INCH OVERLAP WHERE 2 OR MORE STRIP WIDTHS ARE REQUIRED.
- 5. WHEN BLANKETS MUST BE SPLICED DOWN THE SWALE, PLACE BLANKET END OVER END WITH 6 INCH (MIN.) OVERLAP AND ANCHOR DOWN SLOPE BLANKET IN A 6 INCH DEEP TRENCH.
- 6. BLANKET SHALL BE NORTH AMERICAN GREEN C125BN, EAST COAST EROSION CONTROL ECC-2B, AMERICAN EXCELSIOR COMPANY CURLEX III FIBRENET, ROLANKA GEONATURAL EROSION & SEDIMENT CONTROL MATTE JUTEMAT OR BIOD-OCF 30, OR APPROVED EQUAL.
- 7. BLANKET SHALL BE PLACED WITHIN 24-HRS AFTER SOWING SEE IN THE AREA BEING COVERED

EROSION CONTROL BLANKET



A. BURY THE TOP END OF THE

JUTE STRIPS IN A TRENCH 6" OR

- 1. MATTING SHALL BE INSTALLED PER MANUFACTURERS SPECIFICATIONS,
- INCLUDING STAPLE PATTERNS. 2. STAPLES SHALL BE BIODEGRADABLE.


JUTE MATTING NOT TO SCALE

MAINTENANCE:

NOT TO SCALE


THE OUTLET PROTECTION SHOULD BE CHECKED AT LEAST ANNUALLY AND AFTER EVERY MAJOR STORM. IF THE RIP RAP HAS BEEN DISPLACED, UNDERMINED OR DAMAGED, IT SHOULD BE CHECKED TO SEE THAT EROSION IS NOT OCCURRING. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS, AND SEDIMENT THAT COULD CHANGE FLOW PATTERNS AND/OR TAILWATER DEPTHS ON THE PIPES. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE OUTLET PROTECTION APRON.

- 1. THE SUBGRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP RAP SHALL BE
- 2. THE ROCK OR GRAVEL USED FOR FILTER OR RIP
- 3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12".
- 4. STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.



CONSTRUCTION SPECIFICATIONS:


- PREPARED TO THE LINES AND GRADES SHOWN ON
- RAP SHALL CONFORM TO THE SPECIFIED GRADATION.
- 5. ADD ANIMAL SCREEN TO FLARED END SECTION



3.00 TO 4.50 0.90 TO 1.50

RIP RAP AND FLARED END SECTION WITH OUTLET PROTECTION

NOT TO SCALE



REV. DATE

SCALE: NTS

DESCRIPTION

SITE DEVELOPMENT PLANS


TAX MAP 205 LOT 2

DETAILS

LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR **ADL 325 LITTLE HARBOR ROAD TRUST**

SEPTEMBER 29, 2021




Seacoast Division Civil Engineers Structural Engineers raffic Engineers and Surveyors andscape Architects

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com

DR HEG FB


C - 20CK JCC CADFILE 47099-01_DETAILS_MAIN

NOT TO SCALE



PEASTONE GRAVEL DRIVEWAY

NOT TO SCALE



STANDARD DUTY PAVEMENT


SEE GRADING & EROSION CONTROL PLAN FOR PAVEMENT SLOPE AND CROSS-SLOPE. 2. PROVIDE CLEAN BUTT TO EXISTING PAVEMENT- USE TACK COAT. A TACK COAT SHALL ALSO BE PLACED BETWEEN GRAVEL COURSE AND SUCCESSIVE LAYERS OF BITUMINOUS CONCRETE. SPECIFICALLY, A TACK COAT SHALL BE PLACED ATOP THE BINDER COURSE PAVEMENT PRIOR TO PLACING THE WEARING COURSE.

OVERLAY

- 3. REMOVE ALL LOAM AND/OR YIELDING MATERIAL BELOW PAVEMENT. 4. BITUMINOUS MATERIALS SHALL CONFORM TO NHDOT SPECIFICATION SECTION 401.
 5. BITUMINOUS CONCRETE SHALL BE COMPACTED TO AT LEAST 92.5% OF THEORETICAL MAXIMUM
- DENSITY AS DETERMINED BY ASTM D2041 OR AASHTO T209. PLACEMENT TEMPERATURES OF BITUMINOUS CONCRETE MIXES, IN GENERAL, RANGE BETWEEN 270 AND 310 DEGREES FAHRENHEIT
- 6. PAVEMENT BASE COURSE AGGREGATE SHALL CONFORM TO NHDOT SPECIFICATION SECTION 304, ITEM 304.3 AND COMPACTED TO A MINIMUM OF 95% OF MODIFIED PROCTOR MAXIMUM DRY DENSITY. 7. PAVEMENT SUBBASE COURSE AGGREGATE AND AGGREGATE FOR SUBGRADE REPAIR AREAS SHALL BE SUITABLE FOR USE AS STRUCTURAL FILL AND BE PROOF ROLLED AND COMPACTED TO 95%
- MODIFIED PROCTOR MAXIMUM DRY DENSITY. 8. THE EXPOSED SOIL SUBGRADE SHOULD BE PROOF ROLLED PRIOR TO THE PLACEMENT OF SUBBASE GRAVEL, AND SOFT AREAS SHOULD BE REPAIRED AND REPLACED.
- 9. ALL PARKING SPACES SHALL BE STANDARD DUTY. ALL OTHER LOCATIONS SHALL BE HEAVY DUTY.


PAVEMENT SECTIONS


NOT TO SCALE



DOWNSPOUT INFILTRATION

NOT TO SCALE





REFER TO LANDSCAPE ARCHITECTURE FOR ADDITIONAL DETAIL AND SPECIFIC SURFACE TREATMENT.


. PERMEABLE PAVERS SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. . INSTALLATION OF PERMEABLE PAVER SECTION SHALL BEGIN AT LOWEST GRADE AND END AT HIGHEST GRADE.

1. PERMEABLE PAVERS SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. PERMEABLE PAVERS FUNCTION AS AN EFFECTIVE STORMWATER TREATMENT SYSTEM AND REMAIN CLOG-FREE FOR YEARS WITH REASONABLE GOOD HOUSEKEEPING PRACTICES.

- KEEP THE PAVEMENT FREE OF LEAVES, WEEDS, AND SEDIMENT. 3. AVOID THE USE OF SAND IN THE WINTER; IF USED, SPREAD SPARINGLY. 4. PERIODICALLY SWEEP THE OPENINGS TO REMOVE CRUST THAT FORMS ON THE SURFACE. A STIFF BRISTLE BROOM WORKS WELL FOR RESIDENTIAL WALKS AND DRIVEWAYS. 5. IF PUDDLES RESULT FROM CLOGGING, INFILTRATION RATES CAN BE RESTORED TO 100% CAPACITY BY
- REMOVING THE AGGREGATE FROM THE OPENINGS AND REPLACING IT WITH CLEAN MATERIAL. 6. DO NOT PRESSURE WASH.
- MINIMIZE APPLICATION OF SALT FOR ICE CONTROL. 8. INSPECT ANNUALLY FOR PAVER DETERIORATION.
- 9. MONITOR PERIODICALLY TO ENSURE THAT THE PAVERS DRAIN EFFECTIVELY AFTER STORMS.
- 10. PERIODICALLY ADD JOINT MATERIAL TO REPLACE LOST MATERIAL. 11. MAJOR CLOGGING MAY NECESSITATE REPLACEMENT OF PAVERS AND POSSIBLY FILTER COURSE AND SUB-BASE COURSE.

PERMEABLE PAVER

NOT TO SCALE



 PERMEABLE PAVERS FUNCTION AS AN EFFECTIVE STORMWATER TREATMENT SYSTEM AND REMAIN CLOG-FREE FOR YEARS WITH REASONABLE GOOD HOUSEKEEPING PRACTICES.

KEEP THE PAVEMENT FREE OF LEAVES WEEDS AND SEDIMEN AVOID THE USE OF SAND IN THE WINTER; IF USED, SPREAD SPARINGLY.

 PERIODICALLY SWEEP THE OPENINGS TO REMOVE CRUST THAT FORMS ON THE SURFACE. A STIFF BRISTLE BROOM WORKS WELL FOR RESIDENTIAL WALKS AND DRIVEWAYS. • IF PUDDLES RESULT FROM CLOGGING, INFILTRATION RATES CAN BE RESTORED TO 100% CAPACITY BY REMOVING THE AGGREGATE FROM THE OPENINGS AND REPLACING IT WITH CLEAN MATERIAL.


• DO NOT PRESSURE WASH. MINIMIZE APPLICATION OF SALT FOR ICE CONTROL.

• INSPECT ANNUALLY FOR PAVER DETERIORATION. . MONITOR PERIODICALLY TO ENSURE THAT THE PAVERS DRAIN EFFECTIVELY AFTER STORMS. PERIODICALLY ADD JOINT MATERIAL TO REPLACE LOST MATERIAL.

 MAJOR CLOGGING MAY NECESSITATE REPLACEMENT OF PAVERS AND POSSIBLY FILTER COURSE AND SUB-BASE COURSE.

PERMEABLE PAVER DRIVEWAY

NOT TO SCALE



GENERAL NOTES


- 1. THIS DETAIL IS ONLY FOR WALLS LESS THAN 4 FEET IN HEIGHT. 2. WALL DESIGNS SHALL CONSIDER EFFECTS OF SLOPE, TRAFFIC
- LOADS, AND/OR BUILDING LOADS AS REQUIRED. 3. BLOCK COLÓR SHALL BE DETERMINED BY OWNERS REPRESENTATIVE
- 4. FINAL WALL DESIGN SHALL BE SUBJECT TO THE RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEER.
- 5. IF CONDITIONS ARE DIFFERENT THAN THOSE STATED IN THESE DRAWINGS AND SPECIFICATIONS, THE CONTRACTOR MUST CONTACT THE DESIGN ENGINEER PRIOR TO PROCEEDING WITH THE CONSTRUCTION OF THE WALL.


MANUFACTURER'S DESIGN

- 1. DESIGN SHALL BE FROM THE WALL MANUFACTURER. 2. DESIGN CALCULATIONS AND PLANS SHALL BE SUBMITTED TO THE OWNER AND ENGINEER OF RECORD FOR APPROVAL
- 3. DESIGN CALCULATIONS TO INCLUDE SAFETY FACTORS AGAINST OVERTURNING, SLIDING, BEARING CAPACITY, GEOGRID PULLOUT AND GLOBAL STABILITY.
- 4. THE WALL DESIGN ENGINEER SHALL COMPLETE SUFFICIENT INSPECTIONS DURING CONSTRUCTION TO CERTIFY WORK IS COMPLETE IN ACCORDANCE

- CONTRACTOR SHALL DIRECT SURFACE RUNOFF AWAY FROM THE WALL DURING CONSTRUCTION.
- ANY SURFACE DRAINAGE FEATURES, FINISH GRADING, PAVEMENT OR OTHER SURFACE TREATMENT SHALL BE INSTALLED IN THE AREA OF THE WALL CONCURRENTLY WITH WALL CONSTRUCTION

UNREINFORCED RETAINING WALL (MODULAR CONCRETE UNIT)






MANHOLES SHALL MEET NHDOT SPECIFICATIONS.

. ALL COMPONENTS SHALL BE DESIGNED FOR HS-20 LOADING -. REINFORCING SHALL CONFORM TO ASTM 185 OR ASTM 1497 & ASTM A615, GRADE 60. 5. ALL CONCRETE SHALL BE NHDOT CLASS A.

SLAB TOP MANHOLE NOT TO SCALE



- CAP (IF END OF LINE ONLY)

SEE UTILITY OR DRAINAGE

PLANS FOR LOCATION

MANHOLE FRAME AND COVER NOT TO SCALE

SS HARD BRICK

BRICK RISERS (IF REQUIRED)

SEE STRUCTURE DETAILS

ASTM C32-05, CLAY OR SHALE




39-1/4"

SECTION A-A

DETAILS

LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR **ADL 325 LITTLE HARBOR ROAD TRUST**





Civil Engineers Structural Engineers raffic Engineers and Surveyors andscape Architects cientists


170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com

SEPTEMBER 29, 2021


DR HEG FB C - 21CK JCC CADFILE 47099-01_DETAILS_MAIN



NOT TO SCALE




CHLORINE INJECTION CONNECTION



- TAPPING SLEEVES SHALL BE STAINLESS STEEL (SS) WITH SS HARDWARE.
- ALL PIPE SHOULD HAVE A MINIMUM DEPTHS OF 6'FROM TOP OF PIPE TO FINISH GRADE PER NHDOT REQUIREMENTS WITHIN THE RIGHT OF WAY.


3. PRECAST CONCRETE THRUST BLOCK TO BE USED, SIZE TO BE BASED ON SIZE OF FITTING AND PRESSURE IN WATERMAIN.




Copyright 2022 ©TFMoran, Inc. 48 Constitution Drive, Bedford, N.H. 03110

homas F. Moran, Inc.

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc. This plan is not effective unless signed by a duly authorized officer of




BURIED GATE VALVE NOT TO SCALE





- 1. ALL MATERIAL, INSTALLATION PROCEDURES, MANUFACTURERS, AND DIMENSIONAL REQUIREMENTS SHALL CONFORM TO PORTSMOUTH'S INFRASTRUCTURE DESIGN STANDARD AND PORTSMOUTH DPW'S ESTABLISHED RULES AND PROCEDURES.
- IN LOCATIONS WITH EXISTING FILL SOILS, CONSULT WITH THE GEOTECHNICAL ENGINEER FOR METHODS TO PREPARE STABLE SUBGRADE AND REMOVAL OF MATERIAL IF NECESSARY. SUITABLE MATERIAL SHALL BE THE NATURAL MATERIAL EXCAVATED DURING THE COURSE OF CONSTRUCTION, BUT SHALL EXCLUDE DEBRIS, PIECES OF PAVEMENT, ORGANIC MATTER, TOP SOIL, ALL WET OR SOFT MUCK, PEAT OR CLAY, ALL EXCAVATED LEDGE MATERIAL, AND ALL ROCKS OVER 6" IN THE LARGEST DIMENSION, OR ANY MATERIAL WHICH, AS DETERMINED BY THE ENGINEER, WILL NOT PROVIDE SUFFICIENT SUPPORT OR MAINTAIN THE COMPLETED CONSTRUCTION IN A STABLE CONDITION. SUITABLE MATERIAL SHALL BE PLACED IN 12" LIFTS AND COMPACTED TO 95% STANDARD PROCTOR DENSITY.
- RIGID STYROFOAM INSULATION (DOW HI-40 OR EQUAL) WITH 6" CLEAN SAND BLANKET AROUND WATER PIPE WHERE WATER AND DRAIN PIPE SEPARATION IS LESS THAN 18". TRACER WIRE SPECIFIED FOR NON-METALLIC WATER LINES SHALL BE INSTALLED BELOW AND TO THE SIDE OF THE PIPE AND PER THE MANUFACTURER REQUIREMENTS. TRACER WIRE PRODUCT SHALL BE SELECTED FOR OPEN CUT INSTALLATION TECHNIQUE.

WATER TRENCH

NOT TO SCALE







- 1. A 10 FOOT MINIMUM EDGE TO EDGE HORIZONTAL SEPERATION SHALL BE PROVIDED BETWEEN ALL WATER/STORMWATER AND SANITARY SEWER LINES. AN 18" MINIMUM OUTSIDE TO OUTSIDE VERTICAL SEPARATION SHALL BE PROVIDED AT ALL WATER/STORMWATER AND
- 2. PROTECTION OF WATER SUPPLIES
- 1. THERE SHALL BE NO PHYSICAL CONNECTION BETWEEN A PUBLIC OR PRIVATE POTABLE WATER SUPPLY SYSTEM AND A SEWER OR SEWER APPURTENANCE WHICH WOULD PERMIT THE PASSAGE OF SEWAGE OR POLLUTED WATER INTO THE POTABLE SUPPLY. NO WATER PIPE SHALL PASS THROUGH OR COME IN CONTACT WITH ANY PART OF A SEWER OR
- SEWER MANHOLE. 2. NO SEWER SHALL BE LOCATED WITHIN THE WELL PROTECTED RADII ESTABLISHED IN ENV-WS 300 FOR ANY PUBLIC WATER SUPPLY WELLS OR WITHIN 100 FEET OF ANY
- PRIVATE WATER SUPPLY WELL. 3. SEWERS SHALL BE LOCATED AT LEAST 10 FEET HORIZONTALLY FROM ANY EXISTING OR
- PROPOSED WATER MAIN. 4. A DEVIATION FROM THE SEPARATION REQUIREMENTS OF (2) OR (3) ABOVE SHALL BE ALLOWED WHERE NECESSARY TO AVOID CONFLICT WITH SUBSURFACE STRUCTURES, UTILITY CHAMBERS. AND BUILDING FOUNDATIONS, PROVIDED THAT THE SEWER IS CONSTRUCTED IN ACCORDANCE WITH THE FORCE MAIN CONSTRUCTION REQUIREMENTS SPECIFIED IN
- 5. WHENEVER SEWERS MUST CROSS WATER MAINS, THE SEWER SHALL BE CONSTRUCTED AS
- 1. VERTICAL SEPARATION OF THE SEWER AND WATER MAIN SHALL BE NOT LESS THAN 18 INCHES, WITH WATER ABOVE SEWER; AND 2. SEWER PIPE JOINTS SHALL BE LOCATED AT LEAST 6 FEET HORIZONTALLY FROM THE

WATER/STORMWATER & SEWER CROSSING

REV. DATE

NOT TO SCALE




3 2/15/2022 REVISED PER NHDES & UTILITIES PER TAC

1 | 11/23/2021 | REVISED PER NHDES & PROJECT COORDINATION | HEG JCC

DESCRIPTION



DR CK



BEARING AREA REQUIRED, SQUARE FEET

TYPE OF BEARING MATERIAL AND ALLOWABLE LOADS, pfs	4" AND LESS DEGREE BEND			6" AND 8" DEGREE BEND			10" AND 12" DEGREE BEND					
	$11\frac{1}{4}$	$22\frac{1}{2}$	45	90	$11\frac{1}{4}$	$22\frac{1}{2}$	45	90	$11\frac{1}{4}$	$22\frac{1}{2}$	45	90
LOOSE SAND OR MEDIUM CLAY — 2,000	1.0	2.0	2.7	4.0	1.5	3.0	6.0	10.0	3.0	6.2	12.0	22.0
PACKED GRAVEL AND SAND — 4,000	1.0	1.0	1.5	2.0	1.0	1.5	3.0	5.0	1.5	3.1	6.0	11.0
ROCK - 10,000	1.0	1.0	1.0	1.0	1.0	1.0	1.2	2.0	1.0	1.3	2.4	4.4

		E	BEARIN	G AREA	A REQU	JIRED,	SQUAR	E FEE	Γ
	TYPE OF BEARING MATERIAL AND ALLOWABLE LOADS, pfs	1	14" AND 16" 18" AND 20" DEGREE BEND DEGREE BEND OR DEFLECTION OR DEFLECTION)
		$11\frac{1}{4}$	$22\frac{1}{2}$	45	90	$11\frac{1}{4}$	$22\frac{1}{2}$	45	90
	LOOSE SAND OR MEDIUM CLAY - 2,000	6.0	12.0	22.5	40.0	9.5	19.0	37.0	67.0
	PACKED GRAVEL AND SAND — 4,000	3.0	6.0	11.3	20.0	4.8	9.5	18.5	33.5
	ROCK - 10,000	1.2	2.4	4.5	8.0	2.0	3.8	7.4	13.5

- 1. ALL MATERIAL, INSTALLATION PROCEDURES, MANUFACTURERS, AND DIMENSIONAL REQUIREMENTS SHALL CONFORM TO PORTSMOUTH'S INFRASTRUCTURE DESIGN STANDARDS AND PORTSMOUTH DPW'S ESTABLISHED
- 2. A PRECAST CONCRETE THRUST BLOCK IS PREFERRED BY PORTSMOUTH DPW AND MUST CONFORM TO
- PORTSMOUTH DPW'S INFRASTRUCTURE DESIGN STANDARDS. POUR THRUST BLOCKS AGAINST UNDISTURBED MATERIAL, WHERE TRENCH WALL HAS BEEN DISTURBED. EXCAVATE LOOSE MATERIAL AND EXTEND THRUST BLOCK TO UNDISTURBED MATERIAL. NO PIPE JOINTS
- SHALL BE COVERED WITH CONCRETE.
- ON BENDS AND TEES, EXTEND THRUST BLOCKS FULL LENGTH OF FITTING.
 PLACE BOARD IN FRONT OF ALL PLUGS BEFORE POURING THRUST BLOCKS. PLACE ROOFING FELT AROUND HYDRANT ELBOW BEFORE POURING THRUST BLOCKS AND ENSURE CONCRETE DOES NOT PLUG HYDRANT

THRUST BLOCKS

NOT TO SCALE

SITE DEVELOPMENT PLANS

TAX MAP 205 LOT 2

DETAILS

LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR

ADL 325 LITTLE HARBOR ROAD TRUST


SEPTEMBER 29, 2021



Civil Engineers Structural Engineers Traffic Engineers and Surveyors andscape Architects

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com

DR HEG FB C - 22CK JCC CADFILE 47099-01_DETAILS_MAIN



- 2. BARRELS, CONE SECTIONS AND CONCRETE GRADE RINGS SHALL BE PRECAST REINFORCED CONCRETE AND SHALL CONFORM ENV-WQ 704.12 & 704.13.
- 3. PRECAST CONCRETE BARREL SECTIONS, CONES AND BASES SHALL CONFORM TO ASTM C478-06.
- 4. BASE SECTIONS SHALL BE OF MONOLITHIC CONSTRUCTION TO A POINT AT LEAST 6 INCHES ABOVE THE CROWN OF THE INCOMING PIPE.
- 5. MANHOLE CONE SECTIONS SHALL BE ECCENTRIC IN SHAPE.
- 6. ALL PRECAST SECTIONS AND BASES SHALL HAVE THE DATE OF MANUFACTURE AND THE NAME OR TRADEMARK OF THE MANUFACTURER IMPRESSED OR INDELIBLY MARKED ON THE INSIDE WALL.
- 7. ALL PRECAST SECTIONS AND BASES SHALL BE COATED ON THE EXTERIOR WITH A BITUMINOUS DAMP-PROOFING COATING.
- 8. SHALLOW MANHOLE: IN LIEU OF A CONE SECTION, WHEN MANHOLE DEPTH IS LESS THAN 6 FEET, A REINFORCED CONCRETE SLAB COVER MAY BE USED HAVING AN ECCENTRIC ENTRANCE OPENING AND CAPABLE OF SUPPORTING H-20 LOADS.
- 9. HORIZONTAL JOINTS BETWEEN SECTIONS OF PRECAST CONCRETE BARRELS SHALL BE OF AN OVERLAPPING TYPE, SEALED FOR WATERTIGHTNESS USING A DOUBLE ROW OF AN ELASTOMERIC OR MASTIC-LIKE SEALANT. APPROVED ELASTOMERIC SEALANTS ARE:


SIKAFLEX-12-SL


SONNEBORN BUILING PRODUCTS-SONOLASTIC SL-1


- 10. THE MINIMUM INTERNAL DIAMETER OF MANHOLES SHALL BE 48 INCHES. FOR SEWERS LARGER THAN 24-INCH DIAMETER. MANHOLE DIAMETERS SHALL BE INCREASED SO AS TO PROVIDE AT LEAST 12-INCHES OF SHELF ON EACH SIDE OF THE SEWER.
- 11. LEAKAGE TEST SHALL BE PERFORMED IN ACCORDANCE TO ENV-WQ 704.17.
- (a) ALL MANHOLES SHALL BE TESTED FOR LEAKAGE USING A VACUUM TEST IN ACCORDANCE WITH THE ASTM C1244 STARNDARD IN EFFECT WHEN THE TESTING IS PERFORMED. (b) THE MANHOLE VACUUM TEST SHALL CONFORM TO THE FOLLOWING:
- . THE INITIAL VACUUM GUAGE TEST PRESSURE SHALL BE 10 INCHES Hg 2. THE MINIMUM ACCEPTABLE TEST HOLD TIME FOR 1-INCH Hg PRESSURE DROP TO 9 INCHES
- A. NOT LESS THAN 2 MINUTES FOR MANHOLES LESS THAN 10 FEET DEEP. B. NOT LESS THAN 2.5 MINUTES FOR MANHOLES 10 TO 15 FEET DEEP.
- C. NOT LESS THAN 3 MINUTES FOR MANHOLES MORE THAN 15 FEET DEEP. (c) THE MANHOLE SHALL BE REPAIRED AND RETESTED IF THE TEST HOLD TIMES FAIL TO
- ACHIEVE THE ACCEPTANCE LIMITS SPECIFIED IN (b) ABOVE. (d) INVERTS AND SHELVES SHALL NOT BE INSTALLED UNTIL AFTER SUCCESSFUL TESTING IS
- (e) FOLLOWING COMPLETION OF THE LEAKAGE TEST, THE FRAME AND COVER SHALL BE PLACED ON TOP OF THE MANHOLE OR SOME OTHER MEANS USED TO PREVENT
- 12. ACCIDENTAL ENTRY BY UNAUTHORIZED PERSONS, CHILDREN OR ANIMALS, UNTIL THE CONTRACTOR IS READY TO MAKE FINAL ADJUSTMENT TO GRADE.
- 13. BRICK MASONRY FOR SHELF, INVERT AND GRADE ADJUSTMENT SHALL COMPLY WITH ASTM C32-05, CLAY OR SHALE, FOR GRADE SS HARD BRICK.
- MORTAR SHALL BE COMPOSED OF PORTLAND CEMENT AND SAND WITH OR WITHOUT HYDRATED LIME ADDITION. PROPORTIONS IN MORTAR OF PARTS BY VOLUMES SHALL BE:
- (a) 4.5 PARTS SAND AND 1.5 PARTS CEMENT; OR (b) 4.5 PARTS SAND, 1 PART CEMENT AND 0.5 PART HYDRATED LIME
- CEMENT SHALL BE TYPE II PORTLAND CEMENT CONFORMING TO ASTM C150-05. HYDRATED LIME SHALL BE TYPE S CONFORMING TO ASTM C207-06 "STANDARD SPECIFICATIONS FOR HYDRATED LIME FOR MASONRY PURPOSES". SAND SHALL CONSIST OF INERT NATURAL SAND CONFORMING TO ASTM C33-03 "STANDARD SPECIFICATIONS FOR CONCRETE, FINE AGGREGATES".
- 14. INVERTS AND SHELVES: MANHOLES SHALL HAVE A BRICK PAVED OR PRECAST CONCRETE SHELF AND THE INVERTS SHALL BE LAID OUT IN CURVES OF THE LONGEST RADIUS POSSIBLE TANGENT TO THE CENTER LINE OF THE SEWER PIPES. SHELVES SHALL BE CONSTRUCTED TO THE ELEVATION OF THE HIGHEST PIPE CROWN AND SLOPE TO DRAIN TOWARD THE FLOWING THROUGH CHANNEL. UNDERLAYMENT OF INVERT AND SHELF SHALL CONSIST OF BRICK MASONRY.
- 15. FRAMES AND COVERS: MANHOLES FRAMES AND COVERS SHALL BE OF HEAVY DUTY DESIGN, CLASS 30, CONFORMING TO ASTM A48/48M AND PROVIDE A 30-INCH CLEAR OPENING. 3-INCH WORD (MINIMUM HEIGHT) LETTERS "SEWER" SHALL BE PLAINLY CAST INTO THE TOP SURFACE. THE CASTING SHALL BE OF EVEN GRAINED CAST IRON, SMOOTH, AND FREE FROM SCALE, LUMPS, BLISTERS, SAND HOLES AND DEFECTS. CONTACT SURFACES OF COVERS AND FRAMES SHALL BE MACHINED AT THE FOUNDRY TO PREVENT ROCKING OF COVERS IN ANY ORIENTATION.
- 16. BEDDING: PRECAST BASES SHALL BE PLACED ON A 6-INCH LAYER OF COMPACTED BEDDING MATERIAL THAT CONFORMS TO ASTM C33-03 NO. 67 STONE AND FREE FROM CLAY, LOAM AND ORGANNIC MATTER. THE EXCAVATION SHALL BE PROPERLY DEWATERED WHILE PLACING BEDDING MATERIAL AND SETTING OF THE BASE OR POURING CONCRETE. WATER-STOPS SHALL BE USED AT THE HORIZONTAL JOINT OF THE CAST-IN-PLACE MANHOLES.

100% PASSING 1" SCREEN 90-100% PASSING 3/4" SCREEN 20-55% PASSING 3/8" SCREEN 0-10% PASSING #4 SIEVE 0-5% PASSING #8 SIEVE

- 17. FLEXIBLE JOINT: A FLEXIBLE JOINT SHALL BE PROVIDED WIGHIN THE FOLLOWING DISTANCES FROM ANY MANHOLE CONNECTION: (a) WITHIN 48 INCHES FOR REINFORCED CONCRETE PIPE (RCP). (b) WITHIN 60 INCHES FOR PVC PIPE LARGER THAN 15" DIAMETER.
- 18. NO FLEXIBLE JOINT SHALL BE REQUIRED FOR DUCTILE IRON PIPE OR PVC PIPE UP THROUGH 15-INCH DIAMETER.
- 19. PIPE TO MANHOLE JOINTS SHALL BE ONLY AS FOLLOWS:
- A. ELASTOMERIC, RUBBER SLEEVE WITH WATERTIGHT JOINTS AT THE MANHOLE OPENING AND PIPE SURFACES.
- B. CAST INTO WALL OR SECUREED WITH STAINLESS STEEL CLAMPS.
- C. ELASTOMERIC SEALING RING CAST IN THE MANHOLE OPENING WITH THE SEAL FORMED ON THE SURFACE OF THE PIPE BY COMPRESSION OF THE RING.
- D. ON-SHRINK GROUTED JOINTS WHERE WATERTIGHT BONDING TO THE MANHOLE AND PIPE CAN BE OBTAINED.
- 20. THE INVERT OF THE INCOMING PIPE SHALL BE NO MORE THAN 6 INCHES ABOVE THE OUTGOING PIPE UNLESS A DROP ENTRY IS USED.







KOR-N-SEAL JOINT SLEEVE

LOCK-JOINT FLEXIBLE MANHOLE SLEEVE (OR ACCEPTABLE SUBSTITUTE)

DETAIL "A" — PIPE TO MANHOLE JOINTS

NOTES

- ADJUST TO GRADE WITH BRICK OR

MAXIMUM 12" ADJUSTMENT. BRICK

- DOUBLE SEALED JOINTS WITH A DOUBLE ROW OF SEALANT

KNOCKOUTS FOR

FROM TOP AND

PIPES MINIMUM 4"

BOTTOM OF BASE

(SEE NOTE 7)

BRICK MASONRY PAVED

(SEE SECTION NOTE #1 AND

SECTIONS A-A AND B-B)

SHELF AND INVERT

OR CONCRETE RINGS SHALL BE

INSTALLED WITH NO OVERHANG.

PRECAST CONCRETE RINGS

PRECAST REINFORCED

- CONCRETE MANHOLE

LIFTING HOLES(TYP)

(FILL WITH MORTAR)

-PRECAST REINFORCED

GROOVE RISERS AS

CONCRETE TONGUE &


ECCENTRIC CONE

- WELDED WIRE

FABRIC(TYP)

REQUIRED

- 1. UNDERLAYMENT OF MANHOLE INVERT AND SHELF SHALL BE BRICK MASONRY PER ENV-WQ 704.12(K).
- 2. INVERT AND SHELF TO BE PLACED AFTER EACH LEAKAGE TEST.
- 3. CARE SHALL BE TAKEN TO INSURE THAT THE BRICK INVERT IS A SMOOTH CONTINUATION OF THE SEWER INVERT.
- 4. INVERT BRICKS SHALL BE LAID ON EDGE.
- 5. PRECAST CONCRETE MANHOLES SHALL MEET AASHTO M199-93/ ASTM C478-90B, RATED FOR HS-20 LOADING WITH CONCRETE STRENGTH OF 4000 PSI OR GREATER.
- 6. ALL PRECAST SECTIONS AND BASES SHALL BE COATED ON THE EXTERIOR WITH A BITUMINOUS DAMP-PROOFING COATING.
- 7. HORIZONTAL JOINTS BETWEEN SECTIONS OF PRECAST CONCRETE BARRELS SHALL BE OF AN OVERLAPPING TYPE, SEALED FOR WATERTIGHTNESS USING A DOUBLE ROW OF AN ELASTOMERIC OR MASTIC-LIKE
- ALL GASKETS AND SEALANTS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS' WRITTEN INSTRUCTIONS.
- STATE OF NEW HAMPSHIRE APPROVED PRODUCTS A) SIKAFLEX-12-SL
- B) SONNEBORN BUILDING PRODUCTS SONOLASTIC SL-1
- 8. MANHOLE STEPS ARE PROHIBITED BY TILTON SEWER COMMISSION.



SEE MANHOLE FRAME &

COVER DETAIL

2'-6"ø(MIN)


4'-0" (IF DEPTH <15 FT)


5'-0 (IF DEPTH >15 F


OR MATCH EXISTING

TYPICAL SECTION


⊸-3"(MIN)







(WHICHEVER IS GREATER) 1. CONSTRUCT SECTION FOR ALL SANITARY SEWERS AND SOLID DRAINAGE PIPES. **UTILITY TRENCH**



STANDARD MANHOLE

NOT TO SCALE



3 2/15/2022 REVISED PER NHDES & UTILITIES PER TAC

1 | 11/23/2021 | REVISED PER NHDES & PROJECT COORDINATION | HEG JCC

DESCRIPTION

2 2/2/2022 REVISED PER NHDES & UPDATE SURVEY/UTIL

REV. DATE



DR CK

SITE DEVELOPMENT PLANS

NOT TO SCALE

PAVED AREA

SEE PAVEMENT

BASE SEE PAVEMENT

-COMPACTED

SECTION

CRUSHED STONE FOR FULL WIDTH OF

THE TRENCH UP TO SPRINGLINE OF

PIPE AND 12" BELOW PIPE IN ROCK

PRESHAPED TO A HEIGHT OF 10% OF

THE PIPE DIAMETER. BACKFILL WITH

BEDDING MATERIAL TO 12" ABOVE THE

4" SAND OR CRUSHED STONE

BEDDING BELOW THE PIPE AND

& 12" SAND BLANKET

SECTION

— SUBBASEʻ

LOAM AREA

LOAM & SEEDED

CONSTRUCT WARNIN

TAPE FOR WATER

COMPACTED

RIGID STYROFOAM INSULATION_

(DOW HI-40 OR EQUAL) WITH

COMMON FILL

FINISH SUBGRADE , ---

MAIN INSTALLATIONS+

TAX MAP 205 LOT 2

DETAILS

LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR

ADL 325 LITTLE HARBOR ROAD TRUST

SEPTEMBER 29, 2021



Civil Engineers Structural Engineers Traffic Engineers and Surveyors andscape Architects cientists

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com

DR HEG FB C - 23CK JCC CADFILE 47099-01_DETAILS_MAIN

Copyright 2022 ©TFMoran, Inc. 48 Constitution Drive, Bedford, N.H. 03110

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of

homas F. Moran, Inc.

2) PIPE AND JOINT MATERIALS:

A. PLASTIC SEWER PIPE 1. PIPE AND FITTINGS SHALL CONFORM TO THE FOLLOWING ASTM STANDARDS:

STANDARDS	MATERIAL	APPROVED
D3034	*PVC (SOLID WALL)	8" THROUGH 15" (SDR 35)
F679	PVC (SOLID WALL)	18" THROUGH 27" (T-1 & T-2)
F789	PVC (SOLID WALL)	4" THROUGH 18" (T-1 TO T-3)
F794	PVC (RIBBED WALL)	8" THROUGH 36"
D2680	*ABS (COMPOSITES WALL)	8" THROUGH 15"

*PVC: POLY VINYL CHLORIDE *ABS: ACRYLONITRILE-BUTADIENE-STYRENE

2. JOINTS SEALS FOR PVC PIPE SHALL BE OIL RESISTANT COMPRESSION RINGS OF ELASTOMERIC MATERIAL CONFORMING TO ASTM D-3212 AND SHALL BE PUSH-ON, BELL AND SPIGOT TYPE.

ABS TRUSS PIPE AND FITTINGS SHALL CONFORM TO ASTM D-2680, POLYMER COMPOUNDING SHALL BE TO ASTM D-1788 (CLASS 322).

JOINTS FOR ABS TRUSS PIPE SHALL BE CHEMICAL WELDED COUPLINGS TYPE SC IN ACCORDANCE WITH ASTM D-2680, FORMING A CHEMICAL WELDED JOINT

B. DUCTILE-IRON PIPE, FITTINGS AND JOINTS.

1. DUCTILE IRON PIPE AND FITTINGS SHALL CONFORM TO THE FOLLOWING STANDARDS OF THE UNITED STATES OF AMERICA STANDARDS INSTITUTE A21.50 THICKNESS DESIGN OF DUCTILE IRON PIPE AND WITH ASTM A-536 DUCTILE IRON CASTINGS.

A21.51 DUCTILE IRON PIPE, CENTRIFUGALLY CAST IN METAL MOLDS OR SAND-LINED MOLDS FOR WATER OR OTHER LIQUIDS. 2. JOINTS SHALL BE OF THE MECHANICAL OR PUSH-ON TYPE. JOINTS AND GASKETS A21.11 RUBBER GASKETS JOINTS FOR CAST IRON PRESSURE PIPE & FITTINGS

3) DAMAGED PIPE SHALL BE REJECTED AND REMOVED FROM THE JOB SITE.

4) JOINTS SHALL BE DEPENDENT UPON A NEOPRENE OR ELASTOMERIC GASKET FOR WATER-TIGHTNESS. ALL JOINTS SHALL BE PROPERLY MATCHED WITH THE PIPE MATERIALS USED. WHERE DIFFERING MATERIALS ARE TO BE CONNECTED, AS AT THE STREET SEWER WYE OR AT THE FOUNDATION WALL. APPROPRIATE MANUFACTURED ADAPTERS SHALL BE USED.

5) TEES AND WYES: WHERE A TEE OR WYE IS NOT AVAILABLE IN THE EXISTING STREET SEWER, AN APPROPRIATE CONNECTION SHALL BE MADE, FOLLOWING MANUFACTURERS' INSTRUCTIONS USING A BOLTED, CLAMPED OR EPOXY-CEMENTED SADDLE TAPPED INTO A SMOOTHLY DRILLED OR SAWN OPENING IN THE SEWER. THE PRACTICE OF BREAKING AN OPENING WITH A SLEDGE HAMMER, STUFFING CLOTH OR OTHER SUCH MATERIAL AROUND THE JOINT, OR APPLYING MORTAR TO HOLD THE CONNECTION, AND ANY OTHER SIMILAR CRUDE PRACTICES OR INEPT OR HASTY IMPROVISATIONS WILL NOT BE PERMITTED. THE CONNECTION SHALL BE CONCRETE ENCASED AS SHOWN IN THE DETAIL UP TO AND INCLUDING 15" DIAMETER.

6) SEWER SERVICE INSTALLATION: THE PIPE SHALL BE HANDLED, PLACED AND JOINTED IN ACCORDANCE WITH INSTALLATION GUIDES OF THE APPROPRIATE MANUFACTURER. IT SHALL BE CAREFULLY BEDDED ON A 6 INCH LAYER OF CRUSHED STONE AND/OR GRAVEL AS SPECIFIED IN NOTE 10. BEDDING AND RE-FILL FOR DEPTH OF 12 INCHES ABOVÉ THE TOP OF THE PIPE SHALL BE CAREFULLY AND THOROUGHLY TAMPED BY HAND OR WITH APPROPRIATE MECHANICAL DEVICES.

THE PIPE SHALL BE LAID AT A CONTINUOUS AND CONSTANT GRADE FROM THE STREET SEWER CONNECTION TO THE FOUNDATION AT A GRADE OF NOT LESS THAN 1/8" INCH PER FOOT. PIPE JOINTS MUST BE MADE UNDER DRY CONDITIONS. IF WATER IS PRESENT, ALL NECESSARY STEPS SHALL BE TAKEN TO DEWATER THE TRENCH.

7) TESTING: THE COMPLETED SEWER SERVICE SHALL BE SUBJECTED TO A THIRD PARTY LEAKAGE TEST IN ANY OF THE FOLLOWING MANNERS: (PRIOR TO BACKFILLING)

A. AN OBSERVATION TEE SHALL BE INSTALLED AS SHOWN AND WHEN READY FOR TESTING, AN INFLATABLE BLADDER OR PLUG SHALL BE INSERTED JUST UPSTREAM FROM THE OPENING IN THE TEE. AFTER INFLATION, WATER SHALL BE INTRODUCED INTO THE SYSTEM ABOVE THE PLUG TO A HEIGHT OF 5 FEET ABOVE THE LEVEL OF THE PLUG.

THE PIPE SHALL BE LEFT EXPOSED AND LIBERALLY HOSED WITH WATER, TO SIMULATE, AS NEARLY AS POSSIBLE, WET TRENCH CONDITIONS OR, IF TRENCH IS WET, THE GROUND WATER SHALL BE PERMITTED TO RISE IN THE TRENCH OVER THE PIPE. INSPECTIONS FOR LEAKS SHALL BE MADE THROUGH THE CLEANOUT WITH A FLASHLIGHT.

C. DRY FLUORESCENE DYE SHALL BE SPRINKLED INTO THE TRENCH OVER THE PIPE. IF THE TRENCH IS DRY, THE PIPE SHALL BE LIBERALLY HOSED WITH WATER, OR IF THE TRENCH IS WET, GROUND WATER SHALL BE PERMITTED TO RISE IN THE TRENCH OVER THE PIPE. OBSERVATION FOR LEAKS SHALL BE MADE IN THE FIRST DOWN-STREAM MANHOLE.

LEAKAGE OBSERVED IN ANY ONE OF THE ABOVE ALTERNATE TESTS SHALL BE CAUSE FOR NON-ACCEPTANCE AND THE PIPE SHALL BE DUG-UP IF NECESSARY AND RE-LAID SO AS TO ASSURE WATER TIGHTNESS.

8) ILLEGAL CONNECTIONS: NOTHING BUT SANITARY WASTE FLOW FROM TOILETS, SINKS, LAUNDRY ETC. SHALL BE PERMITTED. ROOF LEADERS, FOOTING DRAINS, SUMP PUMPS OR OTHER SIMILAR CONNECTIONS CARRYING RAIN WATER, DRAINAGE OR GROUND WATER SHALL NOT BE PERMITTED.

9) WATER SERVICE SHALL NOT BE LAID IN SAME TRENCH AS SEWER SERVICE.

10) BEDDING: SCREENED GRAVEL AND/OR CRUSHED STONE FREE FROM CLAY, LOAM, ORGANIC MATERIAL AND MEETING ASTM C33-67.

100% PASSING 1 INCH SCREEN 90%-100% PASSING 3/4 INCH SCREEN 20%-55% PASSING 3/8 INCH SCREEN 0%-10% PASSING #4 SIEVE 0%-5% PASSING #8 SIEVE

WHERE ORDERED BY THE ENGINEER TO STABILIZE THE TRENCH BASE, SCREENED GRAVEL OR CRUSHED STONE 1/2 INCH TO 1 1/2 INCH SHALL BE USED.

11) LOCATION: THE LOCATION OF THE TEE OR WYE SHALL BE RECORDED AND FILED IN THE MUNICIPAL RECORDS. IN ADDITION, A FERROUS METAL ROD OR PIPE SHALL BE PLACED OVER THE TEE OR WYE AS DESCRIBED IN THE TYPICAL "CHIMNEY" DETAIL, TO AID IN LOCATING THE BURIED PIPE WITH A DIP NEEDLE OR PIPEFINDER.

12) CHIMNEYS: IF VERTICAL DROP INTO SEWER IS GREATER THAN 4 FEET, A CHIMNEY SHALL BE CONSTRUCTED FOR THE SEWER CONNECTION. CHIMNEY INSTALLATION AS RECOMMENDED BY THE PIPE MANUFACTURER MAY BE USED IF APPROVED BY THE ENGINEER.

GRAVITY SEWER NOTES

1. MINIMUM SIZE PIPE FOR GRAVITY SEWER SHALL BE 8-INCHES.

*PVC: POLY VINYL CHLORIDE

2. PIPE AND JOINT MATERIALS FOR PLASTIC SEWER PIPE SHALL CONFORM TO THE FOLLOWING ASTM STANDARDS:

APPROVED STANDARDS MATERIAL D3034-04a * PVC (SOLID WALL) 8" THROUGH 15" (SDR 35) 18" THROUGH 27" (T-1 & T-2) F679-03 PVC (SOLID WALL) F794-03 PVC (RIBBED WALL) 8" THROUGH 36" F1760-01(2005)e1 PVC, RECYCLED ALL DIAMETERS

3. PLASTIC SEWER PIPE SHALL HAVE A PIPE STIFFNESS RATING OF AT LEAST 46 POUNDS PER SQUARE INCH AT 5 PERCENT PIPE DIAMETER DEFLECTION, AS MEASURED IN ACCORDANCE WITH ASTM D2412-02 DURING MANUFACTURE.

4. JOINTS SEALS FOR PVC PIPE SHALL BE OIL RESISTANT COMPRESSION RINGS OF ELASTOMERIC MATERIAL CONFORMING TO ASTM D-3212-96(a)(2003)e1 AND SHALL BE PUSH-ON, BELL AND SPIGOT TYPE.

5. DUCTILE-IRON PIPE, FITTINGS AND JOINTS SHALL CONFORM TO THE FOLLOWING STANDARDS OF THE AMERICAN WATER WORKS ASSOCIATION (AWWA).

AWWA C151/A21.51-02 THICKNESS DESIGN OF DUCTILE IRON PIPE AND WITH ASTM A-536-84 (2004) DUCTILE IRON CASTINGS.

AWWA C151/A21.51-02 DUCTILE IRON PIPE, CENTRIFUGALLY CAST IN METAL MOLDS OR SAND-LINED MOLDS FOR WATER OR OTHER LIQUIDS.

JOINTS SHALL BE OF THE MECHANICAL OR PUSH-ON TYPE. JOINTS AND GASKETS SHALL CONFORM TO AWWA C151/A21.11 RUBBER GASKETS JOINTS FOR CAST IRON PRESSURE PIPE & FITTINGS.

6. CONCRETE PIPE SHALL CONFORM TO AWWA C302-04.

7. PRESTRESSED CONCRETE CYLINDER PIPE AND FITTINGS SHALL CONFORM TO AWWA C301-99.

JOINTS SEALS FOR CONCRETE CYLINDER PIPE SHALL BE OIL RESISTANT ELASTOMERIC MATERIAL CONFORMING TO ASWWA C301-99 SPECIFICATIONS.

8. DAMAGED PIPE SHALL BE REJECTED AND REMOVED FROM THE JOB SITE.

9. GRAVITY SEWER PIPE TESTING SHALL BE AS FOLLOWS:

ALL NEW GRAVITY SEWERS SHALL BE TESTED FOR WATER TIGHTNESS BY THE USE OF LOW-PRESSURE AIR

LOW PRESSURE AIR TESTING SHALL BE IN CONFORMANCE WITH:

ASTM F1417-92(2005) "STANDARD TEST METHOD FOR INSTALLATION ACCEPTANCE OF PLASTIC GRAVITY SEWER LINES USING LOW PRESSURE AIR".

UNI-BELL PVC PIPE ASSOCIATION UNI-B-6, "LOW PRESSURE AIR TESTING OF INSTALLED SEWER

10. ALL NEW GRAVITY SEWERS SHALL BE CLEANED AND VISUALLY INSPECTED AND SHALL BE TRUE TO LINE AND GRADE FOLLOWING INSTALLATION AND PRIOR TO USE.

11. ALL PLASTIC SEWER PIPE SHALL BE DEFLECTION TESTED NOT LESS THAN 30 DAYS FOLLOWING INSTALLATION.

12. THE MAXIMUM ALLOWABLE DEFLECTION OF FLEXIBLE SEWER PIPE SHALL BE 5.0 PERCENT OF THE AVERAGE INSIDE

13. TRENCH CONSTUCTION SHALL CONFORM TO THE FOLLOWING:

SEWERS SHALL BE BURIED TO A MINIMUM DEPTH OF 6' BELOW GRADE IN ALL ROADWAY LOCATIONS AND TO A MINIMUM DEPTH OF 4 FEET BELOW GRADE IN ALL CROSS COUNTRY LOCATIONS.

WHERE SEWER LINES CROSS WATER PIPES, A MINIMUM OF 18" VERTICAL SEPARATION BETWEEN THE TWO OUTSIDE PIPE WALLS SHALL BE OBSERVED. AT SEWER/WATER INTERSECTIONS, A MINIMUM OF 6 FEET SHALL BE PROVIDED FROM THE WATER LINE TO THE SEWER PIPE JOINT. 12" SEPARATION BETWEEN THE TWO OUTSIDE PIPE WALLS SHALL BE REQUIRED BETWEEN SEWER LINES AND ALL OTHER PIPES.

TRENCH DIMENSIONS FOR SEWER PIPE LESS THAN 15 INCHES IN DIAMETER. THE ALLOWABLE TRENCH WIDTH AT A PLANE 12 INCHES ABOVE THE PIPE SHALL BE NO MORE THAN 36 INCHES AND FOR PIPE 15 INCHES AND LARGER, THE ALLOWABLE WIDTH SHALL BE EQUAL TO THE PIPES OUTSIDE DIAMETER PLUS 24 INCHES.

PIPE TRENCH BEDDING MATERIAL AND FILL MATERIAL FOR EXCAVATION BELOW GRADE SHALL BE SCREENED GRAVEL OR CRUSHED STONE TO ASTM C33-03 STONE SIZE NO. 67. THE PIPE SAND BLANKET MATERIAL SHALL BE GRADED SAND FREE FROM ANY ORGANIC MATERIALS. GRADED SUCH THAT 100 PERCENT PASSED THE 1/2-INCH SIEVE AND A MAXIMUM OF 15 PERCENT PASSES A #200 SIEVE. IN LIEU OF A SAND BLANKET, A STONE ENVELOPE 6 INCHES THICK COMPLETELY AROUND THE PIPE USING 3/4-INCH STONE MAY BE USED.

PIPE BEDDING MATERIAL SHALL EXTEND FROM A HORIZONTAL PLANE THROUGH THE PIPE AXIS TO 6-INCHES BELOW THE BOTTOM OF THE OUTSIDE SURFACE OF THE PIPE.

PIPE SAND BLANKET MATERIAL SHALL COVER THE PIPE A MINIMUM OF 12 INCHES ABOVE THE CROWN OF THE

COMPACTION SHALL BE IN 12-INCH LAYERS FOR BEDDING AND BLANKET MATERIALS.

BACKFILL MATERIAL SHALL BE IN 3-FOOT LAYERS TO THE GROUND SURFACE EXCEPT FOR ROAD CONSTRUCTION WHERE THE FINAL 3-FEET SHALL BE COMPACTED IN 12-INCH LAYERS TO THE ROAD BASE SURFACE.


TRENCH BACKFILL MATERIAL IN ROADWAY LOCATIONS SHALL BE NATURAL MATERIALS EXCAVATED FROM THE TRENCH DURING CONSTRUCTION, EXCLUDING DEBRIS, PAVEMENT PIECES, ORGANIC MATTER, TOP SOIL, WET OR SOFT MUCK, PEAT, CLAY, EXCAVATED LEDGE, ROCKS OVER 6 INCHES IN THE LARGEST DIMENSION, OR ANY OTHER UNSUITABLE MATERIAL NOT APPROVED BY THE ENGINEER.

TRENCH BACKFILL AT CROSS-COUNTRY LOCATIONS SHALL BE AS DESCRIBED ABOVE EXCEPT THAT THE ENGINEER MAY PERMIT THE USE OF TOP SOIL, LOAM, MUCK OR PEAT, IF HE IS SATISFIED THAT THE COMPLETED CONSTRUCTION WILL BE ENTIRELY STABLE AND PROVIDED THAT EASY ACCESS TO THE SEWER FOR MAINTENANCE AND POSSIBLE RECONSTRUCTION, WHEN NECESSARY WILL BE PRESERVED, BACKFILL SHALL BE MOUNDED 6-INCHES ABOVE ORIGINAL

BASE COURSE MATERIALS FOR TRENCH REPAIRS SHALL MEET THE REQUIREMENTS OF DIVISION 300 OF THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" OF NEW HAMPSHIRE DEPARTMENT OF

WHERE SHEETING IS PLACED ALONG SIDE OF THE PIPE AND EXTENDS BELOW MID-DIAMETER, THE SHEETING SHALL BE CUT OFF AND LEFT IN PLACE TO AN ELEVATION NOT LESS THAN ONE FOOT ABOVE THE TOP OF THE PIPE AND AT LEAST 3 FEET BELOW FINISH GRADE.

TRENCHES FOR SEWER PIPES WITH SLOPES OVER 0.08 FEET PER FOOT AND TRENCHES FOR SEWER PIPES BELOW THE SEASONAL HIGH GROUND WATER LEVEL SHALL HAVE IMPERVIOUS TRENCH DAMS CONSTRUCTED EVERY 300 FEET TO PREVENT POTENTIAL DISTURBANCE TO PIPE BEDDING AND BLANKET MATERIALS.



NOT TO SCALE

FOR CROSS COUNTRY CONSTRUCTION,

GROUND SURFACE.

COMPACT IN

'LAYFRS

COMPACT IN

6" LAYERS

COMPACT IN

1' LAYERS

12" MIN.

1/2 OD

COMPACT IN

6" LAYERS

W= MAXIMUM ALLOWABLE

TRENCH WIDTH TO A PLANE 12"

ABOVE THE PIPE. FOR PIPES

LESS, W SHALL BE 24" PLUS

15" NOMINAL DIAMETER OR

SUITABLE -

/ MATERIAL

METAL IMPREGNATED TAPE

OR TRACER WIRE

— SAND BLANKET →

BEDDING

EARTH CONSTRUCTION

NOT TO SCALE

SUITABLE-

-SAND BLANKET -

BEDDING .

BEDDING TO BE THOROUGHLY COMPACTED (SEE NOTE 10)

RIGID STYROFOAM INSULATION.

(DOW HI-40 OR EQUAL) WITH 6" CLEAN SAND BLANKET AROUND

PIPE & INSULATION FOR PIPES

WITH LESS THAN 4' COVER (IN

PAVEMENT LOCATIONS) AND 6'

COVER (IN UNPAVED LOCATIONS)

— MATERIAL

BACKFILL OR FILL SHALL BE MOUNDED

TO A HEIGHT OF 6" ABOVE THE ORIGINAL

SEE A/E PLANS -

LEDGE CONSTRUCTION NOT TO SCALE

FOR CONSTRUCTION IN ROADS, ROAD SHOULDERS AND WALKWAYS


, BASÉ COURSE /

-SAND BLANKET -

OR TRACER WIRE

SUITABLE -

-SURFACE COURSE AS SPECIFIED



39-1/4"

SECTION A-A

OR 'DRAIN' AS APPROPRIATE - 3" HIGH LETTERS <u>COVER</u>

-SAW CUT PAVEMENT WHEN MATCHING

W= MAXIMUM ALLOWABLE

TRENCH WIDTH TO A PLANE 12"

ABOVE THE PIPE. FOR PIPES

LESS, W SHALL BE 24" PLUS

PIPE O.D. W SHALL ALSO BE

LEDGE EXCAVATION AND FOR

ORDERED EXCAVATION BELOW

THE PAYMENT WIDTH FOR

GRADE.

31-1/2"

COVER

SEWER

15" NOMINAL DIAMETER OR

TO EXISTING PAVEMENT

COMPACT IN


6" LAYERS

COMPACT IN

1'LAYERS

COMPACT IN

S"LAYERS



4. FLANGE SHALL INCORPORATE BEDDING SLOTS AND BOLT HOLES. 5. ALL COMPONENTS SHALL BE BLACK COATED.

6. MANHOLE FRAME AND COVER SHALL BE PER TOWN OF TILTON STANDARDS.

BRICK RISERS (IF REQUIRED) ASTM C32-05, CLAY OR SHALE SS HARD BRICK SEE STRUCTURE DETAILS

MANHOLE FRAME AND COVER NOT TO SCALE

BACKFILLING TO BE BROUGHT UP EVENLY ON ALL SIDES. (SEE NOTE 12)

FERROUS METAL

ROD OR PIPE

(SEE NOTE 11)

6" MIN ALL AROUND -

6"MIN

PLUG -

CHIMNEY NOT TO SCALE





SONOTUBE

SITE DEVELOPMENT PLANS

TAX MAP 205 LOT 2

DETAILS

LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR **ADL 325 LITTLE HARBOR ROAD TRUST**

SEPTEMBER 29, 2021



Civil Engineers Structural Engineers Traffic Engineers and Surveyors andscape Architects cientists

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com

DR HEG FB C - 24CK JCC CADFILE 47099-01_DETAILS_MAIN


TRENCH CROSS-SECTION NOT TO SCALE

3 2/15/2022 REVISED PER NHDES & UTILITIES PER TAC > | 2/2/2022 | REVISED PER NHDES & UPDATE SURVEY/UTIL 1 11/23/2021 REVISED PER NHDES & PROJECT COORDINATION HEG JCC REV. DATE **DESCRIPTION** DR CK

E-ONE FLUSHING MANHOLE

NOT TO SCALE

E-ONE CLEANOUT AND AIR VACUUM DETAIL




CONCRETE BALLAST MAY BE REQUIRED SEE INSTALLATION INSTRUCTION FOR DETAILS

NOTES:

- 1. ACTUAL E-ONE PUMP AND SPECIFICATION MUST BE DESIGNED AND PROVIDED BY EONE DESIGNER OR
- 2. THE PUMP CORE CONTAINS BUILT IN CHECK AND ANTI-SIPHON VALVES. IN ADDITION, THERE IS A REDUNDANT UNILATERAL CHECK AND ISOLATION VALVE AT THE LOT LINE WITH THE STAINLESS STEEL
- 3. THE STATION MONITOR CONTAINS A HIGH LEVEL ALARM. THE HIGH LEVEL ALARM IS RUN OFF A REDUNDANT RUN SWITCH THAT OVERRIDES THE RUN SWITCH IF IT SHOULD SEE A POWER FAILURE.
- 4. THE ALARM PANEL HAS THE OPTION TO CONNECT A PORTABLE GENERATOR WITH A 20 AMP, 240 VOLT SUPPLY. POWER TRANSFERS AUTOMATICALLY IF THE PUMP IS CALLING TO RUN.
- 5. THE PUMP RATED TO 700 GPD.
- 6. THE TANK HAS A 150-GAL VOLUME.
- 7. IN CASE OF A POWER FAILURE, A BATTERY BACKUP REMOTE SENTRY ALARM PANEL SHALL BE USED IN CONJUNCTION WITH THE E-ONE PUMP SYSTEM.
- 8. A BACKUP GENERATOR WILL BE PROVIDED THAT SHALL BE AMPLE ENOUGH TO SUPPLY POWER TO RUN THE GRINDER PUMP AND ALARM SYSTEM. THERE SHALL BE ENOUGH FUEL ON SITE TO RUN THE GENERATOR FOR A MINIMUM OF 6 HRS.

E-ONE DH151 PUMP NOT TO SCALE



FINISHED GRADE —

SCHEDULE 40

2. ALL COMPONENTS SHALL BE DESIGNED FOR HS-20 LOADING. 4. ALL CONCRETE SHALL BE NHDOT CLASS A. 5. LARGER DIAMETER STRUCTURES SHALL BE USED AS REQUIRED DUE TO NUMBER, ORIENTATION

OR SIZE OF PIPES AT THE STRUCTURE. 6. "CL" USED AT ALL LOCATIONS WITHOUT CURB AND "C" TO BE USED AT ALL TO NUMBER,

SIZE OR ORIENTATION OF PIPES AT THE BASIN. 7. ALL CASTINGS SHALL BE MADE IN THE USA.

8. INSTALL PIPE SUPPORTS ON THE SWEEP ELBOW. 9. ALL PIPE FITTINGS ARE TO BE RESTRAINED JOINT STYLE.

A. HDPE TO BE FUSION, ELECTROFUSION OR MECHANICAL JOINT. B. PVC WOULD BE SOLVENT GLUE

C. ALL JOINTS TO BE THREADED AND PRESSURE RATED TO 200 PSI 10. MANHOLE STRUCTURES SHALL MEET THE DESIGN REQUIREMENTS OF ENV-WQ 704.12

THROUGH ENV-WQ 704.17. 11. A.R.I. D-025 STAINLESS STEEL AIR RELEASE VALVE OR EQUIVALENT.

FORCE MAIN CURB STOP

NOT TO SCALE









PRESSURE SEWER TESTING NOTES

- 1. PIPE AND JOINT MATERIALS:
- A. PRESSURE SEWERS SHALL BE CONSTRUCTED OF DUCTILE IRON (DI), HIGH DENSITY POLYETHYLENE (HDPE), OR PVC MATERIAL
- B. PRESSURE SEWERS SHALL BE TREATED AS GRAVITY SEWERS FOR PURPOSES OF
- FOUNDATION BEDDING AND BACKFILL REQUIREMENTS. C. PVC PIPE USED PRESSURE SEWERS SHALL BE CERTIFIED BY ITS MANUFACTURER AS
- CONFORMING TO THE ASTM D2241 OR ASTM D1785 STANDARDS IN EFFECT WHEN THE PIPE IS MANUFACTURED.
- D. HDPE PIPE USED FOR PRESSURE SEWERS SHALL BE CERTIFIED BY ITS MANUFACTURER AS CONFORMING TO THE ASTM D3035 STANDARD IN EFFECT WHEN THE PIPE IS
- E. IF DI PIPE IS USED IN AN ENVIRONMENT THAT COULD CAUSE CORROSION OR OTHER DETERIORATION OF OR DAMAGE TO AN IRON PIPE, OR OTHERWISE REDUCE THE TYPICAL LIFE EXPECTANCY OF THE PIPE, SUCH AS MAY OCCUR WITH CERTAIN SOIL TYPES, LOW PH LEVELS, OR WATER CONDITIONS, THE PIPE SHALL BE PROTECTED AGAINST CORROSION, SUCH AS WITH CATHODIC PROTECTION.
- 2. TESTING: THE COMPLETED SEWER SERVICE SHALL BE SUBJECTED TO A THIRD PARTY LEAKAGE TEST ANY OF THE FOLLOWING MANNERS: (PRIOR TO BACKFILLING) PRESSURE SEWERS SHALL BE TESTED IN ACCORDANCE WITH SECTION 5 OF THE AWWA C600, "INSTALLATION OF CAST IRON WATER MAINS AND THEIR APPURTENANCES" STANDARD IN EFFECT WHEN THE TEST IS CONDUCTED AT A PRESSURE EQUAL TO THE GREATER OF 150 PERCENT OF THE DESIGN OPERATING TOTAL DYNAMIC HEAD OR AT LEAST 100 PSI.
- 3. DAMAGED PIPE SHALL BE REJECTED AND REMOVED FROM THE JOB SITE.
- 4. JOINTS SHALL BE DEPENDENT UPON A NEOPRENE OR ELASTOMERIC GASKET FOR WATER-TIGHTNESS. ALL JOINTS SHALL BE PROPERLY MATCHED WITH THE PIPE MATERIALS USED. WHERE DIFFERING MATERIALS ARE TO BE CONNECTED, AS AT THE STREET SEWER WYE OR AT THE FOUNDATION WALL, APPROPRIATE MANUFACTURED ADAPTERS SHALL BE USED.
- 5. SEWER SERVICE INSTALLATION: THE PIPE SHALL BE HANDLED, PLACED AND JOINTED IN ACCORDANCE WITH INSTALLATION GUIDES OF THE APPROPRIATE MANUFACTURER. IT SHALL BE CAREFULLY BEDDED ON A 6 INCH LAYER OF CRUSHED STONE AND/OR GRAVEL AS SPECIFIED IN NOTE 11. BEDDING AND RE-FILL FOR DEPTH OF 12 INCHES ABOVE THE TOP OF THE PIPE SHALL BE CAREFULLY AND THOROUGHLY TAMPED BY HAND OR WITH APPROPRIATE MECHANICAL DEVICES.
- 6. PIPE JOINTS MUST BE MADE UNDER DRY CONDITIONS. IF WATER IS PRESENT, ALL NECESSARY STEPS SHALL BE TAKEN TO DEWATER THE TRENCH.
- 7. THE CENTERLINE OF ALL BUILDING CONNECTIONS SHALL ENTER THE TOP HALF OF THE
- 8. ILLEGAL CONNECTIONS: NOTHING BUT SANITARY WASTE FLOW FROM TOILETS, SINKS, LAUNDRY ETC. SHALL BE PERMITTED. ROOF LEADERS, FOOTING DRAINS, SUMP PUMPS OR OTHER SIMILAR CONNECTIONS CARRYING RAIN WATER, DRAINAGE OR GROUND WATER SHALL NOT BE PERMITTED.
- 9. PRESSURE SEWERAGE SHALL HAVE AN ISOLATION VALVE OR CURB STOP VALVE INSTALLED AT THE PROPERTY LINE / LIMITED COMMON AREA. IF A CHECK VALVE IS USED AT THE PROPERTY LINE, THE VALVE SHALL BE INSTALLED WITHIN A VAULT TO FACILITATE MAINTENANCE.
- 10. WATER SERVICE SHALL NOT BE LAID IN SAME TRENCH AS SEWER SERVICE.
- 11. BEDDING: SCREENED GRAVEL AND/OR CRUSHED STONE FREE FROM CLAY, LOAM, ORGANIC MATERIAL AND MEETING ASTM C33/C33M STONE SIZE 67 AND FREE FROM CLAY, LOAM AND ORGANNIC MATTER. THE EXCAVATION SHALL BE PROPERLY DEWATERED WHILE PLACING BEDDING MATERIAL AND SETTING OF THE BASE OR POURING CONCRETE.

100% PASSING 1 INCH SCREEN 90%-100% PASSING 3/4 INCH SCREEN 20%-55% PASSING 3/8 INCH SCREEN 0%-10% PASSING #4 SIEVE

0%-5% PASSING #8 SIEVE WHERE ORDERED BY THE ENGINEER TO STABILIZE THE TRENCH BASE, SCREENED GRAVEL OR CRUSHED STONE 1/2 INCH TO 1 1/2 INCH SHALL BE USED.

12. LOCATION: THE LOCATION OF THE TEE OR WYE SHALL BE RECORDED AND FILED IN THE MUNICIPAL

13. INTERNAL STEPS IN MANHOLES ARE PROHIBITED PER PORTSMOUTH DPW STANDARDS.

-SEWER MAIN TYPICAL STORM DRAIN 1.5" BLUE DOW STYROFOAM 2' OR 1.5" BLUE DOW LESS STYROFOAM TYPICAL STORM DRAIN CONDITION I CONDITION II

NOTES:

1. THE LENGTH OR WIDTH OF INSULATION SHALL EXTEND 1 STORM DRAIN PIPE DIAMETER BEYOND THE EDGE OF STORM DRAIN PIPE IN EACH DIRECTION OR A MINIMUM OF 2' BEYOND THE CENTERLINE OF THE STORM DRAIN PIPE, WHICHEVER IS GREATER. 2. ALL BUTT JOINT SEAMS TO BE OVERLAPPED WITH A 1' PIECE OF INSULATION CENTERED OVER SEAM.

> INSULATION AT STORM DRAIN AND SEWER MAIN INTERSECTING RUNS NOT TO SCALE





SITE DEVELOPMENT PLANS

TAX MAP 205 LOT 2


DETAILS


LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

OWNED BY & PREPARED FOR

ADL 325 LITTLE HARBOR ROAD TRUST

SEPTEMBER 29, 2021







Civil Engineers Structural Engineers Traffic Engineers and Surveyors andscape Architects

170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com

DR HEG FB CK JCC CADFILE 47099-01_DETAILS_MAIN

C - 25



Copyright 2022 ©TFMoran, Inc.

homas F. Moran, Inc.


48 Constitution Drive, Bedford, N.H. 03110


All rights reserved. These plans and materials may not be copied,

without the prior written permission of Thomas F. Moran, Inc.

duplicated, replicated or otherwise reproduced in any form whatsoever

This plan is not effective unless signed by a duly authorized officer of





STANDARD DUTY PAVEMENT


OVERLAY

1. SEE GRADING & DRAINAGE PLAN & DRIVEWAY GRADING & PROFILE FOR PAVEMENT SLOPE AND CROSS-SLOPE.

- 2. PROVIDE CLEAN BUTT TO EXISTING PAVEMENT USE TACK COAT. A TACK COAT SHALL ALSO BE PLACED BETWEEN GRAVEL COURSE AND SUCCESSIVE LAYERS OF BITUMINOUS CONCRETE. SPECIFICALLY, A TACK COAT SHALL BE PLACED ATOP THE BINDER COURSE PAVEMENT PRIOR TO PLACING THE WEARING COURSE.
- 3. REMOVE ALL LOAM AND/OR YIELDING MATERIAL BELOW PAVEMENT.
- 4. BITUMINOUS MATERIALS SHALL CONFORM TO NHDOT SPECIFICATION SECTION 401.
- 5. BITUMINOUS CONCRETE SHALL BE COMPACTED TO AT LEAST 92.5% OF THEORETICAL MAXIMUM DENSITY AS DETERMINED BY ASTM D2041 OR AASHTO T209. PLACEMENT TEMPERATURES OF BITUMINOUS CONCRETE MIXES, IN GENERAL, RANGE BETWEEN 270 AND 310 DEGREES FAHRENHEIT.
- 6. PAVEMENT BASE COURSE AGGREGATE SHALL CONFORM TO NHDOT SPECIFICATION SECTION 304, ITEM 304.3 AND COMPACTED TO A MINIMUM OF 95% OF MODIFIED PROCTOR MAXIMUM DRY DENSITY.
- 7. PAVEMENT SUBBASE COURSE AGGREGATE AND AGGREGATE FOR SUBGRADE REPAIR AREAS SHALL BE SUITABLE FOR USE AS STRUCTURAL FILL AND BE PROOF ROLLED AND COMPACTED TO 95% MODIFIED PROCTOR MAXIMUM DRY DENSITY.
- 8. THE EXPOSED SOIL SUBGRADE SHOULD BE PROOF ROLLED PRIOR TO THE PLACEMENT OF SUBBASE GRAVEL, AND SOFT AREAS SHOULD BE REPAIRED AND REPLACED.

PAVEMENT SECTIONS

NOT TO SCALE



ELECTRIC PULL BOX NOT TO SCALE

LADY ISLE SITE RENOVATIONS 325 LITTLE HARBOR ROAD, PORTSMOUTH, NH

SITE DEVELOPMENT PLANS


TAX MAP 205 LOT 2


DETAILS

OWNED BY & PREPARED FOR **ADL 325 LITTLE HARBOR ROAD TRUST**

SEPTEMBER 29, 2021

C - 26







| 170 Commerce Way, Suite 102 Portsmouth, NH 03801 Phone (603) 431-2222 Fax (603) 431-0910 www.tfmoran.com

47099.01 DR HEG FB - CK JCC CADFILE 47099-01_DETAILS_MAIN

Civil Engineers Structural Engineers

Traffic Engineers

Land Surveyors

Landscape Architects


Copyright 2022 ©TFMoran, Inc. 48 Constitution Drive, Bedford, N.H. 03110

Thomas F. Moran, Inc.

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of

Gross	Floor Area at M	lain House
	Conditioned sq.ft.	Unconditioned sq.ft
Basement	3,382 sq.ft.	1,050 sq.ft.
First Floor	3,897 sq.ft.	1,496 sq.ft.
Second Floor	3,487 sq.ft.	
Тотаl	10,766 sq.ft.	2,546 sq.ft.
	13,312	SQ.FT.





ISSUED FOR PERMIT 6/24/21

A NEW RESIDENCE & GARAGE

LADY ISLE PORTSMOUTH, NEW HAMPSHIRE

SHEET TITLE:

Basement Overall Plan

June 24, 2021

SHEET NUMBER: MH

PM / AB

DRAWN BY:

1/8" = 1'-0"

G. P. SCHAFER ARCHITECT, DPC

19 Union Square West 4TH FLOOR NEW YORK, NEW YORK 10003 TELEPHONE: 212-965-1355 TELEFAX: 212-965-1356

© COPYRIGHT BY G. P. SCHAFER ARCHITECT, DPC




Basement Floor Plan - Overall

Scale: 1/8'' = 1'-0''



Gross	Floor Area at M	lain House
	Conditioned sq.ft.	Unconditioned sq.ft
Basement	3,382 sq.ft.	1,050 sq.ft.
First Floor	3,897 sq.ft.	1,496 sq.ft.
Second Floor	3,487 sq.ft.	
Total	10,766 sq.ft.	2,546 sq.ft.
	13,312	SQ.FT.









ISSUED FOR PERMIT 6/24/21

A NEW RESIDENCE & GARAGE

LADY ISLE PORTSMOUTH, NEW HAMPSHIRE

SHEET TITLE:

First Floor Overall Plan

June 24, 2021

SHEET NUMBER: MH


1/8" = 1'-0"

DRAWN BY: PM / AB

G. P. SCHAFER ARCHITECT, DPC

19 Union Square West 4TH FLOOR NEW YORK, NEW YORK 10003 TELEPHONE: 212-965-1355 TELEFAX: 212-965-1356

Gross	Floor Area at N	Iain House
	Conditioned sq.ft.	Unconditioned sq.f1
Basement	3,382 sq.ft.	1,050 sq.ft.
First Floor	3,897 sq.ft.	1,496 sq.ft.
Second Floor	3,487 ѕQ.бт.	
Тотац	10,766 sq.ft.	2,546 sq.ft.
	13,312	2 SQ.FT.







SECOND FLOOR PLAN - OVERALL

ISSUED FOR PERMIT 6/24/21

LADY ISLE PORTSMOUTH, NEW HAMPSHIRE

A NEW RESIDENCE & GARAGE

SHEET TITLE:

Second Floor Overall Plan

SHEET NUMBER:

MH

June 24, 2021

1/8" = 1'-0" DRAWN BY:

PM / AB

19 Union Square West 4TH FLOOR NEW YORK, NEW YORK 10003 TELEPHONE: 212-965-1355 TELEFAX: 212-965-1356

G. P. SCHAFER ARCHITECT, DPC

ISSUED FOR PERMIT 6/24/21

LADY ISLE
PORTSMOUTH, NEW HAMPSHIRE

A NEW RESIDENCE & GARAGE

Roof Overall Plan

SHEET NUMBER:

MH

: June 24, 2021

ne 24, 2021

: 1/8" = 1'-0"

DRAWN BY:


PM/AB

SHEET TITLE:


G. P. SCHAFER ARCHITECT, DPC

19 UNION SQUARE WEST
4TH FLOOR
NEW YORK, NEW YORK 10003
TELEPHONE: 212-965-1355
TELEFAX: 212-965-1356












BLUESTONE CHIMNEY CAP -CUSTOM STONE CHIMNEYS +31'-2" RIDGE HEIGHT CEDAR SHINGLE ROOF LEAD COATED COPPER FLAT SEAMED ROOF +20'- 4 1/8" SECOND FLOOR CEILING — — — — — CUSTOM PTD. WD. PILASTERS AT GLAZED PORCH, TYP. - CUSTOM PTD. WD. CASEMENT WINDOWS AT GLAZED PORCH +11'-41/8" SECOND FLOOR FINISH First Floor Ceiling >CUSTOM PTD. WD. SQUARE POSTS AND RAILINGS, TYP. +o'-o" FIRST FLOOR FINISH BASEMENT CEILING MONOLITHIC STONE STEPS STONE VENEER AT BSMT FOUNDATION LEVEL BASEMENT FINISH

OVERALL EAST ELEVATION

A-2.01 Scale: 1/8" = 1'-0"





FOR PERMITT ONLY. NOT FOR CONSTRUCTION

ISSUED FOR PERMIT

A NEW RESIDENCE & GARAGE

6/24/21

LADY ISLE
PORTSMOUTH, NEW HAMPSHIRE

SHEET TITLE:

Exterior Elevations
Overall

DATE:

SHEET NUMBER:

June 24, 2021

SCALE: I/8'' = I'-0''

A-2.0


DRAWN BY:

PM/AB


I / AB

G. P. SCHAFER ARCHITECT, DPC

19 UNION SQUARE WEST
4TH FLOOR
NEW YORK, NEW YORK 10003
TELEPHONE: 212-965-1355
TELEFAX: 212-965-1356







FOR PERMITT ONLY NOT FOR CONSTRUCTION

ISSUED FOR PERMIT

A NEW RESIDENCE & GARAGE

LADY ISLE
PORTSMOUTH, NEW HAMPSHIRE

SHEET TITLE:

Exterior Elevations
Overall

DATE:

SHEET NUMBER:

June 24, 2021

I/8" = I'-0"


DRAWN BY:

PM / AB

6/24/21

G. P. SCHAFER ARCHITECT, DPC

19 UNION SQUARE WEST
4TH FLOOR
NEW YORK, NEW YORK 10003
TELEPHONE: 212-965-1355
TELEFAX: 212-965-1356







ISSUED FOR PERMIT

A NEW RESIDENCE & GARAGE

6/24/21

at Lady Isla

LADY ISLE PORTSMOUTH, NEW HAMPSHIRE

SHEET TITLE:

First Floor Plan

June 24, 2021

SHEET NUMBER:

LE:

PM

I/4" = I'-0"


DRAWN BY:


A-1.01


G. P. SCHAFER ARCHITECT, DPC


19 UNION SQUARE WEST
4TH FLOOR
NEW YORK, NEW YORK 10003
TELEPHONE: 212-965-1355
TELEFAX: 212-965-1356



























LEGEND EXISTING FOUNDATION WALL NEW CONCR. STEM WALL NEW STONE VENEER NEW CMU FOUNDATION NEW FRAMING EXISTING TIMBER POST ISSUED FOR PRICING 9/8/20 (NOT FOR CONSTRUCTION) A RENOVATED BARN LADY ISLE PORTSMOUTH, NEW HAMPSHIRE SHEET TITLE: First Floor Plan Barn SHEET NUMBER: September 8, 2020 1/4"=1'-0" DRAWN BY: G. P. SCHAFER ARCHITECT, DPC 19 Union Square West 4TH FLOOR NEW YORK, NEW YORK 10003 TELEPHONE: 212-965-1355 TELEFAX: 212-965-1356

© COPYRIGHT BY G. P. SCHAFER ARCHITECT, DPC

PROJECT NORTH





LEGEND EXISTING FOUNDATION WALL NEW CONCR. STEM WALL NEW STONE VENEER NEW CMU FOUNDATION NEW FRAMING ISSUED FOR PRICING 9/8/20 (NOT FOR CONSTRUCTION) A RENOVATED BARN LADY ISLE PORTSMOUTH, NEW HAMPSHIRE SHEET TITLE: Second Floor Plan Barn SHEET NUMBER: September 8, 2020 1/4"=1'-0" DRAWN BY:

19 Union Square West 4th Floor New York, New York 10003

TELEPHONE: 212-965-1355
TELEFAX: 212-965-1356
© COPYRIGHT BY G. P. SCHAFER ARCHITECT, DPC

G. P. SCHAFER ARCHITECT, DPC









A NEW RESIDENCE & GARAGE

at

LADY ISLE PORTSMOUTH, NEW HAMPSHIRE

SHEET TITLE:

First Floor Plan

DATE:

SHEET NUMBER:

June 24, 2021

E:

A-1.0


DRAWN BY:

G. P. SCHAFER ARCHITECT, DPC


19 UNION SQUARE WEST
4TH FLOOR
NEW YORK, NEW YORK 10003
TELEPHONE: 212-965-1355
TELEFAX: 212-965-1356









North Elevation A-2.01 Scale: 1/4" = 1'-0"









A NEW RESIDENCE & GARAGE

LADY ISLE PORTSMOUTH, NEW HAMPSHIRE

SHEET TITLE:

ExteriorElevations

June 24, 2021

1/4" = 1'-0"

PM

SHEET NUMBER:

G. P. SCHAFER ARCHITECT, DPC

19 Union Square West 4TH FLOOR NEW YORK, NEW YORK 10003 TELEPHONE: 212-965-1355 TELEFAX: 212-965-1356



Lady Isle

325 Little Harbor Road, Portsmouth NH

General Notes:

1. Existing conditions and topographic data are from a site plan of land dated March 2, 2021; prepared by: Thomas F. Moran Inc., 170 Commerce Way, Suite 102, Portsmouth, NH, 03801 - Tel: (603) 431.2222

2. Existing conditions supplemented from data collected by: Matthew Cunningham Landscape Design LLC, 411 Main Street, Stoneham, MA 02180 - Tel: (617) 905.2246


3. Do not scale drawings



M A T T H E W CUNNINGHAM LANDSCAPE DESIGN LLC

matthew-cunningham.com

SCALE: 1" = 50'-0" DATE: 23 FEBRUARY 202



LANDSCAPE PLAN

SHEET NUMBER:



Lady Isle

325 Little Harbor Road, Portsmouth NH

General Notes:

- 1. Existing conditions and topographic data are from a site plan of land dated March 2, 2021; prepared by: Thomas F. Moran Inc., 170 Commerce Way, Suite 102, Portsmouth, NH, 03801 Tel: (603) 431.2222
- 2. Existing conditions supplemented from data collected by: Matthew Cunningham Landscape Design LLC, 411 Main Street, Stoneham, MA 02180 Tel: (617) 905.2246
- 3. Do not scale drawings



MATTHEW

CUNNINGHAM

LANDSCAPE

DESIGN LLC

matthew-cunningham.com


SCALE: 1" = 30'-0" DATE: 23 FEBRUARY 202

ET TITLE:

LANDSCAPE PLAN

SHEET NUMBER:

L1.1



Vaccinium corymbosum

Viburnum plicatum f. tomentosum

Viburnum dentatum

Viburnum trilobum

Highbush Blueberry

Arrowwood Viburnum

Doublefile Viburnum

American Cranberry Virburnum

Eragrostis spectabilis

Eupatorium dubium

Eurybia divaricata

Galium odoratum

Gillenia trifoliata

Geranium 'Rozanne'

Geranium macrorrhizum

Eupatorium maculatum

Purple Love Grass

White Wood Aster

Sweet Woodruff

Bowman's Root

Cranesbill

Rozanne Cranesbill

Dwarf Joe Pye Weed

Spotted Joe Pye Weed

Sorghastrum nutans

Stachys byzantina

Thymus vulgaris

Sporobolus heterolepsis

Symphyotrichum novae-angliae

Symphyotrichum novi-belgii

Thalictrum rochebrunianum

Symphyotrichum oblongifolium

Indian Grass

Lamb's Ear

Prairie Dropseed

New York Aster

Aromatic Aster

Common Thyme

New England Aster

Lavender Mist Meadow-rue

Lady Isle

325 Little Harbor Road, Portsmouth NH

General Notes:

1. Existing conditions and topographic data are from a site plan of land dated March 2, 2021; prepared by: Thomas F. Moran Inc., 170 Commerce Way, Suite 102, Portsmouth, NH, 03801 - Tel: (603) 431.2222

2. Existing conditions supplemented from data collected by: Matthew Cunningham Landscape Design LLC, 411 Main Street, Stoneham, MA 02180 - Tel: (617) 905.2246

3. Do not scale drawings



MATTHEW CUNNINGHAM LANDSCAPE DESIGN LLC matthew-cunningham.com

SCALE: 1" = 30'-0" DATE: 23 FEBRUARY 202

PLANTING PLAN

SHEET NUMBER:



Lady Isle

325 Little Harbor Road, Portsmouth NH

General Notes:

1. Existing conditions and topographic data are from a site plan of land dated March 2, 2021; prepared by: Thomas F. Moran Inc., 170 Commerce Way, Suite 102, Portsmouth, NH, 03801 - Tel: (603) 431.2222

2. Existing conditions supplemented from data collected by: Matthew Cunningham Landscape Design LLC, 411 Main Street, Stoneham, MA 02180 - Tel: (617) 905.2246

3. Do not scale drawings




MATTHEW
CUNNINGHAM
LANDSCAPE
DESIGN LLC
matthew-cunningham.com

SCALE: 1" = 30'-0" DATE: 23 FEBRUARY 202

SHEET TITLE:

PLANTING PLAN

SHEET NUMBER:



325 Little Harbor Road, Portsmouth NH

General Notes:

1. Existing conditions and topographic data are from a site plan of land dated March 2, 2021; prepared by: Thomas F. Moran Inc., 170 Commerce Way, Suite 102, Portsmouth, NH, 03801 - Tel: (603) 431.2222

2. Existing conditions supplemented from data collected by: Matthew Cunningham Landscape Design LLC, 411 Main Street, Stoneham, MA 02180 - Tel: (617) 905.2246

3. Do not scale drawings

CUNNINGHAM | • |

MATTHEW CUNNINGHAM LANDSCAPE DESIGN LLC

matthew-cunningham.com

SHEET TITLE:

LANDSCAPE DETAILS

SHEET NUMBER:



PLANNING BOARD EXISTING AERIAL PHOTO (06/02/21)

Civil Engineers
Structural Engineers
Traffic Engineers
Land Surveyors Landscape Architects Scientists













G. P. SCHAFER ARCHITECT

















Civil Engineers
Structural Engineers
Traffic Engineers
Land Surveyors
Landscape Architects
Scientists















Civil Engineers
Structural Engineers
Traffic Engineers
Land Surveyors
Landscape Architects
Scientists



