## Kimley *Whorn*

#### Transmittal

Date:				Job Number			
Project Na	ame:						
To:							
We are s	sending the	ese by					
US Ma	ail			FedEx		UPS	
Hand	Deliver			Courier		Other	
We are se	ending you						
Attac	hed		Under s	eparate cover via		the follow	wing items
Shop	drawings	Prir	nts/Plans	Samples	Specifications	Change Order	Other
Number	Date	Сору	Descriptio	n			
Number	Date		Descriptio	11			

These are transmitted as checked below:

	For your use	Approved as submitted	Resubmit
	As requested	Approved as noted	Submit
	For review and comment	Returned for corrections	Return
	Copies for approval	Copies for distribution	Corrected prints
Convit	o.	Signadi	
Copy t	0.	Signed:	

Phone:

February 22, 2022 Updated May 5, 2022

City of Portsmouth Conservation Commission

#### RE: Portsmouth Regional Hospital – Radiation Oncology Project Narrative

The existing Portsmouth Regional Hospital is located at 333 Borthwick Ave, Portsmouth, NH 03801 (Map 240, Lot 2-1). The medical campus is located on the east side of Blue Star Turnpike (I-95), the west side of Borthwick Avenue, and can be accessed via multiple entrances from Borthwick Avenue. The scope of the proposed Radiation Oncology project consists of internal renovations, and a 1-story building addition located on the southeast corner of the existing hospital building.

The proposed footprint of the building addition is approximately ±8,700 square feet. The proposed sitework is anticipated to consist of asphalt, concrete, utility, landscape, and drive-under canopy demolition where the current patient discharge canopy and associated drive are located as well as removal of existing sidewalk and landscaping located along the south side of the existing hospital building. Site improvements are anticipated to consist of the new building addition, new drive-under canopy and associated drive, sidewalk connectivity, new granite curb, new mobile imaging pad, and associated new utilities/ utility relocations.

A portion of the project scope is located adjacent to and partially within a previously man-made stormwater management area which is now delineated as a city jurisdictional inland wetland and has an associated 100-ft wetland buffer, in which a portion of the site improvements will occur. A small amount of disturbance to the actual wetland is being proposed. Refer to the attached wetland exhibit. Please note, the overall wetland data has been calculated with older drawings by others. Only the wetland adjacent to this project was delineated and flagged by Gove Environmental Services, Inc., and surveyed by James Verra and Associates, Inc. Refer to attached letter and site survey.

#### Wetlands and 100-foot buffer, Overall Site

- Subject Parcel: Map 240, Lot2-1 (±20.87 ac)
- Total wetland area onsite: approximately ±2.7 acres
- Total area of 100-foot wetland buffer onsite: approximately ±8.4 acres

#### Wetland and 100-foot buffer, Proposed Impact

- Area of inland wetland to be disturbed:
  - Permanent (due to proposed building location): ±200 square feet (sf)
  - Temporary (due to construction of proposed building and utility relocations, but will be planted back as wetlands): ±4,400 square feet (sf)
  - Total disturbance: ±4,600 square feet (sf)
- Area of 100-ft wetland buffer to be disturbed:
  - Permanent: ±13,200 sf
  - Temporary: ±4,300 sf

The drainage area to the existing man-made stormwater management area/ inland wetland that is located within the proposed project area (**Pond 1**) was analyzed utilizing provided site surveys as well as previous design drawings for the medical campus. It appears a portion of the southeastern parking lot drains to another existing man-made stormwater management area/ inland wetland that is located along the north side of Borthwick Avenue (**Pond 2**). Pond 2 drains to Pond 1 via a 21" RCP pipe. The drainage area to the Pond 2 remains the same as the current existing condition.

The drainage area to the Pond 1 also remains relatively the same as existing conditions as a portion of the existing hospital building roof will continue to drain to Pond 1, new roof for the proposed building addition is located where existing sidewalks and drives are currently located, and some existing pavement is being removed to allow Pond 1 to expand to provide additional pond volume to attempt to offset any pond volume lost due to the proposed project. The existing 24" RCP pipe outfall from Pond 1 remains in place. Refer to the attached drainage area exhibit.

Existing pond volume: ±54,190 cubic feet (cf)

Proposed pond volume: ±56,265 cubic feet (cf)

A HydroCAD stormwater model was utilized to analyze both the pre-developed and postdeveloped conditions, and the following results were generated for Type III, 24-hour storm events:

	CN	2-yr (cfs)	10-yr (cfs)	25-yr (cfs)	50-yr (cfs)	100-yr (cfs)
Pre-developed:	92	9.1	14.2	17.7	19.9	21.9
Post-Developed:	92	8.8	13.6	17.1	19.3	21.5

Total drainage area to Pond 1: +/-4.2 acres

Per the table above, the stormwater discharge for the post-developed conditions from the revised Pond 1 are slightly less than the pre-developed conditions.

Please refer to the photos below, and attached supporting documentation. If you have any questions or need more information, please feel free to reach me by email (<u>chris.akers@kimley-horn.com</u>) or by phone at 615-476-4764.

Sincerely, Chris Akers, Project Manager

Page 3

Photographs	Observations
<image/>	Southern portion of hospital campus with subject wetland (image taken from internal front drive).
Photographs	Observations
<image/>	East elevation of hospital building where Radiation Oncology addition is proposed (image taken from internal front drive). Construction activity from current ICU Med/ Surg Stepdown project.

Page 4

<image/>	Southern portion of hospital campus with subject wetland (image taken from internal ambulance/ ED drive).
<section-header></section-header>	Observations Existing brick canopy at Patient Discharge to be removed. Construction activity from current ICU Med/ Surg Stepdown project.

Page 5





February 21, 2022

Kimley-Horn and Associates, Inc. 10 Lea Avenue, Suite 400 Nashville, TN 37210

404 Wyman Street, Suite 385 Waltham, MA 02451

RE: Agent Authorization

To Whom It May Concern:

Be advised that I am the Chief Executive Officer of the Portsmouth Regional Hospital located at 333 Borthwick Ave, Portsmouth, NH 03801. I am an authorized agent to the owners of HCA Health Services of New Hampshire, Inc. dba Portsmouth Regional Hospital. As the authorized agent, I hereby authorize and empower:

Kimley-Horn and Associates, Inc. to act as agent/ representative to communicate and submit required information as necessary in obtaining site-related approvals and permits for the proposed Radiation Oncology Addition project located at 333 Borthwick Ave, Portsmouth, NH 03801.


۲

Owner's Signature Dean M. Carucci, CEO

333 Borthwick Avenue Portsmouth, NH 03801 Phone: 436-5110 1-800-685-8282 www.portsmouthhospital.com

#### Details

Property		Ownership	Valuation	
Location Map-Lot Vision Account N	333 BORTHWICK AVE 0240-0002-0001 Jumber 35555	Owner HCA HEALTH SVC OF NH INC D/B/A PRH 32902 C/O DUCHARME MCMILLEN & ASSOC AddressPO BOX 80610, INDIANAPOLIS, IN 46280	Total Last Sale Book/Page	\$86,709,000 \$0 on 2784/1340
<b>Land</b> Parcel Area (AC)	20.87	Zoning Zoning OR		





#### GOVE ENVIRONMENTAL SERVICES, INC.

October 15, 2019

Portsmouth Regional Hospital

Subject: Wetland Delineation Report Portsmouth Regional Hospital 333 Borthwick Ave, Portsmouth, NH

Dear Chris Akers,

Per your request, this letter is to verify that Gove Environmental Services, Inc., performed a site inspection to identify wetlands at Portsmouth Regional Hospital, 333 Borthwick Ave, Portsmouth, NH. Wetlands were evaluated utilizing the following standards:

- 1. US Army Corps of Engineers Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region, Technical Report ERDC/EL TR-12-1 (January 2012).
- 2. Field Indicators for Identifying Hydric Soils in New England Version 4, April 2019. New England Hydric Soils Technical Committee.
- 3. US Army Corps of Engineers National Wetland Plant List, 2018.
- 4. Classification of Wetlands and Deepwater Habitats of the United States. USFW Manual FWS/OBS-79/31 (1979).

Brenden Walden performed the site inspection on 9/17/19. During the site inspection, two areas of wetland were identified on the Site. The wetland areas were demarcated with a series of pink "Wetland Delineation" flagging consecutively labeled:

1 Start – 15 Stop & A1-A22

The attached sketch plan depicts the general location of the flag series, which were used to identify the resource areas in the field. A general description of the wetlands is also provided

The wetland demarcated by the 1 Start - 15 Stop series of flags, delineated a drainage area dominated by emergent vegetation, hydric soils on the wetland border consisted of NE-S1 & HTM-S hydric soil classifications, soil saturation and water staining were also observed. Bordering upland area consisted developed area and impervious surface.


The wetland demarcated by the A1-A22 series of flags, delineated the wetland boundary for a detention basin vegetated with emergent vegetation. The wetland boundary consisted of NE-S with areas of HTM-S. Bordering upland areas consist of maintained lawn areas and impervious surface from surrounding development.

This concludes the wetland delineation report. If I can be of further assistance, please feel free to contact me at (603) 778-0644.

Sincerely,


Brenden Walden Business Manager & Wetland Scientist Gove Environmental Services, Inc.


Enc. Wetland Delineation Sketch





8 Continental Dr Unit H, Exeter, NH 03833-7507 Ph (603) 778 0644 / Fax (603) 778 0654 www.gesinc.biz info@gesinc.biz











# Hydrograph Return Period Recap Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020.4

Hyd. No.	Hydrograph type	Inflow hyd(s)				Peak Out	tflow (cfs)	)			Hydrograph Description
0.	(origin)	nya(s)	1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	Description
1	SCS Runoff			16.61		23.20	28.61	36.05	41.44	47.34	PRE-DEVELOPMENT RUNOFF
2	SCS Runoff			16.61		23.20	28.61	36.05	41.44	47.34	POST-DEVELOPMENT RUNOFF
3	Reservoir	1		9.051		10.72	14.18	17.71	19.92	21.93	PRE-DEVELOPMENT
4	Reservoir	2		8.827		10.59	13.57	17.12	19.33	21.45	POST-DEVELOPMENT


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	16.61	2	716	35,198				PRE-DEVELOPMENT RUNOFF
2	SCS Runoff	16.61	2	716	35,198				POST-DEVELOPMENT RUNOFF
3	Reservoir	9.051	2	722	33,767	1	22.45	9,429	PRE-DEVELOPMENT
4	Reservoir	8.827	2	722	33,767	2	22.41	9,733	POST-DEVELOPMENT
PO		G.gpw			Return F	Period: 2 Ye	ear	Thursday,	05 / 5 / 2022

#### Hyd. No. 2

#### POST-DEVELOPMENT RUNOFF

Hydrograph type Storm frequency	= SCS Runoff = 2 yrs	Peak discharge Time to peak	= 16.61 cfs = 716 min
Time interval	= 2 min	Hyd. volume	= 35,198 cuft
Drainage area	= 4.180 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.00 min
Total precip.	= 3.33 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.910 x 98) + (1.320 x 79) + (1.950 x 98)] / 4.180



3

Thursday, 05 / 5 / 2022


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	23.20	2	716	50,272				PRE-DEVELOPMENT RUNOFF
2	SCS Runoff	23.20	2	716	50,272				POST-DEVELOPMENT RUNOFF
3	Reservoir	10.72	2	722	48,841	1	22.91	13,320	PRE-DEVELOPMENT
4	Reservoir	10.59	2	724	48,841	2	22.80	13,648	POST-DEVELOPMENT
PO		G.gpw	1	1	Return F	⊥ Period: 5 Ye	) ear	Thursday,	 05 / 5 / 2022

#### Hyd. No. 2

#### POST-DEVELOPMENT RUNOFF

Hydrograph type Storm frequency	= SCS Runoff = 5 yrs	Peak discharge Time to peak	= 23.20 cfs = 716 min
Time interval	= 2 min	Hyd. volume	= 50,272 cuft
Drainage area	= 4.180 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.00 min
Total precip.	= 4.43 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.910 x 98) + (1.320 x 79) + (1.950 x 98)] / 4.180



5


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	28.61	2	716	62,900				PRE-DEVELOPMENT RUNOFF
2	SCS Runoff	28.61	2	716	62,900				POST-DEVELOPMENT RUNOFF
3	Reservoir	14.18	2	722	61,470	1	23.21	16,336	PRE-DEVELOPMENT
4	Reservoir	13.57	2	722	61,469	2	23.15	16,866	POST-DEVELOPMENT
PO	ND EXISTIN	G.gpw			Return I	Period: 10 `	Year	Thursday,	05 / 5 / 2022

#### Hyd. No. 2

#### POST-DEVELOPMENT RUNOFF

Hydrograph type	= SCS Runoff	Peak discharge	= 28.61 cfs
Storm frequency	= 10 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 62,900 cuft
Drainage area	= 4.180 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.00 min
Total precip.	= 5.34 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.910 x 98) + (1.320 x 79) + (1.950 x 98)] / 4.180



7


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	36.05	2	716	80,516				PRE-DEVELOPMENT RUNOFF
2	SCS Runoff	36.05	2	716	80,516				POST-DEVELOPMENT RUNOFF
3	Reservoir	17.71	2	722	79,085	1	23.60	20,589	PRE-DEVELOPMENT
4	Reservoir	17.12	2	722	79,085	2	23.53	21,204	POST-DEVELOPMENT
PO	ND EXISTIN	G.gpw			Return F	Period: 25 \	/ear	Thursday,	05 / 5 / 2022

#### Hyd. No. 2

#### POST-DEVELOPMENT RUNOFF

Hydrograph type	= SCS Runoff	Peak discharge	= 36.05 cfs
Storm frequency	= 25 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 80,516 cuft
Drainage area	= 4.180 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.00 min
Total precip.	= 6.60 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.910 x 98) + (1.320 x 79) + (1.950 x 98)] / 4.180



9


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	41.44	2	716	93,438				PRE-DEVELOPMENT RUNOFF
2	SCS Runoff	41.44	2	716	93,438				POST-DEVELOPMENT RUNOFF
3	Reservoir	19.92	2	722	92,008	1	23.88	23,729	PRE-DEVELOPMENT
4	Reservoir	19.33	2	722	92,007	2	23.80	24,417	POST-DEVELOPMENT
PO	ND EXISTIN	G.gpw			Return F	Period: 50 \	/ear	Thursday,	05 / 5 / 2022

#### Hyd. No. 2

#### POST-DEVELOPMENT RUNOFF

Hydrograph type Storm frequency Time interval Drainage area Basin Slope	<ul> <li>SCS Runoff</li> <li>50 yrs</li> <li>2 min</li> <li>4.180 ac</li> <li>0.0 %</li> </ul>	Peak discharge Time to peak Hyd. volume Curve number Hydraulic length	<ul> <li>= 41.44 cfs</li> <li>= 716 min</li> <li>= 93,438 cuft</li> <li>= 92*</li> <li>= 0 ft</li> </ul>
Drainage area	= 4.180 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.00 min
Total precip.	= 7.52 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.910 x 98) + (1.320 x 79) + (1.950 x 98)] / 4.180



11

Thursday, 05 / 5 / 2022


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	47.34	2	716	107,662				PRE-DEVELOPMENT RUNOFF
2	SCS Runoff	47.34	2	716	107,662				POST-DEVELOPMENT RUNOFF
3	Reservoir	21.93	2	722	106,232	1	24.17	27,298	PRE-DEVELOPMENT
4	Reservoir	21.45	2	722	106,231	2	24.10	28,058	POST-DEVELOPMENT
PO	ND EXISTIN	G.gpw			Return F	Period: 100	Year	Thursday,	05 / 5 / 2022

#### Hyd. No. 2

#### POST-DEVELOPMENT RUNOFF

Hydrograph type	= SCS Runoff	Peak discharge	= 47.34 cfs
Storm frequency	= 100 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 107,662 cuft
Drainage area	= 4.180 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.00 min
Total precip.	= 8.53 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.910 x 98) + (1.320 x 79) + (1.950 x 98)] / 4.180



13

Thursday, 05 / 5 / 2022

# SITE CIVIL PLANS FOR PORTSMOUTH REGIONAL HOSPITAL **RADIATION ONCOLOGY ADDITION** 333 BORTHWICK AVENUE, PORTSMOUTH, NH 03801

SITE DATA TABLE									
OWNER OF RECORD	HCA HEALTH SERVICES OF NH INC D/B/A PRH 32902								
SITE ADDRESS		HWICK AVE, ITH, NH 03801							
SITE AREA	± 20	.87 AC							
DISTURBANCE LIMITS W/ THIS PROJECT	± 0	.7 AC							
TAX MAP & LOT	TAX MAP	240, LOT 2-1							
ZONING	OR - OFFIC	E RESEARCH							
SETBACKS	REQUIRED	PROPOSED							
FRONT YARD SETBACK	50'-0"	±40'							
REAR YARD SETBACK	50'-0"	±157'							
SIDE YARD SETBACK	75'-0"	±71' * (EXISTING)							
MIN. OPEN SPACE ON A LOT	30%	±39.0%							
MAX BUILDING COVERAGE	30% ± 20.1%								
BUILDING DA	TA								
	EXISTING	PROPOSED ADDITION							
HOSPITAL BEDS	233	0							
HOSPITAL/ MOB FLOOR PLATE	±173,916 SF	± 8,700 SF							
HOSPITAL GROSS AREA	±427,495 SF	± 8,870 SF							
MEDICAL OFFICE BUILDING GROSS AREA (ATTACHED TO HOSPITAL BUILDING)	±46,665 SF	0 SF							
BUILDING HEIGHT	± 65'-4"	± 14'-8"							

PARKING SUMMARY										
EXISTING DEMOLISHED PROPOSED NET RESULT										
ONSITE STANDARD SPACES	754	11	2	745						
ONSITE ACCESSIBLE (INCLUDING VAN ACCESSIBLE)	29	4	6	31						
OFFSITE STANDARD SPACES*	0	0	490	490						
OFFSITE ACCESSIBLE (INCLUDING VAN ACCESSIBLE)*     0     0     11     11										
TOTAL				1277						


\*PER SATELLITE PARKING LOT DRAWINGS PREPARED BY TIGHE & BOND

#### **REFERENCE PLANS**

- "LOT LINE REVISION PLAN FOR PORTSMOUTH HOSPITAL OFFICE BUILDING ASSOCIATION, ISLINGTON WOOD, LLC AND HCA REALTY INC. (TAX MAP 234, LOTS 7-4A & 7-4B) (TAX MAP 240, LOT 2-2) BORTHWICK AVENUE EXTENSION PORTSMOUTH. NEW HAMPSHIRE DATED JAN 13, 2006 PREPARED BY DOUCET SURVEY, INC., R.C.R.D.
- PLAN #D-33642 "TOPOGRAPHIC PLAN" AT PORTSMOUTH REGIONAL HOSPITAL FOR HCA HEALTH SERVICES OF NH, INC. DATED OCTOBER 10, 2007 BY DOUCET SURVEY.
- "SIDEWALK SITE PLAN" FOR PORTSMOUTH REGIONAL HOSPITAL FOR HCA HEALTH SERVICES OF NH, INC. DATED OCTOBER 22, 2003 BY MILLETTE, SPRAGUE & COLWELL
- "SITE PLAN" FOR PORTSMOUTH REGIONAL HOSPITAL FOR HCA HEALTH SERVICES OF NH, INC. DATED AUGUST 19, 2002 BY MILLETTE, SPRAGUE & COLWELL SHEET 2 OF 3.
- JURISDICTIONAL WETLANDS WERE DELINEATED BY NHSC, INC. ON SEPTEMBER 25, 2007 IN ACCORDANCE WITH THE 1987 CORPS OF ENGINEERS WETLANDS DELINEATION MANUAL, AS REQUIRED BY
- THE NH DES WETLANDS BUREAU. **"TOPOGRAPHIC WORKSEET OF THE POWERLINES BY ISLINGTON &** BORTHWICK AVE." PREPARED BY EASTERN TOPOGRAPHIC FOR
- DOUCET SURVEY, DATED SEPT 25, 2007. "PORTSMOUTH REGIONAL HOSPITAL PHASE 1 ADDITIONS AND RENOVATIONS" BY APPLEDORE ENGINEERING, INC., DATED APRIL 1.2008.
- JURISDICTIONAL WETLANDS DELINEATION BY GOVE ENVIRONMENTAL SERVICES, INC. DATED OCTOBER 2019.
- TOPOGRAPHIC SURVEY BY JAMES VERRA & ASSOCIATES, INC.
- DATED 10/2019. ). SHEETS C-2 AND C-2A OF "PORTSMOUTH HOSPITAL EXPANSION" BY APPLEDORE ENGINEERING, DATED 8/4/11. "REVISED TO ADD REAR PARKING"



CONSERVATION COMMISSION SET: MAY 5, 2022



	Sheet List Table
SHEET NUMBER	SHEET TITLE
C0.00	COVER SHEET
C0.01	GENERAL NOTES
C0.02	SURVEY BY OTHERS
C1.00	EXISTING CONDITIONS - OVERAL
C2.00	SITE DEMOLITION PLAN
C3.00	EROSION CONTROL PLAN - PHASE
C3.01	EROSION CONTROL PLAN - PHASE
C3.02	EROSION CONTROL DETAILS
C4.00	SITE LAYOUT - OVERALL
C4.01	SITE LAYOUT - ENLARGEMENT
C5.00	GRADING & DRAINAGE PLAN
C6.00	SITE UTILITY PLAN
C7.00	SITE DETAILS
C7.01	SITE DETAILS

## **PROJECT DESIGN TEAM**

#### ARCHITECT

GOULD TURNER GROUP, P.C. 615 3RD AVENUE SOUTH, SUITE 700 NASHVILLE, TN 37210 PHONE: (615) 254-1500 CONTACT: CHRIS DUMONT, AIA

#### SURVEY

JAMES VERRA & ASSOCIATES, INC. 101 SHATTUCK WAY, SUITE 8 NEWINGTON, NH 03801 PHONE: (603) 436-3557 CONTACT: JIM VERRA, LLS

### **CIVIL ENGINEER**

KIMLEY-HORN AND ASSOCIATES, INC. 404 WYMAN STREET, SUITE 385 WALTHAM, MA 02451 PHONE: (781) 328-0676 CONTACT: CHRIS AKERS

#### ENVIRONMENTAL

GOVE ENVIRONMENTAL SERVICES, INC 8 CONTINENTAL DR, UNIT H EXTER, NH 03833 PHONE: (603) 778-0654 CONTACT: BRENDEN WALDEN

## **UTILITY CONTACTS**

#### WATER/ SANITARY SEWER

PORTSMOUTH DEPT OF PUBLIC WORKS MIKE JENKINS 680 PEVERLY HILL ROAD PORTSMOUTH, NH 03801 PHONE: (603) 427-1530

#### NATURAL GAS NORTHERN UTILITIES, INC. JEFF INGLISH 325 WEST ROAD PORTSMOUTH, NH 03801 PHONE (603) 436-0310

**TELEPHONE/ CABLE** CONSOLIDATED COMMUNICATIONS 1575 GREENLOAD ROAD GREENLAND, NH 03840 PHONE: (800) 240-5019

#### **M,P,E & T CONSULTANTS**

I.C. THOMASSON ASSOCIATES, INC 2950 KRAFT DRIVE, SUITE 500 NASHVILLE, TN 37204 PHONE: (615) 346-3400 CONTACT: BOYD JOHNSON

#### **STRUCTURAL ENGINEER**

STANLEY D. LINDSEY & ASSOCIATES, LTD. 750 OLD HICKORY BLVD, BLD 1, SUITE 175 BRENTWOOD, TN 37027 PHONE: (615) 320-1735 CONTACT: MARK HILNER

#### ELECTRIC

PUBLIC SERVICES OF NH/ EVERSOURCE WAYNE BROOKS 1700 LAFAYETTE ROAD PORTSMOUTH, NH 03801 PHONE:(800) 662-7764

 $\mathbf{\hat{s}}$ (im TION

Ош

Ω DESIGNED BY: DRAWN BY: CHECKED BY: 05/05/202 DATE: KIMLEY-HORN PROJECT NO. 118252004 COVER SHEET

#### CONTRACTOR RESPONSIBILITIES:

- PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR:
- THE CONTRACTOR SHALL VERIFY ALL PROPOSED AND EXISTING CONDITIONS INCLUDING Α. UTILITIES (INVERTS, CONNECTIONS, MATERIALS, ETC.) AND DIMENSIONS WITHIN THE LIMITS OF WORK PRIOR TO THE START OF CONSTRUCTION.
- REFER TO ARCHITECTURAL DRAWINGS FOR DETAILED BUILDING INFORMATION. Β.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL NOTIFICATIONS AND LIAISONS WITH UTILITY C. COMPANIES DURING THE PROCESS OF LOCATING, RELOCATING, AND TYING INTO PUBLIC UTILITIES.
- PRIOR TO COMMENCING LAND DISTURBANCE ACTIVITY, THE LIMITS OF LAND D. DISTURBANCE SHALL BE CLEARLY AND ACCURATELY DEMARCATED WITH STAKES, RIBBONS, OR OTHER APPROPRIATE MEANS. THE LOCATION AND EXTENT OF ALL AUTHORIZED LAND DISTURBANCE SHALL OCCUR INSIDE THE APPROVED LIMITS INDICATED ON THE APPROVED PLANS.
- 2. DURING CONSTRUCTION:
  - THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEVIATIONS FROM THESE PLANS AND Α. SPECIFICATIONS WITHOUT PRIOR WRITTEN CONSENT OF THE ENGINEER MAY CAUSE THE WORK TO BE UNACCEPTABLE.
  - R THE CONTRACTOR SHALL USE MATERIALS AND EMPLOY CONSTRUCTION METHODS IN ORDER TO COMPLY WITH THE DRAWINGS AND SPECIFICATIONS. WHERE A CONFLICT OCCURS, THE STRICTEST DESIGN SHALL GOVERN. THE ENGINEER'S REVIEW OF SHOP DRAWINGS, PRODUCT DATA, ETC., DOES NOT RELIEVE THE CONTRACTOR FROM COMPLYING WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL INFORM THE ENGINEER IN WRITING OF ANY SPECIFIC DEVIATIONS AND OBTAIN ENGINEER'S WRITTEN APPROVAL OF THE SPECIFIC DEVIATION.
  - C. IT IS SOLELY THE CONTRACTOR'S RESPONSIBILITY TO FOLLOW ALL APPLICABLE SAFETY CODES AND REGULATIONS DURING ALL PHASES OF CONSTRUCTION.
  - ALL CONSTRUCTION MUST CONFORM TO THE STANDARDS, SPECIFICATIONS, AND CODES D. OF THE GOVERNING MUNICIPALITIES.
  - CONSTRUCTION SHALL MEET ALL CURRENT STANDARDS SET FORTH IN THE AMERICANS F WITH DISABILITIES ACT.
  - F IF THE CONTRACTOR DAMAGES ANY EXISTING UTILITIES DURING CONSTRUCTION, HE SHALL, AT HIS OWN EXPENSE, REPLACE OR REPAIR THE UTILITIES TO ORIGINAL CONDITION AND QUALITY AS APPROVED BY THE OWNER AND REPRESENTATIVE OF THE APPROPRIATE UTILITY COMPANY.
  - G. SUFFICIENT BARRICADES, LIGHTS, SIGNS, AND OTHER TRAFFIC CONTROL METHODS IN ACCORDANCE WITH GOVERNING ORDINANCES MAY BE NECESSARY FOR THE PROTECTION AND SAFETY OF THE PUBLIC. SAID CONTROL DEVICES SHALL BE PER THE MANUAL OF TRAFFIC CONTROL DEVICES, M.U.T.C.D., CURRENT EDITION, AND SHALL BE PROVIDED AND MAINTAINED THROUGHOUT CONSTRUCTION.
  - TRAFFIC CONTROLS AND OTHER WARNING DEVICES SHALL BE INSTALLED PRIOR TO THE н COMMENCEMENT OF ANY WORK ON CITY, COUNTY, OR NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION ROADS. THEY SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION AND SHALL REMAIN IN PLACE UNTIL THE CONCLUSION OF ALL WORK.
  - ALL WARNING DEVICES SHALL BE EITHER TYPE I BARRICADES OR DRUMS WITH WARNING LIGHTS ON EVERY OTHER DEVICE. THEY SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), CURRENT EDITION, AND PORTSMOUTH STANDARDS FOR COLOR, SIZE, REFLECTIVITY, HEIGHT, AND PLACEMENT
  - FIRE DEPARTMENT ACCESS SHALL BE MAINTAINED AT ALL TIMES.
  - Κ. CONTRACTOR SHALL SHORE AND BRACE ALL EARTH, FORMS, CONCRETE, STEEL, WOOD, AND MASONRY TO RESIST GRAVITY, EARTH, WIND, THERMAL, CONSTRUCTION, AND MISCELLANEOUS LOADS DURING CONSTRUCTION.
  - ON-SITE BURIAL OF DEBRIS IS PROHIBITED.
  - M. UNLESS OTHERWISE NOTED THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ALL FABRICATED MATERIALS TO THE ENGINEER. DESIGN DOCUMENTS SHALL NOT BE REPRODUCED AS SHOP DRAWINGS.
  - IN CASE OF UNFORESEEN CONSTRUCTION COMPLICATIONS OR DISCREPANCIES, THE N CONTRACTOR IS TO IMMEDIATELY NOTIFY THE ENGINEER IN WRITING.
  - Ο. ALL REQUIRED TESTING REPORTS SHALL BE AVAILABLE AT THE JOB SITE.
  - Ρ. AS-BUILT DRAWINGS OF ROADWAYS, STORM DRAINS, SANITARY SEWER AND WATER LINES, FIELD APPROVAL BY THE ENGINEER, AND ALL APPLICABLE BONDS ARE REQUIRED PRIOR TO FINAL ACCEPTANCE BY THE OWNER.
  - Q. CONTRACTOR SHALL MAINTAIN CONTINUOUS UTILITY SERVICE TO ALL EXISTING BUILDINGS THROUGHOUT CONSTRUCTION UNLESS APPROVAL FOR SERVICE INTERRUPTION IS OBTAINED FROM THE OWNERS IN ADVANCE.
  - THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS TO ENSURE THAT THE NEW R WORK SHALL FIT INTO THE EXISTING SITE IN THE MANNER INTENDED AND AS SHOWN ON THE DRAWINGS. SHOULD ANY CONDITIONS EXIST THAT ARE CONTRARY TO THOSE SHOWN ON THE DRAWINGS, THE CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE PRIOR TO PERFORMING ANY WORK IN THE AREA INVOLVING DIFFERENCES. NOTIFICATION SHALL BE IN THE FORM OF A DRAWING OR SKETCH INDICATING FIELD MEASUREMENTS AND NOTES RELATING TO THE AREA.
  - ANY FOREIGN ITEM FOUND DURING CONSTRUCTION IS THE PROPERTY OF THE OWNER S THIS INCLUDES, BUT IS NOT LIMITED TO, PRECIOUS METALS, COINS, PAPER CURRENCY, ARTIFACTS AND ANTIQUITIES.
  - т THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE DONE TO THE PREMISES OR ADJACENT PREMISES, OR INJURIES TO THE PUBLIC DURING THE CONSTRUCTION OF THE WORK, WHETHER CAUSED BY HIMSELF, HIS SUBCONTRACTORS, OR THE CARELESSNESS OF ANY OF HIS EMPLOYEES.
  - U. THE CONTRACTOR SHALL FURNISH, INSTALL AND MAINTAIN ALL NECESSARY TEMPORARY WORKS FOR THE PROTECTION OF THE WORK AND THE PUBLIC, INCLUDING BARRICADES, WARNING SIGNS, LIGHTS, ETC.
  - V THE CONTRACTOR ACKNOWLEDGES & AGREES THAT THE WORK IS ENTIRELY AT HIS RISK UNTIL SITE IS ACCEPTED, AND HE WILL BE HELD RESPONSIBLE FOR ITS SAFETY BY THE OWNER. THE CONTRACTOR WILL INDEMNIFY THE OWNER & OWNER'S REPRESENTATIVE FROM LIABILITY AT THE SITE THROUGHOUT THE CONSTRUCTION PROCESS.
  - W. THE CONTRACTOR SHALL GIVE ALL NECESSARY NOTICES AND OBTAIN ALL PERMITS AND PAY ALL LEGAL FEES. HE SHALL ALSO COMPLY WITH ALL CITY, COUNTY AND STATE BUILDING LAWS, ORDINANCES OR REGULATIONS RELATING TO BUILDING SIDEWALKS, STREETS, BLASTING, PUBLIC INFRASTRUCTURE, STORMWATER REGULATIONS, ETC.
  - THE CONTRACTOR IS TO CHECK AND VERIFY ALL MEASUREMENTS, LEVELS, ETC. BEFORE ORDERING MATERIALS AND PROCEEDING WITH THE WORK, AND IS TO BE RESPONSIBLE FOR THE SAME.

## **CONTRACTOR RESPONSIBILITIES (CONT.):**

- THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR THE DAMAGE OR LOSS OF ANY Υ. REFERENCE POINTS AND HUBS DURING THE CONSTRUCTION OF HIS WORK, AND SHALL BEAR THE COST OF REPLACING SAME.
- Z. CARE SHALL BE TAKEN TO PROTECT ANY UTILITIES, TREES, ETC. WHICH ARE TO REMAIN AND NOT TO BE DISTURBED BY THE CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES TO SUCH PROPERTY.

#### **DEMOLITION INFORMATION:**

NOTIFICATIONS

THE CONTRACTOR SHALL NOTIFY THE OWNER AND CITY INSPECTOR(S) 24 HOURS PRIOR TO ANY DEMOLITION OR CONSTRUCTION.

- DISPOSAL GUIDELINES:
- ONLY ITEMS SPECIFICALLY NOTED TO BE DEMOLISHED SHALL BE REMOVED FROM THE Α. SITE.
- REMOVE EXISTING PAVED AREAS AS SHOWN INCLUDING DRIVEWAYS, SIDEWALKS, PARKING AREAS, SERVICE AREAS, EQUIPMENT PADS, AND ALL MISCELLANEOUS PAVING.
- ALL DEBRIS RESULTING FROM DEMOLITION SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY BY THE CONTRACTOR IN ACCORDANCE WITH LOCAL STATE AND FEDERAL REGULATIONS. BACKFILL ALL TRENCHES AND EXCAVATIONS RESULTING FROM DEMOLITION.
- ALL DEMOLISHED MATERIAL BECOMES THE PROPERTY OF THE CONTRACTOR UNLESS D OTHERWISE NOTED.
- TREE PROTECTION GUIDELINES:

PROTECT ALL EXISTING TREES NOTED "TO REMAIN" AND ALL ITEMS TO BE TURNED OVER TO THE OWNER DURING DEMOLITION. TAKE ALL NECESSARY PRECAUTIONS AND PROTECTIVE MEASURES. ANY EXISTING ITEMS TO BE TURNED OVER TO THE OWNER WHICH ARE DAMAGED DURING DEMOLITION SHALL BE REPAIRED AT NO ADDITIONAL COST TO THE OWNER. TREES WHICH ARE DAMAGED WILL BE REPLACED OR REIMBURSED AT A RATE TO BE DETERMINED BY THE OWNER.

UTILITIES:

3.

- A. PRIOR TO REMOVING OR ABANDONING ANY UTILITY THE CONTRACTOR SHALL VERIFY THAT NO UPSTREAM SERVICE WILL BE TERMINATED. THE CONTRACTOR SHALL INFORM THE ENGINEER IN WRITING OF ANY TERMINATION NOT SHOWN ON THE PLANS.
- ALL ABANDONED WATER LINES, STORM SEWER PIPE, SANITARY SEWER PIPES, GAS Β. LINES, OR ANY OTHER ABANDONED UNDERGROUND UTILITY SHALL BE ABANDONED IN PLACE UNLESS NOTED OTHERWISE.

#### SITE INFORMATION:

1. THE FOLLOWING ARE APPLICABLE TO ALL CIVIL DOCUMENTS:

- A. WHERE A DETAIL SECTION, TYPICAL SECTION, OR A NOTE IS SHOWN FOR ONE CONDITION, IT SHALL APPLY FOR ALL LIKE OR SIMILAR CONDITIONS, UNLESS OTHERWISE NOTED ON THE PLANS.
- EXISTING AND PROPOSED CONTOURS ARE AT ONE (1) FOOT INTERVALS.
- ALL DIMENSIONS ARE TO FACE OF CURB UNLESS OTHERWISE NOTED.
- ALL PIPE LENGTHS SPECIFIED IN THESE PLANS ARE THE HORIZONTAL DISTANCE AND D ARE SHOWN FOR REFERENE ONLY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE ACTUAL LENGTHS BASED ON PROPOSED PIPE SLOPE.
- PIPE LENGTHS IN PLANS ARE MEASURED FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE UNLESS OTHERWISE NOTED.

## **EROSION AND SEDIMENT CONTROL INFORMATION:**

1. COMPREHENSIVE:

- THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO OR CONCURRENT WITH LAND-DISTURBING ACTIVITIES.
- В PROVISIONS TO PREVENT EROSION OF SOIL FROM THE SITE SHALL BE AT A MINIMUM IN CONFORMANCE WITH THE REQUIREMENTS OF THE NEW HAMPSHIRE EROSION AND SEDIMENT CONTROL HANDBOOKS. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- C. FAILURE TO INSTALL, OPERATE, OR MAINTAIN ALL EROSION CONTROL MEASURES WILL RESULT IN ALL CONSTRUCTION BEING STOPPED ON THE JOB SITE UNTIL SUCH MEASURES ARE CORRECTED BACK TO THE STANDARDS SPECIFIED IN THE NEW HAMPSHIRE EROSION AND SEDIMENT CONTROL HANDBOOKS, CURRENT EDITION.
- D. EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- F EROSION CONTROL DEVICES SHALL BE INSTALLED PRIOR TO LAND DISTURBANCE. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE APPROVED PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE FINAL PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY.
- F THE CONSTRUCTION OF THE SITE WILL COMMENCE WITH THE INSTALLATION OF EROSION CONTROL MEASURES SUFFICIENT TO CONTROL SEDIMENT DEPOSITS AND EROSION. ALL SEDIMENT CONTROL WILL BE MAINTAINED UNTIL ALL UPSTREAM GROUND WITHIN THE CONSTRUCTION AREA HAS BEEN COMPLETELY STABILIZED WITH PERMANENT VEGETATION AND ALL ROADS/DRIVEWAYS HAVE BEEN PAVED.
- CONSTRUCTION EXITS SHALL BE CONSTRUCTED AT EACH POINT OF ENTRY OR EXIT G. FROM THE SITE AND SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH STONE AS CONDITIONS DEMAND, REPAIR, AND/OR CLEANOUT OF ANY STRUCTURES USED TO TRAP SEDIMENT. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES OFF SITE ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY. ACCESS POINTS PROTECTED WITH A CONSTRUCTION EXIT SHALL BE OTHERWISE BARRICADED UNTIL THE SITE IS STABILIZED.

## **CONCRETE INFORMATION (SITE WORK ONLY):**

PRODUCT CRITERIA

- A. UNLESS OTHERWISE NOTED CEMENT SHALL BE TYPE I OR III CONFORMING TO ASTM C150. AGGREGATES SHALL BE NORMAL WEIGHT CONFORMING TO ASTM C33.
- CONCRETE SHALL CONFORM TO ACI BUILDING CODE (318-89). UNLESS NOTED В CONCRETE SHALL BE NORMAL WEIGHT AND HAVE A 28 DAY COMPRESSIVE STRENGTH OF 3,500 P.S.I.
- SLUMP SHALL BE 3" TO 5" FOR REGULAR MIX. LARGER SLUMP SHALL BE PERMITTED WITH WATER REDUCING ADMIXTURES AND WRITTEN CONSENT OF THE ENGINEER.
- THE RELATIONSHIP BETWEEN MAXIMUM AGGREGATE SIZE TO MINIMUM AMOUNT OF D. CEMENT IN CONCRETE PAVEMENT (LB. PER C.Y. OR MIX) SHALL BE AS FOLLOWS: 1" - 520, 3/4" - 540, 1/2" - 590, 3/8" - 610.

2. CURING CRITERIA:

- Α. CONCRETE CURING SHALL COMPLY WITH ACI 308. CURING PROCESS SHALL START IMMEDIATELY FOLLOWING INITIAL SET. CURING SHALL BE BY CURING COMPOUND.
- CONCRETE EXPOSED TO THE WEATHER SHALL BE AIR-ENTRAINED IN ACCORDANCE Β. WITH ACI 318-89 TABLE 4.1.1. NORMAL WEIGHT CONCRETE SLABS SHALL HAVE AIR CONTENT IN ACCORDANCE WITH ACI 302.IR-89 TABLE 5.2.7A.
- C. HOT WEATHER CONCRETING SHALL COMPLY WITH ACI 305. NO CONCRETE ABOVE 90 DEGREES FAHRENHEIT SHALL BE POURED. LOWER CONCRETE TEMPERATURE BY COOLING WATER AND AGGREGATE. FORMS, STEEL, AND SUBGRADE SHALL BE SPRINKLED WITH COLD WATER. AFTER FINISHING CONCRETE USE LIGHT FOG SPRAY UNTIL CURING COMPOUND IS USED.
- D. COLD WEATHER CONCRETING SHALL COMPLY WITH ACI 306. SPECIAL MATERIAL PROCEDURES SHALL BE PROVIDED DURING PLACING AND CURING OF CONCRETE BELOW 40 DEGREES FAHRENHEIT.
- CURING, HOT, AND COLD WEATHER CONCRETING PROCEDURES ARE ONLY GIVEN AS A F GUIDE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PREVENT CONCRETE DAMAGE AND CRACKS. DAMAGED OR CRACKED CONCRETE WILL NOT BE ACCEPTED.

## **REINFORCING STEEL INFORMATION (SITE WORK ONLY):**

PRODUCT CRITERIA

- REINFORCING STEEL SHALL CONFORM TO ASTM A-615, GRADE 60 AND GRADE 40 FOR #3 Α. AND SMALLER BARS. MINIMUM LAP 48" DIAMETER.
- WELDED WIRE FABRIC SHALL CONFORM TO ASTM A-185, MINIMUM LAP SHALL BE 8". R
- REINFORCING THAT IS WELDED SHALL BE WELDABLE TYPE AND CONFORM TO ASTM C. A-706

## **PAVEMENT INFORMATION:**

- 1. PAVEMENT:
  - ALL MATERIALS, EQUIPMENT, METHODS OF CONSTRUCTION, AND WORKMANSHIP SHALL Α. CONFORM TO THE NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION. NHDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, CURRENT EDITION.
  - SEE PAVEMENT DETAILS ON CONSTRUCTION DOCUMENTS FOR SPECIFIC DESIGN INFORMATION AND REQUIREMENTS.
  - ALL CURB AND GUTTER TO BE 24" AND CONSTRUCTED OF 3000 P.S.I. CONCRETE UNLESS OTHERWISE NOTED.
- SIGNING AND STRIPING:
- SIGNING AND STRIPING TO BE PROVIDED BY THE CONTRACTOR ACCORDING TO THE DRAWINGS AND SPECIFICATIONS.
- B. ALL STRIPING TO BE THERMOPLASTIC UNLESS OTHERWISE NOTED.

## STORM SEWER NOTES:

- REINFORCED CONCRETE PIPE SHALL BE RCP CLASS III UNLESS OTHERWISE NOTED WITH BELL-AND-SPIGOT AND GASKETED JOINTS WITH ASTM C 443 RUBBER GASKETS.
- 2. FILL HEIGHTS OVER 13' REQUIRE CLASS IV RCP STORM PIPE.
- 3. STORM INLETS SHALL BE PRECAST IN ACCORDANCE WITH PORTSMOUTH PUBLIC WORKS SPECIFICATIONS WHICH MEET OR EXCEED ASTM C 478.
- 4. ALL MANHOLE FRAMES AND COVERS ARE TO BE PER PORTSMOUTH PUBLIC WORKS STANDARD DETAIL FOR DIMENSIONS AND MATERIALS AND AS BELOW IF NOT OTHERWISE INDICATED. FERROUS; 24-INCH (610-MM) ID BY 7- TO 9-INCH (175- TO 225-MM) RISER WITH 4-INCH- (102-MM-) MINIMUM WIDTH FLANGE AND 26-INCH- (660-MM-) DIAMETER COVER. INCLUDE INDENTED TOP DESIGN WITH LETTERING CAST INTO COVER, USING WORDING EQUIVALENT TO "STORM SEWER."
- 5. MATERIAL: GRAY IRON ASTM A48 CLASS 30 UNLESS OTHERWISE INDICATED.
- ALL HDPE PIPE SHALL BE CORRUGATED HIGH DENSITY POLYETHYLENE SMOOTH INTERIOR PIPE. HDPE PIPE SHALL CONFORM TO ASTM D3350 WITH SOIL TIGHT JOINTS.
- 7. ALL HDPE SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS AND AASHTO SECTION 30.
- 8. CONTRACTOR TO PROVIDE AND INSTALL MANUFACTURER RECOMMENDED FITTINGS ON RCP CONNECTIONS TO HDPE STRUCTURES.
- 9. REFER TO PIPE CHART FOR CASTING TYPES. INSTALL REDUCERS AS NECESSARY PER MANUFACTURER'S SPECIFICATIONS TO ACCOMMODATE LARGER INLET SIZES.
- 10. FOLLOW CONSTRUCTION PLANS AND MANUFACTURER DETAILS, SPECIFICATIONS, AND INSTALLATION INSTRUCTION AS INCLUDED WITHIN THE PLANS AND PROVIDED BY MANUFACTURER FOR THE INSTALLATION OF WATER QUALITY AND DETENTION SYSTEMS.
- 11. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR ALL STORM SEWER PIPE, STRUCTURES, WATER QUALITY STRUCTURES, AND DETENTION STRUCTURES FOR ENGINEER AND OWNER APPROVAL PRIOR TO ORDERING MATERIALS.

## **CLEARING AND GRUBBING:**

- ON THE PLANS. Β.
- C.

- F

## **GRADING NOTES:**

- Α.
- R
- С RECOMMENDATIONS.
- D.
- LISTED IN THE BID DOCUMENTS.

G

- TESTS AS REQUIRED.
- SITE.
- ACTION TAKEN.
- Κ.
- М CONTRACTOR.
- PART OF THIS SPECIFICATION:

- SIEVE.
- STANDARD EFFORT
- MM) DROP.

PROVIDE POSITIVE DRAINAGE AWAY FROM BUILDINGS AT ALL LOCATIONS UNLESS Ο. OTHERWISE NOTED.

SHALL APPLY.

Q.

DO NOT EXCEED CLEARING AND GRUBBING LIMITS OF CONSTRUCTION LINES INDICATED

ALL AREAS OUTSIDE THE LIMITS OF CONSTRUCTION LINE SHALL NOT BE CROSSED BY HEAVY EQUIPMENT OR USED FOR STORING HEAVY EQUIPMENT OR MATERIALS.

NO EQUIPMENT SHALL BE STORED UNDER THE DRIP LINE OF TREES TO REMAIN.

DO NOT FALL ANY TREES OR PUSH PILES OF DEBRIS AGAINST ANY TREES TO REMAIN.

REMOVE ALL STUMPS, ROCKS, ASPHALT & CONCRETE DEBRIS, ETC. AND DISPOSE OFF SITE IN ACCORDANCE WITH LOCAL, STATE & FEDERAL REGULATIONS.

CONTACT ALL UTILITY AUTHORITIES WHO HAVE LINES WITHIN THE CLEARING AND GRUBBING LIMITS BEFORE STARTING WORK

ALL EROSION CONTROL SEDIMENT BARRIERS, SILT FENCES, AND TREE PROTECTION DEVICES SHALL BE INSTALLED PRIOR TO STARTING CLEARING AND GRUBBING.

AFTER STAKING IS COMPLETED. TREES WITHIN GRADING LIMITS TO BE SAVED WILL BE IDENTIFIED BY THE OWNER'S REPRESENTATIVE. FIELD CHANGES TO GRADING PLANS SHALL BE MADE FOR SMOOTH TRANSITION OF GRADES AROUND ALL TREES WHICH REQUITE TREE WELLS WITHIN THE GRADING LIMITS.

G. ALL CLEARING SHALL BE LIMITED TO AREAS TO BE GRADED WITHIN 15 CALENDAR DAYS.

TOPSOIL SHALL BE STORED ON SITE IN LOCATIONS APPROVED BY THE OWNER'S REPRESENTATIVE. DRAINAGE SHALL ROUT AROUND THESE TOPSOIL STOCKPILES FOR THE DURATION OF THE GRADING OPERATIONS. EROSION CONTROL MEASURES SHALL PREVENT THE LOSS OF TOPSOIL MATERIAL.

UNSUITABLE SOILS SHALL BE UNIFORMLY SPREAD ACROSS NON-STRUCTURAL FILL AREAS AND COVERED WITH TOPSOIL AND SEEDED.

FILL AREA SHALL BE PROOF-ROLLED WITH RUBBER-TIRED EQUIPMENT WITH A MINIMUM WEIGHT OF FIFTEEN TONS PRIOR TO BEGINNING FILL OPERATION. AREAS WHICH ARE SOFT OR UNSTABLE SHALL BE UNDERCUT UNTIL STABLE SOILS ARE FOUND. RE-COMPACTION OF THESE SOILS SHALL BE PER GEOTECHNICAL ENGINEER

CUT AREA SHALL BE PROOF-ROLLED AFTER FINAL SUBGRADE IS ACHIEVED IN THE SAME MANNER AS FILLED AREAS. SOFT OR UNSTABLE SOILS SHALL BE SCARIFIED TO A DEPTH OF 12" AND RE-COMPACTED PER GEOTECHNICAL ENGINEER RECOMMENDATIONS.

ALL GRADING SHALL BE COMPLETED TO THE LEVEL INDICATED BY THE SCOPE OF WORK

ELEVATIONS SHOWN ON THE PLANS IS THE FINISH GRADE ELEVATION.

GRADING SHALL BE SEQUENCED SO THAT BASE STONE IS PLACED WITHIN 10 CALENDAR DAYS PF ACHIEVING OPTIMUM SUBGRADE COMPACTION.

SOILS TESTING LABORATORY/ SOILS ENGINEER. CONTRACTOR WILL EMPLOY A QUALIFIED SOILS TESTING LABORATORY/ ENGINEER TO OBSERVE THIS WORK AND MAKE

HAVE EARTH BORROW FILL, AGGREGATE, AND TOPSOIL, AND STRUCTURAL FILL TESTED AND APPROVED BY DESIGNATED TESTING LABORATORY BEFORE MOVING IT TO THE JOB

CONTRACTOR SHALL OBSERVE PROOF-ROLLING OF AREAS WHERE BUILDING AND PAVING WILL BE LOCATED TO DETERMINE ADEQUACY OF SOIL COMPACTION AND IN-PLACE SOILS. OTHER AREAS WILL BE INSPECTED BY SOILS ENGINEER TO DETERMINE ADEQUACY IN THOSE AREAS. IF SOILS ARE NOT ADEQUATE TO BEAR WEIGHTS THAT WILL BE IMPOSED, TESTING LABORATORY WILL OBSERVE AND REPORT CORRECTIVE

TEST IN-PLACE SOIL AND FILLED AND COMPACTED AREAS. IF THESE ARE NOT ADEQUATE TO BEAR WEIGHTS IMPOSED. TESTING LABORATORY WILL ADVICE THE OWNER'S REPRESENTATIVE OF THEIR RECOMMENDATIONS. HE WILL DIRECT ANY CORRECTIVE MEASURES THAT ARE NECESSARY.

SOILS COMPACTION TESTING OF IN-PLACE AND FILLED AND COMPACTED AREAS WILL BE PERFORMED BY TESTING LABORATORY IN ACCORDANCE WITH THEIR REQUIREMENTS.

THE SOILS ENGINEER'S AND TESTING LABORATORY'S FEES WILL BE PAID BY THE

APPLICABLE SPECIFICATIONS FOR COMPACTED FILL: THE FOLLOWING CURRENT AMERICAN SOCIETY OF TESTING MATERIALS (ASTM) STANDARDS ARE HEREBY MADE

 D421-58, DRY PREPARATION OF SOIL SAMPLES FOR GRAIN-SIZE ANALYSIS AND DETERMINATION OF SOIL CONSTANTS. D422-63, STANDARD METHOD OF PARTICLE SIZE ANALYSIS OF SOILS.

• D1140-54, METHOD OF TEST FOR AMOUNT OF MATERIAL IN SOILS FINER THAN NO.200

 D698, METHOD FOR LABORATORY COMPACTION CHARACTERISTICS OF SOIL USING D1557-78, STANDARD TEST METHODS FOR MOISTURE-DENSITY RELATIONS OF SOILS


AND SOIL-AGGREGATE MIXTURES USING 10 LB. (4.54-KG) RAMMER AND 18-INCH (457


CONTRACTOR SHALL REVIEW THE SITE SPECIFIC GEOTECHNICAL REPORT PRIOR TO COMMENCING WITH GRADING OPERATIONS. WHERE CONFLICTS BETWEEN THE GRADING NOTES AND GEOTECHNICAL REPORT EXIST, THE MORE STRINGENT REQUIREMENT

CONTRACTOR IS RESPONSIBLE FOR DOCUMENTING WITH LOAD TICKETS, PHOTOGRAPHS, LOG BOOK, VIDEO RECORDING AND OTHER MEANS AS NECESSARY TO VERIFY THE INSTALLATION OF STORMWATER BEST MANAGEMENT PRACTICES REQUIRED BY THE LOCAL MUNICIPALITY AND JURISDICTION. AS-BUILT TOPOGRAPHY AND UTILITY PLANS HAVING BEEN PREPARED BY A QUALIFIED LAND SURVEYOR ARE REQUIRED TO BE SUBMITTED TO KIMLEY-HORN AT THE CONCLUSION OF THE PROJECT FOR VERIFICATION OF DESIGN INTENT. ANY MODIFICATIONS TO THE GRADING AND UTILITY SYSTEMS REQUIRED, NOT PREVIOUSLY APPROVED BY THE OWNER AND ENGINEER ARE THE RESPONSIBILITY OF THE CONTRACTOR.


 $\widehat{\boldsymbol{\mathbf{x}}}$ 

Ζ Ο Ζ Ο Δш C A sh Ш ע ⊲  $\sim \sim$ Ο \_ Ω Οz S Ο ŽΣ S 0 M  $\square$ 0 





Drawing name: K:\NSH\_LDEV\118252004 - portsmouth - cancer center - 2021\4-CADD\plansheets\C0.02 SURVEY BY OTHERS.dwg C0.02 SURVEY BY OTHERS May 05, 2022 3:03pm by: Zack.Newman



SMH DPW#5481(

SEE NOTE 8

ТВМ "D

LARGE SURVEY NAIL

SET IN UTILITY POLE

PSNH 37

1.0' ABOVE GRADE ELEV=29.03

<sup>3</sup>20. 79

TRANSFORMER ON CONC. PAD

BOUNDARY CURVE TABLE

CURVEARCLENGTHRADIUSDELTAANGLECHORDBEARINGCHORDLENGTHC2294.05464.6436°15'38"S68°03'15"W289.17

BOUNDARY LINE TABLE LINE BEARING DISTANCE L3 N 41°56'56" W 10.00 L15 N 87°57'24" W 895.13 LINE BEARING

BRICK COLUMN

**APPROXIMATE** 

SEWER

#333 MULTI LEVEL BRICK

VA PUBLIC WAY

ТВМ "В'

CUT X ON

TOP FLANGE BOLT ELEV=28.37

CONCRETE

SBORTHWICK AVENUE

. TBM "A" LARGE SURVEY NAIL

20

SET IN UTILITY POLE PSNH 317/3 ELEV=26.73

120

LEV.=27.70

SMH DPW#519

h SEWER DETAIL

*160 FEET* 


40 METERS


METAL


ACCESS

COVER


								■   10451	
NOTES	<u>:</u>						7		N.COM
1.		RECORD	C/O DUCHA	RME MCMIL	LEN & ASS	DC ATES		D2457	WWW.KIMLEY-HORN. RN AND ASSOCIATES, INC.
	DEED REFER TAX SHEET	ENCE / LOT A	2784/1340 240-02-01			+0200		385 W/AI	.KIMLE
2.	ZONED: MINIMUM LO	OFFICE, T AREA3 ACRE 300'	/RESEARCH (OF	r) FRC SIDE	NT YARD SE E YARD SETI R YARD SE <sup>-1</sup>	ЗАСК	75'		328.0676 WWW.KIMLEY-HO 2019 KIMLEY-HORN AND ASSOCIATES, INC.
3.	THE RELATIV	E ERROR OF CL	OSURE WAS LE	SS THAN '	1 FOOT IN 1	5,000 F	EE		0676 0167-
4.	APPROXIMAT STRUCTURES COMPILED FF AGENCIES.	DN OF ALL UND E AND ARE BAS (IE CATCH BAS ROM PLANS PRO ALL CONTRACTO NY EXCAVATION	SED UPON THE SINS, MANHOLE OVIDED BY UTIL ORS SHOULD NO	FIELD LOC S, WATER ITY COMPA DTIFY, IN W	ATION OF A GATES ETC.) NIES AND G VRITING, SAIL	LL VISIE AND I OVERNM AGEN	NFORMA MENTAL CIES		MAIN:781.328.
5.	OBSERVATION (2011)(EPOCI	DATUM: NAD 1 N AND NGS "OF H: 2010.0000), NTUM: NAVD 198	PUS" SOLUTION. US SURVEY FO	REFERENC OT.	E FRAME: N	AD83	DUTH "A		2
6.	ENGINEER OF BENCHMARKS	R CONTRACTOR 5 PRIOR TO THE ES ARE TO BE	TO VERIFY SITE E ESTABLISHMEI	E BENCHMA NT OF ANY	NRKS BY LEN GRADES OF	/EL <mark>ING</mark> R ELEV#	<del>BETWEE</del> A <i>TIONS</i> .	V 2	
	CHANCE FLO COUNTY, NEW BY THE FEDE LIMIT OF 300	SHOWN HEREON ODPLAIN) AS ID W HAMPSHIRE, M ERAL EMERGENC O' EVERSOURCE	DENTIFIED ON FL MAP NUMBER 3 CY MANAGEMEN ELECTRIC EASE	LOOD INSUI 3015C0260 T AGENCY. EMENT.	RANCE RATE DE, EFFECTIV	MAP,	RECKING	GHAI	IR 2
9. 10.	THE DELINEA HAMPSHIRE	RATOR ENCLOSU TION OF THE W CERTIFIED WETL	ETLANDS SHOW AND SCIENTIST	/N HEREON #297, GOV	WAS BY BR				
11.	THE SUBSUR GROUND PEN	TAL DRIVE, UNIT FACE UTILITIES IETRATING RADA	SHOWN HEREO	N WERE IDI					EW HA
12.	THE LIBERTY	UNITIL GAS LIN MUTUAL PARC ED BY GROUND	EL & A 6" CLE	DI WATER L	INE IN THE				MOUTH, N
REFERE	ENCE PLAN	<u>S:</u>					SN.		RTS
1.		S-BUILT EASEM							PO
2.	SCHILLER S,	N OF AMERICA, /S—OCEAN ROAI 5—A, DATED 7/	D S/S, 115 KV	TRANSMIS	SION LINE #	U181, N	11L <b>O</b> 4, "	®-1 <b>ह</b> हु: ∀	30.
3.	SUBDIVISION	OF LAND, FRAI URANCE COMPA	NETAL REALTY	TRUST CO	MPAMY, OPT	ONED	TO LIBEI		_
	I CERTIFY TO THIS ARE THOS	TO RSA 676 THAT THIS SUI TITLE AND THAT SE OF PUBLIC C	RVEY PLAT IS T THE LINES OF DR PRIVATE STF	NOT A SU STREETS REETS OR	IBDIVISION P AND WAYS WAYS ALREA	SHOWN	ΝT		
		James Ver		ARE SHOV 11-19- DA	-2019		No. 625 JAMES VERRA		
						s Dov	SIGNATURE		
						REVISIONS			
O REV. NC	11–08–2019 D. DATE			IEW & COMME RIPTION	ENT				JV APPR'D
	LIMI	TED EX.						M	
			BORTHW			DEOL			~ ∞ တ <del>C</del>
		TSMOU SESSOR						E	
		SESSOR	f	or		DATE	:		05/05/2022
	HCA HI	EALTH S	SERVICE.	S OF	NEW I				
JA	AMES VE	SUI	TTUCK WAY TE 8	IATES,	INC.	DATE: JOB NO SCALE:		11—19- 23834 40'	-2019
		NEWINGTON, N.	H., 03801—7876 36—3557 			DWG N	AME:	23834	
	GTD PROJECT JV COPYRIGHT	 ©2019 by JAMES	GT DRAWN VERRA and ASSOC	N BY	-	P_AN I SHEET:		23834 1 of 1	










Drawing name: K:\NSH\_LDEV\118252004 - portsmouth - cancer center - 2021\4-CADD\plansheets\C3.00 EROSION CONTROL PLAN.dwg C3.00 EROSION CONTROL PLAN - PHASE 1 May 05, 2022 3:05pm by: Zack.Newman











SITE DATA	HCA HEALTH S				PAVEMENT LEGEND	1			
OWNER OF RECORD	INC D/B/A		-		DESCRIPTION	DET #/ SHT #			
SITE ADDRESS	333 BORT PORTSMOL		,		SIDEWALK CONCRETE	1 / C7.00		ONSITE STANDARI	) SPACES
		.87 AC						ONSITE ACCESSIB	LE (INCLUDING VAN AC
DISTURBANCE LIMITS W/ THIS PROJECT	± 0 TAX MAP	.7 AC 240, LO	T 2-1		ASPHALT PAVEMENT	2 / C7.00		OFFSITE STANDAR	RD SPACES*
ZONING	OR - OFFIC	E RESE	ARCH	• • • • • • • • • • • • • • • • • • •	CONCRETE PAVEMENT	3 / C7.00		OFFSITE ACCESSI	BLE (INCLUDING VAN A
SETBACKS	REQUIRED		POSED					TOTAL	
FRONT YARD SETBACK	50'-0" 50'-0"		±40' ±157'		MOBILE IMAGING CONCRETE PAD	4 / C7.00		*PER SATELLITE PA	RKING LOT DRAWINGS
REAR YARD SETBACK	75'-0"		(EXISTING)		SPECIALITY SIDEWALK PAVEMENT	NOTE THIS			
MIN. OPEN SPACE ON A LOT	30%	±	39.0%		SPECIALITY SIDEWALK PAVEIMENT	SHEET			
MAX BUILDING COVERAGE	30%	±	20.1%	SPECIALI	TY SIDEWALK PAVEMEN	Τ ΝΟΤΕ			
BUILDING DA	<b>\</b> ΤА	·			RETE SURFACE WITH MEDIUM BROOM FI		1-		
	EXISTING		POSED DITION	BY ARCHITECT.	THOCHROME COLOR HARDENER, COLOR SEAL CURED, COLORED SURFACE WITH S SEAL-VOC MATTE FINISH CLEAR SEALANT	COFIELD	411		
HOSPITAL BEDS	233		0		APPLY MATERIALS PER MANUFACTURER				
HOSPITAL/ MOB FLOOR PLATE	±173,916 SF		,700 SF				<u> </u>		
HOSPITAL GROSS AREA	±427,495 SF	± 8	,870 SF					E06	
(ATTACHED TO HOSPITAL BUILDING)	±46,665 SF		0 SF					30	0' EVERSOURCE ELECT
BUILDING HEIGHT	± 65'-4"	±	14'-8"						100' WE
SITE LAYOUT NOTES									F
1. INSTALL CONCRETE JOINTS WHER									
AND DETAILS. ALIGN ON WALLS, B EVENLY SPACE BETWEEN ELEMEN PROVIDE EXPANSION JOINTS BETV	ITS AS SHOWN.								
PAVEMENT AND ALL VERTICAL ELE CURBS, ETC.).	EMENTS (WALLS,					4 <sup>+</sup> , 4 <sup>-</sup> ,			
<ol> <li>ALL RADIUS ARE 3' UNLESS OTHEF</li> <li>LAYOUT ALL CURVES SMOOTHLY V</li> </ol>		-			V				
<ul> <li>CHANGES AT TANGENT POINTS.</li> <li>4. ALL DIMENSIONS ARE TO THE FAC OTHERWISE NOTED.</li> </ul>	E OF CURB UNLE	SS	=	Þ					
5. LAYOUT ALL ELEMENTS IN FIELD A OWNER'S REPRESENTATIVE FOR A		RE		62.0	250				
BEGINNING ANY CONSTRUCTION. 6. CONTRACTOR TO TAKE ALL PREC						$\vee$ $\vee$		d	
AND AVOID SITE UTILITIES. ALL UT SHOWN ON DRAWING. VERIFY LOC CONSIDER SUCH WHEN ESTIMATIN	CATIONS AND			W "+C	,11.98 S ↓ ↓ ↓	$\checkmark$ $\lor$			· · · · · · · · · · · · · · · · · · ·
7. ALL LANDSCAPE ISLANDS SHALL E TOPSOIL 4" ABOVE THE CURB LINE	E MOUNDED WIT	Н	111	,	$\forall  \forall  \lor$	$\lor$ $\lor$	$\checkmark$		
POSITIVE DRAINAGE. 8. ALL PAVEMENT MARKINGS AND SI	GNAGE SHALL BE								
INSTALLED PER THE MANUAL ON U CONTROL DEVICES, LATEST EDITIO	ON.			11-	in the second s		· ·		
<ol> <li>9. ALL PAVEMENT MARKINGS ON-SIT OTHERWISE NOTED.</li> <li>10. SAW CUT LINES SHALL BE DONE IN</li> </ol>			-	411	$\vee$				2
LINE A MINIMUM OF 18" FROM THE PAVEMENT.						V			
11. IF DURING CONSTRUCTION ACTIVI OF THE PRESENCE OF STATE AND	FEDERALLY	NCE				V		☆ /	
PROTECTED PLANT AND/OR ANIMA DISCOVERED, WORK SHALL COME STOP AND CITY OF PORTSMOUTH	TO AN IMMEDIAT					V J			
WITHIN TWO WORKING DAYS OF T ANIMAL SPECIES FOUND ON THE S	HE PLANT AND/O								
12. PRIOR TO THE START OF THE CLEA GRUBBING, OR ANY SOIL DISTURB	ANCE CONTACT							R10	
PORTSMOUTH STORMWATER MGM FOR A POTENTIAL SOIL EROSION A CONTROL. PRE-INSPECTION MEET	AND SEDIMENT	530					$\neg$	RIO	
13. THE CONTRACTOR MUST PROVIDE PLAN, IF APPLICABLE, TO CITY OF	A DEWATERING	i						ia.	
BUILDING AND SITE DEVELOPMEN 610-7243 FOR REVIEW PRIOR TO T	HE EROSION	)3)							R10
CONTROL MEASURES PRE-INSPEC 14. ALL CONDITIONS ON THIS PLAN SH EFFECT IN PERPETUITY PURSUAN	ALL REMAIN IN								
REQUIREMENTS OF THE SITE PLAN REGULATIONS.			/				\ \	R3'	
15. RECORDING NOTE: • THIS SITE PLAN SHALL BE					FLU	JSH CONDITION, TY DETAIL 3/ C7.		à la	
ROCKINGHAM COUNTY RE     ALL IMPROVEMENTS SHO	WN ON THIS SITE						ð	F P	
PLAN SHALL BE CONSTRU MAINTAINED IN ACCORDA BY THE PROPERTY OWNE	NCE WITH THE P						è la	F 19.	5
SHALL BE MADE TO THIS THE EXPRESS APPROVAL	SITE PLAN WITHO				PROPOSEI	D CONCRETE -	is in the second		
PORTSMOUTH PLANNING 16. TOPOGRAPHY AND EXISTING CON	DITIONS FROM F				WHEEL	STOP, TYP.; TAIL 6/ C7.01	× Fo		- EXIST
SURVEY PERFORMED BY JAMES V INC. ON 10/2019. 17. FLOOD HAZARD ZONE: ZONE X (OL		ATES,			/ ))	ò			TOR
ANNUAL CHANCE FLOODPLAIN) PE #33015C0260F, DATED 01/29/2021.						is the			EXIST GENE TO RI
<ol> <li>HORIZONTAL DATUM IS BASED ON</li> <li>VERTICAL DATUM BASED ON NAVE</li> </ol>	088.				$\phi$	20			
20. JURISDICTIONAL WETLANDS DELIN ENVIRONMENTAL SERVICES, INC. 1									R30'
2019 IN ACCORDANCE WITH: 2012 CORPS OF ENGINEE DELINEATIONS MANUAL, 1		ORT			✓ PARKING, TYP.; DETAIL 11/ C7.00	To Brook To			-C- 1.30'
<ul> <li>ERDC/ EL TR-12-1.</li> <li>FIELD INDICATORS FOR IE</li> </ul>	ENTIFYING HYDE	RIC		·	٩ ٢	PAL PP			
SOILS IN NEW ENGLAND, 7 2019.	VERSION 4, APRII	L			5,		5		P P P
US ARMY CORPS OF ENGI WETLAND PLAN LIS, 2018.     CLASSIFICATION OF WETL		ιL		/	EXISTING TREE TO REMAIN				R3' R50'
DEEPWATER HABITATS O MANUAL FWS/ OBS-79/31 (	F THE U.S USFW (1979).						*		V V V
21. UNDERGROUND ELECTRIC, WATER LOCATIONS BASED ON SURFACE N	R, GAS, & SEWER		/		· · · · · · · · · · · · · · · · · · ·			EXISTING TREE	F F F F F F F F F F F F F F F F F F F
<i>INC</i> ON 10/2019.				300' EVERSOU		1		TO REMAIN	
L			` / ני			- · · -	PA	ROPOSED ACCESSIB RKING SIGN (TYP.);	LE
							DE	ETAIL 12/ C7.00	
			L	//					
						/ $/$		IDEWALK, CURB,	
	/			t.			AND DRIVE		
/ / / / / /									
	/ //				11/				





#### **GRADING NOTES**

- ELEVATIONS OF EXISTING UTILITIES AT CONNECTION POINTS PRIOR TO GRADING OR INSTALLATION OF ANY PROPOSED UTILITIES. DISCREPANCIES ARE FOUND
- BY LOCAL INSPECTOR.
- GRADE, WILL BE ESTABLISHED TO TEMPORARY VEGETATION. MULCH, TEMPORARY VEGETATION OR PERMANENT VEGETATION SHALL BE COMPLETED ON ALL EXPOSED AREAS WITHIN 14 DAYS AFTER PERMANENT VEGETATION UPON COMPLETION.
- UNIFORMLY SPREAD OVER SEEDED AREA WITHIN 24 HOURS OF SEEDING. IF UNABLE TO ACCOMPLISH, MULCH SHALL BE USED AS A STEEPER THAN 2.5:1 AND WITH A HEIGHT OF TEN FEET OR GREATER BUFFERS, SHALL BE STABILIZED WITH THE APPROPRIATE EROSION CONTROL MATTING OR BLANKETS.
- ROAD OR STREET.
- MUST CALL FOR AN INSPECTION TO OBTAIN A PERMIT TO GRADE. YOUR SCHEDULE.
- ACCORDING TO LOCAL AND STATE REQUIREMENTS AND AS STIPULATED IN THE STORMWATER POLLUTION PREVENTION PLAN. EACH DEVICE IS TO BE MAINTAINED OR REPLACED IF SEDIMENT ACCUMULATION HAS REACHED ONE HALF THE CAPACITY OF THE DEVICE. ADDITIONAL DEVICES MAY BE NECESSARY AS THE PROJECT PROGRESSES AND NEW CHANNELS HAVE DEVELOPED.


- ACTIVITIES.
- SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- THIS CONTRACT. REFER TO LANDSCAPING PLANS FOR AREAS TO
- PLANS AND EROSION CONTROL PLANS
- LAWN AREAS.
- BEST MANAGEMENT PRACTICES, AND/OR OTHER WATER QUALITY MANAGEMENT FACILITIES SHALL BE PROVIDED AND MAINTAINED AT ALL TIMES DURING CONSTRUCTION. DAMAGES TO ADJACENT PROPERTY AND/OR THE CONSTRUCTION SITE CAUSED BY THE CONTRACTOR'S OR PROPERTY OWNER'S FAILURE TO PROVIDE AND MAINTAIN ADEQUATE DRAINAGE AND EROSION/SEDIMENT CONTROL FOR THE CONSTRUCTION AREA SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNER AND/OR CONTRACTOR.
- CALL--811 OR 1-800-752-6007
- RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT RESULT FROM THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY UNDERGROUND UTILITIES TO REMAIN.







Drawing name: K:\NSH\_LDEV\118252004 - portsmouth - cancer center - 2021\4-CADD\plansheets\C7.00 SITE DETAILS.dwg C7.00 SITE DETAILS May 05, 2022 3:06pm by: Zack.Newman



Drawing name: K:\NSH\_LDEV\118252004 - portsmouth - cancer center - 2021\4-CADD\plansheets\C7.00 SITE DETAILS.dwg C7.01 SITE DETAILS May 05, 2022 3:06pm by: Zack.Newman