# SITE PLAN REVIEW TECHNICAL ADVISORY COMMITTEE PORTSMOUTH, NEW HAMPSHIRE

#### **WORK SESSION**

# Conference Room A City Hall, Municipal Complex, 1 Junkins Avenue

2:00 PM November 14, 2023

#### **AGENDA**

**2:00 PM** 569 Submarine Way

**Site Plan Review** 

Portsmouth Submarine Memorial Association (Owner) Ambit Engineering INC, Engineer

(LUTW-23- 13)



200 Griffin Road, Unit 3, Portsmouth, NH 03801 Phone (603) 430-9282 Fax 436-2315

7 November 2023

Peter Stith, Chair, City of Portsmouth TAC 1 Junkins Avenue Portsmouth, NH 03801

RE: Request for TAC Workshop Review at 569 Submarine Way, Museum Expansion

Dear Mr. Stith and TAC Members:

On behalf of the Portsmouth Submarine Memorial Association, we are pleased to submit the attached plan set for <u>TAC Workshop Review</u> for the above-mentioned project and request that we be placed on the agenda for your **November 14**, **2023**, Meeting. The project is the proposed construction of an addition to the exiting Albacore Park Museum with the associated and required site improvements.

The following plans are included in our submission:

- Cover Sheet This shows the Development Team, Legend, Site Location, and Abutters.
- Boundary Plan C1 This plan shows the existing site property boundary and the existing site easements.
- Existing Conditions Plan Orthophoto C2 This plan shows the existing site detail based on photography from a drone flight.
- Existing Conditions Plan C3 This plan shows the existing site in detail.
- Site Plan C4 This plan shows the site development with the proposed addition and the circulation and layout with setbacks. The project received a Variance from the Board of Adjustment for the expansion of the museum use.
- Utility Plan C5 This plan shows site utilities. The project will connect utilities internally, with a section of an existing water service being relocated to the same building entrance.
- Grading and Drainage Plan C6 This plan shows the relocation of existing drainage at the proposed addition.
- Erosion Control Notes and Details D1 and Details D2 These plans shows site details.
- Floor Plans and Elevations A1.1 and A 2.1 This plan shows the Architectural design for the buildings.

We look forward to TAC review of this submission and the Committees feedback.

Sincerely,

John R. Chagnon, PE

## **OWNER:**

# PORTSMOUTH SUBMARINE MEMORIAL ASSOCIATION

569 SUBMARINE WAY PORTSMOUTH, NH 03801 TEL: (603) 436-3680

## LAND SURVEYOR & CIVIL ENGINEER:

## AMBIT ENGINEERING

A DIVISION OF HALEY WARD, INC. 200 GRIFFIN ROAD, UNIT 3 PORTSMOUTH, NH 03801 (603) 430-9282

#### **ARCHITECT:**

## PORT ONE ARCHITECTS

959 ISLINGTON STREET PORTSMOUTH, NH. 03801 TEL: (603) 436-8891

# LAND USE ATTORNEY:

# HOEFLE, PHOENIX, GORMLEY & ROBERTS, PLLC

127 PARROTT AVENUE PORTSMOUTH, NH 03801 TEL. (603) 436-0666

#### INDEX OF SHEETS

- BOUNDARY PLAN

- EXISTING CONDITIONS ORTHOPHOTO

- EXISTING CONDITIONS PLAN

SITE PLAN

UTILITY PLAN

- GRADING & DRAINAGE PLAN

D1-D2 - DETAILS

- ARCHITECTURAL PLANS

#### UTILITY CONTACTS

**ELECTRIC: EVERSOURCE** 1700 LAFAYETTE ROAD PORTSMOUTH, N.H. 03801

Tel. (603) 436-7708, Ext. Tel. (603) 294-5144 ATTN: MICHAEL BUSBY, P.E. (MANAGER)

SEWER & WATER: PORTSMOUTH DEPARTMENT OF PUBLIC WORKS 680 PEVERLY HILL ROAD PORTSMOUTH, N.H. 03801 Tel. (603) 427-1530 ATTN: JIM TOW

**COMMUNICATIONS:** COMMUNICATIONS

1575 GREENLAND ROAD GREENLAND, N.H. 03840 Tel. (603) 427-5525 ATTN: JOE CONSIDINE

iconsidine@fairpoint.com

N/F 1010 US ROUTE 1 BYPASS, LLC 720 LAFAYETTE ROAD SEABROOK, NH 03874

> N/F ALLAN I. PECHNER 399 MAPLEWOOD AVENUE #3 PORTSMOUTH, N.H. 03801 5573/1754

5582/0945

5646/0912

CAPE CORAL, FL 33904 4235/1400

N/F MATTHEW C. BEAL &

HEIDI L. MEDLYN

242 LESLIE DRIVE

PORTSMOUTH, N.H. 03801

5766/2758

N/F JAMES J. & CARLA J. MURPHY REV TRUST 214 LESLIE DRIVE PORTSMOUTH, N.H. 03801 5967/2916

6452/2890

N/F GERALD R. & DOLORES BROWN N/F JEFFREY J.. & KELLY L. MEE N/F STATE OF NEW HAMPSHIRE IRREVOCABLE TRUST 920 SE 46th STREET APT. 2A JAMES J. & CARLA J. MURHPY TRUSTEES GERALD R. & DOLORES BROWN TRUSTEES 174 LESLIE DRIVE PORTSMOUTH, N.H. 03801 4860/0981

N/F JEANE CLEMENTS 122 LESLIE DRIVE

N/F DAR BUILDERS LLC 305 MASSABESIC STREET MANCHESTER, N.H. 03103 6397/0611

PORTSMOUTH, NH 03801 6397/0611

N/F JOANNE S. & PETER K. MOGREN

250A NORTHWEST STREET

N/F CHRISTIAN SHORE CONDOMINIUM 250 NORTHWEST STREET PORTSMOUTH, NH 03801

# **REQUIRED PERMITS:**

PORTSMOUTH ZONING BOARD: APPROVED PORTSMOUTH PLANNING BOARD: PENDING

## LEGEND:

NOW OR FORMERLY RECORD OF PROBATE ROCKINGHAM COUNTY REGISTRY OF DEEDS MAP 11/LOT 21 IRON ROD FOUND IRON PIPE FOUND IRON ROD SET DRILL HOLE FOUND DRILL HOLE SET

GRANITE BOUND w/IRON ROD FOUND PROPERTY LINE

SETBACK LINE

EDGE OF PAVEMENT (EP) CONTOUR SPOT ELEVATION UTILITY POLE

ELECTRIC METER TRANSFORMER ON CONCRETE PAD ELECTRIC HANDHOLD/PULLBOX

WATER SHUT OFF/CURB STOP

PIPE CLEANOUT GATE VALVE **HYDRANT** 

CATCH BASIN SEWER MANHOLE

DRAIN MANHOLE

WATER METER MANHOLE TEST BORING

> TEST PIT LANDSCAPED AREA

CAST IRON PIPE COPPER PIPE CORRUGATED METAL PIPE DUCTILE IRON PIPE

POLYVINYL CHLORIDE PIPE REINFORCED CONCRETE PIPE HYDRANT CENTERLINE

HYD EDGE OF PAVEMENT ELEVATION FINISHED FLOOR

TBM TEMPORARY BENCH MARK **TYPICAL** UTILITY HANDHOLE PROPOSED MUSEUM BUILDING

ALBACORE PARK 569 SUBMARINE WAY PORTSMOUTH, N.H.

\(\frac{\psi}{\psi}\)\(\psi\)\

CI

COP

CMP

PVC



200 Griffin Road, Unit 3 Portsmouth, NH 03801 WWW.HALEYWARD.COM PLAN SET SUBMITTAL DATE: 7 NOVEMBER 2023

NATURAL GAS: UNITIL 325 WEST ROAD

ATTN: DAVE BEAULIEU

CABLE: XFINITY BY COMCAST 180 GREENLEAF AVE. PORTSMOUTH, N.H. 03801 PORTSMOUTH, N.H. 03801 Tel. (603) 266-2278 ATTN: MIKE COLLINS

N/F ANDREA L. ARDITO & BRAD R. LEBO 121 NORTHWEST STREET PORTSMOUTH, NH 03801

MAPLEWOOD

N/F DONNA J. FLAGG LIVING TRUST DONNA J. FLAGG, TRUSTEE

N/F SAMANTHA SMART & DEREK SWEITZER 202 LESLIE DRIVE PORTSMOUTH, N.H. 03801

LOCUS MAP

**PROJECT ABUTTERS:** 

PROPOSED MUSEUM BUILDING

ALBACORE PARK

569 SUBMARINE WAY

PORTSMOUTH, NEW HAMPSHIRE

SITE PLANS

N/F WILLIAM & MARTHA **ROULANGER** 354 POST ROAD GREENLAND, N.H. 03840 4614/0005

PORTSMOUTH, N.H. 03801 5313/1380

130 LESLIE DRIVE PORTSMOUTH, N.H. 03801

6084/1599

DIG SAFE

LA

CI

COP

CMP

DI

**PVC** 

**RCP** 

HYD

TBM

APPROVED BY THE PORTSMOUTH PLANNING BOARD

N/F JULIANN C. LEHNE & WILLIAM A. LEHNE JR 73 NORTHWEST STREET 6198/2447

N/F MICHAEL GEORGE PETRIN KATIE MARIE LAVERRIERE 239 NORTHWEST STREET PORTSMOUTH, N.H. 03801 2304/1890

N/F AMANDA B. MORNEAULT

137 NORTHWEST STREET

PORTSMOUTH, N.H. 03801

6479/2400

N/F JOSEPH F. & ROSE M. CALDERARA 230 LESLIE DRIVE PORTSMOUTH, N.H. 03801 2320/1967

N/F PAMELA EIFFE 186 LESLIE DRIVE PORTSMOUTH, NH 03801 JEFFREY J. MEE & KELLY L. MEE TRUSTEES 6098/2784 6497/2676

N/F JEFFREY J. MEE & KELLEY L. MICHAUD MEE TRUST 146 LESLIE DRIVE PORTSMOUTH, N.H. 03801

N/F CUTTS MANSION CONDOMINIUM 525 MAPLEWOOD AVENUE PORTSMOUTH, N.H. 03801 5549/413 D-38356

N/F BRIAN BLANCHETTE 250B NORTHWEST STREET PORTSMOUTH, NH 03801

P.O. BOX 483, 7 HAZEN DRIVE


CONCORD, N.H. 03302


5014/1442

CHAIRMAN


DATE


*-\373-452.02* 







P:\NH\5010373-Portsmouth\_Submarine\_Memorial\_ Assn\452.02-1 Submarine Way, Portsmouth-JRC\2023 Site Plan\Plans & Specs\Site\452.02 Survey 2023.dwg, 1









IF REQUIRED THE CONTRACTOR SHALL OBTAIN AN NPDES PHASE II STORMWATER PERMIT AND SUBMIT A NOTICE OF INTENT (N.O.I) BEFORE BEGINNING CONSTRUCTION AND SHALL HAVE ON SITE A STORMWATER POLLUTION PREVENTION PLAN (S.W.P.P.P.) AVAILABLE FOR INSPECTION BY THE PERMITTING AUTHORITY DURING THE CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CARRYING OUT THE S.W.P.P.P. AND INSPECTING AND MAINTAINING ALL BMP'S CALLED FOR BY THE PLAN. THE CONTRACTOR SHALL SUBMIT A NOTICE OF TERMINATION (N.O.T.) FORM TO THE REGIONAL EPA OFFICE WITHIN 30 DAYS OF FINAL STABILIZATION OF THE ENTIRE SITE OR TURNING OVER CONTROL OF THE SITE TO ANOTHER OPERATOR.

THE FOLLOWING REPRESENTS THE GENERAL OBSERVATION AND REPORTING PRACTICES THAT SHALL BE FOLLOWED AS PART OF THIS PROJECT:

OBSERVATIONS OF THE PROJECT FOR COMPLIANCE WITH THE SWPPP SHALL BE MADE BY THE CONTRACTOR AT LEAST ONCE A WEEK OR WITHIN 24 HOURS OF A STORM 0.25 INCHES OR GREATER

AN OBSERVATION REPORT SHALL BE MADE AFTER EACH OBSERVATION AND DISTRIBUTED TO THE ENGINEER, THE OWNER, AND THE CONTRACTOR;

3. A REPRESENTATIVE OF THE SITE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE AND REPAIR ACTIVITIES;

4. IF A REPAIR IS NECESSARY, IT SHALL BE INITIATED WITHIN 24 HOURS OF REPORT.

INSTALL PERIMETER CONTROLS, i.e., SILTSOXX AND CATCH BASIN PROTECTION AROUND THE LIMITS OF DISTURBANCE BEFORE ANY EARTH MOVING OPERATIONS. THE USE OF HAYBALES IS NOT

THE CONTRACTOR SHALL CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE(S) PRIOR TO ANY EXCAVATION ACTIVITIES. PLACE FODS AS NEEDED.

CUT AND GRUB ALL TREES, SHRUBS, SAPLINGS, BRUSH, VINES AND REMOVE OTHER DEBRIS AND RUBBISH AS REQUIRED.

ROUGH GRADE SITE/EXCAVATE FOR FOUNDATION.

LAYOUT AND INSTALL ALL BURIED UTILITIES AND SERVICES UP TO 10' OF THE PROPOSED BUILDING FOUNDATIONS, CAP AND MARK TERMINATIONS OR LOG SWING TIES.

CONSTRUCT BUILDING

CONNECT UTILITIES.

PLACE BINDER LAYER OF PAVEMENT FOR SIDEWALKS.

PLANT LANDSCAPING IN AREAS OUT OF WAY OF BUILDING CONSTRUCTION. PREPARE AND STABILIZE FINAL SITE GRADING BY ADDING TOPSOIL, SEED, MULCH AND FERTILIZER.

AFTER BUILDINGS ARE COMPLETED, FINISH ALL REMAINING LANDSCAPED WORK

CONSTRUCT SIDEWALKS.

REMOVE TRAPPED SEDIMENTS FROM COLLECTION DEVICES AS APPROPRIATE, AND THEN REMOVE TEMPORARY EROSION CONTROL MEASURES UPON COMPLETION OF FINAL STABILIZATION OF THE SITE.

#### PROJECT DESCRIPTION

THE PROJECT CONSISTS OF A BUILDING ADDITION WITH WALKWAYS.

THE TOTAL AREA TO BE DISTURBED IS APPROXIMATELY 10,000 S.F.

BASED ON THE USCS WEB SOIL SURVEY THE SOILS ON SITE CONSIST OF 799 WHICH IS URBAN LAND COMPLEX. SITE WAS DISTURBED FOR PARK CONSTRUCTION.

THE STORMWATER RUNOFF FROM THE SITE WILL BE DISCHARGED VIA A CLOSED DRAINAGE SYSTEM TO THE CITY OF PORTSMOUTH CLOSED DRAINAGE SYSTEM WHICH ULTIMATELY FLOWS TO INNER INNER CUTS COVE THEN TO THE PISCATAQUA RIVER.

#### GENERAL CONSTRUCTION NOTES

THE EROSION CONTROL PROCEDURES SHALL CONFORM TO SECTION 645 OF THE "STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION" OF THE NHDOT, AND "STORM WATER MANAGEMENT AND EROSION AND SEDIMENT CONTROL HANDBOOK FOR URBAN AND DEVELOPING AREAS IN NEW HAMPSHIRE". THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

DURING CONSTRUCTION AND THEREAFTER, EROSION CONTROL MEASURES ARE TO BE IMPLEMENTED AS NOTED. THE SMALLEST PRACTICAL AREA OF LAND SHOULD BE EXPOSED AT ANY ONE TIME DURING DEVELOPMENT. NO DISTURBED AREA SHALL BE LEFT UNSTABILIZED FOR MORE THAN 45

ANY DISTURBED AREAS WHICH ARE TO BE LEFT TEMPORARILY, AND WHICH WILL BE REGRADED LATER DURING CONSTRUCTION SHALL BE MACHINE HAY MULCHED AND SEEDED WITH RYE GRASS TO

THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

DUST CONTROL: DUST CONTROL MEASURES SHALL INCLUDE BUT ARE NOT LIMITED TO SPRINKLING WATER ON EXPOSED AREAS, COVERING LOADED DUMP TRUCKS LEAVING THE SITE, AND TEMPORARY

DUST CONTROL MEASURES SHALL BE UTILIZED SO AS TO PREVENT THE MIGRATION OF DUST FROM THE SITE TO ABUTTING AREAS. IF TEMPORARY STABILIZATION PRACTICES, SUCH AS TEMPORARY VEGETATION AND MULCHING, DO NOT

ADEQUATELY REDUCE DUST GENERATION, APPLICATION OF WATER OR CALCIUM CHLORIDE SHALL BE APPLIED IN ACCORDANCE WITH BEST MANAGEMENT PRACTICES. SILTSOXX SHALL BE PERIODICALLY INSPECTED DURING THE LIFE OF THE PROJECT AND AFTER EACH

STORM, ALL DAMAGED SILTSOXX SHALL BE REPAIRED. SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED IN A SECURED LOCATION.

ALL FILLS SHALL BE PLACED AND COMPACTED TO REDUCE EROSION, SLIPPAGE. SETTLEMENT. SUBSIDENCE OR OTHER RELATED PROBLEMS.

ALL NON-STRUCTURAL, SITE-FILL SHALL BE PLACED AND COMPACTED TO 90% MODIFIED PROCTOR DENSITY IN LAYERS NOT EXCEEDING 18 INCHES IN THICKNESS UNLESS OTHERWISE NOTED.

FROZEN MATERIAL OR SOFT, MUCKY OR HIGHLY COMPRESSIBLE MATERIAL. TRASH. WOODY DEBRIS. LEAVES, BRUSH OR ANY DELETERIOUS MATTER SHALL NOT BE INCORPORATED INTO FILLS.

FILL MATERIAL SHALL NOT BE PLACED ON FROZEN FOUNDATION SUBGRADE.

DURING CONSTRUCTION AND UNTIL ALL DEVELOPED AREAS ARE FULLY STABILIZED, ALL EROSION CONTROL MEASURES SHALL BE INSPECTED WEEKLY AND AFTER EACH ONE HALF INCH OF RAINFALL

THE CONTRACTOR SHALL MODIFY OR ADD EROSION CONTROL MEASURES AS NECESSARY TO ACCOMMODATE PROJECT CONSTRUCTION.

ALL ROADWAYS AND PARKING AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE. ALL CUT AND FILL SLOPES SHALL BE SEEDED/LOAMED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED: BASE COURSE GRAVELS HAVE BEEN INSTALLED ON AREAS TO BE PAVED

- A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED
- A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED
- EROSION CONTROL BLANKETS HAVE BEEN INSTALLED.
- IN AREAS TO BE PAVED, "STABLE" MEANS THAT BASE COURSE GRAVELS MEETING THE REQUIREMENTS OF NHDOT STANDARD FOR ROAD AND BRIDGE CONSTRUCTION, 2016, ITEM 304.2 HAVE BEEN INSTALLED.

STABILIZATION SHALL BE INITIATED ON ALL LOAM STOCKPILES, AND DISTURBED AREAS, WHERE CONSTRUCTION ACTIVITY SHALL NOT OCCUR FOR MORE THAN TWENTY-ONE (21) CALENDAR DAYS BY THE FOURTEENTH (14TH) DAY AFTER CONSTRUCTION ACTIVITY HAS PERMANENTLY OR TEMPORARILY CEASED IN THAT AREA.

STABILIZATION MEASURES TO BE USED INCLUDE:

- TEMPORARY SEEDING;
- MULCHING.

ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE. WHEN CONSTRUCTION ACTIVITY PERMANENTLY OR TEMPORARILY CEASES WITHIN 100 FEET OF NEARBY SURFACE WATERS OR DELINEATED WETLANDS, THE AREA SHALL BE STABILIZED WITHIN SEVEN (7) DAYS OR PRIOR TO A RAIN EVENT. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN THESE AREAS, SILTSOXX, MULCH BERMS, HAY BALE BARRIERS AND ANY EARTH/DIKES SHALL BE REMOVED ONCE PERMANENT MEASURES ARE ESTABLISHED.

DURING CONSTRUCTION, RUNOFF WILL BE DIVERTED AROUND THE SITE WITH EARTH DIKES. PIPING OR STABILIZED CHANNELS WHERE POSSIBLE. SHEET RUNOFF FROM THE SITE WILL BE FILTERED THROUGH SILTSOXX, MULCH BERMS, HAY BALE BARRIERS, OR SILT SOCKS. ALL STORM DRAIN BASIN INLETS SHALL BE PROVIDED WITH FLARED END SECTIONS AND TRASH RACKS. THE SITE SHALL BE STABILIZED FOR THE WINTER BY OCTOBER 15.

#### MAINTENANCE AND PROTECTION

THE SILTSOXX BARRIER SHALL BE CHECKED AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL

SILTSOXX SHALL BE REMOVED ONCE SITE IS STABILIZED, AND DISTURBED AREAS RESULTING FROM SILTSOXX REMOVAL SHALL BE PERMANENTLY SEEDED.

THE CATCH BASIN INLET BASKET SHALL BE INSPECTED WITHIN 24 HOURS AFTER EACH RAINFALL OR DAILY DURING EXTENDED PERIODS OF PRECIPITATION. REPAIRS SHALL BE MADE IMMEDIATELY, AS NECESSARY, TO PREVENT PARTICLES FROM REACHING THE DRAINAGE SYSTEM AND/OR CAUSING SURFACE FLOODING.

SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT, OR MORE OFTEN IF THE FABRIC BECOMES CLOGGED.

#### WINTER NOTES

ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15. OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS:

AFTER OCTOBER 15, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3, OR IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON BE CLEARED OF ANY ACCUMULATED SNOW AFTER EACH STORM EVENT:

#### **STOCKPILES**

CULVERTS.

LOCATE STOCKPILES A MINIMUM OF 50 FEET AWAY FROM CATCH BASINS, SWALES, AND

ALL STOCKPILES SHOULD BE SURROUNDED WITH TEMPORARY EROSION CONTROL MEASURES PRIOR TO THE ONSET OF PRECIPITATION PERIMETER BARRIERS SHOULD BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMMODATE THE DELIVERY AND REMOVAL OF MATERIALS FROM THE STOCKPILE. THE INTEGRITY OF

THE BARRIER SHOULD BE INSPECTED AT THE END OF EACH WORKING DAY. PROTECT ALL STOCKPILES FROM STORMWATER RUN-OFF USING TEMPORARY EROSION CONTROL MEASURES SUCH AS BERMS, SILT SOCK, OR OTHER APPROVED PRACTICE TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THE STOCKPILES.

#### CONCRETE WASHOUT AREA

THE FOLLOWING ARE THE ONLY NON-STORMWATER DISCHARGES ALLOWED. ALL OTHER NON-STORMWATER DISCHARGES ARE PROHIBITED ON SITE:

THE CONCRETE DELIVERY TRUCKS SHALL, WHENEVER POSSIBLE, USE WASHOUT FACILITIES AT THEIR OWN PLANT OR DISPATCH FAILITY; IF IT IS NECESSARY, SITE CONTRACTOR SHALL DESIGNATE SPECIFIC WASHOUT AREAS AND

DESIGN FACILITIES TO HANDLE ANTICIPATED WASHOUT WATER: CONTRACTOR SHALL LOCATE WASHOUT AREAS AT LEAST 150 FEET AWAY FROM STORM DRAINS. SWALES AND SURFACE WATERS OR DELINEATED WETLANDS:

INSPECT WASHOUT FACILITIES DAILY TO DETECT LEAKS OR TEARS AND TO IDENTIFY WHEN MATERIALS NEED TO BE REMOVED.

#### ALLOWABLE NON-STORMWATER DISCHARGES

- FIRE-FIGHTING ACTIVITIES:
- FIRE HYDRANT FLUSHING; WATERS USED TO WASH VEHICLES WHERE DETERGENTS ARE NOT USED;
- WATER USED TO CONTROL DUST:
- POTABLE WATER INCLUDING UNCONTAMINATED WATER LINE FLUSHING; ROUTINE EXTERNAL BUILDING WASH DOWN WHERE DETERGENTS ARE NOT USED;
- PAVEMENT WASH WATERS WHERE DETERGENTS ARE NOT USED: UNCONTAMINATED AIR CONDITIONING/COMPRESSOR CONDENSATION
- UNCONTAMINATED GROUND WATER OR SPRING WATER:
- FOUNDATION OR FOOTING DRAINS WHICH ARE UNCONTAMINATED; UNCONTAMINATED EXCAVATION DEWATERING;
- LANDSCAPE IRRIGATION.

#### WASTE DISPOSAL

- ALL WASTE MATERIALS SHALL BE COLLECTED AND STORED IN SECURELY LIDDED RECEPTACLES. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE SHALL BE DEPOSITED
- IN A DUMPSTER: - NO CONSTRUCTION WASTE MATERIALS SHALL BE BURIED ON SITE;
- ALL PERSONNEL SHALL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL BY THE SUPERINTENDENT. HAZARDOUS WASTE
- BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER; - SITE PERSONNEL SHALL BE INSTRUCTED IN THESE PRACTICES BY THE SUPERINTENDENT. SANITARY WASTE

- ALL HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF IN THE MANNER SPECIFIED

- ALL SANITARY WASTE SHALL BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF ONCE PER WEEK BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.


#### **BLASTING NOTES**

CONTRACTOR SHALL CONTACT THE NHDES AND/OR LOCAL JURISDICTION PRIOR TO

COMMENCING ANY BLASTING ACTIVITIES. FOR ANY PROJECT FOR WHICH BLASTING OF BEDROCK IS ANTICIPATED, THE APPLICANT SHALL SUBMIT A BLASTING PLAN THAT IDENTIFIES:

WHERE THE BLASTING ACTIVITIES ARE ANTICIPATED TO OCCUR; - THE ESTIMATED QUANTITY OF BLAST ROCK IN CUBIC YARDS; AND

- SITE-SPECIFIC BLASTING BEST MANAGEMENT PRACTICES.



FILTREXX®

SILTS0XX™

COMPOST

FILLTREXX SYSTEM SHALL BE INSTALLED BY A CERTIFIED FILTREXX INSTALLER.


THE CONTRACTOR SHALL MAINTAIN THE COMPOST FILTRATION SYSTEM IN A FUNCTIONAL CONDITION AT ALL TIMES. IT WILL BE ROUTINELY INSPECTED AND REPAIRED WHEN REQUIRED. 4. SILTSOXX DEPICTED IS FOR MINIMUM SLOPES, GREATER SLOPES

2" x 2" HARDWOOD

STAKES SPACED 10'

MAY REQUIRE ADDITIONAL PLACEMENTS. THE COMPOST FILTER MATERIAL WILL BE DISPERSED ON SITE WHEN NO LONGER REQUIRED, AS DETERMINED BY THE





1) INLET BASKETS SHALL BE INSTALLED IMMEDIATELY AFTER CATCH BASIN CONSTRUCTION IS COMPLETE AND SHALL REMAIN IN PLACE AND BE MAINTAINED UNTIL PAVEMENT BINDER COURSE IS

2) FILTER FABRIC SHALL BE PUSHED DOWN AND FORMED TO THE SHAPE OF THE BASKET. THE SHEET OF FABRIC SHALL BE LARGE ENOUGH TO BE SUPPORTED BY THE BASKET FRAME WHEN HOLDING SEDIMENT AND, SHALL EXTEND AT LEAST 6" PAST THE FRAME. THE INLET GRATE SHALL BE PLACED OVER THE BASKET/FRAME AND WILL SERVE AS THE FABRIC ANCHOR.


3) THE FILTER FABRIC SHALL BE A GEOTEXTILE FABRIC; POLYESTER, POLYPROPYLENE, STABILIZED NYLON, POLYETHYLENE, OR POLYVINYLIDENE CHLORIDE MEETING THE FOLLOWING

-RAB STRENGTH: 45 LB. MIN. IN ANY PRINCIPAL DIRECTION (ASTM D1682) -MULLEN BURST STRENGTH: MIN. 60 psi (ASTM D774)

4) THE FABRIC SHALL HAVE AN OPENING NO GREATER THAN A NUMBER 20 U.S. STANDARD SIEVE AND A MINIMUM PERMEABILITY OF 120 gpm/s.f. (MULTIPLY THE PERMITTIVITY IN SEC.-1 FROM ASTM 54491-85 CONSTANT HEAD TEST USING THE CONVERSION FACTOR OF 74.)

5) THE INLET BASKET SHALL BE INSPECTED WITHIN 24 HOURS AFTER EACH RAINFALL OR DAILY DURING EXTENDED PERIODS OF PRECIPITATION. REPAIRS SHALL BE MADE IMMEDIATELY, AS NECESSARY, TO PREVENT PARTICLES FROM REACHING THE DRAINAGE SYSTEM AND/OR CAUSING SURFACE FLOODING.

6) SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT, OR MORE OFTEN IF THE FABRIC BECOMES CLOGGED.




## FODS TRACKOUT CONTROL SYSTEM

THE PURPOSE AND DESIGN OF THE FODS TRACKOUT CONTROL SYSTEM IS TO EFFECTIVELY REMOVE MOST SEDIMENT FROM VEHICLE TIRES AS THEY EXIT A DISTURBED LAND AREA ONTO A PAVED STREET THIS MANUAL IS A PLATFORM FROM WHICH TO INSTALL A FODS TRACKOUT CONTROL SYSTEM. (NOTE: THIS IS NOT A ONE SIZE FITS ALL GUIDE.) THE INSTALLATION MAY NEED TO BE MODIFIED TO MEET THE EXISTING CONDITIONS, EXPECTATIONS, OR DEMANDS OF A PARTICULAR SITE. THIS IS A GUIDELINE. ULTIMATELY THE FODS TRACKOUT CONTROL SYSTEM SHOULD BE INSTALLED SAFELY WITH PROPER ANCHORING AND SIGNS PLACED AT THE ENTRANCE AND EXIT TO CAUTION USERS AND OTHERS.

#### **KEY NOTES:**

- A. FODS TRACKOUT CONTROL SYSTEM MAT.
- B. FODS SAFETY SIGN.
- ANCHOR POINT D. SILTSOXX OR ORANGE CONSTRUCTION FENCE.



THE SITE WHERE THE FODS TRACKOUT CONTROL SYSTEM IS TO BE PLACED SHOULD CORRESPOND TO BEST MANAGEMENT PRACTICES AS MUCH AS POSSIBLE. THE SITE WHERE FODS TRACKOUT CONTROL SYSTEM IS PLACED SHOULD ALSO MEET OR EXCEED THE LOCAL JURISDICTION OR STORM WATER POLLUTION PREVENTION PLAN (SWPPP) REQUIREMENTS.

CALL FOR UTILITY LOCATES 3 BUSINESS DAYS IN ADVANCE OF THE OF FODS TRACKOUT CONTROL SYSTEM INSTALLATION FOR THE MARKING OF UNDERGROUND UTILITIES. CALL THE UTILITY NOTIFICATION CENTER AT 811. ONCE THE SITE IS ESTABLISHED WHERE FODS TRACKOUT CONTROL SYSTEM IS TO BE PLACED, ANY EXCESSIVE UNEVEN TERRAIN SHOULD BE LEVELED OUT OR REMOVED SUCH AS LARGE ROCKS, LANDSCAPING MATERIALS, OR SUDDEN ABRUPT CHANGES IN ELEVATION. 4. THE INDIVIDUAL MATS CAN START TO BE PLACED INTO POSITION. THE FIRST MAT SHOULD BE PLACED

NEXT TO THE CLOSEST POINT OF EGRESS. THIS WILL ENSURE THAT THE VEHICLE WILL EXIT STRAIGHT FROM THE SITE ONTO THE PAVED SURFACE. AFTER THE FIRST MAT IS PLACED DOWN IN THE PROPER LOCATION, MATS SHOULD BE ANCHORED TO PREVENT THE POTENTIAL MOVEMENT WHILE THE ADJOINING MATS ARE INSTALLED. ANCHORS SHOULD BE PLACED AT EVERY ANCHOR POINT (IF FEASIBLE) TO HELP MAINTAIN THE MAT IN ITS CURRENT POSITION. AFTER THE FIRST MAT IS ANCHORED IN ITS PROPER PLACE, AN H BRACKET SHOULD BE PLACED AT THE END OF THE FIRST MAT BEFORE ANOTHER MAT IS PLACED ADJACENT TO THE FIRST MAT.

CORRECTLY SITUATED BETWEEN THE TWO MATS, AND SLIDE MATS TOGETHER. 11. NEXT THE CONNECTOR STRAPS SHOULD BE INSTALLED TO CONNECT THE TWO MATS TOGETHER. 12. UPON PLACEMENT OF EACH NEW MAT IN THE SYSTEM, THAT MAT SHOULD BE ANCHORED AT EVERY ANCHOR POINT TO HELP STABILIZE THE MAT AND ENSURE THE SYSTEM IS CONTINUOUS WITH NO GAPS IN RETWEEN THE MATS. 13. SUCCESSIVE MATS CAN THEN BE PLACED TO CREATE THE FODS TRACKOUT CONTROL SYSTEM REPEATING

10. ONCE THE SECOND MAT IS PLACED ADJACENT TO THE FIRST MAT, MAKE SURE THE H BRACKET IS

THE ABOVE STEPS. VEHICLES SHOULD TRAVEL DOWN THE LENGTH OF THE TRACKOUT CONTROL SYSTEM AND NOT CUT ACROSS THE MATS.


S-TURN ROUTE DOWN THE LENGTH OF THE FODS TRACKOUT CONTROL SYSTEM. MATS SHOULD BE CLEANED ONCE THE VOIDS BETWEEN THE PYRAMIDS BECOME FULL OF SEDIMENT. TYPICALLY THIS WILL NEED TO BE PERFORMED WITHIN TWO WEEKS AFTER A STORM EVENT. BRUSHING IS THE PREFERRED METHOD OF CLEANING. EITHER MANUALLY OR MECHANICALLY. THE USE OF ICE MELT, ROCK SALT, SNOW MELT, DE-ICER, ETC. SHOULD BE UTILIZED AS NECESSARY DURING THE WINTER MONTHS AND AFTER A SNOW EVENT TO PREVENT ICE BUILDUP

DRIVERS SHOULD TURN THE WHEEL OF THEIR VEHICLES SUCH THAT THE VEHICLE WILL MAKE A SHALLOW

REMOVAL OF FODS TRACKOUT CONTROL SYSTEM IS REVERSE ORDER OF INSTALLATION.

STARTING WITH THE LAST MAT, THE MAT THAT IS PLACED AT THE INNERMOST POINT OF THE SITE OR THE MAT FURTHEST FROM THE EXIT OR PAVED SURFACE SHOULD BE REMOVED FIRST. THE ANCHORS SHOULD BE REMOVED.

4. THE CONNECTOR STRAPS SHOULD BE UNBOLTED AT ALL LOCATIONS IN THE FODS TRACKOUT CONTROL STARTING WITH THE LAST MAT IN THE SYSTEM, EACH SUCCESSIVE MAT SHOULD THEN BE MOVED AND STACKED FOR LOADING BY FORKLIFT OR EXCAVATOR ONTO A TRUCK FOR REMOVAL FROM THE SITE.



#### NOTES:

- 1) THE CONTRACTOR SHALL NOTIFY DIG SAFE AT 1-888-DIG-SAFE (1-888-344-7233) AT LEAST 72 HOURS PRIOR TO COMMENCING ANY EXCAVATION ON PUBLIC OR PRIVATE PROPERTY.
- 2) UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERIFIED. LOCATING AND PROTECTING ANY ABOVEGROUND OR UNDERGROUND UTILITIES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND/OR THE OWNER. UTILITY CONFLICTS SHOULD BE REPORTED AT ONCE TO THE DESIGN
- 3) CONTRACTOR SHALL INSTALL AND MAINTAIN EROSION CONTROL MEASURES IN ACCORDANCE WITH THE "NEW HAMPSHIRE STORMWATER MANUAL, VOLUME 3, EROSION AND SEDIMENT CONTROLS DURING CONSTRUCTION. (NHDES DECEMBER 2008).

0 11/7/23 ISSUED FOR COMMENT OMS JRC DATE DESCRIPTION WING ISSUE STATUS

TAC SUBMISSION




WWW.HALEYWARD.COM

ALBACORE PARK BUILDING ADDITION

**EROSION PROTECTION NOTES & DETAILS** 

569 SUBMARINE WAY PORTSMOUTH, NEW HAMPSHIRE



OCTOBER 2023 SCALE: AS SHOWN CHECKED BY DESIGNED BY OMS JRC JRC PROJECT No ELD BOOK & PAGE 5010373-452.02 FB 347 PG 20


200 Griffin Road, Unit 3

Portsmouth, NH 03801

603.430.9282

SHEET 7

NTS



OWNER:

ALBACORE PARK
BUILDING COMMITTEE

ALBACORE PARK PORTSMOUTH, NH

ARCHITECT:

PORT NE

ARCHITECTS

959 Islington Street Portsmouth, NH 03801

603.436.8891 info@portonearchitects.com

CONTRACTOR:

CIVIL / STRUCTURAL ENGINEER:

MEPFP ENGINEER:

	Revision History			
	#	Date	Issuance	
			3	
1				

SCHEMATIC DESIGN

USE DISCLAIMER: COPYRIGHT© BY PORT ONE ARCHITECTS, INC. 2023 NO RE-USE WITHOUT PERMISSION.

LOCUS MAP

PROJECT NAME:

ALBACORE PARK
WELCOME CENTER
ADDITION &
RENOVATIONS

DRAWING TITLE:

SCHEMATIC FLOOR PLAN


PROJECT No: 23-041

DATE: Nove. 7, 2023

DRAWING SCALE: As indicated

DRAWING No:

A1.1



23-041