

# Findings of Fact | Subdivision Rules and Regulations

## City of Portsmouth Planning Board

Date: XXXXXXXX

Property Address: 100 Durgin Lane

Application #: LU-24-62

Decision:  Approve     Deny     Approve with Conditions

### Findings of Fact:

Per RSA 676:3, I: The local land use board shall issue a final written decision which either approves or disapproves an application for a local permit and make a copy of the decision available to the applicant. **The decision shall include specific written findings of fact that support the decision. Failure of the board to make specific written findings of fact supporting a disapproval shall be grounds for automatic reversal and remand by the superior court upon appeal, in accordance with the time periods set forth in RSA 677:5 or RSA 677:15, unless the court determines that there are other factors warranting the disapproval.** If the application is not approved, the board shall provide the applicant with written reasons for the disapproval. If the application is approved with conditions, the board shall include in the written decision a detailed description of the all conditions necessary to obtain final approval.

|   | Subdivision Review Criteria   | Finding<br>(Meets<br>Standards/<br>Requirements) | Supporting Information  |
|---|---|--|---|
| 1 | Subdivision Rules and Regulations III. D.<br>1 The Board shall act to deny any application which is not in compliance with Section IV or V as appropriate.<br><b>SECTION IV - REQUIREMENTS FOR PRELIMINARY PLAT</b> | Meets<br><br>Does Not Meet                       | The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Subdivision Rules and Regulations.<br><br>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.            |
| 2 | <b>SECTION V - REQUIREMENTS FOR FINAL PLAT</b>  | Meets<br><br>Does Not Meet                       | The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Subdivision Rules and Regulations, Section V.<br><br>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting. |
| 3 | <b>SECTION VI - GENERAL REQUIREMENTS</b>  | Meets  | The application has been reviewed by the Technical Advisory Committee for   |

|   | Subdivision Review Criteria           | Finding<br>(Meets<br>Standards/<br>Requirements) | Supporting Information   |
|---|---------------------------------------|--|--|
|   |                                       | Does Not Meet                                    | <p>conformance with the minimum requirements of the Subdivision Rules and Regulations General Requirements, Section VI.</p> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p>   |
| 4 | <b>SECTION VII - DESIGN STANDARDS</b> | <p>Meets</p> <p>Does Not Meet</p>                | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Subdivision Rules and Regulations, Section VII.</p> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p> |
| 5 | <b><u>Other Board Findings:</u></b>   |  |  |

# Findings of Fact | Wetland Conditional Use Permit

## City of Portsmouth Planning Board

Date: XX/XX/XXXX

Property Address: 100 Durgin Lane

Application #: LU-24-62

Decision:  Approve     Deny     Approve with Conditions

### Findings of Fact:

Per RSA 676:3, I: The local land use board shall issue a final written decision which either approves or disapproves an application for a local permit and make a copy of the decision available to the applicant. **The decision shall include specific written findings of fact that support the decision. Failure of the board to make specific written findings of fact supporting a disapproval shall be grounds for automatic reversal and remand by the superior court upon appeal, in accordance with the time periods set forth in RSA 677:5 or RSA 677:15, unless the court determines that there are other factors warranting the disapproval.** If the application is not approved, the board shall provide the applicant with written reasons for the disapproval. If the application is approved with conditions, the board shall include in the written decision a detailed description of all conditions necessary to obtain final approval.

In order to grant Wetland Conditional Use permit approval the Planning Board shall find the application satisfies criteria set forth in the Section 10.1017.50 (Criteria for Approval) of the Zoning Ordinance.

|          | <b>Zoning Ordinance<br/>Sector 10.1017.50<br/>Criteria for Approval</b>   | <b>Finding<br/>(Meets<br/>Criteria for<br/>Approval)</b> | <b>Supporting Information</b>   |
|----------|---|--|---|
| <b>1</b> | <i>1. The land is reasonably suited to the use activity or alteration.</i>  | <b>Meets</b><br><br><b>Does Not Meet</b>                 | <p>The application has been reviewed by the Conservation Commission (CC) for conformance with the Section 10.1017.50 Criteria.</p> <ul style="list-style-type: none"> <li>The land is a currently previously disturbed site with impacts to the buffers. The proposed use, allowed within the Gateway Neighborhood Mixed use District, proposes a net reduction of impervious surfaces within the buffer, as well as buffer enhancement.</li> </ul> <p>The application was recommended for approval by the Conservation Commission Meeting at the September 11, 2024 meeting.</p> |
| <b>2</b> | <i>2. There is no alternative location outside the wetland buffer that is feasible and reasonable for the proposed use, activity or alteration.</i> | <b>Meets</b><br><br><b>Does Not Meet</b>                 | <p>The application has been reviewed by the Conservation Commission (CC) for conformance with the Section 10.1017.50 Criteria.</p> <ul style="list-style-type: none"> <li>The proposed project design reduces the impervious surface within the 25-, 50-, and 100' buffers and proposes to replace existing impacted areas with native plants including trees, shrubs, and grasses.</li> </ul> <p>The application was recommended for approval</p>  |

|          | <b>Zoning Ordinance Sector 10.1017.50 Criteria for Approval</b>   | <b>Finding</b><br>(Meets Criteria for Approval) | <b>Supporting Information</b>   |
|----------|---|---|---|
|          |   |   | by the Conservation Commission Meeting at the September 11, 2024 meeting.   |
| <b>3</b> | <i>3. There will be no adverse impact on the wetland functional values of the site or surrounding properties.</i>                               | <b>Meets</b><br><b>Does Not Meet</b>            | <p>The application has been reviewed by the Conservation Commission (CC) for conformance with the Section 10.1017.50 Criteria.</p> <ul style="list-style-type: none"> <li>The proposed project intends to reduce impervious surfaces from the wetland buffer area. The buffer will be enhanced by the removal of invasive species and enhance the existing vegetation with native vegetation. The proposed site and landscape designs site enhance the previously disturbed wetland buffer area from its existing condition and provide added value by creating public open space for recreation on the site and along the buffer.</li> </ul> <p>The application was recommended for approval by the Conservation Commission Meeting at the September 11, 2024 meeting.</p> |
| <b>4</b> | <i>4. Alteration of the natural vegetative state or managed woodland will occur only to the extent necessary to achieve construction goals.</i> | <b>Meets</b><br><b>Does Not Meet</b>            | <p>The application has been reviewed by the Conservation Commission (CC) for conformance with the Section 10.1017.50 Criteria.</p> <ul style="list-style-type: none"> <li>The proposed project design proposes minimal alteration to the natural woodland to the greatest extent practical. The areas impacted consist primarily of impervious surfaces and previously disturbed areas. Any temporary disturbances of the wetland buffer will be restored following construction.</li> </ul> <p>The application was recommended for approval by the Conservation Commission Meeting at the September 11, 2024 meeting.</p>  |

|   | <b>Zoning Ordinance Sector 10.1017.50 Criteria for Approval</b>  | <b>Finding</b><br>(Meets Criteria for Approval) | <b>Supporting Information</b>   |
|---|--|---|---|
| 5 | 5. The proposal is the alternative with the least adverse impact to areas and environments under the jurisdiction of this section. | Meets<br><br>Does Not Meet                      | <p>The application has been reviewed by the Conservation Commission (CC) for conformance with the Section 10.1017.50 Criteria.</p> <ul style="list-style-type: none"> <li>The proposed project design is not an adverse impact to the site as it would enhance the buffer by reducing overall impervious surface on the site (as well as within wetland buffers), improve water quality through stormwater treatment and provide public access to the site. The alternative to maintain the existing retail use presents greater impacts to the areas and environments under the jurisdiction of this Section.</li> </ul> <p>The application was recommended for approval by the Conservation Commission Meeting at the September 11, 2024 meeting.</p>   |
| 6 | 6. Any area within the vegetated buffer strip will be returned to a natural state to the extent feasible.                          | Meets<br><br>Does Not Meet                      | <p>The application has been reviewed by the Conservation Commission (CC) for conformance with the Section 10.1017.50 Criteria.</p> <ul style="list-style-type: none"> <li>The proposed work within the vegetated buffer strip is limited to the removal of impervious areas, repaving of the existing access road to the north, and reconstruction of drainage outlets. Areas temporarily disturbed for the removal of paved areas within the vegetated buffer strip will be restored following construction. The landscape plans propose replacing the existing disturbed areas within the 25-foot wetland buffer with a native grass mix, mown as required to avoid incursions of invasive species, and the addition of several native trees and shrubs within the previously disturbed buffer area.</li> </ul> <p>The application was recommended for approval by the Conservation Commission Meeting at the September 11, 2024 meeting.</p> |
| 7 | <b><u>Other Board Findings:</u></b>  |   |   |

# Findings of Fact | Site Plan Review

## City of Portsmouth Planning Board

Date: XXXXXXXX

Property Address: 100 Durgin Lane

Application #: LU-24-62

Decision:  Approve     Deny     Approve with Conditions

### Findings of Fact:

Per RSA 676:3, I: The local land use board shall issue a final written decision which either approves or disapproves an application for a local permit and make a copy of the decision available to the applicant. **The decision shall include specific written findings of fact that support the decision. Failure of the board to make specific written findings of fact supporting a disapproval shall be grounds for automatic reversal and remand by the superior court upon appeal, in accordance with the time periods set forth in RSA 677:5 or RSA 677:15, unless the court determines that there are other factors warranting the disapproval.** If the application is not approved, the board shall provide the applicant with written reasons for the disapproval. If the application is approved with conditions, the board shall include in the written decision a detailed description of the all conditions necessary to obtain final approval.

Site Plan Regulations Section 2.9 Evaluation Criteria - in order to grant site plan review approval, the TAC and the Planning Board shall find that the application satisfies evaluation criteria pursuant to NH State Law and listed herein. In making a finding, the TAC and the Planning Board shall consider all standards provided in Articles 3 through 11 of these regulations.

|   | Site Plan Review Regulations Section 2.9 Evaluation Criteria   | Finding (Meets Standard/Criteria) | Supporting Information   |
|---|--|-----------------------------------|--|
| 1 | Compliance with all City Ordinances and Codes and these regulations.<br><u>Applicable standards:</u> | Meets<br><br>Does Not Meet        | <u>Applicable standards:</u><br>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.<br><br>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting. |
| 2 | Provision for the safe development, change or expansion of use of the site.                          | Meets<br><br>Does Not Meet        | The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.<br><br>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.                                 |

|          | <b>Site Plan Review Regulations Section 2.9 Evaluation Criteria</b>  | <b>Finding (Meets Standard/Criteria)</b> | <b>Supporting Information</b>   |
|----------|--|--|---|
| <b>3</b> | Adequate erosion control and stormwater management practices and other mitigative measures, if needed, to prevent adverse effects on downstream water quality and flooding of the property or that of another. | <b>Meets</b><br><b>Does Not Meet</b>     | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>• TAC reviewed the erosion control and stormwater management practices and other mitigative measures for conformance with City design requirements.</li> <li>• A full drainage analysis report was submitted that included analysis of the predevelopment and post development drainage conditions.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p> |
| <b>4</b> | Adequate protection for the quality of groundwater.  | <b>Meets</b><br><b>Does Not Meet</b>     | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>• TAC reviewed the erosion control and stormwater management practices and other mitigative measures for conformance with City design requirements.</li> <li>• A full drainage analysis report was submitted that included analysis of the predevelopment and post development drainage conditions.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p> |
| <b>5</b> | Adequate and reliable water supply sources.  | <b>Meets</b><br><b>Does Not Meet</b>     | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>• TAC reviewed the water service design for conformance with City design requirements.</li> <li>• The site will be served by city water.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p>  |
| <b>6</b> | Adequate and reliable  | <b>Meets</b>                             | The application has been reviewed by the  |

|           | <b>Site Plan Review Regulations Section 2.9 Evaluation Criteria</b>   | <b>Finding (Meets Standard/Criteria)</b> | <b>Supporting Information</b>   |
|-----------|---|--|---|
|           | sewage disposal facilities, lines, and connections.   | <b>Does Not Meet</b>                     | <p>Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>TAC reviewed sewage disposal facilities, lines, and connections for conformance with City design requirements.</li> <li>The site will be served by municipal sewer.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p>                        |
| <b>7</b>  | Absence of undesirable and preventable elements of pollution such as smoke, soot, particulates, odor, wastewater, stormwater, sedimentation or any other discharge into the environment which might prove harmful to persons, structures, or adjacent properties. | <b>Meets</b><br><b>Does Not Meet</b>     | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>TAC reviewed the erosion control and stormwater management practices and other mitigative measures for conformance with City design requirements.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p> |
| <b>8</b>  | Adequate provision for fire safety, prevention and control.   | <b>Meets</b><br><b>Does Not Meet</b>     | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p>   |
| <b>9</b>  | Adequate protection of natural features such as, but not limited to, wetlands.  | <b>Meets</b><br><b>Does Not Meet</b>     | <p>The application has been reviewed by the Technical Advisory Committee and the Conservation Commission for conformance with the minimum requirements of the Site Plan Regulations.</p> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee and September 11, 2024 at the Conservation Commission Meetings.</p>  |
| <b>10</b> | Adequate protection of historical features on the site.   | <b>Meets</b>                             | <p>The application has been reviewed by the Technical Advisory Committee for</p>  |



|           | <b>Site Plan Review Regulations<br/>Section 2.9 Evaluation<br/>Criteria</b>  | <b>Finding<br/>(Meets<br/>Standard/Criteria)</b> | <b>Supporting Information</b>   |
|-----------|--|--|---|
|           |  | <b>Does Not Meet</b>                             | <p>conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>There are no known on-site historical features.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p>   |
| <b>11</b> | Adequate management of the volume and flow of traffic on the site and adequate traffic controls to protect public safety and prevent traffic congestion. | <b>Meets<br/>Does Not Meet</b>                   | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>TAC reviewed the management of the volume and flow of traffic on the site and adequate traffic controls to protect public safety and prevent traffic congestion for conformance with City design requirements.</li> <li>A full traffic impact study was submitted that included analysis of the no-build and build conditions.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p>  |
| <b>12</b> | Adequate traffic controls and traffic management measures to prevent an unacceptable increase in safety hazards and traffic congestion off-site.         | <b>Meets<br/>Does Not Meet</b>                   | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>TAC reviewed the management of the volume and flow of traffic on the site and adequate traffic controls to protect public safety and prevent traffic congestion. for conformance with City design requirements.</li> <li>A full traffic impact study was submitted that included analysis of the no-build and build conditions.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p> |
| <b>13</b> | Adequate insulation from external noise sources.   | <b>Meets</b>                                     | The application has been reviewed by the Technical Advisory Committee for conformance with the minimum  |

|           | <b>Site Plan Review Regulations Section 2.9 Evaluation Criteria</b>  | <b>Finding (Meets Standard/Criteria)</b> | <b>Supporting Information</b>   |
|-----------|--|--|---|
|           |  | <b>Does Not Meet</b>                     | <p>requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>A noise analysis was submitted which included provisions for additional sound barriers and building construction requirements as necessary for compliance within the Highway Noise Overlay District</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p>  |
| <b>14</b> | Existing municipal solid waste disposal, police, emergency medical, and other municipal services and facilities adequate to handle any new demands on infrastructure or services created by the project. | <b>Meets</b><br><b>Does Not Meet</b>     | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>TAC reviewed that police, emergency medical, and other municipal services and facilities adequate to handle any new demands on infrastructure or services created by the project.</li> <li>Project will not utilize municipal solid waste disposal.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p> |
| <b>15</b> | Provision of usable and functional open spaces of adequate proportions, including needed recreational facilities that can reasonably be provided on the site   | <b>Meets</b><br><b>Does Not Meet</b>     | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>TAC reviewed the community space areas proposed as part of the design plan.</li> </ul> <p>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.</p>   |
| <b>16</b> | Adequate layout and coordination of on-site accessways and sidewalks in relationship to off-site existing or planned streets, accessways, bicycle paths, and sidewalks.                                  | <b>Meets</b><br><b>Does Not Meet</b>     | <p>The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.</p> <ul style="list-style-type: none"> <li>TAC reviewed the layout and coordination of on-site accessways and sidewalks in relationship to off-site existing or planned streets, accessways, bicycle paths, and sidewalks.</li> </ul>  |

|           | <b>Site Plan Review Regulations Section 2.9 Evaluation Criteria</b>  | <b>Finding (Meets Standard/Criteria)</b> | <b>Supporting Information</b>   |
|-----------|--|--|---|
|           |  |  | The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.   |
| <b>17</b> | Demonstration that the land indicated on plans submitted with the application shall be of such character that it can be used for building purposes without danger to health. | <b>Meets</b><br><b>Does Not Meet</b>     | The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.<br><br>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.  |
| <b>18</b> | Adequate quantities, type or arrangement of landscaping and open space for the provision of visual, noise and air pollution buffers.   | <b>Meets</b><br><b>Does Not Meet</b>     | The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations. <ul style="list-style-type: none"> <li>TAC reviewed the quantities, type or arrangement of landscaping and open space.</li> </ul> The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting. |
| <b>19</b> | Compliance with applicable City approved design standards.   | <b>Meets</b><br><b>Does Not Meet</b>     | The application has been reviewed by the Technical Advisory Committee for conformance with the minimum requirements of the Site Plan Regulations.<br><br>The application was recommended for approval on November 5, 2024 at the Technical Advisory Committee Meeting.  |
|           | <b>Other Board Findings:</b>   |  |   |

**PART 1 OF 2**

**100 DURGIN LANE**

**11/27/24 PB SUBMISSION  
DOCUMENTS**

**FOR**

**DECEMBER 19, 2024 PB MEETING**

E5071-001  
November 27, 2024

Mr. Rick Chellman, Planning Board Chair  
City of Portsmouth Planning & Sustainability Department  
1 Junkins Avenue  
Portsmouth, New Hampshire 03801

Re: **Request for Site Plan Review & Conditional Use Permits Review  
100 Durgin Lane – Proposed Redevelopment**

Dear Chair Chellman:

On behalf of 100 Durgin Lane Owner, LLC (applicant) we are pleased to submit one (1) set of hard copies and one electronic file (.pdf) of the following information to support a request for a Site Review Permit, Lot Line Revision Permit, Development Site Conditional Use Permit, Highway Noise Overlay District Conditional Use Permit, and a Wetland Conditional Use Permit for the above referenced project.

Updated documents for the attention of the Technical Advisory Committee:

- One (1) 22x34 & one (1) 11x17 copy of the Site Plan Set, last revised November 27, 2024;
- Planning Board Presentation Slide Deck
- TAC Conditions Response Tracker, dated November 27, 2024;
- ConCom Conditions Response Tracker, dated November 27, 2024;
- Response to Comments – Traffic Peer Review, dated October 16, 2024;
- Response to Comments – Water and Sewer Peer Review, dated November 27, 2024;
- Impervious Surface Exhibit; last revised October 23, 2024;
- Wetland Buffer Exhibit, last revised October 23, 2024;
- Wetland Buffer Comparison Exhibit, last revised October 23, 2024;
- Wetland Buffer Impacts Modification Clarification, dated November 4, 2024;
- Grade Plane Exhibits (2), last revised October 23, 2024;
- Fire Truck Turning Exhibits (3), last revised October 23, 2024;
- Location of Motor Vehicle Parking Exhibit, last revised October 23, 2024;
- Front Building Setback Exhibit, last revised October 23, 2024;
- Development Block Standard Exhibit, last revised October 23, 2024;
- Lot Line Revision Exhibit, last revised October 23, 2024;
- Existing Easement Exhibit, dated October 16, 2024;
- Woodbury Ave Water Line Replacement Exhibit, dated October 3, 2024;
- Schematic 10' Multi-Use Path Exhibits (2), last revised November 27, 2024;
- Rendered Plan, dated October 23, 2024;
- Community Space Exhibit, dated October 23, 2024;
- Planting Irrigation / Hydrozone Diagram, dated October 23, 2024;
- Landscape Maintenance Plan, dated November 27, 2024;
- Highway Noise Overlay District Analysis, dated October 23, 2024;
- Green Building Statement, dated October 23, 2024;
- Site Signage Plan, dated October 24, 2024



- Amenity Building Zoning Compliance Diagram, dated October 23, 2024;
- 4-Story Building Zoning Compliance Diagram, dated June 14, 2024;
- Drainage Analysis, last revised September 18, 2024;
- Long-Term Operation & Maintenance Plan, last revised September 18, 2024;
- Water & Wastewater Demand Analysis, dated August 26, 2024;
- Wetland Delineation Report, dated May 8, 2024;
- Traffic Impact Study, dated May 16, 2024;
- Site Review Checklist, dated June 17, 2024;
- Subdivision Review Checklist, dated June 17, 2024;
- Eversource Will-Serve Letter, dated May 21, 2024;
- Lighting Cut Sheets
- Application Fee Calculation Form;
- Authorization Form

## **PROJECT SUMMARY**

### **Existing Conditions**

The proposed project is located at 100 Durgin Lane and includes lots identified as Map 239 Lots 13-2, 16 & 18 on the City of Portsmouth Tax Maps. The site was previously home to Christmas Tree Shops and Bed, Bath and Beyond locations which are no longer in operation. The properties are a combined 26.2 acres of land and are located in the Gateway District (G1) and also lies within the Highway Noise Overlay District. The property is bound to the west by Route 16, to the north by the Motel 6 property and Gosling Road, to the south by the Hampton Inn and Home Depot properties, and to the east by an Eversource easement, Pep Boys and Durgin Plaza.

### **Proposed Redevelopment**

The proposed project consists of the demolition of the existing Christmas Tree Shops and Bed, Bath and Beyond building and the construction of approximately 360 rental housing units in a mix of seventeen (17) 3-story and 4-story buildings. One of these buildings, centrally located, is proposed to contain first and second-floor amenities for the use of residents. Site improvements include parking, pedestrian access, community spaces, utilities, stormwater management, lighting, and landscaping. The proposed project also includes a reduction in overall impervious surface on the development lot.

The proposed project will be providing 10% community space as required under the Development Site Conditional Use Permit for having more than one principal building on a single lot. Based on the lot area the required community spaces will exceed 2 acres and includes a public dog park, recreation areas, community walking paths, and open/green space.

### **Open Space & Buffer Enhancement**

The proposed project results in work within the 100-foot wetland buffer and therefore is a Conditional Use Permit is required for demolition and construction activities. The 100-foot wetland buffer within the development area includes impervious parking surfaces, drive aisles, and roadways. The project will provide an overall improvement by reducing impervious cover within the 100-foot wetland buffer. The impervious surface impacts from the proposed project are shown in Table 1. In addition to the summary in Table 1 below, detailed calculations of the impervious surfaces within the buffer for the existing and proposed condition are depicted in the enclosed Wetland Buffer Impervious Surface Exhibit.

The project’s landscape design proposes to replace existing impervious areas removed from the wetland buffer with a native grass mix and native trees in an effort to enhance the previously disturbed wetlands buffer.

**Table 1. 100 Durgin Lane, Wetland Buffer Impervious Surfaces**

| Buffer Segment         | Existing Impervious (SF) | Final Impervious (SF) |
|------------------------|--------------------------|-----------------------|
| 0-25 feet              | 3,114                    | 2,467                 |
| 25-50 feet             | 12,156                   | 8,526                 |
| 50-100 feet            | 45,975                   | 33,333                |
| Total                  | 61,245                   | 44,326                |
| Net Impervious Surface | <b>-16,919 sf</b>        |                       |

Section 10.1017.24 of the Zoning Ordinance which indicates “Where feasible, the application shall include removal of impervious surfaces at least equal in area to the area of impervious surface impact. The intent of this provision is that the project will not result in a net loss of pervious surface within a jurisdictional wetland buffer.” As shown in Table 1, the proposed project exceeds this requirement by providing an 16,919 SF reduction in impervious surface.

## LAND USE PERMIT APPLICATIONS

### Local Permitting Timeline

The proposed project will require the following site related approvals from the Planning Board:

- Site Plan Review Permit
- Lot Line Revision Permit
- Development Site Conditional Use Permit
- Highway Noise Overlay District Conditional Use Permit
- Wetland Conditional Use Permit

To date the applicant has attended the following meetings with the local land-use boards related to the Site Plan:

- February 15, 2024 – Planning Board Conceptual Consultation
- March 12, 2024 – Technical Advisory Committee Work Session
- April 8, 2024 – Conservation Commission Site Walk
- April 10, 2024 – Conservation Commission Work Session
- May 7, 2024 – Technical Advisory Committee Meeting
- June 12, 2024 – Conservation Commission Meeting
- July 10, 2024 – Conservation Commission Meeting
- July 2, 2024 – Technical Advisory Committee Meeting
- August 6, 2024 – Technical Advisory Committee Meeting
- August 14, 2024 – Conservation Commission Meeting
- September 11, 2024 – Conservation Commission Meeting
  - Recommendation for Approval from the Conservation Commission received
- October 1, 2024 – Technical Advisory Committee Meeting



- November 5, 2024 – Technical Advisory Committee Meeting
  - Recommendation for Approval from the Technical Advisory Committee received

The project will also require the following approvals from the New Hampshire Department of Environmental Services (NHDES):

- Alteration of Terrain Permit
- Sewer Connection Permit

### **Site Plan Review Permit**

The project will require a Site Plan Review Permit for the site improvements described above in the project summary. The project has previously met with the Planning Board for Conceptual Consultation, as well as the Technical Advisory Committee (TAC) and Conservation Commission (CC) for review meetings. Both the TAC and CC have provided their recommendations for approval of the project.

### **Zoning Compliance**

The enclosed plans have been designed to comply with the City of Portsmouth Zoning Ordinance and specifically Article 5B – Gateway Neighborhood Mixed Use Districts. Exhibits have been prepared and included in this submission package demonstrating compliance with sections in the ordinance. Enclosed exhibits demonstrate compliance with Section 10.5B23 Façade Composition Standards and Section 10.5B83 Location of Motor Vehicle Parking Facilities.

The applicant is also requesting that the Planning Board allow an increase of building setback from the front lot line. As allowed by Section 10.5B41.60 “the Planning Board may require an increase in the building setback from lot lines where adjacent land uses may be incompatible. The enclosed figure demonstrates that the land uses along the boundary of the development site (wetland, wetland buffer & overhead utility easement) are incompatible with the required building setback from the lot line.

### **Lot Line Revision**

The proposed redevelopment parcels located at 100 Durgin Lane consist of properties identified as Map 239 Lots 13-2, 16 & 18. The existing internal lot lines separating these three lots are proposed to be relocated to better align the parcels for the proposed building footprints.

## **CONDITIONAL USE PERMITS**

### **Development Site Conditional Use Permit**

Under Section 10.5B41.10 Development Site Standards are “allowed by Conditional Use Permit (CUP) approval from the Planning Board, a development site is any lot or group of contiguous lots owned or controlled by the same person or entity, assembled for the purpose of a single development and including more than one principal building or building type”. As the proposed development includes more than one principal building, a CUP to allow the use of the Development Site Standards is being requested for this proposed project.

Additionally, per Section 10.5B41.60 the “Planning Board may require landscaping, fencing, or an increase in the building setback from lot lines where adjacent land uses may be incompatible”. As the land uses along the boundary of the development site (wetland, wetland buffer & overhead utility easement) are incompatible with the required building setback from



the lot line, the applicant is requesting the planning board to allow an increase of building setback from the front lot line to 239.6' for an apartment building.

### **Community Space**

As required under the Development Site Conditional Use Permit the project is required to provide a minimum of 10% community space. Based on the total lot area of 26.2 acres the project is required to provide a minimum of 2.62 acres of community space. The enclosed Community Space exhibit depicts how the project is meeting this requirement. The community space will be located throughout the development and include a variety of community space types as permitted by the Zoning Ordinance. The community space calculation is depicted in the enclosed Community Space Exhibit.

### **Development Site Conditional Use Permit Criteria**

Based on the above described and enclosed materials, the following addresses how the Project warrants the granting of a Conditional Use Permit for a Development Site by satisfying the following four (4) criteria for approval in Section 10.5B43.10 of the Zoning Ordinance:

#### **(1) The development project is consistent with the Portsmouth Master Plan.**

The Project is consistent with several goals identified in the Master Plan.

- *Goal 1.2 is to encourage walkable mixed-use development along existing commercial corridors.* The proposed project has been designed to promote alternative modes of transportation such as walking and bicycling by incorporating bicycle storage spaces as well as maintaining a sidewalk connection to the existing sidewalks along Durgin Lane.
- *Goal 2.1 is to ensure that new development complements and enhances its surroundings.* The proposed residential buildings will further enhance the continued success of the adjacent commercial, retail, and restaurants located in the adjacent Durgin Plaza and surrounding parcels.

#### **(2) The development project has been designed to allow uses that are appropriate for its context and consistent with City's planning goals and objectives for the area.**

The Project has been designed to be complementary to the abutting uses. Residential buildings are an allowed use within the zone and the addition of public access is consistent with goals laid out in the City's Master Plan as described in criteria item 1.

#### **(3) The project includes measures to mitigate or eliminate anticipated impacts on traffic safety and circulation, demand on municipal services, stormwater runoff, natural resources, and adjacent neighborhood character.**

As described in the attached Traffic Impact Study, it is the professional opinion of Tighe & Bond that the additional traffic expected to be generated by the proposed residential development is not expected to have a significant impact to traffic operations within the study area as compared to the current vacant site condition. Overall, the proposed condition represents a significant reduction in net trips compared to both the prior retail use and to potential re-leasing of the parcel for retail use.

The development site has been designed to mitigate stormwater runoff with the use of detention and filtration stormwater treatment practices. The proposed

project is a significant improvement over existing conditions as there is minimal stormwater treatment on site.

The Project as designed will be complementary to the abutting commercial uses.

**(4) The project is consistent with the purpose and intent set forth in Section 10.5B11.**

Section 10.5B11.10 states that *"The purpose of Article 5B is to implement and support the goals of the City's Master Plan and Housing Policy to encourage walkable mixed-use development and continued economic vitality in the City's primary gateway areas, ensure that new development complements and enhances its surroundings, provide housing stock that is suited for changing demographics, and accommodate the housing needs of the City's current and future workforce."*

As described in Criteria 1 – 3 the Project is consistent with *the goals of the City's Master Plan including Goal 1.2 and Goal 2.1.*

The Project will also provide additional and much needed housing stock to the City in an area outside of the downtown core, with easy access to abutting retail and commercial areas, and public transportation.

## Highway Noise Overlay District Conditional Use Permit

The project site is located within the Highway Noise Overlay District (HNOD) as defined in Section 10.613.60. The proposed residential land use qualifies as a "noise sensitive land use" and therefore requires a conditional use permit. A noise analysis prepared in compliance with Section 10.675 is included with this application for a conditional use permit.

## Wetland Conditional Use Permit

Jurisdictional wetland areas, including forest, dense early successional shrub growth, and emergent wetland are present on site. A Conditional Use Permit for Wetland Buffer Impacts will be required for the project for work within the 100 ft wetland buffer.

At the September 11<sup>th</sup>, 2024 meeting, the Conservation Commission voted to recommend the project for approval.

## Wetland Conditional Use Permit Criteria

Based on the above described and enclosed materials, the following addresses how the proposed project warrants the granting of a Wetland Conditional Use Permit by satisfying the following six (6) criteria for approval in Section 10.1017.50 of the Zoning Ordinance:

**(1) The land is reasonably suited to the use, activity or alteration.**

The land is currently a previously disturbed site that was previously home to Christmas Tree Shops and Bed, Bath and Beyond building. The proposed project design is an allowed use within the Gateway Neighborhood Mixed Use District. Additionally, the proposed project site consists of a previously disturbed wetland buffer area which has historically been used as a commercial area. The proposed project will result in impervious surface reduction in the buffer, buffer enhancement, and will provide public access to the site.

**(2) There is no alternative location outside the wetland buffer that is feasible and reasonable for the proposed use, activity or alteration.**

The placement of the proposed buildings and parking areas were sited in a way to reduce the areas of impervious surface within the 25-, 50-, and 100-foot wetland

buffers. The proposed project design reduces the impervious surface within the 25-, 50-, and 100' buffers and proposes to replace existing impacted areas with native plants including trees, shrubs, and grasses.

**(3) There will be no adverse impact on the wetland functional values of the site or surrounding properties;**

There will be no adverse impact on the wetland functional values of the site as the existing condition is previously disturbed and consisting of parking areas, drive aisles, and accessways. There is no real functional wetland buffer area on the project site. The proposed project intends to reduce impervious surfaces from the wetland buffer area. The buffer will be enhanced by the removal of invasive species and enhance the existing vegetation with native vegetation. The proposed site and landscape designs site enhance the previously disturbed wetland buffer area from its existing condition and provide added value by creating public open space for recreation on the site and along the buffer.

**(4) Alteration of the natural vegetative state or managed woodland will occur only to the extent necessary to achieve construction goals; and**

The proposed project design proposes minimal alteration to the natural woodland to the greatest extent practical. The areas impacted consist primarily of impervious surfaces and previously disturbed areas. Any temporary disturbances of the wetland buffer will be restored following construction.

**(5) The proposal is the alternative with the least adverse impact to areas and environments under the jurisdiction of this Section.**

The proposed project design is not an adverse impact to the site as it would enhance the buffer by reducing overall impervious surface on the site, improve water quality through stormwater treatment and provide public access to the site. In addition, the proposed project will reduce the impervious surface within the 25, 50, and 100-foot wetland buffers. The alternative to maintain the existing retail use presents greater impacts to the areas and environments under the jurisdiction of this Section.

**(6) Any area within the vegetated buffer strip will be returned to a natural state to the extent feasible.**

The proposed work within the vegetated buffer strip is limited to the removal of impervious areas, repaving of the existing access road to the north, and reconstruction of drainage outlets. The proposed project will collect and treat the onsite impervious surfaces prior to discharging to the onsite wetlands. Implementing these treatment measures will help improve the water quality discharged from the property. Areas temporarily disturbed for the removal of paved areas within the vegetated buffer strip will be restored following construction. The landscape plan proposes replacing the existing disturbed areas within the 25-foot wetland buffer with a native grass mix, mown as required to avoid incursions of invasive species, and the addition of several native trees and shrubs within the previously disturb buffer area.

## **CONCLUSION**

As shown in the enclosed information, the proposed project is expected to create a vibrant, authentic, diverse, and connected development that provides high quality housing to a variety of income ranges and meaningful community spaces.


We respectfully request to be placed on the Planning Board meeting agenda for December 19<sup>th</sup>, 2024. If you have any questions or need any additional information, please contact me by phone at (603) 294-9213 or by email at [NAHansen@tighebond.com](mailto:NAHansen@tighebond.com).

Sincerely,

**TIGHE & BOND, INC.**



Patrick M. Crimmins, PE  
Vice President



Neil A. Hansen, PE  
Project Manager

Enclosures

Copy: 100 Durgin Lane Owner, LLC  
John K. Bosen, Bosen & Associates  
Utile, Inc Architects  
Aceto Landscape Architecture



# 100 Durgin Lane



100 Durgin Lane Owner  
Utile, Inc. Architecture and Planning  
Aceto Landscape Architecture  
Tighe and Bond Civil Engineering

December 19, 2024

# Agenda

December 19, 2024

## 1. Overview

- a. Existing Conditions
- b. Project Objectives
- c. What We Heard at the Conceptual Consultation
- d. Review Process and Key Changes

## 2. Site Design

- a. Site Context and Connections
- b. Site Constraints
- c. Proposed Community Spaces
- d. Landscape and Architectural Design

## 3. Technical Approach

- a. Highway Noise Overlay
- b. Sustainability Summary
- c. Stormwater
- d. Grading
- e. Utilities
- f. Traffic
- g. Easements

## 4. Land Use Permits

## 5. Project Benefits

# Overview



# Existing Conditions



**Site Area: 26.15 acres (1,138,161 SF)**  
**Zoning District: G1 Gateway Neighborhood Mixed Use Corridor**





# Project Objectives



**Conforming with Zoning:** Develop a project in conformance with the base zoning for G1 district.



**Sensitively Scaled:** Propose a development which is below the as-of-right density.



**Public Space as Priority:** Prioritize robust public spaces and thoughtful urban design.



**Connect with Community:** Improve connectivity to the site with an enhanced multi-modal network through and around the project site.



**Minimal Impact:** Limit development to previously developed area, improve stormwater management and reduce impervious surface (~17,000sf)



**Sustainable building strategies:** Construct all-electric buildings with access to daylight and fresh air

## Summary

- **360 market-rate rental apartments comprising studio, one bedroom, two bedroom and three bedroom units (~14 units/acre)**
- **Mix of 3-story and 4-story buildings of 12 or 24 units/ ea**
- **573 parking spaces**
- **~2.7 acres of community space**

# What We Heard

*Planning Board Conceptual Consultation  
February 15, 2024*

- **Commission a traffic study to quantify impacts of proposed development.**
- **Focus on types of community spaces to serve the residents and visitors to the site alike.**
  - **Study wayfinding strategies to make public access to community space clear.**
- **Commission an acoustic study to demonstrate compliance with Highway Noise Overlay.**
- **Study solar panel readiness and EV car chargers as part of sustainability strategy.**
- **Provide detail on easements and maintenance agreements.**

# Review Process and Key Changes

|                 |  |
|-----------------|--|
| 01/23/24        | City Staff Meeting   |
| 2/1/2024        | Introductory plan review and easement discussion with abutters |
| 02/15/24        | Planning Board Conceptual Consultation                         |
| 03/12/24        | TAC Work Session   |
| 04/03/24        | City Staff Meeting   |
| 04/08/24        | Conservation Commission Site Walk                              |
| 04/10/24        | Conservation Commission Work Session                           |
| 05/07/24        | TAC Meeting #1   |
| 05/20/24        | City Staff Meeting   |
| 07/02/24        | TAC Meeting #2   |
| 07/10/24        | Conservation Commission Meeting #1                             |
| 07/25/24        | City Staff Meeting   |
| 08/06/24        | TAC Meeting #3   |
| 08/14/24        | Conservation Commission Meeting #2                             |
| 08/28/24        | City Staff Meeting   |
| <b>09/16/24</b> | <b>Conservation Commission Meeting #3 (Approval)</b>           |
| 10/01/24        | TAC Meeting #4   |
| 10/29/24        | City Staff Meeting   |
| <b>11/05/24</b> | <b>TAC Meeting #5 (Approval)</b>                               |

## Key Changes

- Concentrated the development footprint outside the wetland buffers (nearly 17,000sf net reduction of impervious surface in the buffer).
- Strengthened connections to surrounding community with multi-modal pathways.
- Provided turnaround for DPW snow plows and clarified Hampton Inn access.
- Created a variety of landscape experiences and architectural designs to provide a richer experience for residents and visitors.

# Site Design



# Site Context and Connections

Bus Routes, Bike Routes, Surrounding Businesses



# Site Constraints

Easements, Wetlands, Property Boundaries



# Proposed Site Plan



# A Variety of Streetscapes



Neighborhood Street

Shared Street / Mews

Connector Street

Hampton Inn Access

Main Street





# A Network of Community Space

## Overview



# Creating a Connection to Community



Dog Park

Community Green

Greenway


Rain Garden Overlook

Extension of Durgin Lane



# Community Space

A Framework of Active and Passive Spaces



### POTENTIAL COMMUNITY SPACE

|                                     |                        |                                     |                       |
|-------------------------------------|------------------------|-------------------------------------|-----------------------|
| <b>Park</b><br>                     | <b>Greenway</b><br>    | <b>Community Garden or Farm</b><br> | <b>Playground</b><br> |
| <b>Wide Pedestrian Sidewalk</b><br> | <b>Pocket Park</b><br> | <b>Shared Multi-Modal Way</b><br>   |                       |

- Active Community Space
- Transitional Community Space
- Passive Community Space
- Open Space Connector



# Community Space

## Community Spaces by Type

### Shared Multi-Modal Way



A pedestrian priority way where pedestrians, cyclists and motorists all share the multimodal way that shall be designed to promote slow vehicle travel through the use of decorative pavers, street furniture, signage and plantings commensurate to allow the entire street to function effectively as shared public space.

### Pocket Park




A community *space available for informal activities* in close proximity to neighborhood residences. A pocket park is *spatially defined by buildings*. Its landscape shall consist of *paths, lawns and trees, formally disposed*. The minimum size shall be 500 sf.

### Wide Pedestrian Sidewalk



A *wide pedestrian sidewalk (a minimum of 10' in width unless otherwise defined by the Ordinance)* located between the building façade and the public right of way. Wide pedestrian sidewalks *provide space between the façade and the curblin*e for *comfortable pedestrian movement, street trees and street furniture*.



### Active Park




An area of natural, semi-natural, *or planted space set aside for human enjoyment and recreation* or for the protection of wildlife or natural habitats. A park may consist of *grassy areas, trees and other natural or planted landscape features*, and may also *contain walking paths and trails, monuments, fountains, playground equipment, benches, picnic tables* and similar amenities.

### Passive Park



An area of natural, semi-natural, or planted space set aside for human enjoyment and recreation *or for the protection of wildlife or natural habitats*. A park may consist of *grassy areas, trees and other natural or planted landscape features*, and may also contain walking paths and trails, monuments, fountains, playground equipment, benches, picnic tables and similar amenities.

### Greenway



A *linear community space* that may follow natural corridors providing unstructured and limited amounts of structured recreation. A *greenway may be spatially defined by landscaping* rather than buildings. Its landscape shall consist of *paths and trails, waterbodies, and trees, naturalistically disposed*.

# Community Space

Community Spaces - Location and Character

Central Park and Multimodal Way



Pocket Park



Wide Pedestrian Sidewalk



Greenway



Wetland Buffer Park



Rain Garden Park



# Community Space

## Wide Pedestrian Sidewalk



Wide Pedestrian Sidewalk



# Community Space

Active Park and Shared Multi-Modal Way



Central Green and Multi-Modal Way




# Community Space

## Pocket Park



Pocket Park





# Community Space

## Greenways



Greenways



# Community Space

## Passive Park



Rain Garden Park







Buffer Passive Park



# Community Space

## Signage, Wayfinding and Visitor Parking

- A Project Monument Sign**  
Property Entrance
- B Vehicular Wayfinding | Landmarks**  
Project Name  
Hampton Inn  
Gosling Road  
Arthur F. Brady Drive  
Woodbury Avenue
- C Vehicular Wayfinding | Streets & Community Spaces**  
Project Streets A, B, C  
Central Green  
Leasing Office  
Mail/ Deliveries
- D Building Markers**  
Project Structures  
Freestanding or Building Mounted
- E Park Markers**  
Pedestrian Directional
- F Interpretive Markers**  
Wetland Informational Plaques
- G Hampton Inn Entrance**  
8 ft. height  
Illuminated
- Regulatory Signage**  
  -  Cross Walks
  -  Stop & All Way
  -  Keep Right
  -  Accessible Parking



# Multi-Modal Resources

Signage, Wayfinding and Visitor Parking



**EV Charging**



**Bike Room**

18 rooms










**Bike Rack**


7 racks



# Site Servicing and Logistics

Trash, Move-in / Move-out

-  Trash Room
-  Maintenance Yard with Central Dumpster
-  Mail Room
-  Package Room
-  Mail/ Package Delivery Vehicle Parking
-  Primary Entry
-  Secondary Entry (Move in/ Move out)



# Landscape and Architectural Design

View from Durgin Lane Entrance



# Landscape and Architectural Design

View of Community Green



# Landscape and Architectural Design

View of Greenway





# Landscape Design

View of Wetland Buffer




# Landscape Design

View of Rain Garden



# Architectural Design

## Diversity of Building Types



# Architectural Design

Changes in Scale, Entrance Locations and Color to Enhance Variety



3-Story Center Entrance - Paired



3-Story Courtyard Entrance

# Architectural Design

Changes in Scale, Entrance Locations and Color to Enhance Variety



4-Story Center Entrance




4-Story Side Entrance

# Technical Approach

# Highway Noise Overlay District Analysis

## Unadjusted dBA Noise Contours with Common Outdoor Areas



## Noise Mitigation Strategies: Sound Wall and Garages





**Noise Mitigation Strategies: Superinsulated Walls:**  
Based on the OITC 27 composite exterior envelope performance specified, the wall construction suffices for the “superinsulated” construction that the HNOD document suggests is needed to achieve the interior sound level of 45 dBA and no further mitigation is needed to meet the requirements of the Highway Noise Overlay District.

# Sustainability Strategies

- Site
  - Walkability
  - Proximity to public transit (bus stop)
  - Distributed bike parking
  - Stormwater management/ limited impervious surface
  - Landscape supportive of existing ecosystem
  - On-site solar photovoltaic ready
  - EV Chargers
  - Shaded outdoor space
- Building
  - Efficient, all-electric building systems
  - Efficient lighting
  - Dimming/programmed site lighting
  - Attention to building solar orientation
    - Daylighting + shading
    - Ventilation
  - Healthy indoor air quality
  - High acoustic comfort
  - Excellent thermal comfort







**SITE DATA:**  
 LOCATION: TAX MAP 239, LOT 13-2, MAP 239 LOT 16, MAP 239 LOT 18  
 OWNER: 100 DURGIN LANE OWNER LLC  
 ONE MARINA PARK DRIVE, SUITE 1500  
 BOSTON, MA 02210

ZONING DISTRICT: GATEWAY NEIGHBORHOOD MIXED USE CORRIDOR (G1)  
 HIGHWAY NOISE OVERLAY DISTRICT

PROPOSED USE: MULTI-FAMILY RESIDENTIAL DEVELOPMENT  
 EXISTING LOT SIZE: ±1,139,161 SF / 26.15 ACRES (MAP 239 LOT 13-2, LOT 16, LOT 18)

**DEVELOPMENT STANDARDS**

| GENERAL RESIDENTIAL DEVELOPMENT (10.5B42.30) | REQUIRED  | PROPOSED      |
|--|-----------|---------------|
| MINIMUM SITE DEVELOPMENT AREA:               | 10,000 SF | ±1,139,161 SF |
| MINIMUM SITE WIDTH:                          | 75 FT     | >75 FT        |
| MINIMUM SITE LENGTH:                         | 100 FT    | >100 FT       |
| MINIMUM PERIMETER BUFFER:                    | N/A       | -             |
| MAXIMUM DEVELOPMENT BLOCK DIMS:              |           |               |
| BLOCK LENGTH:                                | 500 FT    | 442 FT        |
| BLOCK PERIMETER:                             | 1,500 FT  | 1,266 FT      |
| MAXIMUM BUILDING COVERAGE:                   | 50%       | 8.8%          |
| MINIMUM OPEN SPACE COVERAGE:                 | 20%       | 63.4%         |

| APARTMENT BUILDING (10.5B34.40)         | REQUIRED  | PROPOSED                |
|---|---|-------------------------|
| MINIMUM LOT DEPTH:                      | NR  | -                       |
| MINIMUM STREET FRONTAGE:                | 50 FT   | 200.6 FT                |
| FRONT YARD SETBACK:                     | 10-30 FT  | 239.6 FT <sup>(1)</sup> |
| MIN. SIDE YARD SETBACK:                 | 15 FT   | 26.3 FT                 |
| MIN. REAR YARD SETBACK:                 | 20 FT   | 84.3 FT                 |
| DWELLING UNITS PER BUILDING:            | 4-24  | VARIES (24 MAX.)        |
| MAXIMUM DWELLING UNIT SIZE:             | NR  | -                       |
| MAXIMUM BUILDING HEIGHT:                | 4 STORIES OR 50 FT                                | <50 FT                  |
| MINIMUM STREET-FACING FACADE HEIGHT:    | 24 FT   | >24 FT                  |
| MAX. FINISH FLOOR ABOVE SIDEWALK:       | 36"   | VARIES                  |
| MAXIMUM BUILDING COVERAGE:              | 50%   | 8.1%                    |
| MAXIMUM BUILDING FOOTPRINT:             | NR  | -                       |
| MAXIMUM FACADE MODULATION LENGTH:       | 50 FT   | <50 FT                  |
| MINIMUM STREET FACING FACADE GLAZING:   | 20% GROUND FLOOR                                  | >20%                    |
| MAXIMUM STREET FACING ENTRANCE SPACING: | NR  | -                       |
| ALLOWED ROOF TYPES:                     | ALL   | FLAT                    |
| ALLOWED FACADE TYPES:                   | FORECOURT, RECESSED, ENTRY, DOORYARD, STEP, PORCH | FORECOURT, RECESSED     |

| MIXED-USE BUILDING (10.5B34.80)         | REQUIRED   | PROPOSED                |
|---|--|-------------------------|
| MINIMUM LOT DEPTH:                      | NR   | -                       |
| MINIMUM STREET FRONTAGE:                | 50 FT  | 200.6 FT                |
| FRONT YARD SETBACK:                     | 0-50 FT  | 268.1 FT <sup>(1)</sup> |
| MIN. SIDE YARD SETBACK:                 | 15 FT  | 242.0 FT                |
| MIN. REAR YARD SETBACK:                 | 20 FT  | 453.0 FT                |
| MAXIMUM DWELLING UNITS PER BUILDING:    | 24   | VARIES (24 MAX.)        |
| MAXIMUM DWELLING UNIT SIZE:             | NR   | -                       |
| MAXIMUM BUILDING HEIGHT:                | 4 STORIES OR 50 FT   | <50 FT                  |
| MINIMUM STREET-FACING FACADE HEIGHT:    | 18 FT  | 47.5 FT                 |
| MAX. FINISH FLOOR ABOVE SIDEWALK:       | 24"  | VARIES                  |
| MAXIMUM BUILDING COVERAGE:              | 60%  | <1%                     |
| MAXIMUM BUILDING FOOTPRINT:             | 20,000 SF  | 7,370 SF                |
| MAXIMUM FACADE MODULATION LENGTH:       | 100 FT   | <100 FT                 |
| MINIMUM STREET FACING FACADE GLAZING:   | 50% GROUND FLOOR   | >50%                    |
| MAXIMUM STREET FACING ENTRANCE SPACING: | NR   | -                       |
| ALLOWED ROOF TYPES:                     | ALL  | FLAT                    |
| ALLOWED FACADE TYPES:                   | FORECOURT, RECESSED ENTRY, PORCH, OFFICEFRONT, SHOPFRONT, TERRACE, GALLERY, ARCADE | FORECOURT, RECESSED     |

(1) - THE APPLICANT IS REQUESTING THE PLANNING BOARD TO ALLOW AN INCREASE OF BUILDING SETBACK FROM THE FRONT LOT LINE AS ALLOWED BY SECTION 10.5B41.60.

| COMMUNITY SPACE: | REQUIRED   | PROPOSED   |
|------------------|------------|------------|
|                  | 10%        | 10.6%      |
|                  | 113,916 SF | 120,793 SF |

**PARKING REQUIREMENTS**

|   |                        |            |
|---|------------------------|------------|
| RESIDENTIAL UNITS (<750 SF)             | 209 UNITS X 1.0 SPACES | 209 SPACES |
| RESIDENTIAL UNITS (>750 SF)             | 151 UNITS X 1.3 SPACES | 197 SPACES |
| VISITOR SPACES                          | 1 SPACE / 5 UNITS      | 82 SPACES  |
| TOTAL MINIMUM PARKING SPACES REQUIRED = |                        | 488 SPACES |

| PARKING SPACES | REQUIRED   | PROPOSED   |
|----------------|------------|------------|
|                | 488 SPACES | 573 SPACES |

| ADA PARKING SPACES | REQUIRED <sup>(2)</sup> | PROPOSED  |
|--------------------|-------------------------|-----------|
|                    | 12 SPACES               | 14 SPACES |

(2) - PER THE AMERICANS WITH DISABILITIES ACT (ADA) STANDARDS, LATEST EDITION.

| PARKING SPACE DIMENSIONAL REQUIREMENTS: | REQUIRED   | PROPOSED |
|---|------------|----------|
| STANDARD 90° STALL:                     |            |          |
| WIDTH:                                  | 8.5 FT MIN | 8.5 FT   |
| LENGTH:                                 | 19 FT MIN  | 19 FT    |
| STANDARD 0° STALL:                      |            |          |
| WIDTH:                                  | 8.5 FT MIN | 8.5 FT   |
| LENGTH:                                 | 20 FT MIN  | 20 FT    |
| DRIVE AISLE WIDTH:                      |            |          |
| 90° (2-WAY TRAFFIC):                    | 24 FT      | 24 FT    |
| 0° (2-WAY TRAFFIC):                     | 24 FT      | 24 FT    |

| BICYCLE SPACES   | REQUIRED         | PROPOSED                                       |
|--|------------------|--|
| 1 BICYCLE SPACE / 10 PARKING SPACES:                                   | 30 SPACES (MAX.) | >30 SPACES                                     |
| (INDOOR BIKE STORAGE WILL BE PROVIDED THAT MEETS OR EXCEEDS REQUIRED.) |                  | (ADDITIONAL EXTERIOR BIKE RACKS ARE PROPOSED.) |

LOT LINE REVISIONS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY. FINAL LOT LINE REVISION PLAN SHALL BE PREPARED BY THE PROJECT SURVEYOR AND RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS PRIOR TO ISSUING BUILDING PERMITS.

- SITE RECORDING NOTES:**
- THIS SITE PLAN SHALL BE RECORDED IN THE ROCKINGHAM COUNTY REGISTRY OF DEEDS.
  - ALL IMPROVEMENTS SHOWN ON THIS SITE PLAN SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES SHALL BE MADE TO THIS SITE PLAN WITHOUT THE EXPRESS APPROVAL OF THE PORTSMOUTH PLANNING DIRECTOR.
  - ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.
  - THIS IS NOT A BOUNDARY SURVEY AND SHALL NOT BE USED AS SUCH.

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| F    | 11/27/2024 | PB SUBMISSION  |
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

PROJECT NO: E5071-001  
 DATE: 4/22/2024  
 FILE: E5071-001-C-DSGN\_unlocked.dwg  
 DRAWN BY: BKC/NHW  
 DESIGNED/CHECKED BY: NAH  
 APPROVED BY: PMC

**PROPOSED MULTI-FAMILY DEVELOPMENT**


100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE


**OVERALL SITE PLAN**

SCALE: AS SHOWN

C-300




Last Saved: 11/21/2024 3:28pm By: BCurcio  
 Plotted On: Nov 22, 2024 3:28pm  
 Tighe & Bond \Vignette\com\dwg\Drawn\Projects\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN\_unlocked.dwg



| STORM SEWER STRUCTURE TABLE |       |                      |          |
|-----------------------------|-------|----------------------|----------|
| STRUCTURE                   | RIM   | INV. IN              | INV. OUT |
| PCB1                        | 64.60 | 60.00 SW<br>60.00 NE | 60.00 SE |
| PCB2                        | 64.00 | 60.30 NW             | 60.30 SW |
| PCB3                        | 64.00 |                      | 60.55 SE |
| PCB4                        | 64.60 | 60.10 NW             | 60.10 NE |
| PCB5                        | 64.80 | 60.50 SW             | 60.50 SE |
| PCB6                        | 64.75 | 61.00 SW             | 61.00 NE |
| PCB7                        | 64.75 | 61.30 SW             | 61.30 NE |
| PCB8                        | 65.35 | 61.65 N              | 61.65 NE |
| PCB9                        | 65.25 |                      | 62.00 S  |
| PCB10                       | 64.65 | 60.15 NE             | 60.05 NW |
| PCB11                       | 64.65 |                      | 60.30 SW |
| PCB12                       | 65.25 | 60.35 SE             | 60.25 NW |
| PCB13                       | 65.75 | 60.60 SE             | 60.50 NW |
| PCB14                       | 66.95 | 61.15 SE<br>61.60 NE | 61.05 NW |
| PCB15                       | 67.00 | 61.80 SE<br>61.60 NE | 61.70 NW |
| PCB16                       | 66.50 | 62.60 SE             | 62.60 SW |
| PCB17                       | 66.50 | 62.95 SE             | 62.95 NW |
| PCB18                       | 66.50 |                      | 63.05 NW |
| PCB19                       | 65.25 |                      | 61.00 NW |
| PCB20                       | 65.00 |                      | 61.50 NE |
| PCB21                       | 64.50 |                      | 59.35 SE |
| PCB22                       | 64.50 |                      | 59.35 NE |
| PCB23                       | 65.00 | 60.20 SE             | 60.10 N  |
| PCB24                       | 65.00 |                      | 60.35 NW |
| PCB25                       | 64.70 | 60.95 SE             | 60.85 N  |
| PCB26                       | 64.80 |                      | 61.10 NW |
| PCB27                       | 66.70 | 62.05 SE<br>61.90 N  | 61.90 SW |
| PCB28                       | 66.50 | 62.10 NE             | 62.10 S  |
| PCB29                       | 66.00 | 62.75 SE             | 62.65 SW |
| PCB30                       | 67.15 | 62.35 SE             | 62.35 NW |
| PCB31                       | 67.00 | 62.70 SE<br>62.70 NE | 62.70 NW |
| PCB32                       | 66.90 | 63.10 SE             | 63.10 NW |
| PCB33                       | 66.75 | 63.30 NE             | 63.20 NW |
| PCB34                       | 57.75 |                      | 53.85 SW |
| PCB35                       | 61.00 | 55.25 NE             | 55.15 SW |
| PCB35A                      | 62.75 |                      | 57.50 NE |
| PCB36                       | 59.50 | 55.85 SE             | 55.75 SW |
| PCB37                       | 61.00 |                      | 56.25 NW |
| PCB38                       | 62.90 | 57.00 SE<br>58.00 SW | 56.90 NW |
| PCB39                       | 64.90 | 57.35 SE<br>57.35 W  | 57.25 NE |
| PCB40                       | 65.00 | 58.20 SE<br>60.00 NE | 58.10 NW |
| PCB41                       | 65.50 | 61.25 NE<br>58.75 SE | 58.65 NW |
| PCB42                       | 65.60 | 60.65 SW             | 59.35 NW |
| PCB43                       | 65.60 | 60.85 SW             | 60.85 NE |
| PCB44                       | 65.20 | 61.25 SW             | 61.25 NE |
| PCB45                       | 65.50 | 62.00 NE             | 62.00 N  |

| STORM SEWER STRUCTURE TABLE |       |                                  |                      |
|-----------------------------|-------|----------------------------------|----------------------|
| STRUCTURE                   | RIM   | INV. IN                          | INV. OUT             |
| PCB46                       | 65.00 | 57.85 SW                         | 57.75 E              |
| PCB47                       | 65.00 | 58.35 SE                         | 58.25 NE             |
| PCB48                       | 65.85 | 58.80 SE                         | 58.70 NW             |
| PCB49                       | 66.00 | 59.35 SE<br>60.50 NE             | 59.25 NW             |
| PCB50                       | 65.20 | 59.90 SE                         | 59.80 NW             |
| PCB51                       | 65.40 |                                  | 60.65 NW             |
| PCB52                       | 63.75 | 59.35 S                          | 59.25 NW             |
| PCDS1                       | 66.10 | 58.60 SW                         | 58.50 NW             |
| PCDS2                       | 65.50 | 59.30 SW                         | 59.20 SE             |
| PCDS3                       | 62.25 | 54.50 E                          | 54.00 NE             |
| PDMH1                       | 64.35 | 58.80 NW                         | 58.80 SE             |
| PDMH2                       | 65.50 | 59.00 NE<br>60.15 NW             | 58.90 SE             |
| PDMH3                       | 65.50 | 59.45 SW<br>59.45 NW             | 59.35 NE<br>60.50 SE |
| PDMH4                       | 65.50 | 59.70 SW<br>59.80 SE             | 59.60 NE             |
| PDMH5                       | 65.50 | 60.20 SW<br>60.20 SE<br>60.20 NW | 60.10 NE             |
| PDMH6                       | 67.50 | 62.20 NE                         | 62.10 NW             |
| PDMH7                       | 65.60 | 60.85 SW<br>60.85 NW<br>60.85 SE | 60.75 NE             |
| PDMH8                       | 65.75 | 61.10 SW<br>62.20 SE             | 61.00 NE             |
| PDMH9                       | 64.00 | 57.85 SE                         |                      |
| PDMH10                      | 65.90 | 59.75 SE                         | 58.20 NW             |
| PDMH11                      | 66.00 | 58.65 SW                         | 58.65 NE<br>60.00 NW |
| PDMH12                      | 64.75 | 59.10 SE<br>59.20 SW<br>59.20 NW | 59.10 NE             |
| PDMH13                      | 65.50 | 59.85 SE<br>59.95 NE<br>59.95 S  | 59.85 NW             |
| PDMH14                      | 65.20 | 60.60 NE<br>60.60 S<br>60.50 SE  | 60.50 NW             |
| PDMH15                      | 66.25 | 61.25 NE<br>61.15 SE             | 61.15 NW             |
| PDMH16                      | 67.15 | 61.70 NE                         | 61.70 NW             |
| PDMH17                      | 67.75 | 63.00 NW<br>63.00 SE<br>63.00 NE | 62.90 SW             |
| PDMH18                      | 67.60 | 63.70 N                          | 63.60 SW             |
| PDMH19                      | 62.05 | 53.85 SW<br>55.50 SE             | 53.00 NW             |
| PDMH20                      | 62.00 | 55.00 S<br>54.75 NE<br>57.00 SW  | 54.65 W<br>56.00 NW  |
| PDMH21                      | 63.50 | 56.70 SW<br>56.70 S              | 56.60 N              |
| PDMH22                      | 65.90 | 61.50 S                          | 61.50 NE             |
| PDMH23                      | 65.20 | 60.35 SE<br>61.00 NE             | 60.25 NW             |
| PDMH24                      | 65.00 | 59.75 SW                         | 59.65 N              |
| PDMH25                      | 60.15 | 56.60 E                          | 56.50 NW             |
| PJFF1                       | 66.00 | 58.45 SE                         | 58.35 SW             |
| PJFF2                       | 65.50 | 59.15 NW                         | 59.05 SW             |
| POCS1                       | 54.00 |                                  | 46.50 N              |
| POCS2                       | 60.50 |                                  | 54.50 NE             |
| PYD1                        | 66.75 |                                  | 63.25 NW             |
| PYD2                        | 66.75 |                                  | 63.25 SW             |
| PYD3                        | 66.75 |                                  | 63.90 S              |
| PYD4                        | 63.90 | 58.20 NE<br>58.20 SE             | 58.10 NW             |
| PYD5                        | 64.25 | 58.75 NE                         | 58.65 NW             |
| PYD6                        | 63.00 |                                  | 59.25 SW             |



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

**100 DURGIN  
LANE OWNER,  
LLC**


**100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE**

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

**GRADING, DRAINAGE, AND  
EROSION CONTROL PLAN**

SCALE: AS SHOWN

Last Saved: 10/21/2024 9:33am By: DCurcio  
 Plotted On: Oct 22, 2024 9:33am  
 Tighe & Bond \\\servername\shared\Projects\E1E071 - Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane Drawings\AutoCAD\Sheet\E5071-001-C-DSGN.dwg



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN  
LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE


| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 4/22/2024            |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |


GRADING, DRAINAGE, AND  
EROSION CONTROL PLAN

SCALE: AS SHOWN


C-402



SEE SHEET C-101 FOR GRADING &  
DRAINAGE PLAN NOTES & LEGEND



Last Saved: 10/21/2024 9:37am By: DCurcio  
 Plotted On: Oct 22, 2024 9:37am  
 Tighe & Bond \\lgn\shared\dwg\proj\100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN.dwg



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |


  

|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 4/22/2024            |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |



UTILITIES PLAN

SCALE: AS SHOWN



C-501



SEE SHEET C-101 FOR UTILITY  
PLAN NOTES & LEGEND



Last Saved: 10/21/2024 9:43am By: DCurcio  
 Plotted On: Oct 22, 2024 9:43am  
 Tighe & Bond \\lignwood\cadd\projects\E5071-Estate\Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN.dwg



**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 4/22/2024            |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |


UTILITIES PLAN

SCALE: AS SHOWN

C-502

Last Saved: 10/21/2024 10:49:40am By: DCurcio  
 Plotted On: Oct 22, 2024 2:22:22 PM  
 Tighe & Bond \\lgn\shared\dwg\proj\100 Durgin Lane\Projects\E5071-001-C-DSGN.dwg

SEE SHEET C-101 FOR UTILITY PLAN NOTES & LEGEND



# Required Permits

## *Planning Board*

- **Site Plan Review Permit**
- **Lot Line Revision Permit**
- **Development Site Conditional Use Permit**
- **Highway Noise Overlay District Conditional Use Permit**
- **Wetland Conditional Use Permit**



# Benefits Summary

1. 360 rental apartments homes providing 530 new beds to Portsmouth under supplied housing market supporting the continued growth of the City and its largest employers
2. Revitalization of a deteriorated, vacant building into a dynamic and purposeful community.
3. Low impact site development that will incorporate 'green streets' sustainable stormwater strategies in streetscape design and implementation.
  - a. 28% reduction of impervious surface within the wetland resulting in the restoration of ~17k SF of wetland area.
  - b. 17,837 SF Reduction in impervious overall
4. 10% + public community space equal to ~2.8 across a mix of passive and active community space including:
  - a. Greenway/Common
  - b. Pocket Park
  - c. Shared Multimodal connections
  - d. Pedestrian parks
5. Multi-modal connections strengthening the link between the site and the retail amenities at the South (Whole Foods, Home Goods, and Market Basket).
6. Fossil fuel-free all electric buildings with on site EV charging.



# Economic Benefits Summary

1. The redevelopment of the vacant retail site will create ~300+ private construction jobs and ~20 permanent Jobs.
2. The development has agreed to bear the cost of certain off-site improvements which include:
  - a. The upgrade the water main on Woodbury Avenue estimated at over \$1 million.
  - b. Reconstruction of Durgin Lane and the existing sidewalk along Durgin Square pedestrian sidewalk to convert into a multi-modal path estimated at ~\$200k.
3. Projected \$1 million of incremental annual real estate tax revenue.






# Thank You!

Representative  
Site Signage Type A

100 Durgin Lane Project  
October, 2024






A

**Project Monument Sign**  
Property Entrance  
100 ft. Max Area

# Representative Site Signage Type B, C, D

100 Durgin Lane Project  
October, 2024




**B** Vehicular Wayfinding | Landmarks  
Vehicular Directional  
Perimeter Streets and Landmarks

**C** Vehicular Wayfinding | Streets & Community Spaces  
Vehicular Directional  
Internal Streets and Places

**D** Building Markers  
Project Structures  
Freestanding or Building Mounted

# Representative Site Signage Type E, F

100 Durgin Lane Project  
October, 2024




**E** Park Markers  
Pedestrian Directional



**F** Interpretive Markers  
Wetland Informational Plaques

Representative  
Site Signage Type G


100 Durgin Lane Project  
October, 2024



**G** Hampton Inn Entrance  
8 ft. height  
Illuminated

# Representative Regulatory Signage

100 Durgin Lane Project  
October, 2024




# PROPOSED MULTI-FAMILY DEVELOPMENT

100 DURGIN LANE  
PORTSMOUTH, NEW HAMPSHIRE

APRIL 22, 2024  
LAST REVISED:  
NOVEMBER 27, 2024

| LIST OF DRAWINGS |   |              |
|------------------|---|--------------|
| SHEET NO.        | SHEET TITLE   | LAST REVISED |
| -                | COVER SHEET   | 11/27/2024   |
| 1 OF 4           | TOPOGRAPHIC SURVEY NOTES                                  | 2/29/2024    |
| 2 OF 4           | TOPOGRAPHIC SURVEY  | 2/29/2024    |
| 3 OF 4           | TOPOGRAPHIC SURVEY  | 2/29/2024    |
| 4 OF 4           | TOPOGRAPHIC SURVEY  | 2/29/2024    |
| C-101            | GENERAL NOTES AND LEGEND                                  | 11/27/2024   |
| C-201            | DEMOLITION PLAN   | 11/27/2024   |
| C-202            | DEMOLITION PLAN   | 11/27/2024   |
| C-300            | OVERALL SITE PLAN   | 11/27/2024   |
| C-301            | SITE PLAN   | 11/27/2024   |
| C-302            | SITE PLAN   | 11/27/2024   |
| C-401            | GRADING, DRAINAGE, AND EROSION CONTROL PLAN               | 10/23/2024   |
| C-402            | GRADING, DRAINAGE, AND EROSION CONTROL PLAN               | 10/23/2024   |
| C-501            | UTILITIES PLAN  | 10/23/2024   |
| C-502            | UTILITIES PLAN  | 10/23/2024   |
| C-600            | ABUTTERS' ACCESS EASEMENT PLAN                            | 10/23/2024   |
| C-601            | ABUTTERS' UTILITY, DRAINAGE, AND GRADING EASEMENT PLAN    | 10/23/2024   |
| C-602            | COMMUNITY SPACE EASEMENT PLAN                             | 10/23/2024   |
| C-603            | DEVELOPMENT SITE ACCESS, DRAINAGE, & UTILITY EASEMENTS    | 11/27/2024   |
| C-801            | EROSION CONTROL NOTES AND DETAILS SHEET                   | 10/23/2024   |
| C-802            | DETAILS SHEET   | 10/23/2024   |
| C-803            | DETAILS SHEET   | 11/27/2024   |
| C-804            | DETAILS SHEET   | 10/23/2024   |
| C-805            | DETAILS SHEET   | 10/23/2024   |
| C-806            | DETAILS SHEET   | 10/23/2024   |
| C-807            | DETAILS SHEET   | 10/23/2024   |
| C-808            | DETAILS SHEET   | 10/23/2024   |
| C-809            | DETAILS SHEET   | 10/23/2024   |
| L0-01            | LANDSCAPE NOTES   | 10/23/2024   |
| L2-00            | LAYOUT AND MATERIALS PLAN                                 | 10/23/2024   |
| L3-00            | PLANTING PLAN   | 10/23/2024   |
| L4-00            | PHOTOMETRIC PLAN  | 10/23/2024   |
| L5-00            | SITE DETAILS  | 10/23/2024   |
| L5-01            | SITE DETAILS  | 10/23/2024   |
| L5-02            | SITE DETAILS  | 10/23/2024   |
| L5-03            | SITE DETAILS  | 10/23/2024   |
| L5-04            | PLANTING DETAILS  | 10/23/2024   |
| 1 OF 15          | 4-STORY ELEVATOR BUILDING (AMENITY) ELEVATIONS            | 10/23/2024   |
| 2 OF 15          | 3-STORY WALK-UP BUILDING (SQUARE) ELEVATIONS              | 7/24/2024    |
| 3 OF 15          | 3-STORY WALK-UP BUILDING (SQUARES AGGREGATED) ELEVATIONS  | 7/24/2024    |
| 4 OF 15          | 3-STORY WALK-UP BUILDING (SHIFTED) ELEVATIONS             | 7/24/2024    |
| 5 OF 15          | 3-STORY WALK-UP BUILDING (SHIFTED AGGREGATED) ELEVATIONS  | 7/24/2024    |
| 6 OF 15          | 3-STORY WALK-UP BUILDING (SHIFTED AGGREGATED) ELEVATIONS  | 7/24/2024    |
| 7 OF 15          | 4-STORY BUILDING ELEVATIONS                               | 7/24/2024    |
| 8 OF 15          | 4-STORY ELEVATOR BUILDING (AMENITY) FLOOR PLANS           | 10/23/2024   |
| 9 OF 15          | 4-STORY ELEVATOR BUILDING (AMENITY) FLOOR PLANS           | 10/23/2024   |
| 10 OF 15         | 3-STORY WALK-UP BUILDING (SQUARE) FLOOR PLANS             | 8/21/2024    |
| 11 OF 15         | 3-STORY WALK-UP BUILDING (SQUARES AGGREGATED) FLOOR PLANS | 8/21/2024    |
| 12 OF 15         | 3-STORY WALK-UP BUILDING (SHIFTED) FLOOR PLANS            | 8/21/2024    |
| 13 OF 15         | 3-STORY WALK-UP BUILDING (SHIFTED AGGREGATED) FLOOR PLANS | 8/21/2024    |
| 14 OF 15         | 4-STORY ELEVATOR BUILDING FLOOR PLANS                     | 8/21/2024    |
| 15 OF 15         | MAINTENANCE AREA PLAN & ELEVATIONS                        | 10/23/2024   |

| LIST OF PERMITS   |               |      |
|---|---------------|------|
| LOCAL   | STATUS        | DATE |
| SITE PLAN REVIEW PERMIT                                 | PENDING       |      |
| LOT LINE REVISION PERMIT                                | PENDING       |      |
| CONDITIONAL USE PERMIT - DEVELOPMENT SITE               | PENDING       |      |
| CONDITIONAL USE PERMIT - WETLAND BUFFER                 | PENDING       |      |
| CONDITIONAL USE PERMIT - HIGHWAY NOISE OVERLAY DISTRICT | PENDING       |      |
| STATE   |               |      |
| NHDES - SEWER CONNECTION PERMIT                         | NOT SUBMITTED |      |
| NHDES - ALTERATION OF TERRAIN PERMIT                    | NOT SUBMITTED |      |
| FEDERAL   |               |      |
| NPDES - CONSTRUCTION GENERAL PERMIT                     | NOT SUBMITTED |      |



LOCATION MAP  
SCALE: 1" = 2000'



**CONSTRUCTION NOTES:**

1. THE CONTRACTOR SHALL NOT RELY ON SCALED DIMENSIONS AND SHALL CONTACT THE ENGINEER FOR CLARIFICATION IF A REQUIRED DIMENSION IS NOT PROVIDED ON THE PLANS.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS AND METHODS, AND FOR SITE CONDITIONS THROUGHOUT CONSTRUCTION. NEITHER THE PLANS NOR THE SEAL OF THE ENGINEER AFFIXED HEREON EXTEND TO OR INCLUDE SYSTEMS REQUIRED FOR THE SAFETY OF THE CONTRACTOR, THEIR EMPLOYEES, AGENTS OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING AND IMPLEMENTING SAFETY PROCEDURES AND SYSTEMS AS REQUIRED BY THE UNITED STATES OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA), AND ANY STATE OR LOCAL SAFETY REGULATIONS.
3. TIGHE & BOND ASSUMES NO RESPONSIBILITY FOR ANY ISSUES LEGAL OR OTHERWISE, RESULTING FROM CHANGES MADE TO THESE DRAWINGS WITHOUT WRITTEN AUTHORIZATION OF TIGHE & BOND.

PREPARED BY:

**Tighe & Bond**

177 CORPORATE DRIVE  
PORTSMOUTH, NEW HAMPSHIRE 03801  
603-433-8818



OWNER/APPLICANT:

100 Durgin Lane Owner LLC  
ONE MARINA PARK DRIVE, SUITE 1500  
BOSTON, MA 02210

SURVEYOR:

HOLDEN ENGINEERING & SURVEYING, INC.  
56 OLD SUNCOOK ROAD, PO BOX 480  
CONCORD, NH 03302

ARCHITECT:

UTILE  
115 KINGSTON STREET  
BOSTON, MA 02111

LANDSCAPE ARCHITECT:

ACETO LANDSCAPE ARCHITECTS  
424 FORE STREET #3B  
PORTLAND, ME 04101

**PLANNING BOARD SUBMISSION  
COMPLETE SET (52) SHEETS**

ITEMS CORRESPONDING TO SCHEDULE B:

- 9 Rights and easements in favor of the United States of America relating to electric power transmission lines...
10 Rights and easements granted to Public Service Company of New Hampshire by instrument recorded at Book 1350, Page 166...
11 Right of way granted by Show's Realty Co. to Gilbert E. and Dorothy Soucy dated July 30, 1992...
12 Rights and easements granted to New England Telephone and Telegraph Company dated April 12, 1957...
13 Rights, easements, terms and obligations set forth in the Agreement between Gilbert E. Soucy and Dorothy Soucy...
14 Rights and easements granted to Gilbert E. and Dorothy Soucy for vehicular and pedestrian ingress and egress...
15 Rights and easements to lay, construct, operate, inspect, repair, maintain, renew, replace and remove underground sanitary sewer mains...
16 Rights and easements granted by Costco Wholesale Corporation to Saturn Realty LLC by Access Easement dated June 9, 1994...
17 Rights and easements for ingress and egress as more fully described in the Access Easement from Costco Wholesale Corporation to Robert D. Haverly and Kathleen M. Haverly...
18 Use limitations and general maintenance obligations as more fully set forth in the Real Estate Operation Agreement between the Trustees of SFL Realty Trust and Costco Wholesale Corporation...
19 Rights and easements for access and utilities as described in the Easement Deed from Costco Wholesale Corporation to Gilbert E. Soucy and Dorothy Soucy...
20 Rights and easement for utilities in the Utility Easement Deed from Costco Wholesale Corporation to Gilbert E. Soucy and Dorothy Soucy...
21 Rights and easements in favor of the City of Portsmouth as described in the Access Easement Deed from Costco Wholesale Corporation dated June 12, 1996...
22 Rights and easements granted by Costco Wholesale Corporation to Gilbert E. Soucy and Dorothy Soucy as more fully described in the Slope and Landscape Easement Deed...
23 Rights and easements in favor of Gilbert E. Soucy and Dorothy Soucy as set forth in the Drainage Easement Deed from Costco Wholesale Corporation dated June 12, 1996...
24 Rights and easements for ingress and egress as more fully described in the Access Easement granted by SFL, LLC to Gilbert Soucy and Dorothy Soucy...

ITEMS CORRESPONDING TO SCHEDULE B:

- 25 Terms and provisions set forth in the Conservation Easement from SFL, LLC to the City of Portsmouth dated November 21, 1996...
26 Terms and conditions of the Operation and Maintenance Agreement between SFL, LLC and Daring [sic] Lane Hotel Corp. dated as of June 21, 1998...
27 Rights and easements for access, parking, utilities and signage as more fully described in the Access, Parking Signage and Utility Easement granted by Robert D. Haverly and Kathleen M. Haverly...
28 Rights and easements for access, parking, utilities and signage as more fully described in the instrument granted by Saturn Realty LLC to Robert D. Haverly and Kathleen M. Haverly...
29 Terms and conditions set forth in the Mutual Access Easement between Home Depot U.S.A., Inc. and Thomas J. Flaherty...
30 Rights and easements set forth in the Grant of Right-of-Way from Durgin Square Limited Partnership to Louis L. Dow, Sr. et al...
31 Such state of facts and matters as shown on ALTA/NSPS Land Title Survey prepared by CDS Commercial Due Diligence Services bearing Field Date November 18, 2019...
(c) encroachment of headwall extending 9.9+/- feet onto the Land;
(d) parking spaces and pavement located within easements described herein...
(e) landscaping, berms and medians traversing the boundary lines of the Land;
(f) City of Portsmouth site restrictions, building setbacks, and parking requirements;
(g) catch basins and drain manholes;
(h) water shut-offs and hydrants;
(i) sewer manholes;
(j) electric and gas meters; and
(k) signage.
32 Rights, easements and obligations pertaining to ingress and egress as more fully described in the Access Easement Agreement between Home Depot U.S.A., Inc. and OCV Retail-Portsmouth, LLC...
33 Covenants and restrictions set forth in the Declaration of Use Restriction between Bed Bath & Beyond, Inc. and Home Depot U.S.A., Inc...
34 Rights and easements relating to signage as more fully described in the Directional Signage Easement between Home Depot U.S.A., Inc., OCV Retail-Portsmouth, LLC and Bed Bath & Beyond, Inc...
35 Such state of facts and matters as shown on the plan entitled "Easement Plan Hampton Inn, Tax Map 239 Lots 15 & 18, Property of MIC PNH, LLC & Bed Bath & Beyond, Inc..."

TITLE INFORMATION:

THE TITLE DESCRIPTION AND SCHEDULE B ITEMS HEREON ARE FROM FIRST AMERICAN TITLE INSURANCE COMPANY COMMITMENT NO. OAK ST INVEST DURGIN LANE WITH AN EFFECTIVE DATE OF NOVEMBER 9, 2023 AT 12:00 PM.

BASIS OF BEARINGS:

BEARINGS BASED ON PLAN D-35346 AND SHOWN ON PLAN AS N 59° 39' 24" E.

FLOOD NOTE:

Said described property is located within an area having a Zone Designation X by the Federal Emergency Management Agency (FEMA), on Flood Insurance Rate Map No. 33015C0260E, with a date of identification of May 17, 2005, for Community Panel No. 0260, in Rockingham County, State of New Hampshire, which is the current Flood Insurance Rate Map for the community in which said property is situated.

Zone "X" Denotes Areas of minimal flood hazard (No Shading)
The subject property is NOT in a Special Flood Hazard Area

PARKING INFORMATION:

618 REGULAR SPACES
18 HANDICAPPED ACCESSIBLE SPACES
632 TOTAL PARKING SPACES

NOTES:

- 1. THE OWNER OF RECORD IS OAK STREET INVESTMENT GRADE NET LEASE FUND SERIES 2021-2 LLC, 30 N. LA SALLE ST. SUITE 4140, CHICAGO, IL 60602.
2. REFERENCE THE SUBJECT PROPERTIES AS TAX MAP 239 LOTS 16, 18, AND 13-2, PER THE CITY OF PORTSMOUTH, NH ASSESSORS MAPS.
3. DEED REFERENCE FOR THE SUBJECT PARCEL IS BOOK 6370, PAGE 340, AS RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS.
4. TOTAL AREA OF SUBJECT PARCEL IS 1,138,161 SQUARE FEET, OR 25.15 ACRES.
5. TABLE A ITEM 16- THERE IS NO OBSERVABLE EVIDENCE OF EARTH MOVING WORK, BUILDING CONSTRUCTION OR BUILDING ADDITIONS WITHIN RECENT MONTHS.
6. THE ACCOMPANYING SURVEY WAS MADE ON THE GROUND AND CORRECTLY SHOWS THE LOCATION OF ALL BUILDINGS, STRUCTURES AND OTHER IMPROVEMENTS SITUATED ON THE ABOVE PREMISES; THERE ARE NO VISIBLE ENCROACHMENTS ON THE SUBJECT PROPERTY OR UPON ADJACENT LAND ABUTTING SAID PROPERTY EXCEPT AS SHOWN HEREON AND WAS MADE IN ACCORDANCE WITH LAWS AND/ OR MINIMUM STANDARDS OF THE STATE OF NEW HAMPSHIRE.
7. THE PROPERTY HAS DIRECT ACCESS TO DURGIN LANE A PUBLIC WAY AND INDIRECT ACCESS TO GOSLING ROAD A PUBLIC WAY.
8. THE INTERNAL CONTIGUITY OF THE SUBJECT PROPERTY HAS NO OVERLAPS, GAPS, OR GORES.
9. THE PROPERTY DESCRIBED HEREON HAS THE STREET ADDRESS AS FOLLOWS: 100 DURGIN LANE, PORTSMOUTH, NH
10. SAID PREMISES IS A SEPARATELY SUBDIVIDED TRACT.
11. ANY OFFSITE EASEMENTS OR SERVITUDES BENEFITTING THE SURVEYED PROPERTY AND DISCLOSED IN RECORD DOCUMENTS ARE DEPICTED HEREON.
12. "ALL STATEMENTS WITHIN THE CERTIFICATION, AND OTHER REFERENCES LOCATED ELSEWHERE HEREON, RELATED TO: UTILITIES, IMPROVEMENTS, STRUCTURES, BUILDINGS, PARTY WALLS, PARKING, EASEMENTS SERVITUDES, AND ENCROACHMENTS ARE BASED SOLELY ON ABOVE GROUND, VISIBLE EVIDENCE, UNLESS ANOTHER SOURCE OF INFORMATION IS SPECIFICALLY REFERENCED HEREON" IS NOT NOTED.
13. THE SUBJECT PROPERTY DOES NOT FALL WITHIN A WETLANDS AREA.
14. THERE WERE NO PARTY WALLS OBSERVED AT THE TIME OF SURVEY.
15. THERE IS NO VISIBLE EVIDENCE OF A CEMETERY ON THE SUBJECT PROPERTY AT THE TIME OF THE SURVEY.
16. HORIZONTAL DIMENSIONS ARE BASED ON THE 1983 NORTH AMERICAN DATUM (NAD 83) AND ELEVATIONS ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88).

STATEMENT OF ENCROACHMENTS

(X) HEADWALL EXTENDS ONTO SUBJECT PROPERTY 9.9' +/-

SURVEYOR'S CERTIFICATE:

To: Stebbins, Lazoos & Van Der Beken PLLC; First American Title Insurance Company; and 100 Durgin Lane Owner LLC.

This is to certify that this map or plot and the survey on which it is based were made in accordance with the 2021 Minimum Standard Detail Requirements for ALTA/NSPS Land Title Surveys, jointly established and adopted by ALTA and NSPS, and includes items 1, 2, 3, 4, 6(a), 6(b), 7(c), 7(b)(1), 7(c), 8, 9, 13, 14, 16, and 21(a) (Graphically depict in relation to the subject tract or property any offsite easements or servitudes benefitting the surveyed property and disclosed in Record Documents provided to the surveyor as part of the Schedule "A") of Table A thereof.

The field work was completed on August, 22, 2023



ZONING INFORMATION:

ZONING INFORMATION TAKEN FROM THE REPORT PREPARED BY THE PLANNING & ZONING RESOURCE COMPANY, PZR SITE NUMBER 167869-1, DATED SEPTEMBER 12, 2023.

ZONE IS "G1" GATEWAY NEIGHBORHOOD MIXED USE CORRIDOR

SITE RESTRICTIONS:
MINIMUM LOT SIZE = NOT SPECIFIED
MINIMUM LOT FRONTAGE = 100 FEET
MINIMUM LOT WIDTH = NOT SPECIFIED
MINIMUM LOT DEPTH = NOT SPECIFIED
MAXIMUM BUILDING HEIGHT = 4 STOREYS/50 FEET
MAXIMUM LOT COVERAGE = 70%

SETBACKS:
FRONT = 0 FEET MINIMUM/ 50 FEET MAXIMUM
SIDE = 15 FEET
REAR = 15 FEET

PARKING:
ALL RETAIL TRADE USES: 1 SPACE PER 300 SQ. FT. OF GROSS FLOOR AREA (78,317 / 300 = 261) 261 TOTAL PARKING SPACES REQUIRED.

THE CURRENT USE IS PERMITTED IN THIS DISTRICT.

THE ABOVE RESTRICTIONS WERE OBTAINED FROM THE TOWN OF PORTSMOUTH, NH ZONING CODE

WETLAND NOTES:

The delineation work was performed on November 11, 2023 by Brendan Quigley, CWS #249 utilizing the following standards:

- 1. Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region, (Version 2.0) January 2012, U.S. Army Corps of Engineers.
2. Field Indicators of Hydric Soils in the United States, A Guide for Identifying and Delineating Hydric Soils, Version 8.2. United States Department of Agriculture (2018).
3. New England Hydric Soils Technical Committee, 2019 Version 4, Field Indicators for Identifying Hydric Soils in New England. New England Interstate Water Pollution Control Commission, Lowell, MA.
4. U.S. Army Corps of Engineers National Wetland Plant List, version 3.5. (2020)


HOLDEN ENGINEERING & SURVEYING, inc.
56 Old Suncook Road
PO Box 480 Concord, NH 03302
(603) 225-6449
9 Constitution Drive
Bedford, NH 03110
(603) 472-2078

ALTA / NSPS LAND TITLE SURVEY PREPARED FOR
100 DURGIN LANE OWNER LLC
100 DURGIN LANE, PORTSMOUTH, ROCKINGHAM COUNTY, NEW HAMPSHIRE


Table with 5 columns: Date, Revisions Description, Dr. By, Chk. By, Book, Page. Contains revision history for the survey.

Date: 08-10-23
Scale: NONE
Dr. By: DS Ck By: LR
Job No. 2320547
Sheet no 1 of 8







- LEGEND:**
- ABUTTING PROPERTY LINE
  - TREELINE
  - UNDERGROUND ELECTRIC (Point)
  - SEWER LINE (Point)
  - 10 FOOT CONTOUR
  - 2 FOOT CONTOUR
  - CURBING
  - EDGE OF PAVEMENT
  - FENCE
  - GUARDRAIL
  - PROPERTY LINE
  - FORMER LOT LINE
  - BUILDING SETBACK LINE
  - OVERHEAD UTILITY LINES
  - EASEMENT
  - STONEMALL
  - FLAGGED WETLAND
  - SWALE
  - GAS LINE (Point)
  - CONCRETE
  - CATCH BASIN
  - DRAIN MANHOLE
  - ELECTRIC BOX
  - LIGHT POLE
  - REBAR OR RAILROAD SPIKE
  - DRILL HOLE
  - POST
  - SIGN
  - SEWER MANHOLE
  - UTILITY POLE OR BRACE POLE
  - WATER SHUT-OFF
  - HYDRANT
  - ELECTRIC METER
  - GAS METER
  - FLAG POLE
  - GAS SHUT-OFF
  - BORING
  - WETLAND FLAG LOCATION
  - BOLLARD
  - TREE



I HEREBY CERTIFY THAT THIS PLAN IS BASED ON AN ACTUAL FIELD SURVEY AND HAS A MAX. ERROR OF CLOSURE OF 1:10,000 ON ALL PROPERTY LINES WITHIN AND BORDERING THE SUBJECT PROPERTY.




**HOLDEN ENGINEERING & SURVEYING, inc.**

56 Old Suncook Road  
PO Box 480 Concord, NH 03302  
(603) 225-6449

9 Constitution Drive  
Bedford, NH 03110  
(603) 472-2078

TOPOGRAPHIC SURVEY PREPARED FOR  
**100 DURGAN LANE OWNER LLC**  
100 DURGIN LANE, PORTSMOUTH, ROCKINGHAM COUNTY, NEW HAMPSHIRE



| Date:    | Revisions Description       | Dr. By | Chk. By | Book | Page | Date:                |
|----------|-----------------------------|--------|---------|------|------|----------------------|
| 11-10-23 | REVISED PER CLIENT COMMENTS | DS     | LR      |      |      | 08-10-23             |
| 02-13-24 | MINOR UTILITY EDITS         | DS     | PH      |      |      | Scale: 1"=40'        |
| 02-29-24 | REVISE UTILITIES            | DS     | LR      |      |      | Dr. By: DS Ck By: LR |
|          |                             |        |         |      |      | Job No. 2320547      |
|          |                             |        |         |      |      | Sheet no 6 of 8      |



**LEGEND:**

- ABUTTING PROPERTY LINE
- TREELINE
- UNDERGROUND ELECTRIC (Point)
- SEWER LINE (Point)
- 10 FOOT CONTOUR
- 2 FOOT CONTOUR
- CURBING
- EDGE OF PAVEMENT
- FENCE
- GUARDRAIL
- PROPERTY LINE
- FORMER LOT LINE
- BUILDING SETBACK LINE
- OVERHEAD UTILITY LINES
- EASEMENT
- STONEMALL
- FLAGGED WETLAND
- SWALE
- GAS LINE (Point)
- CONCRETE
- CATCH BASIN
- DRAIN MANHOLE
- ELECTRIC BOX
- LIGHT POLE
- REDBAR OR RAILROAD SPIKE
- DRILL HOLE
- POST
- SIGN
- SEWER MANHOLE
- UTILITY POLE OR BRACE POLE
- WATER SHUT-OFF
- HYDRANT
- ELECTRIC METER
- GAS METER
- FLAG POLE
- GAS SHUT-OFF
- BORING
- WETLAND FLAG LOCATION
- BOLLARD
- TREE


I HEREBY CERTIFY THAT THIS PLAN IS BASED ON AN ACTUAL FIELD SURVEY AND HAS A MAX. ERROR OF CLOSURE OF 1:10,000 ON ALL PROPERTY LINES WITHIN AND BORDERING THE SUBJECT PROPERTY.



**HOLDEN ENGINEERING & SURVEYING, inc.**  
 56 Old Suncook Road  
 PO Box 480 Concord, NH 03302  
 (603) 225-6449  
 9 Constitution Drive  
 Bedford, NH 03110  
 (603) 472-2078


TOPOGRAPHIC SURVEY PREPARED FOR  
**100 DURGAN LANE OWNER LLC**  
 100 DURGAN LANE, PORTSMOUTH, ROCKINGHAM COUNTY, NEW HAMPSHIRE

| Date:    | Revisions                   | Dr. | Chk. | Book | Page | Date:                |
|----------|-----------------------------|-----|------|------|------|----------------------|
|          | Description                 | By  | By   |      |      |                      |
| 11-10-23 | REVISED PER CLIENT COMMENTS | DS  | LR   |      |      | 08-10-23             |
| 02-13-24 | MINOR UTILITY EDITS         | DS  | PH   |      |      | Scale: 1"=40'        |
| 02-29-24 | REVISE UTILITIES            | DS  | LR   |      |      | Dr. By: DS Ck By: LR |
|          |                             |     |      |      |      | Job No. 2320547      |
|          |                             |     |      |      |      | Sheet no 6 of 8      |





**LEGEND:**

- ABUTTING PROPERTY LINE
- TREELINE
- UNDERGROUND ELECTRIC (Point)
- SEWER LINE (Point)
- 10 FOOT CONTOUR
- 2 FOOT CONTOUR
- CURBING
- EDGE OF PAVEMENT
- FENCE
- GUARDRAIL
- PROPERTY LINE
- FORMER LOT LINE
- BUILDING SETBACK LINE
- OVERHEAD UTILITY LINES
- EASEMENT
- STONEMALL
- FLAGGED WETLAND
- SWALE
- GAS LINE (Point)
- CONCRETE
- CATCH BASIN
- DRAIN MANHOLE
- ELECTRIC BOX
- LIGHT POLE
- REDBAR OR RAILROAD SPIKE
- DRILL HOLE
- POST
- SIGN
- SEWER MANHOLE
- UTILITY POLE OR BRACE POLE
- WATER SHUT-OFF
- HYDRANT
- ELECTRIC METER
- GAS METER
- FLAG POLE
- GAS SHUT-OFF
- BORING
- WETLAND FLAG LOCATION
- BOLLARD
- TREE



I HEREBY CERTIFY THAT THIS PLAN IS BASED ON AN ACTUAL FIELD SURVEY AND HAS A MAX. ERROR OF CLOSURE OF 1:10,000 ON ALL PROPERTY LINES WITHIN AND BORDERING THE SUBJECT PROPERTY.



**HOLDEN ENGINEERING & SURVEYING, inc.**




56 Old Suncook Road  
PO Box 480 Concord, NH 03302  
(603) 225-6449

9 Constitution Drive  
Bedford, NH 03110  
(603) 472-2078

TOPOGRAPHIC SURVEY PREPARED FOR  
**100 DURGIN LANE OWNER LLC**  
100 DURGIN LANE, PORTSMOUTH, ROCKINGHAM COUNTY, NEW HAMPSHIRE

| Date:    | Revisions                   | Dr. | Chk. | Book | Page | Date:                |
|----------|-----------------------------|-----|------|------|------|----------------------|
|          | Description                 | By  | By   |      |      |                      |
| 11-10-23 | REVISED PER CLIENT COMMENTS | DS  | LR   |      |      | 08-10-23             |
| 02-13-24 | MINOR UTILITY EDITS         | DS  | PH   |      |      | Scale: 1"=40'        |
| 02-29-24 | REVISE UTILITIES            | DS  | LR   |      |      | Dr. By: DS Ck By: LR |
|          |                             |     |      |      |      | Job No. 2320547      |
|          |                             |     |      |      |      | Sheet no 6 of 8      |





**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN  
LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE




| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| F    | 11/27/2024 | PB SUBMISSION  |
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

|                      |                               |
|----------------------|-------------------------------|
| PROJECT NO:          | E5071-001                     |
| DATE:                | 4/22/2024                     |
| FILE:                | E5071-001-C-DSGN_unlocked.dwg |
| DRAWN BY:            | BKC/NHW                       |
| DESIGNED/CHECKED BY: | NAH                           |
| APPROVED BY:         | PMC                           |

**DEMOLITION PLAN**

SCALE: AS SHOWN

Last Saved: 11/21/2024 3:13pm By: BCircud  
 Plotted On: Nov 22, 2024 3:13pm  
 Tighe & Bond \\\globe.com\data\proj\100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN\_unlocked.dwg



**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| F    | 11/27/2024 | PB SUBMISSION  |
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

PROJECT NO: E5071-001  
 DATE: 4/22/2024  
 FILE: E5071-001-C-DSGN\_unlocked.dwg  
 DRAWN BY: BKC/NHW  
 DESIGNED/CHECKED BY: NAH  
 APPROVED BY: PMC


DEMOLITION PLAN



SCALE: AS SHOWN

C-202

Last Saved: 11/21/2024 3:25pm By: BCurcio  
 Plotted On: Nov 22, 2024 3:25pm  
 Tighe & Bond \\\\na01-tighebond.com\data\proj\100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN\_unlocked.dwg

SEE SHEET C-101 FOR DEMOLITION PLAN NOTES & LEGEND





**SITE DATA:**  
 LOCATION: TAX MAP 239, LOT 13-2, MAP 239 LOT 16, MAP 239 LOT 18  
 OWNER: 100 DURGIN LANE OWNER LLC  
 ONE MARINA PARK DRIVE, SUITE 1500  
 BOSTON, MA 02210

ZONING DISTRICT: GATEWAY NEIGHBORHOOD MIXED USE CORRIDOR (G1)  
 HIGHWAY NOISE OVERLAY DISTRICT

PROPOSED USE: MULTI-FAMILY RESIDENTIAL DEVELOPMENT  
 EXISTING LOT SIZE: ±1,139,161 SF / 26.15 ACRES (MAP 239 LOT 13-2, LOT 16, LOT 18)

**DEVELOPMENT STANDARDS**

| GENERAL RESIDENTIAL DEVELOPMENT (10.5B42.30) | REQUIRED  | PROPOSED      |
|--|-----------|---------------|
| MINIMUM SITE DEVELOPMENT AREA:               | 10,000 SF | ±1,139,161 SF |
| MINIMUM SITE WIDTH:                          | 75 FT     | >75 FT        |
| MINIMUM SITE LENGTH:                         | 100 FT    | >100 FT       |
| MINIMUM PERIMETER BUFFER:                    | N/A       | -             |
| MAXIMUM DEVELOPMENT BLOCK DIMS:              |           |               |
| BLOCK LENGTH:                                | 500 FT    | 442 FT        |
| BLOCK PERIMETER:                             | 1,500 FT  | 1,266 FT      |
| MAXIMUM BUILDING COVERAGE:                   | 50%       | 8.8%          |
| MINIMUM OPEN SPACE COVERAGE:                 | 20%       | 63.4%         |

| APARTMENT BUILDING (10.5B34.40)                  | REQUIRED           | PROPOSED                |
|--|--------------------|-------------------------|
| MINIMUM LOT DEPTH:                               | NR                 | -                       |
| MINIMUM STREET FRONTAGE:                         | 50 FT              | 200.6 FT                |
| FRONT YARD SETBACK:                              | 10-30 FT           | 239.6 FT <sup>(1)</sup> |
| MIN. SIDE YARD SETBACK:                          | 15 FT              | 26.3 FT                 |
| MIN. REAR YARD SETBACK:                          | 20 FT              | 84.3 FT                 |
| DWELLING UNITS PER BUILDING:                     | 4-24               | VARIES (24 MAX.)        |
| MAXIMUM DWELLING UNIT SIZE:                      | NR                 | -                       |
| MAXIMUM BUILDING HEIGHT:                         | 4 STORIES OR 50 FT | <50 FT                  |
| MINIMUM STREET-FACING FACADE HEIGHT:             | 24 FT              | >24 FT                  |
| MAX. FINISH FLOOR ABOVE SIDEWALK:                | 36"                | VARIES                  |
| MAXIMUM BUILDING COVERAGE:                       | 50%                | 8.1%                    |
| MAXIMUM BUILDING FOOTPRINT:                      | NR                 | -                       |
| MAXIMUM FACADE MODULATION LENGTH:                | 50 FT              | <50 FT                  |
| MINIMUM STREET FACING FACADE GLAZING:            | 20% GROUND FLOOR   | >20%                    |
| MAXIMUM STREET FACING ENTRANCE SPACING:          | NR                 | -                       |
| ALLOWED ROOF TYPES:                              | ALL                | FLAT                    |
| ALLOWED FACADE TYPES:                            |                    |                         |
| FORECOURT, RECESSED ENTRY, DOORYARD, STEP, PORCH |                    | FORECOURT, RECESSED     |

| MIXED-USE BUILDING (10.5B34.80)  | REQUIRED           | PROPOSED                |
|--|--------------------|-------------------------|
| MINIMUM LOT DEPTH:   | NR                 | -                       |
| MINIMUM STREET FRONTAGE:   | 50 FT              | 200.6 FT                |
| FRONT YARD SETBACK:  | 0-50 FT            | 268.1 FT <sup>(1)</sup> |
| MIN. SIDE YARD SETBACK:  | 15 FT              | 242.0 FT                |
| MIN. REAR YARD SETBACK:  | 20 FT              | 453.0 FT                |
| MAXIMUM DWELLING UNITS PER BUILDING:   | 24                 | VARIES (24 MAX.)        |
| MAXIMUM DWELLING UNIT SIZE:  | NR                 | -                       |
| MAXIMUM BUILDING HEIGHT:   | 4 STORIES OR 50 FT | <50 FT                  |
| MINIMUM STREET-FACING FACADE HEIGHT:   | 18 FT              | 47.5 FT                 |
| MAX. FINISH FLOOR ABOVE SIDEWALK:  | 24"                | VARIES                  |
| MAXIMUM BUILDING COVERAGE:   | 60%                | <1%                     |
| MAXIMUM BUILDING FOOTPRINT:  | 20,000 SF          | 7,370 SF                |
| MAXIMUM FACADE MODULATION LENGTH:  | 100 FT             | <100 FT                 |
| MINIMUM STREET FACING FACADE GLAZING:  | 50% GROUND FLOOR   | >50%                    |
| MAXIMUM STREET FACING ENTRANCE SPACING:  | NR                 | -                       |
| ALLOWED ROOF TYPES:  | ALL                | FLAT                    |
| ALLOWED FACADE TYPES:  |                    |                         |
| FORECOURT, RECESSED ENTRY, PORCH, OFFICEFRONT, SHOPFRONT, TERRACE, GALLERY, ARCADE |                    | FORECOURT, RECESSED     |

(1) - THE APPLICANT IS REQUESTING THE PLANNING BOARD TO ALLOW AN INCREASE OF BUILDING SETBACK FROM THE FRONT LOT LINE AS ALLOWED BY SECTION 10.5B41.60.

| COMMUNITY SPACE: | REQUIRED   | PROPOSED   |
|------------------|------------|------------|
|                  | 10%        | 10.6%      |
|                  | 113,916 SF | 120,793 SF |

**PARKING REQUIREMENTS**

|   |                        |            |
|---|------------------------|------------|
| RESIDENTIAL UNITS (<750 SF)             | 209 UNITS X 1.0 SPACES | 209 SPACES |
| RESIDENTIAL UNITS (>750 SF)             | 151 UNITS X 1.3 SPACES | 197 SPACES |
| VISITOR SPACES                          | 1 SPACE / 5 UNITS      | 82 SPACES  |
| TOTAL MINIMUM PARKING SPACES REQUIRED = |                        | 488 SPACES |

| PARKING SPACES | REQUIRED   | PROPOSED   |
|----------------|------------|------------|
|                | 488 SPACES | 573 SPACES |

| ADA PARKING SPACES | REQUIRED <sup>(2)</sup> | PROPOSED  |
|--------------------|-------------------------|-----------|
|                    | 12 SPACES               | 14 SPACES |

(2) - PER THE AMERICANS WITH DISABILITIES ACT (ADA) STANDARDS, LATEST EDITION.




| PARKING SPACE DIMENSIONAL REQUIREMENTS: | REQUIRED   | PROPOSED |
|---|------------|----------|
| STANDARD 90° STALL:                     |            |          |
| WIDTH                                   | 8.5 FT MIN | 8.5 FT   |
| LENGTH                                  | 19 FT MIN  | 19 FT    |
| STANDARD 0° STALL:                      |            |          |
| WIDTH                                   | 8.5 FT MIN | 8.5 FT   |
| LENGTH                                  | 20 FT MIN  | 20 FT    |
| DRIVE AISLE WIDTH:                      |            |          |
| 90° (2-WAY TRAFFIC)                     | 24 FT      | 24 FT    |
| 0° (2-WAY TRAFFIC)                      | 24 FT      | 24 FT    |

| BICYCLE SPACES   | REQUIRED         | PROPOSED   |
|--|------------------|------------|
| 1 BICYCLE SPACE / 10 PARKING SPACES:                                   | 30 SPACES (MAX.) | >30 SPACES |
| (INDOOR BIKE STORAGE WILL BE PROVIDED THAT MEETS OR EXCEEDS REQUIRED.) |                  |            |
| (ADDITIONAL EXTERIOR BIKE RACKS ARE PROPOSED.)                         |                  |            |

LOT LINE REVISIONS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY. FINAL LOT LINE REVISION PLAN SHALL BE PREPARED BY THE PROJECT SURVEYOR AND RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS PRIOR TO ISSUING BUILDING PERMITS.

- SITE RECORDING NOTES:**
- THIS SITE PLAN SHALL BE RECORDED IN THE ROCKINGHAM COUNTY REGISTRY OF DEEDS.
  - ALL IMPROVEMENTS SHOWN ON THIS SITE PLAN SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES SHALL BE MADE TO THIS SITE PLAN WITHOUT THE EXPRESS APPROVAL OF THE PORTSMOUTH PLANNING DIRECTOR.
  - ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.
  - THIS IS NOT A BOUNDARY SURVEY AND SHALL NOT BE USED AS SUCH.

SEE SHEET C-101 FOR SITE PLAN NOTES & LEGEND



**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE


| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| F    | 11/27/2024 | PB SUBMISSION  |
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

|                      |                               |
|----------------------|-------------------------------|
| PROJECT NO:          | E5071-001                     |
| DATE:                | 4/22/2024                     |
| FILE:                | E5071-001-C-DSGN_unlocked.dwg |
| DRAWN BY:            | BKC/NHW                       |
| DESIGNED/CHECKED BY: | NAH                           |
| APPROVED BY:         | PMC                           |

OVERALL SITE PLAN

SCALE: AS SHOWN

C-300



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE



| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| F    | 11/27/2024 | PB SUBMISSION  |
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

|                      |                               |
|----------------------|-------------------------------|
| PROJECT NO:          | E5071-001                     |
| DATE:                | 4/22/2024                     |
| FILE:                | E5071-001-C-DSGN_unlocked.dwg |
| DRAWN BY:            | BKC/NHW                       |
| DESIGNED/CHECKED BY: | NAH                           |
| APPROVED BY:         | PMC                           |

SITE PLAN

SCALE: AS SHOWN




C-301



SEE SHEET C-101 FOR SITE PLAN NOTES & LEGEND

Last Saved: 11/21/2024 3:30pm By: BCurcio  
 Plotted On: Nov 22, 2024 10:00am  
 Tighe & Bond \\lgn\shared\dwg\proj\100 Durgin Lane\100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN\_unlocked.dwg





**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

**100 DURGIN LANE OWNER, LLC**

**100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE**

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| F    | 11/27/2024 | PB SUBMISSION  |
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |


|                      |                               |
|----------------------|-------------------------------|
| PROJECT NO:          | E5071-001                     |
| DATE:                | 4/22/2024                     |
| FILE:                | E5071-001-C-DSGN_unlocked.dwg |
| DRAWN BY:            | BKC/NHW                       |
| DESIGNED/CHECKED BY: | NAH                           |
| APPROVED BY:         | PMC                           |

**SITE PLAN**

SCALE: AS SHOWN

**C-302**

Last Saved: 11/21/2024 3:32pm By: BCurcio  
 Plotted On: Nov 22, 2024 3:32pm  
 Tighe & Bond \Vigilant\com\data\proj\100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN\_unlocked.dwg



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |



GRADING, DRAINAGE, AND EROSION CONTROL PLAN

SCALE: AS SHOWN


| STRUCTURE | RIM   | INV. IN              | INV. OUT |
|-----------|-------|----------------------|----------|
| PCB1      | 64.60 | 60.00 SW<br>60.00 NE | 60.00 SE |
| PCB2      | 64.00 | 60.30 NW             | 60.30 SW |
| PCB3      | 64.00 |                      | 60.55 SE |
| PCB4      | 64.60 | 60.10 NW             | 60.10 NE |
| PCB5      | 64.80 | 60.50 SW             | 60.50 SE |
| PCB6      | 64.75 | 61.00 SW             | 61.00 NE |
| PCB7      | 64.75 | 61.30 SW             | 61.30 NE |
| PCB8      | 65.35 | 61.65 N              | 61.65 NE |
| PCB9      | 65.25 |                      | 62.00 S  |
| PCB10     | 64.65 | 60.15 NE             | 60.05 NW |
| PCB11     | 64.65 |                      | 60.30 SW |
| PCB12     | 65.25 | 60.35 SE             | 60.25 NW |
| PCB13     | 65.75 | 60.60 SE             | 60.50 NW |
| PCB14     | 66.95 | 61.15 SE<br>61.60 NE | 61.05 NW |
| PCB15     | 67.00 | 61.80 SE<br>61.60 NE | 61.70 NW |
| PCB16     | 66.50 | 62.60 SE             | 62.60 SW |
| PCB17     | 66.50 | 62.95 SE             | 62.95 NW |
| PCB18     | 66.50 |                      | 63.05 NW |
| PCB19     | 65.25 |                      | 61.00 NW |
| PCB20     | 65.00 |                      | 61.50 NE |
| PCB21     | 64.50 |                      | 59.35 SE |
| PCB22     | 64.50 |                      | 59.35 NE |
| PCB23     | 65.00 | 60.20 SE             | 60.10 N  |
| PCB24     | 65.00 |                      | 60.35 NW |
| PCB25     | 64.70 | 60.95 SE             | 60.85 N  |
| PCB26     | 64.80 |                      | 61.10 NW |
| PCB27     | 66.70 | 62.05 SE<br>61.90 N  | 61.90 SW |
| PCB28     | 66.50 | 62.10 NE             | 62.10 S  |
| PCB29     | 66.00 | 62.75 SE             | 62.65 SW |
| PCB30     | 67.15 | 62.35 SE             | 62.35 NW |
| PCB31     | 67.00 | 62.70 SE<br>62.70 NE | 62.70 NW |
| PCB32     | 66.90 | 63.10 SE             | 63.10 NW |
| PCB33     | 66.75 | 63.30 NE             | 63.20 NW |
| PCB34     | 57.75 |                      | 53.85 SW |
| PCB35     | 61.00 | 55.25 NE             | 55.15 SW |
| PCB35A    | 62.75 |                      | 57.50 NE |
| PCB36     | 59.50 | 55.85 SE             | 55.75 SW |
| PCB37     | 61.00 |                      | 56.25 NW |
| PCB38     | 62.90 | 57.00 SE<br>58.00 SW | 56.90 NW |
| PCB39     | 64.90 | 57.35 SE<br>57.35 W  | 57.25 NE |
| PCB40     | 65.00 | 58.20 SE<br>60.00 NE | 58.10 NW |
| PCB41     | 65.50 | 61.25 NE<br>58.75 SE | 58.65 NW |
| PCB42     | 65.60 | 60.65 SW             | 59.35 NW |
| PCB43     | 65.60 | 60.85 SW             | 60.85 NE |
| PCB44     | 65.20 | 61.25 SW             | 61.25 NE |
| PCB45     | 65.50 | 62.00 NE             | 62.00 N  |

| STRUCTURE | RIM   | INV. IN                          | INV. OUT             |
|-----------|-------|----------------------------------|----------------------|
| PCB46     | 65.00 | 57.85 SW                         | 57.75 E              |
| PCB47     | 65.00 | 58.35 SE                         | 58.25 NE             |
| PCB48     | 65.85 | 58.80 SE                         | 58.70 NW             |
| PCB49     | 66.00 | 59.35 SE<br>60.50 NE             | 59.25 NW             |
| PCB50     | 65.20 | 59.90 SE                         | 59.80 NW             |
| PCB51     | 65.40 |                                  | 60.65 NW             |
| PCB52     | 63.75 | 59.35 S                          | 59.25 NW             |
| PCDS1     | 66.10 | 58.60 SW                         | 58.50 NW             |
| PCDS2     | 65.50 | 59.30 SW                         | 59.20 SE             |
| PCDS3     | 62.25 | 54.50 E                          | 54.00 NE             |
| PDMH1     | 64.35 | 58.80 NW                         | 58.80 SE             |
| PDMH2     | 65.50 | 59.00 NE<br>60.15 NW             | 58.90 SE             |
| PDMH3     | 65.50 | 59.45 SW<br>59.45 NW             | 59.35 NE<br>60.50 SE |
| PDMH4     | 65.50 | 59.70 SW<br>59.80 SE             | 59.60 NE             |
| PDMH5     | 65.50 | 60.20 SW<br>60.20 SE<br>60.20 NW | 60.10 NE             |
| PDMH6     | 67.50 | 62.20 NE                         | 62.10 NW             |
| PDMH7     | 65.60 | 60.85 SW<br>60.85 NW<br>60.85 SE | 60.75 NE             |
| PDMH8     | 65.75 | 61.10 SW<br>62.20 SE             | 61.00 NE             |
| PDMH9     | 64.00 | 57.85 SE                         |                      |
| PDMH10    | 65.90 | 59.75 SE                         | 58.20 NW             |
| PDMH11    | 66.00 | 58.65 SW                         | 58.65 NE<br>60.00 NW |
| PDMH12    | 64.75 | 59.10 SE<br>59.20 SW<br>59.20 NW | 59.10 NE             |
| PDMH13    | 65.50 | 59.85 SE<br>59.95 NE<br>59.95 S  | 59.85 NW             |
| PDMH14    | 65.20 | 60.60 NE<br>60.60 S<br>60.50 SE  | 60.50 NW             |
| PDMH15    | 66.25 | 61.25 NE<br>61.15 SE             | 61.15 NW             |
| PDMH16    | 67.15 | 61.70 NE                         | 61.70 NW             |
| PDMH17    | 67.75 | 63.00 NW<br>63.00 SE<br>63.00 NE | 62.90 SW             |
| PDMH18    | 67.60 | 63.70 N                          | 63.60 SW             |
| PDMH19    | 62.05 | 53.85 SW<br>55.50 SE             | 53.00 NW             |
| PDMH20    | 62.00 | 55.00 S<br>54.75 NE<br>57.00 SW  | 54.65 W<br>56.00 NW  |
| PDMH21    | 63.50 | 56.70 SW<br>56.70 S              | 56.60 N              |
| PDMH22    | 65.90 | 61.50 S                          | 61.50 NE             |
| PDMH23    | 65.20 | 60.35 SE<br>61.00 NE             | 60.25 NW             |
| PDMH24    | 65.00 | 59.75 SW                         | 59.65 N              |
| PDMH25    | 60.15 | 56.60 E                          | 56.50 NW             |
| PJFF1     | 66.00 | 58.45 SE                         | 58.35 SW             |
| PJFF2     | 65.50 | 59.15 NW                         | 59.05 SW             |
| POCS1     | 54.00 |                                  | 46.50 N              |
| POCS2     | 60.50 |                                  | 54.50 NE             |
| PYD1      | 66.75 |                                  | 63.25 NW             |
| PYD2      | 66.75 |                                  | 63.25 SW             |
| PYD3      | 66.75 |                                  | 63.90 S              |
| PYD4      | 63.90 | 58.20 NE<br>58.20 SE             | 58.10 NW             |
| PYD5      | 64.25 | 58.75 NE                         | 58.65 NW             |
| PYD6      | 63.00 |                                  | 59.25 SW             |

SEE SHEET C-101 FOR GRADING & DRAINAGE PLAN NOTES & LEGEND



Last Saved: 10/21/2024 9:33am By: DCurcio  
 Plotted On: Oct 22, 2024 9:44:33am  
 Tighe & Bond \\\gmead\com\dwg\100 Durgin Lane\Projects\E1E071 - Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane Drawings\AutoCAD\Sheet\E5071-001-C-DSGN.dwg



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

**100 DURGIN  
LANE OWNER,  
LLC**

**100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE**


| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 4/22/2024            |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |


**GRADING, DRAINAGE, AND  
EROSION CONTROL PLAN**

SCALE: AS SHOWN


**C-402**



SEE SHEET C-101 FOR GRADING & DRAINAGE PLAN NOTES & LEGEND



Last Saved: 10/21/2024 9:37am By: DCurcio  
 Plotted On: Oct 22, 2024 9:37am  
 Tighe & Bond \\lgn\shared\dwg\proj\100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN.dwg



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |


  

|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 4/22/2024            |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |



UTILITIES PLAN

SCALE: AS SHOWN



C-501



SEE SHEET C-101 FOR UTILITY  
PLAN NOTES & LEGEND



Last Saved: 10/21/2024 9:43am By: DCurcio  
 Plotted On: Oct 22, 2024 9:43am  
 Tighe & Bond \Information\Drawings\AutoCAD\Projects\E5071-Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN.dwg



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN  
LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE



| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 4/22/2024            |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |

UTILITIES PLAN





SCALE: AS SHOWN

C-502



SEE SHEET C-101 FOR UTILITY PLAN  
NOTES & LEGEND

Last Saved: 10/21/2024 10:49:40am By: DCurcio  
 Plotted On: Oct 22, 2024 2:22:22 PM  
 Tighe & Bond \\lgn\shared\dwg\proj\100 Durgin Lane\Projects\E5071-001-C-DSGN.dwg



EASEMENTS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY. FINAL EASEMENT PLAN SHALL BE PREPARED BY THE PROJECT SURVEYOR AND RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS PRIOR TO ISSUING BUILDING PERMITS.

**LEGEND**

|  |  |
|--|--|
|  | PROPOSED ACCESS EASEMENT TO BENEFIT MAP 239 LOT 13, MAP 239 LOT 13-1, MAP 238 LOT 20, MAP 239 LOT 15 |
|  | PROPOSED RELOCATED ACCESS EASEMENT (TO BENEFIT MAP 239 LOT 15)                                       |
|  | PROPOSED ACCESS EASEMENT (TO BENEFIT THE CITY OF PORTSMOUTH)   |
|  | APPROXIMATE EXISTING ACCESS EASEMENT THROUGH MAP 239 LOT 20  |
|  | APPROXIMATE EXISTING ACCESS EASEMENT THROUGH MAP 239 LOT 13-1  |

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |





PROJECT NO: E5071-001  
 DATE: 4/22/2024  
 FILE: E5071-001-FIGS.dwg  
 DRAWN BY: BKC/NHW  
 DESIGNED/CHECKED BY: NAH  
 APPROVED BY: PMC

**ABUTTERS' ACCESS EASEMENT PLAN**

SCALE: AS SHOWN


**C-600**

Last Saved: 10/21/2024 10:21:21 AM  
 Plotted On: Oct 21, 2024 4:29pm  
 By: DCurcio  
 Tighe & Bond \Vigorena\com\data\proj\100 Durgin Lane\Projects\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg



EASEMENTS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY. FINAL EASEMENT PLAN SHALL BE PREPARED BY THE PROJECT SURVEYOR AND RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS PRIOR TO ISSUING BUILDING PERMITS.

**LEGEND**



PROPOSED TEMPORARY GRADING EASEMENT (TO BENEFIT THE DEVELOPMENT LOT)  
 PROPOSED RELOCATED DRAINAGE & UTILITIES EASEMENT (TO BENEFIT MAP 239 LOT 15)  
 SEWER EASEMENT (TO BENEFIT MAP 239 LOT 13, MAP 239 LOT 13-1)

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC






100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

|                      |                    |
|----------------------|--------------------|
| PROJECT NO:          | E5071-001          |
| DATE:                | 4/22/2024          |
| FILE:                | E5071-001-FIGS.dwg |
| DRAWN BY:            | BKC/NHW            |
| DESIGNED/CHECKED BY: | NAH                |
| APPROVED BY:         | PMC                |

ABUTTERS' UTILITY, DRAINAGE, AND GRADING EASEMENT PLAN

SCALE: AS SHOWN



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN  
LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE

EASEMENTS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY. FINAL EASEMENT PLAN SHALL BE PREPARED BY THE PROJECT SURVEYOR AND RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS PRIOR TO ISSUING BUILDING PERMITS.

**LEGEND**

|  |                           |
|--|---------------------------|
|  | COMMUNITY SPACE EASEMENTS |
|--|---------------------------|

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |





|                      |                    |
|----------------------|--------------------|
| PROJECT NO:          | E5071-001          |
| DATE:                | 4/22/2024          |
| FILE:                | E5071-001-FIGS.dwg |
| DRAWN BY:            | BKC/NHW            |
| DESIGNED/CHECKED BY: | NAH                |
| APPROVED BY:         | PMC                |

**COMMUNITY SPACE  
EASEMENT PLAN**

SCALE: AS SHOWN

Last Saved: 10/21/2024 6:34pm By: DCurcio  
 Plotted On: Oct 21, 2024 6:34pm  
 Tighe & Bond \Vigilante\Projects\E5071 - Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg





**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN  
LANE OWNER,  
LLC


100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| F    | 11/27/2024 | PB SUBMISSION  |
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

|                      |                    |
|----------------------|--------------------|
| PROJECT NO:          | E5071-001          |
| DATE:                | 4/22/2024          |
| FILE:                | E5071-001-FIGS.dwg |
| DRAWN BY:            | BKC/NHW            |
| DESIGNED/CHECKED BY: | NAH                |
| APPROVED BY:         | PMC                |

DEVELOPMENT SITE  
ACCESS, DRAINAGE, &  
UTILITY EASEMENTS


SCALE: AS SHOWN



RECIPROCAL DEVELOPMENT SITE  
ACCESS, DRAINAGE, & UTILITY EASEMENT  
(TO BENEFIT DEVELOPMENT SITE LOTS)

EASEMENTS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY. FINAL  
EASEMENT PLAN SHALL BE PREPARED BY THE PROJECT SURVEYOR AND  
RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS PRIOR TO  
ISSUING BUILDING PERMITS.



**LEGEND**



PROPOSED RECIPROCAL ACCESS, DRAINAGE,  
& UTILITY EASEMENT BETWEEN DEVELOPMENT  
SITE LOTS 1, 2, & 3


Last Saved: 11/20/2024 3:43pm By: BCurcio  
 Plotted On: Nov 22, 2024 3:43pm  
 Tighe & Bond \Vigorena\Drawings\Projects\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg






- NOTES:**
1. EROSION CONTROL BLANKET SHALL BE AN ALL NATURAL PRODUCT WITH NO PHOTO DEGRADABLE COMPONENTS, NORTH AMERICAN GREEN SC150BN OR APPROVED EQUAL.
  2. STAKES SHALL BE BIODEGRADABLE BIOSTAKES OR ALL NATURAL WOOD ECOSTAKES OR APPROVED EQUAL. THE LENGTH OF STAKES SHALL BE BASED OFF OF THE MANUFACTURERS RECOMMENDATION.
  3. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, COMPOST AND SEED.
  4. BEGIN AT THE TOP OF THE SLOPE, 36" OVER THE GRADE BREAK, BY ANCHORING THE BLANKET IN A 6" DEEP X 6" WIDE TRENCH WITH APPROXIMATELY 12" OF BLANKET EXTENDED BEYOND THE UPSLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAKES IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAKING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAKES ACROSS THE WIDTH OF THE BLANKET.
  5. ROLL THE BLANKETS DOWN THE SLOPE. ALL BLANKETS MUST BE SECURELY FASTENED TO THE SOIL SURFACE BY PLACING STAKES IN APPROPRIATE LOCATIONS AS SHOWN ON THE MANUFACTURERS PATTERN GUIDE.
  6. THERE SHALL BE NO PLASTIC, OR MULTI-FILAMENT OR MONOFILAMENT POLYPROPYLENE NETTING OR MESH WITH AN OPENING SIZE OF GREATER THAN 1/8 INCHES MATERIAL UTILIZED.

**EROSION CONTROL BLANKET**  
NO SCALE




- NOTES:**
1. CONTAINMENT MUST BE STRUCTURALLY SOUND AND LEAK FREE AND CONTAIN ALL LIQUID WASTES.
  2. CONTAINMENT DEVICES MUST BE OF SUFFICIENT QUANTITY OR VOLUME TO COMPLETELY CONTAIN THE LIQUID WASTES GENERATED.
  3. WASHOUT MUST BE CLEANED OR NEW FACILITIES CONSTRUCTED AND READY TO USE ONCE WASHOUT IS 75% FULL.
  4. WASHOUT AREA(S) SHALL BE INSTALLED IN A LOCATION EASILY ACCESSIBLE BY CONCRETE TRUCKS.
  5. ONE OR MORE AREAS MAY BE INSTALLED ON THE CONSTRUCTION SITE AND MAY BE RELOCATED AS CONSTRUCTION PROGRESSES.
  6. AT LEAST WEEKLY REMOVE ACCUMULATION OF SAND AND AGGREGATE AND DISPOSE OF PROPERLY.

**CONCRETE WASHOUT AREA**  
NO SCALE



- NOTES:**
1. THE TRAP SHALL BE INSTALLED AS CLOSE TO THE DISTURBED AREA AS POSSIBLE.
  2. THE MAXIMUM CONTRIBUTING AREA TO A SINGLE TRAP SHALL BE LESS THAN 5 ACRES.
  3. THE MINIMUM VOLUME OF THE TRAP SHALL BE 3,600 CUBIC FEET OF STORAGE FOR EACH ACRE OF DRAINAGE AREA.
  4. TRAP OUTLET SHALL BE MINIMUM OF ONE FOOT BELOW THE CREST OF THE TRAP.
  5. TRAP SHALL DISCHARGE TO A STABILIZED AREA.
  6. TRAP SHALL BE CLEANED WHEN 50 PERCENT OF THE ORIGINAL VOLUME IS FILLED.
  7. MATERIALS REMOVED FROM THE TRAP SHALL BE PROPERLY DISPOSED OF AND STABILIZED.
  8. SEDIMENT TRAPS MUST BE USED AS NEEDED TO CONTAIN RUNOFF UNTIL SOILS ARE STABILIZED.


**SEDIMENT TRAP**  
NO SCALE



| CURB RADIUS TABLE |                 |
|-------------------|-----------------|
| RADIUS            | MAX. LENGTH     |
| <20'              | USE CURVED CURB |
| 21'               | 3'              |
| 22'-28'           | 4'              |
| 29'-35'           | 5'              |
| 36'-42'           | 6'              |
| 43'-49'           | 7'              |
| 50'-56'           | 8'              |
| 57'-60'           | 9'              |
| >60'              | 10'             |


- NOTES:**
1. SEE SITE PLAN(S) FOR LIMITS OF VERTICAL GRANITE CURB (VGC).
  2. ADJOINING STONES SHALL HAVE THE SAME OR APPROXIMATELY THE SAME LENGTH.
  3. MINIMUM LENGTH OF STRAIGHT CURB STONES = 3'
  4. MAXIMUM LENGTH OF STRAIGHT CURB STONES = 10'
  5. MAXIMUM LENGTH OF STRAIGHT CURB STONES LAID ON CURVES (SEE TABLE).
  6. ALL RADII 20 FEET AND SMALLER SHALL BE CONSTRUCTED USING CURVED SECTIONS.
  7. JOINTS BETWEEN STONES SHALL HAVE A MAXIMUM SPACING OF 1/2" AND SHALL BE MORTARED.

**VERTICAL GRANITE CURB**  
NO SCALE



- NOTES:**
1. THE INTENT OF THIS ITEM IS TO PROVIDE A SMOOTH TRANSITION BETWEEN VERTICAL GRANITE CURB AND MOUNTABLE VERTICAL GRANITE CURB WITHOUT REQUIRING FIELD CHIPPING DURING INSTALLATION. THE MOUNTABLE VERTICAL GRANITE CURB MAY REQUIRE ADJUSTMENTS TO MEET THE TRANSITION PIECE HEIGHT. TRANSITION SLOPE CURB TO STANDARD REVEAL AS QUICKLY AS POSSIBLE TO PROVIDE FOR THIS SMOOTH TRANSITION.



**CURB TRANSITION**  
NO SCALE



| CURB RADIUS TABLE |                   |
|-------------------|-------------------|
| RADIUS            | MAX LENGTH        |
| <2'               | USE CURVED CURB   |
| 2'-15'            | USE RADIAL JOINTS |
| 16'-28'           | 1'-6"             |
| 29'-41'           | 2'                |
| 42'-55'           | 3'                |
| 56'-68'           | 4'                |
| 69'-82'           | 5'                |
| 83'-96'           | 6'                |
| 97'-110'          | 7'                |
| >110'             | 8'                |


- NOTES:**
1. SEE SITE PLAN(S) FOR LIMITS OF SLOPED GRANITE CURB (SGC).
  2. ADJOINING STONES SHALL HAVE THE SAME OR APPROXIMATELY THE SAME LENGTH.
  3. MINIMUM LENGTH OF STRAIGHT CURB STONES = 18"
  4. MAXIMUM LENGTH OF STRAIGHT CURB STONES = 8'
  5. MAXIMUM LENGTH OF STRAIGHT CURB STONES LAID ON CURVES (SEE TABLE).
  6. JOINTS BETWEEN STONES SHALL HAVE A MAXIMUM SPACING OF 1/2" AND SHALL BE MORTARED.

**SLOPED GRANITE CURB**  
NO SCALE



- NOTES:**
1. RAMPS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE AMERICANS WITH DISABILITIES ACT AND LOCAL AND STATE REQUIREMENTS.
  2. A 6" COMPACTED CRUSHED GRAVEL BASE (NHDOT ITEM No. 304.3) SHALL BE PROVIDED BENEATH RAMPS.
  3. DETECTABLE WARNING PANEL SHALL BE CAST IRON SET IN CONCRETE (SEE DETAIL.)
  4. LOCATE THE DETECTABLE WARNING SURFACES AT THE BACK OF THE CURB ALONG THE EDGE OF THE LANDING.
  5. THE MAXIMUM RUNNING SLOPE OF ANY SIDEWALK CURB RAMP IS 12:1, THE MAXIMUM CROSS SLOPE IS 2%. THE SLOPE OF THE LANDING SHALL NOT EXCEED 2% IN ANY DIRECTION.
  6. TRANSITIONS SHALL BE FLUSH AND FREE OF ABRUPT CHANGES. ROADWAY SHOULDER SLOPES ADJOINING SIDEWALK CURB RAMPS SHALL BE A MAXIMUM OF 5% (FULL WIDTH) FOR A DISTANCE OF 2 FT. FROM THE ROADWAY CURBLINE.
  7. THE BOTTOM OF THE SIDEWALK CURB RAMP OR LANDING, EXCLUSIVE OF THE FLARED SIDES, SHALL BE WHOLLY CONTAINED WITHIN THE CROSSWALK MARKINGS.
  8. DETECTABLE WARNING PANELS SHALL BE A MINIMUM OF 2 FEET IN DEPTH. THE ROWS OF TRUNCATED DOMES SHALL BE ALIGNED PERPENDICULAR TO THE GRADE BREAK BETWEEN THE RAMP, BLENDED TRANSITION, OR LANDING AND THE STREET.
  9. THE TEXTURE OF THE DETECTABLE WARNING FEATURE MUST CONTRAST VISUALLY WITH THE SURROUNDING SURFACES (EITHER LIGHT-ON-DARK OR DARK-ON-LIGHT).

**CONCRETE WHEELCHAIR ACCESSIBLE RAMP**  
NO SCALE



- NOTES:**
1. DETECTABLE WARNING SURFACE SHALL BE 2' X 3' CAST IRON PANEL SET IN CONCRETE.
  2. DETECTABLE WARNING SURFACE SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.

**CAST IRON DETECTABLE WARNING SURFACE**  
NO SCALE

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE




| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

PROJECT NO: E5071-001  
DATE: 4/22/2024  
FILE: E5071-001-C-DTILS.dwg  
DRAWN BY: BKC/NHW  
DESIGNED/CHECKED BY: NAH  
APPROVED BY: PMC


**DETAILS SHEET**

SCALE: AS SHOWN

**C-802**




**SIGN LEGEND AND SIGN POST**  
NO SCALE




**PARKING STALL/PAINTED ISLAND STRIPING**  
NO SCALE

- NOTES:**
1. ALL PAINT SHALL BE FAST DRYING TRAFFIC PAINT, MEETING THE REQUIREMENTS OF AASHTO M248-TYPE F. PAINT SHALL BE APPLIED AS SPECIFIED BY MANUFACTURER.
  2. SYMBOLS & PARKING STALLS SHALL CONFORM TO THE REQUIREMENTS OF THE AMERICANS WITH DISABILITIES ACT AND LOCAL AND STATE REQUIREMENTS.
  3. FINISH PAVEMENT GRADES AT ALL HANDICAP ACCESSIBLE STALLS AND PAINTED ACCESS AISLES SHALL NOT EXCEED 2% IN ANY DIRECTION.




**ACCESSIBLE SYMBOL**  
NO SCALE

- NOTES:**
1. SYMBOL SHALL BE CONSTRUCTED IN ALL ACCESSIBLE SPACES USING FAST DRYING TRAFFIC PAINT, MEETING THE REQUIREMENTS OF AASHTO M248-TYPE F. PAINT SHALL BE APPLIED AS SPECIFIED BY MANUFACTURER.
  2. SYMBOL SHALL BE CONSTRUCTED TO THE LATEST ADA, STATE AND LOCAL REQUIREMENTS.




**RAISED CROSSING TRANSITION SECTION**  
NO SCALE




**STOP BAR AND LEGEND**  
NO SCALE

- NOTE:**
1. PAVEMENT MARKINGS TO BE INSTALLED IN LOCATIONS AS SHOWN ON SITE PLAN.
  2. STRIPING SHALL BE CONSTRUCTED USING WHITE THERMO PLASTIC, REFLECTERIZED PAVEMENT MARKING MATERIAL MEETING THE REQUIREMENTS OF ASTM D 4505




**BOLLARD DETAIL**  
NO SCALE


- NOTE:**
1. COORDINATE WITH EVERSOURCE TO VERIFY THAT BOLLARD, FOOTING, AND BOLLARD COVER MEET EVERSOURCE REQUIREMENTS.




**BOLLARD MOUNTED SIGN DETAIL**  
NO SCALE



**CROSSWALK STRIPING**  
NO SCALE




**SPEED HUMP**  
NO SCALE



**ON-SITE PAVEMENT SECTION**  
NO SCALE

- NOTES:**
1. SEE SITE PLAN FOR PAVEMENT WIDTH AND LOCATION.
  2. SEE GRADING, DRAINAGE AND EROSION CONTROL PLAN FOR PAVEMENT SLOPE AND CROSS-SLOPE.
  3. A TACK COAT SHALL BE PLACED ON TOP OF BINDER COURSE PAVEMENT PRIOR TO PLACING WEARING COURSE.



**OFF-SITE PAVEMENT SECTION**  
NO SCALE

- NOTES:**
1. SEE SITE PLAN FOR PAVEMENT WIDTH AND LOCATION.
  2. SEE GRADING, DRAINAGE AND EROSION CONTROL PLAN FOR PAVEMENT SLOPE AND CROSS-SLOPE.
  3. A TACK COAT SHALL BE PLACED ON TOP OF BINDER COURSE PAVEMENT PRIOR TO PLACING WEARING COURSE.

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| F    | 11/27/2024 | PB SUBMISSION  |
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |


PROJECT NO: E5071-001  
DATE: 4/22/2024  
FILE: E5071-001-C-DTLS.dwg  
DRAWN BY: BKC/NHW  
DESIGNED/CHECKED BY: NAH  
APPROVED BY: PMC

**DETAILS SHEET**

SCALE: AS SHOWN


**C-803**

Last Saved: 11/8/2024 11:08:21 AM By: Bcurcio  
Plotted On: Nov 22, 2024 10:10:10 AM  
Digit & Bond\A\TigheandBond\Projects\E5071-Estern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DTLS.dwg




- NOTES:**
1. POLYETHYLENE LINER SHALL BE FABRICATED AT THE SHOP. DOWNSPOUT SHALL BE EXTRUSION FILLET WELDED TO THE POLYETHYLENE SHEET.
  2. PLACE A CONTINUOUS BEAD OF AN APPROVED SILICONE SEALANT (SUBSIDIARY TO ITEM 604.0007) BETWEEN FRAME AND POLYETHYLENE SHEET.
  3. PLACE CLASS AA CONCRETE TO 2" BELOW THE TOP OF THE GRATE ELEVATION (SUBSIDIARY TO DRAINAGE STRUCTURE).
  4. USE ON DRAINAGE STRUCTURES 4' MIN. DIAMETER ONLY.
  5. TRIM POLYETHYLENE SHEET A MAXIMUM OF 4" OUTSIDE THE FLANGE ON THE FRAME FOR THE CATCH BASIN BEFORE PLACING CONCRETE (EXCEPT AS SHOWN WHEN USED WITH 3-FLANGE FRAME AND CURB).
  6. THE CENTER OF THE GRATE & FRAME MAY BE SHIFTED A MAXIMUM OF 6" FROM THE CENTER OF THE DOWNSPOUT IN ANY DIRECTION.
  7. PLACED ONLY IN DRAINAGE STRUCTURES IN PAVEMENT.
  8. SEE NHDOT DR-04, "DI-DB, UNDERDRAIN FLUSHING BASIN AND POLYETHYLENE LINER DETAILS", FOR ADDITIONAL INFORMATION.
  9. CATCHBASINS WITHIN CITY RIGHT OF WAY SHALL HAVE A POLYETHYLENE LINER

**POLYETHYLENE LINER**  
NO SCALE




- NOTES:**
1. ALL DIMENSIONS ARE NOMINAL.
  2. ALL DIMENSIONS ARE NOMINAL. DIMENSIONS FOR THICKNESS ARE ALLOWED PROVIDED:
    - A. THE FRAMES MEET OR EXCEED THE SPECIFIED LOAD RATING.
    - B. THE INTERIOR PERIMETER (SEAT AREA) DIMENSIONS OF THE FRAMES REMAIN THE SAME TO ALLOW CONTINUED USE OF EXISTING GRATES/COVERS AS THE EXISTING FRAMES ALLOW, WITHOUT SHIMS OR OTHER MODIFICATIONS OR ACCOMMODATIONS.
    - C. ALL OTHER PERTINENT REQUIREMENTS OF THE SPECIFICATIONS ARE MET.
  3. LABEL TYPE OF MANHOLE WITH 3" HIGH LETTERS IN THE CENTER OF THE COVER.

**DRAIN MANHOLE FRAME & COVER**  
NO SCALE






- NOTES:**
1. ALL CATCH BASIN OUTLETS TO HAVE "ELIMINATOR" OIL AND FLOATING DEBRIS TRAP MANUFACTURED BY KLEANSTREAM (NO EQUAL)
  2. INSTALL DEBRIS TRAP TIGHT TO INSIDE OF STRUCTURE.
  3. 1/4" HOLE SHALL BE DRILLED IN TOP OF DEBRIS TRAP

**"ELIMINATOR" OIL FLOATING DEBRIS TRAP**




- NOTE:**
1. GRATE TO BE CAST IRON (NHDOT TYPE B ALTERNATE 1)
  2. FRAME AND GRATE TO BE MANUFACTURED IN THE USA

**CATCH BASIN FRAME & GRATE**  
NO SCALE




- NOTES:**
1. ALL SECTIONS SHALL BE 4,000 PSI CONCRETE.
  2. CIRCUMFERENTIAL REINFORCEMENT SHALL BE 0.12 SQUARE INCHES PER LINEAR FOOT IN ALL SECTIONS AND SHALL BE PLACED IN THE CENTER THIRD OF THE WALL.
  3. THE TONGUE AND THE GROOVE OF THE JOINT SHALL CONTAIN ONE LINE OF CIRCUMFERENTIAL REINFORCEMENT EQUAL TO 0.12 SQUARE INCHES PER LINEAR FOOT.
  4. THE STRUCTURES SHALL BE DESIGNED FOR H2O LOADING.
  5. CONSTRUCT CRUSHED STONE BEDDING AND BACKFILL UNDER (6" MINIMUM THICKNESS)
  6. THE TONGUE AND GROOVE JOINT SHALL BE SEALED WITH ONE STRIP OF BUTYL RUBBER SEALANT.
  7. PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO PRECASTING.
  8. OUTSIDE EDGES OF PIPES SHALL PROJECT NO MORE THAN 3" BEYOND INSIDE WALL OF STRUCTURE.
  9. PRECAST SECTIONS SHALL HAVE A TONGUE AND GROOVE JOINT 4" HIGH AT AN 11° ANGLE CENTERED IN THE WIDTH OF THE WALL AND SHALL BE ASSEMBLED USING AN APPROVED FLEXIBLE SEALANT IN JOINTS.
  10. ALL STRUCTURES WITH MULTIPLE PIPES SHALL HAVE A MINIMUM OF 12" OF INSIDE SURFACE BETWEEN HOLES, NO MORE THAN 75% OF A HORIZONTAL CROSS SECTION SHALL BE HOLES, AND THERE SHALL BE NO HOLES CLOSER THAN 3" TO JOINTS.

**DRAIN MANHOLES**  
NO SCALE



| DIAMETER | WALL THICKNESS (MIN.) | FLOOR THICKNESS (MIN.) |
|----------|-----------------------|------------------------|
| 4"       | 5"                    | 6"                     |
| 5"       | 6"                    | 8"                     |
| 6"       | 7"                    | 8"                     |
| 8"       | 9"                    | 10"                    |
| 9"       | 11"                   | 10"                    |



- NOTES:**
1. ALL SECTIONS SHALL BE CONCRETE CLASS AA(4000 psi).
  2. CIRCUMFERENTIAL REINFORCEMENT SHALL BE 0.12 SQ. IN. PER LINEAR FT. IN ALL SECTIONS AND SHALL BE PLACED IN THE CENTER THIRD OF THE WALL.
  3. THE TONGUE AND GROOVE OF THE JOINT SHALL CONTAIN ONE LINE OF CIRCUMFERENTIAL REINFORCEMENT EQUAL TO 0.12 SQ. IN. PER LINEAR FT.
  4. RISERS OF 1', 2', 3' & 4' CAN BE USED TO REACH DESIRED DEPTH.
  5. THE STRUCTURES SHALL BE DESIGNED FOR H2O LOADING.
  6. FITTING FRAME TO GRADE MAY BE DONE WITH PREFABRICATED ADJUSTMENT RINGS OR CLAY BRICKS (2 COURSES MAX.).
  7. CONE SECTIONS MAY BE EITHER CONCENTRIC OR ECCENTRIC, OR FLAT SLAB TOPS MAY BE USED WHERE PIPE WOULD OTHERWISE ENTER INTO THE CONE SECTION OF THE STRUCTURE AND WHERE PERMITTED.
  8. PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO PRECASTING.
  9. OUTSIDE EDGES OF PIPES SHALL PROJECT NO MORE THAN 3" BEYOND INSIDE WALL OF STRUCTURE.
  10. PRECAST SECTIONS SHALL HAVE A TONGUE AND GROOVE JOINT 4" HIGH AT AN 11° ANGLE CENTERED IN THE WIDTH OF THE WALL AND SHALL BE ASSEMBLED USING AN APPROVED FLEXIBLE SEALANT IN JOINTS.
  11. THE TONGUE AND GROOVE JOINT SHALL BE SEALED WITH ONE STRIP OF BUTYL RUBBER SEALANT.
  12. "ELIMINATOR" OIL/WATER SEPARATOR SHALL BE INSTALLED TIGHT TO INSIDE OF CATCHBASIN.

**4" DIAMETER CATCHBASIN**  
NO SCALE

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE



| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

PROJECT NO: E5071-001  
DATE: 4/22/2024  
FILE: E5071-001-C-DTLS.dwg  
DRAWN BY: BKC/NHW  
DESIGNED/CHECKED BY: NAH  
APPROVED BY: PMC


**DETAILS SHEET**

SCALE: AS SHOWN

**C-804**



**RG-1**  
NO SCALE




**RG-2**  
NO SCALE

- NOTES:**
- BARK MULCH SHALL BE AGED A MINIMUM OF 12 MONTHS AND SHALL NOT FLOAT.
  - RAIN GARDENS SHALL NOT BE PLACED INTO SERVICE UNTIL THE PRACTICE HAS BEEN PLANTED AND ITS CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.
  - DO NOT TRAFFIC EXPOSED SOIL SURFACES WITH CONSTRUCTION EQUIPMENT. CONTRACTOR SHALL KEEP ALL EXCAVATION EQUIPMENT OUTSIDE OF THE LIMIT OF THE RAIN GARDEN.
  - SEE GRADING, DRAINAGE & EROSION CONTROL PLAN FOR LOCATIONS, LAYOUTS, AND ELEVATIONS.
  - THE SAND PORTION OF THE FILTER MEDIA SHALL MEET THE FOLLOWING GRADATION (ASTM C-33):


| SIEVE SIZE | PERCENT PASSING |
|------------|-----------------|
| 3/8"       | 100             |
| #4         | 95-100          |
| #8         | 80-100          |
| #16        | 50-85           |
| #30        | 25-60           |
| #50        | 5-30            |
| #100       | 0-10            |

| FILTER MEDIA COMPOSITION:                         |                              |                       |                 |
|---|------------------------------|-----------------------|-----------------|
| COMPONENT MATERIAL                                | PERCENT OF MIXTURE BY VOLUME | GRADATION OF MATERIAL | PERCENT PASSING |
| ASTM C-33 CONCRETE SAND                           | 50-55                        | SEE NOTE #5           |                 |
| LOAMY SAND TOPSOIL                                | 20-30                        | 200                   | 15-25           |
| MODERATELY FINE SHREDDED BARK OR WOOD FIBER MULCH | 20-30                        | 200                   | 5 MAX           |


**RAIN GARDENS**  
NO SCALE



**ELEVATION VIEW**




**PLAN VIEW**




**SECTION A-A**

- NOTES:**
- HEADWALL SHALL BE 5,000 PSI CONCRETE.
  - HEADWALL REINFORCEMENT SHALL BE 0.18 SQUARE INCHES PER LINEAR FOOT IN ALL SECTIONS AND SHALL BE PLACED IN THE CENTER THIRD OF THE WALL.
  - SEE GRADING, DRAINAGE, & EROSION CONTROL PLAN FOR STONE SIZE AND APRON DIMENSIONS.
  - STONE SHALL CONSIST OF SUB-ANGULAR FIELD STONE OR ROUGH UNHEWN QUARRY STONE OF APPROXIMATELY RECTANGULAR SHAPE. FLAT OR ROUND ROCKS ARE NOT ACCEPTABLE. THE STONE SHALL BE HARD AND OF SUCH QUALITY THAT IT WILL NOT DISINTEGRATE ON EXPOSURE TO WATER OR WEATHERING, BE CHEMICALLY STABLE AND IT SHALL BE SUITABLE IN ALL OTHER RESPECTS FOR THE PURPOSE INTENDED. THE BULK SPECIFIC GRAVITY (SATURATED SURFACE-DRY BASIS) OF THE INDIVIDUAL STONES SHALL BE AT LEAST 2.5.
  - THE STONE SHALL BE COMPOSED OF A WELL-GRADED MIXTURE DOWN TO THE ONE-INCH SIZE PARTICLE SUCH THAT 50 PERCENT OF THE MIXTURE BY WEIGHT SHALL BE LARGER THAN THE D50 SIZE SPECIFIED. A WELL-GRADED MIXTURE IS DEFINED AS A MIXTURE COMPOSED PRIMARILY OF THE LARGER STONE SIZE BUT WITH A SUFFICIENT MIXTURE OF OTHER SIZES TO FILL THE PROGRESSIVELY SMALLER VOIDS BETWEEN THE STONES. THE DIAMETER OF THE LARGEST STONE SIZE IN SUCH A MIXTURE SHALL BE 1.5 TIMES THE D50 SIZE.


**PRECAST CONCRETE HEADWALL WITH WING WALLS**  
NO SCALE



**RAIN GARDEN OUTLET STRUCTURE (POCS1)**  
NO SCALE




**RAIN GARDEN OUTLET STRUCTURE (POCS2)**  
NO SCALE




**SECTION A-A**

| OUTLET PLUNGE POOL SIZING |     |      |      |      |                 |       |
|---------------------------|-----|------|------|------|-----------------|-------|
|                           | Do  | S    | W    | L    | D <sub>50</sub> | D     |
| HW1                       | 24" | 2.0' | 4.0' | 6.0' | 6"              | 1.13' |

**OUTLET PLUNGE POOL**  
NO SCALE



**PLAN**



**SECTION**

- NOTES:**
- STONE SIZE AND MAT DIMENSIONS DETAILED ON PLANS.
  - STONE SHALL CONSIST OF SUB-ANGULAR FIELD STONE OR ROUGH UNHEWN QUARRY STONE OF APPROXIMATELY RECTANGULAR SHAPE. FLAT OR ROUND ROCKS ARE NOT ACCEPTABLE. THE STONE SHALL BE HARD AND OF SUCH QUALITY THAT IT WILL NOT DISINTEGRATE ON EXPOSURE TO WATER OR WEATHERING, BE CHEMICALLY STABLE AND IT SHALL BE SUITABLE IN ALL OTHER RESPECTS FOR THE PURPOSE INTENDED. THE BULK SPECIFIC GRAVITY (SATURATED SURFACE-DRY BASIS) OF THE INDIVIDUAL STONES SHALL BE AT LEAST 2.5.
  - THE STONE SHALL BE COMPOSED OF A WELL-GRADED MIXTURE DOWN TO THE ONE-INCH SIZE PARTICLE SUCH THAT 50 PERCENT OF THE MIXTURE BY WEIGHT SHALL BE LARGER THAN THE D50 SIZE SPECIFIED. A WELL-GRADED MIXTURE IS DEFINED AS A MIXTURE COMPOSED PRIMARILY OF THE LARGER STONE SIZE BUT WITH A SUFFICIENT MIXTURE OF OTHER SIZES TO FILL THE PROGRESSIVELY SMALLER VOIDS BETWEEN THE STONES. THE DIAMETER OF THE LARGEST STONE SIZE IN SUCH A MIXTURE SHALL BE 1.5 TIMES THE D50 SIZE.

**RIP-RAP APRON DETAIL**  
NO SCALE

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |



PROJECT NO: E5071-001  
DATE: 4/22/2024  
FILE: E5071-001-C-DTLS.dwg  
DRAWN BY: BKC/NHW  
DESIGNED/CHECKED BY: NAH  
APPROVED BY: PMC

**DETAILS SHEET**

SCALE: AS SHOWN

**C-805**


Last Saved: 10/17/2024 4:38pm By: DCurcio  
Plotted On: Oct 21, 2024 4:38pm  
Tighe & Bond \\lghmead\com\data\proj\100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DTLS.dwg




| PIPE DIA. | S    | B   | H    | L   | W   |
|-----------|------|-----|------|-----|-----|
| 12"       | 6.5" | 10" | 6.5" | 25" | 29" |
| 15"       | 6.5" | 10" | 6.5" | 25" | 29" |
| 18"       | 7.5" | 15" | 6.5" | 32" | 35" |
| 24"       | 7.5" | 18" | 6.5" | 36" | 45" |
| 30"       | 7.5" | 12" | 8.6" | 58" | 63" |
| 36"       | 7.5" | 25" | 8.6" | 58" | 63" |

NOTE:  
1. END SECTIONS MANUFACTURED BY ADVANCED DRAINAGE SYSTEMS, COLUMBUS, OHIO.  
END SECTIONS TO BE WELDED TO PIPE AS PER MANUFACTURER'S RECOMMENDATIONS.


**HDPE FLARED END SECTION**  
NO SCALE



NOTES:  
1. RAIN GUARDIAN OR APPROVED EQUAL.  
2. CURB INLET SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURE RECOMMENDATION.




**RAIN GUARDIAN TURRET**  
NO SCALE



NOTES:  
1. GRATES/SOLID COVER SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05.  
2. FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05  
3. SEE GRADING, DRAINAGE, AND EROSION CONTROL PLAN FOR LOCATIONS.

**YARD DRAIN**  
NO SCALE



PROPOSED CDS STRUCTURE SCHEDULE

| STRUCTURE ID# | JFF TYPE      |
|---------------|---------------|
| PJFF1         | JFPD0808-12-3 |
| PJFF2         | JFPD0808-15-3 |


**GENERAL NOTES:**  
1. CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.  
2. FOR SITE SPECIFIC DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHT, PLEASE CONTACT YOUR CONTECH ENGINEERED SOLUTIONS REPRESENTATIVE. [www.ContechES.com](http://www.ContechES.com)  
3. JELLYFISH WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF PROJECT.  
4. STRUCTURE SHALL MEET AASHTO HS-20 OR PER APPROVING JURISDICTION REQUIREMENTS, WHICHEVER IS MORE STRINGENT, ASSUMING EARTH COVER OF 0' - 3', AND GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. CASTINGS SHALL MEET AASHTO M306 LOAD RATING AND BE CAST WITH THE CONTECH LOGO.  
5. STRUCTURE SHALL BE PRECAST CONCRETE CONFORMING TO ASTM C-478 AND AASHTO LOAD FACTOR DESIGN METHOD.  
6. OUTLET PIPE INVERT IS EQUAL TO THE CARTRIDGE DECK ELEVATION.  
7. THE OUTLET PIPE DIAMETER FOR NEW INSTALLATIONS IS TO BE ONE PIPE SIZE LARGER THAN THE INLET PIPE AT EQUAL OR GREATER SLOPE.  
8. NO PRODUCT SUBSTITUTIONS SHALL BE ACCEPTED UNLESS SUBMITTED 10 DAYS PRIOR TO PROJECT BID DATE, OR AS DIRECTED BY THE ENGINEER OF RECORD.

**INSTALLATION NOTES:**  
A. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.  
B. CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STRUCTURE (LIFTING CLUTCHES PROVIDED)  
C. CONTRACTOR WILL INSTALL AND LEVEL THE STRUCTURE, SEALING THE JOINTS, LINE ENTRY AND EXIT POINTS (NON-SHRINK GROUT WITH APPROVED WATERSTOP OR FLEXIBLE BOOT)  
D. CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT CARTRIDGES FROM CONSTRUCTION-RELATED EROSION RUNOFF.  
E. CARTRIDGE INSTALLATION, BY CONTECH, SHALL OCCUR ONLY AFTER SITE HAS BEEN STABILIZED AND THE JELLYFISH UNIT IS CLEAN AND FREE OF DEBRIS. CONTACT CONTECH TO COORDINATE CARTRIDGE INSTALLATION WITH SITE STABILIZATION AT (866) 740-3318.

NOTE:  
1. A QUALIFIED ENGINEER SHALL PROVIDE SUFFICIENT INSPECTION TO CERTIFY THAT THE SYSTEM HAS BEEN INSTALLED IN ACCORDANCE WITH THE APPROVED DESIGN PLANS PER THE REQUIREMENTS OF THE ALTERATION OF TERRAIN PERMIT. CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO THE CONSTRUCTION OF THE UNDERGROUND FILTRATION UNITS.




**CONTECH JELLYFISH STORMWATER FILTER (JFPD0808)**  
NO SCALE



PROPOSED CDS STRUCTURE SCHEDULE

| STRUCTURE ID# | JFF TYPE   |
|---------------|------------|
| PCDS1         | CDS 6-3025 |
| PCDS2         | CDS 6-3030 |
| PCDS3         | CDS 6-3030 |



**GENERAL NOTES:**  
1. CONTECH TO PROVIDE FINAL DIMENSIONS BASED ON APPROVED FLOWS AND ALL MATERIALS UNLESS NOTED OTHERWISE.  
2. CDS WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING.  
3. STRUCTURE SHALL MEET AASHTO HS20 AND CASTINGS SHALL MEET HS20 (AASHTO M 306) LOAD RATING, ASSUMING GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION.  
4. PVC HYDRAULIC SHEAR PLATE IS PLACED ON SHELF AT BOTTOM OF SCREEN CYLINDER. REMOVE AND REPLACE AS NECESSARY DURING MAINTENANCE CLEANING.

**INSTALLATION NOTES:**  
A. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.  
B. CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CDS MANHOLE STRUCTURE (LIFTING CLUTCHES PROVIDED).  
C. CONTRACTOR TO ADD JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS, AND ASSEMBLE STRUCTURE.  
D. CONTRACTOR TO PROVIDE, INSTALL, AND GROUT PIPES. MATCH PIPE INVERTS WITH ELEVATIONS SHOWN ON GRADING PLAN.  
E. CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED.

**CONTECH CDS UNIT**  
NO SCALE

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |


PROJECT NO: E5071-001  
DATE: 4/22/2024  
FILE: E5071-001-C-DTLS.dwg  
DRAWN BY: BKC/NHW  
DESIGNED/CHECKED BY: NAH  
APPROVED BY: PMC

**DETAILS SHEET**

SCALE: AS SHOWN


**C-806**

Last Saved: 10/17/2024 4:38pm By: DCurcio  
Plotted On: Oct 21, 2024 4:38pm  
Tighe & Bond \\lgn\shared\dwg\100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DTLS.dwg





**TYPICAL BLOCK RETAINING WALL SECTION**  
NO SCALE

- NOTES:**
- RETAINING WALL SHALL BE BY REDI ROCK LEDGESTONE OR APPROVED EQUAL.
  - THE CONTRACTOR SHALL SUBMIT DESIGN AND CALCULATIONS FOR THE RETAINING WALL THAT SHALL BE STAMPED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF NEW HAMPSHIRE. CALCULATIONS SHALL INCLUDE A GLOBAL STABILITY ANALYSIS.
  - MINIMUM DESIGN PARAMETERS:
    - GLOBAL STABILITY FACTOR OF SAFETY = 1.3
    - OVERTURNING FACTOR OF SAFETY = 2.0
    - SLIDING FACTOR OF SAFETY = 1.5
    - GEOGRID PULLOUT FACTOR OF SAFETY = 1.5
    - SEISMIC FACTOR OF SAFETY = 1.1
  - WALL DESIGNS SHALL CONSIDER EFFECTS OF SLOPE, TRAFFIC LOADS, BUILDING LOADS, GUARDRAIL AND/OR FENCING AS REQUIRED.
  - WALL DESIGN ENGINEER SHALL CONSIDER HEIGHT AND SPECIFY SAFETY RAIL WHERE REQUIRED.
  - ALL INSTALLATION PROCEDURES SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION MANUAL AND THE WALL DESIGN ENGINEER'S DESIGN PLANS AND SPECIFICATIONS.
  - THE WALL DESIGN ENGINEER SHALL COMPLETE SUFFICIENT INSPECTIONS DURING CONSTRUCTION TO CERTIFY WORK IS COMPLETED IN ACCORDANCE WITH DESIGN.
  - CONTRACTOR SHALL SUBMIT AS-BUILT DRAWINGS OF WALL WITH WALL DESIGNER'S CERTIFICATION TO OWNER.
  - CONTRACTOR SHALL DIRECT SURFACE RUNOFF AWAY FROM THE WALL DURING CONSTRUCTION.
  - ANY SURFACE DRAINAGE FEATURES, FINISH GRADING, PAVEMENT OR OTHER SURFACE TREATMENT SHALL BE INSTALLED IN THE AREA OF THE WALL IMMEDIATELY AFTER THE WALL IS COMPLETE OR OTHER MEASURES SHALL BE TAKEN TO PROTECT THE WALL FROM RUNOFF.
  - CONTRACTOR SHALL SUPPLY SAMPLE TO THE OWNER FOR APPROVAL PRIOR TO WALL CONSTRUCTION.



- NOTES:**
- HYDRANT TO BE KENNEDY TYPE K-81, RIGHT OPEN (NO EQUAL). COORDINATE WITH CITY OF PORTSMOUTH WATER DEPARTMENT AND CITY OF PORTSMOUTH FIRE DEPARTMENT.
  - PAINT HYDRANT IN ACCORDANCE WITH CITY STANDARD SPECIFICATIONS AFTER INSTALLATION AND TESTING.

**FIRE HYDRANT**  
NO SCALE



NOTE: ALL WATER SERVICE CONNECTIONS SHALL CONFORM TO CITY OF PORTSMOUTH STANDARDS.

**WATER SERVICE CONNECTION**  
NO SCALE


**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC


100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

**NOTES:**



- STONE SIZE AND MAT DIMENSIONS DETAILED ON PLANS.
- STONE SHALL CONSIST OF SUB-ANGULAR FIELD STONE OR ROUGH UNHEWN QUARRY STONE OF APPROXIMATELY RECTANGULAR SHAPE. FLAT OR ROUND ROCKS ARE NOT ACCEPTABLE. THE STONE SHALL BE HARD AND OF SUCH QUALITY THAT IT WILL NOT DISINTEGRATE ON EXPOSURE TO WATER OR WEATHERING, BE CHEMICALLY STABLE AND IT SHALL BE SUITABLE IN ALL OTHER RESPECTS FOR THE PURPOSE INTENDED. THE BULK SPECIFIC GRAVITY (SATURATED SURFACE-DRY BASIS) OF THE INDIVIDUAL STONES SHALL BE AT LEAST 2.5.
- THE STONE SHALL BE COMPOSED OF A WELL-GRADED MIXTURE DOWN TO THE ONE-INCH SIZE PARTICLE SUCH THAT 50 PERCENT OF THE MIXTURE BY WEIGHT SHALL BE LARGER THAN THE D50 SIZE SPECIFIED. A WELL-GRADED MIXTURE IS DEFINED AS A MIXTURE COMPOSED PRIMARILY OF THE LARGER STONE SIZE BUT WITH A SUFFICIENT MIXTURE OF OTHER SIZES TO FILL THE PROGRESSIVELY SMALLER VOIDS BETWEEN THE STONES. THE DIAMETER OF THE LARGEST STONE SIZE IN SUCH A MIXTURE SHALL BE 1.5 TIMES THE D50 SIZE.




**RIP-RAP APRON DETAIL**  
NO SCALE



PLACE OFFSET BLOCK INDENTATION AGAINST THE FACE OF THE POST




**STEEL POST/STEEL BEAM GUARDRAIL**  
NO SCALE



| DESIGNATOR | L      | T                         | INTENDED USE            |
|------------|--------|---------------------------|-------------------------|
| FBB01      | 1 1/2" | FULL LENGTH THREAD        | RAIL SPLICE BOLTS       |
| FBB02      | 2"     | 1 3/4" MIN. THREAD LENGTH | POST BOLT (STEEL POSTS) |
| FBB03      | 9 1/2" | 4" MIN. THREAD LENGTH     | POST BOLT               |

5/8" BUTTON HEAD BOLT AND RECESSED NUT [FBB01-03]



**NOTES:**

- SEE SITE PLAN FOR LIMITS OF GUARDRAIL.
- THE LENGTH OF NEED IS THE TOTAL LENGTH OF A LONGITUDINAL BARRIER NEEDED TO SHIELD AN AREA OF CONCERN. TO DETERMINE THE LENGTH OF NEED, REFER TO THE "ROADSIDE DESIGN GUIDE" - AASHTO (1989).
- DESIGNATION PROVIDED IN BRACKETS ( ) REFERENCE STANDARD ELEMENTS DETAILED IN "A GUIDE TO STANDARDIZED HIGHWAY BARRIER RAIL HARDWARE" (1979) - AASHTO - AGC - ARTBA JOINT COOPERATIVE COMMITTEE.
- USE 12'-6" LENGTH RAIL ELEMENT IN CURVES OF LESS THAN 100' RAIL RADIUS.
- ALL DIMENSIONS SUBJECT TO MANUFACTURER'S TOLERANCES.
- ESTABLISH RAIL HEIGHT AS FOLLOWS:
  - SET THE HEIGHT OF RAIL FROM THE EDGE OF THE PAVEMENT (EP) WHEN THE FACE OF RAIL IS AT THE EDGE OF PAVEMENT.
  - SET THE HEIGHT OF RAIL FROM THE GROUND AT THE FACE OF RAIL WHEN:
    - THE FACE OF RAIL IS OFFSET FROM THE EP AND THE CROSS SLOPE FROM THE EP TO THE FACE OF RAIL IS 10:1 OR FLATTER OR
      - THE FACE OF RAIL IS AT THE BACK OF A CURBED SIDEWALK AND THE CURB IS AT THE EDGE OF PAVEMENT.
      - WHEN SITUATIONS OTHER THAN THOSE DESCRIBED IN 5.1 OR 5.2 ABOVE ARE ENCOUNTERED, ESTABLISH RAIL HEIGHT THROUGH AN ENGINEERING REVIEW TO ENSURE APPROPRIATE SYSTEM PERFORMANCE.
    - WHEN GUARDRAIL IS INSTALLED BEHIND CURB, EITHER 6'-0" BEHIND SLOPE CURB ON A CLOSED RAMP OR AT THE BACK OF SIDEWALK WITH BARRIER CURB, THE RAIL HEIGHT SHALL BE SET FROM THE GRADE AT THE FACE OF RAIL.
- USE 6'-0" LONG POSTS WHEN FILL SLOPE IS 4:1 OR FLATTER AND/OR WHEN FIELD CONDITIONS DICTATE (e.g., LEDGE FILLS), AS DETERMINED BY THE ENGINEER.
- WHEN GUARDRAIL IS INSTALLED BEHIND CURB, EITHER 6'-0" BEHIND SLOPE CURB ON A CLOSED RAMP OR AT THE BACK OF SIDEWALK WITH BARRIER CURB, THE RAIL HEIGHT SHALL BE SET FROM THE GRADE AT THE FACE OF RAIL.
- SEE MOST RECENT NHDOT "BEAM GUARDRAIL STANDARD SECTION" (GR-2) FOR ADDITIONAL DETAILS.


| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

**DETAILS SHEET**

SCALE: AS SHOWN


C-807






- NOTES:**
1. ALL SEWER MANHOLES SHALL BE CONSTRUCTED TO CITY AND STATE STANDARDS.
  2. INVERT AND SHELF TO BE PLACED AFTER EACH LEAKAGE TEST.
  3. CARE SHALL BE TAKEN TO INSURE THAT THE BRICK INVERT IS A SMOOTH CONTINUATION OF THE SEWER INVERT.
  4. INVERT BRICKS SHALL BE LAID ON EDGE.
  5. TWO (2) COATS OF BITUMINOUS WATERPROOF COATING SHALL BE APPLIED TO ENTIRE EXTERIOR OF MANHOLE.
  6. FRAMES AND COVERS: MANHOLE FRAMES AND COVERS WITHIN CITY RIGHT OF WAY SHALL BE CITY STANDARD HINGE COVERS MANUFACTURED BY E.J. FRAMES AND COVERS WILL BE PURCHASED FROM THE CITY OF PORTSMOUTH DEPARTMENT OF PUBLIC WORKS. ALL OTHER MANHOLE FRAMES AND COVERS SHALL BE OF HEAVY DUTY DESIGN AND PROVIDE A 30-INCH CLEAR OPENING. A 3-INCH (MINIMUM HEIGHT) WORD "SEWER" SHALL BE PLAINLY CAST INTO THE CENTER OF EACH COVER.
  7. HORIZONTAL JOINTS SHALL BE SEALED FOR WATER TIGHTNESS USING A DOUBLE ROW OF ELASTOMERIC OR MASTIC-LIKE SEALANT.
  8. BARREL AND CONE SECTIONS SHALL BE PRECAST REINFORCED CONCRETE DESIGNED FOR H2O LOADING, AND CONFORMING TO ASTM C478-06.

**SEWER MANHOLE**  
NO SCALE




- NOTES:**
1. CRUSHED STONE BEDDING AND BACKFILL FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW PIPE IN EARTH AND 12" BELOW PIPE IN ROCK UP TO 6" ABOVE TOP OF PIPE.
  2. ALL UTILITIES SHALL BE INSTALLED PER THE INDIVIDUAL UTILITY COMPANY STANDARDS. COORDINATE ALL INSTALLATIONS WITH INDIVIDUAL UTILITY COMPANIES AND THE CITY OF PORTSMOUTH.

**STORM DRAIN TRENCH**  
NO SCALE




- NOTES:**
1. CRUSHED STONE BEDDING FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW PIPE IN EARTH AND 12" BELOW PIPE IN ROCK. CRUSHED STONE SHALL ALSO COMPLETELY ENCASE THE PIPE AND COVER THE PIPE TO A GRADE 6" OVER THE TOP OF THE PIPE FOR THE ENTIRE WIDTH OF THE TRENCH.
  2. COORDINATE ALL INSTALLATIONS WITH THE CITY OF PORTSMOUTH.

**SEWER SERVICE TRENCH**  
NO SCALE




- NOTE:**
1. SAND BEDDING AND BACKFILL FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW PIPE IN EARTH AND 12" BELOW PIPE IN ROCK UP TO 12" ABOVE TOP OF PIPE.
  2. GAS SHALL BE INSTALLED PER UNITIL STANDARDS. COORDINATE ALL INSTALLATIONS WITH UNITIL AND THE CITY OF PORTSMOUTH.

**GAS TRENCH**  
NO SCALE




- NOTES:**
1. SAND BEDDING AND BACKFILL FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW PIPE IN EARTH AND 12" BELOW PIPE IN ROCK UP TO 12" ABOVE TOP OF PIPE.
  2. WATER MAIN SHALL BE INSTALLED PER CITY OF PORTSMOUTH STANDARDS. COORDINATE ALL INSTALLATIONS WITH THE CITY OF PORTSMOUTH.

**WATER TRENCH**  
NO SCALE




- NOTES:**
1. HORIZONTAL JOINTS BETWEEN THE SECTIONS OF PRECAST CONCRETE BARRELS SHALL BE PER CITY OF PORTSMOUTH DPW STANDARD AND SHALL BE SEALED FOR WATERTIGHTNESS USING A DOUBLE ROW ELASTOMERIC OR MASTIC-LIKE GASKET.
  2. PIPE TO MANHOLE JOINTS SHALL BE PER CITY OF PORTSMOUTH STANDARD.
  3. FOR BITUMASTIC TYPE JOINTS THE AMOUNT OF SEALANT SHALL BE SUFFICIENT TO FILL AT LEAST 75% OF THE JOINT CAVITY.
  4. ALL GASKETS, SEALANTS, MORTAR, ETC. SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS' WRITTEN INSTRUCTIONS.

**MANHOLE JOINTS**  
NO SCALE



- NOTES:**
1. A 10 FOOT MINIMUM EDGE TO EDGE HORIZONTAL SEPARATION SHALL BE PROVIDED FROM ANY EXISTING OR PROPOSED WATER LINE.
  2. AN 18" MINIMUM EDGE TO EDGE VERTICAL SEPARATION SHALL BE PROVIDED, WITH WATER ABOVE SEWER, AT ALL CROSSINGS.
  3. SEWER PIPE JOINTS SHALL BE LOCATED AT LEAST 6 FEET HORIZONTALLY FROM ANY EXISTING OR PROPOSED WATER MAIN.
  4. WHERE AN 18" VERTICAL SEPARATION CANNOT BE PROVIDED, SEWER PIPE SHALL BE CONSTRUCTED USING A SDR 26 PVC PIPE MEETING THE REQUIREMENTS OF SEWER FORCE MAIN STANDARDS. THE SDR26 PIPE SHALL BE USED FOR THE ENTIRE RUN BETWEEN MANHOLES ON EITHER SIDE OF CROSSING.
  5. CROSSINGS SHALL CONFORM TO THE CITY OF PORTSMOUTH STANDARDS AND SPECIFICATIONS.
  6. ALL FUTURE SEWER CONNECTIONS SHALL MEET THE ABOVE REQUIREMENTS.

**WATER & SEWER CROSSING**  
NO SCALE





| NOMINAL DIA. (in) | PIPE SIZE |      |      |       |       |       |
|-------------------|-----------|------|------|-------|-------|-------|
|                   | 4"        | 6"   | 8"   | 10"   | 12"   | 16"   |
| PIPE FITTINGS     | *         | *    | 5.18 | 7.96  | 11.43 | 20.29 |
| A 90°             | *         | 4.11 | 7.33 | 11.26 | 16.17 | 28.69 |
| C 45°             | *         | *    | *    | 6.10  | 8.75  | 15.53 |
| D 22-1/2°         | *         | *    | *    | *     | 4.46  | 7.92  |
| E 11-1/4°         | *         | *    | *    | *     | *     | *     |

\*SEE NOTE 2

SYSTEM PRESSURE: 125 psi  
SAFETY FACTOR: 1.5  
SOIL BEARING CAPACITY: 2,000 psf

- NOTES:**
1. ALL THRUST BLOCKS SHALL BE PRE-CAST CONCRETE UNLESS APPROVED BY THE CITY ENGINEER.
  2. 2'X2' MINIMUM THRUST BLOCK REQUIRED, ANY BEARING AREA OVER 4 SF REQUIRES THRUST BLOCKS, RESTRAINED JOINTS AND CALCULATIONS ASSOCIATED WITH THE JOINT.
  3. FOR MINIMUM BEARING AREAS OVER 4 SF, THE LENGTH (L) OF THE BLOCK IS APPROXIMATELY TWICE AS LONG AS THE HEIGHT (H).
  4. THE MINIMUM BEARING AREAS SHOWN IN THE THRUST BLOCK SCHEDULE ARE BASED ON A SYSTEM PRESSURE OF 125 PSI. IF THE SYSTEM PRESSURE IS ABOVE 125 PSI, INCREASE THE NOTED AREAS PROPORTIONALLY TO THE ACTUAL SYSTEM PRESSURE.
  5. PLACE CRUSHED STONE BEHIND THRUST BLOCK AGAINST UNDISTURBED SOIL.
  6. PLACE THRUST BLOCK ALONG MAXIMUM LENGTH OF THE FITTING TO MAXIMIZE BEARING AREA.
  7. CONCRETE COMPRESSIVE STRENGTH: 2,000 PSI MINIMUM.
  8. WHERE M.J. PIPE IS USED, M.J. PLUG WITH RETAINER GLAND MAY BE SUBSTITUTED FOR END BLOCKINGS.
  9. INSTALLATION AND STANDARD DIMENSIONAL REQUIREMENTS SHALL BE WITH CITY OF PORTSMOUTH WATER DEPARTMENT STANDARDS.

**THRUST BLOCKING DETAIL**  
NO SCALE



**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |


PROJECT NO: E5071-001  
DATE: 4/22/2024  
FILE: E5071-001-C-DTLS.dwg  
DRAWN BY: BKC/NHW  
DESIGNED/CHECKED BY: NAH  
APPROVED BY: PMC

**DETAILS SHEET**

SCALE: AS SHOWN



C-808

Last Saved: 10/17/2024 4:38pm By: EDC/rlc  
Plotted On: Oct 21, 2024 4:38pm  
Tighe & Bond \\\gibson\cadd\proj\100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DTLS.dwg




NOTES:  
 THE GROUND GRID SHALL BE SUPPLIED AND INSTALLED BY THE CONTRACTOR AND IS TO BE BURIED AT LEAST 12 INCHES BELOW GRADE. EIGHT FEET OF EXTRA WIRE FOR EACH GROUND GRID LEG SHALL BE LEFT EXPOSED IN THE CABLE COMPARTMENT TO ALLOW FOR THE CONNECTION TO THE TRANSFORMER. THE TWO 8-FOOT GROUND RODS MAY BE EITHER GALVANIZED STEEL OR COPPERWELD AND THEY SHALL BE CONNECTED TO THE GRID WITH NEC APPROVED CONNECTORS.

**PAD-MOUNTED EQUIPMENT GROUNDING GRID DETAIL**  
 NO SCALE





NOTES:  
 1. DIMENSIONS SHOWN REPRESENT TYPICAL REQUIREMENTS. MANHOLE LOCATIONS AND REQUIREMENTS SHALL BE COORDINATED WITH EVERSOURCE PRIOR TO CONSTRUCTION.  
 2. CONCRETE MINIMUM STRENGTH - 4,000 PSI @ 28 DAYS  
 3. STEEL REINFORCEMENT - ASTM A615, GRADE 60  
 4. PAD MEETS OR EXCEEDS EVERSOURCE SPECIFICATIONS

**3-PHASE TRANSFORMER PAD**  
 NO SCALE




NOTES:  
 1. NUMBER, MATERIAL, AND SIZE OF UTILITY CONDUITS TO BE DETERMINED AS SHOWN ON ELECTRICAL DRAWINGS. CONTRACTOR TO PROVIDE ONE SPARE CONDUIT FOR EACH UTILITY TO BUILDING.  
 2. DIMENSIONS SHOWN REPRESENT MINIMUM REQUIREMENTS. ACTUAL DIMENSIONS MAY BE GREATER BASED ON UTILITY COMPANY STANDARDS, BUT SHALL NOT BE LESS THAN THOSE SHOWN.  
 3. NO CONDUIT RUN SHALL EXCEED 360 DEGREES IN TOTAL BENDS.  
 4. A SUITABLE PULLING STRING, CAPABLE OF 200 POUNDS OF PULL, MUST BE INSTALLED IN THE CONDUIT BEFORE UTILITY COMPANY IS NOTIFIED TO INSTALL CABLE. THE STRING SHOULD BE BLOWN INTO THE CONDUIT AFTER THE RUN IS ASSEMBLED TO AVOID BONDING THE STRING TO THE CONDUIT.  
 5. UTILITY COMPANY MUST BE GIVEN THE OPPORTUNITY TO INSPECT THE CONDUIT PRIOR TO BACKFILL. THE CONTRACTOR IS RESPONSIBLE FOR ALL REPAIRS SHOULD THE UTILITY COMPANY BE UNABLE TO INSTALL ITS CABLE IN A SUITABLE MANNER.  
 6. ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND, WHERE APPLICABLE, THE NATIONAL ELECTRIC CODE.  
 7. ALL 90° SWEEPS WILL BE MADE USING RIGID GALVANIZED STEEL. SWEEPS WITH A 36 TO 48 INCH RADIUS.  
 8. SAND BEDDING TO BE REPLACED WITH CONCRETE ENCASEMENT WHERE COVER IS LESS THAN 3 FEET, WHEN LOCATED BELOW PAVEMENT, OR WHERE SHOWN ON THE UTILITIES PLAN.  
 9. SAND BEDDING AND BACKFILL FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW CONDUIT UP TO 6" ABOVE TOP OF CONDUIT.

**LIGHTING CONDUIT TRENCH**  
 NO SCALE



NOTES:  
 1. NUMBER, MATERIAL, AND SIZE OF UTILITY CONDUITS TO BE DETERMINED BY LOCAL UTILITY OR AS SHOWN ON ELECTRICAL DRAWINGS. CONTRACTOR TO PROVIDE ONE SPARE CONDUIT FOR EACH UTILITY TO BUILDING.  
 2. DIMENSIONS SHOWN REPRESENT OWNERS MINIMUM REQUIREMENTS. ACTUAL DIMENSIONS MAY BE GREATER BASED ON UTILITY COMPANY STANDARDS, BUT SHALL NOT BE LESS THAN THOSE SHOWN.  
 3. NO CONDUIT RUN SHALL EXCEED 360 DEGREES IN TOTAL BENDS.  
 4. A SUITABLE PULLING STRING, CAPABLE OF 200 POUNDS OF PULL, MUST BE INSTALLED IN THE CONDUIT BEFORE UTILITY COMPANY IS NOTIFIED TO INSTALL CABLE. THE STRING SHOULD BE BLOWN INTO THE CONDUIT AFTER THE RUN IS ASSEMBLED TO AVOID BONDING THE STRING TO THE CONDUIT.  
 5. UTILITY COMPANY MUST BE GIVEN THE OPPORTUNITY TO INSPECT THE CONDUIT PRIOR TO BACKFILL. THE CONTRACTOR IS RESPONSIBLE FOR ALL REPAIRS SHOULD THE UTILITY COMPANY BE UNABLE TO INSTALL ITS CABLE IN A SUITABLE MANNER.  
 6. ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND, WHERE APPLICABLE, THE NATIONAL ELECTRIC CODE.  
 7. ALL 90° SWEEPS WILL BE MADE USING RIGID GALVANIZED STEEL. SWEEPS WITH A 36 TO 48 INCH RADIUS.  
 8. SAND BEDDING TO BE REPLACED WITH CONCRETE ENCASEMENT WHERE COVER IS LESS THAN 3 FEET, WHEN LOCATED BELOW PAVEMENT, OR WHERE SHOWN ON THE UTILITIES PLAN.


**ELECTRICAL AND COMMUNICATION CONDUIT**  
 NO SCALE



| POLE HEIGHT | DEPTH (BURIED) | BASE DIAMETER | VERTICAL REINFORCEMENT |
|-------------|----------------|---------------|------------------------|
| <16'        | 72" (MIN.)     | 18"           | 6 - #6                 |
| >16'        | 72" (MIN.)     | 24"           | 6 - #8                 |

NOTES:  
 1. ALL LIGHT POLES, LUMINARIES AND WIRE TO BE FURNISHED BY THE CONTRACTOR UNLESS OTHERWISE DIRECTED.  
 2. CONTRACTOR SHALL VERIFY BOLT TEMPLATE AND ANCHOR BOLT SIZE WITH POLE MANUFACTURER PRIOR TO CONSTRUCTION.  
 3. CONCRETE SHALL BE 4,000 PSI CLASS A, PRE-CAST CONCRETE.  
 4. REINFORCEMENT SHALL BE ASTM A615, GRADE 60.  
 5. FOR LIGHT POLES GREATER THAN 20' IN HEIGHT, THE LIGHT POLE BASE SHALL BE DESIGNED AND STAMPED BY A STRUCTURAL ENGINEER LICENSED IN THE STATE OF NEW HAMPSHIRE.

**TYPICAL LIGHT POLE BASE**  
 NO SCALE



NOTES:  
 1. 14" X 14" CONCRETE PULL BOX, NHDOT ITEM 614.511

**CONCRETE PULL BOX**  
 NO SCALE

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE       | DESCRIPTION    |
|------|------------|----------------|
| E    | 10/23/2024 | TAC SUBMISSION |
| D    | 9/18/2024  | TAC SUBMISSION |
| C    | 8/28/2024  | CC SUBMISSION  |
| B    | 6/17/2024  | TAC SUBMISSION |
| A    | 4/22/2024  | TAC SUBMISSION |

PROJECT NO: E5071-001  
 DATE: 4/22/2024  
 FILE: E5071-001-C-DTLS.dwg  
 DRAWN BY: BKC/NHW  
 DESIGNED/CHECKED BY: NAH  
 APPROVED BY: PMC

DETAILS SHEET

SCALE: AS SHOWN

C-809

## LAYOUT AND MATERIALS NOTES

1. REVIEW CONTRACT DOCUMENTS AND FIELD CONDITIONS BEFORE COMMENCING WORK. REPORT ERRORS, OMISSIONS, OR INCONSISTENCIES PROMPTLY TO THE LANDSCAPE ARCHITECT.
2. CONTACT UTILITY COMPANIES AS REQUIRED BY STATE AND LOCAL REGULATIONS BEFORE DIGGING. LOCATE AND MARK EXISTING UTILITIES.
3. THE CONTRACTOR SHALL OBTAIN ALL PERMITS WHICH ARE NECESSARY TO PERFORM THE PROPOSED WORK.
4. WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS.
5. DIMENSIONS REFERRED TO AS "EQUAL" INDICATE SPACING WHICH IS EQUIDISTANT MEASURED TO THE CENTERLINES.
6. MEASUREMENTS ARE TO THE FINISHED FACE OF BUILDINGS, WALLS, OR OTHER FIXED SITE IMPROVEMENTS. DIMENSIONS TO CENTERLINES ARE IDENTIFIED.
7. INSTALL INTERSECTING ELEMENTS AT 90-DEGREE ANGLES, UNLESS OTHERWISE NOTED.
8. PROVIDE EXPANSION JOINTS WHERE FLATWORK MEETS VERTICAL STRUCTURES, SUCH AS WALLS, CURBS, STEPS, AND OTHER HARDSCAPE.
9. CONTROL JOINTS SHOULD BE SPACED NO GREATER THAN TEN (10) LINEAR FEET MAXIMUM, UNLESS OTHERWISE SPECIFIED.
10. CONTROL JOINT RECOMMENDATIONS TO MINIMIZE CRACKING SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL.
11. ALL TOP OF WALLS AND FENCES ARE TO BE HELD LEVEL, UNLESS OTHERWISE SPECIFIED.
12. SAMPLES OF SPECIFIED MATERIALS SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO ORDERING.
13. THE CONTRACTOR SHALL PROVIDE A FULL-SCALE MOCKUP AND RECEIVE APPROVAL FROM THE LANDSCAPE ARCHITECT BEFORE BEGINNING CONSTRUCTION OF PAVEMENT.
14. ALL SITE FURNITURE LOCATIONS ARE TO BE STAKED BY CONTRACTOR AND APPROVED BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.

## PLANTING NOTES

1. CONTACT UTILITY COMPANIES AS REQUIRED BY STATE AND LOCAL REGULATIONS BEFORE DIGGING. LOCATE AND MARK EXISTING UTILITIES.
2. REFER TO CIVIL ENGINEER'S GRADING PLANS FOR FINAL GRADING AND UTILITY LOCATIONS.
3. THE CONTRACTOR SHALL OBTAIN ALL PERMITS WHICH ARE NECESSARY TO PERFORM THE PROPOSED WORK.
4. LANDSCAPE ARCHITECT TO REVIEW PLANT MATERIALS AT SOURCE OR BY PHOTOGRAPHS PRIOR TO DIGGING OR SHIPPING OF PLANT MATERIAL.
5. CONTRACTOR IS TO VERIFY ALL QUANTITIES. IF QUANTITIES ON PLANT LIST DIFFER FROM GRAPHIC INDICATIONS, GRAPHICS SHALL PREVAIL.
6. EXACT LOCATIONS OF TREES AND B&B SHRUBS ARE TO BE STAKED BY THE CONTRACTOR FOR LANDSCAPE ARCHITECT REVIEW AND APPROVAL PRIOR TO INSTALLATION. THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO ADJUST PLANTS TO EXACT LOCATION IN THE FIELD.
7. PLANT MATERIAL NOT MEETING THE STANDARDS CONTAINED WITHIN CONTRACT DOCUMENTS SHALL BE REPLACED AT NO COST TO THE OWNER.
8. PROVIDE MATCHING SIZES AND FORMS FOR EACH PLANT OF THE SAME SPECIES DESIGNATED ON THE DRAWINGS UNLESS OTHERWISE INDICATED.
9. ALL PLANT MATERIAL IS TO BE INSTALLED PLUMB/PER THE SPECIFICATIONS CONTAINED WITHIN THE CONTRACT DOCUMENTS.
10. PRUNE EXISTING AND/OR NEWLY PLANTED TREES ONLY AS DIRECTED BY THE LANDSCAPE ARCHITECT.
11. PLANT MATERIAL SHALL HAVE ALL WIRE, TWINE, BASKETS, BURLAP, AND ALL OTHER NON-BIODEGRADABLE CONTAINMENT MATERIAL REMOVED FROM THE TRUNK AND/OR ROOT BALL OF THE PLANT PRIOR TO PLANTING. ROOT BALLS SHALL BE FREE OF WEEDS.
12. FINISH GRADE OF PLANTING BEDS SHALL BE ONE (1) INCH BELOW ADJACENT PAVER OR HEADER, UNLESS OTHERWISE SPECIFIED.
13. MULCH OR PLANTING BED DRESSING SHALL BE PLACED IN ALL PLANTING AREAS AS SPECIFIED. MULCH OR PLANTING BED DRESSING SHALL NOT BE PLACED WITHIN SIX (6) INCHES OF TREE TRUNKS. MULCHING SHOULD BE REPEATED ANNUALLY DURING THE AUTUMN TO A 3" DEPTH, SOIL PEP MULCH SHALL BE USED UNLESS OTHERWISE SPECIFIED..
14. ALL PLANT MATERIAL SHOULD RECEIVE AN ORGANIC FERTILIZER IN LIMITED APPLICATION FOLLOWING INSTALLATION. TYPE AND APPLICATION RATE AND METHOD OF APPLICATION TO BE SPECIFIED BY THE CONTRACTOR & APPROVED BY THE LANDSCAPE ARCHITECT.
15. STOCKPILED PLANT MATERIAL TO BE PLACED IN THE SHADE AND PROPERLY HAND-WATERED UNTIL PLANTED.
16. PRESERVE & PROTECT ALL EXISTING VEGETATION INDICATED TO REMAIN AT ALL TIMES.
17. TO THE GREATEST EXTENT POSSIBLE, TOPSOIL THAT IS REMOVED DURING CONSTRUCTION SHALL BE STOCKPILED FOR LATER USE IN AREAS REQUIRING REVEGETATION/PLANTING.
18. ALL MATERIALS USED SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY THE CURRENT AMERICAN STANDARDS FOR NURSERY STOCK, PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
19. ALL DISTURBED AREAS ARE TO BE REVEGETATED

## SEEDING NOTES

1. REVEGETATED AREAS ARE TO BE HYRO-SEEDED, FOLLOWED BY THE APPLICATION OF STRAW MULCH.
2. APPLY STRAW MULCH AT A MINIMUM RATE OF 1.5 TONS PER ACRE OF AIR DRY MATERIAL. SPREAD STRAW MULCH UNIFORMLY OVER THE AREA WITH MECHANICAL MULCH SPREADER/CRIMPER. DO NOT MULCH WHEN WIND VELOCITY EXCEEDS 10 MPH.
3. IMMEDIATELY UPON COMPLETION OF THE MULCHING AND BINDING OPERATION, THE SEEDED AREAS SHALL BE IRRIGATED, KEEPING THE TOP 2 INCHES OF SOIL EVENLY MOIST UNTIL SEED HAS UNIFORMLY GERMINATED AND GROWN TO A HEIGHT OF 2 INCHES.
4. WATERING APPLICATION SHALL BE DONE IN A MANNER WHICH WILL PROVIDE UNIFORM COVERAGE BUT WHICH WILL NOT CAUSE EROSION, MOVEMENT, OR DAMAGE TO THE FINISHED SURFACE.

## GRADING AND DRAINAGE NOTES

1. MATERIALS/WASTE CREATED BY REMOVAL PROCEDURES SHALL BE LEGALLY DISPOSED OF AWAY FROM THE JOB SITE.
2. NOTIFY LOCAL UNDERGROUND SERVICE COMPANIES FOR UTILITY FINDS 48 HOURS PRIOR TO ANY EXCAVATION.
3. THE CONTRACTOR IS TO REVIEW ARCHITECTURAL DRAWINGS FOR THE VERIFICATION OF CONNECTIONS TO DRAINS OVER STRUCTURE.
4. THE CONTRACTOR IS TO REVIEW ARCHITECTURAL DRAWINGS FOR THE VERIFICATION OF WATERPROOFING OF SLAB PENETRATIONS.
5. THE CONTRACTOR IS TO REVIEW CIVIL ENGINEER'S DRAWINGS FOR THE VERIFICATION OF CONNECTIONS TO DRAINS.
6. GRADING AND EXCAVATION WORK SHALL BE COMPLETED DURING DRY AND NON-FREEZING CONDITIONS.
7. POSITIVE DRAINAGE SHALL BE PROVIDED AWAY FROM ALL STRUCTURES.
8. SOIL COMPACTION SHALL BE 95% PROCTOR DENSITY MINIMUM BENEATH PAVEMENTS, STEPS, WALLS AND LIGHT FOUNDATIONS, UNLESS OTHERWISE SPECIFIED.

## ABBREVIATIONS TABLE

|        |                          |       |                          |
|--------|--------------------------|-------|--------------------------|
| APPROX | APPROXIMATE              | MH    | MANHOLE                  |
| ARCH   | ARCHITECT                | MIN   | MINIMUM                  |
| AVG    | AVERAGE                  | MISC  | MISCELLANEOUS            |
| B+B    | BALED AND BURLAPPED      | N     | NORTH                    |
| BF     | BOTTOM OF FOOTING        | NIC   | NOT IN CONTRACT          |
| BLDG   | BUILDING                 | NO    | NUMBER                   |
| BM     | BENCHMARK                | NOM   | NOMINAL                  |
| BOC    | BACK OF CURB             | NTS   | NOT TO SCALE             |
| BR     | BOTTOM OF RAMP           | OC    | ON CENTER                |
| BS     | BOTTOM OF STEP           | OD    | OUTSIDE DIAMETER         |
| BW     | BOTTOM OF WAL            | OPP   | OPPOSITE                 |
| CAL    | CALIPER                  | PAR   | PARALLEL                 |
| CAP    | CAPACITY                 | PC    | POINT OF CURVATURE       |
| CF     | CUBIC FEET               | PE    | POLYURETHANE             |
| CHAM   | CHAMFER                  | PERF  | PERFORATED               |
| CIP    | CAST IN PLACE            | PED   | PEDESTRIAN               |
| CJ     | CONTROL JOINT            | PI    | POINT OF INTERSECTION    |
| CL     | CENTER LINE              | PL    | PROPERTY LINE            |
| CLR    | CLEARANCE                | PT    | POINT, POINT OF TANGENCY |
| CM     | CENTIMETER               | PVC   | POLYVINYL CHLORIDE       |
| CO     | CLEAN OUT                | PVMT  | PAVEMENT                 |
| COMP   | COMPACTED                | PVR   | PAVER                    |
| CONC   | CONCRETE                 | QTY   | QUANTITY                 |
| CONST  | CONSTRUCTION             | R     | RADIUS                   |
| CONT   | CONTINUOUS               | REF   | REFERENCE                |
| CONTR  | CONTRACTOR               | REINF | REINFORCE(D)             |
| CU     | CUBIC                    | REQ'D | REQUIRED                 |
| CY     | CUBIC YARD               | REV   | REVISION, REVISED        |
| DEMO   | DEMOLISH, DEMOLITION     | ROW   | RIGHT OF WAY             |
| DIA    | DIAMETER                 | RT    | RIGHT                    |
| DIM    | DIMENSION                | S     | SOUTH                    |
| DTL    | DETAIL                   | SS    | SANITARY SEWER           |
| DWG    | DRAWING                  | SCH   | SCHEDULE                 |
| E      | EAST                     | SD    | STORM DRAIN              |
| EA     | EACH                     | SEC   | SECTION                  |
| EJ     | EXPANSION JOINT          | SF    | SQUARE FOOT (FEET)       |
| EL     | ELEVATION                | SHT   | SHEET                    |
| ELEC   | ELECTRICAL               | SIM   | SIMILAR                  |
| ENG    | ENGINEER                 | SNT   | SEALANT                  |
| EQ     | EQUAL                    | SPECS | SPECIFICATIONS           |
| EQUIP  | EQUIPMENT                | SQ    | SQUARE                   |
| EST    | ESTIMATE                 | ST    | STORM SEWER              |
| E.W.   | EACH WAY                 | SY    | SQUARE YARD              |
| EXIST  | EXISTING                 | STA   | STATION                  |
| EXP    | EXPANSION, EXPOSED       | STD   | STANDARD                 |
| FFE    | FINISHED FLOOR ELEVATION | STL   | STEEL                    |
| FG     | FINISHED GRADE           | STRL  | STRUCTURAL               |
| FIN    | FINISH                   | SYM   | SYMMETRICAL              |
| FL     | FLOW LINE                | T&B   | TOP AND BOTTOM           |
| FOW    | FACE OF WAL              | TBC   | TOP OF BACK CURB         |
| FT     | FOOT (FEET)              | TC    | TOP OF CURB              |
| FTG    | FOOTING                  | TF    | TOP OF FOOTING           |
| GA     | GAUGE                    | TRANS | ELECTRIC TRANSFORMER     |
| GAL    | GALVANIZED               | TOC   | TOP OF CONCRETE          |
| GEN    | GENERAL                  | TOPO  | TOPOGRAPHY               |
| HORIZ  | HORIZONTAL               | TSL   | TOP OF SLAB              |
| HP     | HIGH POINT               | TR    | TOP OF RAMP              |
| HT     | HEIGHT                   | TS    | TOP OF STEP              |
| ID     | INSIDE DIAMETER          | TW    | TOP OF WAL               |
| INV    | INVERT ELEVATION         | TYP   | TYPICAL                  |
| IN     | INCH(ES)                 | VAR   | VARIES                   |
| INCL   | INCLUDE(D)               | VERT  | VERTICAL                 |
| IRR    | IRRIGATION               | VEH   | VEHICLE                  |
| JT     | JOINT                    | VOL   | VOLUME                   |
| LIN    | LINEAR                   | W/    | WITH                     |
| LF     | LINEAR FEET              | W/O   | WITHOUT                  |
| LP     | LOW POINT                | WT    | WEIGHT                   |
| LT     | LIGHT                    | WWF   | WELDED WIRE FABRIC       |
| MATL   | MATERIAL                 | YD    | YARD                     |
| MAX    | MAXIMUM                  | @     | AT                       |
| MEMB   | MEMBRANE                 |       |                          |
| MD     | MAIN DISCONNECT SWITCH   |       |                          |



SEAL

PROJECT TITLE

100 Durgin Ln

PREPARED FOR

100 DURGIN LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH, NH

REVISIONS DATE

|       |       |
|-------|-------|
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |
| _____ | _____ |

ISSUE DATE

October 23, 2024

SHEET TITLE

NOTES


SHEET INFORMATION

NOTICE OF CONSTRUCTION  
L-0-01

| REVISIONS | DATE |
|-----------|------|
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

MATERIAL LEGEND


|  |   |
|--|---|
|  | BITUMINOUS PAVING                       |
|  | ENHANCED PAVING (CIP, UNIT PAVER, TBD.) |
|  | WOOD DECK                               |
|  | STONEDUST                               |
|  | GRAVEL DRIP EDGE                        |



SITE KEYNOTES:

| 1.0 | PAVEMENTS, RAMPS, CURBS | DETAIL / SHEET |
|-----|-------------------------|----------------|
| 1.1 | BITUMINOUS PATH         | 1/L5-00        |
| 1.2 | CIP CONCRETE            | 2/L5-00        |
| 1.3 | STONE DUST WALK         | 5/L5-00        |
| 1.4 | GRAVEL DRIP EDGE        | 6/L5-00        |
| 2.0 | JOINTING                |                |
| 2.1 | EXPANSION JOINT         | 3/L5-00        |
| 2.2 | CONTROL JOINT           | 4/L5-00        |
| 3.0 | STEPS                   |                |
| 3.1 | CONCRETE STEPS          | 7/L5-00        |
| 3.2 | RECLAIMED GRANITE STEPS | 8/L5-00        |
| 4.0 | SITE WALLS/ EMBANKMENTS |                |
| 4.1 | WALL - CONCRETE         | 1/L5-01        |
| 5.0 | SITE FURNITURE          |                |
| 5.1 | WOOD TOP BENCH          | 2/L5-01        |
| 5.2 | WOOD PLATFORM DECK      | 3/L5-01        |
| 5.3 | BICYCLE RACK            | 4/L5-01        |

| 6.0  | RAILINGS, BARRIERS, FENCING | DETAIL / SHEET |
|------|-----------------------------|----------------|
| 6.1  | HAND RAILING                | 5/L5-01        |
| 6.2  | GUARD RAIL                  | 3/L5-03        |
| 7.0  | SITE LIGHTING               |                |
| 7.1  | BOLLARD LIGHT BASE          | 2/L5-02        |
| 7.2  | POLE LIGHT BASE             | 1/L5-02        |
| 7.3  | CATENARY LIGHT BASE         | 3/L5-02        |
| 8.0  | DRAINAGE                    |                |
| X.X  | NOT USED AT THIS TIME       | X/XX-XX        |
| 9.0  | PLANTING AND LANDSCAPE      |                |
| 9.1  | DECIDUOUS TREE PLANTING     | 1/L5-04        |
| 9.2  | CONIFEROUS TREE PLANTING    | 2/L5-04        |
| 9.3  | SHRUB PLANTING              | 4/L5-04        |
| 9.4  | PERENNIAL/GRASS PLANTING    | 3/L5-04        |
| 9.5  | LANDSCAPE EDGING            | 5/L5-04        |
| 10.0 | MISCELLANEOUS ELEMENTS      |                |
| 10.1 | WATER FEATURE POP JET       | 5/L5-02        |
| 10.2 | ADDRESS MARKER              | 4/L5-02        |
| 10.3 | OBSERVATION DECK            | 1/L5-03        |
| 10.4 | INTERPRETIVE SIGNAGE        | 2/L5-03        |



| NO. | DESCRIPTION | DATE |
|-----|-------------|------|
|     |             |      |
|     |             |      |
|     |             |      |
|     |             |      |
|     |             |      |
|     |             |      |
|     |             |      |
|     |             |      |
|     |             |      |

POTENTIAL PLANT SCHEDULE


| SYMB.   | BOTANICAL NAME                 | COMMON NAME               | QTY.  | SIZE         | MATURE SIZE      | SPACING  |
|---|--------------------------------|---------------------------|-------|--------------|------------------|----------|
| <b>TREES</b>  |                                |                           |       |              |                  |          |
| QP  | QUERCUS PALUSTRIS              | PIN OAK                   | 96    | 3" CAL. MIN. | 30' W, 70' T     | PER PLAN |
| AR  | ACER RUBRUM 'BOWHALL'          | BOWHALL MAPLE             | 70    | 3" CAL. MIN. | 15' W, 45' T     | PER PLAN |
| OR  | QUERCUS ROBUR X BICOLOR 'LONG' | REGAL PRINCE OAK          | 31    | 3" CAL. MIN. | 15' W, 40' T     | PER PLAN |
| AS  | ACER SACCHARUM                 | SUGAR MAPLE               | 12    | 3" CAL. MIN. | 40' W, 60' T     | PER PLAN |
| BP  | BETULA Papyrifera              | PAPER BIRCH (SINGLE-STEM) | 34    | 3" CAL. MIN. | 20' W, 35' T     | PER PLAN |
| AC  | AMELANCHIER CANADENSIS         | SERVICEBERRY (MULTI-STEM) | 53    | 8' HT. B&B   | 15' W, 25' T     | PER PLAN |
| <b>TREES - EVERGREEN</b>                              |                                |                           |       |              |                  |          |
| AB  | ABIES BALSAMEA 'COOKS'         | BALSAM FIR 'COOKS'        | 56    | 7-8'         | 25' W, 75' T     | PER PLAN |
| TC  | TSUGA CANADENSIS               | EASTERN HEMLOCK           | 7     | 7-8'         | 35' W, 70' T     | PER PLAN |
| TO  | THUJA OCCIDENTALIS             | ARBORVITAE                | 7     | 7-8'         | 10' W, 40' T     | PER PLAN |
| <b>SHRUBS</b>   |                                |                           |       |              |                  |          |
| MP  | MYRICA PENNSYLVANICA           | BAYBERRY                  | 921   | #5           | 6-8' W, 6-8' T   | PER PLAN |
| CA  | CLETHRA ALNIFOLIA              | SUMMER SWEET              | 341   | #2           | 4-6' W, 5-8' T   | PER PLAN |
| VA  | VIBURNUM ACERIFOLIUM           | MAPLELEAF VIBURNUM        | 1,045 | #2           | 2-4' W, 3-6' T   | PER PLAN |
| RA  | RHUS AROMATICA                 | LOW-GRO SUMAC             | 1,229 | #2           | 5-6' W, 2' T     | PER PLAN |
| MG  | MYRICA GALE                    | SWEETGALE                 | 298   | #2           | 3-6' W, 2-5' T   | PER PLAN |
| JH  | JUNIPERUS HORIZONTALIS         | CREeping JUNIPER          | 581   | #2           | 6-8' W, 1.5' T   | PER PLAN |
| <b>PERENNIALS, ORNAMENTAL GRASSES AND GROUNDCOVER</b> |                                |                           |       |              |                  |          |
| AU  | TIARELLA CORDIFOLIA            | FOAMFLOWER                | 445   | #1           | 1-2' W, 1' T     | 12" O.C. |
| N   | NEPETA                         | CATMINT                   | 325   | #1           | 1-2' W, 1-2' T   | 12" O.C. |
| SS  | SALVIA YANGII                  | RUSSIAN SAGE              | 368   | #1           | 2-4' W, 3-5' T   | 18" O.C. |
| SY  | SCHIZACHYRIUM SCOPARIUM        | LITTLE BLUESTEM           | 1,964 | #1           | 2-3' W, 2-3' T   | 18" O.C. |
| CAC   | CALAMAGROSTIS X ACUTIFLORA     | KARL FOERSTER GRASS       | 2,818 | #1           | 2-3' W, 3-5' T   | 24" O.C. |
| BG  | BOUTELOUA GRACILIS             | BLUE GRAMA                | 1,079 | #1           | 2-3' W, 1-1.5' T | 18" O.C. |
| P   | PANICUM                        | SWITCHGRASS               | 2,112 | #1           | 2-3' W, 4-5' T   | 18" O.C. |
| CP  | CAREX PENNSYLVANICA            | PENNSYLVANIA SEDGE        | 190   | #1           | 1' W, 1' T       | 12" O.C. |
| PA  | POLYSTICHUM ACROSTICHOIDES     | CHRISTMAS FERN            | 1,449 | #1           | 1-2' W, 1-2' T   | 12" O.C. |
| SP  | SITOBOLIMUM PUNCTILOBULUM      | HAY SCENTED FERN          | 373   | #1           | 3' W, 2' T       | 24" O.C. |

| SYMB.                           | DESCRIPTION   | QTY.  | NOTES |
|---------------------------------|---|---|-------|
| LOAM & SEED                     | 29,241 SF   | TURF GRASS MIX PER PLAN, SEE SEED SUPPLIER SPEC. FOR APPLICATION RATE   |       |
| NATIVE WETLAND GRASSES MIX SEED | 101,503 SF  | NATIVE GRASS MIX PER PLAN, SEE SEED SUPPLIER SPEC. FOR APPLICATION RATE |       |
|                                 | FOX SEDGE (CAREX VULPINOIDEA), LURID SEDGE (CAREX LURIDA), BLUNT BROOM SEDGE (CAREX SCOPARIA), BLUE VERVAIN (VERBENA HASTATA), FOWL BLUEGRASS (POA PALUSTRIS), HOP SEDGE (CAREX LUPULINA), GREEN BULRUSH (SCIRPUS ATROVIRENS), CREEPING SPIKE RUSH (ELEOCHARIS PALUSTRIS), FRINGED SEDGE (CAREX CRINITA), SOFT RUSH (JUNCUS EFFUSUS), SPOTTED JOE PYE WEED (EUPATORIUM MACULATUM), RATTLESNAKE GRASS (GLYCERIA CANADENSIS), SWAMP ASTER (ASTER PUNICEUS), BLUEFLAG (IRIS VERSICOLOR), SWAMP MILKWEED (ASCLEPIAS INCARNATA), SQUARE STEMMED MONKEY FLOWER (MIMULUS RINGENS)                          |   |       |
| NATIVE MEADOW MIX SEED          | 23,801 SF   | MEADOW MIX PER PLAN, SEE SEED SUPPLIER SPEC. FOR APPLICATION RATE       |       |
|                                 | VIRGINIA WILD RYE (ELYMUS VIRGINICUS), LITTLE BLUESTEM (SCHIZACHYRIUM SCOPARIUM), BIG BLUESTEM (ANDROPOGON GERARDII), RED FESCUE (FESTUCA RUBRA), SWITCH GRASS (PANICUM VIRGATUM), PARTRIDGE PEA (CHAMAECRISTA FASCICULATA), PANICLELEAF TICK TREFOL (DESMODIUM PANICULATUM), INDIAN GRASS (SORGHASTRUM NUTANS), BLUE VERVAIN (VERBENA HASTATA), BUTTERFLY MILKWEED (ASCLEPIAS TUBEROSA), BLACK EYED SUSAN (RUDBECKIA HIRTA), COMMON SNEEZEWEED (HELENIUM AUTUNNALE), HEATH ASTER (ASTER PILOSUS/SYMPHYOTRICHUM PILOSUM), EARLY GOLDENROD (SOLIDAGO JUNCEA), UPLAND BENTGRASS (AGROSTIS PERENNANS). |   |       |

SITE KEYNOTES:

|     |                         |                |      |                             |                |
|-----|-------------------------|----------------|------|-----------------------------|----------------|
| 1.0 | PAVEMENTS, RAMPS, CURBS | DETAIL / SHEET | 6.0  | RAILINGS, BARRIERS, FENCING | DETAIL / SHEET |
| 1.1 | BITUMINOUS PATH         | 1/L5-00        | 6.1  | HAND RAILING                | 5/L5-01        |
| 1.2 | CIP CONCRETE            | 2/L5-00        | 6.2  | GUARD RAIL                  | 3/L5-03        |
| 1.3 | STONE DUST WALK         | 5/L5-00        | 7.0  | SITE LIGHTING               |                |
| 1.4 | GRAVEL DRIP EDGE        | 6/L5-00        | 7.1  | BOLLARD LIGHT BASE          | 2/L5-02        |
| 2.0 | JOINTING                |                | 7.2  | POLE LIGHT BASE             | 1/L5-02        |
| 2.1 | EXPANSION JOINT         | 3/L5-00        | 7.3  | CATENARY LIGHT BASE         | 3/L5-02        |
| 2.2 | CONTROL JOINT           | 4/L5-00        | 8.0  | DRAINAGE                    |                |
| 3.0 | STEPS                   |                | X.X  | NOT USED AT THIS TIME       | X/XX-XX        |
| 3.1 | CONCRETE STEPS          | 7/L5-00        | 9.0  | PLANTING AND LANDSCAPE      |                |
| 3.2 | RECLAIMED GRANITE STEPS | 8/L5-00        | 9.1  | DECIDUOUS TREE PLANTING     | 1/L5-04        |
| 4.0 | SITE WALLS/ EMBANKMENTS |                | 9.2  | CONIFEROUS TREE PLANTING    | 2/L5-04        |
| 4.1 | WALL - CONCRETE         | 1/L5-01        | 9.3  | SHRUB PLANTING              | 4/L5-04        |
| 5.0 | SITE FURNITURE          |                | 9.4  | PERENNIAL/GRASS PLANTING    | 3/L5-04        |
| 5.1 | WOOD TOP BENCH          | 2/L5-01        | 9.5  | LANDSCAPE EDGING            | 5/L5-04        |
| 5.2 | WOOD PLATFORM DECK      | 3/L5-01        | 10.0 | MISCELLANEOUS ELEMENTS      |                |
| 5.3 | BICYCLE RACK            | 4/L5-01        | 10.1 | WATER FEATURE POP JET       | 5/L5-02        |
|     |                         |                | 10.2 | ADDRESS MARKER              | 4/L5-02        |
|     |                         |                | 10.3 | OBSERVATION DECK            | 1/L5-03        |
|     |                         |                | 10.4 | INTERPRETIVE SIGNAGE        | 2/L5-03        |

- NOTES:
- LANDSCAPED AREAS SHALL PRIORITIZE NATIVE DROUGHT TOLERANT SPECIES TO MINIMIZE IRRIGATION.
  - ALL IRRIGATION SHALL COMPLY WITH SECTION 6.11 OF THE CITY OF PORTSMOUTH SITE PLAN REVIEW REGULATIONS
  - PLANTING PLAN AND LAYOUT DEPICTED FOR PLANNING PURPOSES ONLY AND SUBJECT TO MODIFICATION BY LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION.




| REVISIONS | DATE |
|-----------|------|
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |




NOTE: ALL SITE LIGHTING FIXTURES ARE DARK SKY COMPLIANT.

| Luminaire Schedule Symbol | Qty | Label   | Arrangement    | Description  | Tag  | LLF   | Luminaire Lumens | Luminaire Watts | Total Watts |
|---------------------------|-----|---------|----------------|--|--|-------|------------------|-----------------|-------------|
| B3                        | 16  | B3      | Single         | NLS: TBL-42-T-16L-40-30R7-URV-AB-CXX                                 |  | 1.000 | 2151             | 18              | 288         |
| QA                        | 4   | QA      | Single         | COOPER: GALN-SALC-730-D-SLQ-CXX                                      | MOUNTED ON 20' VALMONT POLE: DS330-400200-D1-FE-COOPER CXX-FRC-AB                    | 0.900 | 6467             | 57              | 228         |
| Q1                        | 2   | Q1      | Single         | COOPER: GALN-SAZ2-730-D-SLQ-CXX                                      | MOUNTED ON 20' VALMONT POLE: DS330-400200-D1-FE-COOPER CXX-FRC-AB                    | 0.900 | 14762            | 158             | 214         |
| GH-HSS                    | 19  | GH-HSS  | Single         | COOPER: GALN-SAZ2-730-D-P477-CXX-HSS                                 | MOUNTED ON 20' VALMONT POLE: DS330-400200-D1-FE-COOPER CXX-FRC-AB                    | 0.900 | 10272            | 125             | 2375        |
| GA-2                      | 6   | GA-2    | 2 @ 90 Degrees | COOPER: GALN-SAZ2-730-D-T4M-CXX                                      | MOUNTED ON 20' VALMONT POLE: DS330-400200-D1-FE-COOPER CXX-FRC-AB                    | 0.900 | 8784             | 63              | 174         |
| GAH-HSS                   | 2   | GAH-HSS | Single         | COOPER: GALN-SAZ2-730-D-T4M-CXX-HSS                                  | MOUNTED ON 20' VALMONT POLE: DS330-400200-D1-FE-COOPER CXX-FRC-AB                    | 0.900 | 10249            | 125             | 250         |
| GA                        | 1   | GA      | Single         | COOPER: GALN-SAZ2-730-D-SM-CXX                                       | MOUNTED ON 20' VALMONT POLE: DS330-400200-D1-FE-COOPER CXX-FRC-AB                    | 0.900 | 8784             | 63              | 167         |
| GA-2                      | 1   | GA-2    | Back-Back      | COOPER: GALN-SAZ2-730-D-SM-CXX                                       | MOUNTED ON 20' VALMONT POLE: DS330-400200-D1-FE-COOPER CXX-FRC-AB                    | 0.900 | 8784             | 63              | 126         |
| GSB                       | 2   | GSB     | Single         | COOPER: GALN-SAZ2-730-D-SM-CXX                                       | MOUNTED ON 20' VALMONT POLE: DS330-400200-D1-FE-COOPER CXX-FRC-AB                    | 0.900 | 10930            | 82              | 164         |
| FP                        | 11  | FP      | Single         | NLS: FRC-T-14L-75-SM-200V-HSS-CXX-16                                 | MOUNTED ON 14' POLE, INCLUDED WITH FIXTURE   | 0.900 | 4412             | 36              | 396         |
| FI                        | 150 | FI      | Single         | PIVOLI: 1512-B-18-S-30-F-12 // POWER AND LEAD WIRES // MOUNTING POLE | 15' 44" RUBS, GLOBES SPACED 18 IN // CONTRACTOR TO CONFIRM LENGTH // MOUNTED 10' AFF | 0.900 | 5                | 0.2             | 39          |
| MI                        | 157 | MI      | Single         | MACT: WS-W20200-10-CXX   | MOUNTED ON 14' POLE, INCLUDED WITH FIXTURE   | 0.900 | 282              | 5.7             | 534         |


| Label                | Units | Avg  | Max  | Min | Avg/Min | Max/Min |
|----------------------|-------|------|------|-----|---------|---------|
| ENTIRE AREA          | Fc    | 0.28 | 35.3 | 0.0 | N/A     | N/A     |
| DAYS CENTRAL PARKING | Fc    | 1.63 | 3.4  | 0.3 | 4.10    | 11.33   |
| RAIN STREET          | Fc    | 1.19 | 4.7  | 0.3 | 3.97    | 15.67   |
| NORTH PARKING        | Fc    | 1.61 | 2.9  | 0.1 | 14.10   | 29.00   |
| NORTHEAST PARKING    | Fc    | 1.23 | 3.5  | 0.3 | 4.03    | 11.67   |
| SOUTHEAST PARKING    | Fc    | 1.20 | 4.2  | 0.3 | 4.25    | 14.00   |
| SOUTHWEST PARKING    | Fc    | 1.17 | 3.8  | 0.3 | 3.90    | 12.67   |
| WEST CENTRAL PARKING | Fc    | 1.11 | 3.7  | 0.1 | 11.10   | 37.00   |




| REVISIONS | DATE |
|-----------|------|
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |




**1** Bituminous Paving  
1":1'-0"  
1.1




**2** CIP Concrete  
1":1'-0"  
1.2




**3** Expansion Joint  
NTS  
2.1




**4** Control Joint  
NTS  
2.2



**5** Stone Dust  
1":1'-0"  
1.3



**6** Gravel Drip Edge  
1":1'-0"  
1.4



**7** Concrete Steps  
1":2'-0"  
3.1

SITE KEYNOTES:

| 1.0 PAVEMENTS, RAMPS, CURBS | DETAIL / SHEET |
|-----------------------------|----------------|
| 1.1 BITUMINOUS PATH         | 1/L5-00        |
| 1.2 CIP CONCRETE            | 2/L5-00        |
| 1.3 STONE DUST WALK         | 5/L5-00        |
| 1.4 GRAVEL DRIP EDGE        | 6/L5-00        |


| 6.0 RAILINGS, BARRIERS, FENCING | DETAIL / SHEET |
|---------------------------------|----------------|
| 6.1 HAND RAILING                | 5/L5-01        |
| 6.2 GUARD RAIL                  | 3/L5-03        |

| 7.0 SITE LIGHTING       | DETAIL / SHEET |
|-------------------------|----------------|
| 7.1 BOLLARD LIGHT BASE  | 2/L5-02        |
| 7.2 POLE LIGHT BASE     | 1/L5-02        |
| 7.3 CATENARY LIGHT BASE | 3/L5-02        |

| 8.0 DRAINAGE              | DETAIL / SHEET |
|---------------------------|----------------|
| X.X NOT USED AT THIS TIME | X/XX-XX        |

| 9.0 PLANTING AND LANDSCAPE   | DETAIL / SHEET |
|------------------------------|----------------|
| 9.1 DECIDUOUS TREE PLANTING  | 1/L5-04        |
| 9.2 CONIFEROUS TREE PLANTING | 2/L5-04        |
| 9.3 SHRUB PLANTING           | 4/L5-04        |
| 9.4 PERENNIAL/GRASS PLANTING | 3/L5-04        |
| 9.5 LANDSCAPE EDGING         | 5/L5-04        |

| 10.0 MISCELLANEOUS ELEMENTS | DETAIL / SHEET |
|-----------------------------|----------------|
| 10.1 WATER FEATURE POP JET  | 5/L5-02        |
| 10.2 ADDRESS MARKER         | 4/L5-02        |
| 10.3 OBSERVATION DECK       | 1/L5-03        |
| 10.4 INTERPRETIVE SIGNAGE   | 2/L5-03        |




**8** Reclaimed Granite Steps  
1":2'-0"  
3.2

- NOTES:
1. QUANTITY OF RISERS VARIES, RE: GRADING PLAN
  2. HANDRAIL REQUIRED WHERE THERE ARE 4 OR MORE RISERS; RE: HANDRAIL DETAIL
  3. RE: GRADING DRAWINGS FOR RISER HEIGHT
  4. LANDSCAPE ARCHITECT TO APPROVE CONCRETE COLOR PRIOR TO INSTALLATION


- NOTES:
1. TYPICAL RISER HEIGHT 7", TYPICAL TRED WIDTH 12"
  2. LANDSCAPE ARCHITECT TO APPROVE LAYOUT IN THE FIELD PRIOR TO COMPLETION
  3. STONES SHALL BE PLACED AND BACKFILLED SO THERE IS NO TIPPING / SHIFTING, TYPICAL

- NOTES:
1. DETAILS AND SPECIFICATIONS DEPICTED TO CONVEY DESIGN INTENT. FINAL DESIGN AND SPECIFICATION SUBJECT TO CHANGE PRIOR TO CONSTRUCTION AT LANDSCAPE ARCHITECT'S DISCRETION.




**1** Wall - Concrete  
1":1'-0"

4.1




**2** Wood Top Bench  
1":1'-0"

5.1



**3** Wood Platform Deck  
3/4":1'-0"

5.2



**4** Bicycle Rack  
3/4":1'-0"

5.3

**5** Hand Railing  
1/2":1'-0"

6.1





SITE KEYNOTES:

| KEYNOTE                            | DETAIL / SHEET | KEYNOTE                                | DETAIL / SHEET |
|------------------------------------|----------------|--|----------------|
| <b>1.0</b> PAVEMENTS, RAMPS, CURBS |                | <b>6.0</b> RAILINGS, BARRIERS, FENCING |                |
| 1.1 BITUMINOUS PATH                | 1/L5-00        | 6.1 HAND RAILING                       | 5/L5-01        |
| 1.2 CIP CONCRETE                   | 2/L5-00        | 6.2 GUARD RAIL                         | 3/L5-03        |
| 1.3 STONE DUST WALK                | 5/L5-00        | <b>7.0</b> SITE LIGHTING               |                |
| 1.4 GRAVEL DRIP EDGE               | 6/L5-00        | 7.1 BOLLARD LIGHT BASE                 | 2/L5-02        |
| <b>2.0</b> JOINTING                |                | 7.2 POLE LIGHT BASE                    | 1/L5-02        |
| 2.1 EXPANSION JOINT                | 3/L5-00        | 7.3 CATENARY LIGHT BASE                | 3/L5-02        |
| 2.2 CONTROL JOINT                  | 4/L5-00        | <b>8.0</b> DRAINAGE                    |                |
| <b>3.0</b> STEPS                   |                | 8.XX NOT USED AT THIS TIME             | X/XX-XX        |
| 3.1 CONCRETE STEPS                 | 7/L5-00        | <b>9.0</b> PLANTING AND LANDSCAPE      |                |
| 3.2 RECLAIMED GRANITE STEPS        | 8/L5-00        | 9.1 DECIDUOUS TREE PLANTING            | 1/L5-04        |
| <b>4.0</b> SITE WALLS/ EMBANKMENTS |                | 9.2 CONIFEROUS TREE PLANTING           | 2/L5-04        |
| 4.1 WALL - CONCRETE                | 1/L5-01        | 9.3 SHRUB PLANTING                     | 4/L5-04        |
| <b>5.0</b> SITE FURNITURE          |                | 9.4 PERENNIAL/GRASS PLANTING           | 3/L5-04        |
| 5.1 WOOD TOP BENCH                 | 2/L5-01        | 9.5 LANDSCAPE EDGING                   | 5/L5-04        |
| 5.2 WOOD PLATFORM DECK             | 3/L5-01        | <b>10.0</b> MISCELLANEOUS ELEMENTS     |                |
| 5.3 BICYCLE RACK                   | 4/L5-01        | 10.1 WATER FEATURE POP JET             | 5/L5-02        |
|                                    |                | 10.2 ADDRESS MARKER                    | 4/L5-02        |
|                                    |                | 10.3 OBSERVATION DECK                  | 1/L5-03        |
|                                    |                | 10.4 INTERPRETIVE SIGNAGE              | 2/L5-03        |

NOTES:

1. DETAILS AND SPECIFICATIONS DEPICTED TO CONVEY DESIGN INTENT. FINAL DESIGN AND SPECIFICATION SUBJECT TO CHANGE PRIOR TO CONSTRUCTION AT LANDSCAPE ARCHITECT'S DISCRETION.






**1** Pole Light Base  
1/2":1'-0"

**2** Bollard Light Base  
1/2":1'-0"

**3** Catenary Light Base  
1":1'-0"

**4** Address Marker  
1":2'-0"





**NOTE:**  
1. LOCATIONS AND QUANTITIES PER LAYOUT PLAN ; SEE L 1-00  
2. MECHANICAL VAULT LOCATION TBD  
3. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS OF SPECIFICATION AND ASSEMBLY FOR LANDSCAPE ARCHITECT REVIEW

**5** Water Feature Pop Jets  
1":1'-0"

SITE KEYNOTES:

| KEYNOTE | DESCRIPTION                 | DETAIL / SHEET |
|---------|-----------------------------|----------------|
| 1.0     | PAVEMENTS, RAMPS, CURBS     |                |
| 1.1     | BITUMINOUS PATH             | 1/L5-00        |
| 1.2     | CIP CONCRETE                | 2/L5-00        |
| 1.3     | STONE DUST WALK             | 5/L5-00        |
| 1.4     | GRAVEL DRIP EDGE            | 6/L5-00        |
| 2.0     | JOINTING                    |                |
| 2.1     | EXPANSION JOINT             | 3/L5-00        |
| 2.2     | CONTROL JOINT               | 4/L5-00        |
| 3.0     | STEPS                       |                |
| 3.1     | CONCRETE STEPS              | 7/L5-00        |
| 3.2     | RECLAIMED GRANITE STEPS     | 8/L5-00        |
| 4.0     | SITE WALLS/ EMBANKMENTS     |                |
| 4.1     | WALL - CONCRETE             | 1/L5-01        |
| 5.0     | SITE FURNITURE              |                |
| 5.1     | WOOD TOP BENCH              | 2/L5-01        |
| 5.2     | WOOD PLATFORM DECK          | 3/L5-01        |
| 5.3     | BICYCLE RACK                | 4/L5-01        |
| 6.0     | RAILINGS, BARRIERS, FENCING |                |
| 6.1     | HAND RAILING                | 5/L5-01        |
| 6.2     | GUARD RAIL                  | 3/L5-03        |
| 7.0     | SITE LIGHTING               |                |
| 7.1     | BOLLARD LIGHT BASE          | 2/L5-02        |
| 7.2     | POLE LIGHT BASE             | 1/L5-02        |
| 7.3     | CATENARY LIGHT BASE         | 3/L5-02        |
| 8.0     | DRAINAGE                    |                |
| XX      | NOT USED AT THIS TIME       | X/XX-XX        |
| 9.0     | PLANTING AND LANDSCAPE      |                |
| 9.1     | DECIDUOUS TREE PLANTING     | 1/L5-04        |
| 9.2     | CONIFEROUS TREE PLANTING    | 2/L5-04        |
| 9.3     | SHRUB PLANTING              | 4/L5-04        |
| 9.4     | PERENNIAL/GRASS PLANTING    | 3/L5-04        |
| 9.5     | LANDSCAPE EDGING            | 5/L5-04        |
| 10.0    | MISCELLANEOUS ELEMENTS      |                |
| 10.1    | WATER FEATURE POP JET       | 5/L5-02        |
| 10.2    | ADDRESS MARKER              | 4/L5-02        |
| 10.3    | OBSERVATION DECK            | 1/L5-03        |
| 10.4    | INTERPRETIVE SIGNAGE        | 2/L5-03        |


**NOTES:**  
1. DETAILS AND SPECIFICATIONS DEPICTED TO CONVEY DESIGN INTENT. FINAL DESIGN AND SPECIFICATION SUBJECT TO CHANGE PRIOR TO CONSTRUCTION AT LANDSCAPE ARCHITECT'S DISCRETION.



- NOTES:
- CROSS-JOISTS ARE TO FASTEN ON BOTH SIDES OF SUPPORT COLUMNS W/NUTTED THRU-BOLTS
  - SPLICES OF FASCIA JOISTS ARE TO BE CENTERED ON SUPPORT COLUMNS AND BE BACKED BY AN OVERLAP OF 18" EITHER SIDE OF JOINT, FASTENED ACCORDINGLY
  - DECKING FASTENERS SHALL HAVE A COUNTER-SINK HEAD AND BE FLUSH WITH FINISH SURFACE OF DECKING, TO MITIGATE SPLINTERING AND TRIPPING
  - ALL THREADED FASTENERS ARE TO HAVE A WEATHERPROOF FINISH
  - ALL FRAMING DIMENSIONS SUBJECT TO CHANGE BASED ON STRUCTURAL REVIEW PRIOR TO CONSTRUCTION. ALL DIMENSIONS INDICATED FOR CONCEPTUAL PURPOSES.


10.3

1 Observation Deck  
1":3'-0"



2 Interpretive Signage Example  
N.T.S.

10.4



3 Guard Rail  
N.T.S.


6.2

SITE KEYNOTES:


| KEYNOTE              | ITEM                        | DETAIL / SHEET           | KEYNOTE                      | ITEM                        | DETAIL / SHEET |
|----------------------|-----------------------------|--------------------------|------------------------------|-----------------------------|----------------|
| 1.0                  | PAVEMENTS, RAMPS, CURBS     |                          | 6.0                          | RAILINGS, BARRIERS, FENCING |                |
|                      | 1.1 BITUMINOUS PATH         | 1/L5-00                  |                              | 6.1 HAND RAILING            | 5/L5-01        |
|                      | 1.2 CIP CONCRETE            | 2/L5-00                  | 6.2 GUARD RAIL               | 3/L5-03                     |                |
|                      | 1.3 STONE DUST WALK         | 5/L5-00                  | 7.0                          | SITE LIGHTING               |                |
| 1.4 GRAVEL DRIP EDGE | 6/L5-00                     | 7.1 BOLLARD LIGHT BASE   |                              | 2/L5-02                     |                |
|                      |                             | 7.2 POLE LIGHT BASE      |                              | 1/L5-02                     |                |
| 2.0                  | JOINTING                    |                          | 7.3 CATENARY LIGHT BASE      | 3/L5-02                     |                |
|                      | 2.1 EXPANSION JOINT         | 3/L5-00                  | 8.0                          | DRAINAGE                    |                |
| 2.2 CONTROL JOINT    | 4/L5-00                     | XX NOT USED AT THIS TIME |                              | X/XX-XX                     |                |
| 3.0                  | STEPS                       |                          | 9.0                          | PLANTING AND LANDSCAPE      |                |
|                      | 3.1 CONCRETE STEPS          | 7/L5-00                  |                              | 9.1 DECIDUOUS TREE PLANTING | 1/L5-04        |
| 4.0                  | 3.2 RECLAIMED GRANITE STEPS | 8/L5-00                  | 9.2 CONIFEROUS TREE PLANTING | 2/L5-04                     |                |
|                      | SITE WALLS/ EMBANKMENTS     |                          | 9.3 SHRUB PLANTING           | 4/L5-04                     |                |
| 5.0                  | 4.1 WALL - CONCRETE         | 1/L5-01                  | 9.4 PERENNIAL/GRASS PLANTING | 3/L5-04                     |                |
|                      | SITE FURNITURE              |                          | 9.5 LANDSCAPE EDGING         | 5/L5-04                     |                |
| 6.0                  | 5.1 WOOD TOP BENCH          | 2/L5-01                  | 10.0                         | MISCELLANEOUS ELEMENTS      |                |
|                      | 5.2 WOOD PLATFORM DECK      | 3/L5-01                  |                              | 10.1 WATER FEATURE POP JET  | 5/L5-02        |
|                      | 5.3 BICYCLE RACK            | 4/L5-01                  |                              | 10.2 ADDRESS MARKER         | 4/L5-02        |
|                      |                             |                          |                              | 10.3 OBSERVATION DECK       | 1/L5-03        |
|                      |                             |                          | 10.4 INTERPRETIVE SIGNAGE    | 2/L5-03                     |                |

- NOTES:
- DETAILS AND SPECIFICATIONS DEPICTED TO CONVEY DESIGN INTENT. FINAL DESIGN AND SPECIFICATION SUBJECT TO CHANGE PRIOR TO CONSTRUCTION AT LANDSCAPE ARCHITECT'S DISCRETION.


| REVISIONS | DATE |
|-----------|------|
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |




**1** Deciduous Tree Planting  
1":1'-0" 9.1




**2** Conifer Tree Planting  
1":1'-0" 9.2



**3** Perennial / Ornamental Grass Planting  
1":1'-0" 9.4



**4** Shrub Planting  
1":1'-0" 9.3



**5** Steel Edging  
1":1'-0" 9.5

SITE KEYNOTES:


| 1.0                         | PAVEMENTS, RAMPS, CURBS | DETAIL / SHEET | 6.0                         | RAILINGS, BARRIERS, FENCING | DETAIL / SHEET |
|-----------------------------|-------------------------|----------------|-----------------------------|-----------------------------|----------------|
| 1.1                         | BITUMINOUS PATH         | 1/L5-00        | 6.1                         | HAND RAILING                | 5/L5-01        |
| 1.2                         | CIP CONCRETE            | 2/L5-00        | 6.2                         | GUARD RAIL                  | 3/L5-03        |
| 1.3                         | STONE DUST WALK         | 5/L5-00        | 7.0 SITE LIGHTING           |                             |                |
| 1.4                         | GRAVEL DRIP EDGE        | 6/L5-00        | 7.1                         | BOLLARD LIGHT BASE          | 2/L5-02        |
| 2.0 JOINTING                |                         |                | 7.2                         | POLE LIGHT BASE             | 1/L5-02        |
| 2.1                         | EXPANSION JOINT         | 3/L5-00        | 7.3                         | CATENARY LIGHT BASE         | 3/L5-02        |
| 2.2                         | CONTROL JOINT           | 4/L5-00        | 8.0 DRAINAGE                |                             |                |
| 3.0 STEPS                   |                         |                | X.X                         | NOT USED AT THIS TIME       | X/XX-XX        |
| 3.1                         | CONCRETE STEPS          | 7/L5-00        | 9.0 PLANTING AND LANDSCAPE  |                             |                |
| 3.2                         | RECLAIMED GRANITE STEPS | 8/L5-00        | 9.1                         | DECIDUOUS TREE PLANTING     | 1/L5-04        |
| 4.0 SITE WALLS/ EMBANKMENTS |                         |                | 9.2                         | CONIFEROUS TREE PLANTING    | 2/L5-04        |
| 4.1                         | WALL - CONCRETE         | 1/L5-01        | 9.3                         | SHRUB PLANTING              | 4/L5-04        |
| 5.0 SITE FURNITURE          |                         |                | 9.4                         | PERENNIAL/GRASS PLANTING    | 3/L5-04        |
| 5.1                         | WOOD TOP BENCH          | 2/L5-01        | 9.5                         | LANDSCAPE EDGING            | 5/L5-04        |
| 5.2                         | WOOD PLATFORM DECK      | 3/L5-01        | 10.0 MISCELLANEOUS ELEMENTS |                             |                |
| 5.3                         | BICYCLE RACK            | 4/L5-01        | 10.1                        | WATER FEATURE POP JET       | 5/L5-02        |
|                             |                         |                | 10.2                        | ADDRESS MARKER              | 4/L5-02        |
|                             |                         |                | 10.3                        | OBSERVATION DECK            | 1/L5-03        |
|                             |                         |                | 10.4                        | INTERPRETIVE SIGNAGE        | 2/L5-03        |

NOTES:

1. DETAILS AND SPECIFICATIONS DEPICTED TO CONVEY DESIGN INTENT. FINAL DESIGN AND SPECIFICATION SUBJECT TO CHANGE PRIOR TO CONSTRUCTION AT LANDSCAPE ARCHITECT'S DISCRETION.




SOUTH ELEVATION




WEST ELEVATION

- Membrane Roofing Behind Parapet
- Fiber Cement Board & Batten
- Insect Screen
- Double-glazed Fiberglass Fixed and Casement Muller Window, Typ.
- Double-glazed Fiberglass Casement Window, Typ.
- Wood Siding
- Fiber Cement Board over Concrete Stem Wall, Parged




NORTH ELEVATION



EAST ELEVATION

- Membrane Roofing Behind Parapet
- Fiber Cement Board & Batten
- Insect Screen
- Double-glazed Fiberglass Fixed and Casement Muller Window, Typ.
- Double-glazed Fiberglass Casement Window, Typ.
- Wood Siding
- Fiber Cement Board over Concrete Stem Wall, Parged


DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.






FRONT SIDE

- Membrane Roofing
- Fiber Cement Board & Batten
- Double-glazed Fiberglass Fixed and Casement Muller Window, Typ.
- Double-glazed Fiberglass Casement Window, Typ.
- Fiber Cement Shiplap Board
- Natural Cedar Cladding
- Fiber Cement Board over Concrete Stem Wall, Parged




RIGHT SIDE




BACK SIDE


- Membrane Roofing
- Fiber Cement Board & Batten
- Double-glazed Fiberglass Fixed and Casement Muller Window, Typ.
- Double-glazed Fiberglass Casement Window, Typ.
- Fiber Cement Board over Concrete Stem Wall, Parged



LEFT SIDE

DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.





FRONT SIDE

Membrane Roofing


Fiber Cement Board & Batten

Double-glazed Fiberglass Fixed and Casement Muller Window, Typ.


Double-glazed Fiberglass Casement Window, Typ.

Fiber Cement Shiplap Board Natural Cedar Cladding

Fiber Cement Board over Concrete Stem Wall, Parged



RIGHT SIDE



BACK SIDE

Membrane Roofing


Fiber Cement Board & Batten

Double-glazed Fiberglass Fixed and Casement Muller Window, Typ.

Double-glazed Fiberglass Casement Window, Typ.


Fiber Cement Shiplap Board Natural Cedar Cladding



Fiber Cement Board over Concrete Stem Wall, Parged




LEFT SIDE


DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.






DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.






FRONT SIDE





BACK SIDE


DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.









DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.





FRONT SIDE




RIGHT SIDE

- Membrane Roofing
- Fiber Cement Board & Batten
- Double-glazed Fiberglass Fixed and Casement Muller Window, Typ.
- Double-glazed Fiberglass Casement Window, Typ.
- Fiber Cement Shiplap Board
- Fiber Cement Board over Concrete Stem Wall, Parged




BACK SIDE




LEFT SIDE


- Membrane Roofing
- Fiber Cement Board & Batten
- Double-glazed Fiberglass Fixed and Casement Muller Window, Typ.
- Double-glazed Fiberglass Casement Window, Typ.
- Natural Cedar Cladding
- Fiber Cement Board over Concrete Stem Wall, Parged

DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.








**LEVEL 2**  
6,942 GSF




**LEVEL 1**  
7,474 GSF


DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.






DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.







**GROUND FLOOR**  
3,428 GSF



**TYPICAL FLOOR**  
3,460 GSF



DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.




Scale: 1/32" = 1'-0"

Architecture  
& Planning


**utile**




**GROUND FLOOR**  
6,743 GSF




**TYPICAL FLOOR**  
6,808 GSF




DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.







**GROUND FLOOR**  
3,857 GSF



**TYPICAL FLOOR**  
3,876 GSF




DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.




Scale: 1/32" = 1'-0"

Architecture  
& Planning


**utile**




**GROUND FLOOR**  
7,715 GSF



**TYPICAL FLOOR**  
7,753 GSF



DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.









**GROUND FLOOR**  
5,820 GSF




**TYPICAL FLOOR**  
5,846 GSF




DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.







GROUND LEVEL PLAN



EAST (FRONT) ELEVATION




WEST (HIGHWAY) ELEVATION



SOUTH (SIDE) ELEVATION

NORTH (SIDE) ELEVATION

DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.



**100 Durgin Lane - Site Plan Review - TAC STIPULATIONS OF APPROVAL (11/8/24)**

100 Durgin Lane  
Portsmouth, New Hampshire  
November 27, 2024

Prepared by: NAH/BKC  
Project # E5071-001

|   | <b>CHANGES TO BE MADE PRIOR TO PLANNING BOARD SUBMISSION</b>  | <b>Response</b>   | <b>Corresponding Plan Sheet #</b>                         |
|---|---|---|---|
| 1 | R4-7b Keep Right signs to be used at traffic circle, and place signs inside the raised median island, not on the right-hand side of the roadway.  | R4-7b Keep Right signs have been relocated to the inside of the raised median island.   | C-301, C-302  |
| 2 | NO PARKING signs must be installed at the head of each handicap parking space access aisle that is 8 feet wide, in a location that does not block the accessible route.   | NO PARKING signs are now proposed at the head of each ADA parking space access aisle, and do not block the accessible route.  | C-301, C-302  |
| 3 | When W11-2 signs are used at crosswalks, they must also include a W16-7P sign below them.   | Additional W16-7p signs are now proposed below W11-2 signs that are used at crosswalks.   | C-301, C-302  |
| 4 | Detail highlighting changes in wetland buffer impacts since conservation commission approval will be included.  | An exhibit is included which highlights the reason for the modification to wetland buffer impacts. As shown in the exhibit, the increase in total impacts is associated with the request from the City to construct a 10' multi-use path along Durgin Lane.   | Wetland Buffer Impacts Modification Clarification exhibit |
|   | <b>CONDITIONS:</b>  | <b>Response</b>   |   |
| 1 | A CMMP will be required for construction. Portions of that plan will be a proposed utility and access sequencing plan for the two nearby lots that are dependent on this parcel for their utility and access needs. The Department of PW will need to sign off on the proposed plan prior to the CMMP being authorized. | Acknowledged. A CMMP will be provided to the City for approval prior to construction.   | N/A   |
| 2 | Applicant must replace the 6" water main in Woodbury Avenue from Gosling Road to the 16" main on Woodbury Avenue with a new 12" DI pipe installed to City standards.  | Acknowledged. Included are schematic design plans showing the proposed replacement of the 6-inch main in Woodbury Avenue with a 12-inch main ("Woodbury Ave Water Line Replacement"). The Applicant will continue to coordinate with the City of Portsmouth to refine the design and scope of the improvements. | Woodbury Ave Water Line Replacement                       |
| 3 | A 10' multi-use path on Durgin Lane must be constructed by the developer all the way to Woodbury Avenue. Multi-use path tip downs are to be concrete with tactile panels as appropriate. Developer will provide a final layout, drainage and striping plan for final review.  | Acknowledged. Included are schematic design plans showing the potential multi-use path improvements. The Applicant will continue to coordinate with the City of Portsmouth to refine the design and scope of the improvements.  | 10' Multi-Use Sidewalk Exhibits (2)                       |
| 4 | Continue narrowing Durgin Lane to 28' to provide a grass strip along the road in the area adjacent to the Durgin Plaza parking lot.   | Acknowledged. The schematic Multi-Use Sidewalk exhibits have been modified to propose a 28'-wide Durgin Lane width where possible. The Applicant will continue to coordinate with the City of Portsmouth to refine the design and scope of the improvements.  | 10' Multi-Use Sidewalk Exhibits (2)                       |
| 5 | Third party oversite engineer is required.  | Acknowledged.   | N/A   |

**100 Durgin Lane - Site Plan Review - CONCOM STIPULATIONS OF APPROVAL (9/16/24)**

100 Durgin Lane  
Portsmouth, New Hampshire  
November 27, 2024

Prepared by: NAH/BKC  
Project # E5071-001

|   | <b>CONDITIONS</b>  | <b>Response</b>  | <b>Corresponding Plan Sheet #</b>           |
|---|--|--|---|
| 1 | Applicant clarify the mowing plan for the passive areas within the buffer, which should be not be mowed more than 1 to 2 times per year.   | The landscape maintenance plan for the development has been revised to specify mowing within passive buffer areas no more than twice per year.         | Landscape Operations and Maintenance Manual |
| 2 | Applicant should have a conversation with the Department of Public Works to determine the curbing to be used within the roundabout area and use broken and/or slanted curbing for wildlife passage, if appropriate.  | The Applicant will coordinate with DPW to determine the appropriate curbing within the roundabout area.  | N/A   |
| 3 | An educational sign should be installed in the passive recreation area that provides content on wetlands, wetland buffers and the sensitivity of the buffers.  | Interpretive wetland informational plaques are proposed at (3) locations along the northern edge of the site adjacent to passive wetland buffer areas. | Site Signage Plan exhibit                   |
| 4 | In accordance with Section 10.1018.40 of the Zoning Ordinance, applicant shall install permanent wetland boundary markers. We suggest that these markers are placed along the 25' vegetative buffer at intervals of every 50 feet. These must be installed prior to the start of any construction. These can be purchased through the City of Portsmouth Planning and Sustainability Department. Please mark on final plan set where the markers are to be placed. | Marker locations are identified on the plans and supplemented by General Note #17 on C-101.  | C-101, C-201, C-202                         |
| 5 | One year after landscaping is complete, if at least an 80% success rate has not been reached, applicants will replant and report back to the Planning & Sustainability Department one year after planting is complete and each subsequent year until an 80% planting success rate has been achieved.   | Acknowledged.  | N/A   |

E5071-001  
October 16, 2024

Mr. Peter Britz, Director of Planning & Sustainability  
City of Portsmouth Planning & Sustainability Department  
1 Junkins Avenue  
Portsmouth, New Hampshire 03801

Re: **Response to Comments – Traffic Peer Review – Letter 2  
100 Durgin Lane – Proposed Redevelopment**

Dear Peter:

Tighe & Bond has prepared this letter in response to peer review comments on the subject project received from TEC, Inc. (TEC) in a letter dated September 25, 2024. The 100 Durgin Lane Multi-Family Development Traffic Impact Study, dated May 16, 2024, was submitted to the City in June 2024. For ease of review, TEC comments are repeated herein in *italics*, followed by our response in **bold** for each.

### **Traffic Impact Study**

7. *Original TEC Comment from 8/28/2024: The TIA included a distribution analysis for the new trips that was based on U.S. Census Journey-to-Work data. This is reasonable and appropriate. However, TEC has the following comments related to potential variations in route selection for the future residents of the Project:*
  - a. *T&B did not assign any exiting trips to the Motel 6 driveway - TEC concurs that the Project will invite a significant volume of entering traffic via the Gosling Road / Motel 6 access point. The Applicant and City should review the potential to use the northerly driveway as a one-way entrance only connection to limit traffic conflicts within the Motel.*

*Applicant Response 9/18/2024: Site generated trips are not expected to exit via the Motel driveway, as stated in the TIS. Existing exiting traffic volumes from the Motel 6/ northern site driveway at Gosling Road are 13, 30, and 52 vehicles in the weekday morning, weekday afternoon, and Saturday midday peak periods, respectively. Based on the project site being currently vacant, it is assumed that many of these existing vehicle trips may originate from the New Frontier Church or Motel 6. Therefore, based on the minimal existing exiting traffic volumes and no estimated site traffic exiting via this driveway, converting the portion of the site driveway to one-way entrance only may not significantly reduce potential conflicts between driveway traffic and adjacent parking areas.*

*In addition, existing access easements along the driveway and the location of a portion of the driveway outside of the project parcel may preclude the conversion of the driveway to enter only. The Applicant has however proposed several traffic calming measures on site to limit speeds and potential cut-through traffic as described in further detail in response to Comment 13.*

*TEC Follow-up Comment 9/25/2024: TEC believes that the Applicant needs to provide additional information to justify the retention of the current two-way flow. The Applicant should provide copies of any potential deed restrictions and evidence of discussions/coordination with the abutting property owner prior to the Board rendering*



a decision on this important aspect of the project. Without the conversion to one-way traffic, it does not appear that a reasonable or safe multi-modal connection can be provided on the Applicant's property for walking and biking trips to the Gosling Road corridor. Unless the Fire Department expresses a need for two-way flow here, TEC recommends that the City requires additional evidence from the Applicant's team.

**Applicant Response 10/11/2024: Copies of the relevant easements are included with this response and were provided to the City Traffic Engineer via email on 9/27/24. On 9/30/24, the City Traffic Engineer concurred it is not possible to alter the connector roadway to one-way flow based on the existing easements.**

12. *Original TEC Comment from 8/28/2024:* As discussed in Comment #7a above, the Applicant should consider one-way entering traffic from the Motel 6 site to reduce conflict points in the parking area adjacent to Motel 6. It would meanwhile afford an opportunity to use the extra roadway cross-section to create buffered bicycle accommodations for any bicycle trips that may originate at Pease Tradeport or the retail areas to the north.

*Applicant Response 9/18/2024:* The existing roadway connecting the subject parcel and the Motel 6 parcel is covered under an existing shared access easement which may preclude the conversion of the driveway to enter only without consent of both parties. The Applicant is not the Owner of the Motel 6 parcel, and therefore does not have control over adjustments to the site layout on their property.

*TEC Follow-up Comment 9/25/2024:* See TEC's follow-up comment to #7a above.

**Applicant Response 10/11/2024: Copies of the relevant easements are included with this response and were provided to the City Traffic Engineer via email on 9/27/24. On 9/30/24, the City Traffic Engineer concurred it is not possible to alter the connector roadway to one-way flow based on the existing easements.**

13. *Original TEC Comment from 8/28/2024:* The Applicant should consider speed humps or other traffic calming devices along the main access aisles from the north. TEC observed considerable cut-through traffic with seemingly higher operating speeds. Given the nature of the residential redevelopment, the speed characteristics should be reviewed and mitigated.

*Applicant Response 9/18/2024:* Speed bumps have been added at north and south entrances of the north-south access way, in addition to centerline pavement markings. Once within the center of the development, the presence of head-in parking and landscaped islands on both sides of the access ways will promote additional traffic calming, as well as a safety buffer between moving vehicles and pedestrians. The four-way stop-controlled intersection at the center of the site will provide additional speed mitigation.

*TEC Follow-up Comment 9/25/2024:* TEC recommends that the Applicant replaces the current speed bump detail with a speed hump detail that is more closely aligned with current industry guidance, such as the 2007 publication from the Institute of Transportation Engineers (ITE) entitled, "Guidelines for the Design and Application of Speed Humps." This should provide a traffic calming feature that manages vehicle speeds to a reasonable level while also providing more appropriate accommodations for emergency vehicles.

**Applicant Response 10/11/2024:** The "Speed Bump" detail has been replaced with a "Speed Hump" detail in accordance with the 2007 publication from the Institute of Transportation Engineers (ITE) entitled, "Guidelines for the Design and Application of Speed Humps." The site plans have been updated to show the revised limits of the speed hump.

24. *Original TEC Comment from 8/28/2024:* The Applicant should review on-site opportunities for package delivery services near the central mail/delivery room; and a potential future bus stop(s) along the main north-south access aisle near Durgin Lane.

*Applicant Response 9/18/2024:* A central package delivery room is currently planned to be located at the northern corner of ground floor of the "Amenity Building". Deliveries of packages to room will be achieved using one of the nearby parking spaces. The Applicant previously met with COAST in March 2024 to discuss the feasibility of adding bus service to the proposed development. COAST conducted testing and determined that adding service to the site would require service elsewhere to be eliminated to maintain current headways, and therefore was not viable at this time.

*TEC Follow-up Comment 9/25/2024:* Given the frequency of delivery trips to a facility of this size, TEC continues to recommend a dedicated area for delivery vehicles that is signed as 'No Parking' adjacent to the proposed amenity building (assumed to be Building #15). The next set of plans should provide clear labels for the location/designation of the amenity building on Sheets C-301 and C-302.

**Applicant Response 10/11/2024:** A parking space for delivery vehicles has been identified on the plans with associated signage adjacent to the Amenity Building. The Amenity Building has been clearly identified on the plans.


If you have any questions or need any additional information, please contact Patrick Crimmins or Neil Hansen by phone at (603) 433-8818 or by email at [pmcrimmins@tighebond.com](mailto:pmcrimmins@tighebond.com) / [nahansen@tighebond.com](mailto:nahansen@tighebond.com).

Sincerely,

**TIGHE & BOND, INC.**



Patrick M. Crimmins, PE  
Vice President



Neil A. Hansen, PE  
Project Manager

Copy: Eastern Real Estate (via email)

B3160 P2033

ACCESS EASEMENT

KNOW ALL MEN BY THESE PRESENTS, That **SFL, LLC**, a New Hampshire Limited Liability Company, with a principal place of business at 22 Heritage Drive, Woburn, County of Middlesex and Commonwealth of Massachusetts for and in consideration of One (\$1.00) Dollar and other valuable consideration does hereby grant to **GILBERT SOUCY and DOROTHY SOUCY, their heirs, successors and assigns, both of 323 Portsmouth Avenue in Stratham, County of Rockingham and State of New Hampshire**, an easement for the purpose of ingress and egress over and upon land of the Grantor, situate at Gosling Road, Portsmouth, County of Rockingham and State of New Hampshire, more particularly bounded and described as follows:

PORTSMOUTH, NEW HAMPSHIRE


A right to pass and repass over and across the parking area and 24 foot paved drive on land of the within Grantor shown as Lot #2 on Plan entitled "Overall Site Plan for H.B.I., Gosling Road, County of Rockingham, Portsmouth, New Hampshire", prepared by Richard P. Millette and Associates, dated 1-17-94, revised 4-13-94.


Said Plan recorded at the Rockingham County Registry of Deeds, as Plan D-24125.

The within granted Easement is subject to the terms and conditions of a certain Operation and Maintenance Agreement of even date to be recorded herewith.

WITNESS my hand and seal this 13<sup>th</sup> day of June, 1996.

SFL, LLC

  
Witness

By:   
ROBERT D. HAVERTY  
Duly Authorized

JUN 14 11 26 AM '96  
0026463

ROCKINGHAM COUNTY  
REGISTRY OF DEEDS

LAW OFFICES OF  
WHOLEY & PELECH  
55 CONGRESS STREET  
P.O. BOX 325  
PORTSMOUTH, N.H.  
03802-0325




B3160 P2034

STATE OF NEW HAMPSHIRE  
COUNTY OF ROCKINGHAM, SS.


June 2, 1996

Personally appeared the above-named ROBERT D. HAVERTY,  
duly authorized on behalf of SFL, LLC, known to me, or  
satisfactorily proven to be the person whose name is  
subscribed to the foregoing instrument and acknowledged that  
he executed the same for the purposes therein contained.

Before me,

  
Notary Public Justice of the Peace

Commission expires:

|  |   |                             |
|--|---|-----------------------------|
| STATE OF NEW HAMPSHIRE                                     |   |                             |
| DEPARTMENT<br>OF<br>REVENUE<br>ADMINISTRATION              |  | REAL ESTATE<br>TRANSFER TAX |
| <u>XX</u> THOUSAND <u>XX</u> HUNDRED AND <u>40</u> DOLLARS |   |                             |
| <u>061496</u>  | <u>226095</u>   | <u>\$ 40.00</u>             |
| VOID IF ALTERED  |   |                             |

PK 3102 P0400

ACCESS - PARKING - UTILITY - SIGNAGE EASEMENT

KNOW ALL MEN BY THESE PRESENTS, That SATURN REALTY LLC of 1 Gosling Road in Portsmouth, County of Rockingham and State of New Hampshire (mailing address: Post Office Box 3310, Portsmouth, NH 03802) (the "Grantor"), for consideration paid hereby grants to ROBERT D. HAVERTY and KATHLEEN M. HAVERTY, Trustees of SFL REALTY TRUST, under Declaration of Trust dated June 1, 1994, (the "Grantee") of 22 Heritage Drive in Woburn, County of Middlesex and Commonwealth of Massachusetts, its successors, heirs and assigns, without covenants, the perpetual right and easement to lay, construct, inspect, repair, maintain, renew, replace and remove any and all utilities, whether underground or above ground including but not limited to sewer mains, water mains, gas lines, electrical lines, telephone lines, aligns, pipes, conduits, and cables for any and all other utilities of any type and nature as may be required by the Grantee over, across and through land of the Grantor as hereinafter described in Exhibit "A" attached hereto.

Grantor, on behalf of its self, its successors and assigns, for consideration paid hereby grants to the Grantee, without covenants, a perpetual, non-exclusive right and easement to the Grantee, their successors, assigns, customers, guests, licensees, invitees, sub-tenants, employees and agents, in common with the Grantor its customers, guests, licensees, invitees, sub-tenants, employees and agents, over and across land of the Grantor, more particularly described in Exhibit "A" attached hereto for purposes of vehicular and pedestrian ingress and egress over and across any and all driveways, traffic lanes, parking areas, and roadways, and further for the purpose of the parking of motor vehicles, including, without limitation, service vehicles.

Grantor further conveys to Grantee, its successors, assigns and tenants, without covenants a perpetual easement over and upon the premises described in Exhibit "A" attached hereto, for the purpose of erecting signage to benefit Grantee it's successors, assigns and tenants, provided, however, that any signage erected be approved by Grantor and the City of Portsmouth as to location, size, height and illumination.

The actual location of all utilities, access ways, parking areas and sign locations are as shown on plans entitled "Site Plan for H.B.I., Gosling Road, County of Rockingham, Portsmouth, New Hampshire, dated 1-17-94, revised 4-13-94, 4-18-94 - Sheets 3 of 11 and 4 of 11 - " prepared by Richard P. Millette and Associates, to be recorded herewith, and any further amendments thereto.

019139

MAY 30 11 59 AM '95

ROCKINGHAM COUNTY  
REGISTRY OF DEEDS

LAW OFFICES OF  
WHOLEY & PELECH  
224 STATE STREET  
P O BOX 395  
PORTSMOUTH, N. H.  
03802-0395

**PORTSMOUTH, NEW HAMPSHIRE**

Beginning at a point at the northwesterly corner of within described premises on the southerly side of Gosling Road at land now or formerly of the State of New Hampshire, at a New Hampshire Highway bound, thence running N 75° 20' 35" E along the southerly sideline of Gosling Road a distance of 200.00 feet to a point at other land of the within Grantor; thence turning and running S 11° 12' 58" W by other land of the Grantor a distance of 166.55 feet to a point; thence turning and running S 14° 34' 24" E by other land of the Grantor a distance of 170.03 feet to a point; thence turning and running S 17° 53' 36" W by other land of the Grantor a distance of 169.08 feet to a point; thence turning and running S 51° 58' 44" E by other land of the Grantor a distance of 247.14 feet to a point; thence turning and running S 30° 52' 30" E by other land of the Grantor a distance of 257.67 feet to a point at land now or formerly of Costco Wholesale Corp.; thence turning and running S 69° 05' 25" W by land of said Costco Wholesale Corp. a distance of 137.94 feet to a found hub and tack in a stone wall at other land of Costco Wholesale Corp.; thence turning and running N 26° 30' 05" W by said stone wall and land of Costco Wholesale Corp. a distance of 121.94 feet to a point; thence turning and running N 36° 21' 05" W along said stone wall by land of Costco Wholesale Corp. a distance of 100.02 feet to a point; thence turning and running N 28° 38' 05" W along said stone wall and land of Costco Wholesale Corp. a distance of 70.30 feet to a point; thence turning and running S 71° 16' 25" W along land of said Costco Wholesale Corp. a distance of 153.50 feet; thence turning and running N 23° 58' 32" W by land of the State of New Hampshire a distance of 311.71 feet to a point; thence turning and running N 17° 40' 15" E by land of the State of New Hampshire a distance of 168.00 feet to a point; thence turning and running along the arc of a curve to the left, having a radius of 244.00 feet and a central angle 25° 27' 30" along land now or formerly of State of New Hampshire, a distance of 108.42 feet to a point; thence turning and running N 07° 47' 15" W along land now or formerly of State of New Hampshire, a distance of 101.60 feet to a point on the southerly sideline of Gosling Road; thence turning and running N 72° 48' 15" E along the southerly sideline of Gosling Road a distance of 22.60 feet to a point; thence turning and running S 14° 53' 47" E a distance of 2.73 feet to the point of beginning.

Meaning and intending to describe Lot #1 as shown on "Subdivision Plan of Land for HBI, Gosling Road, County of Rockingham, Portsmouth, N.H.", dated December 27, 1993, prepared by Richard P. Millette and Associates, said Lot #1 containing 4.0785 acres. Plan to be recorded herewith.

Being a portion of the premises conveyed to Lawrence E. and Beatrice Carkin by deed recorded in Rockingham County Registry of Deeds, at Book #1356, Page #0416.

See also Consolidation Quitclaim Deed, dated December 17, 1993, recorded in the Rockingham County Registry of Deeds, at Book #3027, Page #1142.

"3102 P0402

Witness its hand and seal this 9<sup>th</sup> day of June, 1994.

SATURN REALTY LLC

Kathy Stavello  
Witness

By: Stephen P. Lannon Jr.  
Duly Authorized

STATE OF NEW HAMPSHIRE  
ROCKINGHAM, SS.

June 9<sup>th</sup>, 1994

Personally appeared the above-named Stephen P. Lannon Jr., a duly authorized officer of the corporation, SATURN REALTY LLC, known to me, or satisfactorily proven to be the person whose name is subscribed to the foregoing instrument and acknowledged that he executed the same for the purposes therein contained.

Before me,

Kathy Stavello  
NOTARY PUBLIC / JUSTICE OF THE PEACE  
My Commission expires: June 23, 1998  
KATHY STAVELLO, Notary Public  
My Commission Expires June 23, 1998

STATE OF NEW HAMPSHIRE

DEPARTMENT OF REVENUE ADMINISTRATION

REAL ESTATE TRANSFER TAX

XX THOUSAND XX HUNDRED AND 40 DOLLARS

|      |     |     |                |
|------|-----|-----|----------------|
| INC. | DAY | YR. | AMOUNT         |
| 05   | 30  | 95  | 183017 \$40.00 |

VOID IF ALTERED

LAW OFFICES OF  
WHOLEY & PELECH  
224 STATE STREET  
P. O. BOX 395  
PORTSMOUTH N.H.  
03802 0395

3102 P0397

ACCESS - PARKING - UTILITY - SIGNAGE EASEMENT

KNOW ALL MEN BY THESE PRESENTS, That **ROBERT D. HAVERTY and KATHLEEN M. HAVERTY, Trustees of SFL REALTY TRUST**, under Declaration of Trust dated June 1, 1994, (the "Grantor") of 22 Heritage Drive in Woburn, County of Middlesex and Commonwealth of Massachusetts, for consideration paid hereby grants to **SATURN REALTY LLC**, (the "Grantee") of 1 Gosling Road in Portsmouth, County of Rockingham and State of New Hampshire (mailing address: Post Office Box 3310, Portsmouth, NH 03802), its successors, heirs and assigns, without covenants, the perpetual right and easement to lay, construct, inspect, repair, maintain, renew, replace and remove any and all utilities, whether underground or above ground including but not limited to sewer mains, water mains, gas lines, electrical lines, telephone lines, aligns, pipes, conduits, and cables for any and all other utilities of any type and nature as may be required by the Grantee over, across and through land of the Grantor as hereinafter described in Exhibit "A" attached hereto.

Grantor, on behalf of its self, its successors and assigns, for consideration paid hereby grants to the Grantee, without covenants, a perpetual, non-exclusive right and easement to the Grantee, their successors, assigns, customers, guests, licensees, invitees, sub-tenants, employees and agents, in common with the Grantor its customers, guests, licensees, invitees, sub-tenants, employees and agents, over and across land of the Grantor, more particularly described in Exhibit "A" attached hereto for purposes of vehicular and pedestrian ingress and egress over and across any and all driveways, traffic lanes, parking areas, and roadways, and further for the purpose of the parking of motor vehicles, including, without limitation, service vehicles.

Grantor further conveys to Grantee, its successors, assigns and tenants, without covenant a perpetual easement over and upon the premises described in Exhibit "A" attached hereto for the purpose of erecting signage to benefit Grantee, its successors, assigns and tenants, provided, however, that any signage erected be approved by Grantor and the City of Portsmouth as to location, size, height and illumination.

The actual location of all utilities, access ways, parking areas and sign locations areas shown on plans entitled "Site Plan for H.B.I., Gosling Road, County of Rockingham, Portsmouth, New Hampshire, dated 1-17-94, revised 4-13-94, 4-18-94 - Sheets 3 of 11 and 4 of 11 - " prepared by Richard P. Millette and Associates, to be recorded herewith, and any future amendments thereto.

MAY 30 11 59 AM '95

019138

ROCKINGHAM COUNTY  
REGISTRY OF DEEDS

LAW OFFICES OF  
WHOLEY & PELECH  
224 STATE STREET  
P O BOX 395  
PORTSMOUTH N H  
03802 0395

"3102 P0398

Exhibit "A"

PORTSMOUTH, NEW HAMPSHIRE

A certain tract or parcel of land situate on Gosling Road in the City of Portsmouth, County of Rockingham and State of New Hampshire, known as Lot #2, and being more particularly bounded and described as follows:

Beginning at the northwesterly corner of within described premises at a point on the southerly side of Gosling Road thence running by the southerly sideline of said Gosling Road N 75° 20' 35" E a distance of 352.75 feet to a point at land now or formerly of Kentucky Fried Chicken; thence turning and running S 36° 45' 15" E by land of said Kentucky Fried Chicken a distance of 190.44 feet to a point; thence turning and running S 35° 35' 50" E by land of said Kentucky Fried Chicken a distance of 211.26 feet to a metal post; thence turning and running S 74° 13' 35" W along land of said Kentucky Fried Chicken a distance of 270.64 feet to a tree at the end of a wire fence; thence turning and running S 37° 15' 30" E along land of said Kentucky Fried Chicken a distance of 43.12 feet to a point; thence turning and running S 44° 42' 55" E along land of said Kentucky Fried Chicken a distance of 145.22 feet to a six (6") hickory tree with wire; thence turning and running S 35° 30' 25" E along land of said Kentucky Fried Chicken a distance of 64.86 feet to a stump with wire; thence turning and running S 44° 28' 10" E along land of said Kentucky Fried Chicken a distance of 108.29 feet to a tack in an eight (8") inch hickory tree with wire; thence turning and running S 34° 29' 40" E along land of said Kentucky Fried Chicken a distance of 138.29 feet to a stump with a wire; thence turning and running S 39° 44' 45" E along land of said Kentucky Fried Chicken a distance of 57.91 feet to a point; thence turning and running S 71° 45' 55" W along land now or formerly of Costco Wholesale Corp. a distance of 158.98 feet to a point; thence turning and running S 74° 49' 25" W along land of said Costco Wholesale Corp. a distance of 89.45 feet to a point; thence turning and running S 71° 09' 55" W along land of said Costco Wholesale Corp. a distance of 100.00 feet to a point; thence turning and running S 69° 05' 25" W by land of said Costco Wholesale Corp. a distance of 61.63 feet to a point; thence turning and running N 30° 52' 30" W by other land of the within Grantor a distance of 257.67 feet to a point; thence turning and running N 51° 58' 44" W by other land of the within Grantor a distance of 247.14 feet; thence turning and running N 17° 53' 36" E by other land of the within Grantor a distance of 169.08 feet to a point; thence turning and running N 14° 34' 24" W by other land of the within Grantor a distance of 170.03 feet to a point; thence turning and running N 11° 12' 58" E by other land of the within Grantor a distance of 166.55 feet to the point of beginning.

Meaning and intending to describe Lot #2 as shown on plan entitled "Subdivision Plan of Land for HBI, Gosling Road, County of Rockingham, Portsmouth, N.H.", dated December 27, 1993, prepared by Richard P. Millette and Associates, said Lot #2 containing 9.0050 acres. Plan to be recorded herewith.

Being a portion of the premises conveyed to Lawrence E. and Beatrice Carkin by deed recorded in Rockingham County Registry of Deeds, at Book #1356, Page #0416.

See also Consolidation Quitclaim Deed, dated December 17, 1993, recorded in the Rockingham County Registry of Deeds, at Book #3027, Page #1142.

FF 3102 P0399

WITNESS its hand and seal this 9<sup>th</sup> day of June, 1994.

SFL REALTY TRUST

Kathy Detwiler  
Witness

By [Signature]  
Trustee

STATE OF NEW HAMPSHIRE  
ROCKINGHAM, SS.

June 9<sup>th</sup>, 1994

Personally appeared the above-named Robert D. Heverly, a duly authorized Trustee of SFL REALTY TRUST, known to me, or satisfactorily proven to be the person whose name is subscribed to the foregoing instrument and acknowledged that he executed the same for the purposes therein contained.

Before me,

Kathy Detwiler  
NOTARY PUBLIC / JUSTICE OF THE PEACE  
My Commission expires:

KATHY PAMUNELLA, Notary Public  
My Commission Expires Jan 23, 1998

NH Transfer Tax Amount

STATE OF NEW HAMPSHIRE

DEPARTMENT OF REVENUE ADMINISTRATION REAL ESTATE TRANSFER TAX

THOUSAND  HUNDRED AND 40 DOLLARS

|    |     |    |          |
|----|-----|----|----------|
| MO | DAY | YR | AMOUNT   |
| 05 | 30  | 95 | \$ 40.00 |

VOID IF ALTERED

LAW OFFICES OF  
WHOLEY & PELECH  
224 STATE STREET  
P O BOX 395  
PORTSMOUTH, N H  
03802-0395

PK 3102 P0391

ACCESS EASEMENT

KNOW ALL MEN BY THESE PRESENTS, That **COSTCO WHOLESALE CORPORATION** of 10809 120 Avenue, Kirkland, County of King and State of Washington, for and in consideration of One (\$1.00) Dollar and other valuable consideration does hereby grant to **ROBERT D. HAVERTY and KATHLEEN M. HAVERTY, Trustees of SPL REALTY TRUST**, under Declaration of Trust dated June 1, 1994, of 22 Heritage Drive, Woburn, County of Middlesex and Commonwealth of Massachusetts, an easement for the purpose of ingress and egress over and upon land of the Grantor, situate at Gosling Road, Portsmouth, County of Rockingham and State of New Hampshire, more particularly bounded and described as follows:

PORTSMOUTH, NEW HAMPSHIRE

Beginning at a point on the westerly side of a cul-de-sac at the terminus of Durgin Lane, thence running S 73° 57' 23" W a distance of 253.97 feet by land of the within Grantor to a point; thence turning and running N 17° 21' 16" W by land of the Grantor a distance of 383.60 feet to a point; thence turning and running N 05° 45' 02" E a distance of 44.70 feet to a point in the southerly sideline of property of the within Grantee; thence turning and running by land of the within Grantee N 72° 38' 12" E a distance of 32.62 feet to a point; thence turning and running S 05° 45' 02" W by land of the Grantor a distance of 51.37 feet to a point; thence turning and running S 17° 21' 16" E by land of the Grantor a distance of 348.14 feet to a point; thence turning and running N 73° 57' 23" E by land of the Grantor a distance of 224.65 feet to a point on a cul-de-sac representing the westerly terminus of Durgin Lane; thence turning and running by an arc of a curve to the left, having a radius of 60.00 feet, and a central angle of 28° 57' 18", a distance of 30.32 feet to the point of beginning.

Being a portion of the premises conveyed to the Grantor by deeds of Louis L. Dow and Beverly Dow recorded in the Rockingham County Registry of Deeds at Book 2071, Page 223; Robert S. Farrington, recorded in said registry at Book 2811, Page 1701; Barbara F. (Lane) Leroux, recorded in said registry at Book 2071, Page 219 and Book 2023, Page 157.

ROCKINGHAM COUNTY  
REGISTRY OF DEEDS  
MAY 30 11 57 AM '95  
019135

|                                      |     |                           |         |
|--------------------------------------|-----|---------------------------|---------|
| STATE OF NEW HAMPSHIRE               |     |                           |         |
| DEPARTMENT OF REVENUE ADMINISTRATION |     | REAL ESTATE TRANSFER TAX  |         |
| XX THOUSAND                          |     | XX HUNDRED AND 40 DOLLARS |         |
| MO                                   | DAY | YR                        | AMOUNT  |
| 25                                   | 30  | 95                        | \$40.00 |
| VOID IF ALTERED                      |     |                           |         |



3102 P0392

The within Access Easement is shown on Plan entitled "Cross Easement Plan for Costco Wholesale Corporation and SFL Realty Trust", by Richard P. Millette and Associates, dated February 10, 1994, revised June 1, 1994, to be recorded herewith.

WITNESS its hand and seal this 9<sup>th</sup> day of June, 1994.

COSTCO WHOLESALE CORPORATION

[Signature]  
Witness:

\* [Signature]  
By its duly authorized officer

STATE OF NEW HAMPSHIRE  
ROCKINGHAM, SS

June 9, 1994

Personally appeared the above-named, Franz E. Lazarius  
Executive Vice President, a duly authorized officer of the corporation, Costco Wholesale Corporation, known to me, or satisfactorily proven, to be the person whose name is subscribed to the foregoing instrument and acknowledged that he executed the same for the purposes therein contained.

Before me,

[Signature]  
Notary Public  
Justice of the Peace



My Commission expires:

NOTARY PUBLIC  
STATE OF MASS. AT LARGE  
MY COMMISSION EXPIRES  
NOV. 7TH 1997

E5071-001  
November 27, 2024

Mr. Peter Britz, Director of Planning & Sustainability  
City of Portsmouth Planning & Sustainability Department  
1 Junkins Avenue  
Portsmouth, New Hampshire 03801

Re: **Response to Comments – Sewer and Water Peer Review  
100 Durgin Lane – Proposed Redevelopment**

Dear Peter:

Tighe & Bond has prepared this letter in response to peer review comments on the subject project received from Weston & Sampson (W&S) in letters dated October 24, 2024 (100 Durgin Lane Development – Water System Review) and October 29, 2024 (Portsmouth Sewer Capacity Review – 100 Durgin Lane Development). For ease of review, recommendations made by the peer reviews are repeated herein in *italics*, followed by our response in **bold** for each.

## **Water System Review**

The following recommendations were made by Weston & Sampson as part of their review of the water system evaluation for the proposed development:

*In general, the water utility design drawings include appropriate notes for necessary coordination with the City. The drawings provide a few details for water main design, but also note that the water main must be installed according to City standards. It is recommended that the drawings be updated to reflect a proposed water main size of 8-inch diameter pipe.*

*The hydraulic model suggest that an 8-inch looped main by the developer paired with replacement of the 6-inch main in Woodbury Avenue with a 12-inch main will provide optimum flows for the development and minimize impact of the development on distribution pressures during peak demand conditions. This upsizing improvement would allow an available flow of approximately 3,500 gpm to reach the development area, approximately 1,000 gpm more than just installing the proposed 8-inch looped main on the development site. Static pressures should be considered at higher floors of the proposed buildings. Booster pumps may be necessary to serve the proposed customers.*

**The last set of drawings submitted to the TAC on 10/23/2024 include callouts to specify an 8-inch diameter main loop around the proposed development.**

**The last submission to the TAC on 10/23/2024 included a schematic design plan showing the proposed replacement of the 6-inch main in Woodbury Avenue with a 12-inch main (“Woodbury Ave Water Line Replacement”). The Applicant will continue to coordinate with the City of Portsmouth to refine the design and scope of the improvements.**



**Additional comments regarding static pressures and potential booster pumps are acknowledged. Building plumbing and fire protection design will implement booster pumps if deemed necessary.**

## **Sewer Capacity Review**

The peer review concluded that the proposed development is not anticipated to increase flows to the existing downstream system beyond current available capacity. Therefore, the Applicant proposes no modification to the current plans.


If you have any questions or need any additional information, please contact Patrick Crimmins or Neil Hansen by phone at (603) 433-8818 or by email at [pmcrimmins@tighebond.com](mailto:pmcrimmins@tighebond.com) / [nahansen@tighebond.com](mailto:nahansen@tighebond.com).

Sincerely,

**TIGHE & BOND, INC.**



Patrick M. Crimmins, PE  
Vice President




Neil A. Hansen, PE  
Project Manager

Copy: Eastern Real Estate (via email)


\\\\tighebond.com\data\Data\Projects\E\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Reports\Applications\City of Portsmouth\20241127\_Water Sewer Review Response\E5071-001 Water & Sewer Review Letter.docx

PROPOSED MULTI-FAMILY DEVELOPMENT  
 DURGIN LANE  
 PORTSMOUTH, NEW HAMPSHIRE

IMPERVIOUS SURFACE  
 REDUCTION EXHIBIT




**EXISTING IMPERVIOUS SURFACES**  
 SCALE 1" = 100'



**PROPOSED IMPERVIOUS SURFACES**  
 SCALE 1" = 100'

| Impervious Surface Within Site |            |
|--------------------------------|------------|
| Existing Conditions            | 434,787 sf |
| Proposed Development           | 416,950 sf |
| Net Impervious Cover           | -17,837 sf |



**Tighe & Bond**

Last Save Date: October 21, 2024 5:12 PM By: BCURCIO  
 Plot Date: Monday, October 21, 2024 Plotted By: Benjamin Curcio  
 TSS File Location: \\tighebond.com\data\Projects\E5071-Eastern Real Estate\01 - Portsmouth, NH - 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg Layout Tab: IMPERV-COMP

PROPOSED MULTI-FAMILY DEVELOPMENT  
 DURGIN LANE  
 PORTSMOUTH, NEW HAMPSHIRE

WETLAND BUFFER IMPERVIOUS  
 SURFACE EXHIBIT




**EXISTING WETLAND BUFFER IMPERVIOUS SURFACE**  
 SCALE 1" = 100'



**PROPOSED WETLAND BUFFER IMPERVIOUS SURFACE**  
 SCALE 1" = 100'

| Impervious Surface Within Buffer Area |                    |                      |
|---------------------------------------|--------------------|----------------------|
| Local Wetland Buffer Setback          | Impervious Surface |                      |
|                                       | Existing Condition | Proposed Development |
| 0 - 25 FT                             | 3,114 SF           | 2,467 SF             |
| 25 - 50 FT                            | 12,156 SF          | 8,526 SF             |
| 50 - 100 FT                           | 45,975 SF          | 33,333 SF            |
| <b>Total Impervious Surface</b>       | <b>61,245 SF</b>   | <b>44,326 SF</b>     |
| <b>Net Impervious Surface</b>         | <b>-16,919 SF</b>  |                      |



**Tighe & Bond**


Last Save Date: October 21, 2024 5:12 PM By: BCURCIO  
 Plot Date: Monday, October 21, 2024 Plotted By: Benjamin Curcio  
 TSS File Location: \\tighebond.com\data\Projects\E5071-001-FIGS.dwg Layout Tab: BUFFER PRE & POST

PROPOSED MULTI-FAMILY DEVELOPMENT  
 DURGIN LANE  
 PORTSMOUTH, NEW HAMPSHIRE

WETLAND BUFFER IMPERVIOUS  
 COMPARISON EXHIBIT




| Wetland Buffer Impervious Surface Comparison |                   |
|--|-------------------|
| Impervious Surface Removed                   | 30,865 SF         |
| Impervious Surface Added                     | 13,946 SF         |
| <b>Net Impervious Surface</b>                | <b>-16,919 SF</b> |



Last Save Date: October 21, 2024 5:12 PM By: BCURCIO  
 Plot Date: Monday, October 21, 2024 Plotted By: Benjamin Curcio  
 T&B File Location: \\fighnbond.com\data\Projects\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg Layout Tab: BUFFER COMP

Last Saved Date: 11/4/2024  
 Plotted On: Nov 04, 2024-1:34pm By: BCurcio  
 T&B File Location: \\tighebond.com\data\Projects\E\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg



**MULTI-USE PATH  
EXTENSION STUDY AREA**

PREVIOUS EDGE OF WALK

WIDTH OF PROPOSED WALK INCREASED  
FROM 6'-WIDE TO 10'-WIDE  
(TO MATCH WIDTH OFF-SITE MUTLI-USE  
PATH REQUESTED BY THE CITY)

RELOCATED (1) PARKING SPACE  
CLOSER TO AMENITY BUILDING

ALIGNMENT OF DRIVE  
SLIGHTLY MODIFIED

PREVIOUS EDGE OF  
DRIVE AISLE

**DRIVE AISLE & PARKING  
STUDY AREA**

50' LIMITED  
CUT BUFFER

25' VEGETATED  
BUFFER

**WETLAND BUFFER IMPACT COMPARISON**

| LOCATION                 | 9/16/24 CC RECOMMENDATION FOR APPROVAL | 10/23/24 TAC SUBMISSION | DELTA   |
|--------------------------|--|-------------------------|---------|
| DRIVE AISLE & PARKING    | 4,663 SF                               | 4,459 SF                | -204 SF |
| MULTI-USE PATH EXTENSION | 3,114 SF                               | 3,727 SF                | +608 SF |

NET CHANGE +404 SF

**Tighe&Bond**



www.tighebond.com

177 Corporate Drive  
Portsmouth, NH 03801  
(603) 433-8818

**100 DURGIN LANE**

**WETLAND BUFFER  
IMPACTS MODIFICATION  
CLARIFICATION**

DATE: 11/4/2024



GRAPHIC SCALE

**PROPOSED MULTI-FAMILY DEVELOPMENT**  
**100 DURGIN LANE**  
**PORTSMOUTH, NEW HAMPSHIRE**

---

**GRADE PLANE EXHIBIT 1**

| BUILDING 1 ELEVATION AND HEIGHT |                    |          |                 |          |
|---------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION           | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                 | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 66.66                           | 116.66'            | 107.75'  | 50.00'          | 40.00    |

| BUILDING 5 ELEVATION AND HEIGHT |                    |          |                 |          |
|---------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION           | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                 | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 65.99                           | 115.99'            | 114.50'  | 50.00'          | 47.50'   |

| BUILDING 2 ELEVATION AND HEIGHT |                    |          |                 |          |
|---------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION           | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                 | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 66.16                           | 116.16'            | 108.00'  | 50.00'          | 40.00    |



| BUILDING 6 ELEVATION AND HEIGHT |                    |          |                 |          |
|---------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION           | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                 | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 66.57                           | 116.57'            | 108.00'  | 50.00'          | 40.00'   |

| BUILDING 3 ELEVATION AND HEIGHT |                    |          |                 |          |
|---------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION           | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                 | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 6.51                            | 116.51'            | 114.25'  | 50.00'          | 47.50'   |

| BUILDING 7 ELEVATION AND HEIGHT |                    |          |                 |          |
|---------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION           | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                 | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 67.97                           | 117.97'            | 108.00'  | 50.00'          | 40.00'   |

| BUILDING 4 ELEVATION AND HEIGHT |                    |          |                 |          |
|---------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION           | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                 | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 65.79                           | 115.79'            | 114.50'  | 50.00'          | 47.50'   |

| BUILDING 8 ELEVATION AND HEIGHT |                    |          |                 |          |
|---------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION           | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                 | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 65.63'                          | 115.63'            | 115.00'  | 50.00'          | 47.50'   |



**Tighe & Bond**

Last Save Date: October 21, 2024 6:57 PM By: BCURCIO  
 Plot Date: Tuesday, October 22, 2024 Plotted By: Benjamin Curcio  
 TSS File Location: \\fighnbond.com\data\Projects\E5071-Eastern Real Estate\001-Portsmouth, NH-100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg Layout Tab: GRADE PLANE 1



**PROPOSED MULTI-FAMILY DEVELOPMENT**  
**100 DURGIN LANE**  
**PORTSMOUTH, NEW HAMPSHIRE**

---

**GRADE PLANE EXHIBIT 2**

| BUILDING 9 ELEVATION AND HEIGHT |                    |          |                 |          |
|---------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION           | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                 | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 65.87'                          | 115.87'            | 114.75'  | 50.00'          | 47.50'   |

| BUILDING 15 ELEVATION AND HEIGHT |                    |          |                 |          |
|----------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION            | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                  | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 64.51'                           | 114.51'            | 113.25'  | 50.00'          | 47.50'   |

| BUILDING 10 ELEVATION AND HEIGHT |                    |          |                 |          |
|----------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION            | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                  | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 65.73'                           | 115.73'            | 107.25'  | 50.00'          | 40.00'   |

| BUILDING 16 ELEVATION AND HEIGHT |                    |          |                 |          |
|----------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION            | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                  | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 64.12'                           | 114.12'            | 103.50'  | 50.00'          | 40.00'   |



| BUILDING 11 ELEVATION AND HEIGHT |                    |          |                 |          |
|----------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION            | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                  | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 65.99'                           | 115.99'            | 107.00'  | 50.00'          | 40.00'   |

| BUILDING 17 ELEVATION AND HEIGHT |                    |          |                 |          |
|----------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION            | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                  | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 63.03'                           | 113.03'            | 103.50'  | 50.00'          | 40.00'   |

| BUILDING 12 ELEVATION AND HEIGHT |                    |          |                 |          |
|----------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION            | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                  | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 65.98'                           | 115.98'            | 107.00'  | 50.00'          | 40.00'   |

| BUILDING 13 ELEVATION AND HEIGHT |                    |          |                 |          |
|----------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION            | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                  | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 65.14'                           | 115.14'            | 106.75'  | 50.00'          | 40.00'   |

| BUILDING 14 ELEVATION AND HEIGHT |                    |          |                 |          |
|----------------------------------|--------------------|----------|-----------------|----------|
| GRADE PLANE ELEVATION            | BUILDING ELEVATION |          | BUILDING HEIGHT |          |
|                                  | ALLOWED            | PROPOSED | ALLOWED         | PROPOSED |
| 64.46'                           | 114.46'            | 106.25'  | 50.00'          | 40.00'   |





**Tighe & Bond**

OCTOBER 23, 2024  
E5071-001-FIGS.dwg

Last Save Date: October 21, 2024 6:57 PM By: BCURCIO  
 Plot Date: Tuesday, October 22, 2024 Plotted By: Benjamin Curcio  
 T&B File Location: \\fighnbond.com\data\Projects\E5071-Eastern Real Estate\001-Portsmouth, NH-100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg Layout Tab: GRADE PLANE 2

PROPOSED MULTI-FAMILY DEVELOPMENT  
 DURGIN LANE  
 PORTSMOUTH, NEW HAMPSHIRE

FIRE TRUCK TURNING EXHIBIT 1




Portsmouth Fire Truck  
 Overall Length  
 Overall Width  
 Overall Body Height  
 Min Body Ground Clearance  
 Track Width  
 Lock-to-lock time  
 Max Steering Angle (Virtual)

47.830ft  
 8.500ft  
 10.432ft  
 0.862ft  
 8.000ft  
 6.00s  
 38.00°

LEGEND

- FORWARD VEHICLE WHEEL BASE
- FORWARD VEHICLE OVERHANG





**Tighe & Bond**

OCTOBER 23, 2024  
 E5071-001-FIGS.dwg

PROPOSED MULTI-FAMILY DEVELOPMENT  
DURGIN LANE  
PORTSMOUTH, NEW HAMPSHIRE

FIRE TRUCK TURNING EXHIBIT 2




Portsmouth Fire Truck  
 Overall Length  
 Overall Width  
 Overall Body Height  
 Min Body Ground Clearance  
 Track Width  
 Lock-to-lock time  
 Max Steering Angle (Virtual)

47.830ft  
 8.500ft  
 10.432ft  
 0.862ft  
 8.000ft  
 6.00s  
 38.00°

LEGEND

- FORWARD VEHICLE WHEEL BASE
- FORWARD VEHICLE OVERHANG





**Tighe & Bond**

OCTOBER 23, 2024  
E5071-001-FIGS.dwg

PROPOSED MULTI-FAMILY DEVELOPMENT  
DURGIN LANE  
PORTSMOUTH, NEW HAMPSHIRE

FIRE TRUCK TURNING EXHIBIT 3





Portsmouth Fire Truck  
Overall Length  
Overall Width  
Overall Body Height  
Min Body Ground Clearance  
Track Width  
Lock-to-lock time  
Max Steering Angle (Virtual)

47.830ft  
8.500ft  
10.432ft  
0.862ft  
8.000ft  
6.00s  
38.00°

LEGEND


- FORWARD VEHICLE WHEEL BASE
- FORWARD VEHICLE OVERHANG



**Tighe & Bond**

OCTOBER 23, 2024  
E5071-001-FIGS.dwg

Plotted On: Oct 21, 2024 6:43pm By: BCurcio  
Tighe & Bond: \\Tighebond.com\data\Projects\E\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg



PRINCIPAL BUILDING LINE

LIMIT OF OFF-STREET PARKING RESTRICTION PER SECTION 10.5B83.10

EDGE OF EXISTING STREET (TYP.)

PROPERTY LINE

DURGIN LANE




**10.5B83 Location of Motor Vehicle Parking Facilities**


10.5B83.10 Required **off-street parking** spaces shall not be located between a **principal building** and a **street** or within any required perimeter buffer area.


**Street**  
A thoroughfare or roadway which is either  
(a) formally accepted by the City, or  
(b) shown on a subdivision plan approved by the Planning Board and constructed to City subdivision specifications or for which surety has been posted to guarantee construction of all improvements required by the Planning Board.

**NOTE:** THE INTENT OF THIS FIGURE IS TO DEMONSTRATE COMPLIANCE WITH SECTION 10.5B83.10 OF THE CITY OF PORTSMOUTH ZONING ORDINANCE ("LOCATION OF MOTOR VEHICLE PARKING FACILITIES")

**LEGEND**

-  EXISTING STREET
-  PRINCIPAL BUILDING LINE
-  LIMIT OF OFF-STREET PARKING RESTRICTION PER 10.5B83.10



|   |   |
|---|---|
| 100 DURGIN LANE<br>PORTSMOUTH, NH               |   |
| ZONING EXHIBITS                                 |   |
| LOCATION OF MOTOR VEHICLE<br>PARKING FACILITIES |   |
| DATE: 10/23/2024                                |  |
| SCALE: AS SHOWN                                 |   |
| FIGURE: 1 OF 1                                  |   |

**NOTE**  
 1. THE INTENT OF THIS FIGURE IS TO DEMONSTRATE TO THE PLANNING BOARD THAT THE LAND USES ALONG THE BOUNDARY OF THE DEVELOPMENT SITE (WETLAND, WETLAND BUFFER & OVERHEAD UTILITY EASEMENT) ARE INCOMPATIBLE WITH THE REQUIRED BUILDING SETBACK FROM THE LOT LINE. THE APPLICANT IS REQUESTING THE PLANNING BOARD TO ALLOW AN INCREASE OF BUILDING SETBACK FROM THE FRONT LOT LINE AS ALLOWED BY SECTION 10.5B41.60.

100' WETLAND BUFFER (TYP.)

100' WETLAND BUFFER (TYP.)

EXISTING 300'-WIDE OVERHEAD UTILITY EASEMENT (TYP.)

PROPERTY LINE (TYP.)

**10.5B34.80 Mixed Use Building**

| LOT STANDARDS                               |                         |
|---|-------------------------|
| Minimum lot depth                           | NR                      |
| Minimum street frontage                     | 50 ft                   |
| Front building setback from lot line        | 0 ft min. to 50 ft max. |
| Minimum side building setback from lot line | 15 ft                   |
| Minimum rear building setback from lot line | 20 ft                   |
| Minimum open space coverage                 | 20%                     |


**10.5B34.40 Apartment Building**

| LOT STANDARDS                               |                          |
|---|--------------------------|
| Minimum lot depth                           | NR                       |
| Minimum street frontage                     | 50 ft                    |
| Front building setback from lot line        | 10 ft min. to 30 ft max. |
| Minimum side building setback from lot line | 15 ft                    |
| Minimum rear building setback from lot line | 20 ft                    |
| Minimum open space coverage                 | 20%                      |

**10.5B41.60 Perimeter Buffer:** The perimeter buffer requirements apply to the outside boundary of the development site where the site abuts adjoining properties that are not part of the development site, but not along the primary street frontage. In addition to the minimum perimeter buffer required, the Planning Board may require landscaping, fencing, or an increase in the building setback from lot lines where adjacent land uses may be incompatible. Perimeter buffer requirements supersede parking setback requirements and building setbacks from lot lines requirements for individual building types.

**LEGEND**

- WETLAND BUFFER AREA
- OVERHEAD UTILITY EASEMENT AREA



100 DURGIN LANE  
 PORTSMOUTH, NH

ZONING EXHIBITS


FRONT BUILDING SETBACK

DATE: 10/23/2024  
 SCALE: AS SHOWN  
 FIGURE: 1 OF 1



Plotted On: Oct 22, 2024 9:04am By: BCurcio  
 Tighe & Bond: \\Tighebond.com\data\Projects\EI\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane Drawings\AutoCAD\Sheet\E5071-001-FIGS.dwg

Last Saved Date: 10/21/2024  
 Plotted On: Oct 21, 2024 4:46:00pm By: BCurcio  
 File Location: \\tbg\work\100 Durgh Lane\100 Durgh Lane\Drawings\AutoCAD\Sheet\ES071-001-FIGS.dwg



BLOCK PERIMETER = 730'  
MAX BLOCK LENGTH = 271'

BLOCK PERIMETER = 1069'  
MAX BLOCK LENGTH = 442'

BLOCK PERIMETER = 645'  
MAX BLOCK LENGTH = 233'

BLOCK PERIMETER = 1041'  
MAX BLOCK LENGTH = 430'

BLOCK PERIMETER = 931'  
MAX BLOCK LENGTH = 362'

BLOCK PERIMETER = 1266'  
MAX BLOCK LENGTH = 391'

| DEVELOPMENT STANDARDS                       |   |
|---|---|
| Minimum <b>development site area</b>        | 10,000 sf   |
| Minimum site width                          | 75 ft   |
| Minimum site depth                          | 100 ft  |
| Minimum perimeter buffer                    | 75 ft from a Residential District, Mixed Residential District, or Character District 4-L1                                   |
| Maximum <b>development block dimensions</b> | <b>block length</b> 500 ft;<br><b>block perimeter</b> 1,500 linear ft   |
| Maximum <b>building coverage</b>            | 50%   |
| Minimum <b>open space coverage</b>          | 20%   |
| <b>Community space types</b>                | <b>greenway, park, pocket park, playground, recreation field or court, common or green, community garden, square, plaza</b> |




Figure 10.541.70 – Development Block Diagram

**NOTE:** THE INTENT OF THIS FIGURE IS TO DEMONSTRATE COMPLIANCE WITH THE MAXIMUM DEVELOPMENT BLOCK DIMENSIONS OF SECTION 10.5B41.70 OF THE CITY OF PORTSMOUTH ZONING ORDINANCE ("DEVELOPMENT BLOCK STANDARDS").


— BLOCK PERIMETER

**Tighe&Bond** 100 DURGIN LANE  
[www.tighebond.com](http://www.tighebond.com)  
 177 Corporate Drive  
 Portsmouth, NH 03801  
 (603) 433-8818

**DEVELOPMENT BLOCK STANDARDS EXHIBIT**

DATE: 10/23/2024

Last Saved Date: 10/21/2024  
Plotted On: Oct 21, 2024 4:26pm By: BCurcio  
Plot File Location: \\tgbond.com\data\Bart\Projects\EL\ES071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\ES071-001-FIGS.dwg



PROPOSED LOT LINE (TYP.)

PROPOSED LOT 2  
±206,429 SF

PROPOSED LOT LINE (TYP.)

EXISTING LOT LINE TO BE RELOCATED

PROPOSED LOT LINE (TYP.)

PROPOSED LOT 1  
±871,390 SF

BUILDING #7

PROPOSED LOT 3  
±61,342 SF

BUILDING #8

BUILDING #10

BUILDING #5

BUILDING #11

BUILDING #12

BUILDING #4

BUILDING #13

BUILDING #14

BUILDING #1

BUILDING #2

BUILDING #3

BUILDING #15

BUILDING #16

BUILDING #17


LOT LINE REVISIONS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY.  
FINAL LOT LINE REVISION PLAN SHALL BE PREPARED BY THE PROJECT  
SURVEYOR AND RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF  
DEEDS PRIOR TO ISSUING BUILDING PERMITS.

**Tighe & Bond** 100 DURGIN LANE  
www.tighebond.com  
177 Corporate Drive  
Portsmouth, NH 03801  
(603) 433-8818  
DATE: 10/23/2024

**LOT LINE REVISION EXHIBIT**



Last Saved Date: 6/25/2024  
 Plotted On: Jun 27, 2024 11:16am By: BCurcio  
 Plot File Location: \\tbg-bond.com\data\pba\Projects\E15971\_Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E15971-001-FIGS.dwg






**LEGEND**

- |  |  |  |  |
|--|--|--|--|
|  | EXISTING ACCESS EASEMENT 1<br>BOOK 5498, PAGE 2502   |  | EXISTING ACCESS, PARKING, UTILITY, SIGNAGE EASEMENT (APPROXIMATE)<br>BOOK 3102, PAGE 397   BOOK 3102, PAGE 400   BOOK 3202 PAGE 2462 |
|  | EXISTING ACCESS EASEMENT 2<br>BOOK 5498, PAGE 2502   |  | EXISTING ACCESS EASEMENT THROUGH MAP 238 LOT 20 (APPROXIMATE)<br>BOOK 4707, PAGE 1682   BOOK 4875, PAGE 1439                         |
|  | EXISTING ACCESS EASEMENT 3<br>BOOK 3102, PAGE 381   BOOK 3160, PAGE 2033                       |  | EXISTING SEWER EASEMENT<br>BOOK 3102, PAGE 379   |
|  | EXISTING SLOPE AND LANDSCAPE EASEMENT<br>BOOK 3160, PAGE 2046                                  |  | EXISTING REAL ESTATE OPERATION AGREEMENT EASEMENT<br>BOOK 3114, PAGE 601   |
|  | EXISTING UTILITY EASEMENT 1<br>BOOK 3160, 2039   |  | EXISTING CONSERVATION EASEMENT<br>BOOK 3192, PAGE 282  |
|  | EXISTING ACCESS, DRAINAGE, & UTILITY EASEMENT 1<br>BOOK 2956, PAGE 2205   BOOK 3160, PAGE 2051 |  | EXISTING 300'-WIDE UTILITY EASEMENT<br>BOOK 2972, PAGE 1422  |
|  | EXISTING UTILITY AND DRAINAGE EASEMENT 1<br>BOOK 2956, PAGE 2205   BOOK 3160, PAGE 2051        |  |  |

**Tighe & Bond**  
 www.tighebond.com  
 177 Corporate Drive  
 Portsmouth, NH 03801  
 (603) 433-8818

**100 DURGIN LANE**  
**EXISTING EASEMENT EXHIBIT**  
 DATE: 10/16/2024

NOTES:  
 1. ALL EXISTING UTILITIES LOCATIONS, SHOWN WERE DERIVED FROM A CAD FILE RECEIVED BY THE CITY OF PORTSMOUTH PUBLIC WORKS ON 9/12/2024 AND SHALL BE CONSIDERED APPROXIMATE. ALL LOCATIONS SHALL BE VERIFIED IN THE FIELD.



SCHEMATIC DRAWINGS

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 10/3/2024            |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |

WOODBURY AVE WATER LINE REPLACEMENT

SCALE: AS SHOWN

**SCHEMATIC DRAWINGS**

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE



|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 11/27/2024           |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |

10' MULTI-USE SIDEWALK DEMO PLAN


SCALE: AS SHOWN

**EXHIBIT 1**



NOTES:  
 1. ALL EXISTING PAVEMENT EDGE AND BUILDING LOCATIONS SHOWN BEYOND THE LIMITS OF THE SURVEY WERE DERIVED FROM A CAD FILE RECEIVED BY THE CITY OF PORTSMOUTH PUBLIC WORKS ON 9/12/2024 AND SHALL BE CONSIDERED APPROXIMATE. ALL LOCATIONS SHALL BE VERIFIED IN THE FIELD.



Last Saved: 11/21/2024 1:38pm By: BCurcio  
 Plotted On: Nov 21, 2024 1:38pm  
 Tighe & Bond \Vigobond\dwg\AutoCAD\Projects\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN.dwg



NOTES:  
 1. ALL EXISTING PAVEMENT EDGE AND BUILDING LOCATIONS SHOWN BEYOND THE LIMITS OF THE SURVEY WERE DERIVED FROM A CAD FILE RECEIVED BY THE CITY OF PORTSMOUTH PUBLIC WORKS ON 9/12/2024 AND SHALL BE CONSIDERED APPROXIMATE. ALL LOCATIONS SHALL BE VERIFIED IN THE FIELD.



SCHEMATIC DRAWINGS

**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 11/27/2024           |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |

10' MULTI-USE SIDEWALK SITE PLAN

SCALE: AS SHOWN

EXHIBIT 2

**PART 2 OF 2**

**100 DURGIN LANE**

**11/27/24 PB SUBMISSION  
DOCUMENTS**

**FOR**

**DECEMBER 19, 2024 PB MEETING**



100 Durgin Ln

100 DURGIN LANE OWNER,  
LLC  
100 DURGIN LANE  
PORTSMOUTH, NH

| REVISIONS | DATE |
|-----------|------|
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

October 23, 2024

RENDERED PLAN

| REVISIONS | DATE |
|-----------|------|
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |




POTENTIAL COMMUNITY SPACE



PROPOSED COMMUNITY SPACE

|                           |                                     |  |  |
|---------------------------|-------------------------------------|--|--|
|                           | POTENTIAL RESIDENT SOCIAL SPACES    |  |  |
|                           | POTENTIAL COMMUNITY SPACE (ACTIVE)  | REQUIRED<br>113,915 SF (10%)<br>(2.62 ACRES) | PROVIDED<br>120,818 SF (10.6%)<br>(2.77 ACRES) |
|                           | POTENTIAL COMMUNITY SPACE (PASSIVE) |  |  |
|                           | TOTAL DEVELOPMENT LOT               | 1,139,156 SF (26.15 ACRES)                   |  |
| COMMUNITY SPACE CONNECTOR |                                     |  |  |
|                           | WETLAND BUFFER: 50'-100'            |  |  |
|                           | WETLAND BUFFER: 25'-50'             |  |  |
|                           | WETLAND BUFFER: 0'-25'              |  |  |



100 Durgin Ln

100 DURGIN LANE OWNER,  
LLC  
100 DURGIN LANE  
PORTSMOUTH, NH

| REVISIONS | DATE |
|-----------|------|
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

October 23, 2024

PLANTING IRRIGATION /  
HYDROZONE  
DIAGRAM



Legend

- Higher Water Usage/Maint. (Lawn)
- Moderate Water Usage/Maint. (Native Trees, Shrubs, Perennials)
- Low Water Usage/Maint. (Native Meadow/Trees/Grasses)







## 100 Durgin Lane - Landscape Operations and Maintenance Manual

November 27, 2024

### Completed By:

Aceto Landscape Architects

### Completed For:

100 Durgin Lane Owner

### Overview

The intent of this plan is to help guide the management and maintenance of the 100 Durgin Lane Redevelopment Site & Landscape. This plan is intended to help preserve the original design intent of the landscape architect. This document is to be used as guidelines for the grounds maintenance staff to adhere to and reference for all surficial site and landscape related maintenance and/or replacement procedures. Refer to Civil Engineers instructions for any subsurface and/or stormwater related infrastructure.

### Weekly Tasks – May 15th to September 15th

1. Remove weeds from planting beds and dispose of off site and per local regulations. Weeds shall be removed manually (by hand). Invasive or noxious species should be removed or controlled according to local regulations and established best practices. Use of chemical herbicide is not permitted.
2. Replace bark mulch in any areas which have worn thin or been displaced by plowing or other operations. Mulch should be spread evenly, by hand. Mulch shall be dark brown or black, shredded, natural, shredded wood with no added colors or dyes blended to match surrounding planting beds.
3. Lawn shall be clipped and edged at regular intervals to maintain an optimal height of 3". Use appropriate machinery, including push mower for small or steeply sloped areas. Ensure blades are sharp and clean, free of weeds and debris. Clippings may be left in place to provide natural fertilizer. Remove clippings if growth is hindered or disease is evident.
4. Inspect plantings for signs of damage or disease. Upon approval of owner, replace dead, dying, or diseased plants in kind unless directed otherwise in consultation with a landscape architect and/or certified arborist. Consult a licensed arborist for appropriate tree pruning and treatment of disease or damage.
5. Remove debris from hard surfaces, gutters, walkways, and paving areas. Sweep and/or blow clean. Patch holes as needed with in-kind materials. Rake level any soft surface pathways.
6. Inspect irrigation system and components. Adjust heads as needed to mitigate overspray and ensure efficient, full coverage. Inspect heads and manifolds to ensure proper working order. Replace parts as needed. Adjust irrigation zone timing as needed based on growing conditions and plant health.
7. Complete monthly checklist items below:



## Monthly Tasks

### January

Water newly planted trees when drought conditions are present. Tree bags may be used when temperatures are above freezing.

### February

Perform deep-root fertilizer application using a slow-release formula. Prune shade trees as needed to remove any dead or dying limbs or those presenting visual or physical obstructions. Some shrubs may be pruned based on species. Do not shear or form shrubs into rounded or unnatural shapes unless otherwise directed.

### March

Inspect bark mulch at all planting beds and replenish as needed to a minimum depth of 3". Bark mulch shall be dark brown/black with no added colors/dyes and raked level to blend with surrounding beds. Inspect irrigation heads and manifolds for damage.

### April

Replace or re-apply mulch which has been displaced by spring rain and/or snow plowing operations. Remove excess de-icing agents and/or sand or other foreign debris within beds. Inspect irrigation heads and manifolds, de-winterize and resume regular, automatic irrigation system operation as long as temperatures remain consistently above freezing.

### May

Inspect all plant material for damage with particular focus on areas surrounding roads, parking lots, and walkways. Prune any winter damage and, with owner approval, replace any plants which have not begun to grow by late May. Supplement automatic irrigation with hand watering for any new plantings unless rainfall is abundant. Continue regular mowing of lawn areas as ground conditions permit. Rake level any soft surface pathways and mulch areas, as needed.

### June

Inspect trees for undesirable or damaged limbs and remove as needed. Provide supplemental watering to all plants as needed. Gator (tree) bags may be used to supplement irrigation for any new planting. Monitor irrigation system for coverage and inspect soil around planting areas for sufficient, consistent moisture.

### July

Prune any groundcovers or other perennial plantings overhanging curbs or sidewalks. Monitor soil moisture ensuring all planting bed soils are receiving consistent irrigation coverage. Identify problem areas and adjust coverage and frequency as needed.

### August

Continue watering plantings at regular intervals unless rainfall has been sufficient. Continue to monitor the health of plantings. Identify any plants showing signs of disease or deficiency and treat as required. In late August, shrubs may be pruned if desired. Young trees and shrubs may receive fertilizer.



### **September**

Aerate, top-dress and over-seed lawns as needed. Treat any evident nutrient deficient or diseased areas as needed. Check all plantings for any signs of water stress and adjust irrigation coverage and frequency as needed.

### **October**

Remove fallen leaves and plant litter from parking lots, walkways, and lawn. Leaves may be mulched into lawn using mulching mower if desired. Winterize irrigation system; check conditions of heads, evidence of leaks or blown pipes. Drain the system and re-program automatic controller as necessary.

### **November**

Remove fallen leaves from planting beds and lawn areas. Prune dead or unsightly limbs from trees and shrubs as needed. Remove any dead or diseased plant material from landscape and dispose off site. Re-stake young trees as needed to provide stability through winter months. Place snow stake markers along edges of paved areas and walkways in preparation from winter snow plowing as needed. Mow native seeded wetland buffer areas (1/year) after wildflowers have bloomed, or leave unmown to allow woody plant material to fill in for habitat.

### **December**

Prune any trees or shrubs in and adjacent to parking lots and walkways to remove potential obstructions. Continue leaf removal as needed. Avoid spreading de-icing salt or other chemicals in planting beds or lawn areas to the greatest extent possible. Sweep and/or remove sand or other debris within walkways.

Intertek Project No. R2107.01

October 23, 2024

Brett Bentson, AIA, LEED AP  
Principal  
Utile  
115 Kingston Street  
Boston, MA 02111

**RE: Highway Noise Overlay District Analysis  
100 Durgin Lane  
Portsmouth, New Hampshire**

Dear Brett:

We have completed a noise analysis of the 100 Durgin Lane development per the requirements of *Section 10.670 of Highway Noise Overlay District (HNOD) within the City of Portsmouth Zoning Ordinance*<sup>1</sup>. This report provides the results of the analysis as listed in *Section 10.675*.

## Project Understanding

The project consists of a 26-acre redevelopment with about half of the new development planned to be housing with approximately 10,000 sq. ft. of amenity space within one of the buildings, parking, and open space. The housing will consist of 17 4-story elevator-serviced and 3-story walk-up buildings with a total of 360 market-rate rental apartments. The buildings are planned to be a standard wood-framed construction.

The 100 Durgin Lane development also includes common outdoor areas for the people to enjoy the outdoors. A layout of the development is shown in *Figure 1*.

The project will be adjacent to State Route 4, which is a multi-lane highway, directly west of the site. The Zoning Ordinance for the City of Portsmouth includes a Highway Noise Overlay District. The requirements of this ordinance will apply to this project and are discussed below.

## Applicable Criteria

The City of Portsmouth Highway Noise Overlay District includes sound level limits for Noise Sensitive Land Uses within *Section 10.673*. *These Standards are summarized in Table 1*.


| TABLE 1. CITY OF PORTSMOUTH HIGHWAY NOISE OVERLAY DISTRICT STANDARDS (SECTION 10.673)                         |                                  |
|---|----------------------------------|
| Structures and Uses   | Loudest Traffic Hour Sound Level |
| Interior of dwelling, institutional residence or residential care facility, hospital or lodging establishment | 45 dBA                           |
| Interior of other Noise Sensitive Use   | 55 dBA                           |

<sup>1</sup> City of Portsmouth, New Hampshire Zoning Ordinance, Adopted by Portsmouth City Council December 21, 2009, effective date January 1, 2010, as amended through August 7, 2023.





|   |        |
|---|--------|
| Uses with outdoor activity areas measured at edge of the active use area closest to the highway | 65 dBA |
|---|--------|



**Figure 1. The proposed layout of 100 Durgin Lane with common outdoor areas (highlighted in blue). State Route 4 is southwest of the site.**

The 100 Durgin Lane project will need to achieve 45 dBA within the residential dwellings and 65 dBA for outdoor activity areas. To compare the exterior sound predictions with the interior sound level goal for the residential dwellings, we note that residential buildings have historically been assumed to provide a sound level reduction of 20 dBA, meaning that the allowable exterior sound level would also be 65 dBA without requiring noise mitigation.

## Noise Analysis

In accordance with the Highway Noise Overlay District requirements, we conducted a noise analysis of the proposed project using Federal Highway Administration (FHWA) Transportation Noise Model (TNM) Version 2.5 computer software. The following describes the methodology of the modeling, results, and mitigation.

### METHOD

The TNM software included three-dimensional geographical representation of roadways within the vicinity, topography, ground types, tree zones, existing buildings on neighboring land uses, and the future project buildings.



Table 2 lists the roadways included in the analysis, along with Annual Average Daily Traffic (AADT) acquired from the New Hampshire Department of Transportation website<sup>2</sup>. Using guidelines from the U.S. Department of Housing and Urban Development (HUD)<sup>3</sup>, we assumed 85% of the AADT is related to daytime traffic between the hours of 7:00 a.m. and 10:00 p.m. (15 hours total) to obtain traffic volumes for a single hour to enter into the analysis.

| <b>TABLE 2. ROADWAYS AND ANNUAL AVERAGE DAILY TRAFFIC (AADT) COUNTS INCLUDED IN THE NOISE ANALYSIS</b> |                            |                                |                        |                                |                        |
|--|----------------------------|--------------------------------|------------------------|--------------------------------|------------------------|
| <b>North/South Roadways</b>  | <b>Year Data Collected</b> | <b>NB Personal Automobiles</b> | <b>NB Heavy Trucks</b> | <b>SB Personal Automobiles</b> | <b>SB Heavy Trucks</b> |
| Highway 4  | 2022                       | 32,430                         | 2,180                  | 29,299                         | 1,971                  |
| AF Brady Off Ramp  | 2022                       | 1,897                          | 127                    | -                              | -                      |
| AF Brady On Ramp   | 2022                       | 1,547                          | 104                    | -                              | -                      |
| Newington Street / Gosling Road Off Ramp   | 2022                       | 6,006                          | 404                    | 4,263                          | 286                    |
| Newington St / Gosling Road On Ramp  | 2022                       | 3,739                          | 252                    | 4,972                          | 335                    |
| <b>East/West Roadways</b>  | <b>Year Data Collected</b> | <b>EB Personal Automobiles</b> | <b>EB Heavy Trucks</b> | <b>WB Personal Automobiles</b> | <b>WB Heavy Trucks</b> |
| Newington Street   | 2022                       | 503*                           | 34*                    | 503*                           | 34*                    |
| Gosling Road   | 2022                       | 528                            | 36                     | 463                            | 31                     |

NB = Northbound, SB = Southbound, EB = Eastbound, WB = Westbound

\*Directional AADT were not available, so the total AADT was divided evenly between the two directions.

Figure 2 is a graphical representation of the noise analysis model in plan view. In TNM, rows of buildings are typically modeled as “building rows” where the input is the average height of the buildings and the percentage of blockage provided by the buildings (typically anywhere from 20% to 80%) is included. For our analysis, we modeled the first row of buildings at 100 Durgin Lane with individual barriers representing each building to get a more detailed assessment of the noise exposure over the façades of the buildings and vicinity. Barriers were also used to represent the following buildings on other land use properties:

- South of 100 Durgin Lane
  - Home Depot
  - Hampton Inn
- North of 100 Durgin Lane
  - New Frontier Church
  - Motel 6

Building rows were used to represent the buildings at the Gosling Meadows development north of the site.


The model included a 6-foot high sound barrier proposed in the southwest corner of the project with portions along the west side that were 7 feet tall, representing the combined mitigation of the sound barrier and the car ports.

<sup>2</sup> <https://nhdot.public.ms2soft.com/tcds/tsearch.asp?loc=Nhdot&mod=TCDS>

<sup>3</sup> “The Noise Guidebook,” U.S. Department of Housing and Urban Development, March 2009.



The default ground type was “lawn” while ground zones were included in the model to represent paved parking lots and driveways on the future site, as well as parking lots and driveways on properties in the vicinity, represented by the black enclosed areas within Figure 2.



**Figure 2. Graphical representation of the TNM Noise Model for 100 Durgin Lane.**

## RESULTS

Noise levels from the Route 4 traffic to the proposed development were calculated at twenty-six individual receiver locations located throughout the Project site, as numbered in Figure 3. The locations were selected to represent the noise exposure at the future Project buildings. Receiver numbers 1, 10, 13, 19, 23 and 26 were located within the planned open common areas. Calculations were made for all receivers at a height of five feet above the local grade. It is not uncommon for upper floors to have higher noise levels than lower floors due to increased exposure to the roadways at those higher elevations. Therefore, additional calculations were made at the mid-level elevations of the top floors of the buildings. The calculated noise levels at all receivers are listed in Table 3.



**Figure 3. Receivers, numbered 1 through 26, included in the noise analysis.**





**TABLE 3. PREDICTED UNADJUSTED NOISE LEVELS FOR INDIVIDUAL RECEIVERS AT 100 DURGIN LANE.**

| Prediction Location (Description)           | HNOD<br>dBA<br>Goal* | dBA<br>@ 5 ft Above<br>Grade | dBA<br>@ Mid-level of Top<br>Floor |
|---|----------------------|------------------------------|------------------------------------|
| Receiver 01 (Building A2)                   | 65                   | 67                           | 72                                 |
| Receiver 02 (Between Building A2&B4)        | 65                   | 66                           | 72                                 |
| Receiver 03 (Between Buildings B4&E4)       | 65                   | 65                           | 71                                 |
| Receiver 04 (Building E4)                   | 65                   | 67                           | 72                                 |
| Receiver 05 (Between Buildings E4&E5 Front) | 65                   | 67                           | 71                                 |
| Receiver 06 (Between Buildings E4&E5 Back)  | 65                   | 58                           | 63                                 |
| Receiver 07 (Between Buildings E5&B5 Front) | 65                   | 67                           | 70                                 |
| Receiver 08 (Between Buildings E5&B5 Back)  | 65                   | 60                           | 65                                 |
| Receiver 09 (Building B5)                   | 65                   | 67                           | 70                                 |
| Receiver 10 (not used in study)             | -                    | -                            | -                                  |
| Receiver 11 (Building C2)                   | 65                   | 54                           | 61                                 |
| Receiver 12 (Building D2)                   | 65                   | 59                           | 64                                 |
| Receiver 13 (Front Center Common Area)      | 65                   | 51                           | -                                  |
| Receiver 14 (Building E3)                   | 65                   | 56                           | 63                                 |
| Receiver 15 (Building E2)                   | 65                   | 55                           | 59                                 |
| Receiver 16 (Building E1)                   | 65                   | 53                           | 57                                 |
| Receiver 17 (Building D1)                   | 65                   | 52                           | 57                                 |
| Receiver 18 (Building C1)                   | 65                   | 52                           | 58                                 |
| Receiver 19 (Rear Center Common Area)       | 65                   | 52                           | -                                  |
| Receiver 20 (Between Buildings F&B2)        | 65                   | 50                           | 56                                 |
| Receiver 21 (Building B2)                   | 65                   | 48                           | 56                                 |
| Receiver 22 (Building B3)                   | 65                   | 49                           | 59                                 |
| Receiver 23 (Building F, Common Building)   | 65                   | 49                           | -                                  |
| Receiver 24 (Building A1)                   | 65                   | 56                           | 60                                 |
| Receiver 25 (Building B1)                   | 65                   | 55                           | 59                                 |
| Receiver 26 (Dog Run)                       | 65                   | 65                           | -                                  |

\*Exterior noise levels only

### 60, 65, and 70 dBA Noise Contours

Unadjusted 60, 65, and 70 dBA noise contours (without any mitigation) for the loudest traffic hour sound levels are overlaid upon the site diagram in Figure 4. The contours in the figure are based upon sound pressure levels calculated at an elevation of 5 feet, which is representative of noise impacts for receivers and building floors at the ground level. Based upon the results for individual receivers discussed above, the sound pressure levels of the contours can be assumed to increase approximately 1 dBA per building floor to represent the noise impacts at subsequent floor levels above the ground level floor.




Figure 4. Unadjusted 60, 65, and 70 dBA noise contours (5 ft elevation) overlaid upon the Project site diagram based upon Year 2022 traffic data.

## IMPACTS AND MITIGATION

The predicted sound pressure levels reported in Table 3 and the contours shown in Figure 4 are reported for the exterior sound exposure at the designated locations. The following sections discuss the noise impacts and mitigation for the outdoor activity areas and the residential dwellings.

### Outdoor Activity Areas

The City of Portsmouth Zoning Ordinance defines Outdoor Activity Areas as “residential yards, gardens, patios, pools, etc.; private and public play areas.” The 100 Durgin Lane development is planning to provide several common outdoor areas for the community as shown in Figure 1. The sound pressure level goal for these outdoor areas is 65 dBA.

The TNM predictions for individual receivers, as listed in Table 3, and the noise contours, shown in Figure 4, indicate that the central common outdoor areas will have sound levels that are less than 65 dBA at the edge closest to the highway and therefore do not require mitigation to meet the goal of 65 dBA for those areas.

The TNM prediction for an individual receiver at the edge of the Dog Run closest to the highway, listed in Table 3, indicates a sound level of 65 dBA while the noise contours in Figure 4 indicate a level that is



greater than 65 dBA but less than 70 dBA. The contours provided by the TNM software lack sufficient detail to accurately indicate sound pressure levels for the Dog Run which is in close proximity to the car ports and the 6-foot sound barrier included at the southwest end of the project. Therefore, we find that the 65 dBA sound pressure level predicted at the individual receiver more accurately represents the sound pressure level at that area per the requirements of the Highway Overlay District. As a result, we conclude that no additional mitigation is required to meet the goal of 65 dBA for that area.

## Residential Dwellings

The residential buildings of the 100 Durgin Lane development are predicted to have a range of sound level exposures from State Route 4. Most of the residential buildings (Locations 11 through 25) are predicted to have exterior sound level exposures of 64 dBA or less, whereas residences along the southwestern edge of the development are predicted to be exposed to a range of exterior sound levels from 60 to 72 dBA. As a reminder, the interior sound pressure level goal for residences is 45 dBA.

As discussed earlier in this report, residential buildings have historically been expected to provide 20 dBA of noise reduction, prior to modern building practices that focus on energy efficiency. This 20 dBA reduction is the value used by the various federal agencies, including FHWA and the FAA. This means that the predicted exterior sound levels of 65 dBA or less would result in interior sound levels that meet the 45 dBA interior sound level goal for the HNOD inside residential dwellings. Based on the sound level predictions, most of the residential buildings are exposed to sound levels that do not require any noise mitigation to meet the Highway Noise Overlay District interior sound level goal.

The anticipated exterior wall and window assemblies of the project and the higher range of sound exposures are discussed below.

### Project Exterior Wall Assembly

The project is expecting to use an exterior wall assembly that consists of the following components (from exterior to interior):

- Fiber cement board and batten siding
- Drainage mat (cedar breather or similar)
- 7/16-inch Zip sheathing
- 2x8 wood stud framing
- Fiberglass batt insulation (R-30) in stud cavity
- 5/8-inch gypsum wallboard

Based on these components, we estimate this assembly will provide approximately OITC 30, which would provide a sound level reduction of approximately 28 dBA.

### Project Window Assembly

The project is expecting that the exterior window assemblies will be a casement vent model Pella Impervia. Pella's product data indicates that this product has a range of OITC values from 24 to 32 depending on the glazing that is chosen.

### Project Composite Exterior Envelope Assembly

The sound reduction provided by the exterior envelope for the residential dwellings will be proportional to the areas and the performance of exterior wall and window systems. This combined performance is referred to as the "composite" sound insulation. For this calculation, we have estimated that the windows make up no more than about 20% of the exterior envelope area. Using window glazing with a rating of



OITC 24 and the OITC 28 wall assembly, we calculate the composite exterior envelope rating to be OITC 27, which equates to a sound level reduction of 27 dBA.

**Buildings with Predicted Sound Exposure above 65 dBA**

Based on the OITC 27 composite exterior envelope performance, sound level exposures of up to 72 dBA are estimated to achieve the interior goal of 45 dBA.

With these planned constructions for this project, we find that the modern building envelope that this project is planning suffices for the “superinsulated” construction that the HNOD document suggests is needed to achieve the interior sound level of 45 dBA. We find that no further mitigation is needed to meet the requirements of the Highway Noise Overlay District.

---

We trust this provides the information that you need at this time. Please feel free to contact us by email or phone (James.Phillips@intertek.com, 510-697-9437 or Jeffrey.Fullerton@intertek.com, 857-523-6576) should you have any questions or require further information.

Sincerely,

Architectural Testing, Inc., an Intertek company

  
Digitally signed by James E. Phillips  
DN: C=US,  
E=james.phillips@intertek.com,  
O=Intertek-ATI, CN=James E.  
Phillips  
Reason: I am the author of this  
document  
Date: 2024.10.23 10:21:22-0700

James Phillips, MS, FASA  
Senior Consultant  
Building Science Solutions

  
Digitally Signed for: Jeffrey Fullerton by Michelle Swanson

Jeffrey Fullerton, INCE Bd. Cert., LEED AP BD+C  
Department Manager, Acoustics  
Building Science Solutions

JP/JF/mds

October 23rd, 2024

Portsmouth Planning Board

100 Durgin Lane  
Portsmouth, NH

utile

## Green Building Statement

**Site / Landscape:** This project is a redevelopment of an existing large chain “big box” retail use and associated parking lot, in proximity to additional shops and services along Durgin Lane and Woodbury Ave. The site design features footpaths and bike connections to and through the project to facilitate alternative transportation and provides distributed surface vehicle parking and indoor bike parking that meets the Portsmouth zoning code requirements.

Currently the site is predominantly impervious surface parking and building footprint. The proposed site plan reduces the impervious surface by approximately 17,323 SF, and distributes the required parking into smaller parcels separated by vegetated buffers. Stormwater will be managed by localized rain gardens near each parking zone. The landscape plan will be supportive of the existing ecosystem, utilizing swaths of low/no irrigation grasses and regionally appropriate shade and shrub trees. Additionally the project provides two acres of publicly accessible community green space.

**Exterior Wall Systems:** Although the final specifications of the exterior wall systems are still being developed, it will meet or exceed the 2021 IECC standards for energy efficiency utilizing either a continuous applied weather barrier or integral system with taped seams to provide excellent air sealing capabilities. The exterior cladding will be a mix of cement board panel and board and batten siding with portions of clear finish wood siding installed over a drainage mat in a ventilated rain screen system.

**Window Systems:** All window systems in the project will meet or exceed 2021 IECC standards for u-value, shading coefficient and solar heat gain coefficient, carefully selected and sized to provide ample daylight to the residents.

**Roofing Systems:** The roofing will primarily be a light colored, low-slope TPO membrane roofing system over continuous exterior insulation that meets or exceeds the code requirements.

**General Systems:** The proposed project will be an entirely electric project with no fossil fuels on site. Infrastructure will be provided for future electric vehicle charging and the project team will continue studying if some of these elements can be delivered “Day 1.”

**HVAC Systems:** The dwelling units will be provided with individualized split electric heat pump systems for space heating and cooling which will be supplemented with individualized ERVs to provide filtered, pre-conditioned makeup air for improved indoor air quality.

October 23rd, 2024

Portsmouth Planning Board

100 Durgin Lane  
Portsmouth, NH

**utile**

**Plumbing Systems:** Domestic hot water heating will be provided by electric domestic water heaters. The project will utilize low-flow plumbing fixtures.

**Lighting Systems:** Interior lighting systems will use LED fixtures and Occupancy sensors where required. Exterior lighting will be selected and located to minimize light trespass onto adjacent properties and will be energy efficient LED fixtures.





**Appliances:** All appliances for the project will be EnergyStar rated whenever possible.


Sincerely,

Brett Benston, AIA  
Principal  
Utile, Inc.

# Site Signage Plan

100 Durgin Lane Project  
October, 2024

- A Project Monument Sign**  
Property Entrance
  - B Vehicular Wayfinding | Landmarks**  
Project Name  
Hampton Inn  
Gosling Road  
Arthur F. Brady Drive  
Woodbury Avenue
  - C Vehicular Wayfinding | Streets & Community Spaces**  
Project Streets A, B, C  
Central Green  
Leasing Office  
Mail/ Deliveries
  - D Building Markers**  
Project Structures  
Freestanding or Building Mounted
  - E Park Markers**  
Pedestrian Directional
  - F Interpretive Markers**  
Wetland Informational Plaques
  - G Hampton Inn Entrance**  
8 ft. height  
Illuminated
- Regulatory Signage**
-  Cross Walks
  -  Stop & All Way
  -  Keep Right
  -  Accessible Parking



Facade Height

Minimum street facing facade height = 18 ft

Building height 47'-6" (51'-6" w/ parapet)

Facade Glazing

Minimum street facing facade glazing = 30%

33.6% glazing provided

Roof Shapes and Rooflines

Flat Roofs: Buildings with flat roofs shall be capped by an articulated parapet wall design that acts as a structural expression of the building facade and its materials, visible from all sides of the building.

Parapet wall provided above low-slope roofing surface. See below.

Horizontal Articulation and Massing Elements


Building facades shall be horizontally articulated with a clearly defined base, middle, and top.

See below; base: water table, wood siding, tight-spaced batten fiber cement board, middle: medium-spaced batten fiber cement board, top: wide-spaced batten fiber cement board, parapet

Facade Orientation

The primary facade of a principal building must be parallel to front lot line or to the tangent of a curved front lot line

Parallel or tangent conditions were difficult to achieve given radius and offset of front lot line. Building stepped massing aims to address - to the extent possible - the curved front lot line, orienting the building towards the street and public realm.




EAST ELEVATION



SOUTH ELEVATION



DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.





Facade Glazing

Minimum street-facing ground floor facade glazing = 20%  
>20% glazing provided

Street Facing Entrance Required

Building entrance located on east elevation, facing front lot line.

Roof Shapes and Rooflines

Flat Roofs: Buildings with flat roofs shall be capped by an articulated parapet wall design that acts as a structural expression of the building facade and its materials, visible from all sides of the building.

Parapet wall provided above low-slope roofing surface.

See below.

Horizontal Articulation and Massing Elements


Building facades shall be horizontally articulated with a clearly defined base, middle, and top.

See below; fiber cement board and batten spacing modulated to establish base, middle, and top.


Facade Orientation

The primary facade of a principal building must be parallel to front lot line or to the tangent of a curved front lot line


Parallel or tangent conditions were difficult to achieve given radius and offset of front lot line. Building stepped massing aims to address - to the extent possible - the curved front lot line, orienting the building towards the street and public realm.



SIDE ELEVATION





FRONT ELEVATION



Top  
Middle  
Base

DISCLAIMER: These plans are conceptual only. They have not been subject to a comprehensive code and regulatory review, nor have they been tested against any as-built surveys. Discoveries in such an analysis may result in fundamental changes to the original concept.







Proposed Multi-Family Development  
 100 Durgin Lane  
 Portsmouth, NH

## Drainage Analysis

100 Durgin Lane Owner, LLC

September 18, 2024



**Tighe & Bond**

**Section 1 Project Description**

1.1 On-Site Soil Description .....1-1  
1.2 Pre- and Post-Development Comparison .....1-2  
1.3 Calculation Methods.....1-2

**Section 2 Pre-Development Conditions**

2.1 Pre-Development Watershed Plan .....2-2  
2.2 Pre-Development Calculations.....2-2

**Section 3 Post-Development Conditions**

3.1 Post-Development Watershed Plan .....3-3  
3.2 Post-Development Calculations .....3-3

**Section 4 Peak Rate Comparison**

**Section 5 Mitigation Description**

5.1 Pre-Treatment Methods for Protecting Water Quality .....5-2  
5.2 Treatment Methods for Protecting Water Quality. ....5-2

**Section 6 BMP Worksheets**

**Section 7 Groundwater Recharge Volume Calculations**

**Appendices**

A Web Soil Survey Report  
B Site Specific Soil Survey Report & Test Pits  
C Extreme Precipitation Tables  
D Coastal Precipitation Increase

# **Section 1**

## **Project Description**

The proposed project is located at 100 Durgin Lane and includes lots identified as Map 239 Lots 13-2, 16 & 18 on the City of Portsmouth Tax Maps. The site was previously home to Christmas Tree Shops and Bed, Bath and Beyond locations which are no longer in operation. The properties are a combined 26.1 acres of land and are bound to the west by Route 16, to the north by the Motel 6 property and Gosling Road, to the south by the Hampton Inn and Home Depot properties, and to the east by an Eversource easement, Pep Boys and Durgin Plaza.

The proposed project consists of the demolition of the existing Christmas Tree Shops and Bed, Bath and Beyond building and the construction of approximately 360 rental housing units in a mix of seventeen (17) 3-story and 4-story buildings. One of these buildings, centrally located, is proposed to contain first and second-floor amenities for the use of residents. Site improvements include parking, pedestrian access, community spaces, utilities, stormwater management, lighting, and landscaping. The proposed project also includes a reduction in overall impervious surface on the development lot.

### **1.1 On-Site Soil Description**

Based on the site-specific soil survey completed by Gove Environmental Services, Inc (attached as Appendix B), the site is largely composed of Udorthents and Canton soils with a Hydrologic Soil Group (HSG) rating of HSG B. Additionally, wetland areas are defined as Scitico soils with a HSG C rating (to remain untouched). The ground cover within the area of study consists mostly of paved surfaces, building, and landscaped islands. There are two (2) wetland systems that drain into two (2) separate unnamed brooks that eventually join together before flowing into the Piscataqua River. The site slopes generally from the center of the parcel to either the eastern or western wetlands.

Infiltration testing was completed where feasible, limited by accessibility of ideal testing locations that did not impact existing paved areas of the site. Soil infiltration testing (included under Appendix B) shows that soils may allow for some level of infiltration, however to remain conservative in the site design, infiltration was not claimed in the drainage model.

## 1.2 Pre- and Post-Development Comparison

The pre-development and post-development watershed areas have been analyzed at five (5) distinct points of analysis (PA-1 through PA-5). While the points of analysis have remained unchanged, the contributing sub-catchment areas varied between pre-development and post-development conditions. These adjustments were made to reflect the differences in drainage patterns between the existing and proposed conditions. The overall area analyzed as part of this drainage analysis was held constant.

**Point of Analysis 1 (PA-1)** is located to the northwest end of the site, and assesses flows discharging to an existing wetland adjacent to NH Route 16. **Point of Analysis 2 (PA-2)** is located to the northeast end of the site, and assesses flows to another delineated wetland on the other side of the access road connecting the subject property to its northwesterly neighboring abutter. **Point of Analysis 3 (PA-3)** is located along the eastern corner of the site, and assesses flows to an existing wetland located on the south side of Durgin Lane. **Point of Analysis 4 (PA-4)** is located at the southern corner of the site, and assesses flows that discharge down a slope to an abutting property. **Point of Analysis 5 (PA-5)** is located along the southeastern edge of the site, a smaller point of analysis to assess flows exiting the property down the access road connecting to the neighboring abutter.

The peak discharge rates at these points of analysis were determined by analyzing Type III, 24-hour storm events. The rainfall data for these storm events were obtained from the data published by the Northeast Regional Climate Center at Cornell University, which can be found in Appendix B.

Furthermore, the site is located within a Coastal and Great Bay Community, therefore an added factor of safety of 15% was included as required by Env-Wq 1503.08(I).

## 1.3 Calculation Methods

The design storms analyzed in this study are the 1-year, 2-year, 10-year, 25-year and 50-year 24-hour duration storm events. The stormwater modeling system, HydroCAD 10.0 was utilized to predict the peak runoff rates from these storm events. The peak discharge rates were determined by analyzing Type III 24-hour storm events. The rainfall data for these storm events were obtained from the data published by the Northeast Regional Climate Center at Cornell University, with an additional 15% added factor of safety as required by Env-Wq 1503.08(I).

The time of concentration was computed using the TR-55 Method, which provides a means of determining the time for an entire watershed to contribute runoff to a specific location via sheet flows, shallow concentrated flow, and channel flow. Runoff curve numbers were calculated by estimating the coverage areas and then summing the curve number for the coverage area as a percent of the entire watershed.

### References:

1. HydroCAD Stormwater Modeling System, by HydroCAD Software Solutions LLC, Chocorua, New Hampshire.

2. New Hampshire Stormwater Management Manual, Volume 2, Post-Construction Best Management Practices Selection and Design, December 2008.
3. "Extreme Precipitation in New York & New England." Extreme Precipitation in New York & New England by Northeast Regional Climate Center (NRCC), 26 June 2012.

---

## Section 2

# Pre-Development Conditions

To analyze the pre-development condition, the site has been modeled utilizing the five (5) distinct points of analysis described in Section 1. These points of analysis and watersheds are depicted on the plan entitled "Pre-Development Watershed Plan", Sheet C-801.

The point of analysis and its contributing watershed areas under the *pre-development conditions* are described below:

### Point of Analysis 1 (PA-1)

Point of Analysis One (PA-1) is comprised of a single subcatchment area (PRE-1.0) that consists of runoff from the existing retail building roof, as well as a combination of impervious loading areas behind the building and grassed and wooded areas to the north. Runoff generally discharges through an existing 24" drainage outlet to an unnamed wetland after flowing through a water quality unit ("Downstream Defender" hydrodynamic separator, capable of meeting contemporary pre-treatment standards only).

### Point of Analysis 2 (PA-2)

Point of Analysis Two (PA-2) is composed of two (2) subcatchment areas (PRE-2.0 and PRE-2.1). PRE-2.0 is comprised primarily of paved parking and access areas, in addition to some vegetated slopes and wooded areas within the limits of analysis. A portion of this subcatchment area directs primarily impervious runoff through underground closed drainage to a water quality unit ("Downstream Defender" hydrodynamic separator, capable of meeting contemporary pre-treatment standards only) prior to discharge to the adjacent wetland. Remaining portions of this subcatchment include the access road extension off of Durgin Lane, adjacent parking lot to the east, and the access road at the north end of the site that discharge directly to the wetlands without treatment.

PRE-2.1 is comprised exclusively of paved parking areas and small landscaped islands. Flows from this subcatchment travel via overland flow to a bioretention cell (RG-1) located along the eastern edge of the site. Curb returns and small rip-rap aprons inlet flows into the cell for a level of treatment prior to discharging to the adjacent wetland via a 24" reinforced concrete pipe outlet.

### Point of Analysis 3 (PA-3)

Point of Analysis Three (PA-3) is composed of three (3) subcatchment areas (PRE-3.0, PRE-3.1, and PRE-3.10).

PRE-3.0 is comprised primarily of paved parking and access areas, in addition to some vegetated slopes and wooded areas within the limits of analysis. A large portion of impervious runoff within this watershed are conveyed via closed drainage to a water quality unit ("Downstream Defender" hydrodynamic separator, capable of meeting contemporary pre-treatment standards only) prior to discharge to the adjacent wetland through a 36" reinforced concrete outlet pipe. The water quality unit is shared with and receives flows from an abutting property (Hampton Inn).

PRE-3.1 is comprised exclusively of parking areas and small landscaped islands. Flows from this subcatchment travel via overland flow to a bioretention cell (RG-2) tucked into the eastern corner of the primary parking lot. A curb return and small rip-rap apron inlets flows into the cell for a level of treatment prior to connecting to the same 36" outlet pipe described under PRE-3.0.

PRE-3.10 represents an off-site subcatchment area on an abutting property whose drainage connects upstream of the water quality unity described under PRE-3.0. This subcatchment area is comprised mostly of paved parking and building roof areas, with a small amount of pervious vegetated and wooded areas along the edges and corners of its respective lot.

#### **Point of Analysis 4 (PA-4)**

Point of Analysis Four (PA-4) is composed of a single subcatchment area (PRE-4.0), comprised of mostly paved parking surfaces. Flows from this watershed travel via overland flow off the edge of pavement and down the adjacent slopes to an abutting property without treatment.

#### **Point of Analysis 5 (PA-5)**

Point of Analysis Five (PA-5) is composed of a single subcatchment area (PRE-5.0), representative of impervious runoff from the southern access road that flows downhill to a couple of off-site catch basins, and ultimately to a separate closed off-site drainage system.

## **2.1 Pre-Development Watershed Plan**

## **2.2 Pre-Development Calculations**



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN  
LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE


| MARK | DATE      | DESCRIPTION    |
|------|-----------|----------------|
| D    | 9/18/2024 | TAC SUBMISSION |
| C    | 8/28/2024 | CC SUBMISSION  |
| B    | 6/17/2024 | TAC SUBMISSION |
| A    | 4/22/2024 | TAC SUBMISSION |

|                      |                     |
|----------------------|---------------------|
| PROJECT NO:          | E5071-001           |
| DATE:                | 4/22/2024           |
| FILE:                | E5071-001-HYDRO.dwg |
| DRAWN BY:            | BKC/NHW             |
| DESIGNED/CHECKED BY: | NAH                 |
| APPROVED BY:         | PMC                 |








**PRE-DEVELOPMENT  
WATERSHED PLAN**

SCALE: AS SHOWN

C-801



Last Saved: 9/13/2024  
 Plotted On: Sep 16, 2024 4:36pm By: NWilcox  
 Tighe & Bond C:\Users\NWilcox\Desktop\WORKING\100 Durgin Lane\1001-HYDRO.dwg



Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment PRE 1.0:** Runoff Area=207,577 sf 57.69% Impervious Runoff Depth>1.42"  
Flow Length=999' Tc=6.8 min CN=82 Runoff=7.56 cfs 24,508 cf

**Subcatchment PRE 2.0:** Runoff Area=143,416 sf 69.16% Impervious Runoff Depth>1.70"  
Flow Length=500' Tc=5.0 min CN=86 Runoff=6.59 cfs 20,368 cf

**Subcatchment PRE 2.1:** Runoff Area=58,945 sf 77.01% Impervious Runoff Depth>1.94"  
Flow Length=360' Slope=0.0150 '/' Tc=5.0 min CN=89 Runoff=3.07 cfs 9,548 cf

**Subcatchment PRE 3.0:** Runoff Area=267,552 sf 54.51% Impervious Runoff Depth>1.29"  
Flow Length=405' Tc=9.7 min CN=80 Runoff=7.95 cfs 28,654 cf

**Subcatchment PRE 3.1:** Runoff Area=16,036 sf 66.20% Impervious Runoff Depth>1.63"  
Flow Length=155' Slope=0.0150 '/' Tc=5.0 min CN=85 Runoff=0.70 cfs 2,177 cf

**Subcatchment PRE 3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>2.21"  
Tc=5.0 min CN=92 Runoff=4.66 cfs 14,627 cf

**Subcatchment PRE 4.0:** Runoff Area=16,868 sf 71.31% Impervious Runoff Depth>1.78"  
Flow Length=115' Tc=5.0 min CN=87 Runoff=0.81 cfs 2,504 cf

**Subcatchment PRE 5.0:** Runoff Area=8,392 sf 100.00% Impervious Runoff Depth>2.82"  
Flow Length=355' Slope=0.0170 '/' Tc=5.0 min CN=98 Runoff=0.57 cfs 1,970 cf

**Pond RG-1:** Peak Elev=60.03' Storage=1,883 cf Inflow=3.07 cfs 9,548 cf  
Outflow=1.38 cfs 9,450 cf

**Pond RG-2:** Peak Elev=62.15' Storage=347 cf Inflow=0.70 cfs 2,177 cf  
Outflow=0.47 cfs 2,140 cf

**Link PA-1:** Inflow=7.56 cfs 24,508 cf  
Primary=7.56 cfs 24,508 cf

**Link PA-2:** Inflow=7.74 cfs 29,818 cf  
Primary=7.74 cfs 29,818 cf

**Link PA-3:** Inflow=12.32 cfs 45,421 cf  
Primary=12.32 cfs 45,421 cf

**Link PA-4:** Inflow=0.81 cfs 2,504 cf  
Primary=0.81 cfs 2,504 cf

**Link PA-5:** Inflow=0.57 cfs 1,970 cf  
Primary=0.57 cfs 1,970 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 104,356 cf Average Runoff Depth = 1.57"**  
**36.33% Pervious = 289,995 sf 63.67% Impervious = 508,318 sf**

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment PRE 1.0:** Runoff Area=207,577 sf 57.69% Impervious Runoff Depth>1.93"  
Flow Length=999' Tc=6.8 min CN=82 Runoff=10.36 cfs 33,388 cf

**Subcatchment PRE 2.0:** Runoff Area=143,416 sf 69.16% Impervious Runoff Depth>2.26"  
Flow Length=500' Tc=5.0 min CN=86 Runoff=8.69 cfs 26,973 cf

**Subcatchment PRE 2.1:** Runoff Area=58,945 sf 77.01% Impervious Runoff Depth>2.52"  
Flow Length=360' Slope=0.0150 '/' Tc=5.0 min CN=89 Runoff=3.98 cfs 12,391 cf

**Subcatchment PRE 3.0:** Runoff Area=267,552 sf 54.51% Impervious Runoff Depth>1.78"  
Flow Length=405' Tc=9.7 min CN=80 Runoff=11.11 cfs 39,624 cf

**Subcatchment PRE 3.1:** Runoff Area=16,036 sf 66.20% Impervious Runoff Depth>2.17"  
Flow Length=155' Slope=0.0150 '/' Tc=5.0 min CN=85 Runoff=0.94 cfs 2,903 cf

**Subcatchment PRE 3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>2.81"  
Tc=5.0 min CN=92 Runoff=5.86 cfs 18,608 cf

**Subcatchment PRE 4.0:** Runoff Area=16,868 sf 71.31% Impervious Runoff Depth>2.34"  
Flow Length=115' Tc=5.0 min CN=87 Runoff=1.06 cfs 3,294 cf

**Subcatchment PRE 5.0:** Runoff Area=8,392 sf 100.00% Impervious Runoff Depth>3.44"  
Flow Length=355' Slope=0.0170 '/' Tc=5.0 min CN=98 Runoff=0.69 cfs 2,409 cf

**Pond RG-1:** Peak Elev=60.33' Storage=2,678 cf Inflow=3.98 cfs 12,391 cf  
Outflow=1.47 cfs 12,282 cf

**Pond RG-2:** Peak Elev=62.29' Storage=449 cf Inflow=0.94 cfs 2,903 cf  
Outflow=0.59 cfs 2,862 cf

**Link PA-1:** Inflow=10.36 cfs 33,388 cf  
Primary=10.36 cfs 33,388 cf

**Link PA-2:** Inflow=10.04 cfs 39,255 cf  
Primary=10.04 cfs 39,255 cf

**Link PA-3:** Inflow=16.62 cfs 61,093 cf  
Primary=16.62 cfs 61,093 cf

**Link PA-4:** Inflow=1.06 cfs 3,294 cf  
Primary=1.06 cfs 3,294 cf

**Link PA-5:** Inflow=0.69 cfs 2,409 cf  
Primary=0.69 cfs 2,409 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 139,589 cf Average Runoff Depth = 2.10"**  
**36.33% Pervious = 289,995 sf 63.67% Impervious = 508,318 sf**

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment PRE 1.0:** Runoff Area=207,577 sf 57.69% Impervious Runoff Depth>3.60"  
Flow Length=999' Tc=6.8 min CN=82 Runoff=19.19 cfs 62,259 cf

**Subcatchment PRE 2.0:** Runoff Area=143,416 sf 69.16% Impervious Runoff Depth>4.01"  
Flow Length=500' Tc=5.0 min CN=86 Runoff=15.27 cfs 47,915 cf

**Subcatchment PRE 2.1:** Runoff Area=58,945 sf 77.01% Impervious Runoff Depth>4.33"  
Flow Length=360' Slope=0.0150 '/' Tc=5.0 min CN=89 Runoff=6.66 cfs 21,255 cf

**Subcatchment PRE 3.0:** Runoff Area=267,552 sf 54.51% Impervious Runoff Depth>3.40"  
Flow Length=405' Tc=9.7 min CN=80 Runoff=21.28 cfs 75,789 cf

**Subcatchment PRE 3.1:** Runoff Area=16,036 sf 66.20% Impervious Runoff Depth>3.91"  
Flow Length=155' Slope=0.0150 '/' Tc=5.0 min CN=85 Runoff=1.67 cfs 5,219 cf

**Subcatchment PRE 3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>4.65"  
Tc=5.0 min CN=92 Runoff=9.45 cfs 30,847 cf

**Subcatchment PRE 4.0:** Runoff Area=16,868 sf 71.31% Impervious Runoff Depth>4.11"  
Flow Length=115' Tc=5.0 min CN=87 Runoff=1.83 cfs 5,783 cf

**Subcatchment PRE 5.0:** Runoff Area=8,392 sf 100.00% Impervious Runoff Depth>5.34"  
Flow Length=355' Slope=0.0170 '/' Tc=5.0 min CN=98 Runoff=1.06 cfs 3,734 cf

**Pond RG-1:** Peak Elev=61.22' Storage=5,022 cf Inflow=6.66 cfs 21,255 cf  
Outflow=4.01 cfs 21,117 cf

**Pond RG-2:** Peak Elev=62.92' Storage=815 cf Inflow=1.67 cfs 5,219 cf  
Outflow=0.96 cfs 5,166 cf

**Link PA-1:** Inflow=19.19 cfs 62,259 cf  
Primary=19.19 cfs 62,259 cf

**Link PA-2:** Inflow=16.81 cfs 69,032 cf  
Primary=16.81 cfs 69,032 cf

**Link PA-3:** Inflow=30.22 cfs 111,802 cf  
Primary=30.22 cfs 111,802 cf

**Link PA-4:** Inflow=1.83 cfs 5,783 cf  
Primary=1.83 cfs 5,783 cf

**Link PA-5:** Inflow=1.06 cfs 3,734 cf  
Primary=1.06 cfs 3,734 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 252,801 cf Average Runoff Depth = 3.80"**  
**36.33% Pervious = 289,995 sf 63.67% Impervious = 508,318 sf**

**Summary for Subcatchment PRE 1.0:**

[47] Hint: Peak is 703% of capacity of segment #3

Runoff = 19.19 cfs @ 12.10 hrs, Volume= 62,259 cf, Depth> 3.60"  
 Routed to Link PA-1 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 59,833    | 61 | >75% Grass cover, Good, HSG B |
| 40,628    | 98 | Paved parking, HSG B          |
| 27,983    | 55 | Woods, Good, HSG B            |
| 79,133    | 98 | Unconnected roofs, HSG B      |
| 0         | 74 | >75% Grass cover, Good, HSG C |
| 0         | 98 | Paved parking, HSG C          |
| *         | 98 | Roofs, HGC C                  |
| 0         | 70 | Woods, Good, HSG C            |
| 0         | 80 | >75% Grass cover, Good, HSG D |
| 0         | 98 | Paved parking, HSG D          |
| 0         | 77 | Woods, Good, HSG D            |
| 207,577   | 82 | Weighted Average              |
| 87,816    |    | 42.31% Pervious Area          |
| 119,761   |    | 57.69% Impervious Area        |
| 79,133    |    | 66.08% Unconnected            |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description  |
|----------|---------------|---------------|-------------------|----------------|--|
| 2.0      | 100           | 0.0050        | 0.85              |                | <b>Sheet Flow,</b><br>Smooth surfaces n= 0.011 P2= 3.68"   |
| 1.5      | 220           | 0.0150        | 2.49              |                | <b>Shallow Concentrated Flow,</b><br>Paved Kv= 20.3 fps  |
| 3.3      | 679           | 0.0050        | 3.47              | 2.73           | <b>Pipe Channel,</b><br>12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'<br>n= 0.012 Corrugated PP, smooth interior |
| 6.8      | 999           | Total         |                   |                |  |

**Summary for Subcatchment PRE 2.0:**

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 606% of capacity of segment #3

Runoff = 15.27 cfs @ 12.07 hrs, Volume= 47,915 cf, Depth> 4.01"  
 Routed to Link PA-2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Yr Rainfall=5.58"

**E-5071-001\_PRE**

Type III 24-hr 10-Yr Rainfall=5.58"

Prepared by Tighe &amp; Bond

Printed 8/27/2024

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Page 8

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 36,387    | 61 | >75% Grass cover, Good, HSG B |
| 99,191    | 98 | Paved parking, HSG B          |
| 7,775     | 55 | Woods, Good, HSG B            |
| 63        | 74 | >75% Grass cover, Good, HSG C |
| 143,416   | 86 | Weighted Average              |
| 44,225    |    | 30.84% Pervious Area          |
| 99,191    |    | 69.16% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft)                            | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|--|-------------------|----------------|---|
| 1.1      | 100           | 0.0200                                   | 1.48              |                | <b>Sheet Flow,</b><br>Smooth surfaces n= 0.011 P2= 3.68"                          |
| 1.2      | 200           | 0.0200                                   | 2.87              |                | <b>Shallow Concentrated Flow,</b><br>Paved Kv= 20.3 fps                           |
| 1.0      | 200           | 0.0050                                   | 3.21              | 2.52           | <b>Pipe Channel,</b><br>12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'<br>n= 0.013 |
| 3.3      | 500           | Total, Increased to minimum Tc = 5.0 min |                   |                |   |

**Summary for Subcatchment PRE 2.1:**

[49] Hint: Tc&lt;2dt may require smaller dt

Runoff = 6.66 cfs @ 12.07 hrs, Volume= 21,255 cf, Depth> 4.33"  
 Routed to Pond RG-1 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 13,550    | 61 | >75% Grass cover, Good, HSG B |
| 45,395    | 98 | Paved parking, HSG B          |
| 0         | 55 | Woods, Good, HSG B            |
| 58,945    | 89 | Weighted Average              |
| 13,550    |    | 22.99% Pervious Area          |
| 45,395    |    | 77.01% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft)                            | Velocity (ft/sec) | Capacity (cfs) | Description  |
|----------|---------------|--|-------------------|----------------|--|
| 1.3      | 100           | 0.0150                                   | 1.31              |                | <b>Sheet Flow,</b><br>Smooth surfaces n= 0.011 P2= 3.68" |
| 1.7      | 260           | 0.0150                                   | 2.49              |                | <b>Shallow Concentrated Flow,</b><br>Paved Kv= 20.3 fps  |
| 3.0      | 360           | Total, Increased to minimum Tc = 5.0 min |                   |                |  |

**Summary for Subcatchment PRE 3.0:**

[47] Hint: Peak is 845% of capacity of segment #3

Runoff = 21.28 cfs @ 12.14 hrs, Volume= 75,789 cf, Depth> 3.40"  
 Routed to Link PA-3 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 49,876    | 61 | >75% Grass cover, Good, HSG B |
| 145,833   | 98 | Paved parking, HSG B          |
| 66,755    | 55 | Woods, Good, HSG B            |
| 5,088     | 70 | Woods, Good, HSG C            |
| 267,552   | 80 | Weighted Average              |
| 121,719   |    | 45.49% Pervious Area          |
| 145,833   |    | 54.51% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---|
| 3.5      | 25            | 0.1000        | 0.12              |                | <b>Sheet Flow,</b><br>Woods: Light underbrush n= 0.400 P2= 3.68"                  |
| 4.7      | 300           | 0.0450        | 1.06              |                | <b>Shallow Concentrated Flow,</b><br>Woodland Kv= 5.0 fps                         |
| 0.3      | 55            | 0.0050        | 3.21              | 2.52           | <b>Pipe Channel,</b><br>12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'<br>n= 0.013 |
| 1.2      | 25            | 0.0050        | 0.35              |                | <b>Shallow Concentrated Flow,</b><br>Woodland Kv= 5.0 fps                         |
| 9.7      | 405           | Total         |                   |                |   |

**Summary for Subcatchment PRE 3.1:**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 1.67 cfs @ 12.07 hrs, Volume= 5,219 cf, Depth> 3.91"  
 Routed to Pond RG-2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 5,420     | 61 | >75% Grass cover, Good, HSG B |
| 10,616    | 98 | Paved parking, HSG B          |
| 16,036    | 85 | Weighted Average              |
| 5,420     |    | 33.80% Pervious Area          |
| 10,616    |    | 66.20% Impervious Area        |



**E-5071-001\_PRE**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 8/27/2024

Page 10

| Tc<br>(min) | Length<br>(feet) | Slope<br>(ft/ft)                         | Velocity<br>(ft/sec) | Capacity<br>(cfs) | Description  |
|-------------|------------------|--|----------------------|-------------------|--|
| 1.3         | 100              | 0.0150                                   | 1.31                 |                   | <b>Sheet Flow,</b><br>Smooth surfaces n= 0.011 P2= 3.68" |
| 0.4         | 55               | 0.0150                                   | 2.49                 |                   | <b>Shallow Concentrated Flow,</b><br>Paved Kv= 20.3 fps  |
| 1.7         | 155              | Total, Increased to minimum Tc = 5.0 min |                      |                   |  |

**Summary for Subcatchment PRE 3.10:**

\*Web Soil Survey data used for off-site analysis.

[49] Hint: Tc&lt;2dt may require smaller dt

Runoff = 9.45 cfs @ 12.07 hrs, Volume= 30,847 cf, Depth> 4.65"  
Routed to Link PA-3 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 12,426    | 61 | >75% Grass cover, Good, HSG B |
| 52,558    | 98 | Paved parking, HSG B          |
| 14,543    | 98 | Unconnected roofs, HSG B      |
| 79,527    | 92 | Weighted Average              |
| 12,426    |    | 15.62% Pervious Area          |
| 67,101    |    | 84.38% Impervious Area        |
| 14,543    |    | 21.67% Unconnected            |

| Tc<br>(min) | Length<br>(feet) | Slope<br>(ft/ft) | Velocity<br>(ft/sec) | Capacity<br>(cfs) | Description          |
|-------------|------------------|------------------|----------------------|-------------------|----------------------|
| 5.0         |                  |                  |                      |                   | <b>Direct Entry,</b> |

**Summary for Subcatchment PRE 4.0:**

[49] Hint: Tc&lt;2dt may require smaller dt

Runoff = 1.83 cfs @ 12.07 hrs, Volume= 5,783 cf, Depth> 4.11"  
Routed to Link PA-4 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,839     | 61 | >75% Grass cover, Good, HSG B |
| 12,029    | 98 | Paved parking, HSG B          |
| 16,868    | 87 | Weighted Average              |
| 4,839     |    | 28.69% Pervious Area          |
| 12,029    |    | 71.31% Impervious Area        |

**E-5071-001\_PRE**

Type III 24-hr 10-Yr Rainfall=5.58"

Prepared by Tighe &amp; Bond

Printed 8/27/2024

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Page 11

| Tc (min) | Length (feet) | Slope (ft/ft)                            | Velocity (ft/sec) | Capacity (cfs) | Description  |
|----------|---------------|--|-------------------|----------------|--|
| 1.0      | 100           | 0.0270                                   | 1.66              |                | <b>Sheet Flow,</b><br>Smooth surfaces n= 0.011 P2= 3.68"             |
| 0.1      | 15            | 0.3300                                   | 4.02              |                | <b>Shallow Concentrated Flow,</b><br>Short Grass Pasture Kv= 7.0 fps |
| 1.1      | 115           | Total, Increased to minimum Tc = 5.0 min |                   |                |  |

**Summary for Subcatchment PRE 5.0:**

[49] Hint: Tc&lt;2dt may require smaller dt

Runoff = 1.06 cfs @ 12.07 hrs, Volume= 3,734 cf, Depth> 5.34"  
Routed to Link PA-5 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 0         | 61 | >75% Grass cover, Good, HSG B |
| 8,392     | 98 | Paved parking, HSG B          |
| 0         | 55 | Woods, Good, HSG B            |
| 8,392     | 98 | Weighted Average              |
| 8,392     |    | 100.00% Impervious Area       |

| Tc (min) | Length (feet) | Slope (ft/ft)                            | Velocity (ft/sec) | Capacity (cfs) | Description  |
|----------|---------------|--|-------------------|----------------|--|
| 1.2      | 100           | 0.0170                                   | 1.38              |                | <b>Sheet Flow, SHEET</b><br>Smooth surfaces n= 0.011 P2= 3.68" |
| 1.6      | 255           | 0.0170                                   | 2.65              |                | <b>Shallow Concentrated Flow,</b><br>Paved Kv= 20.3 fps        |
| 2.8      | 355           | Total, Increased to minimum Tc = 5.0 min |                   |                |  |

**Summary for Pond RG-1:**

[92] Warning: Device #3 is above defined storage

[93] Warning: Storage range exceeded by 0.22'

[58] Hint: Peaked 0.79' above defined flood level

Inflow Area = 58,945 sf, 77.01% Impervious, Inflow Depth > 4.33" for 10-Yr event  
Inflow = 6.66 cfs @ 12.07 hrs, Volume= 21,255 cf  
Outflow = 4.01 cfs @ 12.25 hrs, Volume= 21,117 cf, Atten= 40%, Lag= 10.7 min  
Primary = 4.01 cfs @ 12.25 hrs, Volume= 21,117 cf  
Routed to Link PA-2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Peak Elev= 61.22' @ 12.25 hrs Surf.Area= 4,110 sf Storage= 5,022 cf  
Flood Elev= 60.43' Surf.Area= 3,078 sf Storage= 2,973 cf

Plug-Flow detention time= 28.5 min calculated for 21,073 cf (99% of inflow)

Center-of-Mass det. time= 24.5 min ( 813.8 - 789.3 )

| Volume           | Invert            | Avail.Storage | Storage Description  |                        |
|------------------|-------------------|---------------|--|------------------------|
| #1               | 57.65'            | 5,022 cf      | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |                        |
| Elevation (feet) | Surf.Area (sq-ft) | Voids (%)     | Inc.Store (cubic-feet)                                     | Cum.Store (cubic-feet) |
| 57.65            | 2,300             | 0.0           | 0  | 0                      |
| 58.50            | 2,300             | 40.0          | 782  | 782                    |
| 60.00            | 2,300             | 30.0          | 1,035  | 1,817                  |
| 61.00            | 4,110             | 100.0         | 3,205  | 5,022                  |

| Device | Routing  | Invert | Outlet Devices  |
|--------|----------|--------|---|
| #1     | Primary  | 54.00' | <b>24.0" Round Culvert</b> L= 19.0' Ke= 0.500<br>Inlet / Outlet Invert= 54.00' / 52.19' S= 0.0953 ' / Cc= 0.900<br>n= 0.012, Flow Area= 3.14 sf |
| #2     | Device 1 | 57.65' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads  |
| #3     | Device 1 | 61.15' | <b>4.5" x 2.5" Horiz. Orifice/Grate X 4.00 columns</b> X 8 rows C= 0.600<br>Limited to weir flow at low heads                                   |

**Primary OutFlow** Max=4.00 cfs @ 12.25 hrs HW=61.22' TW=0.00' (Dynamic Tailwater)

- 1=Culvert (Passes 4.00 cfs of 37.73 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 1.72 cfs @ 8.77 fps)
- 3=Orifice/Grate (Weir Controls 2.28 cfs @ 0.87 fps)

**Summary for Pond RG-2:**

Inflow Area = 16,036 sf, 66.20% Impervious, Inflow Depth > 3.91" for 10-Yr event  
 Inflow = 1.67 cfs @ 12.07 hrs, Volume= 5,219 cf  
 Outflow = 0.96 cfs @ 12.19 hrs, Volume= 5,166 cf, Atten= 43%, Lag= 7.2 min  
 Primary = 0.96 cfs @ 12.19 hrs, Volume= 5,166 cf  
 Routed to Link PA-3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
 Peak Elev= 62.92' @ 12.19 hrs Surf.Area= 1,745 sf Storage= 815 cf  
 Flood Elev= 64.25' Surf.Area= 2,000 sf Storage= 1,847 cf

Plug-Flow detention time= 21.2 min calculated for 5,155 cf (99% of inflow)  
 Center-of-Mass det. time= 15.0 min ( 817.1 - 802.0 )

| Volume           | Invert            | Avail.Storage | Storage Description  |                        |
|------------------|-------------------|---------------|--|------------------------|
| #1               | 61.65'            | 1,847 cf      | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |                        |
| Elevation (feet) | Surf.Area (sq-ft) | Voids (%)     | Inc.Store (cubic-feet)                                     | Cum.Store (cubic-feet) |
| 61.65            | 1,745             | 0.0           | 0  | 0                      |
| 62.50            | 1,745             | 40.0          | 593  | 593                    |
| 64.00            | 1,745             | 30.0          | 785  | 1,379                  |
| 64.25            | 2,000             | 100.0         | 468  | 1,847                  |

| Device | Routing  | Invert | Outlet Devices   |
|--------|----------|--------|--|
| #1     | Primary  | 61.60' | <b>12.0" Round Culvert</b> L= 130.0' Ke= 0.500<br>Inlet / Outlet Invert= 61.60' / 61.00' S= 0.0046 '/' Cc= 0.900<br>n= 0.012, Flow Area= 0.79 sf |
| #2     | Device 1 | 61.65' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads   |
| #3     | Primary  | 63.95' | <b>4.5" x 2.5" Horiz. Orifice/Grate X 4.00 columns</b> X 8 rows C= 0.600<br>Limited to weir flow at low heads                                    |

**Primary OutFlow** Max=0.96 cfs @ 12.19 hrs HW=62.92' TW=0.00' (Dynamic Tailwater)

- 1=Culvert (Passes 0.96 cfs of 2.80 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.96 cfs @ 4.86 fps)
- 3=Orifice/Grate ( Controls 0.00 cfs)

**Summary for Link PA-1:**

Inflow Area = 207,577 sf, 57.69% Impervious, Inflow Depth > 3.60" for 10-Yr event  
 Inflow = 19.19 cfs @ 12.10 hrs, Volume= 62,259 cf  
 Primary = 19.19 cfs @ 12.10 hrs, Volume= 62,259 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

**Summary for Link PA-2:**

Inflow Area = 202,361 sf, 71.45% Impervious, Inflow Depth > 4.09" for 10-Yr event  
 Inflow = 16.81 cfs @ 12.07 hrs, Volume= 69,032 cf  
 Primary = 16.81 cfs @ 12.07 hrs, Volume= 69,032 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

**Summary for Link PA-3:**

Inflow Area = 363,115 sf, 61.56% Impervious, Inflow Depth > 3.69" for 10-Yr event  
 Inflow = 30.22 cfs @ 12.11 hrs, Volume= 111,802 cf  
 Primary = 30.22 cfs @ 12.11 hrs, Volume= 111,802 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

**Summary for Link PA-4:**

Inflow Area = 16,868 sf, 71.31% Impervious, Inflow Depth > 4.11" for 10-Yr event  
 Inflow = 1.83 cfs @ 12.07 hrs, Volume= 5,783 cf  
 Primary = 1.83 cfs @ 12.07 hrs, Volume= 5,783 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

**Summary for Link PA-5:**

Inflow Area = 8,392 sf, 100.00% Impervious, Inflow Depth > 5.34" for 10-Yr event  
Inflow = 1.06 cfs @ 12.07 hrs, Volume= 3,734 cf  
Primary = 1.06 cfs @ 12.07 hrs, Volume= 3,734 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment PRE 1.0:** Runoff Area=207,577 sf 57.69% Impervious Runoff Depth>4.98"  
Flow Length=999' Tc=6.8 min CN=82 Runoff=26.26 cfs 86,097 cf

**Subcatchment PRE 2.0:** Runoff Area=143,416 sf 69.16% Impervious Runoff Depth>5.43"  
Flow Length=500' Tc=5.0 min CN=86 Runoff=20.40 cfs 64,896 cf

**Subcatchment PRE 2.1:** Runoff Area=58,945 sf 77.01% Impervious Runoff Depth>5.77"  
Flow Length=360' Slope=0.0150 '/' Tc=5.0 min CN=89 Runoff=8.75 cfs 28,359 cf

**Subcatchment PRE 3.0:** Runoff Area=267,552 sf 54.51% Impervious Runoff Depth>4.75"  
Flow Length=405' Tc=9.7 min CN=80 Runoff=29.52 cfs 105,952 cf

**Subcatchment PRE 3.1:** Runoff Area=16,036 sf 66.20% Impervious Runoff Depth>5.32"  
Flow Length=155' Slope=0.0150 '/' Tc=5.0 min CN=85 Runoff=2.24 cfs 7,105 cf

**Subcatchment PRE 3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>6.12"  
Tc=5.0 min CN=92 Runoff=12.23 cfs 40,564 cf

**Subcatchment PRE 4.0:** Runoff Area=16,868 sf 71.31% Impervious Runoff Depth>5.54"  
Flow Length=115' Tc=5.0 min CN=87 Runoff=2.44 cfs 7,793 cf

**Subcatchment PRE 5.0:** Runoff Area=8,392 sf 100.00% Impervious Runoff Depth>6.83"  
Flow Length=355' Slope=0.0170 '/' Tc=5.0 min CN=98 Runoff=1.35 cfs 4,775 cf

**Pond RG-1:** Peak Elev=61.45' Storage=5,022 cf Inflow=8.75 cfs 28,359 cf  
Outflow=8.56 cfs 28,202 cf

**Pond RG-2:** Peak Elev=63.54' Storage=1,140 cf Inflow=2.24 cfs 7,105 cf  
Outflow=1.21 cfs 7,044 cf

**Link PA-1:** Inflow=26.26 cfs 86,097 cf  
Primary=26.26 cfs 86,097 cf

**Link PA-2:** Inflow=25.58 cfs 93,097 cf  
Primary=25.58 cfs 93,097 cf

**Link PA-3:** Inflow=41.10 cfs 153,561 cf  
Primary=41.10 cfs 153,561 cf

**Link PA-4:** Inflow=2.44 cfs 7,793 cf  
Primary=2.44 cfs 7,793 cf

**Link PA-5:** Inflow=1.35 cfs 4,775 cf  
Primary=1.35 cfs 4,775 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 345,540 cf Average Runoff Depth = 5.19"**  
**36.33% Pervious = 289,995 sf 63.67% Impervious = 508,318 sf**

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment PRE 1.0:** Runoff Area=207,577 sf 57.69% Impervious Runoff Depth>6.29"  
Flow Length=999' Tc=6.8 min CN=82 Runoff=32.86 cfs 108,839 cf

**Subcatchment PRE 2.0:** Runoff Area=143,416 sf 69.16% Impervious Runoff Depth>6.77"  
Flow Length=500' Tc=5.0 min CN=86 Runoff=25.15 cfs 80,962 cf

**Subcatchment PRE 2.1:** Runoff Area=58,945 sf 77.01% Impervious Runoff Depth>7.13"  
Flow Length=360' Slope=0.0150 '/' Tc=5.0 min CN=89 Runoff=10.69 cfs 35,047 cf

**Subcatchment PRE 3.0:** Runoff Area=267,552 sf 54.51% Impervious Runoff Depth>6.05"  
Flow Length=405' Tc=9.7 min CN=80 Runoff=37.26 cfs 134,867 cf

**Subcatchment PRE 3.1:** Runoff Area=16,036 sf 66.20% Impervious Runoff Depth>6.65"  
Flow Length=155' Slope=0.0150 '/' Tc=5.0 min CN=85 Runoff=2.78 cfs 8,892 cf

**Subcatchment PRE 3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>7.50"  
Tc=5.0 min CN=92 Runoff=14.81 cfs 49,674 cf

**Subcatchment PRE 4.0:** Runoff Area=16,868 sf 71.31% Impervious Runoff Depth>6.89"  
Flow Length=115' Tc=5.0 min CN=87 Runoff=2.99 cfs 9,691 cf

**Subcatchment PRE 5.0:** Runoff Area=8,392 sf 100.00% Impervious Runoff Depth>8.22"  
Flow Length=355' Slope=0.0170 '/' Tc=5.0 min CN=98 Runoff=1.61 cfs 5,746 cf

**Pond RG-1:** Peak Elev=62.14' Storage=5,022 cf Inflow=10.69 cfs 35,047 cf  
Outflow=14.00 cfs 34,873 cf

**Pond RG-2:** Peak Elev=64.00' Storage=1,382 cf Inflow=2.78 cfs 8,892 cf  
Outflow=1.95 cfs 8,826 cf

**Link PA-1:** Inflow=32.86 cfs 108,839 cf  
Primary=32.86 cfs 108,839 cf

**Link PA-2:** Inflow=38.42 cfs 115,835 cf  
Primary=38.42 cfs 115,835 cf

**Link PA-3:** Inflow=51.37 cfs 193,367 cf  
Primary=51.37 cfs 193,367 cf

**Link PA-4:** Inflow=2.99 cfs 9,691 cf  
Primary=2.99 cfs 9,691 cf

**Link PA-5:** Inflow=1.61 cfs 5,746 cf  
Primary=1.61 cfs 5,746 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 433,718 cf Average Runoff Depth = 6.52"**  
**36.33% Pervious = 289,995 sf 63.67% Impervious = 508,318 sf**

**Area Listing (all nodes)**

| Area<br>(sq-ft) | CN        | Description<br>(subcatchment-numbers)  |
|-----------------|-----------|--|
| 182,331         | 61        | >75% Grass cover, Good, HSG B (PRE 1.0, PRE 2.0, PRE 2.1, PRE 3.0, PRE 3.1, PRE 3.10, PRE 4.0) |
| 63              | 74        | >75% Grass cover, Good, HSG C (PRE 2.0)  |
| 414,642         | 98        | Paved parking, HSG B (PRE 1.0, PRE 2.0, PRE 2.1, PRE 3.0, PRE 3.1, PRE 3.10, PRE 4.0, PRE 5.0) |
| 93,676          | 98        | Unconnected roofs, HSG B (PRE 1.0, PRE 3.10)   |
| 102,513         | 55        | Woods, Good, HSG B (PRE 1.0, PRE 2.0, PRE 3.0)   |
| 5,088           | 70        | Woods, Good, HSG C (PRE 3.0)   |
| <b>798,313</b>  | <b>84</b> | <b>TOTAL AREA</b>  |



**Soil Listing (all nodes)**

| Area<br>(sq-ft) | Soil<br>Group | Subcatchment<br>Numbers   |
|-----------------|---------------|---|
| 0               | HSG A         |   |
| 793,162         | HSG B         | PRE 1.0, PRE 2.0, PRE 2.1, PRE 3.0, PRE 3.1, PRE 3.10, PRE 4.0, PRE 5.0 |
| 5,151           | HSG C         | PRE 2.0, PRE 3.0  |
| 0               | HSG D         |   |
| 0               | Other         |   |
| <b>798,313</b>  |               | <b>TOTAL AREA</b>   |

## **Section 3**

# **Post-Development Conditions**

To analyze the post-development condition, the site has been modeled utilizing the same five (5) distinct points of analysis as the Pre-Development condition with revised watershed areas to reflect the post-construction conditions.

The points of analysis and their sub-catchment areas are depicted on the plan entitled "Post-Development Watershed Plan," Sheet C-802.

### **Point of Analysis 1 (PA-1)**

Point of Analysis One (PA-1) is comprised of two (2) subcatchment areas (POST-1.0 and POST-1.1).

POST-1.0 is composed of paved parking areas, sidewalks, roof, and landscaped area runoff that is collected via a proposed closed drainage system and conveyed to a treatment train (Contech CDS unit for pre-treatment, Contech Jellyfish Filter unit for treatment) prior to connecting to the existing 24" RCP outlet. Additional previously untreated area from the pre-development condition of PA-4 is conveyed through this watershed for treatment.

POST-1.1 is composed of pervious grassed and wooded areas outside of the impervious site improvements along the northwestern edge of the site. Runoff from these areas travels via overland flow to the adjacent wetland.

### **Point of Analysis 2 (PA-2)**

Point of Analysis Two (PA-2) is comprised of three (3) subcatchment areas (POST-2.1, POST-2.2, & POST-2.3).

POST-2.1 is a large watershed composed of paved parking areas, sidewalks, roof, and landscaped area runoff within the redevelopment area that is collected via a proposed closed drainage system and conveyed to a large rain garden (RG-1) at the north end of the site. Flows are pre-treated by a Contech CDS unit. Effluent from this rain garden is metered by an outlet control structure and discharged via a proposed 24" outlet to the adjacent wetland. A plunge pool is proposed to mitigate erosion from flows under larger storm events.

POST-2.2 is composed of paved parking areas, sidewalks, roof, landscaped area runoff within the redevelopment area that is conveyed via overland flow to a series of Rain Guardian Turrets (for pre-treatment) built into the curblin along the edge of a proposed rain garden (RG-2). This rain garden effectively aims to reconstruct the existing rain garden in this location to the extent practical, taking advantage of the same 24" existing outlet pipe but with a revised outlet control structure to ensure sufficient treatment and storage in accordance with contemporary standards for the revised post-development subcatchment area.

POST-2.3 is composed of planted, grassed, buffer areas and a small amount of impervious surfaces generally located outside the limits of the proposed site improvements. Additionally, a small amount of existing off-site untreated runoff from Durgin Lane is

proposed to be rerouted to a proposed headwall outlet along the northeastern edge of the site. Runoff from these areas travels via overland flow or closed drainage (for existing impervious areas to remain) to the adjacent wetland.

**Point of Analysis 3 (PA-3)**

Point of Analysis Three (PA-3) is comprised of three (3) subcatchment areas (POST-3.0, POST-3.1, and POST-3.10).

POST-3.0 is composed of paved parking areas, sidewalks, roofs, and landscaped area runoff that is collected via a proposed closed drainage system and conveyed to a treatment train (Contech CDS unit for pre-treatment, Contech Jellyfish Filter unit for treatment) prior to connecting to the existing 36" RCP outlet.

POST-3.1 is composed of pervious grassed and wooded areas outside of the impervious site improvements along the southern edge of the site. Runoff from these areas travels via overland flow to the adjacent wetland.

POST-3.2 is a small subcatchment area composed of pervious grassed areas below the retaining wall proposed along the southeastern edge of the site. Runoff from this subcatchment is conveyed through an existing 12" culvert under the adjacent access road to the wetland (PA-3).

POST-3.10 represents the same off-site subcatchment area on the abutting Hampton Inn property as described under the pre-development condition of PRE-3.10. Drainage from this lot is proposed to be reconnected to the revised closed drainage system on the subject property, for conveyance to the same treatment train (Contech CDS unit for pre-treatment, Contech Jellyfish Filter unit for treatment) described under POST-3.0.

**Point of Analysis 4 (PA-4)**

The watershed area in the post-development condition (POST-4.0) to Point of Analysis 4 (PA-4) is proposed to be reduced, as to ultimately reduce off-site flows to the abutter to the extent practical. There are no impervious areas proposed within this watershed in the post-development condition, and all revised impervious areas in this general vicinity are proposed to be directed to the subject property's closed drainage system for proper treatment.


**Point of Analysis 5 (PA-5)**

The watershed area in the post-development condition (POST-5.0) to Point of Analysis 5 (PA-5) is proposed to be reduced, as to ensure that the revised access road alignment and grading does not increase off-site flows down the road in comparison to the pre-development condition.

### **3.1 Post-Development Watershed Plan**

### **3.2 Post-Development Calculations**

Last Saved: 9/13/2024  
 Plotted On: Sep 17, 2024 - 7:02pm By: Scurdo  
 Tighe & Bond \Vigoreland.com\Data\Projects\E\ES071 - Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane Drawings\AutoCAD\Sheet\ES071-001-HYDRO.dwg










**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE

**LEGEND**

-  POST-DEVELOPMENT WATERSHED BOUNDARY
-  SITE-SPECIFIC SOIL SURVEY BOUNDARIES
-  LONGEST FLOW PATH
-  POST 1.0  
POST-DEVELOPMENT WATERSHED AREA DESIGNATION
-  POST POND 1  
POST-DEVELOPMENT POND DESIGNATION
-  PA-1  
POINT OF ANALYSIS



| MARK | DATE      | DESCRIPTION    |
|------|-----------|----------------|
| D    | 9/18/2024 | TAC SUBMISSION |
| C    | 8/28/2024 | CC SUBMISSION  |
| B    | 6/17/2024 | TAC SUBMISSION |
| A    | 4/22/2024 | TAC SUBMISSION |




|                      |                     |
|----------------------|---------------------|
| PROJECT NO:          | E5071-001           |
| DATE:                | 4/22/2024           |
| FILE:                | E5071-001-HYDRO.dwg |
| DRAWN BY:            | BKC/NHW             |
| DESIGNED/CHECKED BY: | NAH                 |
| APPROVED BY:         | PMC                 |

**POST-DEVELOPMENT  
WATERSHED PLAN**

SCALE: AS SHOWN

**C-802**



**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 1-Yr Rainfall=3.05"

Printed 9/17/2024

Page 4

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment POST 1.0:** Runoff Area=138,301 sf 75.24% Impervious Runoff Depth>1.94"  
 Flow Length=1,005' Tc=8.4 min CN=89 Runoff=6.55 cfs 22,389 cf

**Subcatchment POST 1.1:** Runoff Area=53,855 sf 0.99% Impervious Runoff Depth>0.35"  
 Flow Length=75' Slope=0.0350 '/' Tc=5.0 min CN=60 Runoff=0.26 cfs 1,575 cf

**Subcatchment POST 2.1:** Runoff Area=211,170 sf 68.33% Impervious Runoff Depth>1.70"  
 Flow Length=745' Tc=9.2 min CN=86 Runoff=8.53 cfs 29,964 cf

**Subcatchment POST 2.2:** Runoff Area=42,134 sf 69.19% Impervious Runoff Depth>1.78"  
 Flow Length=215' Tc=6.2 min CN=87 Runoff=1.97 cfs 6,254 cf

**Subcatchment POST 2.3:** Runoff Area=58,185 sf 9.83% Impervious Runoff Depth>0.49"  
 Flow Length=115' Slope=0.0200 '/' Tc=6.3 min CN=64 Runoff=0.53 cfs 2,376 cf

**Subcatchment POST 3.0:** Runoff Area=158,759 sf 73.04% Impervious Runoff Depth>1.86"  
 Flow Length=635' Slope=0.0150 '/' Tc=7.2 min CN=88 Runoff=7.52 cfs 24,617 cf

**Subcatchment POST 3.1:** Runoff Area=39,638 sf 0.00% Impervious Runoff Depth>0.38"  
 Flow Length=150' Tc=5.7 min CN=61 Runoff=0.23 cfs 1,267 cf

**Subcatchment POST 3.2:** Runoff Area=3,338 sf 0.00% Impervious Runoff Depth>0.38"  
 Flow Length=115' Tc=5.0 min CN=61 Runoff=0.02 cfs 107 cf

**Subcatchment POST 4.0:** Runoff Area=4,581 sf 0.00% Impervious Runoff Depth>0.38"  
 Tc=5.0 min CN=61 Runoff=0.03 cfs 146 cf

**Subcatchment POST 5.0:** Runoff Area=8,825 sf 89.09% Impervious Runoff Depth>2.40"  
 Flow Length=230' Slope=0.0200 '/' Tc=6.2 min CN=94 Runoff=0.53 cfs 1,763 cf

**Subcatchment POST-3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>2.21"  
 Tc=5.0 min CN=92 Runoff=4.66 cfs 14,627 cf

**Pond PDMH11: PDMH11** Peak Elev=60.40' Inflow=6.55 cfs 22,389 cf  
 Primary=5.60 cfs 22,008 cf Secondary=0.95 cfs 381 cf Outflow=6.55 cfs 22,389 cf

**Pond PDMH20: PDMH20** Peak Elev=56.81' Inflow=8.53 cfs 29,964 cf  
 Primary=4.87 cfs 27,387 cf Secondary=3.66 cfs 2,578 cf Outflow=8.53 cfs 29,964 cf

**Pond PDMH3: PDMH3** Peak Elev=61.41' Inflow=11.99 cfs 39,244 cf  
 Primary=7.00 cfs 35,492 cf Secondary=4.99 cfs 3,751 cf Outflow=11.99 cfs 39,244 cf

**Pond RG-1:** Peak Elev=50.99' Storage=7,309 cf Inflow=8.53 cfs 29,964 cf  
 Outflow=2.75 cfs 29,742 cf

**Pond RG-2:** Peak Elev=58.32' Storage=535 cf Inflow=1.97 cfs 6,254 cf  
 Outflow=1.40 cfs 6,254 cf

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 1-Yr Rainfall=3.05"

Printed 9/17/2024

Page 5

**Link PA-1:**

Inflow=6.82 cfs 23,964 cf  
Primary=6.82 cfs 23,964 cf

**Link PA-2:**

Inflow=4.37 cfs 38,372 cf  
Primary=4.37 cfs 38,372 cf

**Link PA-3:**

Inflow=12.23 cfs 40,618 cf  
Primary=12.23 cfs 40,618 cf

**Link PA-4:**

Inflow=0.03 cfs 146 cf  
Primary=0.03 cfs 146 cf

**Link PA-5:**

Inflow=0.53 cfs 1,763 cf  
Primary=0.53 cfs 1,763 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 105,085 cf Average Runoff Depth = 1.58"  
40.54% Pervious = 323,634 sf 59.46% Impervious = 474,679 sf**



**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Yr Rainfall=3.68"

Printed 9/17/2024

Page 6

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment POST 1.0:** Runoff Area=138,301 sf 75.24% Impervious Runoff Depth>2.52"  
 Flow Length=1,005' Tc=8.4 min CN=89 Runoff=8.44 cfs 29,054 cf

**Subcatchment POST 1.1:** Runoff Area=53,855 sf 0.99% Impervious Runoff Depth>0.61"  
 Flow Length=75' Slope=0.0350 '/' Tc=5.0 min CN=60 Runoff=0.66 cfs 2,739 cf

**Subcatchment POST 2.1:** Runoff Area=211,170 sf 68.33% Impervious Runoff Depth>2.26"  
 Flow Length=745' Tc=9.2 min CN=86 Runoff=11.27 cfs 39,684 cf

**Subcatchment POST 2.2:** Runoff Area=42,134 sf 69.19% Impervious Runoff Depth>2.34"  
 Flow Length=215' Tc=6.2 min CN=87 Runoff=2.58 cfs 8,226 cf

**Subcatchment POST 2.3:** Runoff Area=58,185 sf 9.83% Impervious Runoff Depth>0.80"  
 Flow Length=115' Slope=0.0200 '/' Tc=6.3 min CN=64 Runoff=1.02 cfs 3,864 cf

**Subcatchment POST 3.0:** Runoff Area=158,759 sf 73.04% Impervious Runoff Depth>2.43"  
 Flow Length=635' Slope=0.0150 '/' Tc=7.2 min CN=88 Runoff=9.77 cfs 32,161 cf

**Subcatchment POST 3.1:** Runoff Area=39,638 sf 0.00% Impervious Runoff Depth>0.65"  
 Flow Length=150' Tc=5.7 min CN=61 Runoff=0.53 cfs 2,163 cf

**Subcatchment POST 3.2:** Runoff Area=3,338 sf 0.00% Impervious Runoff Depth>0.65"  
 Flow Length=115' Tc=5.0 min CN=61 Runoff=0.05 cfs 182 cf

**Subcatchment POST 4.0:** Runoff Area=4,581 sf 0.00% Impervious Runoff Depth>0.65"  
 Tc=5.0 min CN=61 Runoff=0.06 cfs 250 cf

**Subcatchment POST 5.0:** Runoff Area=8,825 sf 89.09% Impervious Runoff Depth>3.01"  
 Flow Length=230' Slope=0.0200 '/' Tc=6.2 min CN=94 Runoff=0.66 cfs 2,213 cf

**Subcatchment POST-3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>2.81"  
 Tc=5.0 min CN=92 Runoff=5.86 cfs 18,608 cf

**Pond PDMH11: PDMH11** Peak Elev=60.58' Inflow=8.44 cfs 29,054 cf  
 Primary=6.50 cfs 28,011 cf Secondary=1.94 cfs 1,043 cf Outflow=8.44 cfs 29,054 cf

**Pond PDMH20: PDMH20** Peak Elev=57.07' Inflow=11.27 cfs 39,684 cf  
 Primary=5.24 cfs 34,511 cf Secondary=6.03 cfs 5,174 cf Outflow=11.27 cfs 39,684 cf

**Pond PDMH3: PDMH3** Peak Elev=61.67' Inflow=15.39 cfs 50,768 cf  
 Primary=7.70 cfs 44,233 cf Secondary=7.69 cfs 6,536 cf Outflow=15.39 cfs 50,768 cf

**Pond RG-1:** Peak Elev=51.74' Storage=10,881 cf Inflow=11.27 cfs 39,684 cf  
 Outflow=3.07 cfs 39,437 cf

**Pond RG-2:** Peak Elev=59.12' Storage=792 cf Inflow=2.58 cfs 8,226 cf  
 Outflow=1.69 cfs 8,225 cf

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Yr Rainfall=3.68"

Printed 9/17/2024

Page 7

**Link PA-1:** Inflow=9.09 cfs 31,793 cf  
Primary=9.09 cfs 31,793 cf

**Link PA-2:** Inflow=5.28 cfs 51,526 cf  
Primary=5.28 cfs 51,526 cf

**Link PA-3:** Inflow=15.96 cfs 53,113 cf  
Primary=15.96 cfs 53,113 cf

**Link PA-4:** Inflow=0.06 cfs 250 cf  
Primary=0.06 cfs 250 cf

**Link PA-5:** Inflow=0.66 cfs 2,213 cf  
Primary=0.66 cfs 2,213 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 139,143 cf Average Runoff Depth = 2.09"**  
**40.54% Pervious = 323,634 sf 59.46% Impervious = 474,679 sf**

**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 8

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment POST 1.0:** Runoff Area=138,301 sf 75.24% Impervious Runoff Depth>4.32"  
 Flow Length=1,005' Tc=8.4 min CN=89 Runoff=14.15 cfs 49,841 cf

**Subcatchment POST 1.1:** Runoff Area=53,855 sf 0.99% Impervious Runoff Depth>1.65"  
 Flow Length=75' Slope=0.0350 '/' Tc=5.0 min CN=60 Runoff=2.24 cfs 7,409 cf

**Subcatchment POST 2.1:** Runoff Area=211,170 sf 68.33% Impervious Runoff Depth>4.01"  
 Flow Length=745' Tc=9.2 min CN=86 Runoff=19.69 cfs 70,500 cf

**Subcatchment POST 2.2:** Runoff Area=42,134 sf 69.19% Impervious Runoff Depth>4.11"  
 Flow Length=215' Tc=6.2 min CN=87 Runoff=4.43 cfs 14,442 cf

**Subcatchment POST 2.3:** Runoff Area=58,185 sf 9.83% Impervious Runoff Depth>1.97"  
 Flow Length=115' Slope=0.0200 '/' Tc=6.3 min CN=64 Runoff=2.89 cfs 9,535 cf

**Subcatchment POST 3.0:** Runoff Area=158,759 sf 73.04% Impervious Runoff Depth>4.22"  
 Flow Length=635' Slope=0.0150 '/' Tc=7.2 min CN=88 Runoff=16.59 cfs 55,809 cf

**Subcatchment POST 3.1:** Runoff Area=39,638 sf 0.00% Impervious Runoff Depth>1.73"  
 Flow Length=150' Tc=5.7 min CN=61 Runoff=1.72 cfs 5,708 cf

**Subcatchment POST 3.2:** Runoff Area=3,338 sf 0.00% Impervious Runoff Depth>1.73"  
 Flow Length=115' Tc=5.0 min CN=61 Runoff=0.15 cfs 481 cf

**Subcatchment POST 4.0:** Runoff Area=4,581 sf 0.00% Impervious Runoff Depth>1.73"  
 Tc=5.0 min CN=61 Runoff=0.20 cfs 660 cf

**Subcatchment POST 5.0:** Runoff Area=8,825 sf 89.09% Impervious Runoff Depth>4.88"  
 Flow Length=230' Slope=0.0200 '/' Tc=6.2 min CN=94 Runoff=1.04 cfs 3,587 cf

**Subcatchment POST-3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>4.65"  
 Tc=5.0 min CN=92 Runoff=9.45 cfs 30,847 cf

**Pond PDMH11: PDMH11** Peak Elev=61.16' Inflow=14.15 cfs 49,841 cf  
 Primary=8.11 cfs 45,205 cf Secondary=6.04 cfs 4,636 cf Outflow=14.15 cfs 49,841 cf

**Pond PDMH20: PDMH20** Peak Elev=57.79' Inflow=19.69 cfs 70,500 cf  
 Primary=6.15 cfs 54,903 cf Secondary=13.55 cfs 15,598 cf Outflow=19.69 cfs 70,500 cf

**Pond PDMH3: PDMH3** Peak Elev=62.34' Inflow=25.65 cfs 86,656 cf  
 Primary=9.09 cfs 69,426 cf Secondary=16.56 cfs 17,230 cf Outflow=25.65 cfs 86,656 cf

**Pond RG-1:** Peak Elev=53.43' Storage=20,520 cf Inflow=19.69 cfs 70,500 cf  
 Outflow=7.39 cfs 70,190 cf

**Pond RG-2:** Peak Elev=59.98' Storage=1,977 cf Inflow=4.43 cfs 14,442 cf  
 Outflow=2.15 cfs 14,442 cf

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 9

**Link PA-1:** Inflow=16.31 cfs 57,250 cf  
Primary=16.31 cfs 57,250 cf

**Link PA-2:** Inflow=10.55 cfs 94,167 cf  
Primary=10.55 cfs 94,167 cf

**Link PA-3:** Inflow=27.51 cfs 92,845 cf  
Primary=27.51 cfs 92,845 cf

**Link PA-4:** Inflow=0.20 cfs 660 cf  
Primary=0.20 cfs 660 cf

**Link PA-5:** Inflow=1.04 cfs 3,587 cf  
Primary=1.04 cfs 3,587 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 248,820 cf Average Runoff Depth = 3.74"**  
**40.54% Pervious = 323,634 sf 59.46% Impervious = 474,679 sf**

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 10

**Summary for Subcatchment POST 1.0:**

[47] Hint: Peak is 562% of capacity of segment #2

Runoff = 14.15 cfs @ 12.12 hrs, Volume= 49,841 cf, Depth> 4.32"  
Routed to Pond PDMH11 : PDMH11

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 34,247    | 61 | >75% Grass cover, Good, HSG B |
| 75,627    | 98 | Paved parking, HSG B          |
| 0         | 55 | Woods, Good, HSG B            |
| 28,427    | 98 | Roofs, HSG B                  |
| 138,301   | 89 | Weighted Average              |
| 34,247    |    | 24.76% Pervious Area          |
| 104,054   |    | 75.24% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---|
| 3.4      | 35            | 0.0300        | 0.17              |                | <b>Sheet Flow,</b><br>Grass: Short n= 0.150 P2= 3.68"                             |
| 5.0      | 970           | 0.0050        | 3.21              | 2.52           | <b>Pipe Channel,</b><br>12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'<br>n= 0.013 |
| 8.4      | 1,005         | Total         |                   |                |   |

**Summary for Subcatchment POST 1.1:**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 2.24 cfs @ 12.09 hrs, Volume= 7,409 cf, Depth> 1.65"  
Routed to Link PA-1 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 11

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 36,910    | 61 | >75% Grass cover, Good, HSG B |
| 535       | 98 | Paved parking, HSG B          |
| 16,410    | 55 | Woods, Good, HSG B            |
| 0         | 98 | Unconnected roofs, HSG B      |
| 0         | 74 | >75% Grass cover, Good, HSG C |
| 0         | 98 | Paved parking, HSG C          |
| *         | 98 | Roofs, HSG C                  |
| 0         | 70 | Woods, Good, HSG C            |
| 0         | 80 | >75% Grass cover, Good, HSG D |
| 0         | 98 | Paved parking, HSG D          |
| 0         | 77 | Woods, Good, HSG D            |
| 53,855    | 60 | Weighted Average              |
| 53,320    |    | 99.01% Pervious Area          |
| 535       |    | 0.99% Impervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft)                            | Velocity (ft/sec) | Capacity (cfs) | Description  |
|----------|---------------|--|-------------------|----------------|--|
| 4.2      | 50            | 0.0350                                   | 0.20              |                | <b>Sheet Flow,</b><br>Grass: Short n= 0.150 P2= 3.68"                |
| 0.3      | 25            | 0.0350                                   | 1.31              |                | <b>Shallow Concentrated Flow,</b><br>Short Grass Pasture Kv= 7.0 fps |
| 4.5      | 75            | Total, Increased to minimum Tc = 5.0 min |                   |                |  |

**Summary for Subcatchment POST 2.1:**

[47] Hint: Peak is 782% of capacity of segment #3

Runoff = 19.69 cfs @ 12.13 hrs, Volume= 70,500 cf, Depth> 4.01"  
Routed to Pond PDMH20 : PDMH20

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 66,876    | 61 | >75% Grass cover, Good, HSG B |
| 101,862   | 98 | Paved parking, HSG B          |
| 0         | 55 | Woods, Good, HSG B            |
| 42,432    | 98 | Roofs, HSG B                  |
| 211,170   | 86 | Weighted Average              |
| 66,876    |    | 31.67% Pervious Area          |
| 144,294   |    | 68.33% Impervious Area        |

**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 12

| Tc<br>(min) | Length<br>(feet) | Slope<br>(ft/ft) | Velocity<br>(ft/sec) | Capacity<br>(cfs) | Description   |
|-------------|------------------|------------------|----------------------|-------------------|---|
| 5.2         | 50               | 0.0200           | 0.16                 |                   | <b>Sheet Flow,</b><br>Grass: Short n= 0.150 P2= 3.68"                             |
| 0.6         | 35               | 0.0200           | 0.99                 |                   | <b>Shallow Concentrated Flow,</b><br>Short Grass Pasture Kv= 7.0 fps              |
| 3.4         | 660              | 0.0050           | 3.21                 | 2.52              | <b>Pipe Channel,</b><br>12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'<br>n= 0.013 |
| 9.2         | 745              | Total            |                      |                   |   |

**Summary for Subcatchment POST 2.2:**

Runoff = 4.43 cfs @ 12.09 hrs, Volume= 14,442 cf, Depth> 4.11"  
Routed to Pond RG-2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 12,981    | 61 | >75% Grass cover, Good, HSG B |
| 21,766    | 98 | Paved parking, HSG B          |
| 0         | 55 | Woods, Good, HSG B            |
| 7,387     | 98 | Roofs, HSG B                  |
| 42,134    | 87 | Weighted Average              |
| 12,981    |    | 30.81% Pervious Area          |
| 29,153    |    | 69.19% Impervious Area        |

| Tc<br>(min) | Length<br>(feet) | Slope<br>(ft/ft) | Velocity<br>(ft/sec) | Capacity<br>(cfs) | Description  |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 4.0         | 50               | 0.0400           | 0.21                 |                   | <b>Sheet Flow,</b><br>Grass: Short n= 0.150 P2= 3.68"                |
| 1.7         | 85               | 0.0150           | 0.86                 |                   | <b>Shallow Concentrated Flow,</b><br>Short Grass Pasture Kv= 7.0 fps |
| 0.5         | 80               | 0.0200           | 2.87                 |                   | <b>Shallow Concentrated Flow,</b><br>Paved Kv= 20.3 fps              |
| 6.2         | 215              | Total            |                      |                   |  |

**Summary for Subcatchment POST 2.3:**

Runoff = 2.89 cfs @ 12.10 hrs, Volume= 9,535 cf, Depth> 1.97"  
Routed to Link PA-2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 13

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 44,627    | 61 | >75% Grass cover, Good, HSG B |
| 5,720     | 98 | Paved parking, HSG B          |
| 7,775     | 55 | Woods, Good, HSG B            |
| 0         | 98 | Unconnected roofs, HSG B      |
| 63        | 74 | >75% Grass cover, Good, HSG C |
| 58,185    | 64 | Weighted Average              |
| 52,465    |    | 90.17% Pervious Area          |
| 5,720     |    | 9.83% Impervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description  |
|----------|---------------|---------------|-------------------|----------------|--|
| 5.2      | 50            | 0.0200        | 0.16              |                | <b>Sheet Flow,</b><br>Grass: Short n= 0.150 P2= 3.68"                |
| 1.1      | 65            | 0.0200        | 0.99              |                | <b>Shallow Concentrated Flow,</b><br>Short Grass Pasture Kv= 7.0 fps |
| 6.3      | 115           | Total         |                   |                |  |

**Summary for Subcatchment POST 3.0:**

[47] Hint: Peak is 380% of capacity of segment #2

Runoff = 16.59 cfs @ 12.10 hrs, Volume= 55,809 cf, Depth> 4.22"  
Routed to Pond PDMH3 : PDMH3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 42,799    | 61 | >75% Grass cover, Good, HSG B |
| 94,275    | 98 | Paved parking, HSG B          |
| 0         | 55 | Woods, Good, HSG B            |
| 21,685    | 98 | Roofs, HSG B                  |
| 158,759   | 88 | Weighted Average              |
| 42,799    |    | 26.96% Pervious Area          |
| 115,960   |    | 73.04% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---|
| 5.4      | 45            | 0.0150        | 0.14              |                | <b>Sheet Flow,</b><br>Grass: Short n= 0.150 P2= 3.68"                             |
| 1.8      | 590           | 0.0150        | 5.56              | 4.36           | <b>Pipe Channel,</b><br>12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'<br>n= 0.013 |
| 7.2      | 635           | Total         |                   |                |   |



**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 14

**Summary for Subcatchment POST 3.1:**

[49] Hint: Tc&lt;2dt may require smaller dt

Runoff = 1.72 cfs @ 12.10 hrs, Volume= 5,708 cf, Depth> 1.73"  
 Routed to Link PA-3 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 24,506    | 61 | >75% Grass cover, Good, HSG B |
| 0         | 98 | Paved parking, HSG B          |
| 10,044    | 55 | Woods, Good, HSG B            |
| 0         | 98 | Roofs, HSG B                  |
| 5,088     | 70 | Woods, Good, HSG C            |
| 39,638    | 61 | Weighted Average              |
| 39,638    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description  |
|----------|---------------|---------------|-------------------|----------------|--|
| 4.2      | 50            | 0.0350        | 0.20              |                | <b>Sheet Flow,</b><br>Grass: Short n= 0.150 P2= 3.68"                |
| 1.5      | 100           | 0.0250        | 1.11              |                | <b>Shallow Concentrated Flow,</b><br>Short Grass Pasture Kv= 7.0 fps |
| 5.7      | 150           | Total         |                   |                |  |

**Summary for Subcatchment POST 3.2:**

[49] Hint: Tc&lt;2dt may require smaller dt

Runoff = 0.15 cfs @ 12.09 hrs, Volume= 481 cf, Depth> 1.73"  
 Routed to Link PA-3 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
 Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 3,338     | 61 | >75% Grass cover, Good, HSG B |
| 0         | 98 | Paved parking, HSG B          |
| 0         | 55 | Woods, Good, HSG B            |
| 0         | 98 | Roofs, HSG B                  |
| 3,338     | 61 | Weighted Average              |
| 3,338     |    | 100.00% Pervious Area         |

**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 15

| Tc (min) | Length (feet) | Slope (ft/ft)                            | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|--|-------------------|----------------|---|
| 0.1      | 20            | 0.3000                                   | 3.83              |                | <b>Shallow Concentrated Flow,</b><br>Short Grass Pasture Kv= 7.0 fps              |
| 0.3      | 55            | 0.0050                                   | 3.21              | 2.52           | <b>Pipe Channel,</b><br>12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25'<br>n= 0.013 |
| 1.9      | 40            | 0.0050                                   | 0.35              |                | <b>Shallow Concentrated Flow,</b><br>Woodland Kv= 5.0 fps                         |
| 2.3      | 115           | Total, Increased to minimum Tc = 5.0 min |                   |                |   |

**Summary for Subcatchment POST 4.0:**

[49] Hint: Tc&lt;2dt may require smaller dt

Runoff = 0.20 cfs @ 12.09 hrs, Volume= 660 cf, Depth> 1.73"  
Routed to Link PA-4 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,581     | 61 | >75% Grass cover, Good, HSG B |
| 0         | 98 | Paved parking, HSG B          |
| 0         | 55 | Woods, Good, HSG B            |
| 0         | 98 | Unconnected roofs, HSG B      |
| 4,581     | 61 | Weighted Average              |
| 4,581     |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft)                            | Velocity (ft/sec) | Capacity (cfs) | Description          |
|----------|---------------|--|-------------------|----------------|----------------------|
| 1.0      |               |  |                   |                | <b>Direct Entry,</b> |
| 1.0      | 0             | Total, Increased to minimum Tc = 5.0 min |                   |                |                      |

**Summary for Subcatchment POST 5.0:**

Runoff = 1.04 cfs @ 12.09 hrs, Volume= 3,587 cf, Depth> 4.88"  
Routed to Link PA-5 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 963       | 61 | >75% Grass cover, Good, HSG B |
| 7,862     | 98 | Paved parking, HSG B          |
| 0         | 55 | Woods, Good, HSG B            |
| 0         | 98 | Unconnected roofs, HSG B      |
| 8,825     | 94 | Weighted Average              |
| 963       |    | 10.91% Pervious Area          |
| 7,862     |    | 89.09% Impervious Area        |

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 16

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---|
| 5.2      | 50            | 0.0200        | 0.16              |                | <b>Sheet Flow,</b><br>Grass: Short n= 0.150 P2= 3.68"   |
| 1.0      | 180           | 0.0200        | 2.87              |                | <b>Shallow Concentrated Flow,</b><br>Paved Kv= 20.3 fps |
| 6.2      | 230           | Total         |                   |                |   |

**Summary for Subcatchment POST-3.10:**

\*Web Soil Survey data used for off-site analysis.

[49] Hint: Tc<2dt may require smaller dt

Runoff = 9.45 cfs @ 12.07 hrs, Volume= 30,847 cf, Depth> 4.65"  
Routed to Pond PDMH3 : PDMH3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-Yr Rainfall=5.58"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 12,426    | 61 | >75% Grass cover, Good, HSG B |
| 52,558    | 98 | Paved parking, HSG B          |
| 14,543    | 98 | Unconnected roofs, HSG B      |
| 79,527    | 92 | Weighted Average              |
| 12,426    |    | 15.62% Pervious Area          |
| 67,101    |    | 84.38% Impervious Area        |
| 14,543    |    | 21.67% Unconnected            |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description          |
|----------|---------------|---------------|-------------------|----------------|----------------------|
| 5.0      |               |               |                   |                | <b>Direct Entry,</b> |

**Summary for Pond PDMH11: PDMH11**

Inflow Area = 138,301 sf, 75.24% Impervious, Inflow Depth > 4.32" for 10-Yr event  
Inflow = 14.15 cfs @ 12.12 hrs, Volume= 49,841 cf  
Outflow = 14.15 cfs @ 12.12 hrs, Volume= 49,841 cf, Atten= 0%, Lag= 0.0 min  
Primary = 8.11 cfs @ 12.12 hrs, Volume= 45,205 cf  
Routed to Link PA-1 :  
Secondary = 6.04 cfs @ 12.12 hrs, Volume= 4,636 cf  
Routed to Link PA-1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
Peak Elev= 61.16' @ 12.12 hrs  
Flood Elev= 65.55'

**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 17

| Device | Routing   | Invert | Outlet Devices  |
|--------|-----------|--------|---|
| #1     | Primary   | 58.65' | <b>15.0" Round Culvert</b> L= 8.0' Ke= 0.500<br>Inlet / Outlet Invert= 58.65' / 58.60' S= 0.0062 '/ Cc= 0.900<br>n= 0.013, Flow Area= 1.23 sf |
| #2     | Secondary | 60.00' | <b>24.0" Round Culvert</b> L= 8.0' Ke= 0.500<br>Inlet / Outlet Invert= 60.00' / 59.75' S= 0.0313 '/ Cc= 0.900<br>n= 0.013, Flow Area= 3.14 sf |

**Primary OutFlow** Max=8.02 cfs @ 12.12 hrs HW=61.12' TW=0.00' (Dynamic Tailwater)↑**1=Culvert** (Inlet Controls 8.02 cfs @ 6.54 fps)**Secondary OutFlow** Max=5.75 cfs @ 12.12 hrs HW=61.12' TW=0.00' (Dynamic Tailwater)↑**2=Culvert** (Barrel Controls 5.75 cfs @ 4.59 fps)**Summary for Pond PDMH20: PDMH20**

Inflow Area = 211,170 sf, 68.33% Impervious, Inflow Depth > 4.01" for 10-Yr event  
 Inflow = 19.69 cfs @ 12.13 hrs, Volume= 70,500 cf  
 Outflow = 19.69 cfs @ 12.13 hrs, Volume= 70,500 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 6.15 cfs @ 12.13 hrs, Volume= 54,903 cf  
   Routed to Pond RG-1 :  
 Secondary = 13.55 cfs @ 12.13 hrs, Volume= 15,598 cf  
   Routed to Pond RG-1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 57.79' @ 12.13 hrs

Flood Elev= 62.05'

| Device | Routing   | Invert | Outlet Devices  |
|--------|-----------|--------|---|
| #1     | Primary   | 54.65' | <b>12.0" Round Culvert</b> L= 6.0' Ke= 0.500<br>Inlet / Outlet Invert= 54.65' / 54.50' S= 0.0250 '/ Cc= 0.900<br>n= 0.013, Flow Area= 0.79 sf |
| #2     | Secondary | 56.00' | <b>24.0" Round Culvert</b> L= 8.0' Ke= 0.500<br>Inlet / Outlet Invert= 56.00' / 55.50' S= 0.0625 '/ Cc= 0.900<br>n= 0.013, Flow Area= 3.14 sf |

**Primary OutFlow** Max=6.10 cfs @ 12.13 hrs HW=57.75' TW=51.98' (Dynamic Tailwater)↑**1=Culvert** (Inlet Controls 6.10 cfs @ 7.77 fps)**Secondary OutFlow** Max=13.18 cfs @ 12.13 hrs HW=57.75' TW=51.98' (Dynamic Tailwater)↑**2=Culvert** (Inlet Controls 13.18 cfs @ 4.51 fps)**Summary for Pond PDMH3: PDMH3**

Inflow Area = 238,286 sf, 76.82% Impervious, Inflow Depth > 4.36" for 10-Yr event  
 Inflow = 25.65 cfs @ 12.09 hrs, Volume= 86,656 cf  
 Outflow = 25.65 cfs @ 12.09 hrs, Volume= 86,656 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 9.09 cfs @ 12.09 hrs, Volume= 69,426 cf  
   Routed to Link PA-3 :  
 Secondary = 16.56 cfs @ 12.09 hrs, Volume= 17,230 cf  
   Routed to Link PA-3 :

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 18

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 62.34' @ 12.09 hrs

Flood Elev= 65.50'

| Device | Routing   | Invert | Outlet Devices  |
|--------|-----------|--------|---|
| #1     | Primary   | 59.35' | <b>15.0" Round Culvert</b> L= 9.0' Ke= 0.500<br>Inlet / Outlet Invert= 59.35' / 59.30' S= 0.0056 '/ Cc= 0.900<br>n= 0.013, Flow Area= 1.23 sf |
| #2     | Secondary | 60.50' | <b>36.0" Round Culvert</b> L= 8.0' Ke= 0.500<br>Inlet / Outlet Invert= 60.50' / 60.30' S= 0.0250 '/ Cc= 0.900<br>n= 0.013, Flow Area= 7.07 sf |

**Primary OutFlow** Max=9.03 cfs @ 12.09 hrs HW=62.31' TW=0.00' (Dynamic Tailwater)

↳ **1=Culvert** (Inlet Controls 9.03 cfs @ 7.36 fps)

**Secondary OutFlow** Max=16.17 cfs @ 12.09 hrs HW=62.31' TW=0.00' (Dynamic Tailwater)

↳ **2=Culvert** (Barrel Controls 16.17 cfs @ 5.19 fps)

**Summary for Pond RG-1:**

Inflow Area = 211,170 sf, 68.33% Impervious, Inflow Depth > 4.01" for 10-Yr event  
 Inflow = 19.69 cfs @ 12.13 hrs, Volume= 70,500 cf  
 Outflow = 7.39 cfs @ 12.44 hrs, Volume= 70,190 cf, Atten= 62%, Lag= 18.8 min  
 Primary = 7.39 cfs @ 12.44 hrs, Volume= 70,190 cf  
 Routed to Link PA-2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 53.43' @ 12.44 hrs Surf.Area= 6,437 sf Storage= 20,520 cf

Flood Elev= 55.00' Surf.Area= 7,897 sf Storage= 31,749 cf

Plug-Flow detention time= 42.2 min calculated for 70,044 cf (99% of inflow)

Center-of-Mass det. time= 39.4 min ( 841.9 - 802.5 )

| Volume           | Invert            | Avail.Storage | Storage Description  |                        |
|------------------|-------------------|---------------|--|------------------------|
| #1               | 47.40'            | 31,749 cf     | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |                        |
| Elevation (feet) | Surf.Area (sq-ft) | Voids (%)     | Inc.Store (cubic-feet)                                     | Cum.Store (cubic-feet) |
| 47.40            | 3,709             | 0.0           | 0  | 0                      |
| 48.50            | 3,709             | 40.0          | 1,632  | 1,632                  |
| 50.00            | 3,709             | 30.0          | 1,669  | 3,301                  |
| 51.00            | 4,433             | 100.0         | 4,071  | 7,372                  |
| 52.00            | 5,214             | 100.0         | 4,824  | 12,196                 |
| 53.00            | 6,052             | 100.0         | 5,633  | 17,829                 |
| 54.00            | 6,946             | 100.0         | 6,499  | 24,328                 |
| 55.00            | 7,897             | 100.0         | 7,422  | 31,749                 |

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=5.58"

Printed 9/17/2024

Page 19

| Device | Routing  | Invert | Outlet Devices  |
|--------|----------|--------|---|
| #1     | Primary  | 47.40' | <b>24.0" Round Culvert</b> L= 65.0' Ke= 0.500<br>Inlet / Outlet Invert= 47.40' / 47.00' S= 0.0062 '/' Cc= 0.900<br>n= 0.012, Flow Area= 3.14 sf |
| #2     | Device 1 | 47.40' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads  |
| #3     | Device 1 | 47.40' | <b>10.000 in/hr Exfiltration over Surface area</b>  |
| #4     | Device 1 | 53.00' | <b>4.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)  |
| #5     | Device 1 | 54.00' | <b>1.0" x 1.0" Horiz. Orifice/Grate</b> X 114 rows C= 0.600<br>Limited to weir flow at low heads  |

**Primary OutFlow** Max=7.36 cfs @ 12.44 hrs HW=53.43' TW=0.00' (Dynamic Tailwater)

- 1=Culvert (Passes 7.36 cfs of 33.92 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 2.27 cfs @ 11.58 fps)
- 3=Exfiltration (Exfiltration Controls 1.49 cfs)
- 4=Sharp-Crested Rectangular Weir (Weir Controls 3.60 cfs @ 2.14 fps)
- 5=Orifice/Grate ( Controls 0.00 cfs)

**Summary for Pond RG-2:**

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=81)

Inflow Area = 42,134 sf, 69.19% Impervious, Inflow Depth > 4.11" for 10-Yr event  
 Inflow = 4.43 cfs @ 12.09 hrs, Volume= 14,442 cf  
 Outflow = 2.15 cfs @ 12.26 hrs, Volume= 14,442 cf, Atten= 51%, Lag= 10.2 min  
 Primary = 2.15 cfs @ 12.26 hrs, Volume= 14,442 cf  
 Routed to Link PA-2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs  
 Peak Elev= 59.98' @ 12.26 hrs Surf.Area= 1,843 sf Storage= 1,977 cf  
 Flood Elev= 61.00' Surf.Area= 3,341 sf Storage= 4,618 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 5.9 min ( 802.8 - 796.9 )

| Volume           | Invert            | Avail.Storage | Storage Description  |                        |
|------------------|-------------------|---------------|--|------------------------|
| #1               | 56.40'            | 4,618 cf      | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |                        |
| Elevation (feet) | Surf.Area (sq-ft) | Voids (%)     | Inc.Store (cubic-feet)                                     | Cum.Store (cubic-feet) |
| 56.40            | 779               | 0.0           | 0  | 0                      |
| 57.50            | 779               | 40.0          | 343  | 343                    |
| 59.00            | 779               | 30.0          | 351  | 693                    |
| 60.00            | 1,865             | 100.0         | 1,322  | 2,015                  |
| 61.00            | 3,341             | 100.0         | 2,603  | 4,618                  |

| Device | Routing  | Invert | Outlet Devices   |
|--------|----------|--------|--|
| #1     | Primary  | 54.50' | <b>24.0" Round Culvert</b> L= 4.0' Ke= 0.500<br>Inlet / Outlet Invert= 54.50' / 54.00' S= 0.1250 '/' Cc= 0.900<br>n= 0.012, Flow Area= 3.14 sf |
| #2     | Device 1 | 56.40' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads   |
| #3     | Device 1 | 56.40' | <b>10.000 in/hr Exfiltration over Surface area</b>   |

#4 Device 1 60.50' 1.0" x 1.0" Horiz. Orifice/Grate X 114 rows C= 0.600  
Limited to weir flow at low heads

Primary OutFlow Max=2.15 cfs @ 12.26 hrs HW=59.98' TW=0.00' (Dynamic Tailwater)

- 1=Culvert (Passes 2.15 cfs of 32.00 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 1.72 cfs @ 8.78 fps)
- 3=Exfiltration (Exfiltration Controls 0.43 cfs)
- 4=Orifice/Grate ( Controls 0.00 cfs)

**Summary for Link PA-1:**

Inflow Area = 192,156 sf, 54.43% Impervious, Inflow Depth > 3.58" for 10-Yr event  
 Inflow = 16.31 cfs @ 12.11 hrs, Volume= 57,250 cf  
 Primary = 16.31 cfs @ 12.11 hrs, Volume= 57,250 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

**Summary for Link PA-2:**

Inflow Area = 311,489 sf, 57.52% Impervious, Inflow Depth > 3.63" for 10-Yr event  
 Inflow = 10.55 cfs @ 12.42 hrs, Volume= 94,167 cf  
 Primary = 10.55 cfs @ 12.42 hrs, Volume= 94,167 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

**Summary for Link PA-3:**

Inflow Area = 281,262 sf, 65.09% Impervious, Inflow Depth > 3.96" for 10-Yr event  
 Inflow = 27.51 cfs @ 12.09 hrs, Volume= 92,845 cf  
 Primary = 27.51 cfs @ 12.09 hrs, Volume= 92,845 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

**Summary for Link PA-4:**

Inflow Area = 4,581 sf, 0.00% Impervious, Inflow Depth > 1.73" for 10-Yr event  
 Inflow = 0.20 cfs @ 12.09 hrs, Volume= 660 cf  
 Primary = 0.20 cfs @ 12.09 hrs, Volume= 660 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

**Summary for Link PA-5:**

Inflow Area = 8,825 sf, 89.09% Impervious, Inflow Depth > 4.88" for 10-Yr event  
 Inflow = 1.04 cfs @ 12.09 hrs, Volume= 3,587 cf  
 Primary = 1.04 cfs @ 12.09 hrs, Volume= 3,587 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Yr Rainfall=7.07"

Printed 9/17/2024

Page 21

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment POST 1.0:** Runoff Area=138,301 sf 75.24% Impervious Runoff Depth>5.77"  
 Flow Length=1,005' Tc=8.4 min CN=89 Runoff=18.59 cfs 66,502 cf

**Subcatchment POST 1.1:** Runoff Area=53,855 sf 0.99% Impervious Runoff Depth>2.65"  
 Flow Length=75' Slope=0.0350 '/' Tc=5.0 min CN=60 Runoff=3.76 cfs 11,898 cf

**Subcatchment POST 2.1:** Runoff Area=211,170 sf 68.33% Impervious Runoff Depth>5.43"  
 Flow Length=745' Tc=9.2 min CN=86 Runoff=26.31 cfs 95,487 cf

**Subcatchment POST 2.2:** Runoff Area=42,134 sf 69.19% Impervious Runoff Depth>5.54"  
 Flow Length=215' Tc=6.2 min CN=87 Runoff=5.89 cfs 19,462 cf

**Subcatchment POST 2.3:** Runoff Area=58,185 sf 9.83% Impervious Runoff Depth>3.05"  
 Flow Length=115' Slope=0.0200 '/' Tc=6.3 min CN=64 Runoff=4.61 cfs 14,795 cf

**Subcatchment POST 3.0:** Runoff Area=158,759 sf 73.04% Impervious Runoff Depth>5.66"  
 Flow Length=635' Slope=0.0150 '/' Tc=7.2 min CN=88 Runoff=21.91 cfs 74,834 cf

**Subcatchment POST 3.1:** Runoff Area=39,638 sf 0.00% Impervious Runoff Depth>2.75"  
 Flow Length=150' Tc=5.7 min CN=61 Runoff=2.84 cfs 9,083 cf

**Subcatchment POST 3.2:** Runoff Area=3,338 sf 0.00% Impervious Runoff Depth>2.75"  
 Flow Length=115' Tc=5.0 min CN=61 Runoff=0.24 cfs 765 cf

**Subcatchment POST 4.0:** Runoff Area=4,581 sf 0.00% Impervious Runoff Depth>2.75"  
 Tc=5.0 min CN=61 Runoff=0.33 cfs 1,050 cf

**Subcatchment POST 5.0:** Runoff Area=8,825 sf 89.09% Impervious Runoff Depth>6.35"  
 Flow Length=230' Slope=0.0200 '/' Tc=6.2 min CN=94 Runoff=1.34 cfs 4,672 cf

**Subcatchment POST-3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>6.12"  
 Tc=5.0 min CN=92 Runoff=12.23 cfs 40,564 cf

**Pond PDMH11: PDMH11** Peak Elev=61.56' Inflow=18.59 cfs 66,502 cf  
 Primary=8.92 cfs 57,836 cf Secondary=9.67 cfs 8,666 cf Outflow=18.59 cfs 66,502 cf

**Pond PDMH20: PDMH20** Peak Elev=58.61' Inflow=26.31 cfs 95,487 cf  
 Primary=7.04 cfs 70,527 cf Secondary=19.27 cfs 24,960 cf Outflow=26.31 cfs 95,487 cf

**Pond PDMH3: PDMH3** Peak Elev=62.79' Inflow=33.64 cfs 115,398 cf  
 Primary=9.92 cfs 88,385 cf Secondary=23.72 cfs 27,012 cf Outflow=33.64 cfs 115,398 cf

**Pond RG-1:** Peak Elev=53.91' Storage=23,726 cf Inflow=26.31 cfs 95,487 cf  
 Outflow=14.84 cfs 95,136 cf

**Pond RG-2:** Peak Elev=60.51' Storage=3,150 cf Inflow=5.89 cfs 19,462 cf  
 Outflow=2.53 cfs 19,462 cf



**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Yr Rainfall=7.07"

Printed 9/17/2024

Page 22

**Link PA-1:** Inflow=22.18 cfs 78,400 cf  
Primary=22.18 cfs 78,400 cf

**Link PA-2:** Inflow=19.61 cfs 129,393 cf  
Primary=19.61 cfs 129,393 cf

**Link PA-3:** Inflow=36.72 cfs 125,246 cf  
Primary=36.72 cfs 125,246 cf

**Link PA-4:** Inflow=0.33 cfs 1,050 cf  
Primary=0.33 cfs 1,050 cf

**Link PA-5:** Inflow=1.34 cfs 4,672 cf  
Primary=1.34 cfs 4,672 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 339,112 cf Average Runoff Depth = 5.10"**  
**40.54% Pervious = 323,634 sf 59.46% Impervious = 474,679 sf**

**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 9/17/2024

Page 23

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment POST 1.0:** Runoff Area=138,301 sf 75.24% Impervious Runoff Depth>7.13"  
 Flow Length=1,005' Tc=8.4 min CN=89 Runoff=22.71 cfs 82,186 cf

**Subcatchment POST 1.1:** Runoff Area=53,855 sf 0.99% Impervious Runoff Depth>3.68"  
 Flow Length=75' Slope=0.0350 '/' Tc=5.0 min CN=60 Runoff=5.29 cfs 16,512 cf

**Subcatchment POST 2.1:** Runoff Area=211,170 sf 68.33% Impervious Runoff Depth>6.77"  
 Flow Length=745' Tc=9.2 min CN=86 Runoff=32.44 cfs 119,130 cf

**Subcatchment POST 2.2:** Runoff Area=42,134 sf 69.19% Impervious Runoff Depth>6.89"  
 Flow Length=215' Tc=6.2 min CN=87 Runoff=7.23 cfs 24,203 cf

**Subcatchment POST 2.3:** Runoff Area=58,185 sf 9.83% Impervious Runoff Depth>4.15"  
 Flow Length=115' Slope=0.0200 '/' Tc=6.3 min CN=64 Runoff=6.31 cfs 20,108 cf

**Subcatchment POST 3.0:** Runoff Area=158,759 sf 73.04% Impervious Runoff Depth>7.01"  
 Flow Length=635' Slope=0.0150 '/' Tc=7.2 min CN=88 Runoff=26.83 cfs 92,771 cf

**Subcatchment POST 3.1:** Runoff Area=39,638 sf 0.00% Impervious Runoff Depth>3.80"  
 Flow Length=150' Tc=5.7 min CN=61 Runoff=3.97 cfs 12,537 cf

**Subcatchment POST 3.2:** Runoff Area=3,338 sf 0.00% Impervious Runoff Depth>3.80"  
 Flow Length=115' Tc=5.0 min CN=61 Runoff=0.34 cfs 1,056 cf

**Subcatchment POST 4.0:** Runoff Area=4,581 sf 0.00% Impervious Runoff Depth>3.80"  
 Tc=5.0 min CN=61 Runoff=0.47 cfs 1,449 cf

**Subcatchment POST 5.0:** Runoff Area=8,825 sf 89.09% Impervious Runoff Depth>7.73"  
 Flow Length=230' Slope=0.0200 '/' Tc=6.2 min CN=94 Runoff=1.61 cfs 5,688 cf

**Subcatchment POST-3.10:** Runoff Area=79,527 sf 84.38% Impervious Runoff Depth>7.50"  
 Tc=5.0 min CN=92 Runoff=14.81 cfs 49,674 cf

**Pond PDMH11: PDMH11** Peak Elev=61.91' Inflow=22.71 cfs 82,186 cf  
 Primary=9.59 cfs 69,225 cf Secondary=13.11 cfs 12,961 cf Outflow=22.71 cfs 82,186 cf

**Pond PDMH20: PDMH20** Peak Elev=59.60' Inflow=32.44 cfs 119,130 cf  
 Primary=7.99 cfs 84,905 cf Secondary=24.46 cfs 34,225 cf Outflow=32.44 cfs 119,130 cf

**Pond PDMH3: PDMH3** Peak Elev=63.19' Inflow=41.03 cfs 142,444 cf  
 Primary=10.59 cfs 105,329 cf Secondary=30.44 cfs 37,116 cf Outflow=41.03 cfs 142,444 cf

**Pond RG-1:** Peak Elev=54.26' Storage=26,148 cf Inflow=32.44 cfs 119,130 cf  
 Outflow=23.32 cfs 118,744 cf

**Pond RG-2:** Peak Elev=60.70' Storage=3,674 cf Inflow=7.23 cfs 24,203 cf  
 Outflow=4.27 cfs 24,203 cf

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 9/17/2024

Page 24

**Link PA-1:** Inflow=27.75 cfs 98,698 cf  
Primary=27.75 cfs 98,698 cf

**Link PA-2:** Inflow=31.62 cfs 163,056 cf  
Primary=31.62 cfs 163,056 cf

**Link PA-3:** Inflow=45.35 cfs 156,038 cf  
Primary=45.35 cfs 156,038 cf

**Link PA-4:** Inflow=0.47 cfs 1,449 cf  
Primary=0.47 cfs 1,449 cf

**Link PA-5:** Inflow=1.61 cfs 5,688 cf  
Primary=1.61 cfs 5,688 cf

**Total Runoff Area = 798,313 sf Runoff Volume = 425,314 cf Average Runoff Depth = 6.39"**  
**40.54% Pervious = 323,634 sf 59.46% Impervious = 474,679 sf**

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Printed 9/17/2024

Page 2

**Area Listing (all nodes)**

| Area<br>(sq-ft) | CN        | Description<br>(subcatchment-numbers)   |
|-----------------|-----------|---|
| 284,254         | 61        | >75% Grass cover, Good, HSG B (POST 1.0, POST 1.1, POST 2.1, POST 2.2, POST 2.3, POST 3.0, POST 3.1, POST 3.2, POST 4.0, POST 5.0, POST-3.10) |
| 63              | 74        | >75% Grass cover, Good, HSG C (POST 2.3)  |
| 360,205         | 98        | Paved parking, HSG B (POST 1.0, POST 1.1, POST 2.1, POST 2.2, POST 2.3, POST 3.0, POST 5.0, POST-3.10)  |
| 99,931          | 98        | Roofs, HSG B (POST 1.0, POST 2.1, POST 2.2, POST 3.0)   |
| 14,543          | 98        | Unconnected roofs, HSG B (POST-3.10)  |
| 34,229          | 55        | Woods, Good, HSG B (POST 1.1, POST 2.3, POST 3.1)   |
| 5,088           | 70        | Woods, Good, HSG C (POST 3.1)   |
| <b>798,313</b>  | <b>83</b> | <b>TOTAL AREA</b>   |

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Printed 9/17/2024

Page 3

**Soil Listing (all nodes)**

| Area<br>(sq-ft) | Soil<br>Group | Subcatchment<br>Numbers   |
|-----------------|---------------|---|
| 0               | HSG A         |   |
| 793,162         | HSG B         | POST 1.0, POST 1.1, POST 2.1, POST 2.2, POST 2.3, POST 3.0, POST 3.1, POST 3.2, POST 4.0, POST 5.0, POST-3.10 |
| 5,151           | HSG C         | POST 2.3, POST 3.1  |
| 0               | HSG D         |   |
| 0               | Other         |   |
| <b>798,313</b>  |               | <b>TOTAL AREA</b>   |

## Section 4

### Peak Rate Comparison

The following table summarizes and compares the pre- and post-development peak runoff rates from the 2-year, 10-year, 25-year and 50-year storm events at the point of analysis. The 1-year event has been included in order to demonstrate compliance with the Channel Protection requirements of Env-Wq 1507.05 for select points of analysis.

**Table 4.1**  
**Comparison of Pre- and Post-Development Flows (CFS)**

|                                   | <b>1-Year Storm</b> | <b>2-Year Storm</b> | <b>10-Year Storm</b> | <b>25-Year Storm</b> | <b>50-Year Storm</b> |
|-----------------------------------|---------------------|---------------------|----------------------|----------------------|----------------------|
| <b>Pre-Development Watershed</b>  |                     |                     |                      |                      |                      |
| PA-1                              | 7.56                | 10.36               | 19.19                | 26.26                | 32.86                |
| PA-2                              | 7.74                | 10.04               | 16.81                | 25.58                | 38.42                |
| PA-3                              | 12.32               | 16.62               | 30.22                | 41.10                | 51.37                |
| PA-4                              | 0.81                | 1.06                | 1.83                 | 2.44                 | 2.99                 |
| PA-5                              | 0.57                | 0.69                | 1.06                 | 1.35                 | 1.61                 |
| <b>Post-Development Watershed</b> |                     |                     |                      |                      |                      |
| PA-1                              | 6.82                | 9.09                | 16.31                | 22.18                | 27.75                |
| PA-2                              | 4.37                | 5.28                | 10.55                | 19.61                | 31.62                |
| PA-3                              | 12.23               | 15.96               | 27.51                | 36.72                | 45.35                |
| PA-4                              | 0.03                | 0.06                | 0.20                 | 0.33                 | 0.47                 |
| PA-5                              | 0.53                | 0.66                | 1.04                 | 1.34                 | 1.61                 |

Each of the points of analysis meets the channel protection requirements of Env-Wq 105.05 as follows:

PA-1: The 2-year, 24-hour post-development runoff volume (31,793 cf) has not increased over the 2-year, 24 hour pre-development runoff volume (33,388 cf) by more than 0.1 ac-ft (or 4,356 cf).

PA-2: The 2-year, 24-hour post-development peak flow rate (5.28 cfs) is less than or equal to the 1-year, 24-hour pre-development peak flow rate (7.74 cfs).

PA-3: The 2-year, 24-hour post-development runoff volume (53,113 cf) has not increased over the 2-year, 24 hour pre-development runoff volume (61,093 cf) by more than 0.1 ac-ft (or 4,356 cf).

PA-4: The 2-year, 24-hour post-development peak flow rate (0.06 cfs) is less than or equal to the 1-year, 24-hour pre-development peak flow rate (0.81 cfs).

PA-5: The 2-year, 24-hour post-development runoff volume (2,213 cf) has not increased over the 2-year, 24 hour pre-development runoff volume (2,409 cf) by more than 0.1 ac-ft (or 4,356 cf).

## Section 5

### Mitigation Description

The stormwater management system has been designed to provide stormwater treatment as required by the City of Portsmouth Site Review Regulations and NHDES AoT Regulations (Env-Wq 1500).

#### 5.1 Pre-Treatment Methods for Protecting Water Quality

Pre-treatment for the stormwater filtration systems consists of off-line deep sump catch basins, sediment forebays, Rain Guardian turrets, and Contech CDS units.

#### 5.2 Treatment Methods for Protecting Water Quality.

The runoff from proposed impervious areas will be treated by Contech Jellyfish stormwater filtration systems as well as a Rain Garden bioretention systems. These Jellyfish and Rain Garden systems are sized to treat the Water Quality Flow of their respective sub catchment areas. The BMP worksheets for the treatment practices have been included in Section 6 of this report.

The proposed stormwater management system is required to remove 80% of the annual Total Suspended Solids (TSS) loads and 50% of the annual Total Nitrogen (TN) loads per the City of Portsmouth's Site Plan regulations, Section 7.6.2.1.a.i. As shown in Table 5.1 the pollutant removal efficiencies for the proposed treatment systems exceed the City of Portsmouth's removal requirements.

| BMP  | Total Suspended Solids | Total Nitrogen | Total Phosphorus |
|--|------------------------|----------------|------------------|
| Jellyfish Filter w/Pretreatment <sup>1</sup> | 85%                    | 50%            | 55%              |
| Rain Garden w/ Pretreatment <sup>2</sup>     | 90%                    | 65%            | 65%              |

1. Pollutant removal efficiencies from Contech Engineered Solutions, Jellyfish Filter Stormwater Treatment standard performance specifications. Pre-treatment upstream of the unit is assumed to be accounted for.
2. Pollutant removal efficiencies from NH Stormwater Manual Volume 2, Appendix E. Per the descriptions listed in the Appendix, pre-treatment is already accounted for in the efficiencies cited.

## **Section 6**

# **BMP Worksheets**





## FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

Type/Node Name: \_\_\_\_\_

**RG-1**

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable.

|   |          |   |                           |
|---|----------|---|---------------------------|
|   |          | Check if you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a).  |                           |
| 4.85  | ac       | A = Area draining to the practice   |                           |
| 3.31  | ac       | A <sub>i</sub> = Impervious area draining to the practice   |                           |
| 0.68  | decimal  | I = Percent impervious area draining to the practice, in decimal form   |                           |
| 0.66  | unitless | R <sub>v</sub> = Runoff coefficient = 0.05 + (0.9 x I)  |                           |
| 3.22  | ac-in    | WQV = 1" x R <sub>v</sub> x A   |                           |
| 11,694  | cf       | WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")   |                           |
| 2,924   | cf       | 25% x WQV (check calc for sediment forebay volume)  |                           |
| 8,771   | cf       | 75% x WQV (check calc for surface sand filter volume)   |                           |
| CDS Unit  |          | Method of Pretreatment? (not required for clean or roof runoff)   |                           |
|   | cf       | V <sub>SED</sub> = Sediment forebay volume, if used for pretreatment  | ≥ 25%WQV                  |
| <b>Calculate time to drain if system IS NOT underdrained:</b>           |          |   |                           |
|   | sf       | A <sub>SA</sub> = Surface area of the practice  |                           |
|   | iph      | K <sub>sat</sub> <sub>DESIGN</sub> = Design infiltration rate <sup>1</sup>  |                           |
|   | Yes/No   | If K <sub>sat</sub> (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?<br>(Use the calculations below) |                           |
| -   | hours    | T <sub>DRAIN</sub> = Drain time = V / (A <sub>SA</sub> * I <sub>DESIGN</sub> )  | ≤ 72-hrs                  |
| <b>Calculate time to drain if system IS underdrained:</b>               |          |   |                           |
| 52.25   | ft       | E <sub>WQV</sub> = Elevation of WQV (attach stage-storage table)  |                           |
| 3.28  | cfs      | Q <sub>WQV</sub> = Discharge at the E <sub>WQV</sub> (attach stage-discharge table)   |                           |
| 1.98  | hours    | T <sub>DRAIN</sub> = Drain time = 2WQV/Q <sub>WQV</sub>   | ≤ 72-hrs                  |
| 48.50   | feet     | E <sub>FC</sub> = Elevation of the bottom of the filter course material <sup>2</sup>  |                           |
| 47.40   | feet     | E <sub>UD</sub> = Invert elevation of the underdrain (UD), if applicable  |                           |
| See Notes   | feet     | E <sub>SHWT</sub> = Elevation of SHWT (if none found, enter the lowest elevation of the test pit)                               |                           |
| See Notes   | feet     | E <sub>ROCK</sub> = Elevation of bedrock (if none found, enter the lowest elevation of the test pit)                            |                           |
| 1.10  | feet     | D <sub>FC to UD</sub> = Depth to UD from the bottom of the filter course  | ≥ 1'                      |
| #VALUE!   | feet     | D <sub>FC to ROCK</sub> = Depth to bedrock from the bottom of the filter course   | ≥ 1'                      |
| #VALUE!   | feet     | D <sub>FC to SHWT</sub> = Depth to SHWT from the bottom of the filter course  | ≥ 1'                      |
| 54.26   | ft       | Peak elevation of the 50-year storm event (infiltration can be used in analysis)  |                           |
| 55.00   | ft       | Elevation of the top of the practice  |                           |
| YES   |          | 50 peak elevation ≤ Elevation of the top of the practice  | ← yes                     |
| <b>If a surface sand filter or underground sand filter is proposed:</b> |          |   |                           |
| YES   | ac       | Drainage Area check.  | < 10 ac                   |
|   | cf       | V = Volume of storage <sup>3</sup> (attach a stage-storage table)   | ≥ 75%WQV                  |
|   | inches   | D <sub>FC</sub> = Filter course thickness   | 18", or 24" if within GPA |
| Sheet   |          | Note what sheet in the plan set contains the filter course specification.   |                           |
|   | Yes/No   | Access grate provided?  | ← yes                     |

| If a bioretention area is proposed: |        |   |                           |
|-------------------------------------|--------|---|---------------------------|
| YES                                 | ac     | Drainage Area no larger than 5 ac?  | ← yes                     |
| 16,197                              | cf     | V = Volume of storage <sup>3</sup> (attach a stage-storage table)             | ≥ WQV                     |
| 18.0                                | inches | D <sub>FC</sub> = Filter course thickness                                     | 18", or 24" if within GPA |
| Sheet                               |        | Note what sheet in the plan set contains the filter course specification      |                           |
| 3.0                                 | :1     | Pond side slopes  | > 3:1                     |
| Sheet                               |        | Note what sheet in the plan set contains the planting plans and surface cover |                           |
| If porous pavement is proposed:     |        |   |                           |
|                                     |        | Type of pavement proposed (Concrete? Asphalt? Pavers? Etc.)                   |                           |
|                                     | acres  | A <sub>SA</sub> = Surface area of the pervious pavement                       |                           |
|                                     | :1     | Ratio of the contributing area to the pervious surface area                   | ≤ 5:1                     |
|                                     | inches | D <sub>FC</sub> = Filter course thickness                                     | 12", or 18" if within GPA |
| Sheet                               |        | Note what sheet in the plan set contains the filter course spec.              | mod. 304.1 (see spec)     |

1. Rate of the limiting layer (either the filter course or the underlying soil).  $K_{sat_{design}}$  includes factor of safety. See Env-Wq 1504.14 for guidance on determining the infiltration rate.
2. See lines 34, 40 and 48 for required depths of filter media.
3. Volume without depending on infiltration. The volume includes the storage above the filter (but below the invert of the outlet structure, if any), the filter media voids, and the pretreatment area. The storage above the filter media shall not include the volume above the outlet structure, if any.

Designer's Notes:

Limited test pit information available due to existing site test pit access and location constraints, as described in the test pit data and logs included under Appendix B. Rain garden is proposed to be underdrained by a 6" perforated PVC, and no exfiltration to subgrade soils has been carried in the drainage design or model.

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Area-Storage for Pond RG-1:**

| Elevation<br>(feet) | Surface<br>(sq-ft) | Storage<br>(cubic-feet) | Elevation<br>(feet) | Surface<br>(sq-ft) | Storage<br>(cubic-feet) |
|---------------------|--------------------|-------------------------|---------------------|--------------------|-------------------------|
| 47.40               | 3,709              | 0                       | 50.00               | 3,709              | 3,301                   |
| 47.45               | 3,709              | 74                      | 50.05               | 3,745              | 3,487                   |
| 47.50               | 3,709              | 148                     | 50.10               | 3,781              | 3,676                   |
| 47.55               | 3,709              | 223                     | 50.15               | 3,818              | 3,866                   |
| 47.60               | 3,709              | 297                     | 50.20               | 3,854              | 4,057                   |
| 47.65               | 3,709              | 371                     | 50.25               | 3,890              | 4,251                   |
| 47.70               | 3,709              | 445                     | 50.30               | 3,926              | 4,446                   |
| 47.75               | 3,709              | 519                     | 50.35               | 3,962              | 4,644                   |
| 47.80               | 3,709              | 593                     | 50.40               | 3,999              | 4,843                   |
| 47.85               | 3,709              | 668                     | 50.45               | 4,035              | 5,043                   |
| 47.90               | 3,709              | 742                     | 50.50               | 4,071              | 5,246                   |
| 47.95               | 3,709              | 816                     | 50.55               | 4,107              | 5,450                   |
| 48.00               | 3,709              | 890                     | 50.60               | 4,143              | 5,657                   |
| 48.05               | 3,709              | 964                     | 50.65               | 4,180              | 5,865                   |
| 48.10               | 3,709              | 1,039                   | 50.70               | 4,216              | 6,075                   |
| 48.15               | 3,709              | 1,113                   | 50.75               | 4,252              | 6,286                   |
| 48.20               | 3,709              | 1,187                   | 50.80               | 4,288              | 6,500                   |
| 48.25               | 3,709              | 1,261                   | 50.85               | 4,324              | 6,715                   |
| 48.30               | 3,709              | 1,335                   | 50.90               | 4,361              | 6,932                   |
| 48.35               | 3,709              | 1,409                   | 50.95               | 4,397              | 7,151                   |
| 48.40               | 3,709              | 1,484                   | 51.00               | 4,433              | 7,372                   |
| 48.45               | 3,709              | 1,558                   | 51.05               | 4,472              | 7,595                   |
| 48.50               | 3,709              | 1,632                   | 51.10               | 4,511              | 7,819                   |
| 48.55               | 3,709              | 1,688                   | 51.15               | 4,550              | 8,046                   |
| 48.60               | 3,709              | 1,743                   | 51.20               | 4,589              | 8,274                   |
| 48.65               | 3,709              | 1,799                   | 51.25               | 4,628              | 8,505                   |
| 48.70               | 3,709              | 1,854                   | 51.30               | 4,667              | 8,737                   |
| 48.75               | 3,709              | 1,910                   | 51.35               | 4,706              | 8,971                   |
| 48.80               | 3,709              | 1,966                   | 51.40               | 4,745              | 9,208                   |
| 48.85               | 3,709              | 2,021                   | 51.45               | 4,784              | 9,446                   |
| 48.90               | 3,709              | 2,077                   | 51.50               | 4,824              | 9,686                   |
| 48.95               | 3,709              | 2,133                   | 51.55               | 4,863              | 9,928                   |
| 49.00               | 3,709              | 2,188                   | 51.60               | 4,902              | 10,172                  |
| 49.05               | 3,709              | 2,244                   | 51.65               | 4,941              | 10,418                  |
| 49.10               | 3,709              | 2,300                   | 51.70               | 4,980              | 10,666                  |
| 49.15               | 3,709              | 2,355                   | 51.75               | 5,019              | 10,916                  |
| 49.20               | 3,709              | 2,411                   | 51.80               | 5,058              | 11,168                  |
| 49.25               | 3,709              | 2,466                   | 51.85               | 5,097              | 11,422                  |
| 49.30               | 3,709              | 2,522                   | 51.90               | 5,136              | 11,678                  |
| 49.35               | 3,709              | 2,578                   | 51.95               | 5,175              | 11,936                  |
| 49.40               | 3,709              | 2,633                   | 52.00               | 5,214              | 12,196                  |
| 49.45               | 3,709              | 2,689                   | 52.05               | 5,256              | 12,457                  |
| 49.50               | 3,709              | 2,745                   | 52.10               | 5,298              | 12,721                  |
| 49.55               | 3,709              | 2,800                   | 52.15               | 5,340              | 12,987                  |
| 49.60               | 3,709              | 2,856                   | 52.20               | 5,382              | 13,255                  |
| 49.65               | 3,709              | 2,912                   | 52.25               | 5,424              | 13,525                  |
| 49.70               | 3,709              | 2,967                   | 52.30               | 5,465              | 13,797                  |
| 49.75               | 3,709              | 3,023                   | 52.35               | 5,507              | 14,072                  |
| 49.80               | 3,709              | 3,078                   | 52.40               | 5,549              | 14,348                  |
| 49.85               | 3,709              | 3,134                   | 52.45               | 5,591              | 14,627                  |
| 49.90               | 3,709              | 3,190                   | 52.50               | 5,633              | 14,907                  |
| 49.95               | 3,709              | 3,245                   | 52.55               | 5,675              | 15,190                  |

Bottom of  
Filter  
Course

Ewqv (excluding  
volume below  
filter course

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Area-Storage for Pond RG-1: (continued)**

| Elevation<br>(feet) | Surface<br>(sq-ft) | Storage<br>(cubic-feet) |
|---------------------|--------------------|-------------------------|
| 52.60               | 5,717              | 15,475                  |
| 52.65               | 5,759              | 15,762                  |
| 52.70               | 5,801              | 16,051                  |
| 52.75               | 5,843              | 16,342                  |
| 52.80               | 5,884              | 16,635                  |
| 52.85               | 5,926              | 16,930                  |
| 52.90               | 5,968              | 17,227                  |
| 52.95               | 6,010              | 17,527                  |
| <b>53.00</b>        | <b>6,052</b>       | <b>17,829</b>           |
| 53.05               | 6,097              | 18,132                  |
| 53.10               | 6,141              | 18,438                  |
| 53.15               | 6,186              | 18,746                  |
| 53.20               | 6,231              | 19,057                  |
| 53.25               | 6,276              | 19,369                  |
| 53.30               | 6,320              | 19,684                  |
| 53.35               | 6,365              | 20,001                  |
| 53.40               | 6,410              | 20,321                  |
| 53.45               | 6,454              | 20,642                  |
| 53.50               | 6,499              | 20,966                  |
| 53.55               | 6,544              | 21,292                  |
| 53.60               | 6,588              | 21,621                  |
| 53.65               | 6,633              | 21,951                  |
| 53.70               | 6,678              | 22,284                  |
| 53.75               | 6,723              | 22,619                  |
| 53.80               | 6,767              | 22,956                  |
| 53.85               | 6,812              | 23,296                  |
| 53.90               | 6,857              | 23,637                  |
| 53.95               | 6,901              | 23,981                  |
| 54.00               | 6,946              | 24,328                  |
| 54.05               | 6,994              | 24,676                  |
| 54.10               | 7,041              | 25,027                  |
| 54.15               | 7,089              | 25,380                  |
| 54.20               | 7,136              | 25,736                  |
| 54.25               | 7,184              | 26,094                  |
| 54.30               | 7,231              | 26,454                  |
| 54.35               | 7,279              | 26,817                  |
| 54.40               | 7,326              | 27,182                  |
| 54.45               | 7,374              | 27,549                  |
| 54.50               | 7,422              | 27,919                  |
| 54.55               | 7,469              | 28,292                  |
| 54.60               | 7,517              | 28,666                  |
| 54.65               | 7,564              | 29,043                  |
| 54.70               | 7,612              | 29,423                  |
| 54.75               | 7,659              | 29,804                  |
| 54.80               | 7,707              | 30,189                  |
| 54.85               | 7,754              | 30,575                  |
| 54.90               | 7,802              | 30,964                  |
| 54.95               | 7,849              | 31,355                  |
| 55.00               | <b>7,897</b>       | <b>31,749</b>           |

**First  
Outlet**

**Stage-Discharge for Pond RG-1:**

| Elevation<br>(feet) | Primary<br>(cfs) | Elevation<br>(feet) | Primary<br>(cfs) | Elevation<br>(feet) | Primary<br>(cfs) |
|---------------------|------------------|---------------------|------------------|---------------------|------------------|
| 47.40               | 0.00             | 50.00               | 2.31             | 52.60               | 3.43             |
| 47.45               | 0.01             | 50.05               | 2.33             | 52.65               | 3.45             |
| 47.50               | 0.05             | 50.10               | 2.36             | 52.70               | 3.47             |
| 47.55               | 0.11             | 50.15               | 2.38             | 52.75               | 3.49             |
| 47.60               | 0.21             | 50.20               | 2.40             | 52.80               | 3.51             |
| 47.65               | 0.33             | 50.25               | 2.42             | 52.85               | 3.53             |
| 47.70               | 0.47             | 50.30               | 2.45             | 52.90               | 3.55             |
| 47.75               | 0.64             | 50.35               | 2.47             | 52.95               | 3.57             |
| 47.80               | 0.83             | 50.40               | 2.49             | 53.00               | 3.59             |
| 47.85               | 1.04             | 50.45               | 2.52             | 53.05               | 3.75             |
| 47.90               | 1.27             | 50.50               | 2.54             | 53.10               | 4.04             |
| 47.95               | 1.38             | 50.55               | 2.56             | 53.15               | 4.40             |
| 48.00               | 1.42             | 50.60               | 2.58             | 53.20               | 4.83             |
| 48.05               | 1.46             | 50.65               | 2.61             | 53.25               | 5.30             |
| 48.10               | 1.49             | 50.70               | 2.63             | 53.30               | 5.83             |
| 48.15               | 1.53             | 50.75               | 2.65             | 53.35               | 6.39             |
| 48.20               | 1.56             | 50.80               | 2.67             | 53.40               | 6.99             |
| 48.25               | 1.59             | 50.85               | 2.69             | 53.45               | 7.63             |
| 48.30               | 1.62             | 50.90               | 2.71             | 53.50               | 8.30             |
| 48.35               | 1.65             | 50.95               | 2.74             | 53.55               | 9.00             |
| 48.40               | 1.68             | 51.00               | 2.76             | 53.60               | 9.73             |
| 48.45               | 1.70             | 51.05               | 2.78             | 53.65               | 10.48            |
| 48.50               | 1.73             | 51.10               | 2.80             | 53.70               | 11.26            |
| 48.55               | 1.76             | 51.15               | 2.82             | 53.75               | 12.07            |
| 48.60               | 1.78             | 51.20               | 2.84             | 53.80               | 12.90            |
| 48.65               | 1.80             | 51.25               | 2.87             | 53.85               | 13.75            |
| 48.70               | 1.83             | 51.30               | 2.89             | 53.90               | 14.62            |
| 48.75               | 1.85             | 51.35               | 2.91             | 53.95               | 15.51            |
| 48.80               | 1.87             | 51.40               | 2.93             | 54.00               | 16.42            |
| 48.85               | 1.89             | 51.45               | 2.95             | 54.05               | 18.20            |
| 48.90               | 1.92             | 51.50               | 2.97             | 54.10               | 19.50            |
| 48.95               | 1.94             | 51.55               | 2.99             | 54.15               | 20.73            |
| 49.00               | 1.96             | 51.60               | 3.01             | 54.20               | 21.94            |
| 49.05               | 1.98             | 51.65               | 3.03             | 54.25               | 23.14            |
| 49.10               | 2.00             | 51.70               | 3.06             | 54.30               | 24.33            |
| 49.15               | 2.02             | 51.75               | 3.08             | 54.35               | 25.52            |
| 49.20               | 2.04             | 51.80               | 3.10             | 54.40               | 26.71            |
| 49.25               | 2.05             | 51.85               | 3.12             | 54.45               | 27.91            |
| 49.30               | 2.07             | 51.90               | 3.14             | 54.50               | 29.12            |
| 49.35               | 2.09             | 51.95               | 3.16             | 54.55               | 30.32            |
| 49.40               | 2.11             | 52.00               | 3.18             | 54.60               | 31.54            |
| 49.45               | 2.13             | 52.05               | 3.20             | 54.65               | 32.76            |
| 49.50               | 2.14             | 52.10               | 3.22             | 54.70               | 33.99            |
| 49.55               | 2.16             | 52.15               | 3.24             | 54.75               | 35.22            |
| 49.60               | 2.18             | 52.20               | 3.26             | 54.80               | 36.47            |
| 49.65               | 2.20             | 52.25               | 3.28             | 54.85               | 37.71            |
| 49.70               | 2.21             | 52.30               | 3.30             | 54.90               | 38.57            |
| 49.75               | 2.23             | 52.35               | 3.32             | 54.95               | 38.71            |
| 49.80               | 2.24             | 52.40               | 3.35             | 55.00               | 38.86            |
| 49.85               | 2.26             | 52.45               | 3.37             |                     |                  |
| 49.90               | 2.28             | 52.50               | 3.39             |                     |                  |
| 49.95               | 2.29             | 52.55               | 3.41             |                     |                  |

Discharge @ Ewqv



## GENERAL CALCULATIONS - WQV and WQF (optional worksheet)

This worksheet may be useful when designing a BMP **that does not fit into one of the specific worksheets already provided** (i.e. for a technology which is not a stormwater wetland, infiltration practice, etc.)

### Water Quality Volume (WQV)

|               |   |
|---------------|---|
| 4.85 ac       | A = Area draining to the practice                                     |
| 3.30 ac       | $A_i$ = Impervious area draining to the practice                      |
| 0.68 decimal  | I = Percent impervious area draining to the practice, in decimal form |
| 0.66 unitless | $R_v$ = Runoff coefficient = $0.05 + (0.9 \times I)$                  |
| 3.21 ac-in    | $WQV = 1'' \times R_v \times A$                                       |
| 11,661 cf     | WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")                       |

### Water Quality Flow (WQF)

|                               |   |
|-------------------------------|---|
| 1 inches                      | P = Amount of rainfall. For WQF in NH, P = 1".  |
| 0.66 inches                   | Q = Water quality depth. $Q = WQV/A$  |
| 96 unitless                   | CN = Unit peak discharge curve number. $CN = 1000 / (10 + 5P + 10Q - 10 * [Q^2 + 1.25 * Q * P]^{0.5})$                          |
| 0.4 inches                    | S = Potential maximum retention. $S = (1000/CN) - 10$   |
| 0.074 inches                  | $I_a$ = Initial abstraction. $I_a = 0.2S$   |
| 9.2 minutes                   | $T_c$ = Time of Concentration   |
| 600.0 cfs/mi <sup>2</sup> /in | $q_u$ is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III.   |
| 3.012 cfs                     | $WQF = q_u \times WQV$ . Conversion: to convert "cfs/mi <sup>2</sup> /in * ac-in" to "cfs" multiply by 1mi <sup>2</sup> /640ac. |

Designer's Notes: POST-2.1 WATERSHED

CDS-3

---

Proprietary Pretreatment device located upstream of underground detention.

---

Pretreatment Device - Contech CDS Model 3030-6 (designed to treat maximum 3.0 cfs)

---

Upstream bypass pipe invert set to at least elevation of WQF (refer to stage-storage table)

---



---



---



---



---



---



---



---



---



---



---



---

**CDS ESTIMATED NET ANNUAL TSS REDUCTION  
BASED ON THE RATIONAL RAINFALL METHOD**



**100 DURGIN LANE  
PORTSMOUTH, NH  
for SYSTEM: CDS 3**

|            |      |         |           |      |         |
|------------|------|---------|-----------|------|---------|
| Area       | 4.85 | acres   | CDS Model | 3030 |         |
| Weighted C | 0.71 |         | PSD       | 110  | microns |
| Tc         | 6    | minutes |           |      |         |

| Rainfall Intensity <sup>1</sup> (in/hr) | Percent Rainfall Volume <sup>1</sup> | Cumulative Rainfall Volume | Total Flowrate (cfs) | Treated Flowrate (cfs) | Removal Efficiency (%) | Incremental Removal (%) |
|---|--------------------------------------|----------------------------|----------------------|------------------------|------------------------|-------------------------|
| 0.02                                    | 13.0%                                | 13.0%                      | 0.07                 | 0.07                   | 100.0                  | 13.0                    |
| 0.04                                    | 12.2%                                | 25.2%                      | 0.14                 | 0.14                   | 100.0                  | 12.2                    |
| 0.06                                    | 11.2%                                | 36.4%                      | 0.21                 | 0.21                   | 99.7                   | 11.2                    |
| 0.08                                    | 10.0%                                | 46.4%                      | 0.28                 | 0.28                   | 99.2                   | 9.9                     |
| 0.10                                    | 8.2%                                 | 54.6%                      | 0.34                 | 0.34                   | 98.7                   | 8.1                     |
| 0.12                                    | 5.8%                                 | 60.4%                      | 0.41                 | 0.41                   | 98.1                   | 5.7                     |
| 0.14                                    | 6.5%                                 | 66.9%                      | 0.48                 | 0.48                   | 97.6                   | 6.3                     |
| 0.16                                    | 4.6%                                 | 71.5%                      | 0.55                 | 0.55                   | 97.0                   | 4.5                     |
| 0.18                                    | 3.7%                                 | 75.2%                      | 0.62                 | 0.62                   | 96.5                   | 3.5                     |
| 0.20                                    | 3.3%                                 | 78.5%                      | 0.69                 | 0.69                   | 95.9                   | 3.2                     |
| 0.25                                    | 6.7%                                 | 85.2%                      | 0.86                 | 0.86                   | 94.6                   | 6.3                     |
| 0.30                                    | 3.7%                                 | 88.9%                      | 1.03                 | 1.03                   | 93.2                   | 3.4                     |
| 0.35                                    | 2.4%                                 | 91.3%                      | 1.21                 | 1.21                   | 91.8                   | 2.2                     |
| 0.40                                    | 1.8%                                 | 93.1%                      | 1.38                 | 1.38                   | 90.5                   | 1.7                     |
| 0.45                                    | 1.9%                                 | 95.0%                      | 1.55                 | 1.55                   | 89.1                   | 1.7                     |
| 0.50                                    | 1.1%                                 | 96.1%                      | 1.72                 | 1.72                   | 87.7                   | 0.9                     |
| 0.75                                    | 2.6%                                 | 98.7%                      | 2.58                 | 2.58                   | 80.9                   | 2.1                     |
| 1.00                                    | 0.9%                                 | 99.6%                      | 3.44                 | 3.00                   | 67.6                   | 0.6                     |
| 1.50                                    | 0.4%                                 | 100.0%                     | 5.17                 | 3.00                   | 45.1                   | 0.2                     |
| 2.00                                    | 0.0%                                 | 100.0%                     | 6.89                 | 3.00                   | 33.8                   | 0.0                     |
|   |                                      |                            |                      |                        |                        | 96.8                    |

Removal Efficiency Adjustment<sup>2</sup> = 6.5%  
 Predicted % Annual Rainfall Treated = 93.3%  
**Predicted Net Annual Load Removal Efficiency = 90.3%**

1 - Based on 10 years of hourly precipitation data from NCDC 1683, Concord WSO Airport, Merrimack County, NH  
 2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Discharge for Pond PDMH20: PDMH20**

| Elevation<br>(feet) | Discharge<br>(cfs) | Primary<br>(cfs) | Secondary<br>(cfs) | Elevation<br>(feet) | Discharge<br>(cfs) | Primary<br>(cfs) | Secondary<br>(cfs) |
|---------------------|--------------------|------------------|--------------------|---------------------|--------------------|------------------|--------------------|
| 54.65               | 0.00               | 0.00             | 0.00               | 57.25               | 13.34              | 5.48             | 7.86               |
| 54.70               | 0.01               | 0.01             | 0.00               | 57.30               | 13.94              | 5.55             | 8.39               |
| 54.75               | 0.04               | 0.04             | 0.00               | 57.35               | 14.53              | 5.61             | 8.93               |
| 54.80               | 0.10               | 0.10             | 0.00               | 57.40               | 15.14              | 5.67             | 9.46               |
| 54.85               | 0.17               | 0.17             | 0.00               | 57.45               | 15.74              | 5.74             | 10.00              |
| 54.90               | 0.26               | 0.26             | 0.00               | 57.50               | 16.34              | 5.80             | 10.54              |
| 54.95               | 0.36               | 0.36             | 0.00               | 57.55               | 16.93              | 5.86             | 11.07              |
| 55.00               | 0.47               | 0.47             | 0.00               | 57.60               | 17.52              | 5.92             | 11.60              |
| 55.05               | 0.59               | 0.59             | 0.00               | 57.65               | 18.10              | 5.98             | 12.12              |
| 55.10               | 0.72               | 0.72             | 0.00               | 57.70               | 18.67              | 6.04             | 12.63              |
| 55.15               | 0.86               | 0.86             | 0.00               | 57.75               | 19.23              | 6.10             | 13.13              |
| 55.20               | 1.00               | 1.00             | 0.00               | 57.80               | 19.76              | 6.16             | 13.60              |
| 55.25               | 1.15               | 1.15             | 0.00               | 57.85               | 20.27              | 6.21             | 14.05              |
| 55.30               | 1.31               | 1.31             | 0.00               | 57.90               | 20.74              | 6.27             | 14.47              |
| 55.35               | 1.47               | 1.47             | 0.00               | 57.95               | 21.16              | 6.33             | 14.84              |
| 55.40               | 1.64               | 1.64             | 0.00               | 58.00               | 21.51              | 6.38             | 15.13              |
| 55.45               | 1.81               | 1.81             | 0.00               | 58.05               | 21.94              | 6.44             | 15.50              |
| 55.50               | 1.98               | 1.98             | 0.00               | 58.10               | 22.36              | 6.50             | 15.87              |
| 55.55               | 2.16               | 2.16             | 0.00               | 58.15               | 22.77              | 6.55             | 16.22              |
| 55.60               | 2.33               | 2.33             | 0.00               | 58.20               | 23.17              | 6.60             | 16.57              |
| 55.65               | 2.50               | 2.50             | 0.00               | 58.25               | 23.57              | 6.66             | 16.91              |
| 55.70               | 2.67               | 2.67             | 0.00               | 58.30               | 23.96              | 6.71             | 17.25              |
| 55.75               | 2.83               | 2.83             | 0.00               | 58.35               | 24.34              | 6.76             | 17.58              |
| 55.80               | 2.98               | 2.98             | 0.00               | 58.40               | 24.72              | 6.82             | 17.90              |
| 55.85               | 3.12               | 3.12             | 0.00               | 58.45               | 25.08              | 6.87             | 18.21              |
| 55.90               | 3.25               | 3.25             | 0.00               | 58.50               | 25.45              | 6.92             | 18.53              |
| 55.95               | 3.34               | 3.34             | 0.00               | 58.55               | 25.81              | 6.97             | 18.83              |
| 56.00               | 3.43               | 3.43             | 0.00               | 58.60               | 26.16              | 7.02             | 19.13              |
| 56.05               | 3.60               | 3.59             | 0.02               | 58.65               | 26.51              | 7.07             | 19.43              |
| 56.10               | 3.75               | 3.69             | 0.06               | 58.70               | 26.85              | 7.13             | 19.72              |
| 56.15               | 3.92               | 3.78             | 0.14               | 58.75               | 27.19              | 7.18             | 20.01              |
| 56.20               | 4.12               | 3.88             | 0.25               | 58.80               | 27.52              | 7.22             | 20.29              |
| 56.25               | 4.35               | 3.97             | 0.39               | 58.85               | 27.85              | 7.27             | 20.57              |
| 56.30               | 4.61               | 4.06             | 0.55               | 58.90               | 28.17              | 7.32             | 20.85              |
| 56.35               | 4.89               | 4.14             | 0.74               | 58.95               | 28.50              | 7.37             | 21.12              |
| 56.40               | 5.19               | 4.23             | 0.96               | 59.00               | 28.81              | 7.42             | 21.39              |
| 56.45               | 5.52               | 4.31             | 1.21               | 59.05               | 29.13              | 7.47             | 21.66              |
| 56.50               | 5.87               | 4.39             | 1.48               | 59.10               | 29.44              | 7.52             | 21.92              |
| 56.55               | 6.25               | 4.47             | 1.77               | 59.15               | 29.74              | 7.56             | 22.18              |
| 56.60               | 6.64               | 4.55             | 2.09               | 59.20               | 30.05              | 7.61             | 22.44              |
| 56.65               | 7.06               | 4.63             | 2.43               | 59.25               | 30.35              | 7.66             | 22.69              |
| 56.70               | 7.50               | 4.71             | 2.79               | 59.30               | 30.64              | 7.70             | 22.94              |
| 56.75               | 7.96               | 4.78             | 3.17               | 59.35               | 30.94              | 7.75             | 23.19              |
| 56.80               | 8.43               | 4.86             | 3.57               | 59.40               | 31.23              | 7.80             | 23.43              |
| 56.85               | 8.92               | 4.93             | 3.99               | 59.45               | 31.52              | 7.84             | 23.68              |
| 56.90               | 9.43               | 5.00             | 4.43               | 59.50               | 31.80              | 7.89             | 23.92              |
| 56.95               | 9.95               | 5.07             | 4.88               | 59.55               | 32.09              | 7.93             | 24.16              |
| 57.00               | 10.49              | 5.14             | 5.35               | 59.60               | 32.37              | 7.98             | 24.39              |
| 57.05               | 11.04              | 5.21             | 5.83               | 59.65               | 32.65              | 8.02             | 24.62              |
| 57.10               | 11.60              | 5.28             | 6.32               | 59.70               | 32.92              | 8.07             | 24.86              |
| 57.15               | 12.17              | 5.35             | 6.83               | 59.75               | 33.20              | 8.11             | 25.08              |
| 57.20               | 12.75              | 5.41             | 7.34               | 59.80               | 33.47              | 8.15             | 25.31              |

Bypass  
@  
Primary  
> WQF



**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Discharge for Pond PDMH20: PDMH20 (continued)**

| Elevation<br>(feet) | Discharge<br>(cfs) | Primary<br>(cfs) | Secondary<br>(cfs) |
|---------------------|--------------------|------------------|--------------------|
| 59.85               | 33.74              | 8.20             | 25.54              |
| 59.90               | 34.00              | 8.24             | 25.76              |
| 59.95               | 34.27              | 8.29             | 25.98              |
| 60.00               | 34.53              | 8.33             | 26.20              |
| 60.05               | 34.79              | 8.37             | 26.42              |
| 60.10               | 35.05              | 8.41             | 26.63              |
| 60.15               | 35.30              | 8.46             | 26.85              |
| 60.20               | 35.56              | 8.50             | 27.06              |
| 60.25               | 35.81              | 8.54             | 27.27              |
| 60.30               | 36.06              | 8.58             | 27.48              |
| 60.35               | 36.31              | 8.62             | 27.69              |
| 60.40               | 36.56              | 8.66             | 27.89              |
| 60.45               | 36.80              | 8.71             | 28.10              |
| 60.50               | 37.05              | 8.75             | 28.30              |
| 60.55               | 37.29              | 8.79             | 28.50              |
| 60.60               | 37.53              | 8.83             | 28.70              |
| 60.65               | 37.77              | 8.87             | 28.90              |
| 60.70               | 38.01              | 8.91             | 29.10              |
| 60.75               | 38.24              | 8.95             | 29.29              |
| 60.80               | 38.48              | 8.99             | 29.49              |
| 60.85               | 38.71              | 9.03             | 29.68              |
| 60.90               | 38.94              | 9.07             | 29.87              |
| 60.95               | 39.17              | 9.11             | 30.06              |
| 61.00               | 39.40              | 9.15             | 30.25              |
| 61.05               | 39.63              | 9.19             | 30.44              |
| 61.10               | 39.85              | 9.22             | 30.63              |
| 61.15               | 40.08              | 9.26             | 30.82              |
| 61.20               | 40.30              | 9.30             | 31.00              |
| 61.25               | 40.52              | 9.34             | 31.18              |
| 61.30               | 40.75              | 9.38             | 31.37              |
| 61.35               | 40.97              | 9.42             | 31.55              |
| 61.40               | 41.18              | 9.45             | 31.73              |
| 61.45               | 41.40              | 9.49             | 31.91              |
| 61.50               | 41.62              | 9.53             | 32.09              |
| 61.55               | 41.83              | 9.57             | 32.27              |
| 61.60               | 42.05              | 9.60             | 32.44              |
| 61.65               | 42.26              | 9.64             | 32.62              |
| 61.70               | 42.47              | 9.68             | 32.79              |
| 61.75               | 42.68              | 9.72             | 32.97              |
| 61.80               | 42.89              | 9.75             | 33.14              |
| 61.85               | 43.10              | 9.79             | 33.31              |
| 61.90               | 43.31              | 9.83             | 33.48              |
| 61.95               | 43.52              | 9.86             | 33.65              |
| 62.00               | 43.72              | 9.90             | 33.82              |
| 62.05               | <b>43.93</b>       | <b>9.93</b>      | <b>33.99</b>       |



## FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

Type/Node Name: \_\_\_\_\_

**RG-2**

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable.

|   |          |  |                           |
|---|----------|--|---------------------------|
|   |          | Check if you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a).             |                           |
| 0.97  | ac       | A = Area draining to the practice  |                           |
| 0.67  | ac       | A <sub>i</sub> = Impervious area draining to the practice  |                           |
| 0.69  | decimal  | l = Percent impervious area draining to the practice, in decimal form                                |                           |
| 0.67  | unitless | Rv = Runoff coefficient = 0.05 + (0.9 x l)   |                           |
| 0.65  | ac-in    | WQV = 1" x Rv x A  |                           |
| 2,365   | cf       | WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")  |                           |
| 591   | cf       | 25% x WQV (check calc for sediment forebay volume)   |                           |
| 1,774   | cf       | 75% x WQV (check calc for surface sand filter volume)  |                           |
| Rain Guardian Turret  |          | Method of Pretreatment? (not required for clean or roof runoff)                                      |                           |
| N/A   | cf       | V <sub>SED</sub> = Sediment forebay volume, if used for pretreatment                                 | ≥ 25%WQV                  |
| Calculate time to drain if system IS NOT underdrained:                  |          |  |                           |
|   | sf       | A <sub>SA</sub> = Surface area of the practice   |                           |
|   | iph      | Ksat <sub>DESIGN</sub> = Design infiltration rate <sup>1</sup>                                       |                           |
|   |          | If Ksat (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?                  |                           |
|   | Yes/No   | (Use the calculations below)   |                           |
| -   | hours    | T <sub>DRAIN</sub> = Drain time = V / (A <sub>SA</sub> * I <sub>DESIGN</sub> )                       | ≤ 72-hrs                  |
| Calculate time to drain if system IS underdrained:                      |          |  |                           |
| 60.35   | ft       | E <sub>WQV</sub> = Elevation of WQV (attach stage-storage table)                                     |                           |
| 2.37  | cfs      | Q <sub>WQV</sub> = Discharge at the E <sub>WQV</sub> (attach stage-discharge table)                  |                           |
| 0.55  | hours    | T <sub>DRAIN</sub> = Drain time = 2WQV/Q <sub>WQV</sub>  | ≤ 72-hrs                  |
| 57.50   | feet     | E <sub>FC</sub> = Elevation of the bottom of the filter course material <sup>2</sup>                 |                           |
| 56.40   | feet     | E <sub>UD</sub> = Invert elevation of the underdrain (UD), if applicable                             |                           |
| See Notes   | feet     | E <sub>SHWT</sub> = Elevation of SHWT (if none found, enter the lowest elevation of the test pit)    |                           |
| See Notes   | feet     | E <sub>ROCK</sub> = Elevation of bedrock (if none found, enter the lowest elevation of the test pit) |                           |
| 1.10  | feet     | D <sub>FC to UD</sub> = Depth to UD from the bottom of the filter course                             | ≥ 1'                      |
| #VALUE!   | feet     | D <sub>FC to ROCK</sub> = Depth to bedrock from the bottom of the filter course                      | ≥ 1'                      |
| #VALUE!   | feet     | D <sub>FC to SHWT</sub> = Depth to SHWT from the bottom of the filter course                         | ≥ 1'                      |
| 60.70   | ft       | Peak elevation of the 50-year storm event (infiltration can be used in analysis)                     |                           |
| 61.00   | ft       | Elevation of the top of the practice   |                           |
| YES   |          | 50 peak elevation ≤ Elevation of the top of the practice   | ← yes                     |
| <b>If a surface sand filter or underground sand filter is proposed:</b> |          |  |                           |
| YES   | ac       | Drainage Area check.   | < 10 ac                   |
|   | cf       | V = Volume of storage <sup>3</sup> (attach a stage-storage table)                                    | ≥ 75%WQV                  |
|   | inches   | D <sub>FC</sub> = Filter course thickness  | 18", or 24" if within GPA |
| Sheet   |          | Note what sheet in the plan set contains the filter course specification.                            |                           |
|   | Yes/No   | Access grate provided?   | ← yes                     |

| If a bioretention area is proposed: |        |   |                           |
|-------------------------------------|--------|---|---------------------------|
| YES                                 | ac     | Drainage Area no larger than 5 ac?  | ← yes                     |
| 2,789                               | cf     | V = Volume of storage <sup>3</sup> (attach a stage-storage table)             | ≥ WQV                     |
| 18.0                                | inches | D <sub>FC</sub> = Filter course thickness                                     | 18", or 24" if within GPA |
| Sheet                               |        | Note what sheet in the plan set contains the filter course specification      |                           |
| 3.0                                 | :1     | Pond side slopes  | > 3:1                     |
| Sheet                               |        | Note what sheet in the plan set contains the planting plans and surface cover |                           |
| If porous pavement is proposed:     |        |   |                           |
|                                     |        | Type of pavement proposed (Concrete? Asphalt? Pavers? Etc.)                   |                           |
|                                     | acres  | A <sub>SA</sub> = Surface area of the pervious pavement                       |                           |
|                                     | :1     | Ratio of the contributing area to the pervious surface area                   | ≤ 5:1                     |
|                                     | inches | D <sub>FC</sub> = Filter course thickness                                     | 12", or 18" if within GPA |
| Sheet                               |        | Note what sheet in the plan set contains the filter course spec.              | mod. 304.1 (see spec)     |

1. Rate of the limiting layer (either the filter course or the underlying soil).  $K_{sat_{design}}$  includes factor of safety. See Env-Wq 1504.14 for guidance on determining the infiltration rate.
2. See lines 34, 40 and 48 for required depths of filter media.
3. Volume without depending on infiltration. The volume includes the storage above the filter (but below the invert of the outlet structure, if any), the filter media voids, and the pretreatment area. The storage above the filter media shall not include the volume above the outlet structure, if any.

Designer's Notes:

Limited test pit information available due to existing site test pit access and location constraints, as described in the test pit data and logs included under Appendix B. Rain garden is proposed to be underdrained by a 6" perforated PVC, and no exfiltration to subgrade soils has been carried in the drainage design or model.

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Area-Storage for Pond RG-2:**

| Elevation<br>(feet) | Surface<br>(sq-ft) | Storage<br>(cubic-feet) | Elevation<br>(feet) | Surface<br>(sq-ft) | Storage<br>(cubic-feet) |
|---------------------|--------------------|-------------------------|---------------------|--------------------|-------------------------|
| 56.40               | 779                | 0                       | 59.00               | 779                | 693                     |
| 56.45               | 779                | 16                      | 59.05               | 833                | 734                     |
| 56.50               | 779                | 31                      | 59.10               | 888                | 777                     |
| 56.55               | 779                | 47                      | 59.15               | 942                | 822                     |
| 56.60               | 779                | 62                      | 59.20               | 996                | 871                     |
| 56.65               | 779                | 78                      | 59.25               | 1,051              | 922                     |
| 56.70               | 779                | 93                      | 59.30               | 1,105              | 976                     |
| 56.75               | 779                | 109                     | 59.35               | 1,159              | 1,032                   |
| 56.80               | 779                | 125                     | 59.40               | 1,213              | 1,092                   |
| 56.85               | 779                | 140                     | 59.45               | 1,268              | 1,154                   |
| 56.90               | 779                | 156                     | 59.50               | 1,322              | 1,219                   |
| 56.95               | 779                | 171                     | 59.55               | 1,376              | 1,286                   |
| 57.00               | 779                | 187                     | 59.60               | 1,431              | 1,356                   |
| 57.05               | 779                | 203                     | 59.65               | 1,485              | 1,429                   |
| 57.10               | 779                | 218                     | 59.70               | 1,539              | 1,505                   |
| 57.15               | 779                | 234                     | 59.75               | 1,594              | 1,583                   |
| 57.20               | 779                | 249                     | 59.80               | 1,648              | 1,664                   |
| 57.25               | 779                | 265                     | 59.85               | 1,702              | 1,748                   |
| 57.30               | 779                | 280                     | 59.90               | 1,756              | 1,834                   |
| 57.35               | 779                | 296                     | 59.95               | 1,811              | 1,923                   |
| 57.40               | 779                | 312                     | 60.00               | 1,865              | 2,015                   |
| 57.45               | 779                | 327                     | 60.05               | 1,939              | 2,110                   |
| 57.50               | 779                | 343                     | 60.10               | 2,013              | 2,209                   |
| 57.55               | 779                | 354                     | 60.15               | 2,086              | 2,312                   |
| 57.60               | 779                | 366                     | 60.20               | 2,160              | 2,418                   |
| 57.65               | 779                | 378                     | 60.25               | 2,234              | 2,528                   |
| 57.70               | 779                | 389                     | 60.30               | 2,308              | 2,641                   |
| 57.75               | 779                | 401                     | 60.35               | 2,382              | 2,758                   |
| 57.80               | 779                | 413                     | 60.40               | 2,455              | 2,879                   |
| 57.85               | 779                | 425                     | 60.45               | 2,529              | 3,004                   |
| 57.90               | 779                | 436                     | 60.50               | 2,603              | 3,132                   |
| 57.95               | 779                | 448                     | 60.55               | 2,677              | 3,264                   |
| 58.00               | 779                | 460                     | 60.60               | 2,751              | 3,400                   |
| 58.05               | 779                | 471                     | 60.65               | 2,824              | 3,539                   |
| 58.10               | 779                | 483                     | 60.70               | 2,898              | 3,682                   |
| 58.15               | 779                | 495                     | 60.75               | 2,972              | 3,829                   |
| 58.20               | 779                | 506                     | 60.80               | 3,046              | 3,980                   |
| 58.25               | 779                | 518                     | 60.85               | 3,120              | 4,134                   |
| 58.30               | 779                | 530                     | 60.90               | 3,193              | 4,292                   |
| 58.35               | 779                | 541                     | 60.95               | 3,267              | 4,453                   |
| 58.40               | 779                | 553                     | 61.00               | <b>3,341</b>       | <b>4,618</b>            |
| 58.45               | 779                | 565                     |                     |                    |                         |
| 58.50               | 779                | 576                     |                     |                    |                         |
| 58.55               | 779                | 588                     |                     |                    |                         |
| 58.60               | 779                | 600                     |                     |                    |                         |
| 58.65               | 779                | 612                     |                     |                    |                         |
| 58.70               | 779                | 623                     |                     |                    |                         |
| 58.75               | 779                | 635                     |                     |                    |                         |
| 58.80               | 779                | 647                     |                     |                    |                         |
| 58.85               | 779                | 658                     |                     |                    |                         |
| 58.90               | 779                | 670                     |                     |                    |                         |
| 58.95               | 779                | 682                     |                     |                    |                         |

Bottom of  
Filter  
Course

Ewqv (excluding volume  
below filter course)

First Outlet

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Discharge for Pond RG-2:**

| Elevation<br>(feet) | Primary<br>(cfs) | Elevation<br>(feet) | Primary<br>(cfs) |
|---------------------|------------------|---------------------|------------------|
| 56.40               | 0.00             | 59.00               | 1.63             |
| 56.45               | 0.19             | 59.05               | 1.66             |
| 56.50               | 0.21             | 59.10               | 1.69             |
| 56.55               | 0.25             | 59.15               | 1.71             |
| 56.60               | 0.29             | 59.20               | 1.74             |
| 56.65               | 0.35             | 59.25               | 1.77             |
| 56.70               | 0.41             | 59.30               | 1.79             |
| 56.75               | 0.48             | 59.35               | 1.82             |
| 56.80               | 0.54             | 59.40               | 1.85             |
| 56.85               | 0.61             | 59.45               | 1.88             |
| 56.90               | 0.65             | 59.50               | 1.90             |
| 56.95               | 0.70             | 59.55               | 1.93             |
| 57.00               | 0.74             | 59.60               | 1.95             |
| 57.05               | 0.78             | 59.65               | 1.98             |
| 57.10               | 0.81             | 59.70               | 2.01             |
| 57.15               | 0.85             | 59.75               | 2.03             |
| 57.20               | 0.88             | 59.80               | 2.06             |
| 57.25               | 0.91             | 59.85               | 2.09             |
| 57.30               | 0.94             | 59.90               | 2.11             |
| 57.35               | 0.97             | 59.95               | 2.14             |
| 57.40               | 1.00             | 60.00               | 2.16             |
| 57.45               | 1.03             | 60.05               | 2.19             |
| 57.50               | 1.05             | 60.10               | 2.22             |
| 57.55               | 1.08             | 60.15               | 2.25             |
| 57.60               | 1.10             | 60.20               | 2.28             |
| 57.65               | 1.13             | 60.25               | 2.31             |
| 57.70               | 1.15             | 60.30               | 2.34             |
| 57.75               | 1.17             | 60.35               | 2.37             |
| 57.80               | 1.19             | 60.40               | 2.40             |
| 57.85               | 1.22             | 60.45               | 2.43             |
| 57.90               | 1.24             | 60.50               | 2.46             |
| 57.95               | 1.26             | 60.55               | 3.34             |
| 58.00               | 1.28             | 60.60               | 3.72             |
| 58.05               | 1.30             | 60.65               | 4.02             |
| 58.10               | 1.32             | 60.70               | 4.28             |
| 58.15               | 1.34             | 60.75               | 4.51             |
| 58.20               | 1.36             | 60.80               | 4.72             |
| 58.25               | 1.38             | 60.85               | 4.91             |
| 58.30               | 1.39             | 60.90               | 5.10             |
| 58.35               | 1.41             | 60.95               | 5.27             |
| 58.40               | 1.43             | 61.00               | 5.44             |
| 58.45               | 1.45             |                     |                  |
| 58.50               | 1.47             |                     |                  |
| 58.55               | 1.48             |                     |                  |
| 58.60               | 1.50             |                     |                  |
| 58.65               | 1.52             |                     |                  |
| 58.70               | 1.53             |                     |                  |
| 58.75               | 1.55             |                     |                  |
| 58.80               | 1.57             |                     |                  |
| 58.85               | 1.58             |                     |                  |
| 58.90               | 1.60             |                     |                  |
| 58.95               | 1.61             |                     |                  |

Discharge @ Ewqv



## GENERAL CALCULATIONS - WQV and WQF (optional worksheet)

This worksheet may be useful when designing a BMP **that does not fit into one of the specific worksheets already provided** (i.e. for a technology which is not a stormwater wetland, infiltration practice, etc.)

### Water Quality Volume (WQV)

|               |   |
|---------------|---|
| 3.17 ac       | A = Area draining to the practice                                     |
| 2.39 ac       | A <sub>i</sub> = Impervious area draining to the practice             |
| 0.75 decimal  | I = Percent impervious area draining to the practice, in decimal form |
| 0.73 unitless | R <sub>v</sub> = Runoff coefficient = 0.05 + (0.9 x I)                |
| 2.31 ac-in    | WQV = 1" x R <sub>v</sub> x A   |
| 8,383 cf      | WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")                       |

### Water Quality Flow (WQF)

|                               |  |
|-------------------------------|--|
| 1 inches                      | P = Amount of rainfall. For WQF in NH, P = 1".   |
| 0.73 inches                   | Q = Water quality depth. Q = WQV/A   |
| 97 unitless                   | CN = Unit peak discharge curve number. CN = 1000 / (10 + 5P + 10Q - 10 * [Q <sup>2</sup> + 1.25 * Q * P] <sup>0.5</sup> )          |
| 0.3 inches                    | S = Potential maximum retention. S = (1000/CN) - 10  |
| 0.056 inches                  | I <sub>a</sub> = Initial abstraction. I <sub>a</sub> = 0.2S  |
| 8.4 minutes                   | T <sub>c</sub> = Time of Concentration   |
| 620.0 cfs/mi <sup>2</sup> /in | q <sub>u</sub> is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III.                                   |
| 2.237 cfs                     | WQF = q <sub>u</sub> x WQV. Conversion: to convert "cfs/mi <sup>2</sup> /in * ac-in" to "cfs" multiply by 1mi <sup>2</sup> /640ac. |

Designer's Notes: POST 1.0 WATERSHED

JFF-1 and CDS-1

Proprietary Pretreatment device located upstream of underground detention.

Pretreatment Device - Contech CDS Model 3025-6 (designed to treat maximum 2.4 cfs)

Treatment Device - Contech Jellyfish Filter Model JFPD080812-3 (designed to treat maximum 2.41 cfs)

Upstream bypass pipe invert set to at least elevation of WQF (refer to stage-storage table)

**CDS ESTIMATED NET ANNUAL TSS REDUCTION  
BASED ON THE RATIONAL RAINFALL METHOD**



**100 DURGIN LANE  
PORTSMOUTH, NH  
for SYSTEM: CDS 1**

|            |      |         |           |      |         |
|------------|------|---------|-----------|------|---------|
| Area       | 3.17 | acres   | CDS Model | 3025 |         |
| Weighted C | 0.75 |         | PSD       | 110  | microns |
| Tc         | 6    | minutes |           |      |         |

| Rainfall Intensity <sup>1</sup> (in/hr) | Percent Rainfall Volume <sup>1</sup> | Cumulative Rainfall Volume | Total Flowrate (cfs) | Treated Flowrate (cfs) | Removal Efficiency (%) | Incremental Removal (%) |
|---|--------------------------------------|----------------------------|----------------------|------------------------|------------------------|-------------------------|
| 0.02                                    | 13.0%                                | 13.0%                      | 0.05                 | 0.05                   | 100.0                  | 13.0                    |
| 0.04                                    | 12.2%                                | 25.2%                      | 0.10                 | 0.10                   | 100.0                  | 12.2                    |
| 0.06                                    | 11.2%                                | 36.4%                      | 0.14                 | 0.14                   | 100.0                  | 11.2                    |
| 0.08                                    | 10.0%                                | 46.4%                      | 0.19                 | 0.19                   | 99.5                   | 9.9                     |
| 0.10                                    | 8.2%                                 | 54.6%                      | 0.24                 | 0.24                   | 99.1                   | 8.2                     |
| 0.12                                    | 5.8%                                 | 60.4%                      | 0.29                 | 0.29                   | 98.6                   | 5.7                     |
| 0.14                                    | 6.5%                                 | 66.9%                      | 0.33                 | 0.33                   | 98.1                   | 6.4                     |
| 0.16                                    | 4.6%                                 | 71.5%                      | 0.38                 | 0.38                   | 97.7                   | 4.5                     |
| 0.18                                    | 3.7%                                 | 75.2%                      | 0.43                 | 0.43                   | 97.2                   | 3.6                     |
| 0.20                                    | 3.3%                                 | 78.5%                      | 0.48                 | 0.48                   | 96.7                   | 3.2                     |
| 0.25                                    | 6.7%                                 | 85.2%                      | 0.59                 | 0.59                   | 95.6                   | 6.4                     |
| 0.30                                    | 3.7%                                 | 88.9%                      | 0.71                 | 0.71                   | 94.4                   | 3.5                     |
| 0.35                                    | 2.4%                                 | 91.3%                      | 0.83                 | 0.83                   | 93.2                   | 2.2                     |
| 0.40                                    | 1.8%                                 | 93.1%                      | 0.95                 | 0.95                   | 92.1                   | 1.7                     |
| 0.45                                    | 1.9%                                 | 95.0%                      | 1.07                 | 1.07                   | 90.9                   | 1.8                     |
| 0.50                                    | 1.1%                                 | 96.1%                      | 1.19                 | 1.19                   | 89.8                   | 1.0                     |
| 0.75                                    | 2.6%                                 | 98.7%                      | 1.78                 | 1.78                   | 83.9                   | 2.2                     |
| 1.00                                    | 0.9%                                 | 99.6%                      | 2.38                 | 2.38                   | 78.1                   | 0.7                     |
| 1.50                                    | 0.4%                                 | 100.0%                     | 3.57                 | 2.43                   | 52.9                   | 0.2                     |
| 2.00                                    | 0.0%                                 | 100.0%                     | 4.76                 | 2.43                   | 39.7                   | 0.0                     |
|   |                                      |                            |                      |                        |                        | 97.5                    |

Removal Efficiency Adjustment<sup>2</sup> = 6.5%  
 Predicted % Annual Rainfall Treated = 93.4%

**Predicted Net Annual Load Removal Efficiency = 91.0%**

1 - Based on 10 years of hourly precipitation data from NCDC 1683, Concord WSO Airport, Merrimack County, NH

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.



# Jellyfish Filter Design Calculation

Contech Engineered Solutions, LLC Engineer:  
Date Prepared:

DRA  
9/9/2024

## Site Information

|                                      |                 |
|--------------------------------------|-----------------|
| Project Name                         | 100 Durgin Lane |
| Project City                         | Portsmouth      |
| Project State                        | NH              |
| Site Designation                     | JF 1            |
| Total Drainage Area, Ad              | 3.17 ac         |
| Post Development Impervious Area, Ai | 2.39 ac         |
| Pervious Area, Ap                    | 0.78 ac         |
| % Impervious                         | 75%             |
| Runoff Coefficient, Rc               | 0.73            |
| Upstream pretreatment credit         | 50%             |

## Mass Loading Calculations

|  |                         |
|--|-------------------------|
| Mean Annual Rainfall, P                    | 48 in                   |
| Agency Required % Removal                  | 80%                     |
| Percent Runoff Capture                     | 90%                     |
| Mean Annual Runoff, Vt                     | 362,167 ft <sup>3</sup> |
| Event Mean Concentration of Pollutant, EMC | 70 mg/l                 |
| Annual Mass Load, M total                  | 1,582 lbs               |

## Filter System

|                  |           |
|------------------|-----------|
| Filtration Brand | Jellyfish |
| Cartridge Length | 54 in     |

## Jellyfish Sizing

|   |           |
|---|-----------|
| Mass removed by pretreatment system     | 791 lbs   |
| Mass load to filters after pretreatment | 791 lbs   |
| Mass to be Captured by System           | 633 lbs   |
| Water Quality Flow                      | 2.237 cfs |

## Method to Use

FLOW BASED

| Summary |                       |               |
|---------|-----------------------|---------------|
|         | Treatment Flow Rate   | 2.41 cfs      |
| Flow    | Required Size         | JFPD0808-12-3 |
|         | Mass Capture provided | 1,689 lbs     |



**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Discharge for Pond PDHM19: PDMH19**

| Elevation<br>(feet) | Discharge<br>(cfs) | Primary<br>(cfs) | Secondary<br>(cfs) | Elevation<br>(feet) | Discharge<br>(cfs) | Primary<br>(cfs) | Secondary<br>(cfs) |
|---------------------|--------------------|------------------|--------------------|---------------------|--------------------|------------------|--------------------|
| 58.65               | 0.00               | 0.00             | 0.00               | 61.25               | 15.17              | 8.30             | 6.87               |
| 58.70               | 0.01               | 0.01             | 0.00               | 61.30               | 15.72              | 8.41             | 7.31               |
| 58.75               | 0.03               | 0.03             | 0.00               | 61.35               | 16.27              | 8.51             | 7.76               |
| 58.80               | 0.08               | 0.08             | 0.00               | 61.40               | 16.84              | 8.61             | 8.22               |
| 58.85               | 0.14               | 0.14             | 0.00               | 61.45               | 17.40              | 8.71             | 8.69               |
| 58.90               | 0.21               | 0.21             | 0.00               | 61.50               | 17.97              | 8.81             | 9.16               |
| 58.95               | 0.30               | 0.30             | 0.00               | 61.55               | 18.54              | 8.91             | 9.63               |
| 59.00               | 0.40               | 0.40             | 0.00               | 61.60               | 19.12              | 9.01             | 10.11              |
| 59.05               | 0.51               | 0.51             | 0.00               | 61.65               | 19.70              | 9.11             | 10.59              |
| 59.10               | 0.64               | 0.64             | 0.00               | 61.70               | 20.28              | 9.20             | 11.08              |
| 59.15               | 0.77               | 0.77             | 0.00               | 61.75               | 20.86              | 9.30             | 11.56              |
| 59.20               | 0.92               | 0.92             | 0.00               | 61.80               | 21.44              | 9.39             | 12.05              |
| 59.25               | 1.08               | 1.08             | 0.00               | 61.85               | 22.02              | 9.48             | 12.54              |
| 59.30               | 1.24               | 1.24             | 0.00               | 61.90               | 22.59              | 9.57             | 13.02              |
| 59.35               | 1.42               | 1.42             | 0.00               | 61.95               | 23.17              | 9.66             | 13.50              |
| 59.40               | 1.60               | 1.60             | 0.00               | 62.00               | 23.74              | 9.75             | 13.98              |
| 59.45               | 1.80               | 1.80             | 0.00               | 62.05               | 24.30              | 9.84             | 14.46              |
| 59.50               | 1.99               | 1.99             | 0.00               | 62.10               | 24.86              | 9.93             | 14.93              |
| 59.55               | 2.20               | 2.20             | 0.00               | 62.15               | 25.41              | 10.02            | 15.39              |
| 59.60               | 2.41               | 2.41             | 0.00               | 62.20               | 25.95              | 10.11            | 15.85              |
| 59.65               | 2.62               | 2.62             | 0.00               | 62.25               | 26.48              | 10.19            | 16.29              |
| 59.70               | 2.84               | 2.84             | 0.00               | 62.30               | 27.00              | 10.28            | 16.72              |
| 59.75               | 3.06               | 3.06             | 0.00               | 62.35               | 27.50              | 10.36            | 17.14              |
| 59.80               | 3.28               | 3.28             | 0.00               | 62.40               | 27.98              | 10.45            | 17.54              |
| 59.85               | 3.50               | 3.50             | 0.00               | 62.45               | 28.44              | 10.53            | 17.91              |
| 59.90               | 3.72               | 3.72             | 0.00               | 62.50               | 28.87              | 10.61            | 18.26              |
| 59.95               | 3.94               | 3.94             | 0.00               | 62.55               | 29.28              | 10.69            | 18.58              |
| 60.00               | 4.15               | 4.15             | 0.00               | 62.60               | 29.63              | 10.77            | 18.86              |
| 60.05               | 4.37               | 4.36             | 0.02               | 62.65               | 29.92              | 10.86            | 19.06              |
| 60.10               | 4.62               | 4.55             | 0.06               | 62.70               | 30.36              | 10.94            | 19.43              |
| 60.15               | 4.88               | 4.74             | 0.14               | 62.75               | 30.95              | 11.01            | 19.93              |
| 60.20               | 5.16               | 4.91             | 0.25               | 62.80               | 31.39              | 11.09            | 20.29              |
| 60.25               | 5.45               | 5.06             | 0.39               | 62.85               | 31.75              | 11.17            | 20.57              |
| 60.30               | 5.72               | 5.17             | 0.55               | 62.90               | 32.10              | 11.25            | 20.85              |
| 60.35               | 6.11               | 5.36             | 0.74               | 62.95               | 32.45              | 11.33            | 21.12              |
| 60.40               | 6.59               | 5.62             | 0.96               | 63.00               | 32.80              | 11.40            | 21.39              |
| 60.45               | 7.08               | 5.87             | 1.21               | 63.05               | 33.14              | 11.48            | 21.66              |
| 60.50               | 7.59               | 6.11             | 1.48               | 63.10               | 33.48              | 11.56            | 21.92              |
| 60.55               | 8.11               | 6.34             | 1.76               | 63.15               | 33.81              | 11.63            | 22.18              |
| 60.60               | 8.61               | 6.57             | 2.04               | 63.20               | 34.14              | 11.71            | 22.44              |
| 60.65               | 9.12               | 6.78             | 2.34               | 63.25               | 34.47              | 11.78            | 22.69              |
| 60.70               | 9.64               | 6.99             | 2.65               | 63.30               | 34.80              | 11.85            | 22.94              |
| 60.75               | 10.15              | 7.18             | 2.97               | 63.35               | 35.12              | 11.93            | 23.19              |
| 60.80               | 10.60              | 7.30             | 3.31               | 63.40               | 35.44              | 12.00            | 23.43              |
| 60.85               | 11.07              | 7.42             | 3.66               | 63.45               | 35.75              | 12.07            | 23.68              |
| 60.90               | 11.55              | 7.53             | 4.02               | 63.50               | 36.06              | 12.15            | 23.92              |
| 60.95               | 12.04              | 7.65             | 4.40               | 63.55               | 36.37              | 12.22            | 24.16              |
| 61.00               | 12.54              | 7.76             | 4.78               | 63.60               | 36.68              | 12.29            | 24.39              |
| 61.05               | 13.05              | 7.87             | 5.18               | 63.65               | 36.98              | 12.36            | 24.62              |
| 61.10               | 13.57              | 7.98             | 5.59               | 63.70               | 37.29              | 12.43            | 24.86              |
| 61.15               | 14.10              | 8.09             | 6.01               | 63.75               | 37.58              | 12.50            | 25.08              |
| 61.20               | 14.63              | 8.20             | 6.43               | 63.80               | 37.88              | 12.57            | 25.31              |

Bypass  
@  
Primary  
> WQF

**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Discharge for Pond PDHM19: PDMH19 (continued)**

| Elevation<br>(feet) | Discharge<br>(cfs) | Primary<br>(cfs) | Secondary<br>(cfs) |
|---------------------|--------------------|------------------|--------------------|
| 63.85               | 38.18              | 12.64            | 25.54              |
| 63.90               | 38.47              | 12.71            | 25.76              |
| 63.95               | 38.76              | 12.78            | 25.98              |
| 64.00               | 39.04              | 12.84            | 26.20              |
| 64.05               | 39.33              | 12.91            | 26.42              |
| 64.10               | 39.61              | 12.98            | 26.63              |
| 64.15               | 39.89              | 13.05            | 26.85              |
| 64.20               | 40.17              | 13.11            | 27.06              |
| 64.25               | 40.45              | 13.18            | 27.27              |
| 64.30               | 40.72              | 13.25            | 27.48              |
| 64.35               | 41.00              | 13.31            | 27.69              |
| 64.40               | 41.27              | 13.38            | 27.89              |
| 64.45               | 41.54              | 13.44            | 28.10              |
| 64.50               | 41.81              | 13.51            | 28.30              |
| 64.55               | 42.07              | 13.57            | 28.50              |
| 64.60               | 42.34              | 13.64            | 28.70              |
| 64.65               | 42.60              | 13.70            | 28.90              |
| 64.70               | 42.86              | 13.76            | 29.10              |
| 64.75               | 43.12              | 13.83            | 29.29              |
| 64.80               | 43.38              | 13.89            | 29.49              |
| 64.85               | 43.63              | 13.95            | 29.68              |
| 64.90               | 43.89              | 14.01            | 29.87              |
| 64.95               | 44.14              | 14.08            | 30.06              |
| 65.00               | 44.39              | 14.14            | 30.25              |
| 65.05               | 44.64              | 14.20            | 30.44              |
| 65.10               | 44.89              | 14.26            | 30.63              |
| 65.15               | 45.14              | 14.32            | 30.82              |
| 65.20               | 45.38              | 14.38            | 31.00              |
| 65.25               | 45.63              | 14.44            | 31.18              |
| 65.30               | 45.87              | 14.50            | 31.37              |
| 65.35               | 46.11              | 14.56            | 31.55              |
| 65.40               | 46.35              | 14.62            | 31.73              |
| 65.45               | 46.59              | 14.68            | 31.91              |
| 65.50               | 46.83              | 14.74            | 32.09              |
| 65.55               | <b>47.07</b>       | <b>14.80</b>     | <b>32.27</b>       |



## GENERAL CALCULATIONS - WQV and WQF (optional worksheet)

This worksheet may be useful when designing a BMP **that does not fit into one of the specific worksheets already provided** (i.e. for a technology which is not a stormwater wetland, infiltration practice, etc.)

### Water Quality Volume (WQV)

|               |   |
|---------------|---|
| 4.14 ac       | A = Area draining to the practice                                     |
| 3.07 ac       | A <sub>i</sub> = Impervious area draining to the practice             |
| 0.74 decimal  | I = Percent impervious area draining to the practice, in decimal form |
| 0.72 unitless | R <sub>v</sub> = Runoff coefficient = 0.05 + (0.9 x I)                |
| 2.97 ac-in    | WQV = 1" x R <sub>v</sub> x A   |
| 10,781 cf     | WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")                       |

### Water Quality Flow (WQF)

|                               |  |
|-------------------------------|--|
| 1 inches                      | P = Amount of rainfall. For WQF in NH, P = 1".   |
| 0.72 inches                   | Q = Water quality depth. Q = WQV/A   |
| 97 unitless                   | CN = Unit peak discharge curve number. CN = 1000 / (10 + 5P + 10Q - 10 * [Q <sup>2</sup> + 1.25 * Q * P] <sup>0.5</sup> )          |
| 0.3 inches                    | S = Potential maximum retention. S = (1000/CN) - 10  |
| 0.059 inches                  | I <sub>a</sub> = Initial abstraction. I <sub>a</sub> = 0.2S  |
| 7.2 minutes                   | T <sub>c</sub> = Time of Concentration   |
| 630.0 cfs/mi <sup>2</sup> /in | q <sub>u</sub> is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III.                                   |
| 2.924 cfs                     | WQF = q <sub>u</sub> x WQV. Conversion: to convert "cfs/mi <sup>2</sup> /in * ac-in" to "cfs" multiply by 1mi <sup>2</sup> /640ac. |

Designer's Notes: POST 3.0 WATERSHED + POST 3.10 WATERSHED  
PJFF-2 AND PCDS-2

Pretreatment Device - Contech CDS Model 3030-6 (designed to treat maximum 3.0 cfs)

Treatment Device - Contech Jellyfish Filter Model JFPD0808-15-3 (designed to treat maximum 2.94 cfs)  
Upstream bypass pipe invert set to at least elevation of WQF (refer to stage-storage table)

**\*\*NOTE:** POST 3.10 Watershed represents an abutting lot (the Hampton Inn).

Pre-development, the drainage from this watershed connects to a shared water quality unit on the subject property. That water quality unit does not provide sufficient treatment to contemporary standards. Post-development, the drainage from this abutter is proposed to reconnect to the revised and upgraded stormwater system for sufficient treatment. However, the watershed area of POST 3.10 has been reduced to 30% of the total (for the sake of calculating applicable WQF only) as it represents an existing off-site area that meets the general "redevelopment" criteria listed under sections Env-Wq 1502.53 and Env-Wq 1507.03 (i)(1).

**CDS ESTIMATED NET ANNUAL TSS REDUCTION  
BASED ON THE RATIONAL RAINFALL METHOD**



**100 DURGIN LANE  
PORTSMOUTH, NH  
for SYSTEM: CDS 2**

|            |      |         |           |      |         |
|------------|------|---------|-----------|------|---------|
| Area       | 4.14 | acres   | CDS Model | 3030 |         |
| Weighted C | 0.74 |         | PSD       | 110  | microns |
| Tc         | 6    | minutes |           |      |         |

| Rainfall Intensity <sup>1</sup> (in/hr) | Percent Rainfall Volume <sup>1</sup> | Cumulative Rainfall Volume | Total Flowrate (cfs) | Treated Flowrate (cfs) | Removal Efficiency (%) | Incremental Removal (%) |
|---|--------------------------------------|----------------------------|----------------------|------------------------|------------------------|-------------------------|
| 0.02                                    | 13.0%                                | 13.0%                      | 0.06                 | 0.06                   | 100.0                  | 13.0                    |
| 0.04                                    | 12.2%                                | 25.2%                      | 0.12                 | 0.12                   | 100.0                  | 12.2                    |
| 0.06                                    | 11.2%                                | 36.4%                      | 0.18                 | 0.18                   | 99.9                   | 11.2                    |
| 0.08                                    | 10.0%                                | 46.4%                      | 0.25                 | 0.25                   | 99.4                   | 9.9                     |
| 0.10                                    | 8.2%                                 | 54.6%                      | 0.31                 | 0.31                   | 99.0                   | 8.2                     |
| 0.12                                    | 5.8%                                 | 60.4%                      | 0.37                 | 0.37                   | 98.5                   | 5.7                     |
| 0.14                                    | 6.5%                                 | 66.9%                      | 0.43                 | 0.43                   | 98.0                   | 6.4                     |
| 0.16                                    | 4.6%                                 | 71.5%                      | 0.49                 | 0.49                   | 97.5                   | 4.5                     |
| 0.18                                    | 3.7%                                 | 75.2%                      | 0.55                 | 0.55                   | 97.0                   | 3.6                     |
| 0.20                                    | 3.3%                                 | 78.5%                      | 0.61                 | 0.61                   | 96.5                   | 3.2                     |
| 0.25                                    | 6.7%                                 | 85.2%                      | 0.77                 | 0.77                   | 95.3                   | 6.4                     |
| 0.30                                    | 3.7%                                 | 88.9%                      | 0.92                 | 0.92                   | 94.1                   | 3.5                     |
| 0.35                                    | 2.4%                                 | 91.3%                      | 1.07                 | 1.07                   | 92.9                   | 2.2                     |
| 0.40                                    | 1.8%                                 | 93.1%                      | 1.23                 | 1.23                   | 91.7                   | 1.7                     |
| 0.45                                    | 1.9%                                 | 95.0%                      | 1.38                 | 1.38                   | 90.5                   | 1.8                     |
| 0.50                                    | 1.1%                                 | 96.1%                      | 1.53                 | 1.53                   | 89.3                   | 1.0                     |
| 0.75                                    | 2.6%                                 | 98.7%                      | 2.30                 | 2.30                   | 83.2                   | 2.2                     |
| 1.00                                    | 0.9%                                 | 99.6%                      | 3.06                 | 3.00                   | 76.0                   | 0.7                     |
| 1.50                                    | 0.4%                                 | 100.0%                     | 4.60                 | 3.00                   | 50.7                   | 0.2                     |
| 2.00                                    | 0.0%                                 | 100.0%                     | 6.13                 | 3.00                   | 38.0                   | 0.0                     |
|   |                                      |                            |                      |                        |                        | 97.3                    |

Removal Efficiency Adjustment<sup>2</sup> = 6.5%  
 Predicted % Annual Rainfall Treated = 93.4%

**Predicted Net Annual Load Removal Efficiency = 90.8%**

1 - Based on 10 years of hourly precipitation data from NCDC 1683, Concord WSO Airport, Merrimack County, NH

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.



# Jellyfish Filter Design Calculation

Contech Engineered Solutions, LLC Engineer:  
Date Prepared:

DRA  
9/9/2024

## Site Information

|                                      |                 |
|--------------------------------------|-----------------|
| Project Name                         | 100 Durgin Lane |
| Project City                         | Portsmouth      |
| Project State                        | NH              |
| Site Designation                     | JF 2            |
| Total Drainage Area, Ad              | 4.14 ac         |
| Post Development Impervious Area, Ai | 3.07 ac         |
| Pervious Area, Ap                    | 1.07 ac         |
| % Impervious                         | 74%             |
| Runoff Coefficient, Rc               | 0.72            |
| Upstream pretreatment credit         | 50%             |

## Mass Loading Calculations

|  |                         |
|--|-------------------------|
| Mean Annual Rainfall, P                    | 48 in                   |
| Agency Required % Removal                  | 80%                     |
| Percent Runoff Capture                     | 90%                     |
| Mean Annual Runoff, Vt                     | 465,744 ft <sup>3</sup> |
| Event Mean Concentration of Pollutant, EMC | 70 mg/l                 |
| Annual Mass Load, M total                  | 2,034 lbs               |

## Filter System

|                  |           |
|------------------|-----------|
| Filtration Brand | Jellyfish |
| Cartridge Length | 54 in     |

## Jellyfish Sizing

|   |           |
|---|-----------|
| Mass removed by pretreatment system     | 1,017 lbs |
| Mass load to filters after pretreatment | 1,017 lbs |
| Mass to be Captured by System           | 814 lbs   |
| Water Quality Flow                      | 2.924 cfs |

## Method to Use

FLOW BASED

| Summary |                       |               |
|---------|-----------------------|---------------|
|         | Treatment Flow Rate   | 2.94 cfs      |
| Flow    | Required Size         | JFPD0808-15-3 |
|         | Mass Capture provided | 2,064 lbs     |

**E-5071-001\_POST**

Prepared by Tighe & Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Discharge for Pond PDMH3: PDMH3**

| Elevation<br>(feet) | Discharge<br>(cfs) | Primary<br>(cfs) | Secondary<br>(cfs) | Elevation<br>(feet) | Discharge<br>(cfs) | Primary<br>(cfs) | Secondary<br>(cfs) |
|---------------------|--------------------|------------------|--------------------|---------------------|--------------------|------------------|--------------------|
| 59.35               | 0.00               | 0.00             | 0.00               | 61.95               | 19.38              | 8.30             | 11.08              |
| 59.40               | 0.01               | 0.01             | 0.00               | 62.00               | 20.14              | 8.41             | 11.74              |
| 59.45               | 0.03               | 0.03             | 0.00               | 62.05               | 20.92              | 8.51             | 12.41              |
| 59.50               | 0.08               | 0.08             | 0.00               | 62.10               | 21.71              | 8.61             | 13.09              |
| 59.55               | 0.13               | 0.13             | 0.00               | 62.15               | 22.51              | 8.71             | 13.79              |
| 59.60               | 0.21               | 0.21             | 0.00               | 62.20               | 23.32              | 8.81             | 14.50              |
| 59.65               | 0.29               | 0.29             | 0.00               | 62.25               | 24.14              | 8.91             | 15.23              |
| 59.70               | 0.39               | 0.39             | 0.00               | 62.30               | 24.97              | 9.01             | 15.96              |
| 59.75               | 0.50               | 0.50             | 0.00               | 62.35               | 25.81              | 9.11             | 16.71              |
| 59.80               | 0.63               | 0.63             | 0.00               | 62.40               | 26.67              | 9.20             | 17.47              |
| 59.85               | 0.76               | 0.76             | 0.00               | 62.45               | 27.53              | 9.30             | 18.23              |
| 59.90               | 0.91               | 0.91             | 0.00               | 62.50               | 28.40              | 9.39             | 19.01              |
| 59.95               | 1.07               | 1.07             | 0.00               | 62.55               | 29.28              | 9.48             | 19.80              |
| 60.00               | 1.23               | 1.23             | 0.00               | 62.60               | 30.17              | 9.57             | 20.59              |
| 60.05               | 1.41               | 1.41             | 0.00               | 62.65               | 31.06              | 9.66             | 21.40              |
| 60.10               | 1.59               | 1.59             | 0.00               | 62.70               | 31.96              | 9.75             | 22.21              |
| 60.15               | 1.78               | 1.78             | 0.00               | 62.75               | 32.87              | 9.84             | 23.03              |
| 60.20               | 1.98               | 1.98             | 0.00               | 62.80               | 33.79              | 9.93             | 23.86              |
| 60.25               | 2.18               | 2.18             | 0.00               | 62.85               | 34.71              | 10.02            | 24.69              |
| 60.30               | 2.39               | 2.39             | 0.00               | 62.90               | 35.63              | 10.11            | 25.53              |
| 60.35               | 2.61               | 2.61             | 0.00               | 62.95               | 36.56              | 10.19            | 26.37              |
| 60.40               | 2.82               | 2.82             | 0.00               | 63.00               | 37.49              | 10.28            | 27.22              |
| 60.45               | 3.04               | 3.04             | 0.00               | 63.05               | 38.43              | 10.36            | 28.07              |
| 60.50               | 3.26               | 3.26             | 0.00               | 63.10               | 39.37              | 10.45            | 28.92              |
| 60.55               | 3.50               | 3.48             | 0.02               | 63.15               | 40.31              | 10.53            | 29.78              |
| 60.60               | 3.78               | 3.70             | 0.08               | 63.20               | 41.25              | 10.61            | 30.64              |
| 60.65               | 4.09               | 3.91             | 0.17               | 63.25               | 42.19              | 10.69            | 31.50              |
| 60.70               | 4.43               | 4.13             | 0.31               | 63.30               | 43.13              | 10.77            | 32.36              |
| 60.75               | 4.81               | 4.33             | 0.48               | 63.35               | 44.07              | 10.86            | 33.22              |
| 60.80               | 5.22               | 4.53             | 0.69               | 63.40               | 45.01              | 10.94            | 34.07              |
| 60.85               | 5.64               | 4.72             | 0.93               | 63.45               | 45.94              | 11.01            | 34.93              |
| 60.90               | 6.07               | 4.88             | 1.19               | 63.50               | 46.88              | 11.09            | 35.78              |
| 60.95               | 6.49               | 5.03             | 1.46               | 63.55               | 47.80              | 11.17            | 36.63              |
| 61.00               | 6.89               | 5.14             | 1.75               | 63.60               | 48.72              | 11.25            | 37.47              |
| 61.05               | 7.40               | 5.33             | 2.07               | 63.65               | 49.64              | 11.33            | 38.31              |
| 61.10               | 7.99               | 5.59             | 2.41               | 63.70               | 50.55              | 11.40            | 39.14              |
| 61.15               | 8.60               | 5.83             | 2.77               | 63.75               | 51.44              | 11.48            | 39.96              |
| 61.20               | 9.22               | 6.07             | 3.15               | 63.80               | 52.33              | 11.56            | 40.78              |
| 61.25               | 9.85               | 6.30             | 3.55               | 63.85               | 53.21              | 11.63            | 41.58              |
| 61.30               | 10.49              | 6.52             | 3.97               | 63.90               | 54.07              | 11.71            | 42.37              |
| 61.35               | 11.15              | 6.74             | 4.41               | 63.95               | 54.92              | 11.78            | 43.14              |
| 61.40               | 11.82              | 6.94             | 4.87               | 64.00               | 55.75              | 11.85            | 43.90              |
| 61.45               | 12.50              | 7.14             | 5.35               | 64.05               | 56.57              | 11.93            | 44.64              |
| 61.50               | 13.14              | 7.30             | 5.85               | 64.10               | 57.36              | 12.00            | 45.36              |
| 61.55               | 13.78              | 7.42             | 6.36               | 64.15               | 58.13              | 12.07            | 46.06              |
| 61.60               | 14.43              | 7.53             | 6.89               | 64.20               | 58.87              | 12.15            | 46.73              |
| 61.65               | 15.09              | 7.65             | 7.44               | 64.25               | 59.58              | 12.22            | 47.37              |
| 61.70               | 15.77              | 7.76             | 8.01               | 64.30               | 60.26              | 12.29            | 47.97              |
| 61.75               | 16.46              | 7.87             | 8.59               | 64.35               | 60.89              | 12.36            | 48.53              |
| 61.80               | 17.17              | 7.98             | 9.19               | 64.40               | 61.48              | 12.43            | 49.05              |
| 61.85               | 17.90              | 8.09             | 9.80               | 64.45               | 61.99              | 12.50            | 49.49              |
| 61.90               | 18.63              | 8.20             | 10.43              | 64.50               | 62.35              | 12.57            | 49.78              |

Bypass  
@  
Primary  
> WQF

**E-5071-001\_POST**

Prepared by Tighe &amp; Bond

HydroCAD® 10.20-4b s/n 03437 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 50-Yr Rainfall=8.46"

Printed 8/26/2024

**Stage-Discharge for Pond PDMH3: PDMH3 (continued)**

| Elevation<br>(feet) | Discharge<br>(cfs) | Primary<br>(cfs) | Secondary<br>(cfs) |
|---------------------|--------------------|------------------|--------------------|
| 64.55               | 63.45              | 12.64            | 50.81              |
| 64.60               | 64.52              | 12.71            | 51.81              |
| 64.65               | 65.58              | 12.78            | 52.80              |
| 64.70               | 66.61              | 12.84            | 53.77              |
| 64.75               | 67.63              | 12.91            | 54.72              |
| 64.80               | 68.64              | 12.98            | 55.66              |
| 64.85               | 69.62              | 13.05            | 56.58              |
| 64.90               | 70.60              | 13.11            | 57.48              |
| 64.95               | 71.55              | 13.18            | 58.37              |
| 65.00               | 72.20              | 13.25            | 58.95              |
| 65.05               | 72.75              | 13.31            | 59.44              |
| 65.10               | 73.30              | 13.38            | 59.92              |
| 65.15               | 73.85              | 13.44            | 60.41              |
| 65.20               | 74.39              | 13.51            | 60.88              |
| 65.25               | 74.93              | 13.57            | 61.36              |
| 65.30               | 75.46              | 13.64            | 61.83              |
| 65.35               | 75.99              | 13.70            | 62.29              |
| 65.40               | 76.52              | 13.76            | 62.76              |
| 65.45               | 77.04              | 13.83            | 63.22              |
| 65.50               | <b>77.56</b>       | <b>13.89</b>     | <b>63.67</b>       |

## **Section 7**

# **Groundwater Recharge Volume Calculations**

As described in the following Groundwater Recharge Volume (GRV) worksheet, additional GRV is not required for this site per Env-Wq 1504.12 as impervious surfaces are reduced within a common hydrologic soil group (HSG). However, soil infiltration testing (included under Appendix B) within the areas proximate to each proposed rain garden shows that soils may allow for some level of infiltration. To remain conservative in the site design, infiltration was not claimed in the drainage model.





**Tighe&Bond**

**APPENDIX A**




United States  
Department of  
Agriculture

**NRCS**

Natural  
Resources  
Conservation  
Service

A product of the National  
Cooperative Soil Survey,  
a joint effort of the United  
States Department of  
Agriculture and other  
Federal agencies, State  
agencies including the  
Agricultural Experiment  
Stations, and local  
participants

# Custom Soil Resource Report for Rockingham County, New Hampshire



# Preface

---

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist ([http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2\\_053951](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951)).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

# Contents

---

|   |    |
|---|----|
| <b>Preface</b> .....  | 2  |
| <b>How Soil Surveys Are Made</b> .....                                  | 5  |
| <b>Soil Map</b> .....   | 8  |
| Soil Map.....   | 9  |
| Legend.....   | 10 |
| Map Unit Legend.....  | 11 |
| Map Unit Descriptions.....  | 11 |
| Rockingham County, New Hampshire.....                                   | 13 |
| 33A—Scitico silt loam, 0 to 5 percent slopes.....                       | 13 |
| 134—Maybid silt loam.....   | 14 |
| 140B—Chatfield-Hollis-Canton complex, 0 to 8 percent slopes, rocky..... | 15 |
| 699—Urban land.....   | 18 |
| 799—Urban land-Canton complex, 3 to 15 percent slopes.....              | 18 |
| <b>References</b> .....   | 21 |

# How Soil Surveys Are Made

---

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

## Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and



## Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

# Soil Map


---

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

# Custom Soil Resource Report Soil Map



Map Scale: 1:4,130 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 19N WGS84

### MAP LEGEND

**Area of Interest (AOI)**

 Area of Interest (AOI)

**Soils**

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

**Special Point Features**






-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features

**Water Features**

 Streams and Canals

**Transportation**

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Rockingham County, New Hampshire  
 Survey Area Data: Version 26, Aug 22, 2023

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 19, 2020—Sep 20, 2020

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

| Map Unit Symbol                    | Map Unit Name   | Acres in AOI | Percent of AOI |
|------------------------------------|---|--------------|----------------|
| 33A                                | Scitico silt loam, 0 to 5 percent slopes                      | 8.9          | 25.6%          |
| 134                                | Maybid silt loam  | 0.4          | 1.1%           |
| 140B                               | Chatfield-Hollis-Canton complex, 0 to 8 percent slopes, rocky | 23.0         | 66.0%          |
| 699                                | Urban land  | 1.6          | 4.5%           |
| 799                                | Urban land-Canton complex, 3 to 15 percent slopes             | 1.0          | 2.9%           |
| <b>Totals for Area of Interest</b> |   | <b>34.9</b>  | <b>100.0%</b>  |

## Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

## Custom Soil Resource Report

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

## Rockingham County, New Hampshire

### 33A—Scitico silt loam, 0 to 5 percent slopes

#### Map Unit Setting

*National map unit symbol:* 9cn6  
*Elevation:* 0 to 180 feet  
*Mean annual precipitation:* 47 to 49 inches  
*Mean annual air temperature:* 48 degrees F  
*Frost-free period:* 155 to 165 days  
*Farmland classification:* Farmland of local importance

#### Map Unit Composition

*Scitico and similar soils:* 85 percent  
*Minor components:* 15 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Scitico

##### Setting

*Landform:* Marine terraces

##### Typical profile

*H1 - 0 to 6 inches:* silt loam  
*H2 - 6 to 12 inches:* silty clay loam  
*H3 - 12 to 60 inches:* silty clay

##### Properties and qualities

*Slope:* 0 to 5 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Poorly drained  
*Runoff class:* High  
*Capacity of the most limiting layer to transmit water (Ksat):* Very low to moderately high (0.00 to 0.20 in/hr)  
*Depth to water table:* About 0 to 12 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Available water supply, 0 to 60 inches:* Moderate (about 7.9 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 4w  
*Hydrologic Soil Group:* C/D  
*Ecological site:* F144AY019NH - Wet Lake Plain  
*Hydric soil rating:* Yes

#### Minor Components

##### Maybid

*Percent of map unit:* 5 percent  
*Landform:* Marine terraces  
*Hydric soil rating:* Yes

##### Squamscott

*Percent of map unit:* 5 percent  
*Landform:* Marine terraces

## Custom Soil Resource Report

*Hydric soil rating:* Yes

### **Boxford**

*Percent of map unit:* 5 percent

*Hydric soil rating:* No

## **134—Maybid silt loam**

### **Map Unit Setting**

*National map unit symbol:* 9cmg

*Elevation:* 0 to 180 feet

*Mean annual precipitation:* 47 to 50 inches

*Mean annual air temperature:* 48 degrees F

*Frost-free period:* 155 to 165 days

*Farmland classification:* Not prime farmland

### **Map Unit Composition**

*Maybid and similar soils:* 75 percent

*Minor components:* 25 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

### **Description of Maybid**

#### **Setting**

*Landform:* Marine terraces

*Parent material:* Silty and clayey marine deposits

#### **Typical profile**

*H1 - 0 to 9 inches:* silt loam

*H2 - 9 to 26 inches:* silty clay loam

*H3 - 26 to 63 inches:* silty clay

#### **Properties and qualities**

*Slope:* 0 to 2 percent

*Depth to restrictive feature:* More than 80 inches

*Drainage class:* Very poorly drained

*Runoff class:* High

*Capacity of the most limiting layer to transmit water (Ksat):* Very low to moderately high (0.00 to 0.20 in/hr)

*Depth to water table:* About 0 to 6 inches

*Frequency of flooding:* None

*Frequency of ponding:* Frequent

*Available water supply, 0 to 60 inches:* Moderate (about 8.8 inches)

#### **Interpretive groups**

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 6w

*Hydrologic Soil Group:* C/D

*Ecological site:* F144AY020MA - Very Wet Coastal Lake Plain

*Hydric soil rating:* Yes



**Minor Components**

**Ossipee**

*Percent of map unit:* 10 percent  
*Landform:* Swamps  
*Hydric soil rating:* Yes

**Scitico**

*Percent of map unit:* 10 percent  
*Landform:* Marine terraces  
*Hydric soil rating:* Yes

**Not named wet**

*Percent of map unit:* 5 percent  
*Landform:* Marine terraces  
*Hydric soil rating:* Yes

**140B—Chatfield-Hollis-Canton complex, 0 to 8 percent slopes, rocky**

**Map Unit Setting**

*National map unit symbol:* 2w82m  
*Elevation:* 380 to 1,070 feet  
*Mean annual precipitation:* 36 to 71 inches  
*Mean annual air temperature:* 39 to 55 degrees F  
*Frost-free period:* 145 to 240 days  
*Farmland classification:* Not prime farmland

**Map Unit Composition**

*Chatfield, very stony, and similar soils:* 35 percent  
*Canton, very stony, and similar soils:* 25 percent  
*Hollis, very stony, and similar soils:* 25 percent  
*Minor components:* 15 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

**Description of Chatfield, Very Stony**

**Setting**

*Landform:* Hills, ridges  
*Landform position (two-dimensional):* Summit, shoulder, backslope  
*Landform position (three-dimensional):* Side slope, crest, nose slope  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear, convex  
*Parent material:* Coarse-loamy melt-out till derived from granite, gneiss, and/or schist

**Typical profile**

*O<sub>i</sub> - 0 to 1 inches:* slightly decomposed plant material  
*A - 1 to 2 inches:* fine sandy loam  
*B<sub>w</sub> - 2 to 30 inches:* gravelly fine sandy loam  
*2R - 30 to 40 inches:* bedrock

## Custom Soil Resource Report

### Properties and qualities

*Slope:* 0 to 8 percent  
*Surface area covered with cobbles, stones or boulders:* 1.6 percent  
*Depth to restrictive feature:* 20 to 41 inches to lithic bedrock  
*Drainage class:* Well drained  
*Runoff class:* High  
*Capacity of the most limiting layer to transmit water (Ksat):* Very low (0.00 to 0.00 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Maximum salinity:* Nonsaline (0.0 to 1.9 mmhos/cm)  
*Available water supply, 0 to 60 inches:* Low (about 4.3 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 6s  
*Hydrologic Soil Group:* B  
*Ecological site:* F144AY034CT - Well Drained Till Uplands  
*Hydric soil rating:* No

### Description of Canton, Very Stony

#### Setting

*Landform:* Ridges, hills, moraines  
*Landform position (two-dimensional):* Summit, shoulder, backslope  
*Landform position (three-dimensional):* Side slope, crest, nose slope  
*Down-slope shape:* Convex, linear  
*Across-slope shape:* Convex  
*Parent material:* Coarse-loamy over sandy melt-out till derived from gneiss, granite, and/or schist

#### Typical profile

*O<sub>i</sub> - 0 to 2 inches:* slightly decomposed plant material  
*A - 2 to 5 inches:* fine sandy loam  
*Bw<sub>1</sub> - 5 to 16 inches:* fine sandy loam  
*Bw<sub>2</sub> - 16 to 22 inches:* gravelly fine sandy loam  
*2C - 22 to 67 inches:* gravelly loamy sand

### Properties and qualities

*Slope:* 0 to 8 percent  
*Surface area covered with cobbles, stones or boulders:* 1.6 percent  
*Depth to restrictive feature:* 19 to 39 inches to strongly contrasting textural stratification  
*Drainage class:* Well drained  
*Runoff class:* Low  
*Capacity of the most limiting layer to transmit water (Ksat):* Moderately low to high (0.14 to 14.17 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Maximum salinity:* Nonsaline (0.0 to 1.9 mmhos/cm)  
*Available water supply, 0 to 60 inches:* Low (about 3.4 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified

## Custom Soil Resource Report

*Land capability classification (nonirrigated):* 6s  
*Hydrologic Soil Group:* B  
*Ecological site:* F144AY034CT - Well Drained Till Uplands  
*Hydric soil rating:* No

### Description of Hollis, Very Stony

#### Setting

*Landform:* Hills, ridges  
*Landform position (two-dimensional):* Summit, shoulder, backslope  
*Landform position (three-dimensional):* Side slope, crest, nose slope  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear, convex  
*Parent material:* Coarse-loamy melt-out till derived from granite, gneiss, and/or schist

#### Typical profile

*O<sub>i</sub> - 0 to 2 inches:* slightly decomposed plant material  
*A - 2 to 7 inches:* gravelly fine sandy loam  
*B<sub>w</sub> - 7 to 16 inches:* gravelly fine sandy loam  
*2R - 16 to 26 inches:* bedrock

#### Properties and qualities

*Slope:* 0 to 8 percent  
*Surface area covered with cobbles, stones or boulders:* 1.6 percent  
*Depth to restrictive feature:* 8 to 23 inches to lithic bedrock  
*Drainage class:* Somewhat excessively drained  
*Runoff class:* Very high  
*Capacity of the most limiting layer to transmit water (K<sub>sat</sub>):* Very low (0.00 to 0.00 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Maximum salinity:* Nonsaline (0.0 to 1.9 mmhos/cm)  
*Available water supply, 0 to 60 inches:* Very low (about 2.7 inches)

#### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 6s  
*Hydrologic Soil Group:* D  
*Ecological site:* F144AY033MA - Shallow Dry Till Uplands  
*Hydric soil rating:* No

### Minor Components

#### Freetown

*Percent of map unit:* 5 percent  
*Landform:* Swamps, kettles, bogs, depressions, marshes  
*Down-slope shape:* Concave  
*Across-slope shape:* Concave  
*Hydric soil rating:* Yes

#### Newfields, very stony

*Percent of map unit:* 5 percent  
*Landform:* Moraines, hills, ground moraines  
*Landform position (two-dimensional):* Footslope  
*Landform position (three-dimensional):* Base slope

## Custom Soil Resource Report

*Down-slope shape:* Linear  
*Across-slope shape:* Concave  
*Hydric soil rating:* No

### **Walpole, very stony**

*Percent of map unit:* 3 percent  
*Landform:* Outwash terraces, depressions, outwash plains, depressions, deltas  
*Landform position (three-dimensional):* Tread  
*Down-slope shape:* Concave  
*Across-slope shape:* Concave  
*Hydric soil rating:* Yes

### **Rock outcrop**

*Percent of map unit:* 2 percent  
*Landform:* Hills, ridges  
*Hydric soil rating:* Unranked

## **699—Urban land**

### **Map Unit Composition**

*Urban land:* 85 percent  
*Minor components:* 15 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

### **Minor Components**

#### **Not named**

*Percent of map unit:* 15 percent  
*Hydric soil rating:* No

## **799—Urban land-Canton complex, 3 to 15 percent slopes**

### **Map Unit Setting**

*National map unit symbol:* 9cq0  
*Elevation:* 0 to 1,000 feet  
*Mean annual precipitation:* 42 to 46 inches  
*Mean annual air temperature:* 45 to 48 degrees F  
*Frost-free period:* 120 to 160 days  
*Farmland classification:* Not prime farmland

### **Map Unit Composition**

*Urban land:* 55 percent  
*Canton and similar soils:* 20 percent  
*Minor components:* 25 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

## Description of Canton

### Setting

*Parent material:* Till

### Typical profile

*H1 - 0 to 5 inches:* gravelly fine sandy loam

*H2 - 5 to 21 inches:* gravelly fine sandy loam

*H3 - 21 to 60 inches:* loamy sand

### Properties and qualities

*Slope:* 3 to 8 percent

*Depth to restrictive feature:* More than 80 inches

*Drainage class:* Well drained

*Runoff class:* Low

*Capacity of the most limiting layer to transmit water (Ksat):* High (2.00 to 6.00 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Available water supply, 0 to 60 inches:* Low (about 5.3 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 2e

*Hydrologic Soil Group:* A

*Ecological site:* F144AY034CT - Well Drained Till Uplands

*Hydric soil rating:* No

## Minor Components

### Udorthents

*Percent of map unit:* 5 percent

*Hydric soil rating:* No

### Boxford and eldridge

*Percent of map unit:* 4 percent

*Hydric soil rating:* No

### Squamscott and scitico

*Percent of map unit:* 4 percent

*Landform:* Marine terraces

*Hydric soil rating:* Yes

### Scituate and newfields

*Percent of map unit:* 4 percent

*Hydric soil rating:* No

### Chatfield

*Percent of map unit:* 4 percent

*Hydric soil rating:* No

### Walpole

*Percent of map unit:* 4 percent

*Landform:* Depressions

*Hydric soil rating:* Yes

## Custom Soil Resource Report

# References

---

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_054262](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262)
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053577](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577)
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053580](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580)
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2\\_053374](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374)
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

## Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\\_054242](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242)


United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053624](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624)

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. [http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_052290.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf)



**Tighe&Bond**


**APPENDIX B**



GOVE ENVIRONMENTAL SERVICES, INC

**SITE-SPECIFIC SOIL SURVEY REPORT**

For  
100 Durgin Lane, Portsmouth, NH  
By  
GES, Inc.  
Project # 2023156  
Date:



**1. MAPPING STANDARDS**

*Site-Specific Soil Mapping Standards for New Hampshire and Vermont*. SSSNNE Special Publication No. 3, Version 7.0, July, 2021.

This map product is within the technical standards of the National Cooperative Soil Survey. It is a special purpose product, intended for infiltration requirements by the NH DES Alteration of Terrain Bureau. The soil map was produced by a professional soil scientist and is not a product of the USDA Natural Resources Conservation Service. This report accompanies the soil map.

The site-specific soil map (SSSM) was produced 05-06-24; prepared by JP Gove, CSS #004, GES, Inc.

Soils were identified with the New Hampshire State-wide Numerical Soils Legend, USDA NRCS, Durham, NH. Issue # 10, January 2011.

Hydrologic Soil Group was determined using SSSNNE Special Publication No. 5, Ksat Values for New Hampshire Soils, September 2009.

High Intensity Soil Map symbols, based upon SSSNNE Special Publication 1, December 2017, were added to the Soil Legend.

Scale of soil map: Approximately 1" = 40'.

Contours Interval: 2 feet

**2. LANDFORMS & EXISTING CONDITIONS:**

The site is located on a flat commercial site covered with buildings and pavement, or previous surfaces are fill with the exception of the wetlands and one glacial till hill. The purpose of this soil survey is to characterize the soil conditions that lay below the pavement or buildings. A combination of test pits and borings were used to prepare the subsurface soil map.

**3. DATE SOIL MAP PRODUCED**

Date(s) of on-site field work: 3-22-24 and 4-30-24  
Date(s) of test pits: 4-30-24 (test pits) and November-December of 2023 (borings)  
Test pits recorded by: Test pits recorded by James Gove and boring by S. W. Cole Engineering, Inc.

**4. GEOGRAPHIC LOCATION AND SIZE OF SITE**

City or town where soil mapping was conducted: Portsmouth  
Location: 100 Durgin Lane  
Size of area: Approximately 23 acres  
Was the map for the entire lot? No  
If no, where was the mapping conducted on the parcel: The area of proposed redevelopment

**5. PURPOSE OF THE SOIL MAP**

Was the map prepared to meet the requirement of Alteration of Terrain? Yes  
If no, what was the purpose of the map? N/A  
Who was the map prepared for? Tighe & Bond



**6. SOIL IDENTIFICATION LEGEND**

| Map Unit Symbol | Map Unit Name   | HISS Symbol | Hydrologic Soil Group |
|-----------------|---|-------------|-----------------------|
| 42              | Canton fine sandy loam  | 221         | B                     |
| 33              | Scitico silt loam   | 353         | C                     |
| 299caabb        | Udorthents, smoothed<br>c=well drained, a=no natural soil within 60", a=no restrictive layer, b=moderate Ksat,<br>b=Group B | 261         | B                     |
| 500dcabb        | Udorthents, loamy<br>d=moderately well drained, c=glacial till, a=no restrictive layer, b=moderate Ksat,<br>b=Group B       | 361         | B                     |

**SLOPE PHASE:**

|         |   |       |   |        |   |
|---------|---|-------|---|--------|---|
| 0-8%    | B | 8-15% | C | 15-25% | D |
| 25%-50% | E | 50%+  | F |        |   |

**7. NARRATIVE MAP UNIT DESCRIPTIONS**

SITE-SPECIFIC MAP UNIT: 42

CORRELATED SOIL SERIES: Canton fine sandy loam

LANDSCAPE SETTING: Glacial till hill

CHARACTERISTIC SURFACE FEATURES: Forested and gently sloping

DRAINAGE CLASS: Well drained

PARENT MATERIAL: Loose glacial till

NATURE OF DISSIMILAR INCLUSIONS: Moderately well drained and grading.

ESTIMATED PERCENTAGE OF DISSIMILAR INCLUSIONS: 5%

SOIL PROFILE DESCRIPTIONS- horizon designation, depth, soil texture, Munsell color notation, Munsell color of redox features, soil structure, soil consistence, estimated coarse fragments, estimated seasonal high water table (ESHWT), observed water table (OBSWT), kind of water table (perched, apparent, or both), depth to lithic or paralithic contact:

A, 0-10", fine sandy loam, 10YR3/2, granular, friable, 10% gravel.

B, 10-36", fine sandy loam, 10YR4/6, granular, friable, 10% gravel.

C, 36-48", loamy sand, 2.5Y5/4, massive, friable, 10% gravel. No observed ESHWT, no observed OBSWT, kind of water table not determined, no lithic contact.

SITE-SPECIFIC MAP UNIT: 299caabb

CORRELATED SOIL SERIES: Udorthents, smoothed

LANDSCAPE SETTING: Under pavement or buildings

CHARACTERISTIC SURFACE FEATURES: Flat impervious or pervious graded edges

DRAINAGE CLASS: Well drained

PARENT MATERIAL: No natural soils in 60", but material is glacial till

NATURE OF DISSIMILAR INCLUSIONS: Sloping areas, bedrock, and created basins

ESTIMATED PERCENTAGE OF DISSIMILAR INCLUSIONS: 10%

SOIL PROFILE DESCRIPTIONS- horizon designation, depth, soil texture, Munsell color notation, Munsell color of redox features, soil structure, soil consistence, estimated coarse fragments, estimated seasonal high water table (ESHWT), observed water table (OBSWT), kind of water table (perched, apparent, or both), depth to lithic or paralithic contact:

Fill, 0-48, gravelly loamy sand, 10YR4/6, massive, friable, 20% gravel and stones, no ESHWT and no OBSWT, no kind of water table determined, no lithic.



SITE-SPECIFIC MAP UNIT: 500dcabb

CORRELATED SOIL SERIES: Udorthents, loamy

LANDSCAPE SETTING: Transition from pavement to wetlands.

CHARACTERISTIC SURFACE FEATURES: Forested or fields, and gently sloping

DRAINAGE CLASS: Moderately well drained

PARENT MATERIAL: Glacial till, graded and filled

NATURE OF DISSIMILAR INCLUSIONS: Well drained and natural.

ESTIMATED PERCENTAGE OF DISSIMILAR INCLUSIONS: 5%

SOIL PROFILE DESCRIPTIONS- horizon designation, depth, soil texture, Munsell color notation, Munsell color of redox features, soil structure, soil consistence, estimated coarse fragments, estimated seasonal high water table (ESHWT), observed water table (OBSWT), kind of water table (perched, apparent, or both), depth to lithic or paralithic contact:

Fill 1, 0-36", gravelly loamy sand, 10YR4/6, massive, friable, 20% gravel.

Fill 2, 36-48", gravelly loamy sand, 10YR4/6, 2.5Y5/3 redox, massive, friable, 20% gravel. 36" ESHWT, no OBSWT, kind of water table is perched, no lithic contact.

## 8. RESPONSIBLE SOIL SCIENTIST

Name: James Gove


Certified Soil Scientist Number: 004

## 9. OTHER DISTINGUISHING FEATURES OF SITE

Is the site in a natural condition? Virtually none

If no, what is the nature of the disturbance? Filled, leveled, graded and paved.





**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**


100 DURGIN  
LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE

| MARK                 | DATE                | DESCRIPTION |
|----------------------|---------------------|-------------|
| PROJECT NO:          | E5071-001           |             |
| DATE:                | 5/6/2024            |             |
| FILE:                | E5071-001-HYDRO.dwg |             |
| DRAWN BY:            | BKC/NHW             |             |
| DESIGNED/CHECKED BY: | NAH                 |             |
| APPROVED BY:         | PMC                 |             |

**SITE-SPECIFIC  
SOIL SURVEY PLAN**

SCALE: AS SHOWN



**LEGEND**


- SITE-SPECIFIC SOIL SURVEY BOUNDARIES
- TEST PIT LOCATION
- ⊕ INFILTRATION TEST LOCATION

This map product is within the technical standards of the National Cooperative Soil Survey. It is a special purpose product, intended for infiltration requirements by the NH DES Alteration of Terrain Bureau. It was produced by a professional soil scientist, and is not a product of the USDA Natural Resources Conservation Service. There is a report that accompanies this map.

The site specific soil map was produced 5-6-2024, and was prepared by James P. Gove, CSS # 004, Gove Environmental Services, Inc.


**SOIL IDENTIFICATION LEGEND**

| Map Unit Symbol  | Map Unit Name          | HISS Symbol | Hydrologic Soil Group |
|--|------------------------|-------------|-----------------------|
| 42   | Canton fine sandy loam | 221         | B                     |
| 33   | Scitico silt loam      | 353         | C                     |
| 299caabb   | Udortheents, smoothed  | 261         | B                     |
| c=well drained, a=no natural soil within 60", a=no restrictive layer, b=moderate Ksat, b=Group B |                        |             |                       |
| 500dcabb   | Udortheents, loamy     | 361         | B                     |
| d=moderately well drained, c=glacial till, a=no restrictive layer, b=moderate Ksat, b=Group B    |                        |             |                       |
| <b>SLOPE PHASE:</b>  |                        |             |                       |
| 0-8%   | B                      | 8-15%       | C                     |
|  |                        | 15-25%      | D                     |
| 25%-50%  | E                      | 50%+        | F                     |



Last Saved: 6/13/2024 2:34pm By: ECurcio  
 Plotted On: Jun 14, 2024 2:34pm  
 Tighe & Bond \Vigheand.com\data\Projects\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane Drawings\AutoCAD\Sheet\E5071-001-HYDRO.dwg





GOVE ENVIRONMENTAL SERVICES, INC.

TEST PIT DATA

Project 100 Durgin Lane, Portsmouth, NH
Client Eastern
GES Project No. 2023156
MM/DD/YY Staff 04-30-2024 James Gove, CSS#004

Test Pit No. 1
ESHWT:: None
Termination @ 40"
Refusal: 40"
Obs. Water: None
Soils Series: Udorthents (made land)
Landscape: Commercial site
Slope: Flat
Parent Material: Rocky fill
Hydrologic Soil Group: B


Horizon Color (Munsell) Texture Structure-Consistence-Redox
F 0-40" 10YR4/4 rocky loamy sand massive-friable-none

Dark shale bedrock at 40". Would be similar to the Chatfield soil series.

Test Pit No. 2
ESHWT:: None
Termination @ 45"
Refusal: 45"
Obs. Water: None
Soils Series: Udorthents (made land)
Landscape: Commercial site
Slope: Flat
Parent Material: Rocky fill
Hydrologic Soil Group: B

Horizon Color (Munsell) Texture Structure-Consistence-Redox
F 0-45" 10YR4/3 rocky loamy sand massive-friable-none

Shale bedrock at 45". White pipe was exposed but no broken. Would be similar to thee Chatfield soil series.





Test pit #2

|                     |          |                        |                        |
|---------------------|----------|------------------------|------------------------|
| <b>Test Pit No.</b> | <b>3</b> | Soils Series:          | Udorthents (made land) |
| ESHWT::             | None     | Landscape:             | Commercial site        |
| Termination @       | 48"      | Slope:                 | Flat                   |
| Refusal:            | None     | Parent Material:       | Rocky fill             |
| Obs. Water:         | None     | Hydrologic Soil Group: | B                      |

| Horizon | Color (Munsell) | Texture          | Structure-Consistence-Redox |
|---------|-----------------|------------------|-----------------------------|
| F 0-48" | 10YR4/6         | rocky loamy sand | massive-friable-none        |

Typical staging area of all fill from the rest of the site. Compacted surface. Buried construction debris. Rocks were angular, as if blasted during bedrock removal. Similar to the soil series Canton.



Test pit # 3.

|                     |          |                        |                        |
|---------------------|----------|------------------------|------------------------|
| <b>Test Pit No.</b> | <b>4</b> | Soils Series:          | Udorthents (made land) |
| ESHWT::             | None     | Landscape:             | Commercial site        |
| Termination @       | 48"      | Slope:                 | Flat                   |
| Refusal:            | None     | Parent Material:       | Rocky fill             |
| Obs. Water:         | None     | Hydrologic Soil Group: | B                      |

| Horizon   | Color (Munsell) | Texture          | Structure-Consistence-Redox |
|-----------|-----------------|------------------|-----------------------------|
| F1 0-24"  | 10YR4/6         | rocky loamy sand | massive-friable-none        |
| F2 24-48" | 2.5Y5/4         | gravelly sand    | massive- friable- none      |

Typical staging area. Bricks and pipe buried in profile. Similar to a Canton soil series.

|                     |          |                        |                        |
|---------------------|----------|------------------------|------------------------|
| <b>Test Pit No.</b> | <b>5</b> | Soils Series:          | Udorthents (made land) |
| ESHWT::             | None     | Landscape:             | Commercial site        |
| Termination @       | 48"      | Slope:                 | Flat                   |
| Refusal:            | None     | Parent Material:       | Rocky fill             |
| Obs. Water:         | None     | Hydrologic Soil Group: | B                      |

| Horizon   | Color (Munsell) | Texture          | Structure-Consistence-Redox |
|-----------|-----------------|------------------|-----------------------------|
| F1 0-16"  | 10YR3/2         | rocky loamy sand | massive-friable-none        |
| F2 16-48" | 10YR4/6         | rocky sandy loam | massive-friable-none        |

Many angular rocks, as if blasted during bedrock removal. Some boulders. Would be similar to the Canton soil series.

**Test pit #6 was not accessible. Too close to guard rail and fire hydrant.**

|                     |          |                        |                        |
|---------------------|----------|------------------------|------------------------|
| <b>Test Pit No.</b> | <b>7</b> | Soils Series:          | Udorthents (made land) |
| ESHWT::             | None     | Landscape:             | Commercial site        |
| Termination @       | 30"      | Slope:                 | Flat                   |
| Refusal:            | None     | Parent Material:       | Sandy fill             |
| Obs. Water:         | None     | Hydrologic Soil Group: | B                      |

| Horizon   | Color (Munsell) | Texture             | Structure-Consistence-Redox |
|-----------|-----------------|---------------------|-----------------------------|
| F 0-6"    | 10YR3/2         | gravelly loamy sand | massive-friable-none        |
| F2 6-18"  | 10YR5/6         | gravelly loamy sand | massive-friable-none        |
| F3 18-30" | 10YR5/6         | gravelly sand       | massive-friable-none        |

In created detention basin/gravel wetland. Stopped at fabric that was covering drainpipe. Drainpipe was perforated and surrounded by gravelly sand.



Test pit # 7

|                     |          |                        |                        |
|---------------------|----------|------------------------|------------------------|
| <b>Test Pit No.</b> | <b>8</b> | Soils Series:          | Udorthents (made land) |
| ESHWT::             | None     | Landscape:             | Commercial site        |
| Termination @       | 36"      | Slope:                 | Flat                   |
| Refusal:            | None     | Parent Material:       | Sandy fill             |
| Obs. Water:         | None     | Hydrologic Soil Group: | B                      |

| Horizon   | Color (Munsell) | Texture             | Structure-Consistence-Redox |
|-----------|-----------------|---------------------|-----------------------------|
| F 0-4"    | 10YR3/2         | sandy loam          | massive-friable-none        |
| F2 4-24"  | 10YR5/6         | gravelly loamy sand | massive- friable- none      |
| F3 24-36" | 10YR4/6         | gravelly sand       | massive-friable-none        |

Detention basin/gravel wetland. Stopped at perforated drainpipe.

|                     |          |                        |                        |
|---------------------|----------|------------------------|------------------------|
| <b>Test Pit No.</b> | <b>9</b> | Soils Series:          | Udorthents (made land) |
| ESHWT::             | None     | Landscape:             | Commercial site        |
| Termination @       | 48"      | Slope:                 | Flat                   |
| Refusal:            | None     | Parent Material:       | Rocky and sandy fill   |
| Obs. Water:         | None     | Hydrologic Soil Group: | B                      |

| Horizon   | Color (Munsell) | Texture          | Structure-Consistence-Redox |
|-----------|-----------------|------------------|-----------------------------|
| F 0-6"    | 10YR3/3         | gravelly sand    | massive-friable-none        |
| F2 6-24"  | 10YR5/6         | sand             | massive-friable- none       |
| F3 24-48" | 10YR4/4         | rocky loamy sand | massive-friable-none        |

Sandy rock-free fill placed over very rocky loamy sand fill.

|                     |           |                        |                        |
|---------------------|-----------|------------------------|------------------------|
| <b>Test Pit No.</b> | <b>10</b> | Soils Series:          | Udorthents (made land) |
| ESHWT::             | None      | Landscape:             | Commercial site        |
| Termination @       | 48"       | Slope:                 | Flat                   |
| Refusal:            | None      | Parent Material:       | Rocky fill             |
| Obs. Water:         | None      | Hydrologic Soil Group: | B                      |


| Horizon | Color (Munsell) | Texture          | Structure-Consistence-Redox |
|---------|-----------------|------------------|-----------------------------|
| F 0-48" | 10YR4/4         | rocky loamy sand | massive-friable-none        |

Dark shale angular rocks throughout. Buried pavement. Would be similar to the Canton soil series.

|                     |           |                        |                |
|---------------------|-----------|------------------------|----------------|
| <b>Test Pit No.</b> | <b>11</b> | Soils Series:          | Canton         |
| ESHWT::             | None      | Landscape:             | Forested area  |
| Termination @       | 48"       | Slope:                 | Gently sloping |
| Refusal:            | None      | Parent Material:       | Glacial till   |
| Obs. Water:         | None      | Hydrologic Soil Group: | B              |

| Horizon  | Color (Munsell) | Texture             | Structure-Consistence-Redox |
|----------|-----------------|---------------------|-----------------------------|
| A 0-10"  | 10YR3/2         | fine sandy loam     | granular-friable-none       |
| B 10-36" | 10YR5/6         | fine sandy loam     | granular-friable- none      |
| C 36-48" | 2.5Y5/4         | gravelly loamy sand | massive-friable- none       |

Only natural soil recorded.



GOVE ENVIRONMENTAL SERVICES, INC.


TEST PIT DATA

Project Durgin Lane, Portsmouth, NH  
Client Eastern Location: Proposed western detention area.  
GES Project No. 2023156  
MM/DD/YY Staff 05-22024 James Gove, CSS#004


|                     |                    |                        |                        |
|---------------------|--------------------|------------------------|------------------------|
| <b>Test Pit No.</b> | <b>Detention 1</b> | Soils Series:          | Udorthents (made land) |
| ESHWT::             | None               | Landscape:             | Slope off pavement     |
| Termination @       | 67"                | Slope:                 | D                      |
| Refusal:            | no                 | Parent Material:       | Fill over glacial till |
| Obs. Water:         | None               | Hydrologic Soil Group: | B                      |

| Horizon  | Color (Munsell) | Texture             | Structure-Consistence-Redox |
|----------|-----------------|---------------------|-----------------------------|
| ^A 0-48" | 10YR4/2         | sandy loam          | massive-friable-none        |
| C 48-67" | 10YR4/6         | channery sandy loam | massive-friable-none        |

C soil layer is from the Pennichuck soil series. Topsoil and subsoil was removed and replaced with fill (^A). Pennichuck is derived from a schist glacial till.



Notes: TP 6 tests were completed 1.1 ft above the proposed depth due to large stones/fragmented fill and could not auger the proper hole needed to complete the test at the proposed depth.



Notes: TP 8 tests were completed **ABOVE** the crushed gravel. Could not go any deeper as there was crushed gravel at 24-36in. Below the gravel was large stones/fragmented fill and could not auger the proper hole needed to complete the test at the proposed depth.

**INFILTRATION TEST  
LOCATIONS**





GOVE ENVIRONMENTAL SERVICES, INC.

Amoozemeter Data Sheet

Site: 100 Durgan Lane Portsmouth

Air Temp: 74°F

Project #: 2023156

Water Source: tap water

Date: 5/29/24

Soil Moisture Content %: \_\_\_\_\_

Water Depth in Hole (cm)

Performed By: BQ/MM

Initial: 15 cm

Horizon: Fill

Final: 11 cm

Soil Series: Udorthents (made land)

\* 15 cm e 4 min

Test Location: TP 6-1


Outflow Chamber(s): Small (1on) \_\_\_\_\_  
(20.0cm<sup>2</sup>)

Both (2on) X  
(105.0cm<sup>2</sup>)



**TP 6-1**

| Time Elapsed (min) | Water Level Change (cm) | Chamber Volume (cm <sup>3</sup> ) | min/hr    | Q     | H (cm) | A        | Ksat (cm/hr) | Ksat (in/hr) |
|--------------------|-------------------------|-----------------------------------|-----------|-------|--------|----------|--------------|--------------|
| 1                  | 1.6                     | 105                               | 0.0166667 | 10080 | 15     | 0.001056 | 10.64448     | 4.19074      |
| 2                  | 2.5                     | 105                               | 0.0166667 | 15750 | 15     | 0.001056 | 16.632       | 6.548031     |
| 3                  | 2.4                     | 105                               | 0.0166667 | 15120 | 15     | 0.001056 | 15.96672     | 6.28611      |
| 4                  | 2.1                     | 105                               | 0.0166667 | 13230 | 15     | 0.001056 | 13.97088     | 5.500346     |
| 5                  | 3.2                     | 105                               | 0.0166667 | 20160 | 15     | 0.001056 | 21.28896     | 8.38148      |
| Mean Ksat          |                         |                                   |           |       |        |          | 15.70061     | 6.181342     |
| Std Deviation      |                         |                                   |           |       |        |          | 3.896292     | 1.533973     |



Notes: Between minute 4 and 5 : water in hole washes out between rocks and drops out



Amoozemeter Data Sheet

Site: 100 Durgan Lane Portsmouth

Air Temp: 74°F

Project #: 2023156

Water Source: tap water

Date: 5/29/24

Soil Moisture Content %: \_\_\_\_\_

Water Depth in Hole (cm)

Performed By: BQ/MM

Initial: 15.0 cm

Horizon: Fill

Final: 15.0 cm

Soil Series: Udorthents (middle land)

Test Location: TP 6-2


Outflow Chamber(s): Small (10n) \_\_\_\_\_  
(20.0cm<sup>2</sup>)

Both (20n) X  
(105.0cm<sup>2</sup>)



| TP 6-2             |                         |                                   |           |      |        |          |               |              |          |
|--------------------|-------------------------|-----------------------------------|-----------|------|--------|----------|---------------|--------------|----------|
| Time Elapsed (min) | Water Level Change (cm) | Chamber Volume (cm <sup>3</sup> ) | min/hr    | Q    | H (cm) | A        | Ksat (cm/hr)  | Ksat (in/hr) |          |
| 1                  | 0.7                     | 105                               | 0.0166667 | 4410 | 15     | 0.001056 | 4.65696       | 1.833449     |          |
| 2                  | 0.7                     | 105                               | 0.0166667 | 4410 | 15     | 0.001056 | 4.65696       | 1.833449     |          |
| 3                  | 0.7                     | 105                               | 0.0166667 | 4410 | 15     | 0.001056 | 4.65696       | 1.833449     |          |
| 4                  | 0.7                     | 105                               | 0.0166667 | 4410 | 15     | 0.001056 | 4.65696       | 1.833449     |          |
| 5                  | 0.7                     | 105                               | 0.0166667 | 4410 | 15     | 0.001056 | 4.65696       | 1.833449     |          |
|                    |                         |                                   |           |      |        |          | Mean Ksat     | 4.65696      | 1.833449 |
|                    |                         |                                   |           |      |        |          | Std Deviation | 0            | 2.48E-16 |

Notes:



Amoozemeter Data Sheet

Site: 100 Durgan Lane Portsmouth

Air Temp: 74°F

Project #: 2023156

Water Source: tap water

Date: 5/29/24

Soil Moisture Content %: \_\_\_\_\_

Water Depth in Hole (cm)

Performed By: BQ/MM

Initial: 15 cm

Horizon: Fill

Final: 16 cm

Soil Series: Udorthents (made land)

Test Location: TP 6-3

Outflow Chamber(s): Small (10n) \_\_\_\_\_  
(20.0cm<sup>2</sup>)

Both (20n) X  
(105.0cm<sup>2</sup>)



| TP 6-3             |                         |                                   |           |      |        |          |               |              |          |
|--------------------|-------------------------|-----------------------------------|-----------|------|--------|----------|---------------|--------------|----------|
| Time Elapsed (min) | Water Level Change (cm) | Chamber Volume (cm <sup>3</sup> ) | min/hr    | Q    | H (cm) | A        | Ksat (cm/hr)  | Ksat (in/hr) |          |
| 1                  | 0.4                     | 105                               | 0.0166667 | 2520 | 15     | 0.001056 | 2.66112       | 1.047685     |          |
| 2                  | 0.3                     | 105                               | 0.0166667 | 1890 | 15     | 0.001056 | 1.99584       | 0.785764     |          |
| 3                  | 0.3                     | 105                               | 0.0166667 | 1890 | 15     | 0.001056 | 1.99584       | 0.785764     |          |
| 4                  | 0.3                     | 105                               | 0.0166667 | 1890 | 15     | 0.001056 | 1.99584       | 0.785764     |          |
| 5                  | 0.3                     | 105                               | 0.0166667 | 1890 | 15     | 0.001056 | 1.99584       | 0.785764     |          |
| 6                  | 0.3                     | 105                               | 0.0166667 | 1890 | 15     | 0.001056 | 1.99584       | 0.785764     |          |
| 7                  | 0.4                     | 105                               | 0.0166667 | 2520 | 16     | 0.000961 | 2.42172       | 0.953433     |          |
|                    |                         |                                   |           |      |        |          | Mean Ksat     | 2.10672      | 0.829417 |
|                    |                         |                                   |           |      |        |          | Std Deviation | 0.271599     | 0.106929 |

Notes:



Amoozemeter Data Sheet

Site: 100 Durgan Lane Portsmouth

Air Temp: 66°F

Project #: 2023156

Water Source: tap water

Date: 5/31/24

Soil Moisture Content %: \_\_\_\_\_

Water Depth in Hole (cm)

Performed By: BQ/MM

Initial: 15.0 cm

Horizon: Fill

Final: 15.0 cm

Soil Series: Udentents (made land)

Test Location: TP 8-1

Outflow Chamber(s): Small (1on) \_\_\_\_\_  
(20.0cm<sup>2</sup>)

Both (2on) X  
(105.0cm<sup>2</sup>)



| TP 8-1             |                         |                                   |           |      |        |          |                      |               |               |
|--------------------|-------------------------|-----------------------------------|-----------|------|--------|----------|----------------------|---------------|---------------|
| Time Elapsed (min) | Water Level Change (cm) | Chamber Volume (cm <sup>3</sup> ) | min/hr    | Q    | H (cm) | A        | Ksat (cm/hr)         | Ksat (in/hr)  |               |
| 1                  | 1                       | 105                               | 0.0166667 | 6300 | 15     | 0.001056 | 6.6528               | 2.6192        |               |
| 2                  | 1.1                     | 105                               | 0.0166667 | 6930 | 15     | 0.001056 | 7.3181               | 2.8811        |               |
| 3                  | 0.9                     | 105                               | 0.0166667 | 5670 | 15     | 0.001056 | 5.9875               | 2.3573        |               |
| 4                  | 1                       | 105                               | 0.0166667 | 6300 | 15     | 0.001056 | 6.6528               | 2.6192        |               |
| 5                  | 0.9                     | 105                               | 0.0166667 | 5670 | 15     | 0.001056 | 5.9875               | 2.3573        |               |
|                    |                         |                                   |           |      |        |          | <b>Mean Ksat</b>     | <b>6.5197</b> | <b>2.5668</b> |
|                    |                         |                                   |           |      |        |          | <b>Std Deviation</b> | <b>0.5566</b> | <b>0.2191</b> |

Notes:



GOVE ENVIRONMENTAL SERVICES, INC.

Amoozemeter Data Sheet

Site: 100 Durgan Lane Portsmouth

Air Temp: 66°F

Project #: 2023156

Water Source: tap water

Date: 5/31/24

Soil Moisture Content %: \_\_\_\_\_

Water Depth in Hole (cm)

Performed By: BQ/MM

Initial: 15.0 cm

Horizon: Fill

Final: 15.0 cm

Soil Series: Udorthents (made land)

Test Location: TP 8-2

Outflow Chamber(s): Small (10n) \_\_\_\_\_  
(20.0cm<sup>2</sup>)

Both (20n) X  
(105.0cm<sup>2</sup>)



| TP 8-2             |                         |                                   |           |      |        |          |                      |               |                 |
|--------------------|-------------------------|-----------------------------------|-----------|------|--------|----------|----------------------|---------------|-----------------|
| Time Elapsed (min) | Water Level Change (cm) | Chamber Volume (cm <sup>3</sup> ) | min/hr    | Q    | H (cm) | A        | Ksat (cm/hr)         | Ksat (in/hr)  |                 |
| 1                  | 1.4                     | 105                               | 0.0166667 | 8820 | 15     | 0.001056 | 9.3139               | 3.6669        |                 |
| 2                  | 1.4                     | 105                               | 0.0166667 | 8820 | 15     | 0.001056 | 9.3139               | 3.6669        |                 |
| 3                  | 1.4                     | 105                               | 0.0166667 | 8820 | 15     | 0.001056 | 9.3139               | 3.6669        |                 |
| 4                  | 1.4                     | 105                               | 0.0166667 | 8820 | 15     | 0.001056 | 9.3139               | 3.6669        |                 |
| 5                  | 1.3                     | 105                               | 0.0166667 | 8190 | 15     | 0.001056 | 8.6486               | 3.4050        |                 |
|                    |                         |                                   |           |      |        |          | <b>Mean Ksat</b>     | <b>9.1809</b> | <b>3.614513</b> |
|                    |                         |                                   |           |      |        |          | <b>Std Deviation</b> | <b>0.2975</b> | <b>0.1171</b>   |

Notes:



Amoozemeter Data Sheet

Site: 100 Durgan Lane Portsmouth

Air Temp: 66°F

Project #: 2023156

Water Source: tap water

Date: 5/31/24

Soil Moisture Content %: \_\_\_\_\_

Water Depth in Hole (cm)

Performed By: BQ/MM

Initial: 15.0 cm

Horizon: Fill

Final: 15.2 cm

Soil Series: Vdortherts (made land)

Test Location: TP 8-3

Outflow Chamber(s): Small (1on) \_\_\_\_\_  
(20.0cm<sup>2</sup>)

Both (2on) X  
(105.0cm<sup>2</sup>)



TP 8-3

| Time Elapsed (min)   | Water Level Change (cm) | Chamber Volume (cm <sup>3</sup> ) | min/hr    | Q     | H (cm) | A        | Ksat (cm/hr)   | Ksat (in/hr)  |
|----------------------|-------------------------|-----------------------------------|-----------|-------|--------|----------|----------------|---------------|
| 1                    | 2.2                     | 105                               | 0.0166667 | 13860 | 15     | 0.001056 | 14.6362        | 5.7623        |
| 2                    | 2.5                     | 105                               | 0.0166667 | 15750 | 15     | 0.001056 | 16.6320        | 6.5480        |
| 3                    | 2.2                     | 105                               | 0.0166667 | 13860 | 15     | 0.001056 | 14.6362        | 5.7623        |
| 4                    | 2.2                     | 105                               | 0.0166667 | 13860 | 15     | 0.001056 | 14.6362        | 5.7623        |
| 5                    | 2.3                     | 105                               | 0.0166667 | 14490 | 15.2   | 0.001056 | 15.3014        | 6.0242        |
| <b>Mean Ksat</b>     |                         |                                   |           |       |        |          | <b>15.1684</b> | <b>5.9718</b> |
| <b>Std Deviation</b> |                         |                                   |           |       |        |          | <b>0.8674</b>  | <b>0.3415</b> |

Notes:

**Tighe&Bond**

**APPENDIX C**

# Extreme Precipitation Tables

## Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

| Metadata for Point |   |
|--------------------|---|
| Smoothing          | Yes   |
| State              | New Hampshire   |
| Location           | Rockingham County, New Hampshire, United States           |
| Latitude           | 43.088 degrees North                                      |
| Longitude          | 70.798 degrees West                                       |
| Elevation          | 10 feet   |
| Date/Time          | Tue Mar 05 2024 16:41:17 GMT-0500 (Eastern Standard Time) |

### Extreme Precipitation Estimates

|       | 5min | 10min | 15min | 30min | 60min | 120min |       | 1hr  | 2hr  | 3hr  | 6hr  | 12hr  | 24hr  | 48hr  |       | 1day  | 2day  |
|-------|------|-------|-------|-------|-------|--------|-------|------|------|------|------|-------|-------|-------|-------|-------|-------|
| 1yr   | 0.26 | 0.40  | 0.50  | 0.65  | 0.81  | 1.04   | 1yr   | 0.70 | 0.98 | 1.21 | 1.56 | 2.02  | 2.65  | 2.91  | 1yr   | 2.35  | 2.80  |
| 2yr   | 0.32 | 0.50  | 0.62  | 0.81  | 1.02  | 1.30   | 2yr   | 0.88 | 1.18 | 1.51 | 1.93 | 2.48  | 3.20  | 3.55  | 2yr   | 2.83  | 3.42  |
| 5yr   | 0.37 | 0.58  | 0.73  | 0.97  | 1.24  | 1.60   | 5yr   | 1.07 | 1.46 | 1.88 | 2.42 | 3.13  | 4.05  | 4.56  | 5yr   | 3.59  | 4.38  |
| 10yr  | 0.41 | 0.64  | 0.81  | 1.11  | 1.44  | 1.88   | 10yr  | 1.24 | 1.72 | 2.22 | 2.88 | 3.73  | 4.85  | 5.50  | 10yr  | 4.29  | 5.29  |
| 25yr  | 0.47 | 0.75  | 0.96  | 1.32  | 1.76  | 2.32   | 25yr  | 1.52 | 2.13 | 2.75 | 3.61 | 4.71  | 6.15  | 7.07  | 25yr  | 5.44  | 6.80  |
| 50yr  | 0.53 | 0.85  | 1.09  | 1.52  | 2.05  | 2.73   | 50yr  | 1.77 | 2.51 | 3.26 | 4.29 | 5.63  | 7.36  | 8.54  | 50yr  | 6.52  | 8.22  |
| 100yr | 0.59 | 0.95  | 1.23  | 1.75  | 2.39  | 3.22   | 100yr | 2.06 | 2.95 | 3.86 | 5.11 | 6.73  | 8.82  | 10.33 | 100yr | 7.80  | 9.94  |
| 200yr | 0.66 | 1.08  | 1.40  | 2.01  | 2.78  | 3.78   | 200yr | 2.40 | 3.48 | 4.56 | 6.07 | 8.03  | 10.57 | 12.50 | 200yr | 9.35  | 12.02 |
| 500yr | 0.78 | 1.29  | 1.68  | 2.44  | 3.42  | 4.69   | 500yr | 2.95 | 4.33 | 5.68 | 7.62 | 10.14 | 13.43 | 16.08 | 500yr | 11.88 | 15.46 |

### Lower Confidence Limits

|       | 5min | 10min | 15min | 30min | 60min | 120min |       | 1hr  | 2hr  | 3hr  | 6hr  | 12hr | 24hr | 48hr  |       | 1day | 2day  |
|-------|------|-------|-------|-------|-------|--------|-------|------|------|------|------|------|------|-------|-------|------|-------|
| 1yr   | 0.23 | 0.36  | 0.44  | 0.59  | 0.73  | 0.89   | 1yr   | 0.63 | 0.87 | 0.92 | 1.32 | 1.66 | 2.22 | 2.49  | 1yr   | 1.97 | 2.40  |
| 2yr   | 0.31 | 0.49  | 0.60  | 0.81  | 1.00  | 1.19   | 2yr   | 0.86 | 1.16 | 1.37 | 1.82 | 2.34 | 3.05 | 3.44  | 2yr   | 2.70 | 3.31  |
| 5yr   | 0.35 | 0.54  | 0.67  | 0.92  | 1.17  | 1.40   | 5yr   | 1.01 | 1.37 | 1.61 | 2.13 | 2.74 | 3.78 | 4.18  | 5yr   | 3.34 | 4.02  |
| 10yr  | 0.38 | 0.59  | 0.73  | 1.02  | 1.32  | 1.60   | 10yr  | 1.14 | 1.56 | 1.81 | 2.40 | 3.07 | 4.36 | 4.85  | 10yr  | 3.86 | 4.67  |
| 25yr  | 0.44 | 0.67  | 0.83  | 1.18  | 1.56  | 1.90   | 25yr  | 1.34 | 1.86 | 2.10 | 2.78 | 3.56 | 4.68 | 5.89  | 25yr  | 4.14 | 5.66  |
| 50yr  | 0.48 | 0.73  | 0.91  | 1.31  | 1.76  | 2.17   | 50yr  | 1.52 | 2.12 | 2.35 | 3.10 | 3.97 | 5.29 | 6.80  | 50yr  | 4.68 | 6.54  |
| 100yr | 0.53 | 0.81  | 1.01  | 1.46  | 2.01  | 2.47   | 100yr | 1.73 | 2.42 | 2.63 | 3.45 | 4.40 | 5.94 | 7.86  | 100yr | 5.25 | 7.56  |
| 200yr | 0.59 | 0.89  | 1.13  | 1.63  | 2.27  | 2.82   | 200yr | 1.96 | 2.75 | 2.93 | 3.84 | 4.86 | 6.65 | 9.08  | 200yr | 5.88 | 8.73  |
| 500yr | 0.68 | 1.02  | 1.31  | 1.90  | 2.71  | 3.37   | 500yr | 2.34 | 3.29 | 3.40 | 4.40 | 5.56 | 7.72 | 10.98 | 500yr | 6.83 | 10.55 |

### Upper Confidence Limits

|       | 5min | 10min | 15min | 30min | 60min | 120min |       | 1hr  | 2hr  | 3hr  | 6hr  | 12hr  | 24hr  | 48hr  |       | 1day  | 2day  |
|-------|------|-------|-------|-------|-------|--------|-------|------|------|------|------|-------|-------|-------|-------|-------|-------|
| 1yr   | 0.28 | 0.44  | 0.54  | 0.72  | 0.89  | 1.08   | 1yr   | 0.76 | 1.06 | 1.25 | 1.75 | 2.21  | 2.99  | 3.14  | 1yr   | 2.64  | 3.02  |
| 2yr   | 0.33 | 0.52  | 0.64  | 0.86  | 1.06  | 1.26   | 2yr   | 0.92 | 1.24 | 1.48 | 1.96 | 2.51  | 3.42  | 3.68  | 2yr   | 3.02  | 3.54  |
| 5yr   | 0.40 | 0.61  | 0.76  | 1.04  | 1.33  | 1.61   | 5yr   | 1.15 | 1.58 | 1.88 | 2.53 | 3.24  | 4.32  | 4.93  | 5yr   | 3.82  | 4.74  |
| 10yr  | 0.46 | 0.71  | 0.88  | 1.24  | 1.60  | 1.96   | 10yr  | 1.38 | 1.92 | 2.27 | 3.10 | 3.93  | 5.32  | 6.16  | 10yr  | 4.71  | 5.92  |
| 25yr  | 0.57 | 0.87  | 1.08  | 1.54  | 2.02  | 2.55   | 25yr  | 1.75 | 2.49 | 2.94 | 4.05 | 5.11  | 7.75  | 8.27  | 25yr  | 6.86  | 7.95  |
| 50yr  | 0.66 | 1.01  | 1.26  | 1.80  | 2.43  | 3.09   | 50yr  | 2.10 | 3.02 | 3.57 | 4.97 | 6.25  | 9.70  | 10.36 | 50yr  | 8.58  | 9.96  |
| 100yr | 0.78 | 1.17  | 1.47  | 2.13  | 2.91  | 3.76   | 100yr | 2.52 | 3.67 | 4.34 | 6.11 | 7.66  | 12.13 | 12.98 | 100yr | 10.74 | 12.48 |
| 200yr | 0.91 | 1.37  | 1.73  | 2.50  | 3.49  | 4.58   | 200yr | 3.01 | 4.48 | 5.29 | 7.51 | 9.38  | 15.21 | 16.28 | 200yr | 13.46 | 15.65 |
| 500yr | 1.12 | 1.67  | 2.15  | 3.12  | 4.44  | 5.93   | 500yr | 3.83 | 5.80 | 6.86 | 9.91 | 12.30 | 20.54 | 21.96 | 500yr | 18.18 | 21.11 |





**Tighe&Bond**

**APPENDIX D**

| Coastal and Great Bay Region Precipitation Increase |                         |                               |
|---|-------------------------|-------------------------------|
|   | 24-hr Storm Event (in.) | 24-hr Storm Event + 15% (in.) |
| 1 Year  | 2.65                    | 3.05                          |
| 2 Year  | 3.20                    | 3.68                          |
| 10 Year   | 4.85                    | 5.58                          |
| 25 Year   | 6.15                    | 7.07                          |
| 50 Year   | 7.36                    | 8.46                          |
| 100 Year  | 8.82                    | 10.14                         |





Proposed Multi-Family Development  
100 Durgin Lane  
Portsmouth, NH

## Long-Term Operation & Maintenance Plan

100 Durgin Lane Owner, LLC

SEPTEMBER 18, 2024

**Tighe&Bond**

**Section 1 Long-Term Operation & Maintenance Plan**

1.1 Contact/Responsible Party .....1-1

1.2 Maintenance Items .....1-1

1.3 Overall Site Operation & Maintenance Schedule .....1-2

1.3.1 Disposal Requirements.....1-2

1.4 Rain Garden Maintenance Requirements .....1-3

1.5 Contech Jellyfish Filter System Maintenance Requirements.....1-4

1.6 Contech CDS Unit Maintenance Requirements.....1-5

1.7 Rip Rap Maintenance Requirements .....1-5

1.8 Snow & Ice Management for Standard Asphalt and Walkways.....1-5

**Section 2 Chloride Management Plan**

2.1 Background Information.....2-1

2.2 Operational Guidelines – Chloride Management.....2-1

2.2.1 Winter Operator Certification Requirements .....2-1

2.2.2 Improved Weather Monitoring.....2-2

2.2.3 Equipment Calibration Requirements .....2-2

2.2.4 Increased Mechanical Removal Capabilities.....2-2

2.3 Salt Usage Evaluation and Monitoring .....2-3

2.4 Summary .....2-3

**Section 3 Invasive Species**

**Section 4 Annual Updates and Log Requirements**

# **Section 1**

## **Long-Term Operation & Maintenance Plan**

It is the intent of this Operation and Maintenance Plan to identify the areas of this site that need special attention and consideration, as well as implementing a plan to assure routine maintenance. By identifying the areas of concern as well as implementing a frequent and routine maintenance schedule the site will maintain a high-quality stormwater runoff.

### **1.1 Contact/Responsible Party**

100 Durgin Lane Owner, LLC  
1 Marina Park Drive, Suite 1500  
Boston, MA 02210

(Note: The contact information for the Contact/Responsible Party shall be kept current. If ownership changes, the Operation and Maintenance Plan must be transferred to the new party.)

### **1.2 Maintenance Items**

Maintenance of the following items shall be recorded:

- Litter/Debris Removal
- Landscaping
- Catchbasin Cleaning
- Pavement Sweeping
- Rain Gardens
- Contech Jellyfish Filtration System
- Contech CDS Units
- Rip Rap Outlets

The following maintenance items and schedule represent the minimum action required. Periodic site inspections shall be conducted, and all measures must be maintained in effective operating condition. The following items shall be observed during site inspection and maintenance:

- Inspect vegetated areas, particularly slopes and embankments for areas of erosion. Replant and restore as necessary
- Inspect catch basins for sediment buildup
- Inspect site for trash and debris

### 1.3 Overall Site Operation & Maintenance Schedule

| Maintenance Item  | Frequency of Maintenance  |
|---|---|
| Litter/Debris Removal   | Weekly  |
| Pavement Sweeping<br>- Sweep impervious areas to remove sand and litter.                            | Annually  |
| Landscaping<br>- Landscaped islands to be maintained and mulched.                                   | Maintained as required and mulched each Spring                                      |
| Catch Basin (CB) Cleaning<br>- CB to be cleaned of solids and oils.                                 | Annually  |
| Rain Gardens<br>- Trash and debris to be removed.<br>- Any required maintenance shall be addressed. | Two (2) times annually<br>After any rainfall event exceeding 2.5" in a 24-hr period |
| Contech Jelly Fish Units  | In accordance with Manufacturer's Recommendations                                   |
| Contech CDS Units®  | In accordance with Manufacturer's Recommendations                                   |

#### 1.3.1 Disposal Requirements

Disposal of debris, trash, sediment and other waste material should be done at suitable disposal/recycling sites and in compliance with all applicable local, state and federal waste regulations.

### 1.4 Rain Garden Maintenance Requirements

| <b>Rain Garden Inspection/Maintenance Requirements</b>   |  |  |
|--|--|--|
| <b>Inspection/<br/>Maintenance</b>   | <b>Frequency</b>   | <b>Action</b>  |
| Monitor to ensure that Rain Gardens function effectively after storms                            | Two (2) times annually and after any rainfall event exceeding 2.5" in a 24-hr period | <ul style="list-style-type: none"> <li>- Trash and debris to be removed</li> <li>- Any required maintenance shall be addressed</li> </ul>  |
| Inspect Vegetation   | Annually   | <ul style="list-style-type: none"> <li>- Inspect the condition of all Rain Garden vegetation</li> <li>- Prune back overgrowth</li> <li>- Replace dead vegetation</li> <li>- Remove any invasive species</li> </ul>   |
| Inspect Drawdown Time<br>- The system shall drawdown within 48-hours following a rainfall event. | Annually   | <ul style="list-style-type: none"> <li>- Assess the condition of the facility to determine measures required to restore the filtration function, including but not limited to removal of accumulated sediments or reconstruction of the filter.</li> </ul> |



## 1.5 Contech Jellyfish Filter System Maintenance Requirements

| <b>Contech Jellyfish Filter System Inspection/Maintenance Requirements</b>            |   |  |
|---|---|--|
| <b>Inspection/<br/>Maintenance</b>  | <b>Frequency</b>  | <b>Action</b>  |
| Inspect vault for sediment build up, static water, plugged media and bypass condition | One (1) time annually and after any rainfall event exceeding 2.5" in a 24-hr period | Maintenance required for any of the following:<br>- >4" of sediment on the vault floor<br>- >1/4" of sediment on top of the cartridge<br>- .4" of static water above the cartridge bottom more than 24 hours after a rain event<br>- If pore space between media is absent.<br>- If vault is in bypass condition during an average rainfall event. |
| Replace Cartridges  | As required by inspection, 1-5 years.   | - Remove filter cartridges per manufacturer methods.<br>- Vacuum sediment from vault.<br>- Install new cartridges per manufacturer methods   |

### 1.6 Contech CDS Unit Maintenance Requirements

| Contech Cascade Separator® Inspection/Maintenance Requirements |  |  |
|--|--|--|
| Inspection/<br>Maintenance                                     | Frequency  | Action   |
| Visual Inspection  | Twice per year at a minimum<br>(spring and fall) | -Visually inspect for blockages or obstruction in the inlet chamber, flumes or outlet channel<br><br>- Sediment removal once 50% of maximum storage has been reached |

### 1.7 Rip Rap Maintenance Requirements

| Rip Rap Inspection/Maintenance Requirements |           |   |
|---|-----------|---|
| Inspection/<br>Maintenance                  | Frequency | Action  |
| Visual Inspection                           | Annually  | - Visually inspect for damage and deterioration<br>- Repair damages immediately |

### 1.8 Snow & Ice Management for Standard Asphalt and Walkways

Snow storage areas shall be located such that no direct untreated discharges are possible to receiving waters from the storage site (snow storage areas have been shown on the Site Plan). Salt storage areas shall be covered or located such that no direct untreated discharges are possible to receiving waters from the storage site. Salt and sand shall be used to the minimum extent practical (refer to the attached for de-icing application rate guideline from the New Hampshire Stormwater Management Manual, Volume 2,).

**Deicing Application Rate Guidelines**

24' of pavement (typical two-lane road)

These rates are not fixed values, but rather the middle of a range to be selected and adjusted by an agency according to its local conditions and experience.

| Pavement Temp. (°F) and Trend (↑↓) | Weather Condition     | Maintenance Actions                           | Pounds per two-lane mile                    |   |                 |                                    |
|------------------------------------|-----------------------|---|---|---|-----------------|------------------------------------|
|                                    |                       |   | Salt Prewetted / Pretreated with Salt Brine | Salt Prewetted / Pretreated with Other Blends | Dry Salt*       | Winter Sand (abrasives)            |
| > 30° ↑                            | Snow                  | Plow, treat intersections only                | 80  | 70  | 100*            | Not recommended                    |
|                                    | Freezing Rain         | Apply Chemical                                | 80 - 160                                    | 70 - 140                                      | 100 - 200*      | Not recommended                    |
| 30° ↓                              | Snow                  | Plow and apply chemical                       | 80 - 160                                    | 70 - 140                                      | 100 - 200*      | Not recommended                    |
|                                    | Freezing Rain         | Apply Chemical                                | 150 - 200                                   | 130 - 180                                     | 180 - 240*      | Not recommended                    |
| 25° - 30° ↑                        | Snow                  | Plow and apply chemical                       | 120 - 160                                   | 100 - 140                                     | 150 - 200*      | Not recommended                    |
|                                    | Freezing Rain         | Apply Chemical                                | 150 - 200                                   | 130 - 180                                     | 180 - 240*      | Not recommended                    |
| 25° - 30° ↓                        | Snow                  | Plow and apply chemical                       | 120 - 160                                   | 100 - 140                                     | 150 - 200*      | Not recommended                    |
|                                    | Freezing Rain         | Apply Chemical                                | 160 - 240                                   | 140 - 210                                     | 200 - 300*      | 400                                |
| 20° - 25° ↑                        | Snow or Freezing Rain | Plow and apply chemical                       | 160 - 240                                   | 140 - 210                                     | 200 - 300*      | 400                                |
| 20° - 25° ↓                        | Snow                  | Plow and apply chemical                       | 200 - 280                                   | 175 - 250                                     | 250 - 350*      | Not recommended                    |
|                                    | Freezing Rain         | Apply Chemical                                | 240 - 320                                   | 210 - 280                                     | 300 - 400*      | 400                                |
| 15° - 20° ↑                        | Snow                  | Plow and apply chemical                       | 200 - 280                                   | 175 - 250                                     | 250 - 350*      | Not recommended                    |
|                                    | Freezing Rain         | Apply Chemical                                | 240 - 320                                   | 210 - 280                                     | 300 - 400*      | 400                                |
| 15° - 20° ↓                        | Snow or Freezing Rain | Plow and apply chemical                       | 240 - 320                                   | 210 - 280                                     | 300 - 400*      | 500 for freezing rain              |
| 0° - 15° ↑↓                        | Snow                  | Plow, treat with blends, sand hazardous areas | Not recommended                             | 300 - 400                                     | Not recommended | 500 - 750 spot treatment as needed |
| < 0°                               | Snow                  | Plow, treat with blends, sand hazardous areas | Not recommended                             | 400 - 600**                                   | Not recommended | 500 - 750 spot treatment as needed |

\* Dry salt is not recommended. It is likely to blow off the road before it melts ice.

\*\* A blend of 6 - 8 gal/ton MgCl<sub>2</sub> or CaCl<sub>2</sub> added to NaCl can melt ice as low as -10°.

| Anti-icing Route Data Form             |                      |                   |           |     |
|--|----------------------|-------------------|-----------|-----|
| Truck Station:                         |                      |                   |           |     |
| Date:                                  |                      |                   |           |     |
| Air Temperature                        | Pavement Temperature | Relative Humidity | Dew Point | Sky |
| Reason for applying:                   |                      |                   |           |     |
| Route:                                 |                      |                   |           |     |
| Chemical:                              |                      |                   |           |     |
| Application Time:                      |                      |                   |           |     |
| Application Amount:                    |                      |                   |           |     |
| Observation (first day):               |                      |                   |           |     |
| Observation (after event):             |                      |                   |           |     |
| Observation (before next application): |                      |                   |           |     |
| Name:                                  |                      |                   |           |     |

## **Section 2**

# **Chloride Management Plan**

### **Winter Operational Guidelines**

The following Chloride Management Plan is for the 100 Durgin Lane - Multifamily Development in Portsmouth, New Hampshire. The Plan includes operational guidelines including: winter operator certification requirements, weather monitoring, equipment calibration requirements, mechanical removal, and salt usage evaluation and monitoring. Due to the evolving nature of chloride management efforts, the Chloride Management Plan will be reviewed annually, in advance of the winter season, to reflect the current management standards.

#### **2.1 Background Information**

The 100 Durgin Lane - Multifamily Development located within the Upper Hodgson Brook Watershed in Newington and Portsmouth, New Hampshire. The Upper Hodgson Brook is identified as a chloride-impaired waterbody.

#### **2.2 Operational Guidelines – Chloride Management**

All 100 Durgin Lane Owner LLC private contractors engaged at the 100 Durgin Lane premises for the purposes of winter operational snow removal and surface maintenance, are responsible for assisting in meeting compliance for the following protocols. 100 Durgin Lane Owner LLC private contractors are expected to minimize the effects of the use of de-icing, anti-icing and pretreatment materials by adhering to the strict guidelines outlined below.

The 100 Durgin Lane Owner LLC winter operational de-icing, anti-icing and pretreatment materials will adhere to the following protocols:

##### **2.2.1 Winter Operator Certification Requirements**

All private contractors engaged at the 100 Durgin Lane premises for the purpose of winter operational snow removal and surface maintenance must be current UNHT2 Green SnowPro Certified operators or equivalent and will use only pre-approved methods for spreading abrasives on private roadways and parking lots. All private contractors engaged at the 100 Durgin Lane premises for the purpose of winter operational snow removal and surface maintenance shall provide to 100 Durgin Lane Owner LLC management two copies of the annual UNHT2 Green SnowPro certificate or equivalent for each operator utilized on the 100 Durgin Lane premises. The annual UNHT2 Green SnowPro certificate or equivalent for each operator will be available on file in the 100 Durgin Lane Facilities Management office and be present in the vehicle/carrier at all times.

### **2.2.2 Improved Weather Monitoring**

100 Durgin Lane Owner LLC will coordinate weather information for use by winter maintenance contractors. This information in conjunction with site specific air/ground surface temperature monitoring will ensure that private contractors engaged at the 100 Durgin Lane premises for the purpose of winter operational snow removal and surface maintenance will make more informed decisions as to when and to what extent de-icing, anti-icing and pretreatment materials are applied to private roadways, sidewalks, and parking lots.

### **2.2.3 Equipment Calibration Requirements**

All equipment utilized on the 100 Durgin Lane premises for the purpose of winter operational snow removal and surface maintenance will conform to the following calibration requirements.

#### **2.2.3.1 Annual Calibration Requirements**

All private contractors engaged at the 100 Durgin Lane premises for the purpose of winter operational snow removal and surface maintenance shall provide two copies of the annual calibration report for each piece of equipment utilized on the 100 Durgin Lane premises. Each calibration report shall include the vehicle/carrier VIN number and the serial numbers for each component including, but not limited to, spreader control units, salt aggregate spreader equipment, brining/pre-wetting equipment, ground speed orientation unit, and air/ground surface temperature monitor. Annual calibration reports will be available on file in the 100 Durgin Lane Facilities Management office and be present in the vehicle/carrier at all times.

Prior to each use, each vehicle/carrier operator will perform a systems check to verify that unit settings remain within the guidelines established by the 100 Durgin Lane Owner LLC Management Team in order to accurately dispense material. All private contractors engaged at the 100 Durgin Lane premises for the purpose of winter operational snow removal and surface maintenance will be subject to spot inspections by members of the 100 Durgin Lane Owner LLC Management Team to ensure that each vehicle/carrier is operating in a manner consistent with the guidelines set herein or State and Municipal regulations. All units will be recalibrated, and the updated calibration reports will be provided each time repairs or maintenance procedures affect the hydraulic system of the vehicle/carrier.

### **2.2.4 Increased Mechanical Removal Capabilities**

All private contractors engaged at the 100 Durgin Lane premises will endeavor to use mechanical removal means on a more frequent basis for roadways, parking lots and sidewalks. Dedicating more manpower and equipment to increase snow removal frequencies prevents the buildup of snow and the corresponding need for de-icing, anti-icing and pretreatment materials. Shortened maintenance

routes, with shorter service intervals, will be used to stay ahead of snowfall. Minimized snow and ice packing will reduce the need for abrasives, salt aggregates, and/or brining solution to restore surfaces back to bare surface states after winter precipitation events.

After storm events the 100 Durgin Lane Owner LLC management team will be responsible for having the streets swept to recapture un-melted de-icing materials, when practical.

## **2.3 Salt Usage Evaluation and Monitoring**

All private contractors engaged at the 100 Durgin Lane premises for the purpose of winter operational snow removal and surface maintenance shall provide two copies of a storm report, which includes detailed information regarding treatment areas and the use of de-icing, anti-icing and pretreatment materials applied for the removal of snow and surface maintenance on the 100 Durgin Lane premises. 100 Durgin Lane Owner LLC will maintain copies of Summary Documents, including copies of the Storm Reports, operator certifications, equipment used for roadway and sidewalk winter maintenance, calibration reports and amount of de-icing materials used.

## **2.4 Summary**

The above-described methodologies are incorporated into the 100 Durgin Lane Operational Manual and are to be used to qualify and retain all private contractors engaged at the 100 Durgin Lane premises for the purpose of winter operational snow removal and surface maintenance. This section of the Manual, is intended to be an adaptive management document that is modified as required based on experience gained from past practices and technological advancements that reflect chloride BMP standards. All 100 Durgin Lane Owner LLC employees directly involved with winter operational activities are required to review this document and the current standard Best Management Practices published by the UNH Technology Transfer (T2) program annually. All 100 Durgin Lane Owner LLC employees directly involved with winter operational activities, and all private contractors engaged at the 100 Durgin Lane premises for the purposes of winter operational snow removal and surface maintenance, must be current UNHT2 Green SnowPro Certified operators or equivalent and undergo the necessary requirements to maintain this certification annually.

## **Section 3**


# **Invasive Species**

With respect to a particular ecosystem, any species, including its seeds, eggs, spores, or other biological material capable of propagating that species, that is not native to that ecosystem is classified as an invasive species. Refer to the following fact sheet prepared by the University of New Hampshire Cooperative Extension entitled Methods for Disposing Non-Native Invasive Plants for recommended methods to dispose of invasive plant species.





Prepared by the Invasives Species Outreach Group, volunteers interested in helping people control invasive plants. Assistance provided by the Piscataquog Land Conservancy and the NH Invasives Species Committee. Edited by Karen Bennett, Extension Forestry Professor and Specialist.



**Tatarian honeysuckle**

*Lonicera tatarica*

USDA-NRCS PLANTS Database / Britton, N.L., and A. Brown. 1913. *An illustrated flora of the northern United States, Canada and the British Possessions*. Vol. 3: 282.

Non-native invasive plants crowd out natives in natural and managed landscapes. They cost taxpayers billions of dollars each year from lost agricultural and forest crops, decreased biodiversity, impacts to natural resources and the environment, and the cost to control and eradicate them.

Invasive plants grow well even in less than desirable conditions such as sandy soils along roadsides, shaded wooded areas, and in wetlands. In ideal conditions, they grow and spread even faster. There are many ways to remove these non-native invasives, but once removed, care is needed to dispose the removed plant material so the plants don't grow where disposed.

Knowing how a particular plant reproduces indicates its method of spread and helps determine

the appropriate disposal method. Most are spread by seed and are dispersed by wind, water, animals, or people. Some reproduce by vegetative means from pieces of stems or roots forming new plants. Others spread through both seed and vegetative means.

Because movement and disposal of viable plant parts is restricted (see NH Regulations), viable invasive parts can't be brought to most transfer stations in the state. Check with your transfer station to see if there is an approved, designated area for invasives disposal. This fact sheet gives recommendations for rendering plant parts non-viable.

Control of invasives is beyond the scope of this fact sheet. For information about control visit [www.nhinvasives.org](http://www.nhinvasives.org) or contact your UNH Cooperative Extension office.

### **New Hampshire Regulations**

Prohibited invasive species shall only be disposed of in a manner that renders them nonliving and nonviable. (Agr. 3802.04)

No person shall collect, transport, import, export, move, buy, sell, distribute, propagate or transplant any living and viable portion of any plant species, which includes all of their cultivars and varieties, listed in Table 3800.1 of the New Hampshire prohibited invasive species list. (Agr 3802.01)

## How and When to Dispose of Invasives?

To prevent seed from spreading remove invasive plants before seeds are set (produced). Some plants continue to grow, flower and set seed even after pulling or cutting. Seeds can remain viable in the ground for many years. If the plant has flowers or seeds, place the flowers and seeds in a heavy plastic bag “head first” at the weeding site and transport to the disposal site. The following are general descriptions of disposal methods. See the chart for recommendations by species.

**Burning:** Large woody branches and trunks can be used as firewood or burned in piles. For outside burning, a written fire permit from the local forest fire warden is required unless the ground is covered in snow. Brush larger than 5 inches in diameter can't be burned. Invasive plants with easily airborne seeds like black swallow-wort with mature seed pods (indicated by their brown color) shouldn't be burned as the seeds may disperse by the hot air created by the fire.

**Bagging (solarization):** Use this technique with softer-tissue plants. Use heavy black or clear plastic bags (contractor grade), making sure that no parts of the plants poke through. Allow the bags to sit in the sun for several weeks and on dark pavement for the best effect.

**Tarping and Drying:** Pile material on a sheet of plastic and cover with a tarp, fastening the tarp to the ground and monitoring it for escapes. Let the material dry for several weeks, or until it is clearly nonviable.

**Chipping:** Use this method for woody plants that don't reproduce vegetatively.

**Burying:** This is risky, but can be done with watchful diligence. Lay thick plastic in a deep pit before placing the cut up plant material in the hole. Place the material away from the edge of the plastic before covering it with more heavy plastic. Eliminate as much air as possible and toss in soil to weight down the material in the pit. Note that the top of the buried material should be at least three feet underground. Japanese knotweed should be at least 5 feet underground!

**Drowning:** Fill a large barrel with water and place soft-tissue plants in the water. Check after a few weeks and look for rotted plant material (roots, stems, leaves, flowers). Well-rotted plant material may be composted. A word of caution- seeds may still be viable after using this method. Do this before seeds are set. This method isn't used often. Be prepared for an awful stink!

**Composting:** Invasive plants can take root in compost. Don't compost any invasives unless you know there is no viable (living) plant material left. Use one of the above techniques (bagging, tarping, drying, chipping, or drowning) to render the plants nonviable before composting. Closely examine the plant before composting and avoid composting seeds.






**Japanese knotweed**  
*Polygonum cuspidatum*  
USDA-NRCS PLANTS Database /  
Britton, N.L., and A. Brown. 1913. *An illustrated flora of the northern United States, Canada and the British Possessions*. Vol. 1: 676.

**Be diligent looking for seedlings for years in areas where removal and disposal took place.**

## Suggested Disposal Methods for Non-Native Invasive Plants

This table provides information concerning the disposal of removed invasive plant material. If the infestation is treated with herbicide and left in place, these guidelines don't apply. Don't bring invasives to a local transfer station, unless there is a designated area for their disposal, or they have been rendered non-viable. This listing includes wetland and upland plants from the New Hampshire Prohibited Invasive Species List. The disposal of aquatic plants isn't addressed.

| <b>Woody Plants</b>  | <b>Method of Reproducing</b>   | <b>Methods of Disposal</b>   |
|--|--|--|
| Norway maple<br><i>(Acer platanoides)</i><br>European barberry<br><i>(Berberis vulgaris)</i><br>Japanese barberry<br><i>(Berberis thunbergii)</i><br>autumn olive<br><i>(Elaeagnus umbellata)</i><br>burning bush<br><i>(Euonymus alatus)</i><br>Morrow's honeysuckle<br><i>(Lonicera morrowii)</i><br>Tatarian honeysuckle<br><i>(Lonicera tatarica)</i><br>showy bush honeysuckle<br><i>(Lonicera x bella)</i><br>common buckthorn<br><i>(Rhamnus cathartica)</i><br>glossy buckthorn<br><i>(Frangula alnus)</i> | <b>Fruit and Seeds</b><br>                 | <p><b>Prior to fruit/seed ripening</b></p> <p>Seedlings and small plants</p> <ul style="list-style-type: none"> <li>▪ Pull or cut and leave on site with roots exposed. No special care needed.</li> </ul> <p>Larger plants</p> <ul style="list-style-type: none"> <li>▪ Use as firewood.</li> <li>▪ Make a brush pile.</li> <li>▪ Chip.</li> <li>▪ Burn.</li> </ul> <hr/> <p><b>After fruit/seed is ripe</b></p> <p>Don't remove from site.</p> <ul style="list-style-type: none"> <li>▪ Burn.</li> <li>▪ Make a covered brush pile.</li> <li>▪ Chip once all fruit has dropped from branches.</li> <li>▪ Leave resulting chips on site and monitor.</li> </ul> |
| oriental bittersweet<br><i>(Celastrus orbiculatus)</i><br>multiflora rose<br><i>(Rosa multiflora)</i>  | <b>Fruits, Seeds, Plant Fragments</b><br> | <p><b>Prior to fruit/seed ripening</b></p> <p>Seedlings and small plants</p> <ul style="list-style-type: none"> <li>▪ Pull or cut and leave on site with roots exposed. No special care needed.</li> </ul> <p>Larger plants</p> <ul style="list-style-type: none"> <li>▪ Make a brush pile.</li> <li>▪ Burn.</li> </ul> <hr/> <p><b>After fruit/seed is ripe</b></p> <p>Don't remove from site.</p> <ul style="list-style-type: none"> <li>▪ Burn.</li> <li>▪ Make a covered brush pile.</li> <li>▪ Chip – only after material has fully dried (1 year) and all fruit has dropped from branches. Leave resulting chips on site and monitor.</li> </ul>           |

| Non-Woody Plants   | Method of Reproducing   | Methods of Disposal   |
|--|---|---|
| <p>garlic mustard<br/>(<i>Alliaria petiolata</i>)</p> <p>spotted knapweed<br/>(<i>Centaurea maculosa</i>)</p> <ul style="list-style-type: none"> <li>▪ Sap of related knapweed can cause skin irritation and tumors. Wear gloves when handling.</li> </ul> <p>black swallow-wort<br/>(<i>Cynanchum nigrum</i>)</p> <ul style="list-style-type: none"> <li>▪ May cause skin rash. Wear gloves and long sleeves when handling.</li> </ul> <p>pale swallow-wort<br/>(<i>Cynanchum rossicum</i>)</p> <p>giant hogweed<br/>(<i>Heracleum mantegazzianum</i>)</p> <ul style="list-style-type: none"> <li>▪ Can cause major skin rash. Wear gloves and long sleeves when handling.</li> </ul> <p>dame's rocket<br/>(<i>Hesperis matronalis</i>)</p> <p>perennial pepperweed<br/>(<i>Lepidium latifolium</i>)</p> <p>purple loosestrife<br/>(<i>Lythrum salicaria</i>)</p> <p>Japanese stilt grass<br/>(<i>Microstegium vimineum</i>)</p> <p>mile-a-minute weed<br/>(<i>Polygonum perfoliatum</i>)</p> | <p><b>Fruits and Seeds</b></p>    | <p><b>Prior to flowering</b></p> <p>Depends on scale of infestation</p> <p>Small infestation</p> <ul style="list-style-type: none"> <li>▪ Pull or cut plant and leave on site with roots exposed.</li> </ul> <p>Large infestation</p> <ul style="list-style-type: none"> <li>▪ Pull or cut plant and pile. (You can pile onto or cover with plastic sheeting).</li> <li>▪ Monitor. Remove any re-sprouting material.</li> </ul> <hr/> <p><b>During and following flowering</b></p> <p>Do nothing until the following year or remove flowering heads and bag and let rot.</p> <p>Small infestation</p> <ul style="list-style-type: none"> <li>▪ Pull or cut plant and leave on site with roots exposed.</li> </ul> <p>Large infestation</p> <ul style="list-style-type: none"> <li>▪ Pull or cut plant and pile remaining material. (You can pile onto plastic or cover with plastic sheeting).</li> <li>▪ Monitor. Remove any re-sprouting material.</li> </ul> |
| <p>common reed<br/>(<i>Phragmites australis</i>)</p> <p>Japanese knotweed<br/>(<i>Polygonum cuspidatum</i>)</p> <p>Bohemian knotweed<br/>(<i>Polygonum x bohemicum</i>)</p>  | <p><b>Fruits, Seeds, Plant Fragments</b></p> <p>Primary means of spread in these species is by plant parts. Although all care should be given to preventing the dispersal of seed during control activities, the presence of seed doesn't materially influence disposal activities.</p> | <p><b>Small infestation</b></p> <ul style="list-style-type: none"> <li>▪ Bag all plant material and let rot.</li> <li>▪ Never pile and use resulting material as compost.</li> <li>▪ Burn.</li> </ul> <p><b>Large infestation</b></p> <ul style="list-style-type: none"> <li>▪ Remove material to unsuitable habitat (dry, hot and sunny or dry and shaded location) and scatter or pile.</li> <li>▪ Monitor and remove any sprouting material.</li> <li>▪ Pile, let dry, and burn.</li> </ul>  |

January 2010

UNH Cooperative Extension programs and policies are consistent with pertinent Federal and State laws and regulations, and prohibits discrimination in its programs, activities and employment on the basis of race, color, national origin, gender, religion, age, disability, political beliefs, sex, sexual orientation, or veteran's, marital or family status. College of Life Sciences and Agriculture, County Governments, NH Dept. of Resources and Economic Development, Division of Forests and Lands, NH Fish and Game ,and U.S. Dept. of Agriculture cooperating.

# Managing Invasive Plants

## Methods of Control

by Christopher Mattrick

### They're out there. The problem of invasive plants is as close as your own backyard.

Maybe a favorite dogwood tree is struggling in the clutches of an Oriental bittersweet vine. Clawlike canes of multiflora rose are scratching at the side of your house. That handsome burning bush you planted few years ago has become a whole clump in practically no time ... but what happened to the azalea that used to grow right next to it?

If you think controlling or managing invasive plants on your property is a daunting task, you're not alone. Though this topic is getting lots of attention from federal, state, and local government agencies, as well as the media, the basic question for most homeowners is simply, "How do I get rid of the invasive plants in my own landscape?" Fortunately, the best place to begin to tackle this complex issue is in our own backyards and on local conservation lands. We hope the information provided here will help you take back your yard. We won't kid you—there's some work involved, but the payoff in beauty, wildlife habitat, and peace of mind makes it all worthwhile.

### PLAN OF ATTACK

Three broad categories cover most invasive plant control: mechanical, chemical, and biological. Mechanical control means physically removing plants from the environment



Spraying chemicals to control invasive plants.

through cutting or pulling. Chemical control uses herbicides to kill plants and inhibit regrowth. Techniques and chemicals used will vary depending on the species. Biological controls use plant diseases or insect predators, typically from the targeted species' home range. Several techniques may be effective in controlling a single species, but there is usually one preferred method—the one that is most resource efficient with minimal impact on non-target species and the environment.

### MECHANICAL CONTROL METHODS

Mechanical treatments are usually the first ones to look at when evaluating an invasive plant removal project. These procedures do not require special licensing or introduce chemicals into the environment. They do require permits in some situations, such as wetland zones. [See sidebar on page 23.] Mechanical removal is highly labor intensive and creates a significant amount of site disturbance, which can lead to rapid reinvasion if not handled properly.

#### Pulling and digging

Many herbaceous plants and some woody species (up to about one inch in diameter), if present in limited quantities, can be pulled out or dug up. It's important to remove as much of the root system as possible; even a small portion can restart the infestation. Pull plants by hand or use a digging fork, as shovels can shear off portions of the root system, allowing for regrowth. To remove larger woody stems (up to about three inches in diameter), use a Weed Wrench™, Root Jack, or Root Talon. These tools, available from several manufacturers, are designed to remove the aboveground portion of the plant as well as the entire root system. It's easiest to undertake this type of control in the spring or early summer when soils are moist and plants come out more easily.



Using tools to remove woody stems.



Volunteers hand pulling invasive plants.

### Suffocation

Try suffocating small seedlings and herbaceous plants. Place double or triple layers of thick UV-stabilized plastic sheeting, either clear or black (personally I like clear), over the infestation and secure the plastic with stakes or weights. Make sure the plastic extends at least five feet past the edge of infestation on all sides. Leave the plastic in place for at least two years. This technique will kill everything beneath the plastic—invasive and non-invasive plants alike. Once the plastic is removed, sow a cover crop such as annual rye to prevent new invasions.

### Cutting or mowing

This technique is best suited for locations you can visit and treat often. To be effective, you will need to mow or cut infested areas three or four times a year for up to five years. The goal is to interrupt the plant's ability to photosynthesize by removing as much leafy material as possible. Cut the plants at ground level and remove all resulting debris from the site. With this treatment, the infestation may actually appear to get worse at first, so you will need to be as persistent as the invasive plants themselves. Each time you cut the plants back, the root system gets slightly larger, but must also rely on its energy reserves to push up new growth. Eventually, you will exhaust these reserves and the plants will die. This may take many years, so you have to remain committed to this process once you start; otherwise the treatment can backfire, making the problem worse.

## CHEMICAL CONTROL METHODS

Herbicides are among the most effective and resource-efficient tools to treat invasive species. Most of the commonly known invasive plants can be treated using only two herbicides—glyphosate (the active ingredient in Roundup™ and Rodeo™) and triclopyr (the active ingredient in Brush-B-Gone™ and Garlon™). Glyphosate is non-selective, meaning it kills everything it contacts. Triclopyr is selective and does not injure monocots (grasses, orchids, lilies, etc.). Please read labels and follow directions precisely for both environmental and personal safety. These are relatively benign herbicides, but improperly used they can still cause both short- and long-term health and environmental problems. Special aquatic formulations are required when working in wetland zones. You are required to have a state-issued pesticide applicator license when applying these chemicals on land you do not own. To learn more about the pesticide regulations in your state, visit or call your state's pesticide control division, usually part of the state's Department of Agriculture. In wetland areas, additional permits are usually required by the Wetlands Protection Act. [See sidebar on page 23.]

### Foliar applications

When problems are on a small scale, this type of treatment is usually applied with a backpack sprayer or even a small handheld spray bottle. It is an excellent way to treat large monocultures of herbaceous plants, or to spot-treat individual plants that are difficult to remove mechanically, such as goutweed, swallowwort, or purple loosestrife. It is also an effective treatment for some woody species, such as Japanese barberry, multiflora rose, Japanese honeysuckle, and Oriental bittersweet that grow in dense masses or large numbers over many acres. The herbicide mixture should contain no more than five percent of the active ingredient, but it is important to follow the instructions on the product label. This treatment is most effective when the plants are actively growing, ideally when they are flowering or beginning to form fruit. It has been shown that plants are often more susceptible to this type of treatment if the existing stems are cut off and the regrowth is treated. This is especially true for Japanese knotweed. The target plants should be thoroughly wetted with the herbicide on a day when there is no rain in the forecast for the next 24 to 48 hours.

## Cut stem treatments

There are several different types of cut stem treatments, but here we will review only the one most commonly used. All treatments of this type require a higher concentration of the active ingredient than is used in foliar applications. A 25 to 35 percent solution of the active ingredient should be used for cut stem treatments, but read and follow all label instructions. In most cases, the appropriate herbicide is glyphosate, except for Oriental bittersweet, on which triclopyr should be used. This treatment can be used on all woody stems, as well as phragmites and Japanese knotweed.

For woody stems, treatments are most effective when applied in the late summer and autumn—between late August and November. Stems should be cut close to the ground, but not so close that you will lose track of them. Apply herbicide directly to the cut surface as soon as possible after cutting. Delaying the application will reduce the effectiveness of the treatment. The herbicide can be applied with a sponge, paintbrush, or spray bottle.



Cut stem treatment tools.

For phragmites and Japanese knotweed, treatment is the same, but the timing and equipment are different. Plants should be treated anytime from mid-July through September, but the hottest, most humid days of the summer are best

for this method. Cut the stems halfway between two leaf nodes at a comfortable height. Inject (or squirt) herbicide into the exposed hollow stem. All stems in an infestation should be treated. A wash bottle is the most effective application tool, but you can also use an eyedropper, spray bottle, or one of the recently developed high-tech injection systems.

It is helpful to mix a dye in with the herbicide solution. The dye will stain the treated surface and mark the areas that have been treated, preventing unnecessary reapplication. You can buy a specially formulated herbicide dye, or use food coloring or laundry dye.

There is not enough space in this article to describe all the possible ways to control invasive plants. You can find other treatments, along with more details on the above-described methods, and species-specific recommendations on The Nature Conservancy Web site ([tncweeds.ucdavis.edu](http://tncweeds.ucdavis.edu)). An upcoming posting on the Invasive Plant Atlas of New England ([www.ipane.org](http://www.ipane.org)) and the New England Wild Flower Society ([www.newfs.org](http://www.newfs.org)) Web sites will also provide further details.



Hollow stem injection tools.

## Biological controls—still on the horizon

Biological controls are moving into the forefront of control methodology, but currently the only widely available and applied biocontrol relates to purple loosestrife. More information on purple loosestrife and other biological control projects can be found at [www.invasiveplants.net](http://www.invasiveplants.net).

## DISPOSAL OF INVASIVE PLANTS

Proper disposal of removed invasive plant material is critical to the control process. Leftover plant material can cause new infestations or reinfest the existing project area. There are many appropriate ways to dispose of invasive plant debris. I've listed them here in order of preference.

- 1. Burn it**—Make a brush pile and burn the material following local safety regulations and restrictions, or haul it to your town's landfill and place it in their burn pile.
- 2. Pile it**—Make a pile of the woody debris. This technique will provide shelter for wildlife as well.
- 3. Compost it**—Place all your herbaceous invasive plant debris in a pile and process as compost. Watch the pile closely for resprouts and remove as necessary. Do not use the resulting compost in your garden. The pile is for invasive plants only.



Injecting herbicide into the hollow stem of phragmites.

**4. Dry it/cook it**—Place woody debris out on your driveway or any asphalt surface and let it dry out for a month. Place herbaceous material in a doubled-up black trash bag and let it cook in the sun for one month. At the end of the month, the material should be non-viable and you can dump it or dispose of it with the trash. The method assumes there is no viable seed mixed in with the removed material.

*Care should be taken in the disposal of all invasive plants, but several species need extra attention. These are the ones that have the ability to sprout vigorously from plant fragments and should ideally be burned or dried prior to disposal: Oriental bittersweet, multiflora rose, Japanese honeysuckle, phragmites, and Japanese knotweed.*

Christopher Mattrick is the former Senior Conservation Programs Manager for New England Wild Flower Society, where he managed conservation volunteer and invasive and rare plant management programs. Today, Chris and his family work and play in the White Mountains of New Hampshire, where he is the Forest Botanist and Invasive Species Coordinator for the White Mountain National Forest.



## Controlling Invasive Plants in Wetlands

### Special concerns; special precautions

Control of invasive plants in or around wetlands or bodies of water requires a unique set of considerations. Removal projects in wetland zones can be legal and effective if handled appropriately. In many cases, herbicides may be the least disruptive tools with which to remove invasive plants. You will need a state-issued pesticide license to apply herbicide on someone else's property, but all projects in wetland or aquatic systems fall under the jurisdiction of the Wetlands Protection Act and therefore require a permit. *Yes, even hand-pulling that colony of glossy buckthorn plants from your own swampland requires a permit.* Getting a permit for legal removal is fairly painless if you plan your project carefully.

**1.** Investigate and understand the required permits and learn how to obtain them. The entity charged with the enforcement of the Wetlands Protection Act varies from state to state. For more information in your state, contact:

**ME:** Department of Environmental Protection  
[www.state.me.us/dep/blwq/docstand/nrpapage.htm](http://www.state.me.us/dep/blwq/docstand/nrpapage.htm)

**NH:** Department of Environmental Services  
[www.des.state.nh.us/wetlands/](http://www.des.state.nh.us/wetlands/)

**VT:** Department of Environmental Conservation  
[www.anr.state.vt.us/dec/waterq/permits/htm/pm\\_cud.htm](http://www.anr.state.vt.us/dec/waterq/permits/htm/pm_cud.htm)

**MA:** Consult your local town conservation commission

**RI:** Department of Environmental Management  
[www.dem.ri.gov/programs/benviron/water/permits/fresh/index.htm](http://www.dem.ri.gov/programs/benviron/water/permits/fresh/index.htm)

**CT:** Consult your local town Inland Wetland and Conservation Commission

**2.** Consult an individual or organization with experience in this area. Firsthand experience in conducting projects in wetland zones and navigating the permitting process is priceless. Most states have wetland scientist societies whose members are experienced in working in wetlands and navigating the regulations affecting them. A simple Web search will reveal the contact point for these societies. Additionally, most environmental consulting firms and some nonprofit organizations have skills in this area.

**3.** Develop a well-written and thorough project plan. You are more likely to be successful in obtaining a permit for your project if you submit a project plan along with your permit application. The plan should include the reasons for the project, your objectives in completing the project, how you plan to reach those objectives, and how you will monitor the outcome.

**4.** Ensure that the herbicides you plan to use are approved for aquatic use. Experts consider most herbicides harmful to water quality or aquatic organisms, but rate some formulations as safe for aquatic use. Do the research and select an approved herbicide, and then closely follow the instructions on the label.

**5.** If you are unsure—research, study, and most of all, ask for help. Follow the rules. The damage caused to aquatic systems by the use of an inappropriate herbicide or the misapplication of an appropriate herbicide not only damages the environment, but also may reduce public support for safe, well-planned projects.



## **Section 4**

# **Annual Updates and Log Requirements**

The Owner and/or Contact/Responsible Party shall review this Operation and Maintenance Plan once per year for its effectiveness and adjust the plan and deed as necessary.

A log of all preventative and corrective measures for the stormwater system shall be kept on-site and be made available upon request by any public entity with administrative, health environmental or safety authority over the site including NHDES.

Copies of the Stormwater Maintenance report shall be submitted to the City of Portsmouth on an annual basis.

| Stormwater Management Report |                    |                 |  |                                     |                           |              |
|------------------------------|--------------------|-----------------|--|-------------------------------------|---------------------------|--------------|
| Multifamily Development      |                    | 100 Durgin Lane |  |                                     |                           |              |
| BMP Description              | Date of Inspection | Inspector       | BMP Installed and Operating Properly?                    | Cleaning / Corrective Action Needed | Date of Cleaning / Repair | Performed By |
| Deep Sump CB's               |                    |                 | <input type="checkbox"/> Yes <input type="checkbox"/> No |                                     |                           |              |
| Jellyfish Filter 1           |                    |                 | <input type="checkbox"/> Yes <input type="checkbox"/> No |                                     |                           |              |
| Jellyfish Filter 2           |                    |                 | <input type="checkbox"/> Yes <input type="checkbox"/> No |                                     |                           |              |
| CDS Unit 1                   |                    |                 | <input type="checkbox"/> Yes <input type="checkbox"/> No |                                     |                           |              |
| CDS Unit 2                   |                    |                 | <input type="checkbox"/> Yes <input type="checkbox"/> No |                                     |                           |              |
| CDS Unit 3                   |                    |                 | <input type="checkbox"/> Yes <input type="checkbox"/> No |                                     |                           |              |
| Rain Garden 1                |                    |                 | <input type="checkbox"/> Yes <input type="checkbox"/> No |                                     |                           |              |
| Rain Garden 2                |                    |                 | <input type="checkbox"/> Yes <input type="checkbox"/> No |                                     |                           |              |

\\Tighebond.com\data\Data\Projects\E\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Reports\Applications\City of Portsmouth\20240617\_TAC Submission\O-M\E5071-001\_Operations and Maintenance.docx

**Jellyfish<sup>®</sup> Filter  
Owner's Manual**



# Table of Contents


|           |   |    |
|-----------|---|----|
| Chapter 1 | 1.0 Owner Specific Jellyfish Product Information.....             | 4  |
| Chapter 2 | 2.0 Jellyfish Filter System Operations & Functions .....          | 5  |
|           | 2.1 Components & Cartridges .....                                 | 6  |
|           | 2.2 Jellyfish Membrane Filtration Cartridges Assembly .....       | 7  |
|           | 2.3 Installation of Jellyfish Membrane Filtration Cartridges..... | 7  |
| Chapter 3 | 3.0 Inspection and Maintenance Overview .....                     | 8  |
| Chapter 4 | 4.0 Inspection Timing .....                                       | 8  |
| Chapter 5 | 5.0 Inspection Procedure.....                                     | 8  |
|           | 5.1 Dry Weather Inspections .....                                 | 8  |
|           | 5.1 Wet Weather Inspections .....                                 | 9  |
| Chapter 6 | 6.0 Maintenance Requirements.....                                 | 9  |
| Chapter 7 | 7.0 Maintenance Procedure .....                                   | 9  |
|           | 7.1 Filter Cartridge Removal .....                                | 9  |
|           | 7.2 Filter Cartridge Rinsing .....                                | 9  |
|           | 7.3 Sediment and Flotables Extraction .....                       | 10 |
|           | 7.4 Filter Cartridge Reinstallation and Replacement.....          | 10 |
|           | 7.5 Chemical Spills.....  | 10 |
|           | 5.6 Material Disposal .....                                       | 10 |
|           | Jellyfish Filter Inspection and Maintenance Log .....             | 12 |

## THANK YOU FOR PURCHASING THE JELLYFISH® FILTER!

Contech Engineered Solutions would like to thank you for selecting the Jellyfish Filter to meet your project’s stormwater treatment needs. With proper inspection and maintenance, the Jellyfish Filter is designed to deliver ongoing, high levels of stormwater pollutant removal.

If you have any questions, please feel free to call us or e-mail us:

**Contech Engineered Solutions**  
9025 Centre Pointe Drive, Suite 400 | West Chester, OH 45069  
513-645-7000 | 800-338-1122  
[www.ContechES.com](http://www.ContechES.com)  
[info@conteches.com](mailto:info@conteches.com)



## WARNINGS / CAUTION

1. FALL PROTECTION may be required.
2. WATCH YOUR STEP if standing on the Jellyfish Filter Deck at any time; Great care and safety must be taken while walking or maneuvering on the Jellyfish Filter Deck. Attentive care must be taken while standing on the Jellyfish Filter Deck at all times to prevent stepping onto a lid, into or through a cartridge hole or slipping on the deck.
3. The Jellyfish Filter Deck can be SLIPPERY WHEN WET.
4. If the Top Slab, Covers or Hatches have not yet been installed, or are removed for any reason, great care must be taken to NOT DROP ANYTHING ONTO THE JELLYFISH FILTER DECK. The Jellyfish Filter Deck and Cartridge Receptacle Rings can be damaged under high impact loads. This type of activity voids all warranties. All damaged items to be replaced at owner's expense.
5. Maximum deck load 2 persons, total weight 450 lbs.

## Safety Notice

Jobsite safety is a topic and practice addressed comprehensively by others. The inclusions here are intended to be reminders to whole areas of Safety Practice that are the responsibility of the Owner(s), Manager(s) and Contractor(s). OSHA and Canadian OSH, and Federal, State/Provincial, and Local Jurisdiction Safety Standards apply on any given site or project. The knowledge and applicability of those responsibilities is the Contractor's responsibility and outside the scope of Contech Engineered Solutions.

## Confined Space Entry

Secure all equipment and perform all training to meet applicable local and OSHA regulations regarding confined space entry. It is the Contractor's or entry personnel's responsibility to proceed safely at all times.

## Personal Safety Equipment

Contractor is responsible to provide and wear appropriate personal protection equipment as needed including, but not limited to safety boots, hard hat, reflective vest, protective eyewear, gloves and fall protection equipment as necessary. Make sure all equipment is staffed with trained and/or certified personnel, and all equipment is checked for proper operation and safety features prior to use.

- Fall protection equipment
- Eye protection
- Safety boots
- Ear protection
- Gloves
- Ventilation and respiratory protection
- Hard hat
- Maintenance and protection of traffic plan

## Chapter 1

### 1.0 – Owner Specific Jellyfish Filter Product Information

Below you will find a reference page that can be filled out according to your Jellyfish Filter specification to help you easily inspect, maintain and order parts for your system.

|  |  |
|--|--|
| Owner Name:                            |  |
| Phone Number:                          |  |
| Site Address:                          |  |
| Site GPS Coordinates/unit location:    |  |
| Unit Location Description:             |  |
| Jellyfish Filter Model No.:            |  |
| Contech Project & Sequence Number      |  |
| No. of Hi-Flo Cartridges               |  |
| No. of Cartridges:                     |  |
| Length of Draindown Cartridges:        |  |
| No. of Blank Cartridge Lids:           |  |
| Bypass Configuration (Online/Offline): |  |

### Notes:

---

---

---


---

## Chapter 2

### 2.0 – Jellyfish Filter System Operations and Functions

The Jellyfish Filter is an engineered stormwater quality treatment technology that removes a high level and wide variety of stormwater pollutants. Each Jellyfish Filter cartridge consists of eleven membrane - encased filter elements (“filtration tentacles”) attached to a cartridge head plate. The filtration tentacles provide a large filtration surface area, resulting in high flow and high pollutant removal capacity.

The Jellyfish Filter functions are depicted in Figure 1 below.



Jellyfish Filter cartridges are backwashed after each peak storm event, which removes accumulated sediment from the membranes. This backwash process extends the service life of the cartridges and increases the time between maintenance events.


For additional details on the operation and pollutant capabilities of the Jellyfish Filter please refer to additional details on our website at [www.ContechES.com](http://www.ContechES.com).

## 2.1 – Components and Cartridges

The Jellyfish Filter and components are depicted in Figure 2 below.

**FIGURE 2**

### Jellyfish Filter Components



Tentacles are available in various lengths as depicted in Table 1 below.

Table 1 – Cartridge Lengths / Weights and Cartridge Lid Orifice Diameters

| Cartridge Lengths    | Dry Weight        | Hi-Flo Orifice Diameter | Draindown Orifice Diameter |
|----------------------|-------------------|-------------------------|----------------------------|
| 15 inches (381 mm)   | 10 lbs (4.5 kg)   | 35 mm                   | 20 mm                      |
| 27 inches (686 mm)   | 14.5 lbs (6.6 kg) | 45 mm                   | 25 mm                      |
| 40 inches (1,016 mm) | 19.5 lbs (8.9 kg) | 55 mm                   | 30 mm                      |
| 54 inches (1,372 mm) | 25 lbs (11.4 kg)  | 70 mm                   | 35 mm                      |



## 2.2 – Jellyfish Membrane Filtration Cartridge Assembly

The Jellyfish Filter utilizes multiple membrane filtration cartridges. Each cartridge consists of removable cylindrical filtration “tentacles” attached to a cartridge head plate. Each filtration tentacle has a threaded pipe nipple and o-ring. To attach, insert the top pipe nipples with the o-ring through the head plate holes and secure with locking nuts. Hex nuts to be hand tightened and checked with a wrench as shown below.

## 2.3 – Jellyfish Membrane Filtration Cartridge Installation

- Cartridge installation will be performed by trained individuals and coordinated with the installing site Contractor. Flow diversion devices are required to be in place until the site is stabilized (final paving and landscaping in place). Failure to address this step completely will reduce the time between required maintenance.
- Descend to the cartridge deck (see Safety Notice and page 3).
- Refer to Contech's submittal drawings to determine proper quantity and placement of Hi-Flo, Draindown and Blank cartridges with appropriate lids. Lower the Jellyfish membrane filtration cartridges into the cartridge receptacles within the cartridge deck. It is possible that not all cartridge receptacles will be filled with a filter cartridge. In that case, a blank headplate and blank cartridge lid (no orifice) would be installed.



**Cartridge Assembly**

Do not force the tentacles down into the cartridge receptacle, as this may damage the membranes. Apply downward pressure on the cartridge head plate to seat the lubricated rim gasket (thick circular gasket surrounding the circumference of the head plate) into the cartridge receptacle. (See Figure 3 for details on approved lubricants for use with rim gasket.)

- Examine the cartridge lids to differentiate lids with a small orifice, a large orifice, and no orifice.
  - Lids with a small orifice are to be inserted into the Draindown cartridge receptacles, outside of the backwash pool weir.
  - Lids with a large orifice are to be inserted into the Hi-Flo cartridge receptacles within the backwash pool weir.
  - Lids with no orifice (blank cartridge lids) and a blank headplate are to be inserted into unoccupied cartridge receptacles.
- To install a cartridge lid, align both cartridge lid male threads with the cartridge receptacle female threads before rotating approximately 1/3 of a full rotation until firmly seated. Use of an approved rim gasket lubricant may facilitate installation.

### 3.0 Inspection and Maintenance Overview

The primary purpose of the Jellyfish® Filter is to capture and remove pollutants from stormwater runoff. As with any filtration system, these pollutants must be removed to maintain the filter's maximum treatment performance. Regular inspection and maintenance are required to insure proper functioning of the system. Maintenance frequencies and requirements are site specific and vary depending on pollutant loading. Additional maintenance activities may be required in the event of non-storm event runoff, such as base-flow or seasonal flow, an upstream chemical spill or due to excessive sediment loading from site erosion or extreme runoff events. It is a good practice to inspect the system after major storm events.

Inspection activities are typically conducted from surface observations and include:


- Observe if standing water is present
- Observe if there is any physical damage to the deck or cartridge lids
- Observe the amount of debris in the Maintenance Access Wall (MAW) or inlet bay for vault systems

Maintenance activities include:

- Removal of oil, floatable trash and debris
- Removal of collected sediments
- Rinsing and re-installing the filter cartridges
- Replace filter cartridge tentacles, as needed

### 4.0 Inspection Timing

Inspection of the Jellyfish Filter is key in determining the maintenance requirements for, and to develop a history of, the site's pollutant loading characteristics. In general, inspections should be performed at the times indicated below; *or per the approved project stormwater quality documents (if applicable), whichever is more frequent.*



Note: Separator Skirt not shown

1. A minimum of quarterly inspections during the first year of operation to assess the sediment and floatable pollutant accumulation, and to ensure proper functioning of the system.
2. Inspection frequency in subsequent years is based on the inspection and maintenance plan developed in the first year of operation. Minimum frequency should be once per year.
3. Inspection is recommended after each major storm event.
4. Inspection is required immediately after an upstream oil, fuel or other chemical spill.

### 5.0 Inspection Procedure

The following procedure is recommended when performing inspections:

1. Provide traffic control measures as necessary.
2. Inspect the MAW or inlet bay for floatable pollutants such as trash, debris, and oil sheen.
3. Measure oil and sediment depth in several locations, by lowering a sediment probe until contact is made with the floor of the structure. Record sediment depth, and presences of any oil layers.
4. Inspect cartridge lids. Missing or damaged cartridge lids to be replaced.
5. Inspect the MAW (where appropriate), cartridge deck and receptacles, and backwash pool weir, for damaged or broken components.

#### 5.1 Dry weather inspections

- Inspect the cartridge deck for standing water, and/or sediment on the deck.
- No standing water under normal operating conditions.
- Standing water inside the backwash pool, but not outside the backwash pool indicates, that the filter cartridges need to be rinsed.



Inspection Utilizing Sediment Probe

- Standing water outside the backwash pool is not anticipated and may indicate a backwater condition caused by high water elevation in the receiving water body, or possibly a blockage in downstream infrastructure.
- Any appreciable sediment ( $\geq 1/16''$ ) accumulated on the deck surface should be removed.

## 5.2 Wet weather inspections

- Observe the rate and movement of water in the unit. Note the depth of water above deck elevation within the MAW or inlet bay.
- Less than 6 inches, flow should be exiting the cartridge lids of each of the draindown cartridges (i.e. cartridges located outside the backwash pool).
- Greater than 6 inches, flow should be exiting the cartridge lids of each of the draindown cartridges and each of the hi-flo cartridges (i.e. cartridges located inside the backwash pool), and water should be overflowing the backwash pool weir.
- 18 inches or greater and relatively little flow is exiting the cartridge lids and outlet pipe, this condition indicates that the filter cartridges need to be rinsed.

## 6.0 Maintenance Requirements

Required maintenance for the Jellyfish Filter is based upon results of the most recent inspection, historical maintenance records, or the site specific water quality management plan; whichever is more frequent. In general, maintenance requires some combination of the following:

1. Sediment removal for depths reaching 12 inches or greater, or within 3 years of the most recent sediment cleaning, whichever occurs sooner.
2. Floatable trash, debris, and oil removal.
3. Deck cleaned and free from sediment.
4. Filter cartridges rinsed and re-installed as required by the most recent inspection results, or within 12 months of the most recent filter rinsing, whichever occurs sooner.
5. Replace tentacles if rinsing does not restore adequate hydraulic capacity, remove accumulated sediment, or if damaged or missing. It is recommended that tentacles should remain in service no longer than 5 years before replacement.
6. Damaged or missing cartridge deck components must be repaired or replaced as indicated by results of the most recent inspection.
7. The unit must be cleaned out and filter cartridges inspected immediately after an upstream oil, fuel, or chemical spill. Filter cartridge tentacles should be replaced if damaged or compromised by the spill.

## 7.0 Maintenance Procedure

The following procedures are recommended when maintaining the Jellyfish Filter:

1. Provide traffic control measures as necessary.
2. Open all covers and hatches. Use ventilation equipment as required, according to confined space entry procedures. *Caution: Dropping objects onto the cartridge deck may cause damage.*
3. Perform Inspection Procedure prior to maintenance activity.

4. To access the cartridge deck for filter cartridge service, descend into the structure and step directly onto the deck. *Caution: Do not step onto the maintenance access wall (MAW) or backwash pool weir, as damage may result. Note that the cartridge deck may be slippery.*
5. Maximum weight of maintenance crew and equipment on the cartridge deck not to exceed 450 lbs.

### 7.1 Filter Cartridge Removal

1. Remove a cartridge lid.
2. Remove cartridges from the deck using the lifting loops in the cartridge head plate. Rope or a lifting device (available from Contech) should be used. *Caution: Should a snag occur, do not force the cartridge upward as damage to the tentacles may result. Wet cartridges typically weigh between 100 and 125 lbs.*
3. Replace and secure the cartridge lid on the exposed empty receptacle as a safety precaution. Contech does not recommend exposing more than one empty cartridge receptacle at a time.

### 7.2 Filter Cartridge Rinsing

1. Remove all 11 tentacles from the cartridge head plate. Take care not to lose or damage the O-ring seal as well as the plastic threaded nut and connector.
2. Position tentacles in a container (or over the MAW), with the



Cartridge Removal & Lifting Device



threaded connector (open end) facing down, so rinse water is flushed through the membrane and captured in the container.

3. Using the Jellyfish rinse tool (available from Contech) or a low-pressure garden hose sprayer, direct water spray onto the tentacle membrane, sweeping from top to bottom along the length of the tentacle. Rinse until all sediment is removed from the membrane. *Caution: Do not use a high pressure sprayer or focused stream of water on the membrane. Excessive water pressure may damage the membrane.*
4. Collected rinse water is typically removed by vacuum hose.

5. Reassemble cartridges as detailed later in this document. Reuse O-rings and nuts, ensuring proper placement on each tentacle.

### 7.3 Sediment and Floatables Extraction

1. Perform vacuum cleaning of the Jellyfish Filter only after filter cartridges have been removed from the system. Access the lower chamber for vacuum cleaning only through the maintenance access wall (MAW) opening. Be careful not to damage the flexible plastic separator skirt that is attached to the underside of the deck on manhole systems. Do not lower the vacuum wand through a cartridge receptacle, as damage to the receptacle will result.
2. Vacuum floatable trash, debris, and oil, from the MAW opening or inlet bay. Alternatively, floatable solids may be removed by a net or skimmer.
3. Pressure wash cartridge deck and receptacles to remove all



*Rinsing Cartridge with Contech Rinse Tool*

sediment and debris. Sediment should be rinsed into the sump area. Take care not to flush rinse water into the outlet pipe.

4. Remove water from the sump area. Vacuum or pump equipment should only be introduced through the MAW or inlet bay.
5. Remove the sediment from the bottom of the unit through the MAW or inlet bay opening.
6. For larger diameter Jellyfish Filter manholes ( $\geq 8$ -ft) and some



*Vacuuming Sump Through MAW*

vaults complete sediment removal may be facilitated by removing a cartridge lid from an empty receptacle and inserting a jetting wand (not a vacuum wand) through the receptacle. Use the sprayer to rinse loosened sediment toward the vacuum hose in the MAW opening, being careful not to damage the receptacle.

### 7.4 Filter Cartridge Reinstallation and Replacement

1. Cartridges should be installed after the deck has been cleaned. It is important that the receptacle surfaces be free from grit and debris.
2. Remove cartridge lid from deck and carefully lower the filter cartridge into the receptacle until head plate gasket is seated squarely in receptacle. *Caution: Do not force the cartridge downward; damage may occur.*
3. Replace the cartridge lid and check to see that both male threads are properly seated before rotating approximately 1/3 of a full rotation until firmly seated. Use of an approved rim gasket lubricant may facilitate installation. See next page for additional details.
4. If rinsing is ineffective in removing sediment from the tentacles, or if tentacles are damaged, provisions must be made to replace the spent or damaged tentacles with new tentacles. Contact Contech to order replacement tentacles.

### 7.5 Chemical Spills

*Caution: If a chemical spill has been captured, do not attempt maintenance. Immediately contact the local hazard response agency and contact Contech.*

### 7.6 Material Disposal

The accumulated sediment found in stormwater treatment and conveyance systems must be handled and disposed of in accordance with regulatory protocols. It is possible for sediments to contain measurable concentrations of heavy metals and organic chemicals (such as pesticides and petroleum products). Areas with the greatest potential for high pollutant loading include industrial areas and heavily traveled roads. Sediments and water must be disposed of in accordance with all applicable waste disposal regulations. When scheduling maintenance, consideration must be made for the disposal of solid and liquid wastes. This typically requires coordination with a local landfill for solid waste disposal. For liquid waste disposal a number of options are available including a municipal vacuum truck decant facility, local waste water treatment plant or on-site treatment and discharge.

# Jellyfish Filter Components & Filter Cartridge Assembly and Installation





TABLE 1: BOM

| ITEM NO. | DESCRIPTION                      |
|----------|----------------------------------|
| 1        | JF HEAD PLATE                    |
| 2        | JF TENTACLE                      |
| 3        | JF O-RING                        |
| 4        | JF HEAD PLATE GASKET             |
| 5        | JF CARTRIDGE EYELET              |
| 6        | JF 14IN COVER                    |
| 7        | JF RECEPTACLE                    |
| 8        | BUTTON HEAD CAP SCREW M6X14MM SS |
| 9        | JF CARTRIDGE NUT                 |

TABLE 2: APPROVED GASKET LUBRICANTS

| PART NO.  | MFR       | DESCRIPTION          |
|-----------|-----------|----------------------|
| 78713     | LA-CO     | LUBRI-JOINT          |
| 40501     | HERCULES  | DUCK BUTTER          |
| 30600     | OATEY     | PIPE LUBRICANT       |
| PSLUBXL1Q | PROSELECT | PIPE JOINT LUBRICANT |

## NOTES:

### Head Plate Gasket Installation:

Install Head Plate Gasket (Item 4) onto the Head Plate (Item 1) and liberally apply a lubricant from Table 2: Approved Gasket Lubricants onto the gasket where it contacts the Receptacle (Item 7) and Cartridge Lid (Item 6). Follow Lubricant manufacturer's instructions.

### Lid Assembly:

Rotate Cartridge Lid counter-clockwise until both male threads drop down and properly seat. Then rotate Cartridge Lid clock-wise approximately one-third of a full rotation until Cartridge Lid is firmly secured, creating a watertight seal.

# Jellyfish Filter Inspection and Maintenance Log

Owner: \_\_\_\_\_ Jellyfish Model No.: \_\_\_\_\_

Location: \_\_\_\_\_ GPS Coordinates: \_\_\_\_\_

Land Use:      Commercial: \_\_\_\_\_      Industrial: \_\_\_\_\_      Service Station: \_\_\_\_\_

                 Road/Highway: \_\_\_\_\_      Airport: \_\_\_\_\_      Residential: \_\_\_\_\_      Parking Lot: \_\_\_\_\_

|   |  |  |  |  |  |
|---|--|--|--|--|--|
| Date/Time:  |  |  |  |  |  |
| Inspector:  |  |  |  |  |  |
| Maintenance Contractor:                             |  |  |  |  |  |
| Visible Oil Present: (Y/N)                          |  |  |  |  |  |
| Oil Quantity Removed                                |  |  |  |  |  |
| Floatable Debris Present: (Y/N)                     |  |  |  |  |  |
| Floatable Debris removed: (Y/N)                     |  |  |  |  |  |
| Water Depth in Backwash Pool                        |  |  |  |  |  |
| Cartridges externally rinsed/re-commissioned: (Y/N) |  |  |  |  |  |
| New tentacles put on Cartridges: (Y/N)              |  |  |  |  |  |
| Sediment Depth Measured: (Y/N)                      |  |  |  |  |  |
| Sediment Depth (inches or mm):                      |  |  |  |  |  |
| Sediment Removed: (Y/N)                             |  |  |  |  |  |
| Cartridge Lids intact: (Y/N)                        |  |  |  |  |  |
| Observed Damage:                                    |  |  |  |  |  |
| Comments:   |  |  |  |  |  |

## CDS<sup>®</sup> Inspection and Maintenance Guide

---



## Maintenance

The CDS system should be inspected at regular intervals and maintained when necessary to ensure optimum performance. The rate at which the system collects pollutants will depend more heavily on site activities than the size of the unit. For example, unstable soils or heavy winter sanding will cause the grit chamber to fill more quickly but regular sweeping of paved surfaces will slow accumulation.

## Inspection

Inspection is the key to effective maintenance and is easily performed. Pollutant transport and deposition may vary from year to year and regular inspections will help ensure that the system is cleaned out at the appropriate time. At a minimum, inspections should be performed twice per year (e.g. spring and fall) however more frequent inspections may be necessary in climates where winter sanding operations may lead to rapid accumulations, or in equipment washdown areas. Installations should also be inspected more frequently where excessive amounts of trash are expected.

The visual inspection should ascertain that the system components are in working order and that there are no blockages or obstructions in the inlet and separation screen. The inspection should also quantify the accumulation of hydrocarbons, trash, and sediment in the system. Measuring pollutant accumulation can be done with a calibrated dipstick, tape measure or other measuring instrument. If absorbent material is used for enhanced removal of hydrocarbons, the level of discoloration of the sorbent material should also be identified during inspection. It is useful and often required as part of an operating permit to keep a record of each inspection. A simple form for doing so is provided.

Access to the CDS unit is typically achieved through two manhole access covers. One opening allows for inspection and cleanout of the separation chamber (cylinder and screen) and isolated sump. The other allows for inspection and cleanout of sediment captured and retained outside the screen. For deep units, a single manhole access point would allow both sump cleanout and access outside the screen.

The CDS system should be cleaned when the level of sediment has reached 75% of capacity in the isolated sump or when an appreciable level of hydrocarbons and trash has accumulated. If absorbent material is used, it should be replaced when significant discoloration has occurred. Performance will not be impacted until 100% of the sump capacity is exceeded however it is recommended that the system be cleaned prior to that for easier removal of sediment. The level of sediment is easily determined by measuring from finished grade down to the top of the sediment pile. To avoid underestimating the level of sediment in the chamber, the measuring device must be lowered to the top of the sediment pile carefully. Particles at the top of the pile typically offer less resistance to the end of the rod than consolidated particles toward the bottom of the pile. Once this measurement is recorded, it should be compared to the as-built drawing for the unit to determine whether the height of the sediment pile off the bottom of the sump floor exceeds 75% of the total height of isolated sump.

## Cleaning

Cleaning of a CDS system should be done during dry weather conditions when no flow is entering the system. The use of a vacuum truck is generally the most effective and convenient method of removing pollutants from the system. Simply remove the manhole covers and insert the vacuum hose into the sump. The system should be completely drained down and the sump fully evacuated of sediment. The area outside the screen should also be cleaned out if pollutant build-up exists in this area.

In installations where the risk of petroleum spills is small, liquid contaminants may not accumulate as quickly as sediment. However, the system should be cleaned out immediately in the event of an oil or gasoline spill should be cleaned out immediately. Motor oil and other hydrocarbons that accumulate on a more routine basis should be removed when an appreciable layer has been captured. To remove these pollutants, it may be preferable to use absorbent pads since they are usually less expensive to dispose than the oil/water emulsion that may be created by vacuuming the oily layer. Trash and debris can be netted out to separate it from the other pollutants. The screen should be power washed to ensure it is free of trash and debris.

Manhole covers should be securely seated following cleaning activities to prevent leakage of runoff into the system from above and also to ensure that proper safety precautions have been followed. Confined space entry procedures need to be followed if physical access is required. Disposal of all material removed from the CDS system should be done in accordance with local regulations. In many jurisdictions, disposal of the sediments may be handled in the same manner as the disposal of sediments removed from catch basins or deep sump manholes.





| CDS Model | Diameter |     | Distance from Water Surface to Top of Sediment Pile |     | Sediment Storage Capacity |                |
|-----------|----------|-----|---|-----|---------------------------|----------------|
|           | ft       | m   | ft  | m   | y <sup>3</sup>            | m <sup>3</sup> |
| CDS1515   | 3        | 0.9 | 3.0   | 0.9 | 0.5                       | 0.4            |
| CDS2015   | 4        | 1.2 | 3.0   | 0.9 | 0.9                       | 0.7            |
| CDS2015   | 5        | 1.3 | 3.0   | 0.9 | 1.3                       | 1.0            |
| CDS2020   | 5        | 1.3 | 3.5   | 1.1 | 1.3                       | 1.0            |
| CDS2025   | 5        | 1.3 | 4.0   | 1.2 | 1.3                       | 1.0            |
| CDS3020   | 6        | 1.8 | 4.0   | 1.2 | 2.1                       | 1.6            |
| CDS3025   | 6        | 1.8 | 4.0   | 1.2 | 2.1                       | 1.6            |
| CDS3030   | 6        | 1.8 | 4.6   | 1.4 | 2.1                       | 1.6            |
| CDS3035   | 6        | 1.8 | 5.0   | 1.5 | 2.1                       | 1.6            |
| CDS4030   | 8        | 2.4 | 4.6   | 1.4 | 5.6                       | 4.3            |
| CDS4040   | 8        | 2.4 | 5.7   | 1.7 | 5.6                       | 4.3            |
| CDS4045   | 8        | 2.4 | 6.2   | 1.9 | 5.6                       | 4.3            |
| CDS5640   | 10       | 3.0 | 6.3   | 1.9 | 8.7                       | 6.7            |
| CDS5653   | 10       | 3.0 | 7.7   | 2.3 | 8.7                       | 6.7            |
| CDS5668   | 10       | 3.0 | 9.3   | 2.8 | 8.7                       | 6.7            |
| CDS5678   | 10       | 3.0 | 10.3  | 3.1 | 8.7                       | 6.7            |

Table 1: CDS Maintenance Indicators and Sediment Storage Capacities



**Support**

- Drawings and specifications are available at [www.contechstormwater.com](http://www.contechstormwater.com).
- Site-specific design support is available from our engineers.

©2017 Contech Engineered Solutions LLC, a QUIKRETE Company

Contech Engineered Solutions LLC provides site solutions for the civil engineering industry. Contech's portfolio includes bridges, drainage, sanitary sewer, stormwater, earth stabilization and wastewater treatment products. For information, visit [www.ContechES.com](http://www.ContechES.com) or call 800.338.1122

NOTHING IN THIS CATALOG SHOULD BE CONSTRUED AS AN EXPRESSED WARRANTY OR AN IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE. SEE THE CONTECH STANDARD CONDITION OF SALES (VIEWABLE AT [WWW.CONTECHES.COM/COS](http://WWW.CONTECHES.COM/COS)) FOR MORE INFORMATION.

The product(s) described may be protected by one or more of the following US patents: 5,322,629; 5,624,576; 5,707,527; 5,759,415; 5,788,848; 5,985,157; 6,027,639; 6,350,374; 6,406,218; 6,641,720; 6,511,595; 6,649,048; 6,991,114; 6,998,038; 7,186,058; 7,296,692; 7,297,266; 7,517,450 related foreign patents or other patents pending.





## 100 Durgin Lane Multi-family Redevelopment Preliminary Water and Wastewater Demand Analysis

**To:** City of Portsmouth, Technical Advisory Committee  
**FROM:** Neil A. Hansen, PE  
 Patrick M. Crimmins, PE  
**COPY:** 100 Durgin Lane Owner, LLC  
**DATE:** August 26, 2024

The following memo is to provide an estimate of the average daily water and wastewater flows anticipated for the above-mentioned project for the purpose of allowing city staff to review capacity of the existing system. The flows have been calculated as a total development area.

The proposed project is located at 100 Durgin Lane and includes lots identified as Map 239 Lots 16, 16 & 18 on the City of Portsmouth Tax Maps. The site was previously home to Christmas Tree Shops and Bed, Bath and Beyond locations which are no longer in operation. The proposed project consists of the demolition of the existing Christmas Tree Shops and Bed, Bath and Beyond building and the construction of approximately 360 rental housing units in a mix of 3-story and 4-story buildings. The proposed sewer connection will be connected to the existing sewer manhole in Durgin Lane which has a 10" PVC outlet pipe.

As depicted in the table below, the average daily flow in gallons per day (GPD) has been calculated for the proposed project in accordance with Table 3-3: of Metcalf and Eddy, "Wastewater Engineering Treatment and Resource Reuse" as required under NHDES Env-Wq 700.

| <b>Overall Net Proposed Peak Gal/Day Design</b> |                    |                               |                    |
|---|--------------------|-------------------------------|--------------------|
| <u>Use</u>                                      | <u>Design Unit</u> | <u>Unit Design Flow (GPD)</u> | <u>Design Flow</u> |
| <b>Proposed:</b>                                |                    |                               |                    |
| Studio Apartment                                | 49 Units           | 120 GPD/Bdrm                  | 5,880 GPD          |
| 1 Bdrm Apartment                                | 160 Units          | 120 GPD/Bdrm                  | 19,200 GPD         |
| 2 Bdrm Apartment                                | 140 Units          | 120 GPD/Bdrm                  | 33,600 GPD         |
| 3 Bdrm Apartment                                | 11 Units           | 120 GPD/Bdrm                  | 3,960 GPD          |
| Amenity Building                                | 10,880 SF          | 5 GPD/100 SF                  | 544 GPD            |
|   | 11 Employees       | 10 GPD/Employee               | 110 GPD            |
| <b>Total Proposed:</b>                          |                    |                               | <b>63,294 GPD</b>  |
| <b>Existing, To Be Removed:</b>                 |                    |                               |                    |
| Shopping Center                                 | 632 Parking Spaces | 2 GPD/Parking Space           | 1,264 GPD          |
|   | 70 Employees       | 10 GPD/Employee               | 700 GPD            |
| <b>Total, To Be Removed</b>                     |                    |                               | <b>1,964 GPD</b>   |
| <b>Total Net Flow</b>                           |                    |                               | <b>61,330 GPD</b>  |

# WETLAND DELINEATION REPORT

100 Durgin Lane  
Portsmouth, NH  
May 8, 2024



---

As requested, I am pleased to provide the following report documenting the wetland delineation performed by Gove Environmental Services, Inc. in connection with the above referenced property. This is an update to my February 28<sup>th</sup> report which includes a functional assessment of the identified wetland areas. The work was conducted on three lots, referenced on the City of Portsmouth assessors' maps as lots 239-13-2, 239-16, and 239-18 which together total approximately 26.15 acres (the Site). The resource areas discussed in this report are depicted on the enclosed sketch.

## WETLAND DELINEATION

The delineation work was performed on November 11, 2023 by Brendan Quigley utilizing the following standards:

1. *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region*, (Version 2.0) January 2012, U.S. Army Corps of Engineers.
2. *Field Indicators of Hydric Soils in the United States, A Guide for Identifying and Delineating Hydric Soils*, Version 8.2. United States Department of Agriculture (2018).
3. *New England Hydric Soils Technical Committee. 2019 Version 4, Field Indicators for Identifying Hydric Soils in New England*. New England Interstate Water Pollution Control Commission, Lowell, MA.
4. *U.S. Army Corps of Engineers National Wetland Plant List, version 3.5*. (2020)

The central part of the Site is a developed commercial property consisting of a large retail building, associated parking areas, and a connector road running between Gosling Road and Arthur Brady Drive. The developed portions of the Site are generally well defined from the surrounding vegetated areas which are a mix of forest, dense early successional shrub growth, and emergent wetland. Wetlands were identified in three main areas east and north of the developed portion of the Site. These were demarcated with seven (7) series of consecutively numbered pink "WETLAND DELINEATION" flagging as shown on the attached sketch. The following table provides a description of each wetland area.

**Table 1—Wetland Descriptions**

| Wetland ID | Cowardin Class <sup>1</sup> | Description/Notes   |
|------------|-----------------------------|---|
| A and C    | PSS1B                       | These two wetlands occupy the area under the power lines in the southeast corner of the Site. They are scrub shrub wetlands with a saturated hydrology, dominated by silky dogwood, willow, and glossy buckthorn. The wetlands are isolated from one another and surrounded by development or roadway. At the time of the delineation timber mats and stabilized access had been installed in and adjacent to the wetlands for power line maintenance activities.   |
| B          | PSS1Kh                      | This small wetland occupies a portion of a constructed stormwater basin. It is otherwise similar to Wetlands A and C.   |
| #1-62      | PSS1E/PFO1E<br>PEM1/5E      | This wetland lies on the west side of the connector road north of the existing development. Much of the wetland lies off-site and is predominantly a cattail/phragmites marsh. The edges of this emergent wetland that lie on the Site are a mix of scrub shrub and forested wetland dominated by speckled alder, common and glossy buckthorn, and red maple. Hydrology of the wetland is seasonally flooded /saturated. The wetland also contains a shallow pond and an old weir structure that appear to be components of legacy drainage system, now nearly indistinguishable from the larger wetland. The wetland drains into Wetland E via a culvert under the connector road. |
| D & E      | PSS1E/PFO1E<br>PEM1/5E      | These two series of flags define two on-site portions of a larger wetland situated under the power lines and extending off-site to the north and east. Like the wetland defined by flags #1-62, to which this area is connected, this is predominantly a cattail and Phragmites marsh with a limited forested and scrub shrub edge.   |
| F          | PEM1/5B                     | This small wetland is essentially the same as D&E but appears to have been purposely separated from the main wetland by construction of a dyke and weir like the one contained in the #1-62 wetland. Though its intended function is not clear this is also likely part of a legacy drainage system.  |

<sup>1</sup> *Classification of Wetlands and Deepwater Habitats of the United States*. USFW Manual FWS/OBS-79/31 (1979)

## OTHER REGULATED WETLAND RESOURCES

The NHDES' web-based Wetlands Permit and Planning Tool (WPPT) was used to identify the presence of other regulated wetland resources such as protected shoreland, prime wetland, and other Priority Resource Areas as defined by NH Administrative Rule Env-Wt 103.66. The planning tool indicates that no such areas are present on the property. A copy of the WPPT map is attached.

The field work for the delineation was conducted in late fall so no formal vernal pool survey was conducted. The large cattail and phragmites marsh wetland (D, E, F, 1-62) that constitutes most of the wetlands on the site is not typically suitable vernal pool habitat. The smaller scrub-shrub wetland (A, B, & C) do not appear to have the topography to maintain a pool. Furthermore, all the wetland on the site exist in a highly developed area with very minimal supporting upland habitat necessary to support vernal pool species. It is therefore very unlikely that any of the wetlands identified on the Site contain vernal pools. This should be verified during the vernal pool breeding season.

## PORTSMOUTH WETLAND PROTECTION ORDINANCE

Section 10.1010 of the Portsmouth Zoning Ordinance regulates wetland resource areas including vegetated wetlands, vernal pools, tidal areas, streams, other surface water, and specific buffers to these resources. The Site only contains inland freshwater wetlands which are regulated under the Ordinance if they are 10,000 square feet in size or greater<sup>2</sup>. Wetlands B and F are 4,594 square feet and 2,442 square feet respectively, so these two small wetlands are not regulated under the Ordinance. Note, however, that these areas are still jurisdictional wetlands subject to state and federal regulation. All other wetlands identified on the Site, and a 100-foot buffer from these areas, are regulated under the Ordinance.

## WETLAND FUNCTION & VALUE ASSESSMENT

A wetland function and value assessment was conducted using the US Army Corps Highway Methodology guidelines. Functions are self-sustaining properties of wetlands, which exist in the absence of human involvement. Values refers to the benefits gained by society from a given wetland or ecosystem and their inherent functions. Functions and values identified as "primary" have been determined to be significant features of the wetland being evaluated. An important distinction is that the primary functions and values of a particular wetland does not necessarily indicate the wetland supports them at a significant *level* in comparison to other wetlands in the region or even near the site.

---

<sup>2</sup> Section 10.1013.10

The Highway Methodology considers 13 functions and values:

- 1. Groundwater recharge/discharge:** This function considers the potential for a wetland to serve as a groundwater recharge and/or discharge area. Recharge should relate to the potential for the wetland to contribute water to an aquifer. Discharge should relate to the potential for the wetland to serve as an area where ground water can be discharged to the surface.
- 2. Floodflow Alteration:** This function considers the effectiveness of the wetland in reducing flood damage by attenuation of floodwaters for prolonged periods following precipitation events.
- 3. Fish and Shellfish Habitat:** This function considers the effectiveness of seasonal or permanent water bodies associated with the wetland in question for fish and shellfish habitat.
- 4. Sediment/Toxicant/Pathogen Retention:** This function reduces or prevents degradation of water quality. It relates to the effectiveness of the wetland as a trap for sediments, toxicants or pathogens.
- 5. Nutrient Removal/Retention/Transformation:** This function relates to the effectiveness of the wetland to prevent adverse effects of excess nutrients entering aquifers or surface waters such as ponds, lakes, streams, rivers or estuaries.
- 6. Production Export:** This function relates to the effectiveness of the wetland to produce food or usable products for human, or other living organisms.
- 7. Sediment/Shoreline Stabilization:** This function relates to the effectiveness of a wetland to stabilize stream banks and shorelines against erosion.
- 8. Wildlife Habitat:** This function considers the effectiveness of the wetland to provide habitat for various types and populations of animals typically associated with wetlands and the wetland edge. Both resident and or migrating species must be considered.
- 9. Recreation:** This value considers the effectiveness of the wetland and associated watercourses to provide recreational opportunities such as canoeing, boating, fishing, hunting and other active or passive recreational activities. Consumptive opportunities consume or diminish the plants, animals or other resources that are intrinsic to the wetland, whereas non-consumptive opportunities do not.
- 10. Educational/Scientific Value:** This value considers the effectiveness of the wetland as a site for an “outdoor classroom” or as a location for scientific study or research.
- 11. Uniqueness/Heritage:** This value relates to the effectiveness of the wetland or its associated water bodies to produce certain special values. Special values may include such things as archeological sites, unusual aesthetic quality, historical events, or unique plants, animals, or geological features.
- 12. Visual Quality/Aesthetics:** This value relates to the visual and aesthetic qualities of the wetland.
- 13. Threatened or Endangered Species Habitat:** This value relates to the effectiveness of the wetland or associated water bodies to support threatened or endangered species.



The collection of individually flagged wetlands on the Site were evaluated in two groups based on their proximity to one another, type, and connectivity. The A and C series wetlands located in the southeast corner of the site were evaluated as one since they lie directly adjacent to one another and share the same characteristics. The D and E series were grouped together with the wetland numbered 1-65 since these three areas are part of a larger wetland extending off-site to the east and separated only by an access driveway. Wetlands B and F are stormwater management features which are too small to be regulated under the Portsmouth Wetlands Protection Ordinance and were not evaluated.

Due to the character of the wetlands and the densely developed setting, several of the functions and values listed above are clearly not supported or are supported to a very limited extent. The lack of permanent or any significant surface water is the most obvious limiting factor. Functions such as fish habitat and shoreline stabilization, which require close association with surface water are not supported in these wetlands. Wetland supported recreation is also strongly linked with surface water for activities such as boating and fishing. Recreational value of this type is not supported but other more passive forms of recreation may be supported to a limited degree depending on how broadly recreation is defined. Aesthetic value is even more subjective, as is value for scientific or educational pursuits. These are traditionally associated with more diverse, unique, and accessible wetlands than those present in this area. In the context of the densely developed area, however, these wetlands provide notable value by providing readily viewable green space amongst developed areas. They may also offer unique educational or scientific opportunities for the study of wetlands in a developed landscape. These values have therefore been considered secondary values supported by all the wetlands on the Site.


The densely developed setting also highlights the importance of certain wetland functions and strongly influences the *Principal Functions* of the wetlands. The most important function of the larger interconnected wetland system (#1-62/D/E) is protection of water quality. This area receives significant runoff from the surrounding developed areas and drains through dense emergent wetlands and restricted outlets. This arrangement provides both sediment trapping, retention, and nutrient transformation function. This is also likely to provide an important flood attenuation function, not as a floodplain, but by intercepting and storing runoff. The smaller wetland areas (A/C) supports these functions to a much lesser degree or not at all due to their limited connectivity.

The long-term effects of performing these water quality functions and overall fragmentation of the wetland in this area does degrade their ecological integrity and suitability for functions as wildlife habitat. However, considering the limited habitat in this developed landscape and the fact that some of the wetlands are quite large, they function as important habitat islands. These areas are likely to be used by numerous avian species and small mammals with limited habitat requirements. The wetter areas in the larger wetlands (#1-62/D/E) may also provide habitat for amphibian and reptile species but this is limited by general lack of permanent water.

The table below summarizes all the identified principle and secondary functions of the two groups of wetlands evaluated. The Highway Methodology data forms are attached.

**Table 2—Wetland Function & Value Summary**

| Wetland ID | Principle Functions/Values   | Secondary Functions/Values  | Justification/Discussion  |
|------------|--|---|---|
| A & C      | Export/Production<br>Wildlife Habitat  | Sediment Retention<br>Nutrient Removal<br>Educational/Scientific<br>Aesthetic | <p>Principle Function is that of a habitat island in the context of a developed landscape. Production for wildlife food sources is enhanced by the dense cover of berry producing shrubs and nectar producing herbaceous vegetation.</p> <p>Water quality has been considered secondary due to lack of connectivity and lack of emergent wetland. Limited Educational/Scientific and Aesthetic value supported in the context of densely developed area.</p>  |
|            | Wildlife Habitat<br>Sediment Retention<br>Nutrient Removal<br>Floodflow Alteration | Groundwater<br>Educational/Scientific<br>Aesthetic                            | <p>Principal water quality function is based on significant urban runoff and diffuse and constricted flow through dense mostly emergent vegetation. Floodflow attenuation by way of storage is derived in a similar way. Principal Wildlife habitat functions is as a habitat island in context of developed landscape.</p> <p>Production for wildlife food sources is considered secondary due to significant areas of invasive or uniform vegetation (Phragmites and Cattail). Limited groundwater interaction in wettest areas but not located in aquafer area. Limited Educational/Scientific and Aesthetic value supported in the context of densely developed area.</p> |



**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK                       | DATE      | DESCRIPTION    |
|----------------------------|-----------|----------------|
| A                          | 4/22/2024 | TAC SUBMISSION |
| PROJECT NO: E5071-001      |           |                |
| DATE: 4/22/2024            |           |                |
| FILE: E5071-001-C-DSGN.dwg |           |                |
| DRAWN BY: BKC/NHW          |           |                |
| DESIGNED/CHECKED BY: NAH   |           |                |
| APPROVED BY: FMC           |           |                |

DEMOLITION PLAN

SCALE: AS SHOWN

Last Saved: 4/19/2024  
 Plotted On: Apr 19, 2024 11:02am By: BJC/ldc  
 Tighe & Bond \\Tighebond.com\data\AutoCAD\Projects\E5071\Sheet\E5071-001-C-DSGN.dwg

SEE SHEET C-101 FOR DEMOLITION PLAN NOTES & LEGEND



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

100 DURGIN  
LANE OWNER,  
LLC

100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE


| MARK | DATE      | DESCRIPTION    |
|------|-----------|----------------|
| A    | 4/22/2024 | TAC SUBMISSION |

PROJECT NO: E5071-001  
 DATE: 4/22/2024  
 FILE: E5071-001-C-DSGN.dwg  
 DRAWN BY: BKC/NHW  
 DESIGNED/CHECKED BY: NAH  
 APPROVED BY: FMC

**DEMOLITION PLAN**

SCALE: AS SHOWN

C-201




Last Saved: 4/19/2024  
 Plotted On: Apr 19, 2024 12:01:50 PM By: BCuroso  
 Tighe & Bond: \\tighebond.com\data\Projects\E\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Sheet\E5071-001-C-DSGN.dwg

SEE SHEET C-101 FOR DEMOLITION  
PLAN NOTES & LEGEND



# Durgin Lane WPPT



## Legend

- Additional Lines
- City/Town
- ▭ Prime Wetlands
- ▭ Prime Wetlands with 100
- ▭ Peatland
- ▨ Flood Plain Wetlands Adj:
- ▨ Marsh-Scrub / Shrub Wet
- Dunes
  - backdune
  - foredune
  - interdune
  - other

Map Scale

1: 6,494

© NH GRANIT, [www.granit.unh.edu](http://www.granit.unh.edu)

Map Generated: 2/29/2024



## Notes

# Wetland Function-Value Evaluation Form

Total area of wetland ~1.1 ac Human made? No Is wetland part of a wildlife corridor? NO or a "habitat island"? YES

Adjacent land use Commercial Development, Elec. Transmission Distance to nearest roadway or other development >100 ft

Dominant wetland systems present PSS1B Contiguous undeveloped buffer zone present No

Is the wetland a separate hydraulic system? Yes If not, where does the wetland lie in the drainage basin? \_\_\_\_\_

How many tributaries contribute to the wetland? isolated Wildlife & vegetation diversity/abundance (see wetland report)

Wetland I.D. A & C













Latitude see report Longitude \_\_\_\_\_

Prepared by: BJQ Date 5/2/24

Wetland Impact:  
Type Buffer Area see plans

Evaluation based on:  
Office Yes Field Yes

Corps manual wetland delineation completed? Y<sup>x</sup> N

| Function/Value  | Suitability<br>Y / N | Rationale<br>(Reference #)* | Principal<br>Function(s)/Value(s) | Comments   |
|---|----------------------|-----------------------------|-----------------------------------|--|
|  Groundwater Recharge/Discharge    | N                    |                             |                                   | <b>wetland is characteristic of perched GW</b>                               |
|  Floodflow Alteration              | N                    |                             |                                   | <b>isolated</b>  |
|  Fish and Shellfish Habitat        | N                    | N/A                         |                                   | <b>No permanent surface water</b>  |
|  Sediment/Toxicant Retention       | Y                    | 1,2,5                       |                                   | potential sources but limited connectivity, minimal function                 |
|  Nutrient Removal                  | Y                    | 3,4,8,9                     |                                   | potential sources but limited connectivity, minimal function                 |
|  Production Export                 | Y                    | 1,7,12                      | X                                 | wildlife food sources in dense berry bearing shrubs and nectar prod. species |
|  Sediment/Shoreline Stabilization | N                    |                             |                                   | <b>not associated with surface water</b>                                     |
|  Wildlife Habitat                | Y                    | 8,19,21                     | X                                 | limited habitat island for songbirds and small mammal                        |
|  Recreation                      | N                    |                             |                                   | Common wetland, subject to transmission line maintenance; low diversity      |
|  Educational/Scientific Value    | Y                    |                             |                                   | limited potential for study of fragmentation and development                 |
|  Uniqueness/Heritage             | N                    |                             |                                   | Common wetland, subject to transmission line maintenance; low diversity      |
|  Visual Quality/Aesthetics       | Y                    |                             |                                   | minimal, open space in context of developed landscape                        |
| <b>ES</b> Endangered Species Habitat  | N                    |                             |                                   | <b>None identified</b>   |
| Other   |                      | N/A                         |                                   | <b>N/A</b>   |

Notes:

\* Refer to backup list of numbered considerations.

# Wetland Function-Value Evaluation Form

Total area of wetland ~20 ac Human made? No Is wetland part of a wildlife corridor? NO or a "habitat island"? YES

Adjacent land use Commercial Development, Elec. Transmission Distance to nearest roadway or other development >100 ft

Dominant wetland systems present PEM1/5E/PSS1E Contiguous undeveloped buffer zone present No

Is the wetland a separate hydraulic system? NO If not, where does the wetland lie in the drainage basin? LOW

How many tributaries contribute to the wetland? UNK Wildlife & vegetation diversity/abundance (see wetland report)

Wetland I.D. #1-62/E/D













Latitude see report Longitude \_\_\_\_\_

Prepared by: BJQ Date 5/2/24

Wetland Impact:  
Type none Area see plans


Evaluation based on:  
Office Yes Field Yes

Corps manual wetland delineation completed? Y<sup>x</sup> N

| Function/Value  | Suitability<br>Y / N | Rationale<br>(Reference #)* | Principal<br>Function(s)/Value(s) | Comments  |
|---|----------------------|-----------------------------|-----------------------------------|---|
|  Groundwater Recharge/Discharge    | Y                    |                             |                                   | <b>some potential in very poorly drained areas</b>  |
|  Floodflow Alteration              | Y                    | 4,5,6,7,15                  | X                                 | significant urban runoff, constricted outlet, large area of storage relative to its watershed |
|  Fish and Shellfish Habitat        | N                    | N/A                         |                                   | <b>No permanent surface water</b>   |
|  Sediment/Toxicant Retention       | Y                    | 1,2,3,4,5,10,12,14,16       | X                                 | Significant sources, diffuse flow though dense vegetation                                     |
|  Nutrient Removal                  | Y                    | 1,3,5,6,7,8,9,11,13,14,15   | X                                 | Significant sources, diffuse flow, long retention time, dense emergent vegetation             |
|  Production Export                 | Y                    | 1,2,7,12,14                 |                                   | high production but limited export, berry and nectar wildlife food sources, low diversity     |
|  Sediment/Shoreline Stabilization | N                    |                             |                                   | <b>not associated with surface water</b>  |
|  Wildlife Habitat                | Y                    | 8,19,21                     | X                                 | part of a larger habitat island for songbirds and small sp. tolerant of proximate devel.      |
|  Recreation                      | N                    |                             |                                   | <b>disturbed wetland, densely developed area</b>  |
|  Educational/Scientific Value    | Y                    |                             |                                   | limited potential for study of fragmentation and development                                  |
|  Uniqueness/Heritage             | N                    |                             |                                   | <b>disturbed wetland, densely developed area</b>  |
|  Visual Quality/Aesthetics       | Y                    |                             |                                   | minimal, open space in context of developed landscape   |
| <b>ES</b> Endangered Species Habitat  | N                    |                             |                                   | <b>None identified</b>  |
| Other   |                      | N/A                         |                                   | N/A   |

Notes:

\* Refer to backup list of numbered considerations.



100 Durgin Lane Multi-Family Development  
Portsmouth, NH

## TRAFFIC IMPACT STUDY

100 Durgin Lane Owner, LLC

May 16, 2024

**Tighe&Bond**



**Section 1 Study Overview**

**Section 2 Existing Conditions**

2.1 Roadways .....2-1

    2.1.1 Woodbury Avenue.....2-1

    2.1.2 Gosling Road .....2-1

    2.1.3 Arthur F Brady Drive .....2-2

    2.1.4 Durgin Lane .....2-2

2.2 Study Area Intersections .....2-2

    2.2.1 Pease Boulevard at US Route 4 Southbound Ramps.....2-2

    2.2.2 Gosling Road at US Route 4 Northbound Ramps.....2-2

    2.2.3 Gosling Road at Woodbury Avenue.....2-3

    2.2.4 Woodbury Avenue at Durgin Lane .....2-3

    2.2.5 Woodbury Avenue at Market Street .....2-3

    2.2.6 Gosling Road at Motel 6/North Site Driveway.....2-4

    2.2.7 Arthur F Brady Drive at South Site Driveway .....2-4

2.3 Traffic Volumes .....2-4

2.4 Capacity and Queue Analyses - Existing Condition .....2-5

2.5 Collision History .....2-6

2.6 Alternative Travel Modes .....2-8

**Section 3 No-Build Conditions**

3.1 Traffic Growth.....3-1

3.2 Capacity and Queue Analyses – No-Build Conditions .....3-1

**Section 4 Proposed Conditions**

4.1 Site Access .....4-3

4.2 Trip Generation .....4-3

4.3 Arrival and Departure Distribution .....4-4

4.4 Multi-Modal Accommodations .....4-4

**Section 5 Build Conditions**

5.1 Capacity and Queue Analyses - Build Condition .....5-1

**Section 6 Conclusions & Recommendations**

**Section 7 Tables**

**Section 8 Figures**

**Technical Appendices (Available Upon Request Under Separate Cover)**

- A. Traffic Count Data
- B. NHDOT Traffic Volume Data
- C. Traffic Volume Adjustment Calculations
- D. Capacity Analysis Methodology
- E. Capacity Analysis Worksheets
- F. COAST & Wildcat Transit Bus Maps
- G. U.S. Census Journey-to-Work Data
- H. Site Development Plan
- I. Background Development Traffic Volumes
- J. Collision History Summary

## **Section 1**

# **Study Overview**

This Traffic Impact Study (TIS) evaluates the potential traffic impact of the proposed residential development located at 100 Durgin Lane, in the City of Portsmouth, New Hampshire. The site is bounded by US Route 4 (Spauling Turnpike) to the west, Hampton Inn and the Home Depot shopping plaza to the south, Motel 6 to the north, and wetlands and Durgin Square shopping plaza to the east. Figure 1 shows the Site location relative to the surrounding roadway network.

The project proposes to demolish the currently vacant retail building, which formerly housed Bed Bath and Beyond and The Christmas Tree Shops, and construct 144 residential units spread across seven three-story buildings and 216 units spread across nine four-story buildings, for a total of 360 units. On-site parking will be provided by surface parking lots on site. Site access will continue to be provided via the three existing full-access driveways: the northern driveway to Gosling Road via the Motel 6 parking lot, the eastern driveway to Durgin Lane, and the southern driveway to Arthur F Brady Drive via the Home Depot shopping plaza driveway. The project is expected to be completed in 2026.

Based on the analyses conducted, it is the professional opinion of Tighe & Bond that the additional traffic expected to be generated by the proposed residential development is not expected to have a significant impact to traffic operations within the study area as compared to the current vacant site condition. Overall, it represents a significant reduction in net trips compared to both the prior retail use and to potential re-leasing of the parcel for retail use.

## **Section 2**

# **Existing Conditions**

The Project site is bounded by US Route 4 (Spaulding Turnpike) to the west, commercial uses to the north and south, and existing wetlands to the east. The property is currently accessible via three full-access driveways. The northern driveway runs adjacent the Motel 6 parking lot to provide an unsignalized access at Gosling Road; the eastern driveway, which becomes Durgin Lane, forms a signalized intersection at Woodbury Avenue; and the southern driveway connects to Arthur F Brady Drive via the Home Depot shopping plaza driveway. The following sections provide details on the adjacent roadways within the study area.

### **2.1 Roadways**

#### **2.1.1 Woodbury Avenue**

Woodbury Avenue is classified as an urban minor arterial from Market Street to Gosling Road and is maintained by the City of Portsmouth. South of the Market Street intersection, Woodbury Road is classified as an urban major collector. The roadway is located east of the site location and primarily runs north-south in the study area. Woodbury Avenue runs from the Spaulding Turnpike interchange in Newington to the north and terminates at an intersection with Bartlett Street in the south.

Within the study area, northbound and southbound traffic are divided by an approximately 10-foot wide raised concrete median. Woodbury Avenue typically provides two travel lanes in each direction with two- to four-foot wide marked shoulders, widening at intersections to provide additional turning lanes. An approximately five- to seven-foot sidewalk is provided along both sides of Woodbury Avenue throughout the entire study area. Woodbury Avenue has a posted speed limit of 30 mph in both directions in the vicinity of Durgin Lane.

#### **2.1.2 Gosling Road**

Gosling Road is classified as an urban major collector west of Woodbury Avenue and a local road east of Woodbury Avenue and is maintained by the City of Portsmouth. The roadway is located north of the site location and runs primarily in the east-west direction connecting US Route 4 (Spaulding Turnpike) on/off ramps to the west and the Granite Shore Power facilities along the Piscataqua River to the east. Eastbound and westbound traffic on Gosling Road is divided by a six-foot wide raised concrete median between the US Route 4 Southbound ramps and Woodbury Avenue; the median opens at The Crossings shopping plaza driveway and Winsor Road to allow for turns.

In the eastbound direction, the roadway begins east of the US Route 4 overpass with four 11-foot travel lanes, with two left turn lanes to the southbound on-ramp and two through lanes. The westbound approach widens from two travel lanes to three lanes with two dedicated through lanes and one shared through and right turn lane. Gosling Road carries two lanes eastbound through the intersection and widens to a four-lane section with two left turn lanes and two through lanes at signalized intersection at The Crossings shopping plaza. East of The Crossings intersection, Gosling has two 11-foot lanes in both the eastbound and westbound directions. East of Woodbury Avenue, Gosling Road provides one 14-foot lane in each direction.

A five-foot sidewalk is provided on the north side of the roadway between the US Route 4 ramps and the Longhorn Steakhouse driveway. A five-foot sidewalk is provided on the south side of the roadway between the Motel 6 driveway and Woodbury Avenue. Marked crosswalks are provided at Wedgewood Road, Winsor Road, and Weald Road. A wide 12-foot paved shoulder is provided for the Gosling Road at Gosling Meadows eastbound bus stop, and a 10-foot wide unpaved shoulder is used for the westbound bus stop.

### **2.1.3 Arthur F Brady Drive**

Arthur F Brady Drive is classified as local roadway and is maintained by the City of Portsmouth. The roadway runs east-west, providing access to and from US Route 4 Northbound (Spaulding Turnpike) at the roadway's western terminus and access to Woodbury Avenue to the east. The roadway generally provides one 15-foot travel lane with a one-to two-foot shoulder in each direction. The eastbound and westbound travel lanes split as they approach US Route 4 and opens to provide a dedicated right turn at the intersection with Woodbury Avenue. An approximately six-foot wide sidewalk is provided on the north side of the roadway between the Woodbury Avenue intersection to the South Site Driveway.

### **2.1.4 Durgin Lane**

Durgin Lane is classified as a local roadway and is maintained by the City of Portsmouth. The roadway runs east-west, beginning at the subject project parcel and ending at a signalized intersection with Woodbury Avenue. The roadway provides one approximately 17' wide travel lane in each direction, widening at the Woodbury Avenue intersection to provide additional turn lanes. Durgin Lane is striped with a painted centerline and no marked shoulders. An approximately five-foot wide sidewalk with a six- to eight-foot grass buffer is provided along the south side of the roadway between the rear entrance of the Durgin Square shopping plaza and Woodbury Avenue.

## **2.2 Study Area Intersections**

### **2.2.1 Pease Boulevard at US Route 4 Southbound Ramps**

Pease Boulevard intersects the US Route 4 Southbound Ramps to the west of the US Route 4 (Spaulding Turnpike) overpass at a signalized intersection, with the southbound off-ramp approaching from the north and the southbound on-ramp departing to the south. The Pease Boulevard westbound approach provides four lanes, with two left-turn lanes and two through travel lanes. The Pease Boulevard eastbound approach consists of five lanes, with four through lanes and one exclusive right-turn lane. The two left-most eastbound through lanes align with the left-turn lanes at the downstream northbound ramp intersection. The southbound off-ramp approach provides four lanes, with two left-turn lanes and two right-turn lanes. Left turn movements from Pease Boulevard westbound and from the southbound off-ramp are controlled with exclusive signal phases. The southbound on-ramp provides two lanes departing from the intersection. As previously described, a sidewalk is provided on the north side of Pease Boulevard through the intersection, with a crosswalk across the southbound off-ramp. A concurrent pedestrian traffic signal phase is provided for this crosswalk. Marked edge lines are provided on all approaches with a 1-to-2-foot offset from the curb or edge of roadway.

### **2.2.2 Gosling Road at US Route 4 Northbound Ramps**

Gosling Road intersects the US Route 4 Northbound Ramps to the east of the US Route 4 (Spaulding Turnpike) overpass at a signalized intersection, with the northbound off-ramp

approaching from the south and the northbound on-ramp departing to the north. The Gosling Road eastbound approach provides four lanes, with two left-turn lanes and two through travel lanes. The Gosling Road westbound approach consists of three lanes, with two through lanes and one shared through/right-turn lane. The left-most westbound through lane aligns with a left-turn lane at the downstream southbound ramp intersection. The northbound off-ramp approach provides four lanes, with two left-turn lanes and two right-turn lanes. Left turn movements from Gosling Road eastbound and from the northbound off-ramp are controlled with exclusive signal phases. The northbound on-ramp provides two lanes departing from the intersection. As previously described, a sidewalk is provided on the north side of Gosling Road through the intersection, with a crosswalk across the northbound on-ramp. A concurrent pedestrian traffic signal phase is provided for this crosswalk. Marked edge lines are provided on all approaches with a 1-to-2-foot offset from the curb or edge of roadway.

### **2.2.3 Gosling Road at Woodbury Avenue**

Gosling Road intersects Woodbury Avenue from the east and west to form a four-way signalized intersection. The eastbound approach provides a dedicated right turn lane and a shared through and left turn lane. The westbound approach provides one all-purpose lane. The northbound approach provides dual left turn lanes, one through lane, and a shared through and right turn lane. The southbound approach provides dedicated right and left turn lanes and two through lanes. The north, south, and west legs are divided by a raised concrete median. Protected only left turn phasing is provided on the northbound and southbound approaches. The eastbound and westbound approaches operate under split phasing. A right turn overlap is provided on the eastbound and southbound approaches.

Sidewalks are provided at all four intersection corners and marked crosswalks are provided across all intersection legs. An exclusive pedestrian phase is provided for the intersection.

### **2.2.4 Woodbury Avenue at Durgin Lane**

Woodbury Avenue runs north-south and is intersected by Durgin Lane to the west and BJ's Driveway from the east to form a four-way signalized intersection. The eastbound and westbound approaches each provide a dedicated right turn lane, shared through and left turn lane, and a dedicated left turn lane. The northbound and southbound approaches both provide a dedicated right turn lane, two through lanes, and a dedicated left turn lane. Marked edge lines are provided only on the southbound and westbound approaches with a 1-to-2-foot offset from the curb. All intersection legs are divided by a raised concrete median. Protected only left turn phasing is provided on the northbound and southbound approaches. The eastbound and westbound approaches operate under split phasing. A right turn overlap is provided on all approaches.

Sidewalks are provided at all four intersection corners and marked crosswalks are provided across all intersection legs. An exclusive pedestrian phase is provided for the intersection.

### **2.2.5 Woodbury Avenue at Market Street**

Woodbury Avenue becomes Market Street at its intersection with the Market Basket driveway, while Woodbury Avenue turns to the south, all meeting to form a four-way signalized intersection. Woodbury Avenue forms the north and west legs, Market Street forms the south leg, and the Market Basket driveway forms the east leg. The southbound approach provides a dedicated right turn lane, two through lanes, and a

dedicated left turn lane. The eastbound approach provides a shared right turn and through lane and two dedicated left turn lanes. The northbound approach provides a shared through and right turn lane, a through lane, and a dedicated left turn lane. The westbound approach provides a shared right and through lane and a dedicated left turn lane. The north, south, and west legs are divided by a raised concrete median while the east leg is divided by a raised median with landscaping. Marked edge lines are provided on all approaches with a 1-to-2-foot offset from the curb. Protected only left turn phasing is provided on the eastbound and westbound approaches. A right turn overlap is provided on the eastbound approach. The northbound and southbound approaches operate under split phasing.

Sidewalks are provided at all four intersection corners with marked crosswalks provided across all intersection legs. An exclusive pedestrian phase is provided for the intersection.

### **2.2.6 Gosling Road at Motel 6/North Site Driveway**

The north site driveway provides primary access to Motel 6 and New Frontiers Church while also extending to the existing retail uses on site. The driveway intersects Gosling Road from the south, with a raised median prohibiting turns to and from Gosling Road westbound to provide right-in/ right-out access only. Gosling Road eastbound provides four lanes of through traffic at the driveway. The driveway approach provides a separate channelized entrance and exit lane separated by a raised landscaped island. No signage is provided on the driveway approach. However, the driveway presumably operates under stop/ yield control. A sidewalk is provided along the north side of Gosling Road and on the south side of Gosling Road, beginning at the Motel 6/North Site Driveway and continuing east. No sidewalk is provided along the site driveway.

### **2.2.7 Arthur F Brady Drive at South Site Driveway**

Arthur F Brady Drive runs primarily east-west and is intersected by the existing Home Depot/ South Site Driveway from the north to form a three-way intersection with the driveway operating under stop control.

Arthur F Brady Drive provides an all-purpose travel lane in both the eastbound and westbound directions. A channelized right turn lane under yield control is provided on the westbound approach. Westbound vehicles entering the site must yield to vehicles entering the site from the Spaulding Turnpike off-ramp. The South Site Driveway provides a dedicated left turn lane and a dedicated right turn lane. There is a marked crosswalk across the south leg of the intersection on both the stop controlled and channelized leg of the intersection which connects the sidewalk on the north side of Arthur F Brady Drive to the sidewalk located along the west side of the South Site Driveway.

## **2.3 Traffic Volumes**

Turning movement counts (TMC) were collected at the study area intersections on Wednesday, March 20, 2024, during the weekday morning (7:00 AM to 9:00 AM) and weekday afternoon peak periods (4:00 PM to 6:00 PM) and on Saturday, March 23, 2024, during the Saturday midday peak period (11:00 AM to 2:00 PM). Automatic Traffic Recorder (ATR) counts were collected on Woodbury Avenue between the intersection with Gosling Road and Durgin Lane during a 48-hour period from Wednesday, March 20, 2024, thru Thursday, March 21, 2024, concurrently with the TMC to record hourly traffic volumes and vehicular speeds.

Based on current NHDOT guidance, 2024 traffic volumes were compared to 2019 traffic volumes to determine if adjustments to the collected traffic volumes should be made to account for pandemic-related impacts to daily traffic volumes. The City of Portsmouth provided continuous TMC data for the intersection of Lafayette Road and South Street, which is located approximately 2.5 miles southeast of the Project study area. Localized data from a commercial corridor on Lafayette Road was determined to be more applicable to the study area as compared to permanent count station data maintained by NHDOT on I-95 and Spaulding Turnpike.

The average peak hour traffic volumes from Tuesday to Thursday during the same week in March 2019 and March 2024 were used as a basis for comparison for weekday morning and weekday afternoon peak periods; Saturday traffic volumes during the same day in March 2019 and March 2024 was used as a basis of comparison for the Saturday midday peak period. The review shows weekday morning traffic volumes in March 2024 were 1% higher on average as compared to the same period in March 2019. A review of the afternoon peak hour traffic volumes indicates March 2024 traffic volumes were on average 9% lower as compared to 2019 traffic volumes. The Saturday midday peak hour traffic volumes were approximately 33% lower in March 2024 as compared to March 2019. Based on the traffic volume comparison, no pandemic-related adjustment was made to the weekday morning peak period. However, because the weekday afternoon and Saturday midday peak periods traffic volumes were found to be lower in March 2024 as compared to March 2019, the existing traffic volume volumes were adjusted upward by 9% and 33%, respectively.

The ATR data from Woodbury Avenue indicated average daily traffic (ADT) of approximately 7,000 vehicles per day in the northbound direction and 9,100 vehicles per day in the southbound direction. The measured 85<sup>th</sup> percentile speeds, also known as the operating speed of the roadway, were approximately 35 mph and 33 mph in the northbound and southbound directions, respectively, slightly exceeding the posted 30 mph limit

The weekday morning, weekday afternoon, and Saturday midday turning movement counts were seasonally adjusted to a peak month per NHDOT guidelines. A seasonal adjustment factor of 1.15 was applied to the traffic volumes based on Group 4 Averages: Urban Highways for the month of March. The adjusted 2024 existing traffic volumes for the weekday morning, weekday afternoon, and Saturday midday peak hours are shown in Figure 2. The raw TMC data and ATR data are provided in Appendix A. The NHDOT seasonal adjustment factors are enclosed in Appendix B. The traffic volume adjustment factor calculation and City of Portsmouth traffic volume data is provided in Appendix C.

## 2.4 Capacity and Queue Analyses - Existing Condition

Capacity and queue analyses were performed for the study intersections for the 2024 Existing Conditions during the weekday morning, weekday afternoon, and Saturday midday peak hours. Analyses were conducted using Trafficware Synchro Studio 11 software, which conducts the analysis based on *Highway Capacity Manual (HCM)* methodology. Consistent with NHDOT guidelines, analyses for signalized intersections were conducted using methods of the 2000 HCM, while analysis for unsignalized intersections utilized the HCM 6<sup>th</sup> Edition methodology. The analysis results are categorized in terms of Level of Service (LOS), which describes the qualitative intersection operational conditions based on the calculated average delay per vehicle. A



summary of the HCM capacity analysis methodology and a detailed definition of LOS is provided in Appendix D. The queue analysis results are summarized based upon the length of vehicle queueing on an intersection approach. For unsignalized intersections, queues are quantified for 95<sup>th</sup> percentile (design queues). For signalized intersections, queues are quantified by 95<sup>th</sup> percentile (design) and 50<sup>th</sup> percentile (average) queues. Tables 1 and 2 in Section 7 summarize the capacity and queue analyses results, respectively. Capacity analysis worksheets with full inputs, settings, and results are provided in Appendix E.

As shown in Table 1, all of the overall intersections and a majority of the individual intersection approaches operate at acceptable at LOS D or better during the peak hours with the following exceptions:

- **Gosling Road at Woodbury Avenue**
  - The southbound left turn movement onto Gosling Road operates at LOS E during the weekday morning and afternoon peak hour.
  - The eastbound shared through and left turn movement operates at LOS F during the weekday afternoon peak hour.
- **Woodbury Avenue at Market Street**
  - The eastbound shared through and right turn movement operates at LOS E during the weekday afternoon peak.

A review of the queueing results in Table 2 shows design queues on all study intersection movements are accommodated within the available storage within turn bays and between intersections during each peak period.

## 2.5 Collision History

Vehicle collision data between January 2021 and December 2023 was obtained from the Portsmouth Police Department at the study intersections. Table 3 provides a summary of the reported collisions within the study area including type, severity, day and time, and location. Appendix J includes detailed collision summaries for each of the study intersections with reported collisions.

As shown in Table 3, there were 24 motor vehicle collisions reported in the study area during the three-year period analyzed. Crashes most frequently occurred at the Woodbury Avenue and Gosling Road intersection with eight total collisions and accounting for about 33% of the reported total. The Woodbury Avenue and Durgin Lane intersection and the Woodbury Avenue and Market Street intersection are tied for the next highest number of collisions, with five collisions representing about 20% of the total crashes each. The intersections of Pease Boulevard at US Route 4 Southbound Ramps and Gosling Road at US Route 4 Northbound Ramps had the remaining crashes with two and four crashes, respectively. Both the North Site Driveway and South Site Driveway intersections experienced zero reported collisions in the time period analyzed.

The most frequent type of collision was angle, accounting for about 38% of total collisions within the study area. The second most frequent type was rear-end which made up about 33% of the total collisions. The third most frequent type of collision was sideswipe, same direction making up about 17% of total collisions. The remainder of

collisions were single vehicle crashes and fixed object crashes. Three of the 24 collisions resulted in personal injury.

About 71% of the collisions occurred on weekdays, with a majority occurring outside of the study peak hour time periods. Weather and roadway conditions at the time of the collisions were not able to be determined from the police reports.

The collision data indicates no reported fatalities and three collisions with suspected minor injuries. The remaining crashes resulted in property damage only. There were no reported fatalities.

**TABLE 3**  
Study Area Crash History Summary

| <b>COLLISION TYPE</b>     | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------------------|-------------|-------------|-------------|--------------|----------------|
| Angle                     | 3           | 1           | 5           | <b>9</b>     | <b>37.5%</b>   |
| Rear-End                  | 3           | 3           | 2           | <b>8</b>     | <b>33.3%</b>   |
| Sideswipe, Same Direction | 0           | 1           | 3           | <b>4</b>     | <b>16.7%</b>   |
| Fixed Object              | 0           | 2           | 0           | <b>2</b>     | <b>8.3%</b>    |
| Single Vehicle Crash      | 1           | 0           | 0           | <b>1</b>     | <b>4.2%</b>    |
| <b>TOTAL</b>              | <b>7</b>    | <b>7</b>    | <b>10</b>   | <b>24</b>    | <b>100%</b>    |

| <b>SEVERITY</b>            | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|----------------------------|-------------|-------------|-------------|--------------|----------------|
| Personal Injury            | 0           | 1           | 2           | <b>3</b>     | <b>12.5%</b>   |
| Property Damage Only (PDO) | 7           | 6           | 8           | <b>21</b>    | <b>87.5%</b>   |
| <b>TOTAL</b>               | <b>7</b>    | <b>7</b>    | <b>10</b>   | <b>24</b>    | <b>100%</b>    |

| <b>DAY &amp; TIME</b>     | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------------------|-------------|-------------|-------------|--------------|----------------|
| Weekday Off-Peak          | 2           | 3           | 7           | <b>12</b>    | <b>50.0%</b>   |
| Weekend Off-Peak          | 2           | 2           | 0           | <b>4</b>     | <b>16.7%</b>   |
| Weekday 3-6 P.M.          | 1           | 1           | 1           | <b>3</b>     | <b>12.5%</b>   |
| Saturday 11 A.M. - 2 P.M. | 2           | 0           | 1           | <b>3</b>     | <b>12.5%</b>   |
| Weekday 6-9 A.M.          | 0           | 1           | 1           | <b>2</b>     | <b>8.3%</b>    |
| <b>TOTAL</b>              | <b>7</b>    | <b>7</b>    | <b>10</b>   | <b>24</b>    | <b>100%</b>    |

| <b>CRASHES BY STUDY AREA INTERSECTION</b> | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---|-------------|-------------|-------------|--------------|----------------|
| Woodbury Avenue at Gosling Road           | 0           | 4           | 4           | <b>8</b>     | <b>33.3%</b>   |
| Woodbury Avenue at Durgin Lane            | 2           | 2           | 1           | <b>5</b>     | <b>20.8%</b>   |
| Woodbury Avenue at Market Street          | 1           | 0           | 4           | <b>5</b>     | <b>20.8%</b>   |
| Gosling Road at US Route 4 NB Ramps       | 2           | 1           | 1           | <b>4</b>     | <b>16.7%</b>   |
| Pease Boulevard at US Route 4 SB Ramps    | 2           | 0           | 0           | <b>2</b>     | <b>8.3%</b>    |
| <b>TOTAL</b>                              | <b>7</b>    | <b>7</b>    | <b>10</b>   | <b>24</b>    | <b>100%</b>    |

## 2.6 Alternative Travel Modes

The study area is in a moderately densely developed setting in the City of Portsmouth where many multimodal travel options are available. The following summarizes the details of various alternative travel modes supported within the study area.

Pedestrian facilities are present intermittently throughout the study area. Existing sidewalks are present on both sides of Woodbury Avenue and Market Street within the study area. There is a sidewalk on the north side of Gosling Road from the study area limit at between the US Route 4 Southbound Ramps and the Longhorn Steakhouse driveway and on the south side of Gosling Road from the Motel 6/North Site Driveway east until the Woodbury Avenue intersection. A marked crosswalk is provided across the US Route 4 Southbound Off-Ramp and the US Route 4 Northbound On-Ramp and serviced by a concurrent pedestrian phase. Marked crosswalks are provided across all legs of the Woodbury Avenue/Gosling Road, Woodbury Avenue/Durgin Lane, and Woodbury Avenue/Market Street intersections, each providing an exclusive pedestrian phase. A sidewalk is provided on the south side of Durgin Lane between Woodbury Avenue and the Whole Foods shopping plaza.

The Cooperative Alliance for Seacoast Transportation (COAST) provides transit service within the study area. Bus Route 43 is the primary bus route in the study area with stops along Woodbury Avenue and Gosling Road between Hanover Station to the south and Fox Run Mall to the north. Two existing bus stops are located within the project study area: one stop is located at Gosling Meadows approximately 800 feet west of the Woodbury Avenue/Gosling Road intersection; the other stop is located at Starbucks along Woodbury Avenue approximately 800 feet south of the Woodbury Avenue/Gosling Road intersection. The route operates from 6:30 AM to 8:57 PM Monday through Saturday. The Route 43 map and schedule are included in Appendix F.

The University of New Hampshire (UNH) operates Wildcat Transit which provides transit service in the area for UNH students. Bus Route 4 runs from UNH Durham Campus to Portsmouth Market Square and utilizes COAST Bus Route 43 stops previously described. The route operates from 6:40 AM to 10:49 PM on weekdays and from 11:35 AM to 10:33 PM on weekends during the school semester. During school breaks, the bus operates on a reduced service schedule with the route operating from 6:40 AM to 5:53 PM on weekdays only. The Route 4 map and schedules are included in Appendix F.

## Section 3

# No-Build Conditions

The No-Build Condition represents the projection of traffic volumes and operating conditions without the anticipated additional site generated traffic. Consistent with NHDOT guidelines, the study area is analyzed for an Opening Year (2026) and Design Year (2036). This section describes the growth and development considerations included in the 2026 and 2036 No-Build traffic volumes.

### 3.1 Traffic Growth

To develop the traffic volumes for the 2026 and 2036 No-Build Conditions, the 2024 Existing traffic volumes were grown by one percent per year to represent the general growth of traffic on the study area roadways. This growth rate is consistent with the average growth rate in NHDOT Region E - Southeast, the region in which Portsmouth is located. Background NHDOT growth data is included in Appendix B.

NHDOT, the City of Portsmouth, and the Pease Development Authority were contacted about other planned/approved developments in the area that may add new traffic to the study area prior to 2026. The following developments were identified:

- **100 New Hampshire Avenue:** The project proposes to construct a 100,000+/- square foot distribution facility in the Pease Tradeport area. The project has been approved and is anticipated to be occupied in 2024. Estimated site traffic volumes outlined in the project's Traffic Impact Assessment are included in the development of the 2026 and 2036 No-Build traffic volumes.
- **70 & 80 Corporate Drive (Lonza Biologics):** The project proposes to construct an approximately 800,000+/- square foot industrial facility on Corporate Drive in the Pease Tradeport area. The project is estimated to be complete and occupied in 2025. Estimated site traffic volumes outlined in the project's TIA are included in the 2026 and 2036 No-Build traffic volumes.

It is assumed that other smaller developments or small vacancies in existing developments are also captured by the background traffic growth rate. The 2026 and 2036 No-Build traffic volumes for the weekday morning, weekday afternoon, and Saturday midday peak hours are shown in Figures 3 and 4, respectively.

### 3.2 Capacity and Queue Analyses – No-Build Conditions

Capacity and queue analyses were conducted for the 2026 and 2036 No-Build Conditions traffic volumes for all peak periods using the methodology described in Section 2.4. Tables 1 and 2 in Section 7 summarize the capacity and queue results, respectively. Capacity analysis worksheets with full inputs, settings, and results are provided in Appendix E.

The increase in expected future traffic based on the one percent per year compounded growth rate and background development traffic volumes that were added to the existing 2024 traffic volumes resulted in some degradation in LOS of operations when compared to existing conditions for the 2026 No-Build Condition. The following

intersections showed degradation in level of service when comparing the 2026 No-Build Condition from the existing conditions:

- **Pease Boulevard at US Route 4 Southbound Ramps**

- The southbound right turn movement onto Pease Boulevard degrades from LOS D to LOS E during the weekday morning peak hour in 2026.

The 2036 No-Build Condition resulted in more substantial increases in degradation of level of service and increases in delay when compared to the 2026 No-Build Condition due to the addition of ten years of compounded annual growth. The following intersections showed additional degradation of operations from the 2026 to 2036 No-Build Condition:

- **Pease Boulevard at US Route 4 Southbound Ramps**

- The southbound right turn movement onto Pease Boulevard degrades from LOS E to LOS F during the weekday morning peak hour in 2036.

- **Gosling Road at US Route 4 Northbound Ramps**

- The northbound left turn movement onto Gosling Road degrades from LOS D to LOS E during the weekday morning peak hour in 2036.

- **Woodbury Avenue at Market Street**

- The eastbound shared through and right turn movement degrades from LOS E to LOS F during the weekday afternoon peak hour in 2036.
- The southbound left turn movement from Woodbury Avenue into the Market Basket driveway degrades from LOS D to LOS E during the Saturday midday peak hour in 2036.

Design queues continue to be accommodated within available storage in the 2026 No-Build condition. A majority of design queues increased by two vehicle lengths or less at all intersection approaches or less between the existing and 2026 No-Build conditions. While some intersections experience increases in design queue length of greater than two vehicle lengths in 2036 due to the compounded annual growth rate and approved developments in the area, design queues in 2036 are predicted to remain within available storage as shown in Table 2.

## Section 4 Proposed Conditions

The project proposes to demolish the currently vacant retail building, which formerly housed Bed Bath and Beyond and The Christmas Tree Shops, and construct 144 residential units spread across seven three-story buildings and 216 units spread across nine four-story buildings, for a total of 360 units. On-site parking will be provided by surface parking lots on site with approximately 567 spaces. The proposed development is expected to be complete and occupied in 2026. The Site Plan is presented in Appendix H.

### 4.1 Site Access

Site access will continue to be provided via the three existing full-access driveways: the northern driveway to Gosling Road via the Motel 6 parking lot, the eastern driveway to Durgin Lane, and the southern driveway to Arthur F Brady Drive via the Home Depot shopping plaza driveway. Four separate access points within the site will provide access to the existing driveway running north to south between Gosling Road and Arthur F Brady Drive that will remain as part of the project. One new site access point opposite Durgin Lane will intersect the existing north-south driveway to create a four-way intersection controlled by an all-way stop. The remaining three access driveways will be controlled on the minor site driveway access under stop control. Each driveway is positioned to maximize sight lines. Internal driveways will allow access to the various buildings and parking areas throughout the site.

### 4.2 Trip Generation

Trips expected to be generated by the proposed development were estimated using the Institute of Transportation Engineers (ITE) Trip Generation, 11<sup>th</sup> Edition, 2021. Multifamily Housing (Low-Rise) (LUC-220) and Multifamily Housing (Mid-Rise) (LUC-221) were used to estimate vehicle trips based on the current development program, which proposes 144 units in seven three-story buildings and 216 units in nine four-story buildings.

Based on the ITE data, the proposed development is estimated to generate 151 trips (35 entering, 116 exiting) during the weekday morning peak hour, 167 trips (104 entering, 63 exiting) during the weekday afternoon peak hour, and 146 trips (74 entering, 72 exiting) during the Saturday midday peak hour. Table 4 provides a detailed summary of the trip generation.

While the study evaluates new trips to the study area network because the retail building to be demolished was vacant at the time of the existing data collection for the study, the overall impact on the study area should consider the prior site use to determine the net increase on trips experienced over the study area. Bed Bath and Beyond and Christmas Tree Shops ceased operations on site in May 2023 and July 2023, respectively. Trips assumed to be generated by the prior use were estimated using ITE LUC 821 (Shopping Plaza) and compared to new trips estimated to be generated by the residential redevelopment. Based on the ITE data, the net impact on the site is a slight increase in trips in the weekday morning peak hour, a decrease in trips in the weekday afternoon and Saturday midday peak hours, and an overall decrease in weekday and Saturday daily trips. The net new trips are 16 trips (decrease of 49 entering, increase of

65 exiting) during the weekday morning peak hour, a decrease of 239 trips (95 entering, 144 exiting) during the weekday afternoon peak hour, and a decrease of 341 trips (179 entering, 162 exiting) during the Saturday midday peak hour. Table 5 provides a comparison of net site trips to be generated. Both the prior use and re-leasing of the currently vacant parcel for retail use would have greater impact on the study area network than the proposed residential use.

### 4.3 Arrival and Departure Distribution

The distribution of the proposed site-generated traffic entering and exiting the Site was applied to the roadway network based on existing traffic patterns within the study area as well as a review of US Census Journey-to-Work data which is included in Appendix G. The following arrival/departure distributions are anticipated:

- 30% to/ from the South to Portsmouth Center via Market Street/ Woodbury Avenue
- 25% to/ from the South via US Route 1 Bypass
- 20% to/ from the North via US Route 4 (Spaulding Turnpike)
- 20% to/ from the South to I-95 South
- 5% to/ from the North to I-95 North

Based on the regional distribution and surrounding roadway network, it is estimated that that half (10%) of departing vehicles destined for I-95 South will exit the site via the Durgin Lane driveway to access Spaulding Turnpike via Woodbury Avenue and Gosling Road, while the remaining 10% will travel to I-95 South via Woodbury Avenue. In addition, it is estimated the exiting site traffic destined for US Route 1 Bypass and I-95 South will utilize Woodbury Avenue when departing the site, while traffic arriving to the site is estimated to enter directly from Spaulding Turnpike via Arthur F Brady Drive for traffic originating from US Route 1 Bypass, and via the off-ramp at Gosling Road for traffic originating from I-95 to the south.

Figure 5 presents the arrival and departure distributions of the traffic through the study area by intersection movement. Figure 6 shows the proposed site generated traffic distributed to the study area roadways for the weekday morning, weekday afternoon peak periods, and Saturday midday peak periods.

### 4.4 Multi-Modal Accommodations

Pedestrian, bicycle, and transit facilities are provided on site and to connect to the surrounding networks. Internal sidewalks are proposed adjacent to all parking areas and buildings on site. Sidewalks are proposed along the north side of Durgin Lane to ultimately connect via a midblock crossing to the existing sidewalk located along the south side of the roadway. The existing and proposed sidewalk network will provide a continuous network to the existing bus stops located on Woodbury Avenue. In addition, indoor bicycle storage will be provided on site.

---

## Section 5

# Build Conditions

The anticipated site generated traffic volumes associated with the proposed development were added to the 2026 and 2036 No-Build Conditions traffic volumes to develop the 2026 and 2036 Build Conditions traffic volumes, which are presented in Figures 7 and 8, respectively.

### 5.1 Capacity and Queue Analyses - Build Condition

Capacity and queue analyses were conducted for the 2026 and 2036 Build Conditions for the peak hours using the methodology described in Section 2.4. Tables 1 and 2 in Section 7 summarize the capacity and queue results, respectively. Capacity analysis worksheets with full inputs, settings, and results are provided in Appendix E.

All the study area intersections and a majority of the individual intersection approaches continue to operate at acceptable LOS D or better during the peak hours in the 2026 and 2036 Build Conditions. All study area intersections that were identified in Section 2.4 and 3.2 to operate at LOS E or LOS F in the 2026 No-Build Conditions continue to operate at the same LOS under 2026 Build Conditions. The study area intersections identified to operate at LOS E or LOS F in the 2036 No-Build Conditions continue to operate at the same LOS under the 2036 Build Conditions, with the exception of the following:

- **Gosling Road and US Route 4 Northbound Ramps**

- The eastbound left turn movement from Gosling Road is predicted to degrade from LOS D to LOS E during the weekday afternoon peak hour.

Design queues on all intersection approaches for the Build Conditions increased by less than two vehicle lengths or experience increases in design queues that are accommodated within available storage when compared to 2026 and 2036 No-Build Conditions with the exception of the following:

- **Gosling Road and Woodbury Avenue**

- The northbound left turn is predicted to exceed the available storage by approximately one vehicle length during the weekday afternoon peak hour. This is an increase of less than one vehicle length compared to the 2036 No-Build Condition.



## **Section 6**

# **Conclusions & Recommendations**

1. The project proposes to construct 360 residential units spread over a mix of 16 three- and four-story buildings. Surface parking lots will be provided throughout the Site, totaling approximately 567 parking spaces. The development is expected to be complete and occupied in 2026.
2. Access to the site will be provided via the three existing driveways on Gosling Road (unsignalized), Durgin Lane (signalized), and Arthur F Brady Drive (unsignalized). A series of internal driveways will provide access to buildings and parking areas within the development.
3. Overall, the proposed redevelopment represents a significant reduction in net trips compared to the prior retail use. Based on the previous retail use on site, which was occupied by Bed Bath and Beyond and Christmas Tree Shops until mid-2023, the net impact on the site compared to the prior use (or compared to re-leasing the parcel for retail use) is a slight increase in trips in the weekday morning peak hour, a decrease in trips in the weekday afternoon and Saturday midday peak hours, and an overall decrease in weekday and Saturday daily trips. The net new trips are 16 trips (decrease of 49 entering, increase of 65 exiting) during the weekday morning peak hour, a decrease of 239 trips (95 entering, 144 exiting) during the weekday afternoon peak hour, and a decrease of 341 trips (179 entering, 162 exiting) during the Saturday midday peak hour.
4. In comparison of the proposed project compared to the current vacant building and based on the ITE data, the project is expected to generate 151 trips (35 entering, 116 exiting) during the weekday morning peak hour, 167 trips (104 entering, 63 exiting) during the weekday afternoon peak hour, and 146 trips (74 entering, 72 exiting) during the Saturday midday peak hour.
5. The project proposes internal sidewalk connections throughout the site as well as a new connection to the existing sidewalk along Durgin Lane to promote a pedestrian connection to the areas that are anticipated to generate pedestrians.
6. Vehicle collision history, compiled from local police reports, do not indicate a significant or notable pattern of collisions in the study area.
7. Consistent with NHDOT guidelines, existing traffic volumes have been seasonally adjusted to the peak month condition. A review of 2024 and 2019 data provided by the City of Portsmouth revealed stagnant volumes during the weekday morning peak hour in 2024 and lower traffic volumes in 2024 as compared to 2019 in the weekday afternoon and Saturday midday peak periods; therefore, the weekday afternoon and Saturday midday peak periods were adjusted to reflect a pre-pandemic condition. As such, the existing weekday afternoon and Saturday midday traffic volumes represent a conservative estimate, by increasing volumes collected under actual 2024 conditions to an assumed pre-pandemic peak.
8. The capacity analyses show that the study area intersections will generally continue to operate at the same LOS under Build Conditions as compared to the No-Build Conditions for both the 2026 opening year and 2036 design year, except for the

Gosling Road and US Route 4 Northbound ramp intersection which experiences a degradation in LOS from D to E in 2036 during the weekday afternoon peak period, but only an increase in delay of one second. A review of design queues indicates minor increases of two vehicles or less in the 2026 and 2036 Build Conditions compared to the corresponding No Build Conditions with the exception of the Gosling Road intersection which see design queues exceed available storage by one vehicle length in 2036 during the weekday afternoon peak hour, but only an increase in design queue length of one vehicle length compared to the 2036 No-Build Condition.

9. The recent vacancy of the former retail uses on site coupled with the recent traffic signal upgrades at the study intersections along Woodbury Avenue provide adequate capacity at the Woodbury Avenue study intersections under Existing, No-Build, and Build Conditions.
10. Based on the results of the foregoing analysis, it is the professional opinion of Tighe & Bond that the addition of site-generated traffic is expected to have a negligible effect on traffic operations within the study area as compared to the current vacant site condition. Overall, it represents a significant reduction in net trips compared to both the prior retail use and to potential re-leasing of the parcel for retail use.

## **Section 7 Tables**

**TABLE 1**  
Intersection Operation Summary - Capacity

|  |      | Weekday Morning Peak Hour |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
|--|------|---------------------------|-------------|-------------|---------------|-------------|-------------|------------|-------------|-------------|---------------|-------------|-------------|------------|-------------|-------------|
| Lane Use   |      | 2024 Existing             |             |             | 2026 No-Build |             |             | 2026 Build |             |             | 2036 No-Build |             |             | 2036 Build |             |             |
|  |      | LOS                       | Delay       | V/C         | LOS           | Delay       | V/C         | LOS        | Delay       | V/C         | LOS           | Delay       | V/C         | LOS        | Delay       | V/C         |
| <b>Traffic Signal - Pease Boulevard at US Route 4 Southbound Ramps</b>                 |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                  | <b>26.7</b> | <b>0.76</b> | <b>C</b>      | <b>34.2</b> | <b>0.97</b> | <b>C</b>   | <b>34.5</b> | <b>0.97</b> | <b>D</b>      | <b>51.4</b> | <b>1.14</b> | <b>D</b>   | <b>51.7</b> | <b>1.14</b> |
| Pease Boulevard  | EBT  | C                         | 25.3        | 0.12        | C             | 25.2        | 0.15        | C          | 25.1        | 0.15        | C             | 25.3        | 0.16        | C          | 25.2        | 0.16        |
|  | EBR  | C                         | 24.9        | 0.06        | C             | 24.7        | 0.07        | C          | 24.6        | 0.07        | C             | 24.7        | 0.08        | C          | 24.7        | 0.08        |
|  | WBL  | C                         | 23.4        | 0.12        | C             | 24.1        | 0.13        | C          | 24.7        | 0.14        | C             | 24.1        | 0.14        | C          | 24.8        | 0.16        |
| US Route 4 Southbound Off Ramp   | WBT  | B                         | 16.7        | 0.46        | B             | 16.8        | 0.50        | B          | 16.5        | 0.50        | B             | 17.4        | 0.54        | B          | 17.2        | 0.54        |
|  | SBL  | C                         | 31.2        | 0.51        | C             | 32.6        | 0.53        | C          | 33.0        | 0.54        | C             | 34.7        | 0.60        | D          | 35.2        | 0.61        |
|  | SBT  | C                         | 31.2        | 0.51        | C             | 32.6        | 0.53        | C          | 33.0        | 0.55        | C             | 34.7        | 0.60        | D          | 35.3        | 0.61        |
|  | SBR  | D                         | 37.1        | 0.76        | E             | 60.5        | 0.97        | E          | 61.6        | 0.97        | F             | 114.4       | 1.14        | F          | 115.7       | 1.14        |
| <b>Traffic Signal - Gosling Road at US Route 4 Northbound Ramps</b>                    |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                  | <b>32.1</b> | <b>0.78</b> | <b>C</b>      | <b>33.3</b> | <b>0.86</b> | <b>C</b>   | <b>33.3</b> | <b>0.86</b> | <b>D</b>      | <b>38.6</b> | <b>0.95</b> | <b>D</b>   | <b>38.8</b> | <b>0.95</b> |
| Gosling Road   | EBL  | C                         | 21.0        | 0.08        | C             | 20.2        | 0.12        | C          | 20.1        | 0.12        | B             | 17.6        | 0.12        | B          | 17.5        | 0.12        |
|  | EBT  | D                         | 38.7        | 0.57        | D             | 36.7        | 0.57        | D          | 36.8        | 0.58        | D             | 38.2        | 0.62        | D          | 38.4        | 0.63        |
|  | WBTR | B                         | 18.3        | 0.16        | B             | 18.2        | 0.18        | B          | 18.2        | 0.19        | C             | 20.4        | 0.22        | C          | 20.4        | 0.22        |
| US Route 4 Northbound Off Ramp   | NBL  | D                         | 37.0        | 0.78        | D             | 42.5        | 0.86        | D          | 42.8        | 0.86        | E             | 55.2        | 0.95        | E          | 55.9        | 0.95        |
|  | NBT  | C                         | 26.1        | 0.09        | C             | 27.0        | 0.10        | C          | 27.2        | 0.10        | C             | 27.6        | 0.11        | C          | 27.8        | 0.11        |
|  | NBR  | C                         | 26.1        | 0.09        | C             | 27.0        | 0.10        | C          | 27.2        | 0.10        | C             | 27.6        | 0.11        | C          | 27.8        | 0.11        |
| <b>Traffic Signal - Gosling Road at Woodbury Avenue</b>                                |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                  | <b>24.6</b> | <b>0.66</b> | <b>C</b>      | <b>24.3</b> | <b>0.67</b> | <b>C</b>   | <b>24.4</b> | <b>0.68</b> | <b>C</b>      | <b>25.3</b> | <b>0.75</b> | <b>C</b>   | <b>25.6</b> | <b>0.77</b> |
| Gosling Road   | EBTL | D                         | 37.7        | 0.66        | D             | 38.4        | 0.67        | D          | 38.7        | 0.68        | D             | 45.6        | 0.75        | D          | 47.1        | 0.77        |
|  | EBR  | C                         | 20.8        | 0.28        | C             | 20.1        | 0.30        | C          | 20.0        | 0.30        | C             | 20.5        | 0.33        | C          | 20.6        | 0.33        |
|  | WB   | D                         | 35.2        | 0.43        | D             | 35.5        | 0.45        | D          | 35.6        | 0.45        | D             | 36.7        | 0.49        | D          | 36.6        | 0.49        |
|  | NBL  | C                         | 28.3        | 0.42        | C             | 27.7        | 0.46        | C          | 27.7        | 0.48        | C             | 28.0        | 0.48        | C          | 28.1        | 0.50        |
| Woodbury Avenue  | NBTR | B                         | 15.5        | 0.17        | B             | 16.8        | 0.19        | B          | 16.7        | 0.19        | B             | 16.7        | 0.20        | B          | 16.7        | 0.20        |
|  | SBL  | E                         | 56.8        | 0.65        | D             | 35.5        | 0.40        | D          | 35.6        | 0.40        | D             | 36.7        | 0.45        | D          | 36.7        | 0.44        |
|  | SBT  | C                         | 23.1        | 0.39        | C             | 24.3        | 0.42        | C          | 24.5        | 0.43        | C             | 24.8        | 0.46        | C          | 25.0        | 0.46        |
|  | SBR  | B                         | 10.9        | 0.01        | B             | 11.6        | 0.01        | B          | 11.7        | 0.01        | B             | 11.8        | 0.01        | B          | 12.0        | 0.01        |
| <b>Traffic Signal - Woodbury Avenue at Durgin Lane/BJ's Driveway</b>                   |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>B</b>                  | <b>18.1</b> | <b>0.48</b> | <b>B</b>      | <b>18.1</b> | <b>0.50</b> | <b>C</b>   | <b>21.4</b> | <b>0.59</b> | <b>B</b>      | <b>18.3</b> | <b>0.53</b> | <b>C</b>   | <b>21.6</b> | <b>0.61</b> |
| Durgin Lane  | EBL  | C                         | 31.2        | 0.14        | C             | 31.6        | 0.15        | C          | 31.0        | 0.15        | C             | 32.6        | 0.17        | C          | 32.2        | 0.17        |
|  | EBT  | C                         | 31.2        | 0.14        | C             | 31.5        | 0.14        | C          | 31.0        | 0.16        | C             | 32.6        | 0.16        | C          | 32.2        | 0.17        |
|  | EBR  | C                         | 27.5        | 0.02        | C             | 27.8        | 0.02        | C          | 25.0        | 0.09        | C             | 28.8        | 0.02        | C          | 26.1        | 0.09        |
| BJ's Driveway  | WBL  | C                         | 30.8        | 0.16        | C             | 31.2        | 0.17        | C          | 32.1        | 0.16        | C             | 32.2        | 0.18        | C          | 33.3        | 0.17        |
|  | WBT  | C                         | 30.8        | 0.16        | C             | 31.2        | 0.17        | C          | 32.1        | 0.16        | C             | 32.2        | 0.18        | C          | 33.3        | 0.18        |
|  | WBR  | C                         | 25.3        | 0.19        | C             | 25.7        | 0.20        | C          | 26.4        | 0.19        | C             | 26.7        | 0.22        | C          | 27.5        | 0.22        |
|  | NBL  | C                         | 33.1        | 0.15        | C             | 33.5        | 0.15        | C          | 31.6        | 0.17        | C             | 34.7        | 0.17        | C          | 32.9        | 0.18        |
| Woodbury Avenue  | NBT  | B                         | 16.7        | 0.30        | B             | 16.9        | 0.33        | B          | 18.6        | 0.35        | B             | 16.8        | 0.35        | B          | 18.4        | 0.36        |
|  | NBR  | B                         | 11.7        | 0.03        | B             | 11.5        | 0.03        | B          | 12.7        | 0.03        | B             | 11.4        | 0.03        | B          | 12.4        | 0.03        |
|  | SBL  | C                         | 30.6        | 0.28        | C             | 31.1        | 0.29        | C          | 32.0        | 0.28        | C             | 32.3        | 0.32        | C          | 33.4        | 0.32        |
|  | SBT  | B                         | 16.4        | 0.48        | B             | 16.4        | 0.50        | C          | 21.0        | 0.59        | B             | 16.6        | 0.53        | C          | 21.1        | 0.61        |
| SBR  | A    | 7.4                       | 0.03        | A           | 7.3           | 0.03        | A           | 8.9        | 0.03        | A           | 7.2           | 0.04        | A           | 8.7        | 0.04        |             |
| <b>Traffic Signal - Woodbury Avenue at Market Street/ Market Basket Driveway</b>       |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>B</b>                  | <b>19.2</b> | <b>0.49</b> | <b>B</b>      | <b>19.5</b> | <b>0.49</b> | <b>B</b>   | <b>19.3</b> | <b>0.49</b> | <b>C</b>      | <b>20.2</b> | <b>0.53</b> | <b>B</b>   | <b>20.0</b> | <b>0.54</b> |
| Woodbury Avenue  | EBL  | C                         | 25.3        | 0.26        | C             | 25.1        | 0.30        | C          | 25.4        | 0.31        | C             | 25.7        | 0.32        | C          | 26.2        | 0.33        |
|  | EBTR | C                         | 26.3        | 0.36        | C             | 26.0        | 0.36        | C          | 26.2        | 0.36        | C             | 26.8        | 0.40        | C          | 27.2        | 0.40        |
| Market Basket Driveway   | WBL  | C                         | 26.6        | 0.03        | C             | 26.4        | 0.03        | C          | 26.8        | 0.03        | C             | 27.0        | 0.03        | C          | 27.5        | 0.03        |
|  | WBTR | C                         | 28.9        | 0.39        | C             | 28.8        | 0.40        | C          | 29.3        | 0.40        | C             | 29.8        | 0.45        | C          | 30.4        | 0.46        |
| Market Street  | NBL  | C                         | 29.4        | 0.49        | C             | 29.3        | 0.49        | C          | 29.6        | 0.49        | C             | 31.1        | 0.53        | C          | 31.7        | 0.54        |
|  | NBTR | B                         | 16.0        | 0.38        | B             | 16.5        | 0.42        | B          | 16.5        | 0.42        | B             | 17.2        | 0.46        | B          | 17.0        | 0.46        |
| Woodbury Avenue  | SBL  | C                         | 33.1        | 0.09        | C             | 33.0        | 0.09        | C          | 33.4        | 0.09        | C             | 34.1        | 0.09        | C          | 34.6        | 0.09        |
|  | SBT  | B                         | 19.4        | 0.29        | B             | 19.9        | 0.32        | C          | 20.1        | 0.35        | C             | 20.6        | 0.35        | C          | 20.6        | 0.37        |
|  | SBR  | A                         | 8.8         | 0.13        | A             | 8.9         | 0.14        | A          | 9.0         | 0.17        | A             | 9.1         | 0.15        | A          | 9.2         | 0.18        |
| <b>Unsignalized TWSC - Gosling Road at Motel 6 Driveway/North Site Access Driveway</b> |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| Motel 6 Driveway/North Site Access Driveway  | NB   | A                         | 9.7         | 0.04        | A             | 9.8         | 0.04        | A          | 9.8         | 0.04        | A             | 10.0        | 0.04        | B          | 10.0        | 0.04        |
| <b>Unsignalized TWSC - Arthur F Brady Drive at South Site Access Driveway</b>          |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| Arthur F Brady Drive   | EB   | A                         | 7.5         | 0.04        | A             | 7.5         | 0.04        | A          | 7.5         | 0.05        | A             | 7.5         | 0.04        | A          | 7.6         | 0.05        |
| South Site Driveway  | SBL  | B                         | 11.4        | 0.15        | B             | 11.5        | 0.16        | B          | 11.8        | 0.16        | B             | 12.0        | 0.18        | B          | 12.3        | 0.18        |
|  | SBR  | A                         | 8.9         | 0.06        | A             | 9.0         | 0.06        | A          | 9.1         | 0.09        | A             | 9.0         | 0.07        | A          | 9.2         | 0.10        |

**Legend**  
LOS - Level of Service  
Delay - average delay per vehicle in seconds  
V/C - volume to capacity ratio

**TABLE 1 (CONTINUED)**  
Intersection Operation Summary - Capacity

|  |      | Weekday Afternoon Peak Hour |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
|--|------|-----------------------------|-------------|-------------|---------------|-------------|-------------|------------|-------------|-------------|---------------|-------------|-------------|------------|-------------|-------------|
| Lane Use   |      | 2024 Existing               |             |             | 2026 No-Build |             |             | 2026 Build |             |             | 2036 No-Build |             |             | 2036 Build |             |             |
|  |      | LOS                         | Delay       | V/C         | LOS           | Delay       | V/C         | LOS        | Delay       | V/C         | LOS           | Delay       | V/C         | LOS        | Delay       | V/C         |
| <b>Traffic Signal - Pease Boulevard at US Route 4 Southbound Ramps</b>                 |      |                             |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                    | <b>26.2</b> | <b>0.68</b> | <b>C</b>      | <b>27.0</b> | <b>0.68</b> | <b>C</b>   | <b>27.7</b> | <b>0.68</b> | <b>C</b>      | <b>29.9</b> | <b>0.73</b> | <b>C</b>   | <b>30.4</b> | <b>0.73</b> |
| Pease Boulevard  | EBT  | C                           | 22.7        | 0.54        | C             | 24.0        | 0.60        | C          | 24.7        | 0.61        | C             | 26.7        | 0.68        | C          | 27.1        | 0.69        |
|  | EBR  | C                           | 22.9        | 0.48        | C             | 25.1        | 0.58        | C          | 25.9        | 0.58        | C             | 31.2        | 0.71        | C          | 31.6        | 0.72        |
|  | WBL  | D                           | 47.8        | 0.68        | D             | 47.6        | 0.68        | D          | 48.3        | 0.68        | D             | 49.6        | 0.73        | D          | 50.4        | 0.73        |
|  | WBT  | A                           | 6.9         | 0.15        | A             | 7.2         | 0.16        | A          | 7.3         | 0.16        | A             | 7.9         | 0.18        | A          | 8.0         | 0.18        |
| US Route 4 Southbound Off Ramp   | SBL  | C                           | 32.9        | 0.35        | C             | 33.6        | 0.36        | C          | 33.7        | 0.38        | C             | 34.0        | 0.38        | C          | 34.3        | 0.40        |
|  | SBT  | C                           | 33.0        | 0.35        | C             | 33.7        | 0.36        | C          | 33.8        | 0.38        | C             | 34.1        | 0.38        | C          | 34.3        | 0.40        |
|  | SBR  | C                           | 29.7        | 0.04        | C             | 30.3        | 0.04        | C          | 30.1        | 0.04        | C             | 30.4        | 0.05        | C          | 30.3        | 0.05        |
| <b>Traffic Signal - Gosling Road at US Route 4 Northbound Ramps</b>                    |      |                             |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                    | <b>23.6</b> | <b>0.73</b> | <b>C</b>      | <b>26.9</b> | <b>0.82</b> | <b>C</b>   | <b>27.3</b> | <b>0.83</b> | <b>C</b>      | <b>31.6</b> | <b>0.91</b> | <b>C</b>   | <b>32.0</b> | <b>0.91</b> |
| Gosling Road   | EBL  | C                           | 31.0        | 0.73        | D             | 41.8        | 0.82        | D          | 42.6        | 0.83        | D             | 54.6        | 0.91        | E          | 55.5        | 0.91        |
|  | EBT  | B                           | 11.4        | 0.56        | B             | 11.5        | 0.59        | B          | 12.3        | 0.62        | B             | 13.7        | 0.67        | B          | 14.5        | 0.70        |
|  | WBTR | C                           | 22.0        | 0.48        | C             | 23.3        | 0.51        | C          | 23.8        | 0.52        | C             | 26.7        | 0.61        | C          | 27.2        | 0.61        |
| US Route 4 Northbound Off Ramp   | NBL  | C                           | 31.0        | 0.21        | C             | 31.7        | 0.22        | C          | 31.5        | 0.21        | C             | 31.9        | 0.23        | C          | 31.8        | 0.23        |
|  | NBT  | C                           | 31.1        | 0.18        | C             | 31.7        | 0.18        | C          | 31.6        | 0.19        | C             | 32.1        | 0.20        | C          | 32.0        | 0.21        |
|  | NBR  | C                           | 31.1        | 0.18        | C             | 31.7        | 0.18        | C          | 31.6        | 0.19        | C             | 32.1        | 0.20        | C          | 32.0        | 0.21        |
| <b>Traffic Signal - Gosling Road at Woodbury Avenue</b>                                |      |                             |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>D</b>                    | <b>35.2</b> | <b>1.01</b> | <b>D</b>      | <b>36.1</b> | <b>1.03</b> | <b>D</b>   | <b>36.2</b> | <b>1.03</b> | <b>D</b>      | <b>40.3</b> | <b>1.15</b> | <b>D</b>   | <b>40.4</b> | <b>1.15</b> |
| Gosling Road   | EBTL | F                           | 112.8       | 1.01        | F             | 120.2       | 1.03        | F          | 120.2       | 1.03        | F             | 157.9       | 1.15        | F          | 157.9       | 1.15        |
|  | EBR  | C                           | 28.0        | 0.30        | C             | 28.7        | 0.33        | C          | 28.7        | 0.33        | C             | 29.2        | 0.37        | C          | 29.2        | 0.37        |
|  | WB   | D                           | 40.8        | 0.67        | D             | 41.5        | 0.67        | D          | 41.5        | 0.67        | D             | 43.0        | 0.71        | D          | 43.0        | 0.71        |
|  | NBL  | D                           | 39.0        | 0.67        | D             | 41.1        | 0.71        | D          | 41.6        | 0.72        | D             | 45.4        | 0.79        | D          | 46.2        | 0.81        |
|  | NBTR | C                           | 20.7        | 0.40        | C             | 20.8        | 0.40        | C          | 20.8        | 0.40        | C             | 23.3        | 0.48        | C          | 23.3        | 0.48        |
| Woodbury Avenue  | SBL  | E                           | 60.8        | 0.60        | E             | 59.5        | 0.59        | E          | 59.5        | 0.59        | D             | 44.7        | 0.40        | D          | 44.7        | 0.40        |
|  | SBT  | C                           | 30.3        | 0.56        | C             | 30.3        | 0.56        | C          | 30.3        | 0.56        | C             | 32.1        | 0.64        | C          | 32.1        | 0.64        |
|  | SBR  | B                           | 16.3        | 0.08        | B             | 16.2        | 0.08        | B          | 16.2        | 0.08        | B             | 16.7        | 0.09        | B          | 16.7        | 0.09        |
| <b>Traffic Signal - Woodbury Avenue at Durgin Lane/BJ's Driveway</b>                   |      |                             |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                    | <b>21.6</b> | <b>0.69</b> | <b>C</b>      | <b>21.8</b> | <b>0.70</b> | <b>C</b>   | <b>22.8</b> | <b>0.73</b> | <b>C</b>      | <b>22.6</b> | <b>0.72</b> | <b>C</b>   | <b>23.6</b> | <b>0.75</b> |
| Durgin Lane  | EBL  | C                           | 31.7        | 0.44        | C             | 32.2        | 0.45        | C          | 31.6        | 0.46        | C             | 34.6        | 0.51        | C          | 33.9        | 0.51        |
|  | EBT  | C                           | 31.7        | 0.44        | C             | 32.1        | 0.44        | C          | 31.5        | 0.45        | C             | 34.5        | 0.50        | C          | 34.2        | 0.52        |
|  | EBR  | C                           | 24.8        | 0.05        | C             | 25.2        | 0.05        | C          | 23.7        | 0.09        | C             | 26.9        | 0.06        | C          | 25.4        | 0.09        |
| BJ's Driveway  | WBL  | C                           | 31.1        | 0.41        | C             | 31.7        | 0.42        | C          | 30.9        | 0.42        | C             | 34.0        | 0.48        | C          | 33.2        | 0.47        |
|  | WBT  | C                           | 31.0        | 0.40        | C             | 31.7        | 0.42        | C          | 30.9        | 0.41        | C             | 33.9        | 0.47        | C          | 33.1        | 0.46        |
|  | WBR  | B                           | 18.4        | 0.24        | B             | 18.9        | 0.25        | B          | 18.2        | 0.24        | C             | 20.5        | 0.28        | B          | 19.8        | 0.27        |
|  | NBL  | C                           | 33.5        | 0.29        | C             | 34.1        | 0.31        | D          | 35.2        | 0.53        | D             | 36.6        | 0.36        | D          | 39.6        | 0.58        |
| Woodbury Avenue  | NBT  | C                           | 22.6        | 0.69        | C             | 22.8        | 0.70        | C          | 23.7        | 0.73        | C             | 23.3        | 0.72        | C          | 24.1        | 0.75        |
|  | NBR  | B                           | 11.5        | 0.06        | B             | 11.4        | 0.07        | B          | 11.6        | 0.07        | B             | 11.2        | 0.07        | B          | 11.4        | 0.07        |
|  | SBL  | C                           | 29.7        | 0.36        | C             | 30.2        | 0.38        | C          | 29.5        | 0.37        | C             | 32.3        | 0.42        | C          | 31.5        | 0.41        |
|  | SBT  | B                           | 17.3        | 0.52        | B             | 17.6        | 0.55        | B          | 19.2        | 0.59        | B             | 17.6        | 0.57        | B          | 19.2        | 0.61        |
|  | SBR  | A                           | 6.5         | 0.02        | A             | 6.4         | 0.02        | A          | 7.1         | 0.02        | A             | 6.2         | 0.02        | A          | 6.8         | 0.02        |
| <b>Traffic Signal - Woodbury Avenue at Market Street/ Market Basket Driveway</b>       |      |                             |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                    | <b>32.8</b> | <b>0.79</b> | <b>C</b>      | <b>33.6</b> | <b>0.82</b> | <b>C</b>   | <b>33.9</b> | <b>0.83</b> | <b>D</b>      | <b>38.0</b> | <b>0.96</b> | <b>D</b>   | <b>38.4</b> | <b>0.96</b> |
| Woodbury Avenue  | EBL  | D                           | 43.7        | 0.61        | D             | 46.0        | 0.65        | D          | 48.5        | 0.70        | D             | 51.0        | 0.73        | D          | 54.2        | 0.78        |
|  | EBTR | E                           | 61.3        | 0.79        | E             | 67.4        | 0.82        | E          | 68.3        | 0.83        | F             | 98.6        | 0.96        | F          | 98.6        | 0.96        |
| Market Basket Driveway   | WBL  | D                           | 47.9        | 0.73        | D             | 49.7        | 0.74        | D          | 50.4        | 0.75        | D             | 52.8        | 0.78        | D          | 52.8        | 0.78        |
|  | WBTR | D                           | 37.9        | 0.38        | D             | 38.5        | 0.39        | D          | 38.9        | 0.39        | D             | 39.0        | 0.40        | D          | 39.0        | 0.40        |
| Market Street  | NBL  | D                           | 46.5        | 0.60        | D             | 48.1        | 0.62        | D          | 48.6        | 0.62        | D             | 51.7        | 0.67        | D          | 51.7        | 0.67        |
|  | NBTR | C                           | 23.9        | 0.52        | C             | 23.9        | 0.53        | C          | 24.0        | 0.54        | C             | 25.3        | 0.58        | C          | 25.7        | 0.60        |
| Woodbury Avenue  | SBL  | D                           | 52.0        | 0.39        | D             | 52.8        | 0.40        | D          | 53.5        | 0.41        | D             | 54.4        | 0.43        | D          | 54.4        | 0.43        |
|  | SBT  | C                           | 32.0        | 0.68        | C             | 32.3        | 0.69        | C          | 32.4        | 0.70        | D             | 35.4        | 0.77        | D          | 36.2        | 0.79        |
|  | SBR  | B                           | 15.3        | 0.26        | B             | 15.4        | 0.28        | B          | 15.5        | 0.29        | B             | 16.3        | 0.30        | B          | 16.5        | 0.32        |
| <b>Unsignalized TWSC - Gosling Road at Motel 6 Driveway/North Site Access Driveway</b> |      |                             |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| Motel 6 Driveway/North Site Access Driveway  | NB   | B                           | 10.7        | 0.06        | B             | 10.9        | 0.07        | B          | 11.1        | 0.07        | B             | 11.2        | 0.08        | B          | 11.5        | 0.08        |
| <b>Unsignalized TWSC - Arthur F Brady Drive at South Site Access Driveway</b>          |      |                             |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| Arthur F Brady Drive   | EB   | A                           | 8.0         | 0.05        | A             | 8.0         | 0.05        | A          | 8.1         | 0.08        | A             | 8.1         | 0.06        | A          | 8.2         | 0.08        |
| South Site Driveway  | SBL  | C                           | 17.5        | 0.34        | C             | 18.1        | 0.35        | C          | 20.3        | 0.39        | C             | 21.2        | 0.43        | C          | 24.3        | 0.48        |
|  | SBR  | B                           | 10.5        | 0.12        | B             | 10.6        | 0.12        | B          | 10.7        | 0.15        | B             | 10.9        | 0.14        | B          | 11.1        | 0.17        |

**Legend**  
LOS - Level of Service  
Delay - average delay per vehicle in seconds  
V/C - volume to capacity ratio

**TABLE 1 (CONTINUED)**  
Intersection Operation Summary - Capacity

|  |      | Saturday Midday Peak Hour |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
|--|------|---------------------------|-------------|-------------|---------------|-------------|-------------|------------|-------------|-------------|---------------|-------------|-------------|------------|-------------|-------------|
| Lane Use   |      | 2024 Existing             |             |             | 2026 No-Build |             |             | 2026 Build |             |             | 2036 No-Build |             |             | 2036 Build |             |             |
|  |      | LOS                       | Delay       | V/C         | LOS           | Delay       | V/C         | LOS        | Delay       | V/C         | LOS           | Delay       | V/C         | LOS        | Delay       | V/C         |
| <b>Traffic Signal - Pease Boulevard at US Route 4 Southbound Ramps</b>                 |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                  | <b>26.9</b> | <b>0.61</b> | <b>C</b>      | <b>27.2</b> | <b>0.61</b> | <b>C</b>   | <b>27.8</b> | <b>0.62</b> | <b>C</b>      | <b>29.4</b> | <b>0.66</b> | <b>C</b>   | <b>29.9</b> | <b>0.67</b> |
| Pease Boulevard  | EBT  | C                         | 20.4        | 0.17        | C             | 20.6        | 0.17        | C          | 20.7        | 0.17        | C             | 21.4        | 0.18        | C          | 21.5        | 0.18        |
|  | EBR  | B                         | 19.6        | 0.05        | B             | 19.8        | 0.05        | B          | 19.9        | 0.05        | C             | 20.4        | 0.05        | C          | 20.6        | 0.05        |
|  | WBL  | D                         | 44.1        | 0.61        | D             | 44.6        | 0.61        | D          | 45.4        | 0.62        | D             | 48.7        | 0.66        | D          | 49.6        | 0.67        |
|  | WBT  | A                         | 5.7         | 0.11        | A             | 5.6         | 0.11        | A          | 5.5         | 0.11        | A             | 5.5         | 0.12        | A          | 5.5         | 0.12        |
| US Route 4 Southbound Off Ramp   | SBL  | C                         | 28.1        | 0.43        | C             | 28.4        | 0.43        | C          | 29.2        | 0.46        | C             | 31.2        | 0.49        | C          | 31.7        | 0.51        |
|  | SBT  | C                         | 28.2        | 0.43        | C             | 28.5        | 0.44        | C          | 29.2        | 0.46        | C             | 31.2        | 0.49        | C          | 31.7        | 0.51        |
|  | SBR  | C                         | 24.0        | 0.02        | C             | 24.2        | 0.02        | C          | 24.5        | 0.02        | C             | 26.0        | 0.02        | C          | 26.2        | 0.02        |
| <b>Traffic Signal - Gosling Road at US Route 4 Northbound Ramps</b>                    |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                  | <b>22.6</b> | <b>0.51</b> | <b>C</b>      | <b>22.9</b> | <b>0.52</b> | <b>C</b>   | <b>23.2</b> | <b>0.53</b> | <b>C</b>      | <b>24.1</b> | <b>0.56</b> | <b>C</b>   | <b>24.5</b> | <b>0.57</b> |
| Gosling Road   | EBL  | B                         | 14.0        | 0.09        | B             | 14.3        | 0.10        | B          | 14.5        | 0.10        | B             | 14.7        | 0.11        | B          | 14.9        | 0.11        |
|  | EBT  | C                         | 24.9        | 0.51        | C             | 25.3        | 0.52        | C          | 26.1        | 0.53        | C             | 27.1        | 0.56        | C          | 27.9        | 0.57        |
|  | WBTR | B                         | 18.4        | 0.33        | B             | 18.5        | 0.34        | B          | 18.4        | 0.34        | B             | 18.4        | 0.35        | B          | 18.5        | 0.36        |
| US Route 4 Northbound Off Ramp   | NBL  | C                         | 24.5        | 0.10        | C             | 24.7        | 0.10        | C          | 25.1        | 0.10        | C             | 26.7        | 0.11        | C          | 26.9        | 0.11        |
|  | NBT  | C                         | 26.0        | 0.23        | C             | 26.2        | 0.23        | C          | 26.6        | 0.24        | C             | 28.3        | 0.26        | C          | 28.6        | 0.26        |
|  | NBR  | C                         | 25.9        | 0.22        | C             | 26.1        | 0.23        | C          | 26.5        | 0.23        | C             | 28.2        | 0.25        | C          | 28.5        | 0.26        |
| <b>Traffic Signal - Gosling Road at Woodbury Avenue</b>                                |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                  | <b>28.6</b> | <b>0.63</b> | <b>C</b>      | <b>28.8</b> | <b>0.65</b> | <b>C</b>   | <b>28.9</b> | <b>0.65</b> | <b>C</b>      | <b>30.4</b> | <b>0.73</b> | <b>C</b>   | <b>30.5</b> | <b>0.73</b> |
| Gosling Road   | EBTL | D                         | 44.4        | 0.63        | D             | 46.3        | 0.65        | D          | 46.4        | 0.65        | D             | 53.6        | 0.73        | D          | 53.6        | 0.73        |
|  | EBR  | C                         | 25.7        | 0.23        | C             | 26.0        | 0.24        | C          | 26.0        | 0.24        | C             | 26.6        | 0.26        | C          | 26.6        | 0.26        |
|  | WB   | D                         | 36.6        | 0.53        | D             | 37.2        | 0.54        | D          | 37.3        | 0.54        | D             | 38.3        | 0.58        | D          | 38.3        | 0.58        |
|  | NBL  | D                         | 35.7        | 0.60        | D             | 36.2        | 0.61        | D          | 36.2        | 0.62        | D             | 38.2        | 0.67        | D          | 38.6        | 0.69        |
| Woodbury Avenue  | NBTR | C                         | 20.2        | 0.35        | C             | 20.1        | 0.35        | C          | 20.1        | 0.35        | C             | 20.8        | 0.39        | C          | 20.8        | 0.39        |
|  | SBL  | D                         | 42.2        | 0.43        | D             | 42.6        | 0.43        | D          | 42.8        | 0.43        | D             | 43.8        | 0.47        | D          | 43.8        | 0.47        |
|  | SBT  | C                         | 28.6        | 0.57        | C             | 28.6        | 0.57        | C          | 28.7        | 0.57        | C             | 30.3        | 0.63        | C          | 30.3        | 0.63        |
|  | SBR  | B                         | 14.6        | 0.04        | B             | 14.5        | 0.04        | B          | 14.6        | 0.04        | B             | 15.0        | 0.05        | B          | 15.0        | 0.05        |
| <b>Traffic Signal - Woodbury Avenue at Durgin Lane/BJ's Driveway</b>                   |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                  | <b>20.8</b> | <b>0.69</b> | <b>C</b>      | <b>20.8</b> | <b>0.69</b> | <b>C</b>   | <b>21.2</b> | <b>0.69</b> | <b>C</b>      | <b>21.5</b> | <b>0.68</b> | <b>C</b>   | <b>22.6</b> | <b>0.73</b> |
| Durgin Lane  | EBL  | C                         | 28.6        | 0.42        | C             | 28.9        | 0.44        | C          | 30.8        | 0.48        | C             | 32.7        | 0.52        | C          | 32.5        | 0.53        |
|  | EBT  | C                         | 28.6        | 0.43        | C             | 28.8        | 0.43        | C          | 30.9        | 0.48        | C             | 32.6        | 0.52        | C          | 32.8        | 0.54        |
|  | EBR  | C                         | 22.3        | 0.06        | C             | 22.5        | 0.06        | C          | 22.9        | 0.10        | C             | 24.9        | 0.07        | C          | 23.6        | 0.11        |
| BJ's Driveway  | WBL  | C                         | 28.0        | 0.35        | C             | 28.3        | 0.36        | C          | 29.7        | 0.37        | C             | 31.4        | 0.42        | C          | 30.8        | 0.41        |
|  | WBT  | C                         | 28.0        | 0.36        | C             | 28.3        | 0.36        | C          | 29.7        | 0.38        | C             | 31.4        | 0.42        | C          | 30.9        | 0.42        |
|  | WBR  | B                         | 16.7        | 0.13        | B             | 16.9        | 0.13        | B          | 17.9        | 0.14        | B             | 17.6        | 0.14        | B          | 17.1        | 0.14        |
|  | NBL  | C                         | 30.6        | 0.24        | C             | 30.8        | 0.24        | C          | 31.9        | 0.39        | C             | 33.7        | 0.28        | C          | 33.1        | 0.43        |
| Woodbury Avenue  | NBT  | C                         | 21.0        | 0.62        | C             | 21.0        | 0.63        | C          | 20.0        | 0.58        | C             | 22.5        | 0.66        | C          | 23.1        | 0.68        |
|  | NBR  | B                         | 11.4        | 0.07        | B             | 11.3        | 0.07        | B          | 11.0        | 0.07        | B             | 11.9        | 0.08        | B          | 12.1        | 0.08        |
|  | SBL  | C                         | 29.7        | 0.46        | C             | 30.0        | 0.47        | C          | 31.1        | 0.47        | C             | 30.0        | 0.42        | C          | 29.5        | 0.42        |
|  | SBT  | C                         | 20.7        | 0.69        | C             | 20.8        | 0.69        | C          | 21.1        | 0.69        | B             | 19.8        | 0.68        | C          | 22.1        | 0.73        |
|  | SBR  | A                         | 7.5         | 0.15        | A             | 7.4         | 0.16        | A          | 7.9         | 0.16        | A             | 7.1         | 0.17        | A          | 7.9         | 0.18        |
| <b>Traffic Signal - Woodbury Avenue at Market Street/ Market Basket Driveway</b>       |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| <b>Overall</b>   |      | <b>C</b>                  | <b>24.9</b> | <b>0.66</b> | <b>C</b>      | <b>25.2</b> | <b>0.68</b> | <b>C</b>   | <b>25.4</b> | <b>0.72</b> | <b>C</b>      | <b>27.3</b> | <b>0.79</b> | <b>C</b>   | <b>27.7</b> | <b>0.83</b> |
| Woodbury Avenue  | EBL  | D                         | 35.9        | 0.66        | D             | 37.0        | 0.68        | D          | 38.7        | 0.72        | D             | 44.7        | 0.79        | D          | 47.8        | 0.83        |
|  | EBTR | C                         | 34.5        | 0.55        | D             | 35.3        | 0.56        | D          | 35.7        | 0.57        | D             | 41.2        | 0.65        | D          | 41.5        | 0.66        |
| Market Basket Driveway   | WBL  | C                         | 34.1        | 0.58        | C             | 34.4        | 0.59        | C          | 34.9        | 0.59        | D             | 36.4        | 0.62        | D          | 36.7        | 0.63        |
|  | WBTR | C                         | 30.9        | 0.36        | C             | 31.1        | 0.37        | C          | 31.4        | 0.37        | C             | 32.1        | 0.39        | C          | 32.3        | 0.39        |
| Market Street  | NBL  | D                         | 36.8        | 0.44        | D             | 37.3        | 0.45        | D          | 37.7        | 0.45        | D             | 39.3        | 0.50        | D          | 39.5        | 0.50        |
|  | NBTR | C                         | 20.5        | 0.51        | C             | 20.7        | 0.52        | C          | 20.6        | 0.53        | C             | 21.3        | 0.56        | C          | 21.4        | 0.57        |
| Woodbury Avenue  | SBL  | D                         | 52.9        | 0.48        | D             | 53.2        | 0.48        | D          | 53.6        | 0.48        | E             | 55.4        | 0.50        | E          | 55.6        | 0.50        |
|  | SBT  | C                         | 24.9        | 0.56        | C             | 25.0        | 0.56        | C          | 25.0        | 0.57        | C             | 25.8        | 0.60        | C          | 25.9        | 0.61        |
|  | SBR  | B                         | 11.1        | 0.26        | B             | 11.2        | 0.26        | B          | 11.2        | 0.28        | B             | 11.7        | 0.29        | B          | 11.8        | 0.31        |
| <b>Unsignalized TWSC - Gosling Road at Motel 6 Driveway/North Site Access Driveway</b> |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| Motel 6 Driveway/North Site Access Driveway  | NB   | B                         | 11.3        | 0.14        | B             | 11.4        | 0.15        | B          | 11.6        | 0.15        | B             | 11.9        | 0.17        | B          | 12.1        | 0.17        |
| <b>Unsignalized TWSC - Arthur F Brady Drive at South Site Access Driveway</b>          |      |                           |             |             |               |             |             |            |             |             |               |             |             |            |             |             |
| Arthur F Brady Drive   | EB   | A                         | 7.7         | 0.07        | A             | 7.7         | 0.08        | A          | 7.8         | 0.09        | A             | 7.8         | 0.08        | A          | 7.8         | 0.10        |
| South Site Driveway  | SBL  | C                         | 17.8        | 0.37        | C             | 18.4        | 0.39        | C          | 19.9        | 0.41        | C             | 21.8        | 0.47        | C          | 24.2        | 0.51        |
|  | SBR  | A                         | 9.3         | 0.06        | A             | 9.3         | 0.06        | A          | 9.4         | 0.08        | A             | 9.4         | 0.07        | A          | 9.5         | 0.09        |

**Legend**  
LOS - Level of Service  
Delay - average delay per vehicle in seconds  
V/C - volume to capacity ratio

**TABLE 2**  
Intersection Operation Summary - Queues (In Feet)

|  |                   | Weekday Morning Peak Hour |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
|--|-------------------|---------------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|-----|
| Lane Use   | Available Storage | 2024 Existing             |                  | 2026 No-Build    |                  | 2026 Build       |                  | 2036 No-Build    |                  | 2036 Build       |                  |     |
|  |                   | 50 <sup>th</sup>          | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> |     |
| <b>Traffic Signal - Pease Boulevard at US Route 4 Southbound Ramps</b>                 |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Pease Boulevard  | EBT               | 550                       | 26               | 40               | 33               | 49               | 33               | 49               | 36               | 53               | 36               | 53  |
|  | EBR               | 550                       | 0                | 32               | 0                | 37               | 0                | 37               | 0                | 38               | 0                | 38  |
|  | WBL               | 360                       | 31               | 44               | 30               | 42               | 36               | 48               | 32               | 43               | 37               | 49  |
| US Route 4 Southbound Off Ramp   | WBT               | 360                       | 236              | 298              | 261              | 320              | 261              | 316              | 297              | 332              | 295              | 328 |
|  | SBL               | 500                       | 121              | 213              | 128              | 217              | 132              | 221              | 152              | 240              | 155              | 245 |
|  | SBT               | 500                       | 122              | 213              | 128              | 217              | 133              | 222              | 152              | 240              | 156              | 245 |
|  | SBR               | 500                       | 157              | 253              | 231              | 384              | 235              | 384              | 350              | 477              | 351              | 477 |
| <b>Traffic Signal - Gosling Road at US Route 4 Northbound Ramps</b>                    |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Gosling Road   | EBL               | 370                       | 18               | 36               | 25               | 45               | 25               | 46               | 28               | 45               | 28               | 43  |
|  | EBT               | 370                       | 136              | 248              | 136              | 255              | 141              | 258              | 157              | 279              | 160              | 283 |
|  | WB                | 480                       | 42               | 73               | 49               | 83               | 52               | 86               | 55               | 91               | 57               | 94  |
| US Route 4 Northbound Off Ramp   | NBL               | 450                       | 197              | 325              | 223              | 364              | 227              | 364              | 268              | 420              | 269              | 420 |
|  | NBT               | 300                       | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0   |
|  | NBR               | 300                       | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0   |
| <b>Traffic Signal - Gosling Road at Woodbury Avenue</b>                                |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Gosling Road   | EBTL              | 500                       | 50               | 256              | 53               | 262              | 53               | 262              | 61               | 291              | 61               | 291 |
|  | EBR               | 500                       | 0                | 57               | 0                | 59               | 0                | 59               | 0                | 61               | 0                | 61  |
|  | WBT               | 575                       | 15               | 71               | 16               | 72               | 17               | 72               | 19               | 78               | 19               | 78  |
|  | NBL               | 300                       | 37               | 113              | 45               | 133              | 48               | 140              | 51               | 145              | 54               | 154 |
| Woodbury Avenue  | NBTR              | 415                       | 23               | 101              | 35               | 103              | 35               | 103              | 39               | 114              | 39               | 114 |
|  | SBL               | 210                       | 13               | 63               | 14               | 65               | 14               | 65               | 16               | 70               | 16               | 70  |
|  | SBT               | 440                       | 55               | 161              | 58               | 164              | 59               | 164              | 67               | 182              | 67               | 182 |
|  | SBR               | 280                       | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0   |
| <b>Traffic Signal - Woodbury Avenue at Durgin Lane/BJ's Driveway</b>                   |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Durgin Lane  | EBL               | 170                       | 5                | 32               | 5                | 32               | 8                | 42               | 6                | 36               | 9                | 46  |
|  | EBT               | 170                       | 5                | 32               | 5                | 32               | 8                | 44               | 6                | 36               | 9                | 46  |
|  | EBR               | 170                       | 0                | 0                | 0                | 0                | 0                | 22               | 0                | 0                | 0                | 22  |
| BJ's Driveway  | WBL               | 100                       | 7                | 30               | 7                | 31               | 7                | 31               | 8                | 33               | 8                | 33  |
|  | WBT               | 100                       | 7                | 30               | 7                | 31               | 7                | 31               | 8                | 33               | 8                | 33  |
|  | WBR               | 100                       | 12               | 27               | 13               | 28               | 13               | 28               | 15               | 33               | 15               | 33  |
|  | NBL               | 400                       | 4                | 26               | 4                | 26               | 9                | 45               | 4                | 28               | 9                | 48  |
| Woodbury Avenue  | NBT               | 400                       | 52               | 144              | 60               | 163              | 61               | 163              | 67               | 177              | 68               | 177 |
|  | NBR               | 200                       | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0   |
|  | SBL               | 125                       | 15               | 69               | 15               | 71               | 15               | 71               | 17               | 80               | 18               | 80  |
|  | SBT               | 350                       | 106              | 284              | 112              | 296              | 114              | 296              | 128              | 330              | 130              | 330 |
|  | SBR               | 105                       | 0                | 6                | 0                | 6                | 0                | 6                | 0                | 9                | 0                | 9   |
| <b>Traffic Signal - Woodbury Avenue at Market Street/Market Basket Driveway</b>        |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Woodbury Avenue  | EBL               | 215                       | 20               | 38               | 25               | 44               | 26               | 47               | 28               | 50               | 30               | 52  |
|  | EBTR              | 280                       | 26               | 58               | 27               | 60               | 27               | 61               | 33               | 69               | 34               | 70  |
| Market Basket Driveway   | WBL               | 500                       | 2                | 8                | 2                | 8                | 2                | 8                | 2                | 8                | 2                | 9   |
|  | WBTR              | 500                       | 22               | 44               | 23               | 45               | 24               | 46               | 29               | 51               | 30               | 52  |
| Market Street  | NBL               | 270                       | 30               | 63               | 31               | 64               | 31               | 65               | 36               | 71               | 37               | 73  |
|  | NBTR              | 600                       | 54               | 104              | 60               | 113              | 62               | 115              | 71               | 126              | 73               | 128 |
|  | SBL               | 200                       | 1                | 7                | 1                | 7                | 1                | 7                | 1                | 7                | 1                | 8   |
| Woodbury Avenue  | SBT               | 550                       | 46               | 89               | 48               | 93               | 56               | 104              | 56               | 103              | 65               | 114 |
|  | SBR               | 200                       | 0                | 35               | 0                | 36               | 0                | 39               | 0                | 38               | 0                | 40  |
| <b>Unsignalized TWSC - Gosling Road at Motel 6 Driveway/North Site Access Driveway</b> |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Motel 6 Driveway/ North Site Access Driveway   | NB                | 150                       | --               | 3                | --               | 3                | --               | 3                | --               | 3                | --               | 3   |
| <b>Unsignalized TWSC - Arthur F Brady Drive at South Site Access Driveway</b>          |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Arthur F Brady Drive   | EB                | 420                       | --               | 3                | --               | 3                | --               | 3                | --               | 3                | --               | 5   |
| South Site Access Driveway   | SBL               | 325                       | --               | 13               | --               | 13               | --               | 15               | --               | 15               | --               | 18  |
|  | SBR               | 325                       | --               | 5                | --               | 5                | --               | 8                | --               | 5                | --               | 8   |

**Legend**

50th & 90th - 50th and 95th percentile queue lengths in feet

**TABLE 2 (CONTINUED)**

Intersection Operation Summary - Queues (In Feet)

|  |                   | Weekday Afternoon Peak Hour |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
|--|-------------------|-----------------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|-----|
| Lane Use   | Available Storage | 2024 Existing               |                  | 2026 No-Build    |                  | 2026 Build       |                  | 2036 No-Build    |                  | 2036 Build       |                  |     |
|  |                   | 50 <sup>th</sup>            | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> |     |
| <b>Traffic Signal - Pease Boulevard at US Route 4 Southbound Ramps</b>                 |                   |                             |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Pease Boulevard  | EBT               | 550                         | 170              | 212              | 202              | 244              | 212              | 244              | 253              | 272              | 255              | 272 |
|  | EBR               | 550                         | 24               | 93               | 50               | 150              | 53               | 151              | 120              | 242              | 123              | 243 |
|  | WBL               | 360                         | 161              | 228              | 171              | 233              | 176              | 235              | 196              | 254              | 200              | 256 |
| US Route 4 Southbound Off Ramp   | WBT               | 360                         | 29               | 43               | 32               | 46               | 32               | 46               | 36               | 50               | 36               | 50  |
|  | SBL               | 500                         | 64               | 121              | 69               | 123              | 75               | 133              | 76               | 134              | 84               | 145 |
|  | SBT               | 500                         | 65               | 123              | 70               | 125              | 76               | 134              | 77               | 135              | 85               | 146 |
|  | SBR               | 500                         | 0                | 23               | 0                | 24               | 0                | 24               | 0                | 25               | 0                | 25  |
| <b>Traffic Signal - Gosling Road at US Route 4 Northbound Ramps</b>                    |                   |                             |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Gosling Road   | EBL               | 370                         | 179              | 248              | 226              | 294              | 235              | 294              | 286              | 354              | 289              | 357 |
|  | EBT               | 370                         | 62               | 78               | 65               | 83               | 71               | 89               | 74               | 113              | 80               | 120 |
|  | WB                | 480                         | 142              | 208              | 160              | 218              | 167              | 220              | 197              | 248              | 201              | 250 |
| US Route 4 Northbound Off Ramp   | NBL               | 450                         | 37               | 65               | 40               | 67               | 40               | 67               | 45               | 73               | 45               | 73  |
|  | NBT               | 300                         | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0   |
|  | NBR               | 300                         | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0   |
| <b>Traffic Signal - Gosling Road at Woodbury Avenue</b>                                |                   |                             |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Gosling Road   | EBTL              | 500                         | 78               | 339              | 81               | 345              | 81               | 345              | 99               | 384              | 99               | 384 |
|  | EBR               | 500                         | 0                | 67               | 0                | 69               | 0                | 69               | 0                | 73               | 0                | 73  |
|  | WBT               | 575                         | 84               | 197              | 86               | 200              | 86               | 200              | 98               | 220              | 98               | 220 |
| Woodbury Avenue  | NBL               | 300                         | 80               | 261              | 87               | 281              | 88               | 288              | 98               | 319              | 100              | 326 |
|  | NBTR              | 415                         | 74               | 290              | 75               | 303              | 75               | 303              | 124              | 365              | 124              | 365 |
|  | SBL               | 210                         | 14               | 61               | 14               | 61               | 14               | 61               | 16               | 65               | 16               | 65  |
|  | SBT               | 440                         | 105              | 320              | 108              | 332              | 108              | 332              | 124              | 382              | 124              | 382 |
|  | SBR               | 280                         | 0                | 49               | 0                | 50               | 0                | 50               | 0                | 52               | 0                | 52  |
| <b>Traffic Signal - Woodbury Avenue at Durgin Lane/BJ's Driveway</b>                   |                   |                             |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Durgin Lane  | EBL               | 170                         | 33               | 78               | 35               | 81               | 36               | 84               | 41               | 97               | 42               | 100 |
|  | EBT               | 170                         | 34               | 78               | 35               | 81               | 36               | 84               | 41               | 93               | 44               | 105 |
|  | EBR               | 170                         | 0                | 14               | 0                | 15               | 0                | 26               | 0                | 19               | 0                | 29  |
| BJ's Driveway  | WBL               | 100                         | 33               | 68               | 34               | 71               | 34               | 71               | 41               | 80               | 41               | 80  |
|  | WBT               | 100                         | 33               | 68               | 35               | 72               | 35               | 72               | 41               | 80               | 41               | 80  |
|  | WBR               | 100                         | 38               | 72               | 40               | 74               | 40               | 74               | 47               | 85               | 47               | 85  |
|  | NBL               | 400                         | 13               | 41               | 14               | 42               | 33               | 90               | 17               | 47               | 36               | 101 |
| Woodbury Avenue  | NBT               | 400                         | 154              | 207              | 162              | 216              | 162              | 216              | 188              | 241              | 188              | 241 |
|  | NBR               | 200                         | 0                | 10               | 0                | 10               | 0                | 10               | 0                | 10               | 0                | 10  |
|  | SBL               | 125                         | 33               | 78               | 35               | 81               | 35               | 81               | 40               | 91               | 40               | 91  |
|  | SBT               | 350                         | 129              | 177              | 141              | 191              | 141              | 191              | 159              | 212              | 159              | 212 |
|  | SBR               | 105                         | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0                | 0   |
| <b>Traffic Signal - Woodbury Avenue at Market Street/Market Basket Driveway</b>        |                   |                             |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Woodbury Avenue  | EBL               | 215                         | 64               | 147              | 68               | 158              | 74               | 176              | 77               | 182              | 82               | 198 |
|  | EBTR              | 280                         | 80               | 264              | 82               | 269              | 82               | 269              | 97               | 311              | 97               | 311 |
| Market Basket Driveway   | WBL               | 500                         | 115              | 277              | 118              | 287              | 118              | 287              | 133              | 330              | 133              | 330 |
|  | WBTR              | 500                         | 57               | 141              | 59               | 144              | 59               | 144              | 66               | 156              | 66               | 156 |
| Market Street  | NBL               | 270                         | 60               | 150              | 62               | 158              | 62               | 158              | 70               | 182              | 70               | 182 |
|  | NBTR              | 600                         | 117              | 305              | 123              | 317              | 129              | 331              | 144              | 381              | 150              | 401 |
| Woodbury Avenue  | SBL               | 200                         | 10               | 38               | 10               | 39               | 10               | 39               | 11               | 41               | 11               | 41  |
|  | SBT               | 550                         | 185              | 390              | 197              | 418              | 205              | 436              | 228              | 483              | 237              | 502 |
|  | SBR               | 200                         | 0                | 65               | 0                | 67               | 0                | 69               | 0                | 71               | 0                | 73  |
| <b>Unsignalized TWSC - Gosling Road at Motel 6 Driveway/North Site Access Driveway</b> |                   |                             |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Motel 6 Driveway/ North Site Access Driveway   | NB                | 150                         | --               | 5                | --               | 5                | --               | 5                | --               | 6                | --               | 6   |
| <b>Unsignalized TWSC - Arthur F Brady Drive at South Site Access Driveway</b>          |                   |                             |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Arthur F Brady Drive   | EB                | 420                         | --               | 5                | --               | 5                | --               | 5                | --               | 5                | --               | 8   |
| South Site Access Driveway   | SBL               | 325                         | --               | 38               | --               | 40               | --               | 45               | --               | 53               | --               | 63  |
|  | SBR               | 325                         | --               | 10               | --               | 10               | --               | --               | --               | 13               | --               | 15  |

**Legend**

50th & 90th - 50th and 95th percentile queue lengths in feet



**TABLE 2 (CONTINUED)**

Intersection Operation Summary - Queues (In Feet)

|  |                   | Saturday Midday Peak Hour |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
|--|-------------------|---------------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|-----|
| Lane Use   | Available Storage | 2024 Existing             |                  | 2026 No-Build    |                  | 2036 No-Build    |                  | 2026 Build       |                  | 2036 Build       |                  |     |
|  |                   | 50 <sup>th</sup>          | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> | 50 <sup>th</sup> | 95 <sup>th</sup> |     |
| <b>Traffic Signal - Pease Boulevard at US Route 4 Southbound Ramps</b>                 |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Pease Boulevard  | EBT               | 550                       | 38               | 60               | 39               | 61               | 39               | 61               | 45               | 67               | 46               | 67  |
|  | EBR               | 550                       | 0                | 20               | 0                | 21               | 0                | 21               | 0                | 26               | 0                | 26  |
|  | WBL               | 360                       | 128              | 189              | 131              | 192              | 135              | 196              | 158              | 210              | 162              | 213 |
|  | WBT               | 360                       | 19               | 29               | 20               | 30               | 20               | 29               | 22               | 32               | 22               | 32  |
| US Route 4 Southbound Off Ramp   | SBL               | 500                       | 82               | 167              | 85               | 170              | 91               | 178              | 107              | 188              | 114              | 195 |
|  | SBT               | 500                       | 83               | 168              | 86               | 171              | 92               | 178              | 108              | 188              | 115              | 196 |
|  | SBR               | 500                       | 0                | 6                | 0                | 6                | 0                | 6                | 0                | 9                | 0                | 9   |
| <b>Traffic Signal - Gosling Road at US Route 4 Northbound Ramps</b>                    |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Gosling Road   | EBL               | 370                       | 14               | 30               | 14               | 31               | 14               | 31               | 17               | 34               | 18               | 35  |
|  | EBT               | 370                       | 105              | 154              | 108              | 157              | 114              | 164              | 128              | 273              | 135              | 281 |
|  | WB                | 480                       | 88               | 141              | 91               | 144              | 93               | 146              | 104              | 163              | 105              | 164 |
| US Route 4 Northbound Off Ramp   | NBL               | 450                       | 17               | 41               | 17               | 42               | 18               | 42               | 22               | 45               | 22               | 45  |
|  | NBT               | 300                       | 1                | 77               | 1                | 77               | 1                | 78               | 1                | 83               | 1                | 84  |
|  | NBR               | 300                       | 0                | 74               | 0                | 75               | 0                | 76               | 0                | 81               | 0                | 82  |
| <b>Traffic Signal - Gosling Road at Woodbury Avenue</b>                                |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Gosling Road   | EBTL              | 500                       | 48               | 187              | 50               | 192              | 50               | 192              | 56               | 218              | 56               | 218 |
|  | EBR               | 500                       | 0                | 41               | 0                | 41               | 0                | 41               | 0                | 42               | 0                | 42  |
|  | WBT               | 575                       | 52               | 147              | 52               | 148              | 52               | 148              | 60               | 165              | 60               | 165 |
|  | NBL               | 300                       | 69               | 214              | 71               | 219              | 73               | 226              | 80               | 258              | 82               | 265 |
| Woodbury Avenue  | NBTR              | 415                       | 80               | 230              | 82               | 234              | 82               | 234              | 93               | 264              | 93               | 264 |
|  | SBL               | 210                       | 17               | 67               | 17               | 67               | 17               | 67               | 19               | 74               | 19               | 74  |
|  | SBT               | 440                       | 104              | 303              | 106              | 313              | 106              | 313              | 122              | 368              | 122              | 368 |
|  | SBR               | 280                       | 0                | 24               | 0                | 25               | 0                | 25               | 0                | 32               | 0                | 32  |
|  |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| <b>Traffic Signal - Woodbury Avenue at Durgin Lane/BJ's Driveway</b>                   |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Durgin Lane  | EBL               | 170                       | 34               | 77               | 35               | 80               | 37               | 83               | 42               | 97               | 44               | 102 |
|  | EBT               | 170                       | 35               | 80               | 35               | 80               | 38               | 85               | 43               | 93               | 45               | 104 |
|  | EBR               | 170                       | 0                | 20               | 0                | 20               | 0                | 25               | 0                | 23               | 0                | 27  |
| BJ's Driveway  | WBL               | 100                       | 29               | 72               | 29               | 73               | 29               | 73               | 34               | 84               | 34               | 84  |
|  | WBT               | 100                       | 29               | 74               | 30               | 75               | 30               | 75               | 35               | 85               | 35               | 85  |
|  | WBR               | 100                       | 18               | 48               | 19               | 49               | 19               | 49               | 22               | 57               | 22               | 57  |
|  | NBL               | 400                       | 11               | 35               | 11               | 36               | 23               | 60               | 13               | 40               | 26               | 68  |
| Woodbury Avenue  | NBT               | 400                       | 124              | 177              | 127              | 180              | 127              | 180              | 147              | 200              | 147              | 200 |
|  | NBR               | 200                       | 0                | 11               | 0                | 11               | 0                | 11               | 0                | 11               | 0                | 11  |
|  | SBL               | 125                       | 34               | 79               | 34               | 80               | 34               | 80               | 40               | 92               | 40               | 92  |
|  | SBT               | 350                       | 155              | 212              | 160              | 217              | 160              | 217              | 182              | 244              | 182              | 244 |
|  | SBR               | 105                       | 16               | 42               | 17               | 42               | 17               | 42               | 20               | 47               | 20               | 47  |
| <b>Traffic Signal - Woodbury Avenue at Market Street/Market Basket Driveway</b>        |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Woodbury Avenue  | EBL               | 215                       | 75               | 114              | 78               | 117              | 84               | 124              | 94               | 141              | 100              | 150 |
|  | EBTR              | 280                       | 59               | 112              | 60               | 114              | 62               | 114              | 74               | 136              | 75               | 136 |
| Market Basket Driveway   | WBL               | 500                       | 82               | 135              | 84               | 137              | 86               | 137              | 99               | 151              | 101              | 151 |
|  | WBTR              | 500                       | 49               | 90               | 50               | 92               | 52               | 92               | 60               | 101              | 61               | 101 |
| Market Street  | NBL               | 270                       | 30               | 74               | 31               | 75               | 32               | 75               | 37               | 81               | 37               | 81  |
|  | NBTR              | 600                       | 102              | 206              | 105              | 211              | 108              | 217              | 124              | 237              | 127              | 244 |
| Woodbury Avenue  | SBL               | 200                       | 6                | 24               | 6                | 24               | 6                | 24               | 7                | 25               | 7                | 25  |
|  | SBT               | 550                       | 127              | 197              | 131              | 202              | 137              | 211              | 153              | 226              | 159              | 235 |
|  | SBR               | 200                       | 0                | 47               | 0                | 47               | 0                | 49               | 0                | 49               | 0                | 51  |
| <b>Unsignalized TWSC - Gosling Road at Motel 6 Driveway/North Site Access Driveway</b> |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Motel 6 Driveway/ North Site Access Driveway   | NB                | 150                       | --               | 12               | --               | 13               | --               | 13               | --               | 15               | --               | 15  |
| <b>Unsignalized TWSC - Arthur F Brady Drive at South Site Access Driveway</b>          |                   |                           |                  |                  |                  |                  |                  |                  |                  |                  |                  |     |
| Arthur F Brady Drive   | EB                | 420                       | --               | 5                | --               | 5                | --               | 8                | --               | 8                | --               | 8   |
| South Site Access Driveway   | SBL               | 325                       | --               | 43               | --               | 45               | --               | 50               | --               | 60               | --               | 68  |
|  | SBR               | 325                       | --               | 5                | --               | 5                | --               | 8                | --               | 5                | --               | 8   |

**Legend**

50th & 90th - 50th and 95th percentile queue lengths in feet

**TABLE 4**  
Proposed Site-Generated Traffic Summary

| <b>Proposed - 144 Units Residential</b> |              |             | <b>LUC 220</b> |
|---|--------------|-------------|----------------|
| <b>Peak Hour Period</b>                 | <b>Enter</b> | <b>Exit</b> | <b>Total</b>   |
| Weekday Morning                         | 16           | 51          | 67             |
| Weekday Afternoon                       | 52           | 30          | 82             |
| Saturday Midday                         | 30           | 29          | 59             |
| <b>Weekday</b>                          | <b>499</b>   | <b>499</b>  | <b>998</b>     |
| <b>Saturday</b>                         | <b>328</b>   | <b>327</b>  | <b>655</b>     |

| <b>Proposed - 216 Units Residential</b> |              |             | <b>LUC 221</b> |
|---|--------------|-------------|----------------|
| <b>Peak Hour Period</b>                 | <b>Enter</b> | <b>Exit</b> | <b>Total</b>   |
| Weekday Morning                         | 19           | 64          | 83             |
| Weekday Afternoon                       | 52           | 33          | 85             |
| Saturday Midday                         | 44           | 43          | 87             |
| <b>Weekday</b>                          | <b>491</b>   | <b>490</b>  | <b>981</b>     |
| <b>Saturday</b>                         | <b>494</b>   | <b>493</b>  | <b>987</b>     |

| <b>Total Proposed</b>    |              |             |              |
|--------------------------|--------------|-------------|--------------|
| <b>Peak Hour Period</b>  | <b>Enter</b> | <b>Exit</b> | <b>Total</b> |
| <b>Weekday Morning</b>   | <b>35</b>    | <b>116</b>  | <b>151</b>   |
| <b>Weekday Afternoon</b> | <b>104</b>   | <b>63</b>   | <b>167</b>   |
| <b>Saturday Midday</b>   | <b>74</b>    | <b>72</b>   | <b>146</b>   |
| <b>Weekday</b>           | <b>990</b>   | <b>989</b>  | <b>1,979</b> |
| <b>Saturday</b>          | <b>822</b>   | <b>820</b>  | <b>1,642</b> |

**Source:** Institute of Transportation Engineers, Trip Generation, 11th Edition, 2021  
Land Use - 220 [Residential - Multifamily Housing (Low-Rise)]  
Land Use - 221 [Residential - Multifamily Housing (Mid-Rise)]


**TABLE 5**  
Net Site-Generated Traffic Summary

| <b>Existing - 78,317 SF Retail Space</b>                             |               |               | <b>LUC 821</b>           |
|--|---------------|---------------|--------------------------|
| <b>Peak Hour Period</b>  | <b>Enter</b>  | <b>Exit</b>   | <b>Total</b>             |
| Weekday Morning  | 84            | 51            | 135                      |
| Weekday Afternoon  | 199           | 207           | 406                      |
| Saturday Midday  | 253           | 234           | 487                      |
| <b>Weekday</b>   | <b>2,644</b>  | <b>2,644</b>  | <b>5,288</b>             |
| <b>Saturday</b>  | <b>3,175</b>  | <b>3,174</b>  | <b>6,349</b>             |
| <b>Proposed - 360 Units Residential</b>                              |               |               | <b>LUC 220 &amp; 221</b> |
| <b>Peak Hour Period</b>  | <b>Enter</b>  | <b>Exit</b>   | <b>Total</b>             |
| Weekday Morning  | 35            | 116           | 151                      |
| Weekday Afternoon  | 104           | 63            | 167                      |
| Saturday Midday  | 74            | 72            | 146                      |
| <b>Weekday</b>   | <b>990</b>    | <b>989</b>    | <b>1,979</b>             |
| <b>Saturday</b>  | <b>822</b>    | <b>820</b>    | <b>1,642</b>             |
| <b>Net Vehicular Trips (Proposed minus Existing Occupied Demand)</b> |               |               |                          |
| <b>Peak Hour Period</b>  | <b>Enter</b>  | <b>Exit</b>   | <b>Total</b>             |
| <b>Weekday Morning</b>   | <b>-49</b>    | <b>65</b>     | <b>16</b>                |
| <b>Weekday Afternoon</b>   | <b>-95</b>    | <b>-144</b>   | <b>-239</b>              |
| <b>Saturday Midday</b>   | <b>-179</b>   | <b>-162</b>   | <b>-341</b>              |
| <b>Weekday</b>   | <b>-1,654</b> | <b>-1,655</b> | <b>-3,309</b>            |
| <b>Saturday</b>  | <b>-2,353</b> | <b>-2,354</b> | <b>-4,707</b>            |


**Source:** Institute of Transportation Engineers, Trip Generation, 11th Edition, 2021  
 Land Use - 220 [Residential - Multifamily Housing (Low-Rise)]  
 Land Use - 221 [Residential - Multifamily Housing (Mid-Rise)]  
 Land Use - 821 [Shopping Plaza (40-150k)]

# **Section 8**

## **Figures**



Apr 22, 2024-10:40am Plotted By: WBlair Tighe & Bond, Inc. J:\VE\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Figures\E5071-001 Traffic Study Area Figure.dwg



**SITE**

HAMPTON INN

HOME DEPOT

DURGIN SQUARE SHOPPING PLAZA

MOTEL 6

GOSLING RD

WOODBURY AVE

DURGIN LN

PEASE BLVD

4

SPAULDING TURNPIKE

ARTHUR F BRADY DR

MARKET ST


WOODBURY AVE

100 DURGIN LANE  
PORTSMOUTH, NH

STUDY AREA

**LEGEND**


- SITE LOCATION
- STUDY AREA INTERSECTION



DATE: 4/16/2024  
SCALE: 1" = 1000'  
FIGURE: 1




Apr 29, 2024-10:18am Plotted By: MBlair Tighe & Bond, Inc. J:\VE\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Figures\E5071-001 Traffic Volume Figures.dwg




|   |  |
|---|--|
| 100 DURGIN LANE DEVELOPMENT<br>PORTSMOUTH, NH |  |
| 2024 EXISTING TRAFFIC VOLUMES                 |  |
| DATE: 04/29/2024                              |  |
| SCALE: NTS                                    |  |
| FIGURE 2                                      |  |

Apr 29, 2024-10:18am Plotted By: MBlair Tighe & Bond, Inc. J:\VE\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Figures\E5071-001 Traffic Volume Figures.dwg




DATE: 04/29/2024  
SCALE: NTS  
FIGURE 3

Apr 29, 2024-10:18am Plotted By: MBlair Tighe & Bond, Inc. J:\VE\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Figures\E5071-001 Traffic Volume Figures.dwg






Apr 29, 2024-10:18am Plotted By: MBlair Tighe & Bond, Inc. J:\VE\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Figures\E5071-001 Traffic Volume Figures.dwg




DATE: 04/29/2024  
 SCALE: NTS  
 FIGURE 5

Apr 29, 2024-10:18am Plotted By: MBlair Tighe & Bond, Inc. J:\VE\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Figures\E5071-001 Traffic Volume Figures.dwg




|   |  |
|---|--|
| 100 DURGIN LANE DEVELOPMENT<br>PORTSMOUTH, NH |  |
| SITE GENERATED TRAFFIC VOLUMES                |  |
| DATE: 04/29/2024                              |  |
| SCALE: NTS                                    |  |
| FIGURE 6                                      |  |

Apr 29, 2024-10:18am Plotted By: MBlair Tighe & Bond, Inc. J:\VE\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Figures\E5071-001 Traffic Volume Figures.dwg




|   |  |
|---|--|
| 100 DURGIN LANE DEVELOPMENT<br>PORTSMOUTH, NH |  |
| 2026 BULD<br>TRAFFIC VOLUMES                  |  |
| DATE: 04/29/2024                              |  |
| SCALE: NTS                                    |  |
| FIGURE 7                                      |  |

Apr 29, 2024-10:18am Plotted By: MBlair Tighe & Bond, Inc. J:\VE\5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane\Drawings\AutoCAD\Figures\E5071-001 Traffic Volume Figures.dwg



|   |  |
|---|--|
| <b>100 DURGIN LANE DEVELOPMENT<br/>PORTSMOUTH, NH</b> |  |
| <b>2036 BUILD<br/>TRAFFIC VOLUMES</b>                 |  |
| DATE: 04/29/2024                                      |  |
| SCALE: NTS  |  |
| FIGURE 8  |  |

**APPENDIX A**  
Traffic Count Data



Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 1  
 Location: Portsmouth, NH  
 Street 1: Newington Street  
 Street 2: US Route 4 Southbound Ramps  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|------------|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|            | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
| 7:00 AM    | 0  | 0    | 0    | 0     | 0   | 38   | 0    | 100   | 0                          | 0    | 37   | 13    | 0                          | 17   | 97   | 0     |
| 7:15 AM    | 0  | 0    | 0    | 0     | 0   | 48   | 0    | 122   | 0                          | 0    | 21   | 10    | 0                          | 17   | 101  | 0     |
| 7:30 AM    | 0  | 0    | 0    | 0     | 0   | 68   | 0    | 130   | 0                          | 0    | 45   | 13    | 0                          | 16   | 130  | 0     |
| 7:45 AM    | 0  | 0    | 0    | 0     | 0   | 97   | 0    | 175   | 0                          | 0    | 43   | 19    | 0                          | 21   | 203  | 0     |
| 8:00 AM    | 0  | 0    | 0    | 0     | 0   | 78   | 0    | 159   | 1                          | 0    | 34   | 19    | 1                          | 16   | 177  | 0     |
| 8:15 AM    | 0  | 0    | 0    | 0     | 0   | 97   | 0    | 126   | 0                          | 0    | 41   | 19    | 0                          | 26   | 170  | 0     |
| 8:30 AM    | 0  | 0    | 0    | 0     | 0   | 77   | 0    | 123   | 0                          | 0    | 46   | 19    | 0                          | 23   | 142  | 0     |
| 8:45 AM    | 0  | 0    | 0    | 0     | 0   | 61   | 0    | 111   | 0                          | 0    | 59   | 23    | 1                          | 21   | 133  | 0     |

| Start Time | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|------------|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|            | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
| 4:00 PM    | 0  | 0    | 0    | 0     | 0   | 51   | 0    | 15    | 0                          | 0    | 194  | 111   | 0                          | 74   | 60   | 0     |
| 4:15 PM    | 0  | 0    | 0    | 0     | 0   | 53   | 0    | 18    | 0                          | 0    | 171  | 109   | 0                          | 77   | 80   | 0     |
| 4:30 PM    | 0  | 0    | 0    | 0     | 0   | 39   | 0    | 32    | 0                          | 0    | 190  | 113   | 0                          | 84   | 83   | 0     |
| 4:45 PM    | 0  | 0    | 0    | 0     | 0   | 47   | 0    | 15    | 0                          | 0    | 194  | 93    | 1                          | 77   | 62   | 0     |
| 5:00 PM    | 0  | 0    | 0    | 0     | 0   | 46   | 0    | 17    | 0                          | 0    | 241  | 128   | 0                          | 118  | 47   | 0     |
| 5:15 PM    | 0  | 0    | 0    | 0     | 0   | 46   | 1    | 16    | 0                          | 0    | 193  | 95    | 1                          | 79   | 36   | 0     |
| 5:30 PM    | 0  | 0    | 0    | 0     | 0   | 42   | 0    | 16    | 0                          | 0    | 153  | 70    | 0                          | 78   | 53   | 0     |
| 5:45 PM    | 0  | 0    | 0    | 0     | 0   | 44   | 0    | 19    | 0                          | 0    | 80   | 47    | 1                          | 80   | 53   | 0     |

| AM PEAK HOUR<br>7:45 AM to 8:45 AM | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |       |      |       |
|------------------------------------|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|-------|------|-------|
|                                    | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left  | Thru | Right |
|                                    | 0  | 0    | 0    | 0     | 0   | 349  | 0    | 583   | 1                          | 0    | 164  | 76    | 1                          | 86    | 692  | 0     |
| <b>PHF</b>                         | 0.00                                     |      |      |       | 0.86                                      |      |      |       | 0.93                       |      |      |       | 0.87                       |       |      |       |
| <b>HV %</b>                        | 0.0%                                     | 0.0% | 0.0% | 0.0%  | 0.0%                                      | 0.3% | 0.0% | 1.2%  | 0.0%                       | 0.0% | 2.4% | 5.3%  | 0.0%                       | 12.8% | 1.3% | 0.0%  |

| PM PEAK HOUR<br>4:15 PM to 5:15 PM | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|------------------------------------|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|                                    | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
|                                    | 0  | 0    | 0    | 0     | 0   | 185  | 0    | 82    | 0                          | 0    | 796  | 443   | 1                          | 356  | 272  | 0     |
| <b>PHF</b>                         | 0.00                                     |      |      |       | 0.94                                      |      |      |       | 0.84                       |      |      |       | 0.94                       |      |      |       |
| <b>HV %</b>                        | 0.0%                                     | 0.0% | 0.0% | 0.0%  | 0.0%                                      | 0.5% | 0.0% | 0.0%  | 0.0%                       | 0.0% | 0.3% | 0.7%  | 0.0%                       | 1.1% | 0.7% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 1  
 Location: Portsmouth, NH  
 Street 1: Newington Street  
 Street 2: US Route 4 Southbound Ramps  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**HEAVY VEHICLES**

| Start Time | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|------------|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|            | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
| 7:00 AM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 1    | 2     | 0                          | 0    | 0    | 0     |
| 7:15 AM    | 0  | 0    | 0    | 0     | 0   | 1    | 0    | 2     | 0                          | 0    | 0    | 2     | 0                          | 4    | 2    | 0     |
| 7:30 AM    | 0  | 0    | 0    | 0     | 0   | 1    | 0    | 1     | 0                          | 0    | 1    | 1     | 0                          | 2    | 2    | 0     |
| 7:45 AM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 2     | 0                          | 0    | 1    | 0     | 0                          | 3    | 2    | 0     |
| 8:00 AM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 1     | 0                          | 0    | 1    | 3     | 0                          | 2    | 3    | 0     |
| 8:15 AM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 4    | 1    | 0     |
| 8:30 AM    | 0  | 0    | 0    | 0     | 0   | 1    | 0    | 4     | 0                          | 0    | 2    | 1     | 0                          | 2    | 3    | 0     |
| 8:45 AM    | 0  | 0    | 0    | 0     | 0   | 2    | 0    | 0     | 0                          | 0    | 3    | 1     | 0                          | 3    | 1    | 0     |

| Start Time | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|------------|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|            | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
| 4:00 PM    | 0  | 0    | 0    | 0     | 0   | 1    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     |
| 4:15 PM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 1    | 0     | 0                          | 0    | 0    | 0     |
| 4:30 PM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 1    | 1     | 0                          | 0    | 2    | 0     |
| 4:45 PM    | 0  | 0    | 0    | 0     | 0   | 1    | 0    | 0     | 0                          | 0    | 0    | 1     | 0                          | 3    | 0    | 0     |
| 5:00 PM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 0    | 1     | 0                          | 1    | 0    | 0     |
| 5:15 PM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 1    | 0     | 0                          | 2    | 0    | 0     |
| 5:30 PM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     |
| 5:45 PM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 1     | 0                          | 0    | 0    | 0     | 0                          | 1    | 0    | 0     |

| AM PEAK HOUR<br>8:00 AM to 9:00 AM<br>PHF | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|---|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|   | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
|   | 0  | 0    | 0    | 0     | 0   | 3    | 0    | 5     | 0                          | 0    | 6    | 5     | 0                          | 11   | 8    | 0     |
|   | 0.00                                     |      |      |       | 0.40                                      |      |      |       | 0.69                       |      |      |       | 0.95                       |      |      |       |

| PM PEAK HOUR<br>4:30 PM to 5:30 PM<br>PHF | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|---|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|   | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
|   | 0  | 0    | 0    | 0     | 0   | 1    | 0    | 0     | 0                          | 0    | 2    | 3     | 0                          | 6    | 2    | 0     |
|   | 0.00                                     |      |      |       | 0.25                                      |      |      |       | 0.63                       |      |      |       | 0.67                       |      |      |       |



Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 1  
 Location: Portsmouth, NH  
 Street 1: Newington Street  
 Street 2: US Route 4 Southbound Ramps  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PEDESTRIANS & BICYCLES**

| Start Time | US Route 4 Southbound On Ramp Northbound |      |       |     | US Route 4 Southbound Off Ramp Southbound |      |       |     | Newington Street Eastbound |      |       | Newington Street Westbound |      |      |       |     |
|------------|--|------|-------|-----|---|------|-------|-----|----------------------------|------|-------|----------------------------|------|------|-------|-----|
|            | Left                                     | Thru | Right | PED | Left                                      | Thru | Right | PED | Left                       | Thru | Right | PED                        | Left | Thru | Right | PED |
| 7:00 AM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 7:15 AM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 7:30 AM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 7:45 AM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 8:00 AM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 8:15 AM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 8:30 AM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 8:45 AM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |

| Start Time | US Route 4 Southbound On Ramp Northbound |      |       |     | US Route 4 Southbound Off Ramp Southbound |      |       |     | Newington Street Eastbound |      |       | Newington Street Westbound |      |      |       |     |
|------------|--|------|-------|-----|---|------|-------|-----|----------------------------|------|-------|----------------------------|------|------|-------|-----|
|            | Left                                     | Thru | Right | PED | Left                                      | Thru | Right | PED | Left                       | Thru | Right | PED                        | Left | Thru | Right | PED |
| 4:00 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 2   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 4:15 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 4:30 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 4:45 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 5:00 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 5:15 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 5:30 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |
| 5:45 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |

| AM PEAK HOUR <sup>1</sup><br>7:45 AM to 8:45 AM | US Route 4 Southbound On Ramp Northbound |      |       |     | US Route 4 Southbound Off Ramp Southbound |      |       |     | Newington Street Eastbound |      |       | Newington Street Westbound |      |      |       |     |
|---|--|------|-------|-----|---|------|-------|-----|----------------------------|------|-------|----------------------------|------|------|-------|-----|
|   | Left                                     | Thru | Right | PED | Left                                      | Thru | Right | PED | Left                       | Thru | Right | PED                        | Left | Thru | Right | PED |
|   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |

| PM PEAK HOUR <sup>1</sup><br>4:15 PM to 5:15 PM | US Route 4 Southbound On Ramp Northbound |      |       |     | US Route 4 Southbound Off Ramp Southbound |      |       |     | Newington Street Eastbound |      |       | Newington Street Westbound |      |      |       |     |
|---|--|------|-------|-----|---|------|-------|-----|----------------------------|------|-------|----------------------------|------|------|-------|-----|
|   | Left                                     | Thru | Right | PED | Left                                      | Thru | Right | PED | Left                       | Thru | Right | PED                        | Left | Thru | Right | PED |
|   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0                          | 0    | 0    | 0     | 0   |

<sup>1</sup> NOTE: Peak hour summaries here correspond to peak hours identified for passenger cars and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 1  
 Location: Portsmouth, NH  
 Street 1: Newington Street  
 Street 2: US Route 4 Southbound Ramps  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|------------|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|            | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
| 11:00 AM   | 0  | 0    | 0    | 0     | 0   | 42   | 1    | 9     | 0                          | 0    | 26   | 10    | 0                          | 40   | 29   | 0     |
| 11:15 AM   | 0  | 0    | 0    | 0     | 0   | 40   | 3    | 7     | 0                          | 0    | 38   | 13    | 1                          | 54   | 31   | 0     |
| 11:30 AM   | 0  | 0    | 0    | 0     | 0   | 48   | 0    | 13    | 0                          | 0    | 48   | 11    | 1                          | 56   | 31   | 0     |
| 11:45 AM   | 0  | 0    | 0    | 0     | 0   | 52   | 0    | 13    | 0                          | 0    | 54   | 20    | 2                          | 45   | 32   | 0     |
| 12:00 PM   | 0  | 0    | 0    | 0     | 0   | 59   | 1    | 8     | 0                          | 0    | 51   | 17    | 1                          | 54   | 31   | 0     |
| 12:15 PM   | 0  | 0    | 0    | 0     | 0   | 46   | 0    | 2     | 0                          | 0    | 47   | 6     | 1                          | 77   | 29   | 0     |
| 12:30 PM   | 0  | 0    | 0    | 0     | 0   | 43   | 0    | 10    | 0                          | 0    | 40   | 2     | 0                          | 57   | 33   | 0     |
| 12:45 PM   | 0  | 0    | 0    | 0     | 0   | 56   | 0    | 8     | 0                          | 0    | 41   | 3     | 0                          | 72   | 32   | 0     |
| 1:00 PM    | 0  | 0    | 0    | 0     | 0   | 53   | 1    | 3     | 0                          | 0    | 48   | 9     | 1                          | 76   | 38   | 0     |
| 1:15 PM    | 0  | 0    | 0    | 0     | 0   | 42   | 0    | 7     | 1                          | 0    | 42   | 10    | 2                          | 62   | 33   | 0     |
| 1:30 PM    | 0  | 0    | 0    | 0     | 0   | 64   | 0    | 5     | 1                          | 0    | 39   | 5     | 1                          | 78   | 29   | 0     |
| 1:45 PM    | 0  | 0    | 0    | 0     | 0   | 55   | 0    | 9     | 0                          | 0    | 48   | 10    | 1                          | 74   | 27   | 0     |

| MID PEAK HOUR<br>1:00 PM<br>to<br>2:00 PM | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|---|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|   | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
|   | 0  | 0    | 0    | 0     | 0   | 214  | 1    | 24    | 2                          | 0    | 177  | 34    | 5                          | 290  | 127  | 0     |
| <i>PHF</i>                                | 0.00                                     |      |      |       | 0.87                                      |      |      |       | 0.92                       |      |      |       | 0.92                       |      |      |       |
| <i>HV %</i>                               | 0.0%                                     | 0.0% | 0.0% | 0.0%  | 0.0%                                      | 0.9% | 0.0% | 0.0%  | 0.0%                       | 0.0% | 1.1% | 0.0%  | 0.0%                       | 0.7% | 0.0% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 1  
 Location: Portsmouth, NH  
 Street 1: Newington Street  
 Street 2: US Route 4 Southbound Ramps  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**HEAVY VEHICLES**

| Start Time | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|------------|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|            | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
| 11:00 AM   | 0  | 0    | 0    | 0     | 0   | 1    | 0    | 0     | 0                          | 0    | 1    | 0     | 0                          | 0    | 0    | 0     |
| 11:15 AM   | 0  | 0    | 0    | 0     | 0   | 0    | 3    | 0     | 0                          | 0    | 0    | 0     | 0                          | 0    | 2    | 0     |
| 11:30 AM   | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 1    | 1    | 0     |
| 11:45 AM   | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 3     | 0                          | 0    | 0    | 3     | 0                          | 2    | 0    | 0     |
| 12:00 PM   | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 0    | 1     | 0                          | 1    | 0    | 0     |
| 12:15 PM   | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     |
| 12:30 PM   | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     |
| 12:45 PM   | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     |
| 1:00 PM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 1    | 0    | 0     |
| 1:15 PM    | 0  | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                          | 0    | 2    | 0     | 0                          | 0    | 0    | 0     |
| 1:30 PM    | 0  | 0    | 0    | 0     | 0   | 1    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 1    | 0    | 0     |
| 1:45 PM    | 0  | 0    | 0    | 0     | 0   | 1    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     |

| MID PEAK HOUR<br>11:00 AM<br>to<br>12:00 PM<br><i>PHF</i> | US Route 4 Southbound On Ramp Northbound |      |      |       | US Route 4 Southbound Off Ramp Southbound |      |      |       | Newington Street Eastbound |      |      |       | Newington Street Westbound |      |      |       |
|---|--|------|------|-------|---|------|------|-------|----------------------------|------|------|-------|----------------------------|------|------|-------|
|   | U-Turn                                   | Left | Thru | Right | U-Turn                                    | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right |
|   | 0  | 0    | 0    | 0     | 0   | 1    | 3    | 3     | 0                          | 0    | 1    | 3     | 0                          | 3    | 3    | 0     |
|   | <b>0.00</b>                              |      |      |       | <b>0.58</b>                               |      |      |       | <b>0.33</b>                |      |      |       | <b>0.75</b>                |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 1  
 Location: Portsmouth, NH  
 Street 1: Newington Street  
 Street 2: US Route 4 Southbound Ramps  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PEDESTRIANS & BICYCLES**

| Start Time | US Route 4 Southbound On Ramp Northbound |      |       |     | US Route 4 Southbound Off Ramp Southbound |      |       |     | Newington Street Eastbound |      |       |     | Newington Street Westbound |      |       |     |
|------------|--|------|-------|-----|---|------|-------|-----|----------------------------|------|-------|-----|----------------------------|------|-------|-----|
|            | Left                                     | Thru | Right | PED | Left                                      | Thru | Right | PED | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED |
| 11:00 AM   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 11:15 AM   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 11:30 AM   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 11:45 AM   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 12:00 PM   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 12:15 PM   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 12:30 PM   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 12:45 PM   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 1:00 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 1:15 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 1:30 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |
| 1:45 PM    | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |

| MID PEAK HOUR<br>1:00 PM<br>to<br>2:00 PM | US Route 4 Southbound On Ramp Northbound |      |       |     | US Route 4 Southbound Off Ramp Southbound |      |       |     | Newington Street Eastbound |      |       |     | Newington Street Westbound |      |       |     |
|---|--|------|-------|-----|---|------|-------|-----|----------------------------|------|-------|-----|----------------------------|------|-------|-----|
|   | Left                                     | Thru | Right | PED | Left                                      | Thru | Right | PED | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED |
|   | 0  | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   |

NOTE: Peak hour summaries here correspond to peak hours identified for passenger car and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 2  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: US Route 4 Northbound Ramps  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 7:00 AM    | 0   | 69   | 0    | 43    | 0  | 0    | 0    | 0     | 0                      | 24   | 50   | 0     | 0                      | 0    | 39   | 7     |
| 7:15 AM    | 0   | 74   | 0    | 44    | 0  | 0    | 0    | 0     | 0                      | 6    | 64   | 0     | 0                      | 0    | 47   | 11    |
| 7:30 AM    | 0   | 100  | 0    | 52    | 0  | 0    | 0    | 0     | 0                      | 24   | 88   | 0     | 0                      | 0    | 41   | 8     |
| 7:45 AM    | 0   | 163  | 0    | 50    | 0  | 0    | 0    | 0     | 0                      | 16   | 122  | 0     | 0                      | 0    | 66   | 6     |
| 8:00 AM    | 0   | 136  | 0    | 65    | 0  | 0    | 0    | 0     | 0                      | 11   | 105  | 0     | 0                      | 0    | 56   | 10    |
| 8:15 AM    | 0   | 148  | 0    | 53    | 0  | 0    | 0    | 0     | 0                      | 16   | 121  | 0     | 0                      | 0    | 50   | 8     |
| 8:30 AM    | 0   | 114  | 0    | 50    | 0  | 0    | 0    | 0     | 0                      | 22   | 102  | 0     | 0                      | 0    | 48   | 13    |
| 8:45 AM    | 0   | 103  | 0    | 54    | 0  | 0    | 0    | 0     | 0                      | 20   | 101  | 0     | 0                      | 0    | 54   | 5     |

| Start Time | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 4:00 PM    | 0   | 24   | 0    | 83    | 0  | 0    | 0    | 0     | 0                      | 131  | 114  | 0     | 0                      | 0    | 110  | 58    |
| 4:15 PM    | 0   | 42   | 0    | 94    | 0  | 0    | 0    | 0     | 0                      | 107  | 117  | 0     | 0                      | 0    | 114  | 65    |
| 4:30 PM    | 0   | 32   | 0    | 105   | 0  | 0    | 0    | 0     | 0                      | 121  | 105  | 0     | 0                      | 0    | 131  | 58    |
| 4:45 PM    | 0   | 25   | 0    | 93    | 0  | 0    | 0    | 0     | 0                      | 117  | 133  | 0     | 0                      | 0    | 123  | 81    |
| 5:00 PM    | 0   | 32   | 0    | 93    | 0  | 0    | 0    | 0     | 0                      | 144  | 138  | 0     | 0                      | 0    | 129  | 70    |
| 5:15 PM    | 0   | 20   | 0    | 108   | 0  | 0    | 0    | 0     | 0                      | 120  | 127  | 0     | 0                      | 0    | 96   | 49    |
| 5:30 PM    | 0   | 21   | 1    | 85    | 0  | 0    | 0    | 0     | 0                      | 77   | 111  | 0     | 0                      | 0    | 103  | 76    |
| 5:45 PM    | 0   | 28   | 1    | 93    | 0  | 0    | 0    | 0     | 0                      | 41   | 84   | 0     | 1                      | 0    | 113  | 48    |

| AM PEAK HOUR<br>7:45 AM<br>to<br>8:45 AM | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|--|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|  | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|  | 0   | 561  | 0    | 218   | 0  | 0    | 0    | 0     | 0                      | 65   | 450  | 0     | 0                      | 0    | 220  | 37    |
| <b>PHF</b>                               | 0.91                                      |      |      |       | 0.00                                     |      |      |       | 0.93                   |      |      |       | 0.89                   |      |      |       |
| <b>HV %</b>                              | 0.0%                                      | 1.6% | 0.0% | 6.4%  | 0.0%                                     | 0.0% | 0.0% | 0.0%  | 0.0%                   | 3.1% | 0.7% | 0.0%  | 0.0%                   | 0.0% | 5.5% | 0.0%  |

| PM PEAK HOUR<br>4:15 PM<br>to<br>5:15 PM | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|--|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|  | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|  | 0   | 131  | 0    | 385   | 0  | 0    | 0    | 0     | 0                      | 489  | 493  | 0     | 0                      | 0    | 497  | 274   |
| <b>PHF</b>                               | 0.94                                      |      |      |       | 0.00                                     |      |      |       | 0.87                   |      |      |       | 0.94                   |      |      |       |
| <b>HV %</b>                              | 0.0%                                      | 1.5% | 0.0% | 1.8%  | 0.0%                                     | 0.0% | 0.0% | 0.0%  | 0.0%                   | 0.2% | 0.4% | 0.0%  | 0.0%                   | 0.0% | 0.8% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 2  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: US Route 4 Northbound Ramps  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**HEAVY VEHICLES**

| Start Time | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 7:00 AM    | 0   | 0    | 0    | 5     | 0  | 0    | 0    | 0     | 0                      | 1    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 7:15 AM    | 0   | 2    | 0    | 7     | 0  | 0    | 0    | 0     | 0                      | 0    | 1    | 0     | 0                      | 0    | 5    | 0     |
| 7:30 AM    | 0   | 2    | 0    | 3     | 0  | 0    | 0    | 0     | 0                      | 1    | 1    | 0     | 0                      | 0    | 1    | 1     |
| 7:45 AM    | 0   | 2    | 0    | 2     | 0  | 0    | 0    | 0     | 0                      | 0    | 1    | 0     | 0                      | 0    | 3    | 0     |
| 8:00 AM    | 0   | 2    | 0    | 5     | 0  | 0    | 0    | 0     | 0                      | 0    | 1    | 0     | 0                      | 0    | 4    | 0     |
| 8:15 AM    | 0   | 2    | 0    | 5     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 3    | 0     |
| 8:30 AM    | 0   | 3    | 0    | 2     | 0  | 0    | 0    | 0     | 0                      | 2    | 1    | 0     | 0                      | 0    | 2    | 0     |
| 8:45 AM    | 0   | 1    | 0    | 1     | 0  | 0    | 0    | 0     | 0                      | 1    | 4    | 0     | 0                      | 0    | 2    | 0     |

| Start Time | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 4:00 PM    | 0   | 0    | 0    | 0     | 0  | 0    | 0    | 0     | 0                      | 0    | 1    | 0     | 0                      | 0    | 0    | 0     |
| 4:15 PM    | 0   | 0    | 0    | 2     | 0  | 0    | 0    | 0     | 0                      | 0    | 1    | 0     | 0                      | 0    | 0    | 0     |
| 4:30 PM    | 0   | 1    | 0    | 2     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 1    | 0     |
| 4:45 PM    | 0   | 1    | 0    | 1     | 0  | 0    | 0    | 0     | 0                      | 1    | 1    | 0     | 0                      | 0    | 2    | 0     |
| 5:00 PM    | 0   | 0    | 0    | 2     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 1    | 0     |
| 5:15 PM    | 0   | 0    | 0    | 0     | 0  | 0    | 0    | 0     | 0                      | 1    | 0    | 0     | 0                      | 0    | 2    | 0     |
| 5:30 PM    | 0   | 0    | 0    | 0     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 5:45 PM    | 0   | 0    | 0    | 1     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 1    | 0     |

| AM PEAK HOUR<br>7:15 AM to 8:15 AM<br>PHF | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|---|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|   | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|   | 0   | 8    | 0    | 17    | 0  | 0    | 0    | 0     | 0                      | 1    | 4    | 0     | 0                      | 0    | 13   | 1     |
|   | 0.69                                      |      |      |       | 0.00                                     |      |      |       | 0.63                   |      |      |       | 0.70                   |      |      |       |

| PM PEAK HOUR<br>4:15 PM to 5:15 PM<br>PHF | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|---|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|   | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|   | 0   | 2    | 0    | 7     | 0  | 0    | 0    | 0     | 0                      | 1    | 2    | 0     | 0                      | 0    | 4    | 0     |
|   | 0.75                                      |      |      |       | 0.00                                     |      |      |       | 0.38                   |      |      |       | 0.50                   |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 2  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: US Route 4 Northbound Ramps  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PEDESTRIANS & BICYCLES**

| Start Time | US Route 4 Northbound Off Ramp Northbound |      |       |     | US Route 4 Northbound On Ramp Southbound |      |       |     | Gosling Road Eastbound |      |       | Gosling Road Westbound |      |      |       |     |
|------------|---|------|-------|-----|--|------|-------|-----|------------------------|------|-------|------------------------|------|------|-------|-----|
|            | Left                                      | Thru | Right | PED | Left                                     | Thru | Right | PED | Left                   | Thru | Right | PED                    | Left | Thru | Right | PED |
| 7:00 AM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 7:15 AM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 1   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 7:30 AM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 7:45 AM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 8:00 AM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 8:15 AM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 8:30 AM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 8:45 AM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |

| Start Time | US Route 4 Northbound Off Ramp Northbound |      |       |     | US Route 4 Northbound On Ramp Southbound |      |       |     | Gosling Road Eastbound |      |       | Gosling Road Westbound |      |      |       |     |
|------------|---|------|-------|-----|--|------|-------|-----|------------------------|------|-------|------------------------|------|------|-------|-----|
|            | Left                                      | Thru | Right | PED | Left                                     | Thru | Right | PED | Left                   | Thru | Right | PED                    | Left | Thru | Right | PED |
| 4:00 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 1   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 4:15 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 4:30 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 4:45 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 5:00 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 5:15 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 5:30 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 5:45 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |

| AM PEAK HOUR <sup>1</sup><br>7:45 AM to 8:45 AM | US Route 4 Northbound Off Ramp Northbound |      |       |     | US Route 4 Northbound On Ramp Southbound |      |       |     | Gosling Road Eastbound |      |       | Gosling Road Westbound |      |      |       |     |
|---|---|------|-------|-----|--|------|-------|-----|------------------------|------|-------|------------------------|------|------|-------|-----|
|   | Left                                      | Thru | Right | PED | Left                                     | Thru | Right | PED | Left                   | Thru | Right | PED                    | Left | Thru | Right | PED |
|   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |

| PM PEAK HOUR <sup>1</sup><br>4:15 PM to 5:15 PM | US Route 4 Northbound Off Ramp Northbound |      |       |     | US Route 4 Northbound On Ramp Southbound |      |       |     | Gosling Road Eastbound |      |       | Gosling Road Westbound |      |      |       |     |
|---|---|------|-------|-----|--|------|-------|-----|------------------------|------|-------|------------------------|------|------|-------|-----|
|   | Left                                      | Thru | Right | PED | Left                                     | Thru | Right | PED | Left                   | Thru | Right | PED                    | Left | Thru | Right | PED |
|   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |

<sup>1</sup> NOTE: Peak hour summaries here correspond to peak hours identified for passenger cars and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 2  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: US Route 4 Northbound Ramps  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 11:00 AM   | 0   | 15   | 0    | 86    | 0  | 0    | 0    | 0     | 0                      | 5    | 63   | 0     | 0                      | 0    | 54   | 21    |
| 11:15 AM   | 0   | 16   | 3    | 68    | 0  | 0    | 0    | 0     | 0                      | 9    | 68   | 0     | 1                      | 0    | 72   | 24    |
| 11:30 AM   | 0   | 15   | 1    | 91    | 0  | 0    | 0    | 0     | 0                      | 14   | 85   | 0     | 0                      | 0    | 70   | 24    |
| 11:45 AM   | 0   | 13   | 0    | 102   | 0  | 0    | 0    | 0     | 0                      | 17   | 90   | 0     | 0                      | 0    | 68   | 33    |
| 12:00 PM   | 0   | 14   | 0    | 97    | 0  | 0    | 0    | 0     | 0                      | 12   | 99   | 0     | 0                      | 0    | 69   | 25    |
| 12:15 PM   | 0   | 9    | 2    | 116   | 0  | 0    | 0    | 0     | 1                      | 18   | 74   | 0     | 0                      | 0    | 97   | 34    |
| 12:30 PM   | 0   | 16   | 0    | 107   | 0  | 0    | 0    | 0     | 0                      | 7    | 80   | 0     | 1                      | 0    | 75   | 30    |
| 12:45 PM   | 0   | 5    | 0    | 81    | 0  | 0    | 0    | 0     | 0                      | 4    | 92   | 0     | 0                      | 0    | 104  | 23    |
| 1:00 PM    | 0   | 19   | 0    | 93    | 0  | 0    | 0    | 0     | 0                      | 16   | 84   | 0     | 0                      | 0    | 93   | 44    |
| 1:15 PM    | 0   | 10   | 0    | 91    | 0  | 0    | 0    | 0     | 0                      | 5    | 81   | 0     | 0                      | 0    | 90   | 49    |
| 1:30 PM    | 0   | 10   | 0    | 98    | 0  | 0    | 0    | 0     | 0                      | 7    | 99   | 0     | 1                      | 0    | 96   | 27    |
| 1:45 PM    | 0   | 8    | 0    | 100   | 0  | 0    | 0    | 0     | 0                      | 8    | 95   | 0     | 0                      | 0    | 92   | 37    |

| MID PEAK HOUR<br>1:00 PM<br>to<br>2:00 PM | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|---|---|------|------|-------|--|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|   | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|   | 0   | 47   | 0    | 382   | 0  | 0    | 0    | 0     | 0                      | 36   | 359  | 0     | 1                      | 0    | 371  | 157   |
| <i>PHF</i>                                | <b>0.96</b>                               |      |      |       | <b>0.00</b>                              |      |      |       | <b>0.93</b>            |      |      |       | <b>0.95</b>            |      |      |       |
| <i>HV %</i>                               | 0.0%                                      | 0.0% | 0.0% | 0.3%  | 0.0%                                     | 0.0% | 0.0% | 0.0%  | 0.0%                   | 2.8% | 0.8% | 0.0%  | 0.0%                   | 0.0% | 0.5% | 0.0%  |



Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 2  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: US Route 4 Northbound Ramps  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**HEAVY VEHICLES**

| Start Time | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      | Gosling Road Westbound |        |      |      |       |
|------------|---|------|------|-------|--|------|------|-------|------------------------|------|------|------------------------|--------|------|------|-------|
|            | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right                  | U-Turn | Left | Thru | Right |
| 11:00 AM   | 0   | 0    | 0    | 0     | 0  | 0    | 0    | 0     | 0                      | 0    | 2    | 0                      | 0      | 0    | 0    | 0     |
| 11:15 AM   | 0   | 1    | 3    | 0     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 1    | 0     |
| 11:30 AM   | 0   | 1    | 0    | 0     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 2    | 0     |
| 11:45 AM   | 0   | 1    | 0    | 3     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 0    | 3     |
| 12:00 PM   | 0   | 0    | 0    | 0     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 1    | 0     |
| 12:15 PM   | 0   | 0    | 0    | 1     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 0    | 0     |
| 12:30 PM   | 0   | 0    | 0    | 1     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 0    | 0     |
| 12:45 PM   | 0   | 0    | 0    | 1     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 0    | 0     |
| 1:00 PM    | 0   | 0    | 0    | 1     | 0  | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 1    | 0     |
| 1:15 PM    | 0   | 0    | 0    | 0     | 0  | 0    | 0    | 0     | 0                      | 0    | 2    | 0                      | 0      | 0    | 0    | 0     |
| 1:30 PM    | 0   | 0    | 0    | 0     | 0  | 0    | 0    | 0     | 0                      | 0    | 1    | 0                      | 0      | 0    | 1    | 0     |
| 1:45 PM    | 0   | 0    | 0    | 0     | 0  | 0    | 0    | 0     | 0                      | 1    | 0    | 0                      | 0      | 0    | 0    | 0     |

| MID PEAK HOUR<br>11:00 AM<br>to<br>12:00 PM<br><i>PHF</i> | US Route 4 Northbound Off Ramp Northbound |      |      |       | US Route 4 Northbound On Ramp Southbound |      |      |       | Gosling Road Eastbound |      |      | Gosling Road Westbound |        |      |      |       |
|---|---|------|------|-------|--|------|------|-------|------------------------|------|------|------------------------|--------|------|------|-------|
|   | U-Turn                                    | Left | Thru | Right | U-Turn                                   | Left | Thru | Right | U-Turn                 | Left | Thru | Right                  | U-Turn | Left | Thru | Right |
|   | 0   | 3    | 3    | 3     | 0  | 0    | 0    | 0     | 0                      | 0    | 2    | 0                      | 0      | 0    | 3    | 3     |
|   | <b>0.56</b>                               |      |      |       | <b>0.00</b>                              |      |      |       | <b>0.25</b>            |      |      | <b>0.50</b>            |        |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 2  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: US Route 4 Northbound Ramps  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PEDESTRIANS & BICYCLES**

| Start Time | US Route 4 Northbound Off Ramp Northbound |      |       |     | US Route 4 Northbound On Ramp Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|------------|---|------|-------|-----|--|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|            | Left                                      | Thru | Right | PED | Left                                     | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
| 11:00 AM   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 11:15 AM   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 11:30 AM   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 11:45 AM   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:00 PM   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:15 PM   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:30 PM   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:45 PM   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:00 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:15 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:30 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:45 PM    | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |

| MID PEAK HOUR<br>1:00 PM<br>to<br>2:00 PM | US Route 4 Northbound Off Ramp Northbound |      |       |     | US Route 4 Northbound On Ramp Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|---|---|------|-------|-----|--|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|   | Left                                      | Thru | Right | PED | Left                                     | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
|   | 0   | 0    | 0     | 0   | 0  | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |

NOTE: Peak hour summaries here correspond to peak hours identified for passenger car and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 3  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: Motel 6/North site access drive  
 Count Date: 3/20/2024  
 Day of Week: Thursday  
 Weather: Clouds & Sun, 50°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Motel 6/North site access drive Northbound |        |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|--|--------|------|------|-------|------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
| Start Time                                 | U-Turn | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 7:00 AM                                    | 0      | 0    | 0    | 5     | 0          | 0    | 0    | 0     | 0                      | 0    | 83   | 7     | 0                      | 0    | 47   | 0     |
| 7:15 AM                                    | 0      | 0    | 0    | 2     | 0          | 0    | 0    | 0     | 0                      | 0    | 104  | 7     | 0                      | 0    | 58   | 0     |
| 7:30 AM                                    | 0      | 0    | 0    | 5     | 0          | 0    | 0    | 0     | 0                      | 0    | 130  | 5     | 0                      | 0    | 51   | 0     |
| 7:45 AM                                    | 0      | 0    | 0    | 1     | 0          | 0    | 0    | 0     | 0                      | 0    | 148  | 26    | 0                      | 0    | 72   | 0     |
| 8:00 AM                                    | 0      | 0    | 0    | 6     | 0          | 0    | 0    | 0     | 0                      | 0    | 156  | 14    | 0                      | 0    | 62   | 0     |
| 8:15 AM                                    | 0      | 0    | 0    | 2     | 0          | 0    | 0    | 0     | 0                      | 0    | 159  | 15    | 0                      | 0    | 58   | 0     |
| 8:30 AM                                    | 0      | 0    | 0    | 2     | 0          | 0    | 0    | 0     | 0                      | 0    | 133  | 21    | 0                      | 0    | 64   | 0     |
| 8:45 AM                                    | 0      | 0    | 0    | 2     | 0          | 0    | 0    | 0     | 0                      | 0    | 141  | 15    | 0                      | 0    | 57   | 0     |

| Motel 6/North site access drive Northbound |        |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|--|--------|------|------|-------|------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
| Start Time                                 | U-Turn | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 4:00 PM                                    | 0      | 0    | 0    | 4     | 0          | 0    | 0    | 0     | 0                      | 0    | 179  | 18    | 0                      | 0    | 169  | 0     |
| 4:15 PM                                    | 0      | 0    | 0    | 5     | 0          | 0    | 0    | 0     | 0                      | 0    | 186  | 22    | 0                      | 0    | 181  | 0     |
| 4:30 PM                                    | 0      | 0    | 0    | 6     | 0          | 0    | 0    | 0     | 0                      | 0    | 193  | 19    | 0                      | 0    | 198  | 0     |
| 4:45 PM                                    | 0      | 0    | 0    | 4     | 0          | 0    | 0    | 0     | 0                      | 0    | 211  | 16    | 0                      | 0    | 195  | 0     |
| 5:00 PM                                    | 0      | 0    | 0    | 8     | 0          | 0    | 0    | 0     | 0                      | 0    | 212  | 21    | 0                      | 0    | 194  | 0     |
| 5:15 PM                                    | 0      | 0    | 0    | 6     | 0          | 0    | 0    | 0     | 0                      | 0    | 221  | 16    | 0                      | 0    | 151  | 0     |
| 5:30 PM                                    | 0      | 0    | 0    | 4     | 0          | 0    | 0    | 0     | 0                      | 0    | 167  | 25    | 0                      | 0    | 174  | 0     |
| 5:45 PM                                    | 0      | 0    | 0    | 3     | 0          | 0    | 0    | 0     | 0                      | 0    | 168  | 10    | 0                      | 0    | 162  | 0     |

| AM PEAK HOUR<br>7:45 AM<br>to<br>8:45 AM | Motel 6/North site access drive Northbound |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|--|--|------|------|-------|------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|  | U-Turn                                     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|  | 0  | 0    | 0    | 11    | 0          | 0    | 0    | 0     | 0                      | 0    | 596  | 76    | 0                      | 0    | 256  | 0     |
| PHF                                      | 0.46                                       |      |      |       | 0.00       |      |      |       | 0.97                   |      |      |       | 0.89                   |      |      |       |
| HV %                                     | 0.0%                                       | 0.0% | 0.0% | 0.0%  | 0.0%       | 0.0% | 0.0% | 0.0%  | 0.0%                   | 0.0% | 2.7% | 1.3%  | 0.0%                   | 0.0% | 4.7% | 0.0%  |

| PM PEAK HOUR<br>4:15 PM<br>to<br>5:15 PM | Motel 6/North site access drive Northbound |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|--|--|------|------|-------|------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|  | U-Turn                                     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|  | 0  | 0    | 0    | 23    | 0          | 0    | 0    | 0     | 0                      | 0    | 802  | 78    | 0                      | 0    | 768  | 0     |
| PHF                                      | 0.72                                       |      |      |       | 0.00       |      |      |       | 0.94                   |      |      |       | 0.97                   |      |      |       |
| HV %                                     | 0.0%                                       | 0.0% | 0.0% | 0.0%  | 0.0%       | 0.0% | 0.0% | 0.0%  | 0.0%                   | 0.0% | 1.1% | 0.0%  | 0.0%                   | 0.0% | 0.5% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 3  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: Motel 6/North site access drive  
 Count Date: 3/20/2024  
 Day of Week: Thursday  
 Weather: Clouds & Sun, 50°F



**HEAVY VEHICLES**

| Start Time | Motel 6/North site access drive Northbound |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|--|------|------|-------|------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                                     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 7:00 AM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 5    | 0     | 0                      | 0    | 0    | 0     |
| 7:15 AM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 8    | 0     | 0                      | 0    | 6    | 0     |
| 7:30 AM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 4    | 0     | 0                      | 0    | 1    | 0     |
| 7:45 AM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 3    | 0     | 0                      | 0    | 3    | 0     |
| 8:00 AM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 5    | 1     | 0                      | 0    | 4    | 0     |
| 8:15 AM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 5    | 0     | 0                      | 0    | 3    | 0     |
| 8:30 AM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 3    | 0     | 0                      | 0    | 2    | 0     |
| 8:45 AM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 5    | 0     | 0                      | 0    | 2    | 0     |

| Start Time | Motel 6/North site access drive Northbound |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|--|------|------|-------|------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                                     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 4:00 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 1    | 0     | 0                      | 0    | 0    | 0     |
| 4:15 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 3    | 0     | 0                      | 0    | 0    | 0     |
| 4:30 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 2    | 0     | 0                      | 0    | 2    | 0     |
| 4:45 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 2    | 0     | 0                      | 0    | 1    | 0     |
| 5:00 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 2    | 0     | 0                      | 0    | 1    | 0     |
| 5:15 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 2    | 0     |
| 5:30 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 5:45 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 1    | 0     | 0                      | 0    | 1    | 0     |

| AM PEAK HOUR<br>7:15 AM to 8:15 AM<br>PHF | Motel 6/North site access drive Northbound |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|---|--|------|------|-------|------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|   | U-Turn                                     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 20   | 1     | 0                      | 0    | 14   | 0     |
|   | 0.00                                       |      |      |       | 0.00       |      |      |       | 0.66                   |      |      |       | 0.58                   |      |      |       |

| PM PEAK HOUR<br>4:15 PM to 5:15 PM<br>PHF | Motel 6/North site access drive Northbound |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|---|--|------|------|-------|------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|   | U-Turn                                     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 9    | 0     | 0                      | 0    | 4    | 0     |
|   | 0.00                                       |      |      |       | 0.00       |      |      |       | 0.75                   |      |      |       | 0.50                   |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 3  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: Motel 6/North site access drive  
 Count Date: 3/20/2024  
 Day of Week: Thursday  
 Weather: Clouds & Sun, 50°F



**PEDESTRIANS & BICYCLES**

| Start Time | Motel 6/North site access drive Northbound |      |       |     | Southbound |      |       |     | Gosling Road Eastbound |      |       | Gosling Road Westbound |      |      |       |     |
|------------|--|------|-------|-----|------------|------|-------|-----|------------------------|------|-------|------------------------|------|------|-------|-----|
|            | Left                                       | Thru | Right | PED | Left       | Thru | Right | PED | Left                   | Thru | Right | PED                    | Left | Thru | Right | PED |
| 7:00 AM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 7:15 AM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 7:30 AM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 7:45 AM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 8:00 AM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 8:15 AM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 8:30 AM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 8:45 AM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |

| Start Time | Motel 6/North site access drive Northbound |      |       |     | Southbound |      |       |     | Gosling Road Eastbound |      |       | Gosling Road Westbound |      |      |       |     |
|------------|--|------|-------|-----|------------|------|-------|-----|------------------------|------|-------|------------------------|------|------|-------|-----|
|            | Left                                       | Thru | Right | PED | Left       | Thru | Right | PED | Left                   | Thru | Right | PED                    | Left | Thru | Right | PED |
| 4:00 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 4:15 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 4:30 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 4:45 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 5:00 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 2   |
| 5:15 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |
| 5:30 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 1   |
| 5:45 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |

| AM PEAK HOUR <sup>1</sup><br>7:45 AM to 8:45 AM | Motel 6/North site access drive Northbound |      |       |     | Southbound |      |       |     | Gosling Road Eastbound |      |       | Gosling Road Westbound |      |      |       |     |
|---|--|------|-------|-----|------------|------|-------|-----|------------------------|------|-------|------------------------|------|------|-------|-----|
|   | Left                                       | Thru | Right | PED | Left       | Thru | Right | PED | Left                   | Thru | Right | PED                    | Left | Thru | Right | PED |
|   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 0   |

| PM PEAK HOUR <sup>1</sup><br>4:15 PM to 5:15 PM | Motel 6/North site access drive Northbound |      |       |     | Southbound |      |       |     | Gosling Road Eastbound |      |       | Gosling Road Westbound |      |      |       |     |
|---|--|------|-------|-----|------------|------|-------|-----|------------------------|------|-------|------------------------|------|------|-------|-----|
|   | Left                                       | Thru | Right | PED | Left       | Thru | Right | PED | Left                   | Thru | Right | PED                    | Left | Thru | Right | PED |
|   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0                      | 0    | 0    | 0     | 2   |

<sup>1</sup> NOTE: Peak hour summaries here correspond to peak hours identified for passenger cars and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 3  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: Motel 6/North site access drive  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | Motel 6/North site access drive Northbound |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|--|------|------|-------|------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                                     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 11:00 AM   | 0  | 0    | 0    | 4     | 0          | 0    | 0    | 0     | 0                      | 0    | 142  | 9     | 0                      | 0    | 78   | 0     |
| 11:15 AM   | 0  | 0    | 0    | 8     | 0          | 0    | 0    | 0     | 0                      | 0    | 129  | 13    | 0                      | 0    | 97   | 0     |
| 11:30 AM   | 0  | 0    | 0    | 4     | 0          | 0    | 0    | 0     | 0                      | 0    | 157  | 14    | 0                      | 0    | 94   | 0     |
| 11:45 AM   | 0  | 0    | 0    | 15    | 0          | 0    | 0    | 0     | 0                      | 0    | 189  | 9     | 0                      | 0    | 98   | 0     |
| 12:00 PM   | 0  | 0    | 0    | 5     | 0          | 0    | 0    | 0     | 0                      | 0    | 181  | 12    | 0                      | 0    | 95   | 0     |
| 12:15 PM   | 0  | 0    | 0    | 7     | 0          | 0    | 0    | 0     | 0                      | 0    | 174  | 15    | 0                      | 0    | 131  | 0     |
| 12:30 PM   | 0  | 0    | 0    | 7     | 0          | 0    | 0    | 0     | 0                      | 0    | 181  | 8     | 0                      | 0    | 107  | 0     |
| 12:45 PM   | 0  | 0    | 0    | 3     | 0          | 0    | 0    | 0     | 0                      | 0    | 157  | 15    | 0                      | 0    | 127  | 0     |
| 1:00 PM    | 0  | 0    | 0    | 11    | 0          | 0    | 0    | 0     | 0                      | 0    | 162  | 15    | 0                      | 0    | 136  | 0     |
| 1:15 PM    | 0  | 0    | 0    | 2     | 0          | 0    | 0    | 0     | 0                      | 0    | 163  | 9     | 0                      | 0    | 139  | 0     |
| 1:30 PM    | 0  | 0    | 0    | 3     | 0          | 0    | 0    | 0     | 0                      | 0    | 183  | 15    | 0                      | 0    | 124  | 0     |
| 1:45 PM    | 0  | 0    | 0    | 8     | 0          | 0    | 0    | 0     | 0                      | 0    | 185  | 8     | 0                      | 0    | 130  | 0     |

| MID PEAK HOUR<br>1:00 PM<br>to<br>2:00 PM | Motel 6/North site access drive Northbound |      |      |       | Southbound  |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|---|--|------|------|-------|-------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|   | U-Turn                                     | Left | Thru | Right | U-Turn      | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|   | 0  | 0    | 0    | 24    | 0           | 0    | 0    | 0     | 0                      | 0    | 693  | 47    | 0                      | 0    | 529  | 0     |
| <i>PHF</i>                                | <b>0.55</b>                                |      |      |       | <b>0.00</b> |      |      |       | <b>0.93</b>            |      |      |       | <b>0.95</b>            |      |      |       |
| <i>HV %</i>                               | 0.0%                                       | 0.0% | 0.0% | 0.0%  | 0.0%        | 0.0% | 0.0% | 0.0%  | 0.0%                   | 0.0% | 0.6% | 0.0%  | 0.0%                   | 0.0% | 0.4% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 3  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: Motel 6/North site access drive  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F

# BOSTON TRAFFIC DATA

PO BOX 1723, Framingham, MA 01701  
 Office: 978-746-1259  
 DataRequest@BostonTrafficData.com  
 www.BostonTrafficData.com

## HEAVY VEHICLES

| Start Time | Motel 6/North site access drive Northbound |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      | Gosling Road Westbound |        |      |      |       |
|------------|--|------|------|-------|------------|------|------|-------|------------------------|------|------|------------------------|--------|------|------|-------|
|            | U-Turn                                     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right                  | U-Turn | Left | Thru | Right |
| 11:00 AM   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 2    | 0                      | 0      | 0    | 0    | 0     |
| 11:15 AM   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 1    | 0     |
| 11:30 AM   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 2    | 0     |
| 11:45 AM   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 3    | 0                      | 0      | 0    | 3    | 0     |
| 12:00 PM   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 1    | 0     |
| 12:15 PM   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 1    | 0                      | 0      | 0    | 0    | 0     |
| 12:30 PM   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 1    | 0                      | 0      | 0    | 0    | 0     |
| 12:45 PM   | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 1    | 0                      | 0      | 0    | 0    | 0     |
| 1:00 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 1    | 0                      | 0      | 0    | 1    | 0     |
| 1:15 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 2    | 0                      | 0      | 0    | 0    | 0     |
| 1:30 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 1    | 0                      | 0      | 0    | 1    | 0     |
| 1:45 PM    | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 0    | 0                      | 0      | 0    | 0    | 0     |

| MID PEAK HOUR<br>11:00 AM to 12:00 PM<br>PHF | Motel 6/North site access drive Northbound |      |      |       | Southbound |      |      |       | Gosling Road Eastbound |      |      | Gosling Road Westbound |        |      |      |       |
|--|--|------|------|-------|------------|------|------|-------|------------------------|------|------|------------------------|--------|------|------|-------|
|  | U-Turn                                     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn                 | Left | Thru | Right                  | U-Turn | Left | Thru | Right |
|  | 0  | 0    | 0    | 0     | 0          | 0    | 0    | 0     | 0                      | 0    | 5    | 0                      | 0      | 0    | 6    | 0     |
|  | 0.00                                       |      |      |       | 0.00       |      |      |       | 0.42                   |      |      | 0.50                   |        |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 3  
 Location: Portsmouth, NH  
 Street 1: Gosling Road  
 Street 2: Motel 6/North site access drive  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PEDESTRIANS & BICYCLES**

| Start Time | Motel 6/North site access drive Northbound |      |       |     | Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|------------|--|------|-------|-----|------------|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|            | Left                                       | Thru | Right | PED | Left       | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
| 11:00 AM   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 11:15 AM   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 11:30 AM   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 11:45 AM   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 2   |
| 12:00 PM   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:15 PM   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:30 PM   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:45 PM   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:00 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:15 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 2   |
| 1:30 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 1   |
| 1:45 PM    | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |

| MID PEAK HOUR<br>1:00 PM<br>to<br>2:00 PM | Motel 6/North site access drive Northbound |      |       |     | Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|---|--|------|-------|-----|------------|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|   | Left                                       | Thru | Right | PED | Left       | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
|   | 0  | 0    | 0     | 0   | 0          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 3   |

NOTE: Peak hour summaries here correspond to peak hours identified for passenger car and heavy vehicles combined.



Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 4  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Gosling Road  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 7:00 AM    | 0                          | 24   | 17   | 2     | 0                          | 1    | 52   | 9     | 0                      | 19   | 6    | 39    | 0                      | 3    | 1    | 2     |
| 7:15 AM    | 0                          | 39   | 39   | 2     | 0                          | 1    | 55   | 8     | 0                      | 26   | 8    | 51    | 0                      | 1    | 4    | 2     |
| 7:30 AM    | 0                          | 39   | 40   | 1     | 0                          | 2    | 49   | 6     | 0                      | 20   | 6    | 83    | 0                      | 2    | 4    | 2     |
| 7:45 AM    | 1                          | 49   | 43   | 3     | 1                          | 2    | 57   | 7     | 3                      | 25   | 6    | 101   | 0                      | 8    | 3    | 0     |
| 8:00 AM    | 0                          | 39   | 34   | 2     | 0                          | 2    | 54   | 8     | 0                      | 24   | 6    | 90    | 0                      | 4    | 5    | 0     |
| 8:15 AM    | 0                          | 32   | 33   | 7     | 1                          | 2    | 61   | 9     | 1                      | 18   | 6    | 91    | 0                      | 3    | 2    | 4     |
| 8:30 AM    | 0                          | 40   | 37   | 4     | 0                          | 1    | 73   | 6     | 3                      | 13   | 14   | 89    | 0                      | 8    | 1    | 1     |
| 8:45 AM    | 0                          | 33   | 49   | 7     | 0                          | 4    | 56   | 6     | 0                      | 15   | 4    | 60    | 0                      | 6    | 3    | 5     |

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 4:00 PM    | 2                          | 50   | 103  | 9     | 0                          | 9    | 103  | 29    | 2                      | 13   | 8    | 85    | 0                      | 11   | 16   | 8     |
| 4:15 PM    | 1                          | 65   | 83   | 6     | 1                          | 8    | 84   | 20    | 1                      | 17   | 10   | 90    | 0                      | 16   | 12   | 9     |
| 4:30 PM    | 1                          | 86   | 82   | 5     | 0                          | 6    | 89   | 29    | 0                      | 16   | 14   | 83    | 0                      | 12   | 14   | 15    |
| 4:45 PM    | 0                          | 69   | 101  | 6     | 0                          | 3    | 90   | 20    | 1                      | 17   | 7    | 103   | 0                      | 13   | 10   | 8     |
| 5:00 PM    | 1                          | 58   | 97   | 9     | 1                          | 3    | 92   | 30    | 0                      | 18   | 13   | 83    | 0                      | 10   | 12   | 8     |
| 5:15 PM    | 1                          | 56   | 98   | 7     | 0                          | 12   | 97   | 17    | 2                      | 19   | 13   | 102   | 0                      | 14   | 9    | 7     |
| 5:30 PM    | 1                          | 59   | 95   | 8     | 0                          | 5    | 78   | 22    | 1                      | 23   | 13   | 71    | 0                      | 15   | 6    | 11    |
| 5:45 PM    | 1                          | 56   | 78   | 12    | 1                          | 6    | 71   | 13    | 0                      | 8    | 18   | 68    | 0                      | 16   | 16   | 6     |

| AM PEAK HOUR<br>7:45 AM<br>to<br>8:45 AM | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |       |      |       | Gosling Road Eastbound |      |       |       | Gosling Road Westbound |      |      |       |
|--|----------------------------|------|------|-------|----------------------------|-------|------|-------|------------------------|------|-------|-------|------------------------|------|------|-------|
|  | U-Turn                     | Left | Thru | Right | U-Turn                     | Left  | Thru | Right | U-Turn                 | Left | Thru  | Right | U-Turn                 | Left | Thru | Right |
|  | 1                          | 160  | 147  | 16    | 2                          | 7     | 245  | 30    | 7                      | 80   | 32    | 371   | 0                      | 23   | 11   | 5     |
| <b>PHF</b>                               | 0.84                       |      |      |       | 0.89                       |       |      |       | 0.91                   |      |       |       | 0.89                   |      |      |       |
| <b>HV %</b>                              | 0.0%                       | 1.9% | 3.4% | 0.0%  | 0.0%                       | 14.3% | 2.0% | 20.0% | 0.0%                   | 7.5% | 12.5% | 1.9%  | 0.0%                   | 8.7% | 9.1% | 40.0% |

| PM PEAK HOUR<br>4:30 PM<br>to<br>5:30 PM | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |       |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|--|----------------------------|------|------|-------|----------------------------|-------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|  | U-Turn                     | Left | Thru | Right | U-Turn                     | Left  | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|  | 3                          | 269  | 378  | 27    | 1                          | 24    | 368  | 96    | 3                      | 70   | 47   | 371   | 0                      | 49   | 45   | 38    |
| <b>PHF</b>                               | 0.96                       |      |      |       | 0.97                       |       |      |       | 0.90                   |      |      |       | 0.80                   |      |      |       |
| <b>HV %</b>                              | 0.0%                       | 1.1% | 0.5% | 7.4%  | 0.0%                       | 12.5% | 0.3% | 4.2%  | 0.0%                   | 4.3% | 2.1% | 1.3%  | 0.0%                   | 0.0% | 0.0% | 7.9%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 4  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Gosling Road  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**HEAVY VEHICLES**

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 7:00 AM    | 0                          | 0    | 0    | 0     | 0                          | 0    | 3    | 0     | 0                      | 1    | 0    | 1     | 0                      | 0    | 0    | 0     |
| 7:15 AM    | 0                          | 3    | 1    | 1     | 0                          | 0    | 3    | 0     | 0                      | 5    | 1    | 2     | 0                      | 0    | 2    | 0     |
| 7:30 AM    | 0                          | 1    | 2    | 0     | 0                          | 0    | 2    | 0     | 0                      | 2    | 1    | 4     | 0                      | 0    | 1    | 0     |
| 7:45 AM    | 0                          | 1    | 0    | 0     | 0                          | 0    | 0    | 1     | 0                      | 2    | 0    | 1     | 0                      | 2    | 0    | 0     |
| 8:00 AM    | 0                          | 1    | 2    | 0     | 0                          | 0    | 0    | 3     | 0                      | 1    | 0    | 2     | 0                      | 0    | 0    | 0     |
| 8:15 AM    | 0                          | 0    | 3    | 0     | 0                          | 0    | 1    | 1     | 0                      | 2    | 1    | 2     | 0                      | 0    | 0    | 1     |
| 8:30 AM    | 0                          | 1    | 0    | 0     | 0                          | 1    | 4    | 1     | 0                      | 1    | 3    | 2     | 0                      | 0    | 1    | 1     |
| 8:45 AM    | 0                          | 1    | 0    | 0     | 0                          | 0    | 2    | 1     | 0                      | 0    | 1    | 1     | 0                      | 1    | 0    | 2     |

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 4:00 PM    | 0                          | 1    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                      | 0    | 0    | 1     | 0                      | 1    | 0    | 0     |
| 4:15 PM    | 0                          | 1    | 0    | 1     | 0                          | 0    | 0    | 0     | 0                      | 0    | 0    | 2     | 0                      | 0    | 0    | 3     |
| 4:30 PM    | 0                          | 1    | 0    | 1     | 0                          | 0    | 1    | 1     | 0                      | 0    | 1    | 3     | 0                      | 0    | 0    | 3     |
| 4:45 PM    | 0                          | 0    | 1    | 0     | 0                          | 0    | 0    | 1     | 0                      | 1    | 0    | 1     | 0                      | 0    | 0    | 0     |
| 5:00 PM    | 0                          | 1    | 1    | 0     | 0                          | 0    | 0    | 1     | 0                      | 1    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 5:15 PM    | 0                          | 1    | 0    | 1     | 0                          | 3    | 0    | 1     | 0                      | 1    | 0    | 1     | 0                      | 0    | 0    | 0     |
| 5:30 PM    | 0                          | 0    | 1    | 0     | 0                          | 0    | 0    | 0     | 0                      | 0    | 0    | 1     | 0                      | 0    | 0    | 4     |
| 5:45 PM    | 0                          | 1    | 1    | 0     | 0                          | 0    | 2    | 0     | 0                      | 1    | 0    | 0     | 0                      | 0    | 0    | 0     |

| AM PEAK HOUR<br>7:15 AM to 8:15 AM | Woodbury Avenue Northbound |          |          |          | Woodbury Avenue Southbound |          |          |          | Gosling Road Eastbound |           |          |          | Gosling Road Westbound |          |          |          |
|------------------------------------|----------------------------|----------|----------|----------|----------------------------|----------|----------|----------|------------------------|-----------|----------|----------|------------------------|----------|----------|----------|
|                                    | U-Turn                     | Left     | Thru     | Right    | U-Turn                     | Left     | Thru     | Right    | U-Turn                 | Left      | Thru     | Right    | U-Turn                 | Left     | Thru     | Right    |
| <b>PHF</b>                         | <b>0</b>                   | <b>6</b> | <b>5</b> | <b>1</b> | <b>0</b>                   | <b>0</b> | <b>5</b> | <b>4</b> | <b>0</b>               | <b>10</b> | <b>2</b> | <b>9</b> | <b>0</b>               | <b>2</b> | <b>3</b> | <b>0</b> |
|                                    | <b>0.60</b>                |          |          |          | <b>0.75</b>                |          |          |          | <b>0.66</b>            |           |          |          | <b>0.63</b>            |          |          |          |

| PM PEAK HOUR<br>4:30 PM to 5:30 PM | Woodbury Avenue Northbound |          |          |          | Woodbury Avenue Southbound |          |          |          | Gosling Road Eastbound |          |          |          | Gosling Road Westbound |          |          |          |
|------------------------------------|----------------------------|----------|----------|----------|----------------------------|----------|----------|----------|------------------------|----------|----------|----------|------------------------|----------|----------|----------|
|                                    | U-Turn                     | Left     | Thru     | Right    | U-Turn                     | Left     | Thru     | Right    | U-Turn                 | Left     | Thru     | Right    | U-Turn                 | Left     | Thru     | Right    |
| <b>PHF</b>                         | <b>0</b>                   | <b>3</b> | <b>2</b> | <b>2</b> | <b>0</b>                   | <b>3</b> | <b>1</b> | <b>4</b> | <b>0</b>               | <b>3</b> | <b>1</b> | <b>5</b> | <b>0</b>               | <b>0</b> | <b>0</b> | <b>3</b> |
|                                    | <b>0.88</b>                |          |          |          | <b>0.50</b>                |          |          |          | <b>0.56</b>            |          |          |          | <b>0.25</b>            |          |          |          |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 4  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Gosling Road  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PEDESTRIANS & BICYCLES**

| Start Time | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|------------|----------------------------|------|-------|-----|----------------------------|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|            | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
| 7:00 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 7:15 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 7:30 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 7:45 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 8:00 AM    | 0                          | 0    | 0     | 2   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 8:15 AM    | 0                          | 0    | 0     | 0   | 0                          | 1    | 0     | 0   | 0                      | 0    | 0     | 1   | 0                      | 0    | 0     | 0   |
| 8:30 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 1   | 0                      | 0    | 0     | 0   |
| 8:45 AM    | 0                          | 2    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |

| Start Time | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|------------|----------------------------|------|-------|-----|----------------------------|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|            | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
| 4:00 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 1   | 0                      | 0    | 0     | 2   | 0                      | 0    | 0     | 1   |
| 4:15 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 2   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 2   |
| 4:30 PM    | 0                          | 1    | 0     | 2   | 0                          | 0    | 0     | 0   | 1                      | 0    | 0     | 2   | 0                      | 0    | 0     | 0   |
| 4:45 PM    | 0                          | 0    | 0     | 1   | 0                          | 0    | 0     | 1   | 0                      | 0    | 0     | 0   | 0                      | 0    | 1     | 1   |
| 5:00 PM    | 0                          | 0    | 0     | 4   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 5:15 PM    | 0                          | 1    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 5:30 PM    | 0                          | 0    | 0     | 0   | 0                          | 2    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 5:45 PM    | 0                          | 0    | 0     | 1   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |

| AM PEAK HOUR <sup>1</sup><br>7:45 AM to 8:45 AM | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|---|----------------------------|------|-------|-----|----------------------------|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|   | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
|   | 0                          | 0    | 0     | 2   | 0                          | 1    | 0     | 0   | 0                      | 0    | 0     | 2   | 0                      | 0    | 0     | 0   |

| PM PEAK HOUR <sup>1</sup><br>4:30 PM to 5:30 PM | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|---|----------------------------|------|-------|-----|----------------------------|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|   | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
|   | 0                          | 2    | 0     | 7   | 0                          | 0    | 0     | 1   | 1                      | 0    | 0     | 2   | 0                      | 0    | 1     | 1   |

<sup>1</sup> NOTE: Peak hour summaries here correspond to peak hours identified for passenger cars and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 4  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Gosling Road  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 11:00 AM   | 1                          | 51   | 41   | 4     | 0                          | 5    | 41   | 9     | 1                      | 10   | 10   | 55    | 0                      | 7    | 4    | 7     |
| 11:15 AM   | 2                          | 33   | 51   | 2     | 0                          | 1    | 60   | 6     | 1                      | 5    | 6    | 55    | 0                      | 15   | 9    | 7     |
| 11:30 AM   | 3                          | 42   | 63   | 1     | 0                          | 7    | 61   | 12    | 2                      | 12   | 6    | 61    | 0                      | 10   | 4    | 3     |
| 11:45 AM   | 0                          | 38   | 54   | 2     | 0                          | 3    | 63   | 6     | 0                      | 16   | 7    | 76    | 0                      | 10   | 3    | 2     |
| 12:00 PM   | 1                          | 51   | 66   | 3     | 2                          | 6    | 67   | 10    | 0                      | 9    | 6    | 68    | 0                      | 9    | 9    | 5     |
| 12:15 PM   | 2                          | 61   | 59   | 3     | 0                          | 7    | 81   | 10    | 0                      | 15   | 9    | 63    | 0                      | 9    | 8    | 5     |
| 12:30 PM   | 1                          | 42   | 73   | 5     | 0                          | 7    | 74   | 13    | 2                      | 7    | 10   | 84    | 0                      | 14   | 8    | 4     |
| 12:45 PM   | 1                          | 49   | 80   | 3     | 1                          | 5    | 73   | 14    | 1                      | 5    | 9    | 70    | 0                      | 9    | 4    | 5     |
| 1:00 PM    | 2                          | 59   | 61   | 3     | 0                          | 4    | 85   | 13    | 0                      | 10   | 6    | 70    | 0                      | 15   | 11   | 1     |
| 1:15 PM    | 1                          | 43   | 79   | 3     | 0                          | 2    | 103  | 11    | 0                      | 8    | 7    | 71    | 0                      | 14   | 5    | 6     |
| 1:30 PM    | 1                          | 35   | 61   | 1     | 0                          | 8    | 95   | 21    | 0                      | 15   | 7    | 86    | 0                      | 14   | 6    | 2     |
| 1:45 PM    | 0                          | 53   | 59   | 3     | 0                          | 6    | 81   | 17    | 1                      | 9    | 13   | 59    | 0                      | 7    | 8    | 2     |

| MID PEAK HOUR<br>12:45 PM<br>to<br>1:45 PM | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|--|----------------------------|------|------|-------|----------------------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|  | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|  | 5                          | 186  | 281  | 10    | 1                          | 19   | 356  | 59    | 1                      | 38   | 29   | 297   | 0                      | 52   | 26   | 14    |
| <i>PHF</i>                                 | <b>0.91</b>                |      |      |       | <b>0.88</b>                |      |      |       | <b>0.84</b>            |      |      |       | <b>0.85</b>            |      |      |       |
| <i>HV %</i>                                | 0.0%                       | 1.1% | 1.4% | 0.0%  | 0.0%                       | 0.0% | 0.0% | 1.7%  | 0.0%                   | 0.0% | 3.4% | 1.3%  | 0.0%                   | 0.0% | 0.0% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 4  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Gosling Road  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F

# BOSTON TRAFFIC DATA

PO BOX 1723, Framingham, MA 01701  
 Office: 978-746-1259  
 DataRequest@BostonTrafficData.com  
 www.BostonTrafficData.com

## HEAVY VEHICLES

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
| 11:00 AM   | 0                          | 1    | 3    | 0     | 0                          | 1    | 1    | 0     | 0                      | 0    | 0    | 1     | 0                      | 0    | 0    | 0     |
| 11:15 AM   | 0                          | 2    | 1    | 0     | 0                          | 0    | 1    | 0     | 0                      | 1    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 11:30 AM   | 0                          | 0    | 0    | 0     | 0                          | 0    | 1    | 1     | 0                      | 0    | 0    | 1     | 0                      | 0    | 0    | 0     |
| 11:45 AM   | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                      | 1    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 12:00 PM   | 0                          | 1    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 12:15 PM   | 0                          | 0    | 0    | 0     | 0                          | 0    | 3    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 12:30 PM   | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                      | 0    | 0    | 1     | 0                      | 0    | 0    | 0     |
| 12:45 PM   | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 1:00 PM    | 0                          | 1    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 0    | 0     |
| 1:15 PM    | 0                          | 1    | 2    | 0     | 0                          | 0    | 0    | 0     | 0                      | 0    | 0    | 1     | 0                      | 0    | 0    | 0     |
| 1:30 PM    | 0                          | 0    | 2    | 0     | 0                          | 0    | 0    | 1     | 0                      | 0    | 1    | 3     | 0                      | 0    | 0    | 0     |
| 1:45 PM    | 0                          | 0    | 0    | 0     | 0                          | 0    | 1    | 0     | 0                      | 0    | 0    | 0     | 0                      | 0    | 0    | 0     |

| MID PEAK HOUR<br>11:00 AM<br>to<br>12:00 PM<br><i>PHF</i> | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Gosling Road Eastbound |      |      |       | Gosling Road Westbound |      |      |       |
|---|----------------------------|------|------|-------|----------------------------|------|------|-------|------------------------|------|------|-------|------------------------|------|------|-------|
|   | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                 | Left | Thru | Right | U-Turn                 | Left | Thru | Right |
|   | 0                          | 3    | 4    | 0     | 0                          | 1    | 3    | 1     | 0                      | 2    | 0    | 2     | 0                      | 0    | 0    | 0     |
|   | <b>0.44</b>                |      |      |       | <b>0.63</b>                |      |      |       | <b>1.00</b>            |      |      |       | <b>0.00</b>            |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 4  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Gosling Road  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PEDESTRIANS & BICYCLES**

| Start Time | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|------------|----------------------------|------|-------|-----|----------------------------|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|            | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
| 11:00 AM   | 0                          | 0    | 0     | 2   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 11:15 AM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 1   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 11:30 AM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 11:45 AM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:00 PM   | 0                          | 0    | 0     | 2   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 3   | 0                      | 0    | 0     | 0   |
| 12:15 PM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:30 PM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 12:45 PM   | 0                          | 0    | 0     | 1   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:00 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:15 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:30 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |
| 1:45 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |

| MID PEAK HOUR<br>12:45 PM<br>to<br>1:45 PM | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Gosling Road Eastbound |      |       |     | Gosling Road Westbound |      |       |     |
|--|----------------------------|------|-------|-----|----------------------------|------|-------|-----|------------------------|------|-------|-----|------------------------|------|-------|-----|
|  | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                   | Thru | Right | PED | Left                   | Thru | Right | PED |
|  | 0                          | 0    | 0     | 1   | 0                          | 0    | 0     | 0   | 0                      | 0    | 0     | 0   | 0                      | 0    | 0     | 0   |

NOTE: Peak hour summaries here correspond to peak hours identified for passenger car and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 5  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Durgin Lane & BJ Drive  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      |       | BJ Drive Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|-------|--------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right | U-Turn             | Left | Thru | Right |
| 7:00 AM    | 0                          | 1    | 42   | 11    | 0                          | 1    | 81   | 4     | 0                     | 2    | 0    | 2     | 0                  | 3    | 1    | 3     |
| 7:15 AM    | 0                          | 1    | 55   | 8     | 0                          | 3    | 95   | 3     | 0                     | 6    | 1    | 4     | 0                  | 1    | 0    | 6     |
| 7:30 AM    | 0                          | 0    | 60   | 7     | 0                          | 2    | 108  | 10    | 0                     | 5    | 0    | 4     | 0                  | 6    | 0    | 3     |
| 7:45 AM    | 0                          | 3    | 80   | 3     | 0                          | 6    | 149  | 8     | 0                     | 3    | 1    | 4     | 0                  | 4    | 0    | 4     |
| 8:00 AM    | 0                          | 3    | 56   | 11    | 0                          | 13   | 125  | 15    | 0                     | 5    | 1    | 8     | 0                  | 5    | 0    | 6     |
| 8:15 AM    | 0                          | 1    | 53   | 5     | 0                          | 12   | 145  | 5     | 0                     | 8    | 1    | 5     | 0                  | 13   | 0    | 7     |
| 8:30 AM    | 0                          | 1    | 64   | 13    | 0                          | 7    | 138  | 15    | 0                     | 4    | 0    | 6     | 0                  | 7    | 0    | 6     |
| 8:45 AM    | 0                          | 8    | 69   | 17    | 0                          | 9    | 104  | 16    | 0                     | 11   | 2    | 4     | 0                  | 7    | 4    | 5     |

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      |       | BJ Drive Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|-------|--------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right | U-Turn             | Left | Thru | Right |
| 4:00 PM    | 0                          | 9    | 123  | 24    | 0                          | 19   | 133  | 34    | 0                     | 26   | 2    | 13    | 0                  | 22   | 4    | 14    |
| 4:15 PM    | 0                          | 3    | 97   | 18    | 0                          | 16   | 151  | 27    | 0                     | 31   | 6    | 19    | 0                  | 25   | 6    | 18    |
| 4:30 PM    | 0                          | 5    | 132  | 16    | 0                          | 14   | 162  | 22    | 0                     | 28   | 7    | 7     | 0                  | 17   | 2    | 11    |
| 4:45 PM    | 0                          | 2    | 137  | 22    | 0                          | 16   | 150  | 33    | 0                     | 23   | 2    | 11    | 0                  | 30   | 4    | 21    |
| 5:00 PM    | 0                          | 11   | 144  | 26    | 0                          | 14   | 169  | 25    | 0                     | 20   | 2    | 8     | 0                  | 17   | 2    | 23    |
| 5:15 PM    | 0                          | 5    | 119  | 14    | 0                          | 18   | 167  | 34    | 0                     | 20   | 4    | 20    | 0                  | 20   | 4    | 18    |
| 5:30 PM    | 0                          | 3    | 125  | 13    | 0                          | 14   | 133  | 16    | 0                     | 22   | 3    | 13    | 0                  | 21   | 4    | 15    |
| 5:45 PM    | 0                          | 2    | 116  | 19    | 0                          | 17   | 131  | 21    | 0                     | 23   | 1    | 16    | 0                  | 12   | 3    | 10    |

| AM PEAK HOUR<br>7:45 AM<br>to<br>8:45 AM | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      |       | BJ Drive Westbound |      |      |       |
|--|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|-------|--------------------|------|------|-------|
|  | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right | U-Turn             | Left | Thru | Right |
|  | 0                          | 8    | 253  | 32    | 0                          | 38   | 557  | 43    | 0                     | 20   | 3    | 23    | 0                  | 29   | 0    | 23    |
| <b>PHF</b>                               | 0.85                       |      |      |       | 0.98                       |      |      |       | 0.82                  |      |      |       | 0.65               |      |      |       |
| <b>HV %</b>                              | 0.0%                       | 0.0% | 2.8% | 9.4%  | 0.0%                       | 2.6% | 2.2% | 0.0%  | 0.0%                  | 0.0% | 0.0% | 8.7%  | 0.0%               | 3.4% | 0.0% | 4.3%  |

| PM PEAK HOUR<br>4:30 PM<br>to<br>5:30 PM | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      |       | BJ Drive Westbound |      |      |       |
|--|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|-------|--------------------|------|------|-------|
|  | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right | U-Turn             | Left | Thru | Right |
|  | 0                          | 23   | 532  | 78    | 0                          | 62   | 648  | 114   | 0                     | 91   | 15   | 46    | 0                  | 84   | 12   | 73    |
| <b>PHF</b>                               | 0.87                       |      |      |       | 0.94                       |      |      |       | 0.86                  |      |      |       | 0.77               |      |      |       |
| <b>HV %</b>                              | 0.0%                       | 0.0% | 1.5% | 0.0%  | 0.0%                       | 1.6% | 0.9% | 0.0%  | 0.0%                  | 0.0% | 0.0% | 0.0%  | 0.0%               | 1.2% | 0.0% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 5  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Durgin Lane & BJ Drive  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**HEAVY VEHICLES**

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      |       | BJ Drive Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|-------|--------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right | U-Turn             | Left | Thru | Right |
| 7:00 AM    | 0                          | 0    | 1    | 0     | 0                          | 0    | 2    | 1     | 0                     | 0    | 0    | 0     | 0                  | 0    | 0    | 0     |
| 7:15 AM    | 0                          | 0    | 3    | 0     | 0                          | 0    | 4    | 0     | 0                     | 1    | 0    | 1     | 0                  | 0    | 0    | 0     |
| 7:30 AM    | 0                          | 0    | 1    | 0     | 0                          | 0    | 6    | 0     | 0                     | 1    | 0    | 0     | 0                  | 0    | 0    | 0     |
| 7:45 AM    | 0                          | 0    | 2    | 0     | 0                          | 1    | 3    | 0     | 0                     | 0    | 0    | 0     | 0                  | 0    | 0    | 0     |
| 8:00 AM    | 0                          | 0    | 3    | 2     | 0                          | 0    | 3    | 0     | 0                     | 0    | 0    | 0     | 0                  | 1    | 0    | 0     |
| 8:15 AM    | 0                          | 0    | 2    | 0     | 0                          | 0    | 1    | 0     | 0                     | 0    | 0    | 1     | 0                  | 0    | 0    | 1     |
| 8:30 AM    | 0                          | 0    | 0    | 1     | 0                          | 0    | 5    | 0     | 0                     | 0    | 0    | 1     | 0                  | 0    | 0    | 0     |
| 8:45 AM    | 0                          | 1    | 0    | 0     | 0                          | 0    | 6    | 0     | 0                     | 0    | 0    | 0     | 0                  | 0    | 0    | 1     |

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      |       | BJ Drive Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|-------|--------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right | U-Turn             | Left | Thru | Right |
| 4:00 PM    | 0                          | 0    | 1    | 0     | 0                          | 0    | 1    | 0     | 0                     | 0    | 0    | 0     | 0                  | 0    | 0    | 0     |
| 4:15 PM    | 0                          | 0    | 2    | 0     | 0                          | 0    | 1    | 1     | 0                     | 0    | 0    | 0     | 0                  | 1    | 0    | 0     |
| 4:30 PM    | 0                          | 0    | 2    | 0     | 0                          | 1    | 3    | 0     | 0                     | 0    | 0    | 0     | 0                  | 0    | 0    | 0     |
| 4:45 PM    | 0                          | 0    | 2    | 0     | 0                          | 0    | 2    | 0     | 0                     | 0    | 0    | 0     | 0                  | 1    | 0    | 0     |
| 5:00 PM    | 0                          | 0    | 2    | 0     | 0                          | 0    | 1    | 0     | 0                     | 0    | 0    | 0     | 0                  | 0    | 0    | 0     |
| 5:15 PM    | 0                          | 0    | 2    | 0     | 0                          | 0    | 0    | 0     | 0                     | 0    | 0    | 0     | 0                  | 0    | 0    | 0     |
| 5:30 PM    | 0                          | 0    | 1    | 0     | 0                          | 0    | 1    | 0     | 0                     | 0    | 0    | 0     | 0                  | 0    | 0    | 0     |
| 5:45 PM    | 0                          | 0    | 2    | 0     | 0                          | 0    | 2    | 0     | 0                     | 0    | 0    | 0     | 0                  | 0    | 0    | 0     |

| AM PEAK HOUR<br>7:15 AM to 8:15 AM | Woodbury Avenue Northbound |          |          |          | Woodbury Avenue Southbound |          |           |          | Durgin Lane Eastbound |          |          |          | BJ Drive Westbound |          |          |          |
|------------------------------------|----------------------------|----------|----------|----------|----------------------------|----------|-----------|----------|-----------------------|----------|----------|----------|--------------------|----------|----------|----------|
|                                    | U-Turn                     | Left     | Thru     | Right    | U-Turn                     | Left     | Thru      | Right    | U-Turn                | Left     | Thru     | Right    | U-Turn             | Left     | Thru     | Right    |
| <b>PHF</b>                         | <b>0</b>                   | <b>0</b> | <b>9</b> | <b>2</b> | <b>0</b>                   | <b>1</b> | <b>16</b> | <b>0</b> | <b>0</b>              | <b>2</b> | <b>0</b> | <b>1</b> | <b>0</b>           | <b>1</b> | <b>0</b> | <b>0</b> |
|                                    | <b>0.55</b>                |          |          |          | <b>0.71</b>                |          |           |          | <b>0.38</b>           |          |          |          | <b>0.25</b>        |          |          |          |

| PM PEAK HOUR<br>4:15 PM to 5:15 PM | Woodbury Avenue Northbound |          |          |          | Woodbury Avenue Southbound |          |          |          | Durgin Lane Eastbound |          |          |          | BJ Drive Westbound |          |          |          |
|------------------------------------|----------------------------|----------|----------|----------|----------------------------|----------|----------|----------|-----------------------|----------|----------|----------|--------------------|----------|----------|----------|
|                                    | U-Turn                     | Left     | Thru     | Right    | U-Turn                     | Left     | Thru     | Right    | U-Turn                | Left     | Thru     | Right    | U-Turn             | Left     | Thru     | Right    |
| <b>PHF</b>                         | <b>0</b>                   | <b>0</b> | <b>8</b> | <b>0</b> | <b>0</b>                   | <b>1</b> | <b>7</b> | <b>1</b> | <b>0</b>              | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b>           | <b>2</b> | <b>0</b> | <b>0</b> |
|                                    | <b>1.00</b>                |          |          |          | <b>0.56</b>                |          |          |          | <b>0.00</b>           |          |          |          | <b>0.50</b>        |          |          |          |



Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 5  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Durgin Lane & BJ Drive  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PEDESTRIANS & BICYCLES**

| Start Time | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Durgin Lane Eastbound |      |       |     | BJ Drive Westbound |      |       |     |
|------------|----------------------------|------|-------|-----|----------------------------|------|-------|-----|-----------------------|------|-------|-----|--------------------|------|-------|-----|
|            | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                  | Thru | Right | PED | Left               | Thru | Right | PED |
| 7:00 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 7:15 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 7:30 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 7:45 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 8:00 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 8:15 AM    | 0                          | 0    | 0     | 1   | 0                          | 0    | 1     | 0   | 0                     | 0    | 0     | 2   | 0                  | 0    | 0     | 0   |
| 8:30 AM    | 0                          | 1    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 8:45 AM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |

| Start Time | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Durgin Lane Eastbound |      |       |     | BJ Drive Westbound |      |       |     |
|------------|----------------------------|------|-------|-----|----------------------------|------|-------|-----|-----------------------|------|-------|-----|--------------------|------|-------|-----|
|            | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                  | Thru | Right | PED | Left               | Thru | Right | PED |
| 4:00 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 4:15 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 4:30 PM    | 0                          | 1    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 4:45 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 5:00 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 3   | 0                  | 0    | 0     | 0   |
| 5:15 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 1   | 0                  | 0    | 0     | 0   |
| 5:30 PM    | 0                          | 0    | 0     | 0   | 0                          | 5    | 0     | 0   | 0                     | 0    | 0     | 2   | 0                  | 0    | 0     | 0   |
| 5:45 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |

| AM PEAK HOUR <sup>1</sup><br>7:45 AM to 8:45 AM | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Durgin Lane Eastbound |      |       |     | BJ Drive Westbound |      |       |     |
|---|----------------------------|------|-------|-----|----------------------------|------|-------|-----|-----------------------|------|-------|-----|--------------------|------|-------|-----|
|   | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                  | Thru | Right | PED | Left               | Thru | Right | PED |
|   | 0                          | 1    | 0     | 1   | 0                          | 0    | 1     | 0   | 0                     | 0    | 0     | 2   | 0                  | 0    | 0     | 0   |

| PM PEAK HOUR <sup>1</sup><br>4:30 PM to 5:30 PM | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Durgin Lane Eastbound |      |       |     | BJ Drive Westbound |      |       |     |
|---|----------------------------|------|-------|-----|----------------------------|------|-------|-----|-----------------------|------|-------|-----|--------------------|------|-------|-----|
|   | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                  | Thru | Right | PED | Left               | Thru | Right | PED |
|   | 0                          | 1    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 4   | 0                  | 0    | 0     | 0   |

<sup>1</sup> NOTE: Peak hour summaries here correspond to peak hours identified for passenger cars and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 5  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Durgin Lane & BJ Drive  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      |       | BJ Drive Westbound |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|-------|--------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right | U-Turn             | Left | Thru | Right |
| 11:00 AM   | 0                          | 3    | 85   | 12    | 0                          | 9    | 76   | 17    | 0                     | 11   | 1    | 18    | 0                  | 18   | 2    | 14    |
| 11:15 AM   | 0                          | 6    | 65   | 15    | 0                          | 11   | 116  | 19    | 0                     | 13   | 5    | 11    | 0                  | 9    | 3    | 7     |
| 11:30 AM   | 0                          | 4    | 90   | 25    | 1                          | 7    | 91   | 24    | 0                     | 15   | 3    | 13    | 0                  | 18   | 2    | 14    |
| 11:45 AM   | 0                          | 2    | 84   | 13    | 0                          | 10   | 119  | 40    | 0                     | 16   | 3    | 10    | 0                  | 23   | 1    | 5     |
| 12:00 PM   | 0                          | 4    | 96   | 21    | 0                          | 16   | 108  | 19    | 0                     | 16   | 4    | 17    | 0                  | 11   | 3    | 11    |
| 12:15 PM   | 0                          | 6    | 104  | 16    | 0                          | 10   | 134  | 23    | 0                     | 23   | 4    | 11    | 0                  | 23   | 1    | 7     |
| 12:30 PM   | 0                          | 4    | 89   | 20    | 0                          | 17   | 130  | 24    | 0                     | 23   | 4    | 13    | 0                  | 21   | 2    | 15    |
| 12:45 PM   | 0                          | 6    | 110  | 17    | 0                          | 15   | 113  | 34    | 0                     | 18   | 0    | 18    | 0                  | 22   | 4    | 11    |
| 1:00 PM    | 0                          | 4    | 89   | 18    | 0                          | 10   | 138  | 21    | 0                     | 19   | 5    | 19    | 0                  | 20   | 1    | 15    |
| 1:15 PM    | 1                          | 6    | 89   | 23    | 0                          | 12   | 149  | 25    | 0                     | 12   | 4    | 10    | 0                  | 24   | 3    | 15    |
| 1:30 PM    | 0                          | 8    | 74   | 11    | 0                          | 16   | 143  | 31    | 0                     | 28   | 4    | 16    | 0                  | 18   | 2    | 9     |
| 1:45 PM    | 0                          | 6    | 91   | 22    | 0                          | 17   | 110  | 24    | 0                     | 14   | 1    | 18    | 0                  | 18   | 2    | 9     |

| MID PEAK HOUR<br>12:30 PM<br>to<br>1:30 PM | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      |       | BJ Drive Westbound |      |      |       |
|--|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|-------|--------------------|------|------|-------|
|  | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right | U-Turn             | Left | Thru | Right |
|  | 1                          | 20   | 377  | 78    | 0                          | 54   | 530  | 104   | 0                     | 72   | 13   | 60    | 0                  | 87   | 10   | 56    |
| <i>PHF</i>                                 | 0.89                       |      |      |       | 0.92                       |      |      |       | 0.84                  |      |      |       | 0.91               |      |      |       |
| <i>HV %</i>                                | 0.0%                       | 0.0% | 0.8% | 1.3%  | 0.0%                       | 0.0% | 0.6% | 0.0%  | 0.0%                  | 0.0% | 0.0% | 0.0%  | 0.0%               | 0.0% | 0.0% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 5  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Durgin Lane & BJ Drive  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F

# BOSTON TRAFFIC DATA

PO BOX 1723, Framingham, MA 01701  
 Office: 978-746-1259  
 DataRequest@BostonTrafficData.com  
 www.BostonTrafficData.com

## HEAVY VEHICLES

| Start Time | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      | BJ Drive Westbound |        |      |      |       |
|------------|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|--------------------|--------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right              | U-Turn | Left | Thru | Right |
| 11:00 AM   | 0                          | 0    | 1    | 0     | 0                          | 0    | 0    | 0     | 0                     | 1    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 11:15 AM   | 0                          | 0    | 2    | 0     | 0                          | 0    | 1    | 0     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 11:30 AM   | 0                          | 0    | 0    | 0     | 0                          | 0    | 2    | 0     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 11:45 AM   | 0                          | 0    | 0    | 0     | 0                          | 0    | 0    | 0     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 12:00 PM   | 0                          | 1    | 2    | 0     | 0                          | 0    | 0    | 0     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 12:15 PM   | 0                          | 1    | 0    | 0     | 0                          | 0    | 2    | 1     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 12:30 PM   | 0                          | 0    | 0    | 0     | 0                          | 0    | 1    | 0     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 12:45 PM   | 0                          | 0    | 0    | 0     | 0                          | 0    | 1    | 0     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 1:00 PM    | 0                          | 0    | 1    | 0     | 0                          | 0    | 0    | 0     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 1:15 PM    | 0                          | 0    | 2    | 1     | 0                          | 0    | 1    | 0     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 1:30 PM    | 0                          | 0    | 1    | 0     | 0                          | 0    | 3    | 0     | 0                     | 1    | 0    | 0                  | 0      | 0    | 0    | 0     |
| 1:45 PM    | 0                          | 0    | 0    | 0     | 0                          | 0    | 1    | 0     | 0                     | 0    | 0    | 0                  | 0      | 0    | 0    | 0     |

| MID PEAK HOUR<br>12:45 PM<br>to<br>1:45 PM<br><i>PHF</i> | Woodbury Avenue Northbound |      |      |       | Woodbury Avenue Southbound |      |      |       | Durgin Lane Eastbound |      |      | BJ Drive Westbound |        |      |      |       |
|--|----------------------------|------|------|-------|----------------------------|------|------|-------|-----------------------|------|------|--------------------|--------|------|------|-------|
|  | U-Turn                     | Left | Thru | Right | U-Turn                     | Left | Thru | Right | U-Turn                | Left | Thru | Right              | U-Turn | Left | Thru | Right |
|  | 0                          | 0    | 4    | 1     | 0                          | 0    | 5    | 0     | 0                     | 1    | 0    | 0                  | 0      | 0    | 0    | 0     |
|  | 0.42                       |      |      |       | 0.42                       |      |      |       | 0.25                  |      |      | 0.00               |        |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 5  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Durgin Lane & BJ Drive  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PEDESTRIANS & BICYCLES**

| Start Time | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Durgin Lane Eastbound |      |       |     | BJ Drive Westbound |      |       |     |
|------------|----------------------------|------|-------|-----|----------------------------|------|-------|-----|-----------------------|------|-------|-----|--------------------|------|-------|-----|
|            | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                  | Thru | Right | PED | Left               | Thru | Right | PED |
| 11:00 AM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 1   | 0                  | 0    | 0     | 1   |
| 11:15 AM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 11:30 AM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 11:45 AM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 12:00 PM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 12:15 PM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 12:30 PM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 12:45 PM   | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 1:00 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 1:15 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 1:30 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |
| 1:45 PM    | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |

| MID PEAK HOUR<br>12:30 PM<br>to<br>1:30 PM | Woodbury Avenue Northbound |      |       |     | Woodbury Avenue Southbound |      |       |     | Durgin Lane Eastbound |      |       |     | BJ Drive Westbound |      |       |     |
|--|----------------------------|------|-------|-----|----------------------------|------|-------|-----|-----------------------|------|-------|-----|--------------------|------|-------|-----|
|  | Left                       | Thru | Right | PED | Left                       | Thru | Right | PED | Left                  | Thru | Right | PED | Left               | Thru | Right | PED |
|  | 0                          | 0    | 0     | 0   | 0                          | 0    | 0     | 0   | 0                     | 0    | 0     | 0   | 0                  | 0    | 0     | 0   |

NOTE: Peak hour summaries here correspond to peak hours identified for passenger car and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 6  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Market Street  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      |       | Market Street Westbound |      |      |       |
|------------|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------|-------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right | U-Turn                  | Left | Thru | Right |
| 7:00 AM    | 0                          | 10   | 10   | 3     | 0                              | 7    | 1    | 1     | 0                       | 0    | 40   | 15    | 0                       | 9    | 35   | 11    |
| 7:15 AM    | 0                          | 8    | 4    | 13    | 0                              | 4    | 10   | 2     | 0                       | 0    | 51   | 23    | 0                       | 5    | 52   | 9     |
| 7:30 AM    | 0                          | 11   | 4    | 7     | 0                              | 10   | 6    | 1     | 0                       | 0    | 44   | 31    | 0                       | 14   | 61   | 20    |
| 7:45 AM    | 0                          | 14   | 13   | 8     | 0                              | 8    | 5    | 1     | 1                       | 0    | 46   | 41    | 0                       | 15   | 67   | 8     |
| 8:00 AM    | 0                          | 14   | 4    | 12    | 0                              | 8    | 6    | 1     | 0                       | 0    | 53   | 49    | 0                       | 22   | 60   | 20    |
| 8:15 AM    | 0                          | 16   | 10   | 8     | 0                              | 12   | 9    | 0     | 0                       | 1    | 60   | 35    | 0                       | 11   | 50   | 21    |
| 8:30 AM    | 0                          | 30   | 6    | 12    | 0                              | 6    | 7    | 1     | 1                       | 1    | 60   | 41    | 0                       | 8    | 59   | 18    |
| 8:45 AM    | 0                          | 14   | 6    | 8     | 0                              | 18   | 12   | 1     | 1                       | 1    | 56   | 46    | 1                       | 25   | 90   | 18    |

| Start Time | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      |       | Market Street Westbound |      |      |       |
|------------|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------|-------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right | U-Turn                  | Left | Thru | Right |
| 4:00 PM    | 0                          | 43   | 14   | 6     | 0                              | 34   | 12   | 4     | 0                       | 1    | 114  | 78    | 0                       | 15   | 78   | 29    |
| 4:15 PM    | 0                          | 39   | 13   | 10    | 0                              | 32   | 20   | 7     | 0                       | 2    | 100  | 76    | 0                       | 20   | 62   | 33    |
| 4:30 PM    | 0                          | 33   | 6    | 15    | 0                              | 38   | 15   | 3     | 1                       | 4    | 123  | 64    | 0                       | 20   | 82   | 34    |
| 4:45 PM    | 0                          | 45   | 13   | 22    | 0                              | 44   | 11   | 3     | 0                       | 3    | 136  | 84    | 0                       | 22   | 105  | 29    |
| 5:00 PM    | 0                          | 47   | 20   | 16    | 0                              | 39   | 24   | 4     | 0                       | 5    | 104  | 66    | 0                       | 17   | 77   | 26    |
| 5:15 PM    | 0                          | 40   | 17   | 26    | 0                              | 37   | 24   | 3     | 0                       | 1    | 139  | 71    | 0                       | 18   | 95   | 26    |
| 5:30 PM    | 0                          | 41   | 15   | 11    | 0                              | 40   | 20   | 5     | 0                       | 1    | 109  | 62    | 0                       | 15   | 79   | 22    |
| 5:45 PM    | 0                          | 31   | 12   | 16    | 0                              | 22   | 14   | 4     | 0                       | 0    | 110  | 71    | 0                       | 23   | 77   | 20    |

| AM PEAK HOUR<br>8:00 AM to 9:00 AM | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      |       | Market Street Westbound |      |      |       |
|------------------------------------|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------|-------------------------|------|------|-------|
|                                    | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right | U-Turn                  | Left | Thru | Right |
|                                    | 0                          | 74   | 26   | 40    | 0                              | 44   | 34   | 3     | 2                       | 3    | 229  | 171   | 1                       | 66   | 259  | 77    |
| <b>PHF</b>                         | 0.73                       |      |      |       | 0.65                           |      |      |       | 0.97                    |      |      |       | 0.75                    |      |      |       |
| <b>HV %</b>                        | 0.0%                       | 1.4% | 0.0% | 0.0%  | 0.0%                           | 4.5% | 0.0% | 33.3% | 0.0%                    | 0.0% | 4.8% | 1.2%  | 0.0%                    | 0.0% | 2.7% | 2.6%  |

| PM PEAK HOUR<br>4:30 PM to 5:30 PM | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      |       | Market Street Westbound |      |      |       |
|------------------------------------|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------|-------------------------|------|------|-------|
|                                    | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right | U-Turn                  | Left | Thru | Right |
|                                    | 0                          | 165  | 56   | 79    | 0                              | 158  | 74   | 13    | 1                       | 13   | 502  | 285   | 0                       | 77   | 359  | 115   |
| <b>PHF</b>                         | 0.90                       |      |      |       | 0.91                           |      |      |       | 0.90                    |      |      |       | 0.88                    |      |      |       |
| <b>HV %</b>                        | 0.0%                       | 0.0% | 0.0% | 1.3%  | 0.0%                           | 1.3% | 0.0% | 0.0%  | 0.0%                    | 0.0% | 0.8% | 0.4%  | 0.0%                    | 0.0% | 0.8% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 6  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Market Street  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**HEAVY VEHICLES**

| Start Time | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      |       | Market Street Westbound |      |      |       |
|------------|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------|-------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right | U-Turn                  | Left | Thru | Right |
| 7:00 AM    | 0                          | 0    | 0    | 0     | 0                              | 1    | 0    | 0     | 0                       | 0    | 1    | 0     | 0                       | 0    | 0    | 0     |
| 7:15 AM    | 0                          | 1    | 0    | 2     | 0                              | 0    | 0    | 0     | 0                       | 0    | 3    | 2     | 0                       | 1    | 1    | 0     |
| 7:30 AM    | 0                          | 0    | 0    | 0     | 0                              | 1    | 0    | 0     | 0                       | 0    | 3    | 1     | 0                       | 1    | 1    | 0     |
| 7:45 AM    | 0                          | 0    | 0    | 0     | 0                              | 1    | 0    | 0     | 0                       | 0    | 3    | 0     | 0                       | 0    | 1    | 0     |
| 8:00 AM    | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 1     | 0                       | 0    | 2    | 1     | 0                       | 0    | 2    | 1     |
| 8:15 AM    | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 3    | 1     | 0                       | 0    | 3    | 0     |
| 8:30 AM    | 0                          | 1    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 3    | 0     | 0                       | 0    | 1    | 0     |
| 8:45 AM    | 0                          | 0    | 0    | 0     | 0                              | 2    | 0    | 0     | 0                       | 0    | 3    | 0     | 0                       | 0    | 1    | 1     |

| Start Time | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      |       | Market Street Westbound |      |      |       |
|------------|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------|-------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right | U-Turn                  | Left | Thru | Right |
| 4:00 PM    | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 1    | 0     | 0                       | 0    | 1    | 0     |
| 4:15 PM    | 0                          | 0    | 0    | 1     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 2     | 0                       | 0    | 0    | 0     |
| 4:30 PM    | 0                          | 0    | 0    | 0     | 0                              | 1    | 0    | 0     | 0                       | 0    | 1    | 1     | 0                       | 0    | 0    | 0     |
| 4:45 PM    | 0                          | 0    | 0    | 0     | 0                              | 1    | 0    | 0     | 0                       | 0    | 2    | 0     | 0                       | 0    | 1    | 0     |
| 5:00 PM    | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 1    | 0     | 0                       | 0    | 1    | 0     |
| 5:15 PM    | 0                          | 0    | 0    | 1     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 0     | 0                       | 0    | 1    | 0     |
| 5:30 PM    | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 0     | 0                       | 0    | 2    | 0     |
| 5:45 PM    | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 0     | 0                       | 0    | 0    | 0     |

| AM PEAK HOUR<br>7:15 AM to 8:15 AM | Woodbury Avenue Northbound |          |          |          | Market Basket Drive Southbound |          |          |          | Market Street Eastbound |          |           |          | Market Street Westbound |          |          |          |
|------------------------------------|----------------------------|----------|----------|----------|--------------------------------|----------|----------|----------|-------------------------|----------|-----------|----------|-------------------------|----------|----------|----------|
|                                    | U-Turn                     | Left     | Thru     | Right    | U-Turn                         | Left     | Thru     | Right    | U-Turn                  | Left     | Thru      | Right    | U-Turn                  | Left     | Thru     | Right    |
| <b>PHF</b>                         | <b>0</b>                   | <b>1</b> | <b>0</b> | <b>2</b> | <b>0</b>                       | <b>2</b> | <b>0</b> | <b>1</b> | <b>0</b>                | <b>0</b> | <b>11</b> | <b>4</b> | <b>0</b>                | <b>2</b> | <b>5</b> | <b>1</b> |
|                                    | <b>0.25</b>                |          |          |          | <b>0.75</b>                    |          |          |          | <b>0.75</b>             |          |           |          | <b>0.67</b>             |          |          |          |

| PM PEAK HOUR<br>4:00 PM to 5:00 PM | Woodbury Avenue Northbound |          |          |          | Market Basket Drive Southbound |          |          |          | Market Street Eastbound |          |          |          | Market Street Westbound |          |          |          |
|------------------------------------|----------------------------|----------|----------|----------|--------------------------------|----------|----------|----------|-------------------------|----------|----------|----------|-------------------------|----------|----------|----------|
|                                    | U-Turn                     | Left     | Thru     | Right    | U-Turn                         | Left     | Thru     | Right    | U-Turn                  | Left     | Thru     | Right    | U-Turn                  | Left     | Thru     | Right    |
| <b>PHF</b>                         | <b>0</b>                   | <b>0</b> | <b>0</b> | <b>1</b> | <b>0</b>                       | <b>2</b> | <b>0</b> | <b>0</b> | <b>0</b>                | <b>0</b> | <b>4</b> | <b>3</b> | <b>0</b>                | <b>0</b> | <b>2</b> | <b>0</b> |
|                                    | <b>0.25</b>                |          |          |          | <b>0.50</b>                    |          |          |          | <b>0.88</b>             |          |          |          | <b>0.50</b>             |          |          |          |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 6  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Market Street  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PEDESTRIANS & BICYCLES**

| Start Time | Woodbury Avenue Northbound |      |       |     | Market Basket Drive Southbound |      |       |     | Market Street Eastbound |      |       |     | Market Street Westbound |      |       |     |
|------------|----------------------------|------|-------|-----|--------------------------------|------|-------|-----|-------------------------|------|-------|-----|-------------------------|------|-------|-----|
|            | Left                       | Thru | Right | PED | Left                           | Thru | Right | PED | Left                    | Thru | Right | PED | Left                    | Thru | Right | PED |
| 7:00 AM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 7:15 AM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 1   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 1   |
| 7:30 AM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 7:45 AM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 8:00 AM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 8:15 AM    | 0                          | 1    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 8:30 AM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 1    | 0     | 0   |
| 8:45 AM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |

| Start Time | Woodbury Avenue Northbound |      |       |     | Market Basket Drive Southbound |      |       |     | Market Street Eastbound |      |       |     | Market Street Westbound |      |       |     |
|------------|----------------------------|------|-------|-----|--------------------------------|------|-------|-----|-------------------------|------|-------|-----|-------------------------|------|-------|-----|
|            | Left                       | Thru | Right | PED | Left                           | Thru | Right | PED | Left                    | Thru | Right | PED | Left                    | Thru | Right | PED |
| 4:00 PM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 1   | 0                       | 0    | 0     | 0   |
| 4:15 PM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 4:30 PM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 4:45 PM    | 0                          | 0    | 0     | 0   | 0                              | 1    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 5:00 PM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 5:15 PM    | 0                          | 0    | 0     | 2   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 5:30 PM    | 0                          | 0    | 0     | 2   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 5:45 PM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 1   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |

| AM PEAK HOUR <sup>1</sup><br>8:00 AM to 9:00 AM | Woodbury Avenue Northbound |      |       |     | Market Basket Drive Southbound |      |       |     | Market Street Eastbound |      |       |     | Market Street Westbound |      |       |     |
|---|----------------------------|------|-------|-----|--------------------------------|------|-------|-----|-------------------------|------|-------|-----|-------------------------|------|-------|-----|
|   | Left                       | Thru | Right | PED | Left                           | Thru | Right | PED | Left                    | Thru | Right | PED | Left                    | Thru | Right | PED |
|   | 0                          | 1    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 1    | 0     | 0   |

| PM PEAK HOUR <sup>1</sup><br>4:30 PM to 5:30 PM | Woodbury Avenue Northbound |      |       |     | Market Basket Drive Southbound |      |       |     | Market Street Eastbound |      |       |     | Market Street Westbound |      |       |     |
|---|----------------------------|------|-------|-----|--------------------------------|------|-------|-----|-------------------------|------|-------|-----|-------------------------|------|-------|-----|
|   | Left                       | Thru | Right | PED | Left                           | Thru | Right | PED | Left                    | Thru | Right | PED | Left                    | Thru | Right | PED |
|   | 0                          | 0    | 0     | 2   | 0                              | 1    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |

<sup>1</sup> NOTE: Peak hour summaries here correspond to peak hours identified for passenger cars and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 6  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Market Street  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      |       | Market Street Westbound |      |      |       |
|------------|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------|-------------------------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right | U-Turn                  | Left | Thru | Right |
| 11:00 AM   | 0                          | 30   | 15   | 7     | 0                              | 33   | 7    | 3     | 0                       | 3    | 60   | 41    | 0                       | 11   | 71   | 25    |
| 11:15 AM   | 0                          | 51   | 8    | 17    | 0                              | 24   | 16   | 5     | 0                       | 4    | 74   | 52    | 0                       | 6    | 54   | 25    |
| 11:30 AM   | 0                          | 36   | 15   | 8     | 0                              | 24   | 12   | 3     | 0                       | 5    | 80   | 59    | 0                       | 17   | 85   | 30    |
| 11:45 AM   | 0                          | 35   | 10   | 5     | 0                              | 23   | 12   | 2     | 1                       | 1    | 88   | 63    | 0                       | 6    | 69   | 20    |
| 12:00 PM   | 0                          | 37   | 13   | 11    | 0                              | 23   | 16   | 3     | 0                       | 3    | 69   | 69    | 0                       | 9    | 74   | 24    |
| 12:15 PM   | 0                          | 42   | 9    | 7     | 0                              | 25   | 10   | 6     | 0                       | 0    | 101  | 64    | 0                       | 13   | 69   | 17    |
| 12:30 PM   | 0                          | 41   | 13   | 9     | 0                              | 19   | 9    | 3     | 0                       | 4    | 96   | 58    | 0                       | 11   | 86   | 22    |
| 12:45 PM   | 0                          | 38   | 14   | 17    | 0                              | 34   | 13   | 3     | 0                       | 0    | 79   | 71    | 0                       | 11   | 68   | 26    |
| 1:00 PM    | 0                          | 40   | 12   | 18    | 0                              | 23   | 14   | 5     | 0                       | 3    | 97   | 75    | 0                       | 14   | 74   | 32    |
| 1:15 PM    | 0                          | 36   | 11   | 6     | 0                              | 29   | 16   | 1     | 0                       | 3    | 90   | 94    | 0                       | 8    | 88   | 27    |
| 1:30 PM    | 0                          | 30   | 12   | 7     | 0                              | 45   | 16   | 3     | 0                       | 3    | 103  | 82    | 0                       | 15   | 63   | 25    |
| 1:45 PM    | 0                          | 23   | 13   | 7     | 0                              | 31   | 15   | 2     | 0                       | 5    | 106  | 80    | 0                       | 9    | 69   | 31    |

| MID PEAK HOUR<br>1:00 PM<br>to<br>2:00 PM | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      |       | Market Street Westbound |      |      |       |
|---|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------|-------------------------|------|------|-------|
|   | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right | U-Turn                  | Left | Thru | Right |
|   | 0                          | 129  | 48   | 38    | 0                              | 128  | 61   | 11    | 0                       | 14   | 396  | 331   | 0                       | 46   | 294  | 115   |
| <i>PHF</i>                                | <b>0.77</b>                |      |      |       | <b>0.78</b>                    |      |      |       | <b>0.97</b>             |      |      |       | <b>0.92</b>             |      |      |       |
| <i>HV %</i>                               | 0.0%                       | 1.6% | 0.0% | 2.6%  | 0.0%                           | 0.0% | 0.0% | 0.0%  | 0.0%                    | 0.0% | 0.5% | 0.0%  | 0.0%                    | 2.2% | 1.4% | 0.0%  |



Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 6  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Market Street  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**HEAVY VEHICLES**

| Start Time | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      | Market Street Westbound |        |      |      |       |
|------------|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------------------------|--------|------|------|-------|
|            | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right                   | U-Turn | Left | Thru | Right |
| 11:00 AM   | 0                          | 1    | 0    | 2     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 0                       | 0      | 0    | 0    | 0     |
| 11:15 AM   | 0                          | 1    | 0    | 1     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 0                       | 0      | 0    | 1    | 0     |
| 11:30 AM   | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 1    | 0                       | 0      | 0    | 0    | 0     |
| 11:45 AM   | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 1                       | 0      | 0    | 0    | 0     |
| 12:00 PM   | 0                          | 0    | 0    | 1     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 0                       | 0      | 0    | 2    | 0     |
| 12:15 PM   | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 0                       | 0      | 0    | 0    | 0     |
| 12:30 PM   | 0                          | 0    | 0    | 0     | 0                              | 1    | 0    | 0     | 0                       | 0    | 1    | 1                       | 0      | 0    | 0    | 0     |
| 12:45 PM   | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 2    | 0                       | 0      | 0    | 0    | 0     |
| 1:00 PM    | 0                          | 1    | 0    | 1     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 0                       | 0      | 0    | 1    | 0     |
| 1:15 PM    | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 1    | 0                       | 0      | 0    | 3    | 0     |
| 1:30 PM    | 0                          | 1    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 0    | 0                       | 0      | 1    | 0    | 0     |
| 1:45 PM    | 0                          | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                       | 0    | 1    | 0                       | 0      | 0    | 0    | 0     |

| MID PEAK HOUR<br>12:30 PM<br>to<br>1:30 PM<br><i>PHF</i> | Woodbury Avenue Northbound |      |      |       | Market Basket Drive Southbound |      |      |       | Market Street Eastbound |      |      | Market Street Westbound |        |      |      |       |
|--|----------------------------|------|------|-------|--------------------------------|------|------|-------|-------------------------|------|------|-------------------------|--------|------|------|-------|
|  | U-Turn                     | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                  | Left | Thru | Right                   | U-Turn | Left | Thru | Right |
|  | 0                          | 1    | 0    | 1     | 0                              | 1    | 0    | 0     | 0                       | 0    | 4    | 1                       | 0      | 0    | 4    | 0     |
|  | <b>0.25</b>                |      |      |       | <b>0.25</b>                    |      |      |       | <b>0.63</b>             |      |      | <b>0.33</b>             |        |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 6  
 Location: Portsmouth, NH  
 Street 1: Woodbury Avenue  
 Street 2: Market Street  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PEDESTRIANS & BICYCLES**

| Start Time | Woodbury Avenue Northbound |      |       |     | Market Basket Drive Southbound |      |       |     | Market Street Eastbound |      |       |     | Market Street Westbound |      |       |     |
|------------|----------------------------|------|-------|-----|--------------------------------|------|-------|-----|-------------------------|------|-------|-----|-------------------------|------|-------|-----|
|            | Left                       | Thru | Right | PED | Left                           | Thru | Right | PED | Left                    | Thru | Right | PED | Left                    | Thru | Right | PED |
| 11:00 AM   | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 11:15 AM   | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 11:30 AM   | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 11:45 AM   | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 12:00 PM   | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 12:15 PM   | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 12:30 PM   | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 12:45 PM   | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 1:00 PM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 1:15 PM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 1:30 PM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |
| 1:45 PM    | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |

| MID PEAK HOUR<br>1:00 PM<br>to<br>2:00 PM | Woodbury Avenue Northbound |      |       |     | Market Basket Drive Southbound |      |       |     | Market Street Eastbound |      |       |     | Market Street Westbound |      |       |     |
|---|----------------------------|------|-------|-----|--------------------------------|------|-------|-----|-------------------------|------|-------|-----|-------------------------|------|-------|-----|
|   | Left                       | Thru | Right | PED | Left                           | Thru | Right | PED | Left                    | Thru | Right | PED | Left                    | Thru | Right | PED |
|   | 0                          | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                       | 0    | 0     | 0   | 0                       | 0    | 0     | 0   |

NOTE: Peak hour summaries here correspond to peak hours identified for passenger car and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 7  
 Location: Portsmouth, NH  
 Street 1: Arthur F Brady Drive  
 Street 2: Home Depot/South site access drive  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | Northbound |      |      |       | Southbound |      |      |       | Eastbound |      |      |       | Westbound |      |      |       |
|------------|------------|------|------|-------|------------|------|------|-------|-----------|------|------|-------|-----------|------|------|-------|
|            | U-Turn     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn    | Left | Thru | Right | U-Turn    | Left | Thru | Right |
| 7:00 AM    | 0          | 0    | 0    | 0     | 0          | 8    | 0    | 7     | 0         | 8    | 12   | 0     | 0         | 0    | 10   | 7     |
| 7:15 AM    | 0          | 0    | 0    | 0     | 0          | 7    | 0    | 2     | 0         | 7    | 9    | 0     | 0         | 0    | 10   | 6     |
| 7:30 AM    | 0          | 0    | 0    | 0     | 0          | 10   | 0    | 7     | 0         | 8    | 13   | 0     | 0         | 0    | 19   | 11    |
| 7:45 AM    | 0          | 0    | 0    | 0     | 0          | 13   | 0    | 11    | 0         | 9    | 20   | 0     | 0         | 0    | 19   | 19    |
| 8:00 AM    | 0          | 0    | 0    | 0     | 0          | 19   | 0    | 6     | 0         | 5    | 17   | 0     | 0         | 0    | 13   | 16    |
| 8:15 AM    | 0          | 0    | 0    | 0     | 0          | 16   | 0    | 10    | 0         | 14   | 19   | 0     | 0         | 0    | 11   | 12    |
| 8:30 AM    | 0          | 0    | 0    | 0     | 0          | 20   | 0    | 14    | 0         | 15   | 16   | 0     | 0         | 0    | 22   | 14    |
| 8:45 AM    | 0          | 0    | 0    | 0     | 0          | 29   | 0    | 9     | 0         | 18   | 18   | 0     | 0         | 0    | 16   | 21    |

| Start Time | Northbound |      |      |       | Southbound |      |      |       | Eastbound |      |      |       | Westbound |      |      |       |
|------------|------------|------|------|-------|------------|------|------|-------|-----------|------|------|-------|-----------|------|------|-------|
|            | U-Turn     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn    | Left | Thru | Right | U-Turn    | Left | Thru | Right |
| 4:00 PM    | 0          | 0    | 0    | 0     | 0          | 16   | 0    | 9     | 0         | 11   | 32   | 0     | 0         | 0    | 39   | 12    |
| 4:15 PM    | 0          | 0    | 0    | 0     | 0          | 15   | 0    | 20    | 0         | 15   | 44   | 0     | 0         | 0    | 27   | 13    |
| 4:30 PM    | 0          | 0    | 0    | 0     | 0          | 28   | 0    | 7     | 0         | 7    | 39   | 0     | 0         | 0    | 38   | 16    |
| 4:45 PM    | 0          | 0    | 0    | 0     | 0          | 25   | 0    | 8     | 0         | 14   | 35   | 0     | 0         | 0    | 39   | 11    |
| 5:00 PM    | 0          | 0    | 0    | 0     | 0          | 23   | 0    | 24    | 0         | 15   | 32   | 0     | 0         | 0    | 51   | 13    |
| 5:15 PM    | 0          | 0    | 0    | 0     | 0          | 12   | 0    | 12    | 0         | 15   | 34   | 0     | 0         | 0    | 60   | 17    |
| 5:30 PM    | 0          | 0    | 0    | 0     | 0          | 20   | 0    | 17    | 0         | 14   | 21   | 0     | 0         | 0    | 44   | 9     |
| 5:45 PM    | 0          | 0    | 0    | 0     | 0          | 23   | 0    | 18    | 0         | 16   | 19   | 0     | 0         | 0    | 29   | 14    |

| AM PEAK HOUR<br>8:00 AM<br>to<br>9:00 AM | Northbound |      |      |       | Southbound |      |      |       | Eastbound |      |      |       | Westbound |      |      |       |
|--|------------|------|------|-------|------------|------|------|-------|-----------|------|------|-------|-----------|------|------|-------|
|  | U-Turn     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn    | Left | Thru | Right | U-Turn    | Left | Thru | Right |
|  | 0          | 0    | 0    | 0     | 0          | 84   | 0    | 39    | 0         | 52   | 70   | 0     | 0         | 0    | 62   | 63    |
| <b>PHF</b>                               | 0.00       |      |      |       | 0.81       |      |      |       | 0.85      |      |      |       | 0.84      |      |      |       |
| <b>HV %</b>                              | 0.0%       | 0.0% | 0.0% | 0.0%  | 0.0%       | 0.0% | 0.0% | 0.0%  | 0.0%      | 1.9% | 5.7% | 0.0%  | 0.0%      | 0.0% | 3.2% | 0.0%  |

| PM PEAK HOUR<br>4:30 PM<br>to<br>5:30 PM | Northbound |      |      |       | Southbound |      |      |       | Eastbound |      |      |       | Westbound |      |      |       |
|--|------------|------|------|-------|------------|------|------|-------|-----------|------|------|-------|-----------|------|------|-------|
|  | U-Turn     | Left | Thru | Right | U-Turn     | Left | Thru | Right | U-Turn    | Left | Thru | Right | U-Turn    | Left | Thru | Right |
|  | 0          | 0    | 0    | 0     | 0          | 88   | 0    | 51    | 0         | 51   | 140  | 0     | 0         | 0    | 188  | 57    |
| <b>PHF</b>                               | 0.00       |      |      |       | 0.74       |      |      |       | 0.97      |      |      |       | 0.80      |      |      |       |
| <b>HV %</b>                              | 0.0%       | 0.0% | 0.0% | 0.0%  | 0.0%       | 0.0% | 0.0% | 2.0%  | 0.0%      | 0.0% | 0.0% | 0.0%  | 0.0%      | 0.0% | 0.0% | 0.0%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 7  
 Location: Portsmouth, NH  
 Street 1: Arthur F Brady Drive  
 Street 2: Home Depot/South site access drive  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**HEAVY VEHICLES**

| Start Time | Home Depot/South site access drive Northbound |      |      |       | Home Depot/South site access drive Southbound |      |      |       | Arthur F Brady Drive Eastbound |      |      |       | Arthur F Brady Drive Westbound |      |      |       |
|------------|---|------|------|-------|---|------|------|-------|--------------------------------|------|------|-------|--------------------------------|------|------|-------|
|            | U-Turn  | Left | Thru | Right | U-Turn  | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                         | Left | Thru | Right |
| 7:00 AM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 1    | 0     | 0                              | 0    | 0    | 0     |
| 7:15 AM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 1    | 0     |
| 7:30 AM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 1    | 0     | 0                              | 0    | 1    | 0     |
| 7:45 AM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 1    | 0     | 0                              | 0    | 0    | 0     |
| 8:00 AM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 1    | 0     | 0                              | 0    | 0    | 0     |
| 8:15 AM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 2    | 0     | 0                              | 0    | 0    | 0     |
| 8:30 AM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 1    | 1    | 0     | 0                              | 0    | 1    | 0     |
| 8:45 AM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 1    | 0     |

| Start Time | Home Depot/South site access drive Northbound |      |      |       | Home Depot/South site access drive Southbound |      |      |       | Arthur F Brady Drive Eastbound |      |      |       | Arthur F Brady Drive Westbound |      |      |       |
|------------|---|------|------|-------|---|------|------|-------|--------------------------------|------|------|-------|--------------------------------|------|------|-------|
|            | U-Turn  | Left | Thru | Right | U-Turn  | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                         | Left | Thru | Right |
| 4:00 PM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 1    | 0     | 0                              | 0    | 0    | 0     |
| 4:15 PM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 4:30 PM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 4:45 PM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 1     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 5:00 PM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 5:15 PM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 5:30 PM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 5:45 PM    | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 0     |

| AM PEAK HOUR<br>7:45 AM to 8:45 AM<br>PHF | Home Depot/South site access drive Northbound |      |      |       | Home Depot/South site access drive Southbound |      |      |       | Arthur F Brady Drive Eastbound |      |      |       | Arthur F Brady Drive Westbound |      |      |       |
|---|---|------|------|-------|---|------|------|-------|--------------------------------|------|------|-------|--------------------------------|------|------|-------|
|   | U-Turn  | Left | Thru | Right | U-Turn  | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                         | Left | Thru | Right |
|   | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 1    | 5    | 0     | 0                              | 0    | 1    | 0     |
|   | 0.00  |      |      |       | 0.00  |      |      |       | 0.75                           |      |      |       | 0.25                           |      |      |       |

| PM PEAK HOUR<br>4:00 PM to 5:00 PM<br>PHF | Home Depot/South site access drive Northbound |      |      |       | Home Depot/South site access drive Southbound |      |      |       | Arthur F Brady Drive Eastbound |      |      |       | Arthur F Brady Drive Westbound |      |      |       |
|---|---|------|------|-------|---|------|------|-------|--------------------------------|------|------|-------|--------------------------------|------|------|-------|
|   | U-Turn  | Left | Thru | Right | U-Turn  | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                         | Left | Thru | Right |
|   | 0   | 0    | 0    | 0     | 0   | 0    | 0    | 1     | 0                              | 0    | 1    | 0     | 0                              | 0    | 0    | 0     |
|   | 0.00  |      |      |       | 0.25  |      |      |       | 0.25                           |      |      |       | 0.00                           |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 7  
 Location: Portsmouth, NH  
 Street 1: Arthur F Brady Drive  
 Street 2: Home Depot/South site access drive  
 Count Date: 3/20/2024  
 Day of Week: Wednesday  
 Weather: Cloudy, 40°F



**PEDESTRIANS & BICYCLES**

| Start Time | Home Depot/South site access drive |   |            |   | Arthur F Brady Drive |   |           |   | Arthur F Brady Drive |      |       |     |      |      |       |     |
|------------|------------------------------------|---|------------|---|----------------------|---|-----------|---|----------------------|------|-------|-----|------|------|-------|-----|
|            | Northbound                         |   | Southbound |   | Eastbound            |   | Westbound |   | Left                 | Thru | Right | PED | Left | Thru | Right | PED |
| 7:00 AM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 7:15 AM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 2 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 7:30 AM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 7:45 AM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 8:00 AM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 8:15 AM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 8:30 AM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 1 | 0                    | 0    | 0     | 1   | 0    | 0    | 0     | 0   |
| 8:45 AM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |

| Start Time | Home Depot/South site access drive |   |            |   | Arthur F Brady Drive |   |           |   | Arthur F Brady Drive |      |       |     |      |      |       |     |
|------------|------------------------------------|---|------------|---|----------------------|---|-----------|---|----------------------|------|-------|-----|------|------|-------|-----|
|            | Northbound                         |   | Southbound |   | Eastbound            |   | Westbound |   | Left                 | Thru | Right | PED | Left | Thru | Right | PED |
| 4:00 PM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 1 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 4:15 PM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 4:30 PM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 4:45 PM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 5:00 PM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 5:15 PM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 5:30 PM    | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |
| 5:45 PM    | 0                                  | 0 | 0          | 0 | 3                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |

| AM PEAK HOUR <sup>1</sup><br>8:00 AM<br>to<br>9:00 AM | Home Depot/South site access drive |   |            |   | Arthur F Brady Drive |   |           |   | Arthur F Brady Drive |      |       |     |      |      |       |     |
|---|------------------------------------|---|------------|---|----------------------|---|-----------|---|----------------------|------|-------|-----|------|------|-------|-----|
|   | Northbound                         |   | Southbound |   | Eastbound            |   | Westbound |   | Left                 | Thru | Right | PED | Left | Thru | Right | PED |
|   | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 1 | 0                    | 0    | 0     | 1   | 0    | 0    | 0     | 0   |

| PM PEAK HOUR <sup>1</sup><br>4:30 PM<br>to<br>5:30 PM | Home Depot/South site access drive |   |            |   | Arthur F Brady Drive |   |           |   | Arthur F Brady Drive |      |       |     |      |      |       |     |
|---|------------------------------------|---|------------|---|----------------------|---|-----------|---|----------------------|------|-------|-----|------|------|-------|-----|
|   | Northbound                         |   | Southbound |   | Eastbound            |   | Westbound |   | Left                 | Thru | Right | PED | Left | Thru | Right | PED |
|   | 0                                  | 0 | 0          | 0 | 0                    | 0 | 0         | 0 | 0                    | 0    | 0     | 0   | 0    | 0    | 0     | 0   |

<sup>1</sup> NOTE: Peak hour summaries here correspond to peak hours identified for passenger cars and heavy vehicles combined.

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 7  
 Location: Portsmouth, NH  
 Street 1: Arthur F Brady Drive  
 Street 2: Home Depot/South site access drive  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PASSENGER CARS & HEAVY VEHICLES COMBINED**

| Start Time | Northbound |      |      |       | Home Depot/South site access drive Southbound |      |      |       | Arthur F Brady Drive Eastbound |      |      |       | Arthur F Brady Drive Westbound |      |      |       |
|------------|------------|------|------|-------|---|------|------|-------|--------------------------------|------|------|-------|--------------------------------|------|------|-------|
|            | U-Turn     | Left | Thru | Right | U-Turn  | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                         | Left | Thru | Right |
| 11:00 AM   | 0          | 0    | 0    | 0     | 0   | 16   | 0    | 7     | 1                              | 11   | 30   | 0     | 0                              | 0    | 12   | 14    |
| 11:15 AM   | 0          | 0    | 0    | 0     | 0   | 14   | 0    | 9     | 0                              | 26   | 33   | 0     | 0                              | 0    | 14   | 16    |
| 11:30 AM   | 0          | 0    | 0    | 0     | 0   | 20   | 0    | 10    | 0                              | 16   | 39   | 0     | 0                              | 0    | 22   | 19    |
| 11:45 AM   | 0          | 0    | 0    | 0     | 0   | 25   | 0    | 11    | 0                              | 19   | 32   | 0     | 0                              | 0    | 21   | 12    |
| 12:00 PM   | 0          | 0    | 0    | 0     | 0   | 27   | 0    | 6     | 0                              | 17   | 34   | 0     | 0                              | 0    | 17   | 9     |
| 12:15 PM   | 0          | 0    | 0    | 0     | 0   | 22   | 0    | 6     | 1                              | 18   | 37   | 0     | 0                              | 0    | 21   | 12    |
| 12:30 PM   | 0          | 0    | 0    | 0     | 0   | 23   | 0    | 8     | 0                              | 11   | 28   | 0     | 0                              | 0    | 18   | 21    |
| 12:45 PM   | 0          | 0    | 0    | 0     | 0   | 23   | 0    | 10    | 0                              | 9    | 37   | 0     | 0                              | 0    | 14   | 15    |
| 1:00 PM    | 0          | 0    | 0    | 0     | 0   | 17   | 0    | 12    | 0                              | 13   | 29   | 0     | 0                              | 0    | 24   | 10    |
| 1:15 PM    | 0          | 0    | 0    | 0     | 0   | 19   | 0    | 10    | 0                              | 21   | 38   | 0     | 0                              | 0    | 17   | 15    |
| 1:30 PM    | 0          | 0    | 0    | 0     | 0   | 24   | 0    | 12    | 0                              | 19   | 36   | 0     | 0                              | 0    | 15   | 8     |
| 1:45 PM    | 0          | 0    | 0    | 0     | 0   | 20   | 0    | 9     | 0                              | 10   | 39   | 0     | 0                              | 0    | 16   | 8     |

| MID PEAK HOUR<br>11:30 AM<br>to<br>12:30 PM | Northbound  |      |      |       | Home Depot/South site access drive Southbound |      |      |       | Arthur F Brady Drive Eastbound |      |      |       | Arthur F Brady Drive Westbound |      |      |       |
|---|-------------|------|------|-------|---|------|------|-------|--------------------------------|------|------|-------|--------------------------------|------|------|-------|
|   | U-Turn      | Left | Thru | Right | U-Turn  | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                         | Left | Thru | Right |
|   | 0           | 0    | 0    | 0     | 0   | 94   | 0    | 33    | 1                              | 70   | 142  | 0     | 0                              | 0    | 81   | 52    |
| <b>PHF</b>                                  | <b>0.00</b> |      |      |       | <b>0.88</b>                                   |      |      |       | <b>0.95</b>                    |      |      |       | <b>0.81</b>                    |      |      |       |
| <b>HV %</b>                                 | 0.0%        | 0.0% | 0.0% | 0.0%  | 0.0%  | 0.0% | 0.0% | 0.0%  | 0.0%                           | 1.4% | 0.7% | 0.0%  | 0.0%                           | 0.0% | 0.0% | 3.8%  |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTD #: Location 7  
 Location: Portsmouth, NH  
 Street 1: Arthur F Brady Drive  
 Street 2: Home Depot/South site access drive  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**HEAVY VEHICLES**

| Start Time | Northbound |      |      |       | Home Depot/South site access drive Southbound |      |      |       | Arthur F Brady Drive Eastbound |      |      |       | Arthur F Brady Drive Westbound |      |      |       |
|------------|------------|------|------|-------|---|------|------|-------|--------------------------------|------|------|-------|--------------------------------|------|------|-------|
|            | U-Turn     | Left | Thru | Right | U-Turn  | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                         | Left | Thru | Right |
| 11:00 AM   | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 1     |
| 11:15 AM   | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 3     | 0                              | 3    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 11:30 AM   | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 11:45 AM   | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 1    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 12:00 PM   | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 1    | 0     | 0                              | 0    | 0    | 1     |
| 12:15 PM   | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 1     |
| 12:30 PM   | 0          | 0    | 0    | 0     | 0   | 1    | 0    | 0     | 0                              | 1    | 0    | 0     | 0                              | 0    | 0    | 0     |
| 12:45 PM   | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 1     |
| 1:00 PM    | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 1     |
| 1:15 PM    | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 1     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 1     |
| 1:30 PM    | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 1     |
| 1:45 PM    | 0          | 0    | 0    | 0     | 0   | 0    | 0    | 0     | 0                              | 0    | 0    | 0     | 0                              | 0    | 0    | 0     |

| MID PEAK HOUR<br>11:15 AM<br>to<br>12:15 PM<br><i>PHF</i> | Northbound  |      |      |       | Home Depot/South site access drive Southbound |      |      |       | Arthur F Brady Drive Eastbound |      |      |       | Arthur F Brady Drive Westbound |      |      |       |
|---|-------------|------|------|-------|---|------|------|-------|--------------------------------|------|------|-------|--------------------------------|------|------|-------|
|   | U-Turn      | Left | Thru | Right | U-Turn  | Left | Thru | Right | U-Turn                         | Left | Thru | Right | U-Turn                         | Left | Thru | Right |
|   | 0           | 0    | 0    | 0     | 0   | 0    | 0    | 3     | 0                              | 4    | 1    | 0     | 0                              | 0    | 0    | 1     |
|   | <b>0.00</b> |      |      |       | <b>0.25</b>                                   |      |      |       | <b>0.42</b>                    |      |      |       | <b>0.25</b>                    |      |      |       |

Client: Matthew Stoutz, PE, PTOE, RSP1  
 Project #: 1486\_4\_TB  
 BTM #: Location 7  
 Location: Portsmouth, NH  
 Street 1: Arthur F Brady Drive  
 Street 2: Home Depot/South site access drive  
 Count Date: 3/23/2024  
 Day of Week: Saturday  
 Weather: Rain, 50°F



**PEDESTRIANS & BICYCLES**

| Start Time | Northbound |      |       |     | Home Depot/South site access drive Southbound |      |       |     | Arthur F Brady Drive Eastbound |      |       |     | Arthur F Brady Drive Westbound |      |       |     |
|------------|------------|------|-------|-----|---|------|-------|-----|--------------------------------|------|-------|-----|--------------------------------|------|-------|-----|
|            | Left       | Thru | Right | PED | Left  | Thru | Right | PED | Left                           | Thru | Right | PED | Left                           | Thru | Right | PED |
| 11:00 AM   | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 1   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 11:15 AM   | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 11:30 AM   | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 11:45 AM   | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 12:00 PM   | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 12:15 PM   | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 12:30 PM   | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 12:45 PM   | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 1:00 PM    | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 1:15 PM    | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 1:30 PM    | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |
| 1:45 PM    | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |

| MID PEAK HOUR<br>11:30 AM<br>to<br>12:30 PM | Northbound |      |       |     | Home Depot/South site access drive Southbound |      |       |     | Arthur F Brady Drive Eastbound |      |       |     | Arthur F Brady Drive Westbound |      |       |     |
|---|------------|------|-------|-----|---|------|-------|-----|--------------------------------|------|-------|-----|--------------------------------|------|-------|-----|
|   | Left       | Thru | Right | PED | Left  | Thru | Right | PED | Left                           | Thru | Right | PED | Left                           | Thru | Right | PED |
|   | 0          | 0    | 0     | 0   | 0   | 0    | 0     | 0   | 0                              | 0    | 0     | 0   | 0                              | 0    | 0     | 0   |

NOTE: Peak hour summaries here correspond to peak hours identified for passenger car and heavy vehicles combined.



# Speed Report

Job 1486\_4\_TB\_ATR 1  
 Area Portsmouth, NH  
 Location Woodbury Ave NB, approx. 250' north of Durgin Lane  
 Dir Northbound  
**Wednesday, March 20, 2024**



| Time         | Total       | Speed Bins (mph) |          |           |            |            |             |             |            |            |           |          |          |          |          |          |          |
|--------------|-------------|------------------|----------|-----------|------------|------------|-------------|-------------|------------|------------|-----------|----------|----------|----------|----------|----------|----------|
|              |             | 0-5              | 5-10     | 10-15     | 15-20      | 20-25      | 25-30       | 30-35       | 35-40      | 40-45      | 45-50     | 50-55    | 55-60    | 60-65    | 65-70    | 70-75    | 75-80    |
| 0000         | 7           | 0                | 0        | 0         | 0          | 0          | 1           | 4           | 1          | 1          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0100         | 4           | 0                | 0        | 0         | 0          | 0          | 1           | 2           | 1          | 0          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0200         | 9           | 0                | 0        | 0         | 0          | 0          | 2           | 4           | 3          | 0          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0300         | 9           | 0                | 0        | 0         | 0          | 0          | 3           | 3           | 1          | 2          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0400         | 20          | 0                | 0        | 0         | 0          | 0          | 4           | 8           | 5          | 3          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0500         | 86          | 0                | 0        | 0         | 5          | 3          | 7           | 39          | 27         | 4          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0600         | 173         | 0                | 0        | 0         | 4          | 6          | 33          | 71          | 48         | 10         | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0700         | 262         | 0                | 1        | 0         | 4          | 6          | 48          | 131         | 56         | 14         | 2         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0800         | 281         | 0                | 0        | 0         | 5          | 9          | 65          | 140         | 50         | 11         | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0900         | 393         | 0                | 0        | 0         | 6          | 6          | 185         | 154         | 40         | 2          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1000         | 463         | 0                | 0        | 1         | 6          | 32         | 167         | 213         | 43         | 1          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1100         | 598         | 0                | 0        | 1         | 4          | 30         | 229         | 248         | 78         | 8          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1200         | 687         | 0                | 0        | 1         | 11         | 61         | 266         | 274         | 66         | 7          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1300         | 626         | 0                | 0        | 2         | 5          | 41         | 290         | 236         | 48         | 4          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1400         | 565         | 0                | 0        | 1         | 5          | 36         | 226         | 255         | 39         | 3          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1500         | 545         | 0                | 1        | 1         | 7          | 23         | 202         | 241         | 63         | 5          | 2         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1600         | 607         | 0                | 0        | 3         | 11         | 27         | 215         | 270         | 73         | 7          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1700         | 616         | 0                | 0        | 2         | 15         | 47         | 203         | 266         | 75         | 8          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1800         | 424         | 0                | 0        | 0         | 6          | 12         | 125         | 198         | 74         | 8          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1900         | 297         | 0                | 0        | 1         | 4          | 6          | 86          | 153         | 37         | 10         | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 2000         | 150         | 0                | 0        | 0         | 2          | 6          | 28          | 67          | 41         | 6          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 2100         | 82          | 0                | 0        | 0         | 1          | 2          | 19          | 44          | 11         | 5          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 2200         | 32          | 0                | 0        | 0         | 0          | 1          | 8           | 19          | 4          | 0          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 2300         | 16          | 0                | 0        | 1         | 0          | 1          | 2           | 8           | 3          | 1          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| <b>Total</b> | <b>6952</b> | <b>0</b>         | <b>2</b> | <b>14</b> | <b>101</b> | <b>355</b> | <b>2415</b> | <b>3048</b> | <b>887</b> | <b>120</b> | <b>10</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> |

100.00% 0.00% 0.03% 0.20% 1.45% 5.11% 34.74% 43.84% 12.76% 1.73% 0.14% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00%

Maximum = 47.6 mph, Minimum = 7.0 mph, Mean = 30.8 mph  
 85% Speed = 34.90 mph, 95% Speed = 37.64 mph, Median = 30.81 mph  
 10 mph Pace = 26 - 36, Number in Pace = 5539 (79.67%)  
 Variance = 18.52, Standard Deviation = 4.30 mph

# Speed Report

Job 1486\_4\_TB\_ATR 1  
 Area Portsmouth, NH  
 Location Woodbury Ave NB, approx. 250' north of Durgin Lane  
 Dir Northbound  
**Thursday, March 21, 2024**



| Time         | Total       | Speed Bins (mph) |          |           |            |            |             |             |            |            |           |          |          |          |          |          |          |
|--------------|-------------|------------------|----------|-----------|------------|------------|-------------|-------------|------------|------------|-----------|----------|----------|----------|----------|----------|----------|
|              |             | 0-5              | 5-10     | 10-15     | 15-20      | 20-25      | 25-30       | 30-35       | 35-40      | 40-45      | 45-50     | 50-55    | 55-60    | 60-65    | 65-70    | 70-75    | 75-80    |
| 0000         | 9           | 0                | 0        | 0         | 0          | 0          | 3           | 3           | 2          | 1          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0100         | 5           | 0                | 0        | 0         | 0          | 0          | 0           | 2           | 2          | 1          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0200         | 7           | 0                | 0        | 0         | 0          | 0          | 2           | 3           | 2          | 0          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0300         | 15          | 0                | 0        | 0         | 0          | 1          | 4           | 7           | 3          | 0          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0400         | 31          | 0                | 0        | 0         | 1          | 0          | 2           | 14          | 10         | 4          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0500         | 81          | 0                | 0        | 1         | 0          | 2          | 16          | 29          | 20         | 9          | 4         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0600         | 176         | 0                | 0        | 0         | 2          | 3          | 27          | 91          | 41         | 10         | 2         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0700         | 279         | 0                | 0        | 2         | 9          | 15         | 56          | 125         | 61         | 9          | 2         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0800         | 323         | 0                | 0        | 1         | 3          | 19         | 108         | 143         | 45         | 4          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 0900         | 350         | 0                | 0        | 1         | 5          | 11         | 116         | 177         | 32         | 8          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1000         | 456         | 0                | 0        | 1         | 4          | 24         | 184         | 200         | 39         | 3          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1100         | 526         | 0                | 0        | 1         | 9          | 37         | 200         | 225         | 51         | 2          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1200         | 687         | 0                | 0        | 1         | 11         | 61         | 286         | 263         | 58         | 7          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1300         | 601         | 0                | 0        | 0         | 11         | 50         | 296         | 187         | 51         | 4          | 2         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1400         | 609         | 0                | 0        | 2         | 8          | 41         | 234         | 263         | 59         | 2          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1500         | 616         | 0                | 0        | 1         | 9          | 39         | 240         | 268         | 52         | 7          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1600         | 630         | 0                | 0        | 0         | 9          | 33         | 231         | 286         | 65         | 5          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1700         | 604         | 0                | 0        | 0         | 14         | 34         | 179         | 297         | 72         | 7          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1800         | 441         | 0                | 0        | 4         | 9          | 18         | 143         | 199         | 64         | 3          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 1900         | 274         | 0                | 0        | 2         | 1          | 5          | 68          | 146         | 45         | 6          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| 2000         | 167         | 0                | 0        | 0         | 3          | 3          | 43          | 82          | 31         | 5          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 2100         | 77          | 0                | 0        | 1         | 0          | 0          | 14          | 39          | 19         | 4          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 2200         | 37          | 0                | 0        | 0         | 0          | 0          | 8           | 20          | 7          | 2          | 0         | 0        | 0        | 0        | 0        | 0        | 0        |
| 2300         | 18          | 0                | 0        | 0         | 0          | 1          | 6           | 2           | 8          | 0          | 1         | 0        | 0        | 0        | 0        | 0        | 0        |
| <b>Total</b> | <b>7019</b> | <b>0</b>         | <b>0</b> | <b>18</b> | <b>108</b> | <b>397</b> | <b>2466</b> | <b>3071</b> | <b>839</b> | <b>103</b> | <b>17</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> |

**100.00% 0.00% 0.00% 0.26% 1.54% 5.66% 35.13% 43.75% 11.95% 1.47% 0.24% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00%**

Maximum = 48.2 mph, Minimum = 10.5 mph, Mean = 30.7 mph  
 85% Speed = 34.78 mph, 95% Speed = 37.41 mph, Median = 30.76 mph  
 10 mph Pace = 26 - 36, Number in Pace = 5625 (80.14%)  
 Variance = 18.91, Standard Deviation = 4.35 mph

# Speed Report

Job 1486\_4\_TB\_ATR 2  
 Area Portsmouth, NH  
 Location Woodbury Ave SB, approx. 250' north of Durgin Lane  
 Dir Southbound  
**Wednesday, March 20, 2024**



PO BOX 1723, Frammingham, MA 01701  
 Office: 978-746-1259  
 DataRequest@BostonTrafficData.com  
 www.BostonTrafficData.com

| Time         | Total       | Speed Bins (mph) |           |            |            |             |             |             |            |           |          |          |          |          |          |          |          |
|--------------|-------------|------------------|-----------|------------|------------|-------------|-------------|-------------|------------|-----------|----------|----------|----------|----------|----------|----------|----------|
|              |             | 0-5              | 5-10      | 10-15      | 15-20      | 20-25       | 25-30       | 30-35       | 35-40      | 40-45     | 45-50    | 50-55    | 55-60    | 60-65    | 65-70    | 70-75    | 75-80    |
| 0000         | 19          | 0                | 0         | 0          | 0          | 1           | 6           | 11          | 0          | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0100         | 8           | 0                | 0         | 0          | 0          | 1           | 2           | 3           | 1          | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0200         | 14          | 0                | 0         | 0          | 0          | 1           | 5           | 5           | 3          | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0300         | 21          | 0                | 0         | 0          | 0          | 1           | 2           | 15          | 2          | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0400         | 47          | 0                | 0         | 0          | 0          | 1           | 9           | 23          | 12         | 1         | 1        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0500         | 78          | 0                | 0         | 0          | 0          | 4           | 21          | 39          | 11         | 3         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0600         | 192         | 0                | 1         | 1          | 1          | 10          | 49          | 98          | 29         | 3         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0700         | 456         | 0                | 0         | 2          | 16         | 59          | 137         | 173         | 60         | 6         | 3        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0800         | 584         | 0                | 0         | 7          | 22         | 94          | 209         | 182         | 62         | 7         | 1        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0900         | 533         | 0                | 0         | 0          | 33         | 107         | 195         | 158         | 38         | 2         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1000         | 561         | 0                | 2         | 17         | 65         | 157         | 209         | 92          | 17         | 2         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1100         | 769         | 0                | 1         | 32         | 85         | 212         | 247         | 163         | 27         | 1         | 1        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1200         | 896         | 4                | 13        | 59         | 119        | 248         | 291         | 138         | 21         | 2         | 1        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1300         | 741         | 0                | 3         | 30         | 68         | 161         | 293         | 162         | 23         | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1400         | 692         | 0                | 4         | 27         | 100        | 180         | 227         | 128         | 25         | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1500         | 712         | 1                | 8         | 23         | 85         | 170         | 267         | 127         | 31         | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1600         | 728         | 1                | 4         | 27         | 96         | 186         | 251         | 136         | 27         | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1700         | 692         | 0                | 5         | 26         | 64         | 183         | 250         | 140         | 24         | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1800         | 511         | 0                | 1         | 3          | 24         | 153         | 197         | 111         | 22         | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1900         | 420         | 0                | 0         | 1          | 19         | 93          | 163         | 117         | 26         | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 2000         | 213         | 0                | 0         | 0          | 5          | 23          | 80          | 88          | 16         | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 2100         | 127         | 0                | 0         | 0          | 3          | 11          | 48          | 51          | 14         | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 2200         | 69          | 0                | 0         | 0          | 0          | 1           | 15          | 39          | 14         | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 2300         | 40          | 0                | 0         | 0          | 0          | 2           | 13          | 20          | 3          | 2         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| <b>Total</b> | <b>9123</b> | <b>6</b>         | <b>42</b> | <b>255</b> | <b>805</b> | <b>2059</b> | <b>3186</b> | <b>2219</b> | <b>508</b> | <b>36</b> | <b>7</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> |

**100.00% 0.07% 0.46% 2.80% 8.82% 22.57% 34.92% 24.32% 5.57% 0.39% 0.08% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00%**

Maximum = 47.1 mph, Minimum = 2.9 mph, Mean = 26.8 mph  
 85% Speed = 32.66 mph, 95% Speed = 35.40 mph, Median = 27.18 mph  
 10 mph Pace = 23 - 33, Number in Pace = 5822 (63.82%)  
 Variance = 33.38, Standard Deviation = 5.78 mph

# Speed Report

Job 1486\_4\_TB\_ATR 2  
 Area Portsmouth, NH  
 Location Woodbury Ave SB, approx. 250' north of Durgin Lane  
 Dir Southbound  
 Thursday, March 21, 2024



PO BOX 1723, Frammingham, MA 01701  
 Office: 978-746-1259  
 DataRequest@BostonTrafficData.com  
 www.BostonTrafficData.com

| Time         | Total       | Speed Bins (mph) |           |            |            |             |             |             |            |           |          |          |          |          |          |          |          |
|--------------|-------------|------------------|-----------|------------|------------|-------------|-------------|-------------|------------|-----------|----------|----------|----------|----------|----------|----------|----------|
|              |             | 0-5              | 5-10      | 10-15      | 15-20      | 20-25       | 25-30       | 30-35       | 35-40      | 40-45     | 45-50    | 50-55    | 55-60    | 60-65    | 65-70    | 70-75    | 75-80    |
| 0000         | 15          | 0                | 0         | 0          | 0          | 0           | 8           | 6           | 1          | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0100         | 11          | 0                | 0         | 0          | 0          | 1           | 3           | 5           | 2          | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0200         | 20          | 0                | 0         | 0          | 0          | 2           | 2           | 9           | 6          | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0300         | 17          | 0                | 0         | 0          | 1          | 3           | 4           | 7           | 2          | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0400         | 56          | 0                | 0         | 0          | 1          | 3           | 17          | 24          | 9          | 2         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0500         | 97          | 0                | 0         | 1          | 1          | 9           | 38          | 42          | 6          | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0600         | 164         | 0                | 0         | 0          | 3          | 10          | 42          | 85          | 22         | 2         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0700         | 460         | 0                | 0         | 2          | 5          | 37          | 131         | 197         | 76         | 12        | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0800         | 599         | 0                | 1         | 4          | 22         | 95          | 196         | 191         | 79         | 10        | 1        | 0        | 0        | 0        | 0        | 0        | 0        |
| 0900         | 511         | 0                | 1         | 8          | 30         | 115         | 170         | 150         | 33         | 3         | 1        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1000         | 563         | 0                | 0         | 2          | 36         | 125         | 228         | 139         | 29         | 3         | 1        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1100         | 743         | 0                | 5         | 23         | 81         | 184         | 267         | 148         | 34         | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1200         | 863         | 1                | 7         | 58         | 116        | 215         | 259         | 167         | 39         | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1300         | 726         | 1                | 1         | 30         | 88         | 172         | 232         | 181         | 19         | 2         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1400         | 687         | 0                | 3         | 24         | 88         | 167         | 229         | 147         | 27         | 2         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1500         | 747         | 0                | 3         | 22         | 70         | 184         | 241         | 196         | 31         | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1600         | 759         | 0                | 3         | 32         | 91         | 191         | 282         | 133         | 26         | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1700         | 648         | 0                | 4         | 26         | 73         | 131         | 201         | 175         | 33         | 5         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1800         | 536         | 0                | 0         | 3          | 25         | 122         | 205         | 153         | 23         | 5         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 1900         | 416         | 0                | 0         | 4          | 22         | 76          | 175         | 120         | 19         | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 2000         | 268         | 0                | 0         | 1          | 6          | 39          | 121         | 76          | 24         | 1         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 2100         | 121         | 0                | 0         | 0          | 1          | 8           | 33          | 57          | 20         | 1         | 1        | 0        | 0        | 0        | 0        | 0        | 0        |
| 2200         | 55          | 0                | 0         | 0          | 0          | 0           | 18          | 26          | 9          | 2         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| 2300         | 41          | 0                | 0         | 0          | 0          | 0           | 7           | 27          | 7          | 0         | 0        | 0        | 0        | 0        | 0        | 0        | 0        |
| <b>Total</b> | <b>9123</b> | <b>2</b>         | <b>28</b> | <b>240</b> | <b>760</b> | <b>1889</b> | <b>3109</b> | <b>2461</b> | <b>576</b> | <b>54</b> | <b>4</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> |

100.00% 0.02% 0.31% 2.63% 8.33% 20.71% 34.08% 26.98% 6.31% 0.59% 0.04% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00%

Maximum = 46.8 mph, Minimum = 3.1 mph, Mean = 27.3 mph  
 85% Speed = 32.99 mph, 95% Speed = 35.79 mph, Median = 27.79 mph  
 10 mph Pace = 23 - 33, Number in Pace = 5794 (63.51%)  
 Variance = 33.43, Standard Deviation = 5.78 mph

# Volume Report

**Job** 1486\_4\_TB\_ATR 1  
**Area** Portsmouth, NH  
**Location** Woodbury Ave NB, approx. 250' north of Durgin Lane



PO BOX 1723, Framingham, MA 01701  
 Office: 978-746-1259  
 DataRequest@BostonTrafficData.com  
 www.BostonTrafficData.com

**Wednesday, March 20, 2024**

| Time         | Total       | NB          |             |             |          | Time     | Total       | NB          |             |          |          |          |
|--------------|-------------|-------------|-------------|-------------|----------|----------|-------------|-------------|-------------|----------|----------|----------|
| 0000         | 2           | 2           |             | 0           |          | 1200     | 165         | 165         |             | 0        |          |          |
| 0015         | 1           | 1           |             | 0           |          | 1215     | 167         | 167         |             | 0        |          |          |
| 0030         | 3           | 3           |             | 0           |          | 1230     | 187         | 187         |             | 0        |          |          |
| 0045         | 1           | 7           | 1           | 7           | 0        | 1245     | 168         | 687         | 168         | 687      | 0        | 0        |
| 0100         | 0           | 0           |             | 0           |          | 1300     | 188         | 188         |             | 0        |          |          |
| 0115         | 1           | 1           |             | 0           |          | 1315     | 149         | 149         |             | 0        |          |          |
| 0130         | 1           | 1           |             | 0           |          | 1330     | 159         | 159         |             | 0        |          |          |
| 0145         | 2           | 4           | 2           | 4           | 0        | 1345     | 130         | 626         | 130         | 626      | 0        | 0        |
| 0200         | 5           | 5           |             | 0           |          | 1400     | 146         | 146         |             | 0        |          |          |
| 0215         | 1           | 1           |             | 0           |          | 1415     | 138         | 138         |             | 0        |          |          |
| 0230         | 2           | 2           |             | 0           |          | 1430     | 143         | 143         |             | 0        |          |          |
| 0245         | 1           | 9           | 1           | 9           | 0        | 1445     | 138         | 565         | 138         | 565      | 0        | 0        |
| 0300         | 1           | 1           |             | 0           |          | 1500     | 129         | 129         |             | 0        |          |          |
| 0315         | 1           | 1           |             | 0           |          | 1515     | 148         | 148         |             | 0        |          |          |
| 0330         | 4           | 4           |             | 0           |          | 1530     | 140         | 140         |             | 0        |          |          |
| 0345         | 3           | 9           | 3           | 9           | 0        | 1545     | 128         | 545         | 128         | 545      | 0        | 0        |
| 0400         | 3           | 3           |             | 0           |          | 1600     | 143         | 143         |             | 0        |          |          |
| 0415         | 3           | 3           |             | 0           |          | 1615     | 143         | 143         |             | 0        |          |          |
| 0430         | 8           | 8           |             | 0           |          | 1630     | 158         | 158         |             | 0        |          |          |
| 0445         | 6           | 20          | 6           | 20          | 0        | 1645     | 163         | 607         | 163         | 607      | 0        | 0        |
| 0500         | 9           | 9           |             | 0           |          | 1700     | 168         | 168         |             | 0        |          |          |
| 0515         | 18          | 18          |             | 0           |          | 1715     | 150         | 150         |             | 0        |          |          |
| 0530         | 31          | 31          |             | 0           |          | 1730     | 150         | 150         |             | 0        |          |          |
| 0545         | 28          | 86          | 28          | 86          | 0        | 1745     | 148         | 616         | 148         | 616      | 0        | 0        |
| 0600         | 30          | 30          |             | 0           |          | 1800     | 102         | 102         |             | 0        |          |          |
| 0615         | 38          | 38          |             | 0           |          | 1815     | 105         | 105         |             | 0        |          |          |
| 0630         | 55          | 55          |             | 0           |          | 1830     | 125         | 125         |             | 0        |          |          |
| 0645         | 50          | 173         | 50          | 173         | 0        | 1845     | 92          | 424         | 92          | 424      | 0        | 0        |
| 0700         | 48          | 48          |             | 0           |          | 1900     | 99          | 99          |             | 0        |          |          |
| 0715         | 62          | 62          |             | 0           |          | 1915     | 81          | 81          |             | 0        |          |          |
| 0730         | 66          | 66          |             | 0           |          | 1930     | 62          | 62          |             | 0        |          |          |
| 0745         | 86          | 262         | 86          | 262         | 0        | 1945     | 55          | 297         | 55          | 297      | 0        | 0        |
| 0800         | 62          | 62          |             | 0           |          | 2000     | 50          | 50          |             | 0        |          |          |
| 0815         | 63          | 63          |             | 0           |          | 2015     | 47          | 47          |             | 0        |          |          |
| 0830         | 72          | 72          |             | 0           |          | 2030     | 36          | 36          |             | 0        |          |          |
| 0845         | 84          | 281         | 84          | 281         | 0        | 2045     | 17          | 150         | 17          | 150      | 0        | 0        |
| 0900         | 95          | 95          |             | 0           |          | 2100     | 26          | 26          |             | 0        |          |          |
| 0915         | 93          | 93          |             | 0           |          | 2115     | 24          | 24          |             | 0        |          |          |
| 0930         | 89          | 89          |             | 0           |          | 2130     | 21          | 21          |             | 0        |          |          |
| 0945         | 116         | 393         | 116         | 393         | 0        | 2145     | 11          | 82          | 11          | 82       | 0        | 0        |
| 1000         | 120         | 120         |             | 0           |          | 2200     | 16          | 16          |             | 0        |          |          |
| 1015         | 106         | 106         |             | 0           |          | 2215     | 4           | 4           |             | 0        |          |          |
| 1030         | 101         | 101         |             | 0           |          | 2230     | 4           | 4           |             | 0        |          |          |
| 1045         | 136         | 463         | 136         | 463         | 0        | 2245     | 8           | 32          | 8           | 32       | 0        | 0        |
| 1100         | 151         | 151         |             | 0           |          | 2300     | 5           | 5           |             | 0        |          |          |
| 1115         | 147         | 147         |             | 0           |          | 2315     | 5           | 5           |             | 0        |          |          |
| 1130         | 150         | 150         |             | 0           |          | 2330     | 2           | 2           |             | 0        |          |          |
| 1145         | 150         | 598         | 150         | 598         | 0        | 2345     | 4           | 16          | 4           | 16       | 0        | 0        |
| <b>Total</b> | <b>6952</b> | <b>6952</b> | <b>6952</b> | <b>6952</b> | <b>0</b> | <b>0</b> | <b>6952</b> | <b>6952</b> | <b>6952</b> | <b>0</b> | <b>0</b> | <b>0</b> |

# Volume Report

**Job** 1486\_4\_TB\_ATR 1  
**Area** Portsmouth, NH  
**Location** Woodbury Ave NB, approx. 250' north of Durgin Lane



PO BOX 1723, Framingham, MA 01701  
 Office: 978-746-1259  
 DataRequest@BostonTrafficData.com  
 www.BostonTrafficData.com

**Thursday, March 21, 2024**

| Time         | Total       | NB          |             |          |          | Time | Total | NB  |     |     |   |   |
|--------------|-------------|-------------|-------------|----------|----------|------|-------|-----|-----|-----|---|---|
| 0000         | 3           | 3           |             | 0        |          | 1200 | 165   | 165 |     | 0   |   |   |
| 0015         | 3           | 3           |             | 0        |          | 1215 | 172   | 172 |     | 0   |   |   |
| 0030         | 2           | 2           |             | 0        |          | 1230 | 190   | 190 |     | 0   |   |   |
| 0045         | 1           | 1           | 9           | 0        | 0        | 1245 | 160   | 687 | 160 | 687 | 0 | 0 |
| 0100         | 0           | 0           |             | 0        |          | 1300 | 161   |     | 161 |     | 0 |   |
| 0115         | 0           | 0           |             | 0        |          | 1315 | 155   |     | 155 |     | 0 |   |
| 0130         | 2           | 2           |             | 0        |          | 1330 | 144   |     | 144 |     | 0 |   |
| 0145         | 3           | 3           | 5           | 0        | 0        | 1345 | 141   | 601 | 141 | 601 | 0 | 0 |
| 0200         | 5           | 5           |             | 0        |          | 1400 | 132   |     | 132 |     | 0 |   |
| 0215         | 0           | 0           |             | 0        |          | 1415 | 161   |     | 161 |     | 0 |   |
| 0230         | 1           | 1           |             | 0        |          | 1430 | 150   |     | 150 |     | 0 |   |
| 0245         | 1           | 1           | 7           | 0        | 0        | 1445 | 166   | 609 | 166 | 609 | 0 | 0 |
| 0300         | 3           | 3           |             | 0        |          | 1500 | 142   |     | 142 |     | 0 |   |
| 0315         | 4           | 4           |             | 0        |          | 1515 | 170   |     | 170 |     | 0 |   |
| 0330         | 4           | 4           |             | 0        |          | 1530 | 153   |     | 153 |     | 0 |   |
| 0345         | 4           | 4           | 15          | 0        | 0        | 1545 | 151   | 616 | 151 | 616 | 0 | 0 |
| 0400         | 5           | 5           |             | 0        |          | 1600 | 151   |     | 151 |     | 0 |   |
| 0415         | 4           | 4           |             | 0        |          | 1615 | 144   |     | 144 |     | 0 |   |
| 0430         | 10          | 10          |             | 0        |          | 1630 | 169   |     | 169 |     | 0 |   |
| 0445         | 12          | 12          | 31          | 0        | 0        | 1645 | 166   | 630 | 166 | 630 | 0 | 0 |
| 0500         | 7           | 7           |             | 0        |          | 1700 | 173   |     | 173 |     | 0 |   |
| 0515         | 15          | 15          |             | 0        |          | 1715 | 132   |     | 132 |     | 0 |   |
| 0530         | 25          | 25          |             | 0        |          | 1730 | 162   |     | 162 |     | 0 |   |
| 0545         | 34          | 34          | 81          | 0        | 0        | 1745 | 137   | 604 | 137 | 604 | 0 | 0 |
| 0600         | 28          | 28          |             | 0        |          | 1800 | 106   |     | 106 |     | 0 |   |
| 0615         | 37          | 37          |             | 0        |          | 1815 | 100   |     | 100 |     | 0 |   |
| 0630         | 57          | 57          |             | 0        |          | 1830 | 115   |     | 115 |     | 0 |   |
| 0645         | 54          | 54          | 176         | 0        | 0        | 1845 | 120   | 441 | 120 | 441 | 0 | 0 |
| 0700         | 47          | 47          |             | 0        |          | 1900 | 103   |     | 103 |     | 0 |   |
| 0715         | 61          | 61          |             | 0        |          | 1915 | 64    |     | 64  |     | 0 |   |
| 0730         | 87          | 87          |             | 0        |          | 1930 | 54    |     | 54  |     | 0 |   |
| 0745         | 84          | 84          | 279         | 0        | 0        | 1945 | 53    | 274 | 53  | 274 | 0 | 0 |
| 0800         | 67          | 67          |             | 0        |          | 2000 | 46    |     | 46  |     | 0 |   |
| 0815         | 75          | 75          |             | 0        |          | 2015 | 52    |     | 52  |     | 0 |   |
| 0830         | 93          | 93          |             | 0        |          | 2030 | 39    |     | 39  |     | 0 |   |
| 0845         | 88          | 88          | 323         | 0        | 0        | 2045 | 30    | 167 | 30  | 167 | 0 | 0 |
| 0900         | 75          | 75          |             | 0        |          | 2100 | 28    |     | 28  |     | 0 |   |
| 0915         | 91          | 91          |             | 0        |          | 2115 | 23    |     | 23  |     | 0 |   |
| 0930         | 81          | 81          |             | 0        |          | 2130 | 15    |     | 15  |     | 0 |   |
| 0945         | 103         | 103         | 350         | 0        | 0        | 2145 | 11    | 77  | 11  | 77  | 0 | 0 |
| 1000         | 102         | 102         |             | 0        |          | 2200 | 10    |     | 10  |     | 0 |   |
| 1015         | 111         | 111         |             | 0        |          | 2215 | 8     |     | 8   |     | 0 |   |
| 1030         | 115         | 115         |             | 0        |          | 2230 | 9     |     | 9   |     | 0 |   |
| 1045         | 128         | 128         | 456         | 0        | 0        | 2245 | 10    | 37  | 10  | 37  | 0 | 0 |
| 1100         | 111         | 111         |             | 0        |          | 2300 | 7     |     | 7   |     | 0 |   |
| 1115         | 132         | 132         |             | 0        |          | 2315 | 3     |     | 3   |     | 0 |   |
| 1130         | 134         | 134         |             | 0        |          | 2330 | 4     |     | 4   |     | 0 |   |
| 1145         | 149         | 149         | 526         | 0        | 0        | 2345 | 4     | 18  | 4   | 18  | 0 | 0 |
| <b>Total</b> | <b>7019</b> | <b>7019</b> | <b>7019</b> | <b>0</b> | <b>0</b> |      |       |     |     |     |   |   |

# Volume Report

**Job** 1486\_4\_TB\_ATR 2  
**Area** Portsmouth, NH  
**Location** Woodbury Ave SB, approx. 250' north of Durgin Lane



PO BOX 1723, Framingham, MA 01701  
 Office: 978-746-1259  
 DataRequest@BostonTrafficData.com  
 www.BostonTrafficData.com

**Wednesday, March 20, 2024**

| Time         | Total       | SB          |          |          | Time | Total | SB  |     |     |
|--------------|-------------|-------------|----------|----------|------|-------|-----|-----|-----|
| 0000         | 10          | 10          |          | 0        | 1200 | 231   | 231 |     | 0   |
| 0015         | 4           | 4           |          | 0        | 1215 | 236   | 236 |     | 0   |
| 0030         | 3           | 3           |          | 0        | 1230 | 214   | 214 |     | 0   |
| 0045         | 2           | 19          | 2        | 19       | 1245 | 215   | 896 | 215 | 896 |
| 0100         | 4           | 4           |          | 0        | 1300 | 186   | 186 |     | 0   |
| 0115         | 2           | 2           |          | 0        | 1315 | 168   | 168 |     | 0   |
| 0130         | 1           | 1           |          | 0        | 1330 | 206   | 206 |     | 0   |
| 0145         | 1           | 8           | 1        | 8        | 1345 | 181   | 741 | 181 | 741 |
| 0200         | 4           | 4           |          | 0        | 1400 | 167   | 167 |     | 0   |
| 0215         | 2           | 2           |          | 0        | 1415 | 157   | 157 |     | 0   |
| 0230         | 5           | 5           |          | 0        | 1430 | 186   | 186 |     | 0   |
| 0245         | 3           | 14          | 3        | 14       | 1445 | 182   | 692 | 182 | 692 |
| 0300         | 2           | 2           |          | 0        | 1500 | 172   | 172 |     | 0   |
| 0315         | 1           | 1           |          | 0        | 1515 | 174   | 174 |     | 0   |
| 0330         | 6           | 6           |          | 0        | 1530 | 182   | 182 |     | 0   |
| 0345         | 12          | 21          | 12       | 21       | 1545 | 184   | 712 | 184 | 712 |
| 0400         | 6           | 6           |          | 0        | 1600 | 185   | 185 |     | 0   |
| 0415         | 10          | 10          |          | 0        | 1615 | 185   | 185 |     | 0   |
| 0430         | 12          | 12          |          | 0        | 1630 | 167   | 167 |     | 0   |
| 0445         | 19          | 47          | 19       | 47       | 1645 | 191   | 728 | 191 | 728 |
| 0500         | 18          | 18          |          | 0        | 1700 | 174   | 174 |     | 0   |
| 0515         | 16          | 16          |          | 0        | 1715 | 205   | 205 |     | 0   |
| 0530         | 20          | 20          |          | 0        | 1730 | 162   | 162 |     | 0   |
| 0545         | 24          | 78          | 24       | 78       | 1745 | 151   | 692 | 151 | 692 |
| 0600         | 23          | 23          |          | 0        | 1800 | 151   | 151 |     | 0   |
| 0615         | 38          | 38          |          | 0        | 1815 | 139   | 139 |     | 0   |
| 0630         | 53          | 53          |          | 0        | 1830 | 107   | 107 |     | 0   |
| 0645         | 78          | 192         | 78       | 192      | 1845 | 114   | 511 | 114 | 511 |
| 0700         | 81          | 81          |          | 0        | 1900 | 132   | 132 |     | 0   |
| 0715         | 95          | 95          |          | 0        | 1915 | 100   | 100 |     | 0   |
| 0730         | 118         | 118         |          | 0        | 1930 | 114   | 114 |     | 0   |
| 0745         | 162         | 456         | 162      | 456      | 1945 | 74    | 420 | 74  | 420 |
| 0800         | 143         | 143         |          | 0        | 2000 | 74    | 74  |     | 0   |
| 0815         | 154         | 154         |          | 0        | 2015 | 69    | 69  |     | 0   |
| 0830         | 159         | 159         |          | 0        | 2030 | 35    | 35  |     | 0   |
| 0845         | 128         | 584         | 128      | 584      | 2045 | 35    | 213 | 35  | 213 |
| 0900         | 123         | 123         |          | 0        | 2100 | 39    | 39  |     | 0   |
| 0915         | 134         | 134         |          | 0        | 2115 | 41    | 41  |     | 0   |
| 0930         | 129         | 129         |          | 0        | 2130 | 20    | 20  |     | 0   |
| 0945         | 147         | 533         | 147      | 533      | 2145 | 27    | 127 | 27  | 127 |
| 1000         | 122         | 122         |          | 0        | 2200 | 25    | 25  |     | 0   |
| 1015         | 135         | 135         |          | 0        | 2215 | 15    | 15  |     | 0   |
| 1030         | 156         | 156         |          | 0        | 2230 | 13    | 13  |     | 0   |
| 1045         | 148         | 561         | 148      | 561      | 2245 | 16    | 69  | 16  | 69  |
| 1100         | 158         | 158         |          | 0        | 2300 | 11    | 11  |     | 0   |
| 1115         | 190         | 190         |          | 0        | 2315 | 9     | 9   |     | 0   |
| 1130         | 204         | 204         |          | 0        | 2330 | 15    | 15  |     | 0   |
| 1145         | 217         | 769         | 217      | 769      | 2345 | 5     | 40  | 5   | 40  |
| <b>Total</b> | <b>9123</b> | <b>9123</b> | <b>0</b> | <b>0</b> |      |       |     |     |     |

# Volume Report

**Job** 1486\_4\_TB\_ATR 2  
**Area** Portsmouth, NH  
**Location** Woodbury Ave SB, approx. 250' north of Durgin Lane



PO BOX 1723, Framingham, MA 01701  
 Office: 978-746-1259  
 DataRequest@BostonTrafficData.com  
 www.BostonTrafficData.com

**Thursday, March 21, 2024**

| Time         | Total       | SB          |          |          |          | Time         | Total       | SB          |          |          |          |
|--------------|-------------|-------------|----------|----------|----------|--------------|-------------|-------------|----------|----------|----------|
| 0000         | 8           | 8           |          |          | 0        | 1200         | 222         | 222         |          |          | 0        |
| 0015         | 0           | 0           |          |          | 0        | 1215         | 221         | 221         |          |          | 0        |
| 0030         | 3           | 3           |          |          | 0        | 1230         | 198         | 198         |          |          | 0        |
| 0045         | 4           | 4           | 15       |          | 0        | 1245         | 222         | 222         | 863      | 863      | 0        |
| 0100         | 3           | 3           |          |          | 0        | 1300         | 208         | 208         |          |          | 0        |
| 0115         | 2           | 2           |          |          | 0        | 1315         | 166         | 166         |          |          | 0        |
| 0130         | 3           | 3           |          |          | 0        | 1330         | 190         | 190         |          |          | 0        |
| 0145         | 3           | 3           | 11       |          | 0        | 1345         | 162         | 162         | 726      | 726      | 0        |
| 0200         | 8           | 8           |          |          | 0        | 1400         | 161         | 161         |          |          | 0        |
| 0215         | 2           | 2           |          |          | 0        | 1415         | 174         | 174         |          |          | 0        |
| 0230         | 4           | 4           |          |          | 0        | 1430         | 169         | 169         |          |          | 0        |
| 0245         | 6           | 6           | 20       |          | 0        | 1445         | 183         | 183         | 687      | 687      | 0        |
| 0300         | 1           | 1           |          |          | 0        | 1500         | 196         | 196         |          |          | 0        |
| 0315         | 4           | 4           |          |          | 0        | 1515         | 185         | 185         |          |          | 0        |
| 0330         | 6           | 6           |          |          | 0        | 1530         | 187         | 187         |          |          | 0        |
| 0345         | 6           | 6           | 17       |          | 0        | 1545         | 179         | 179         | 747      | 747      | 0        |
| 0400         | 11          | 11          |          |          | 0        | 1600         | 192         | 192         |          |          | 0        |
| 0415         | 12          | 12          |          |          | 0        | 1615         | 201         | 201         |          |          | 0        |
| 0430         | 22          | 22          |          |          | 0        | 1630         | 165         | 165         |          |          | 0        |
| 0445         | 11          | 11          | 56       |          | 0        | 1645         | 201         | 201         | 759      | 759      | 0        |
| 0500         | 15          | 15          |          |          | 0        | 1700         | 181         | 181         |          |          | 0        |
| 0515         | 16          | 16          |          |          | 0        | 1715         | 167         | 167         |          |          | 0        |
| 0530         | 22          | 22          |          |          | 0        | 1730         | 147         | 147         |          |          | 0        |
| 0545         | 44          | 44          | 97       |          | 0        | 1745         | 153         | 153         | 648      | 648      | 0        |
| 0600         | 20          | 20          |          |          | 0        | 1800         | 157         | 157         |          |          | 0        |
| 0615         | 43          | 43          |          |          | 0        | 1815         | 124         | 124         |          |          | 0        |
| 0630         | 52          | 52          |          |          | 0        | 1830         | 144         | 144         |          |          | 0        |
| 0645         | 49          | 49          | 164      |          | 0        | 1845         | 111         | 111         | 536      | 536      | 0        |
| 0700         | 96          | 96          |          |          | 0        | 1900         | 133         | 133         |          |          | 0        |
| 0715         | 98          | 98          |          |          | 0        | 1915         | 121         | 121         |          |          | 0        |
| 0730         | 121         | 121         |          |          | 0        | 1930         | 88          | 88          |          |          | 0        |
| 0745         | 145         | 145         | 460      |          | 0        | 1945         | 74          | 74          | 416      | 416      | 0        |
| 0800         | 140         | 140         |          |          | 0        | 2000         | 93          | 93          |          |          | 0        |
| 0815         | 176         | 176         |          |          | 0        | 2015         | 65          | 65          |          |          | 0        |
| 0830         | 146         | 146         |          |          | 0        | 2030         | 66          | 66          |          |          | 0        |
| 0845         | 137         | 137         | 599      |          | 0        | 2045         | 44          | 44          | 268      | 268      | 0        |
| 0900         | 113         | 113         |          |          | 0        | 2100         | 44          | 44          |          |          | 0        |
| 0915         | 125         | 125         |          |          | 0        | 2115         | 28          | 28          |          |          | 0        |
| 0930         | 136         | 136         |          |          | 0        | 2130         | 19          | 19          |          |          | 0        |
| 0945         | 137         | 137         | 511      |          | 0        | 2145         | 30          | 30          | 121      | 121      | 0        |
| 1000         | 136         | 136         |          |          | 0        | 2200         | 13          | 13          |          |          | 0        |
| 1015         | 132         | 132         |          |          | 0        | 2215         | 14          | 14          |          |          | 0        |
| 1030         | 131         | 131         |          |          | 0        | 2230         | 16          | 16          |          |          | 0        |
| 1045         | 164         | 164         | 563      |          | 0        | 2245         | 12          | 12          | 55       | 55       | 0        |
| 1100         | 175         | 175         |          |          | 0        | 2300         | 16          | 16          |          |          | 0        |
| 1115         | 188         | 188         |          |          | 0        | 2315         | 6           | 6           |          |          | 0        |
| 1130         | 210         | 210         |          |          | 0        | 2330         | 7           | 7           |          |          | 0        |
| 1145         | 170         | 170         | 743      |          | 0        | 2345         | 12          | 12          | 41       | 41       | 0        |
| <b>Total</b> | <b>9123</b> | <b>9123</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>Total</b> | <b>9123</b> | <b>9123</b> | <b>0</b> | <b>0</b> | <b>0</b> |



**APPENDIX B**  
NHDOT Traffic Data

Year 2019 Monthly Data


Group 4 Averages: Urban Highways

| Month        | ADT    | Adjustment<br>to Average | Adjustment<br>to Peak | GROUP | COUNTER  | TOWN          | LOCATION   |
|--------------|--------|--------------------------|-----------------------|-------|----------|---------------|--|
| January      | 11,431 | 1.12                     | 1.23                  | 04    | 02051003 | BOW           | NH 3A south of Robinson Rd                               |
| February     | 11,848 | 1.08                     | 1.18                  | 04    | 02089001 | CHICHESTER    | NH 28 (Suncook Valley Rd) north of Bear Hill Rd          |
| March        | 12,141 | 1.06                     | 1.15                  | 04    | 02091001 | CLAREMONT     | NH 12/103 east of Vermont SL                             |
| April        | 12,860 | 1.00                     | 1.09                  | 04    | 62099056 | CONCORD       | NH 106 (Sheep Davis Rd) at Loudon TL (north of Ashby Rd) |
| May          | 13,551 | 0.95                     | 1.03                  | 04    | 72099278 | CONCORD       | US 3 (Fisherville Rd) north of Sewalls Falls Rd          |
| June         | 13,785 | 0.93                     | 1.02                  | 04    | 02125001 | DOVER         | Dover Point Rd south of Thornwood Ln                     |
| July         | 13,942 | 0.92                     | 1.01                  | 04    | 02133021 | DURHAM        | US 4 east of NH 108                                      |
| August       | 14,016 | 0.92                     | 1.00                  | 04    | 82197076 | HAMPTON       | US 1 (Lafayette Rd) south of Ramp to NH 101              |
| September    | 13,379 | 0.96                     | 1.05                  | 04    | 02229022 | HUDSON*       | <i>Circumferential Hwy east of Nashua TL</i>             |
| October      | 13,339 | 0.96                     | 1.05                  | 04    | 02253025 | LEBANON       | NH 120 1 mile south of Hanover TL (south of Lahaye Dr)   |
| November     | 12,265 | 1.05                     | 1.14                  | 04    | 02255001 | LEE           | NH 125 (Calef Hwy) north of Pinkham Rd                   |
| December     | 11,496 | 1.12                     | 1.22                  | 04    | 02287001 | MARLBOROUGH   | NH 12 at Swanzey TL                                      |
|              |        |                          |                       | 04    | 02297001 | MERRIMACK     | US 3 (Daniel Webster Hwy) north of Hilton Dr             |
| Average ADT: | 12,838 |                          |                       | 04    | 02303001 | MILFORD*      | <i>NH 101A at Amherst TL (west of Overlook Dr)</i>       |
| Peak ADT:    | 14,016 |                          |                       | 04    | 02315051 | NASHUA*       | <i>NH 111 (Bridge / Ferry St) at Hudson TL</i>           |
|              |        |                          |                       | 04    | 02339001 | NEWPORT       | NH 10 1 mile south of Croydon TL (north of Corbin Rd)    |
|              |        |                          |                       | 04    | 02345001 | NORTH HAMPTON | US 1 (Lafayette Rd) north of North Rd                    |
|              |        |                          |                       | 04    | 62387052 | RINDGE*       | <i>US 202 at Jaffrey TL (north of County Rd)</i>         |
|              |        |                          |                       | 04    | 02445001 | TEMPLE        | NH 101 at Wilton TL (west of Old County Farm Rd)         |
|              |        |                          |                       | 04    | 02489001 | WINDHAM       | NH 28 at Derry TL (north of Northland Rd)                |

\* denotes counter that is not included in calculation

| Year | Total   |
|------|---------|
| 2009 | 1303948 |
| 2010 | 1312251 |
| 2011 | 1279824 |
| 2012 | 1284314 |
| 2013 | 1298171 |
| 2014 | 1320862 |
| 2015 | 1353486 |
| 2016 | 1385361 |
| 2017 | 1396932 |
| 2018 | 1408237 |
| 2019 | 1422176 |

|      |       |
|------|-------|
| CAGR | 0.87% |
| Exp  | 1.07% |
| Avg  | 0.97% |



**APPENDIX C**

Traffic Volume Adjustment Calculation

Traffic Volume Adjustment Check

| City of Portsmouth (GRIDS MART Turning Movement Counts) - South & Lafayette |                      |               |                 |               |                    |                      |                      |               |                 |               |                    |                      |                      | Comparison         |                        |                           |                     |         |                           |                        |
|---|----------------------|---------------|-----------------|---------------|--------------------|----------------------|----------------------|---------------|-----------------|---------------|--------------------|----------------------|----------------------|--------------------|------------------------|---------------------------|---------------------|---------|---------------------------|------------------------|
| Time Period   | 2019 Traffic Volumes |               |                 |               |                    |                      | 2024 Traffic Volumes |               |                 |               |                    |                      | Tues-Tues Comparison | Wed-Wed Comparison | Thurs-Thurs Comparison | Tues-Thurs Avg Comparison | Saturday Comparison | Average | Notes                     |                        |
|   | Tues 3/19/2019       | Wed 3/20/2019 | Thurs 3/21/2019 | Sat 3/23/2019 | Average (Tues-Wed) | Average (Tues-Thurs) | Tues 3/19/2024       | Wed 3/20/2024 | Thurs 3/21/2024 | Sat 3/23/2024 | Average (Tues-Wed) | Average (Tues-Thurs) |                      |                    |                        |                           |                     |         |                           |                        |
| Daily   | 15,492               | 15,909        | 15,884          | 13,216        | 15,701             | 15,125               | 14,450               | 14,338        | 14,179          | 8,951         | 12,980             | 12,980               | -6.7%                | -9.9%              | -10.7%                 | -14.2%                    | -32.3%              | --      | --                        |                        |
| Weekday AM Peak (8AM-9AM)   | 1,173                | 1,172         | 1,271           | --            | 1,173              | 1,205                | 1,279                | 1,222         | 1,157           | --            | 1,251              | 1,219                |                      |                    |                        | 1.2%                      | --                  | --      | No adjustment necessary   |                        |
| Weekday PM Peak (4PM-5PM)   | 1,255                | 1,268         | 1,317           | --            | 1,262              | 1,280                | 1,175                | 1,178         | 1,183           | --            | 1,177              | 1,179                | -6.4%                | -7.1%              | -10.2%                 | -7.9%                     | --                  | -9%     | Volumes adjusted up by 9% |                        |
| Weekday PM Peak (5PM-6PM)   | 1,287                | 1,290         | 1,265           | --            | 1,289              | 1,281                | 1,187                | 1,180         | 1,076           | --            | 1,184              | 1,148                |                      |                    |                        | -10.4%                    | --                  | --      |                           |                        |
| Sat Midday Peak (11AM-12PM)   | --                   | --            | --              | 1,102         | --                 | --                   | --                   | --            | --              | 765           | --                 | --                   | --                   | --                 | --                     | --                        | --                  | -30.6%  | -33%                      | Volumes adjusted up by |
| Sat Midday Peak (12PM-1PM)  | --                   | --            | --              | 1,161         | --                 | --                   | --                   | --            | --              | 743           | --                 | --                   | --                   | --                 | --                     | --                        | --                  | -36.0%  | 33%                       |                        |



# Turning Movement Counts

**Intersection** South & Lafayette

**Date** 3/19/2019

|              | Northbound  |             |            |          | Eastbound  |             |            | Southbound |             |            |          | Westbound  |             |             |
|--------------|-------------|-------------|------------|----------|------------|-------------|------------|------------|-------------|------------|----------|------------|-------------|-------------|
|              | R           | T           | L          | U        | R          | T           | L          | R          | T           | L          | U        | R          | T           | L           |
| 00:00        | 2           | 4           | 1          |          | 3          | 7           | 7          |            | 9           | 1          |          |            | 7           | 8           |
| 01:00        | 1           | 4           | 1          |          | 2          | 4           | 1          |            | 15          |            |          |            | 1           | 1           |
| 02:00        | 1           | 7           |            |          | 1          | 2           | 1          | 1          | 12          |            |          |            |             | 4           |
| 03:00        | 2           | 4           |            |          |            |             |            |            | 5           | 1          |          |            | 2           | 4           |
| 04:00        | 9           | 10          | 3          |          | 2          | 3           |            |            | 20          |            |          |            | 9           | 20          |
| 05:00        | 13          | 33          | 2          |          | 16         | 7           |            | 3          | 55          |            |          | 5          | 17          | 48          |
| 06:00        | 77          | 105         | 11         |          | 10         | 39          | 5          | 5          | 90          | 1          |          | 4          | 50          | 86          |
| 07:00        | 117         | 195         | 32         |          | 44         | 122         | 20         | 11         | 235         | 19         |          | 9          | 86          | 190         |
| 08:00        | 94          | 270         | 26         |          | 44         | 113         | 25         | 14         | 274         | 22         |          | 25         | 93          | 173         |
| 09:00        | 128         | 204         | 31         |          | 19         | 70          | 25         | 9          | 190         | 5          |          | 6          | 72          | 125         |
| 10:00        | 111         | 239         | 28         |          | 21         | 89          | 29         | 6          | 216         | 6          |          | 12         | 67          | 100         |
| 11:00        | 116         | 293         | 43         | 1        | 16         | 105         | 28         | 3          | 230         | 7          | 2        | 7          | 77          | 134         |
| 12:00        | 121         | 288         | 33         |          | 32         | 92          | 31         | 9          | 235         | 9          |          | 11         | 68          | 150         |
| 13:00        | 139         | 288         | 52         | 1        | 30         | 92          | 26         | 13         | 215         | 10         |          | 7          | 82          | 137         |
| 14:00        | 138         | 257         | 29         |          | 36         | 105         | 36         | 9          | 230         | 8          |          | 17         | 110         | 159         |
| 15:00        | 133         | 319         | 65         |          | 32         | 82          | 46         | 17         | 268         | 17         |          | 27         | 143         | 212         |
| 16:00        | 131         | 295         | 39         |          | 30         | 130         | 41         | 12         | 272         | 9          |          | 20         | 113         | 163         |
| 17:00        | 131         | 370         | 55         |          | 25         | 126         | 24         | 3          | 291         | 8          |          | 29         | 97          | 128         |
| 18:00        | 103         | 279         | 34         |          | 30         | 85          | 16         | 3          | 201         | 10         |          | 14         | 56          | 97          |
| 19:00        | 57          | 96          | 28         |          | 42         | 56          | 5          | 3          | 134         | 5          |          | 8          | 35          | 58          |
| 20:00        | 43          | 59          | 26         |          | 19         | 35          | 6          | 2          | 102         | 5          |          | 6          | 17          | 43          |
| 21:00        | 21          | 28          | 12         |          | 11         | 26          | 8          | 4          | 80          | 7          |          | 6          | 14          | 28          |
| 22:00        | 14          | 13          | 1          |          | 3          | 18          | 3          | 1          | 48          | 1          |          | 1          | 10          | 15          |
| 23:00        | 4           | 7           | 3          |          | 4          | 13          | 1          |            | 21          | 1          |          | 2          | 10          | 20          |
| <b>Total</b> | <b>1706</b> | <b>3667</b> | <b>555</b> | <b>2</b> | <b>472</b> | <b>1421</b> | <b>384</b> | <b>128</b> | <b>3448</b> | <b>152</b> | <b>2</b> | <b>216</b> | <b>1236</b> | <b>2103</b> |



# Turning Movement Counts

**Intersection** South & Lafayette

**Date** 3/20/2019

|              | Northbound  |             |            |          | Eastbound  |             |            | Southbound |             |            |          | Westbound  |             |             |          |
|--------------|-------------|-------------|------------|----------|------------|-------------|------------|------------|-------------|------------|----------|------------|-------------|-------------|----------|
|              | R           | T           | L          | U        | R          | T           | L          | R          | T           | L          | U        | R          | T           | L           | U        |
| 00:00        | 5           | 7           |            |          | 4          | 3           | 1          | 1          | 13          |            |          |            | 3           | 7           |          |
| 01:00        |             | 3           |            |          | 1          | 2           |            |            | 16          |            |          |            |             | 4           |          |
| 02:00        | 1           | 4           |            |          |            | 1           |            |            | 7           |            |          |            | 3           | 1           |          |
| 03:00        | 1           | 9           |            |          |            | 1           |            |            | 8           | 1          |          |            | 1           | 9           |          |
| 04:00        | 6           | 8           |            |          | 4          | 2           |            |            | 15          |            |          |            | 5           | 14          |          |
| 05:00        | 9           | 32          | 2          |          | 7          | 6           | 1          | 2          | 50          | 1          |          | 4          | 11          | 48          |          |
| 06:00        | 82          | 88          | 8          |          | 11         | 44          | 3          | 3          | 86          | 1          |          | 3          | 43          | 89          |          |
| 07:00        | 114         | 189         | 27         |          | 50         | 125         | 12         | 8          | 242         | 25         |          | 14         | 87          | 193         |          |
| 08:00        | 98          | 267         | 35         |          | 40         | 111         | 25         | 9          | 277         | 13         |          | 20         | 118         | 159         |          |
| 09:00        | 105         | 231         | 37         |          | 18         | 83          | 24         | 9          | 192         | 5          |          | 10         | 71          | 126         |          |
| 10:00        | 107         | 281         | 36         |          | 26         | 81          | 21         | 6          | 196         | 12         |          | 8          | 70          | 138         |          |
| 11:00        | 136         | 293         | 42         |          | 20         | 100         | 36         | 11         | 228         | 8          |          | 15         | 76          | 150         |          |
| 12:00        | 118         | 284         | 45         | 2        | 20         | 97          | 33         | 10         | 254         | 12         | 1        | 17         | 95          | 165         |          |
| 13:00        | 131         | 296         | 44         |          | 27         | 88          | 30         | 13         | 282         | 16         |          | 13         | 89          | 148         | 1        |
| 14:00        | 165         | 261         | 33         |          | 27         | 107         | 36         | 7          | 219         | 11         |          | 16         | 108         | 173         |          |
| 15:00        | 131         | 302         | 61         |          | 30         | 92          | 27         | 9          | 266         | 18         |          | 22         | 173         | 193         |          |
| 16:00        | 130         | 295         | 39         |          | 34         | 128         | 55         | 7          | 300         | 15         |          | 20         | 109         | 136         |          |
| 17:00        | 150         | 331         | 59         |          | 37         | 129         | 41         | 3          | 287         | 15         |          | 13         | 90          | 135         |          |
| 18:00        | 107         | 289         | 37         |          | 28         | 109         | 19         | 2          | 196         | 10         |          | 8          | 55          | 102         | 1        |
| 19:00        | 47          | 87          | 16         |          | 34         | 48          | 14         | 3          | 136         | 5          |          | 9          | 58          | 84          |          |
| 20:00        | 39          | 79          | 20         |          | 16         | 52          | 9          | 4          | 119         | 5          |          | 1          | 32          | 47          |          |
| 21:00        | 29          | 34          | 11         |          | 13         | 31          | 3          | 4          | 78          | 3          |          | 13         | 28          | 33          |          |
| 22:00        | 14          | 7           | 4          |          | 7          | 23          | 1          |            | 63          | 1          |          |            | 10          | 14          |          |
| 23:00        | 7           | 10          |            |          | 2          | 15          |            |            | 34          |            |          | 1          | 14          | 28          |          |
| <b>Total</b> | <b>1732</b> | <b>3687</b> | <b>556</b> | <b>2</b> | <b>456</b> | <b>1478</b> | <b>391</b> | <b>111</b> | <b>3564</b> | <b>177</b> | <b>1</b> | <b>207</b> | <b>1349</b> | <b>2196</b> | <b>2</b> |



# Turning Movement Counts

**Intersection** South & Lafayette

**Date** 3/21/2019

|              | Northbound  |             |            |          | Eastbound  |             |            | Southbound |             |            | Westbound  |             |             |          |
|--------------|-------------|-------------|------------|----------|------------|-------------|------------|------------|-------------|------------|------------|-------------|-------------|----------|
|              | R           | T           | L          | U        | R          | T           | L          | R          | T           | L          | R          | T           | L           | U        |
| 00:00        | 2           | 6           | 2          |          | 3          | 5           | 4          |            | 7           |            | 2          | 4           | 8           |          |
| 01:00        | 2           | 1           |            |          | 1          | 3           |            | 1          | 6           |            | 1          | 5           | 2           |          |
| 02:00        | 1           | 5           |            |          | 3          | 2           |            |            | 8           |            |            |             | 3           |          |
| 03:00        |             | 8           |            |          | 1          |             |            | 1          | 7           |            | 1          | 4           | 2           |          |
| 04:00        | 6           | 8           | 1          |          | 1          | 1           |            |            | 12          |            | 1          | 7           | 9           |          |
| 05:00        | 9           | 27          | 2          |          | 10         | 6           | 2          | 2          | 52          | 1          | 3          | 18          | 47          |          |
| 06:00        | 68          | 107         | 10         |          | 8          | 44          | 4          | 2          | 88          | 1          | 4          | 45          | 77          |          |
| 07:00        | 108         | 185         | 26         |          | 39         | 116         | 11         | 9          | 242         | 25         | 13         | 74          | 178         |          |
| 08:00        | 93          | 280         | 51         |          | 42         | 119         | 13         | 12         | 311         | 17         | 19         | 114         | 200         |          |
| 09:00        | 123         | 233         | 34         |          | 15         | 76          | 26         | 11         | 175         | 8          | 9          | 84          | 150         |          |
| 10:00        | 118         | 220         | 33         |          | 21         | 88          | 27         | 5          | 190         | 3          | 7          | 81          | 135         | 1        |
| 11:00        | 137         | 306         | 30         |          | 29         | 87          | 35         | 9          | 229         | 10         | 7          | 66          | 128         |          |
| 12:00        | 118         | 300         | 29         | 1        | 26         | 103         | 31         | 9          | 259         | 20         | 8          | 84          | 134         |          |
| 13:00        | 114         | 287         | 50         |          | 22         | 86          | 33         | 4          | 259         | 11         | 13         | 98          | 152         |          |
| 14:00        | 133         | 268         | 23         |          | 31         | 95          | 35         | 8          | 229         | 10         | 17         | 105         | 138         |          |
| 15:00        | 131         | 325         | 72         |          | 38         | 103         | 33         | 12         | 259         | 16         | 26         | 120         | 205         |          |
| 16:00        | 151         | 302         | 50         |          | 41         | 137         | 37         | 13         | 295         | 16         | 12         | 106         | 157         |          |
| 17:00        | 134         | 352         | 54         |          | 23         | 123         | 44         | 4          | 275         | 15         | 19         | 85          | 137         |          |
| 18:00        | 87          | 257         | 37         |          | 32         | 94          | 29         | 3          | 223         | 19         | 10         | 69          | 111         |          |
| 19:00        | 54          | 98          | 38         |          | 36         | 72          | 12         | 5          | 156         | 6          | 16         | 42          | 82          |          |
| 20:00        | 28          | 53          | 23         |          | 30         | 36          | 8          | 3          | 113         | 7          | 4          | 31          | 46          |          |
| 21:00        | 23          | 51          | 8          |          | 20         | 30          | 6          | 6          | 95          | 9          | 4          | 25          | 28          |          |
| 22:00        | 15          | 23          | 6          |          | 9          | 18          | 4          | 5          | 58          | 4          | 2          | 15          | 20          |          |
| 23:00        | 10          | 21          | 7          |          | 5          | 15          | 1          | 2          | 31          |            | 1          | 11          | 24          |          |
| <b>Total</b> | <b>1665</b> | <b>3723</b> | <b>586</b> | <b>1</b> | <b>486</b> | <b>1459</b> | <b>395</b> | <b>126</b> | <b>3579</b> | <b>198</b> | <b>199</b> | <b>1293</b> | <b>2173</b> | <b>1</b> |





# Turning Movement Counts

**Intersection** South & Lafayette

**Date** 3/23/2019

|              | Northbound  |             |            |          | Eastbound  |             |            | Southbound |             |            |          | Westbound  |            |             |
|--------------|-------------|-------------|------------|----------|------------|-------------|------------|------------|-------------|------------|----------|------------|------------|-------------|
|              | R           | T           | L          | U        | R          | T           | L          | R          | T           | L          | U        | R          | T          | L           |
| 00:00        | 7           | 18          |            |          | 4          | 15          | 1          | 3          | 37          | 1          |          | 1          | 13         | 16          |
| 01:00        | 3           | 12          | 2          |          | 2          | 9           | 1          | 1          | 42          |            |          | 2          | 1          | 6           |
| 02:00        | 7           | 9           |            |          | 1          | 2           | 1          |            | 14          |            |          | 2          | 3          | 2           |
| 03:00        | 3           | 5           |            |          | 1          | 1           |            |            | 9           |            |          |            | 4          | 7           |
| 04:00        | 5           | 6           | 2          |          | 3          | 1           |            | 1          | 6           |            |          | 1          | 4          | 9           |
| 05:00        | 3           | 8           | 4          |          | 3          | 4           |            |            | 18          |            |          | 2          | 8          | 12          |
| 06:00        | 41          | 36          | 4          |          | 5          | 20          | 1          |            | 34          | 1          |          | 1          | 18         | 30          |
| 07:00        | 43          | 91          | 6          |          | 8          | 23          | 4          | 2          | 91          | 1          |          | 1          | 33         | 86          |
| 08:00        | 53          | 173         | 23         |          | 15         | 46          | 6          | 2          | 158         | 1          |          | 7          | 32         | 92          |
| 09:00        | 96          | 246         | 16         |          | 12         | 49          | 16         | 5          | 191         | 6          |          | 7          | 74         | 130         |
| 10:00        | 99          | 279         | 29         | 1        | 28         | 66          | 25         | 7          | 220         | 9          |          | 9          | 54         | 127         |
| 11:00        | 112         | 311         | 37         |          | 41         | 75          | 35         | 2          | 244         | 12         |          | 12         | 71         | 150         |
| 12:00        | 103         | 347         | 34         |          | 22         | 114         | 28         | 11         | 256         | 14         | 1        | 15         | 75         | 141         |
| 13:00        | 113         | 329         | 34         |          | 14         | 91          | 35         | 8          | 217         | 14         | 1        | 10         | 59         | 125         |
| 14:00        | 131         | 324         | 27         |          | 20         | 127         | 33         | 5          | 255         | 16         |          | 12         | 80         | 150         |
| 15:00        | 120         | 301         | 29         |          | 27         | 91          | 30         | 8          | 212         | 13         |          | 8          | 60         | 112         |
| 16:00        | 83          | 289         | 24         |          | 30         | 93          | 24         | 7          | 229         | 9          |          | 6          | 74         | 115         |
| 17:00        | 77          | 258         | 28         |          | 23         | 92          | 31         | 6          | 184         | 12         |          | 10         | 76         | 115         |
| 18:00        | 71          | 238         | 24         |          | 15         | 66          | 14         | 8          | 177         | 7          |          | 13         | 49         | 105         |
| 19:00        | 40          | 123         | 12         |          | 30         | 30          | 7          | 4          | 146         | 11         |          | 3          | 35         | 80          |
| 20:00        | 45          | 55          | 12         |          | 19         | 35          | 6          | 7          | 111         | 10         |          | 6          | 26         | 39          |
| 21:00        | 32          | 50          | 6          |          | 10         | 34          | 3          | 3          | 117         | 7          |          | 3          | 42         | 57          |
| 22:00        | 19          | 28          | 4          |          | 10         | 21          | 3          | 6          | 86          | 3          |          | 3          | 19         | 45          |
| 23:00        | 13          | 28          | 4          |          | 4          | 15          | 2          | 2          | 46          | 1          |          |            | 15         | 40          |
| <b>Total</b> | <b>1319</b> | <b>3564</b> | <b>361</b> | <b>1</b> | <b>347</b> | <b>1120</b> | <b>306</b> | <b>98</b>  | <b>3100</b> | <b>148</b> | <b>2</b> | <b>134</b> | <b>925</b> | <b>1791</b> |



# Turning Movement Counts

**Intersection** South & Lafayette

**Date** 3/19/2024

|              | Northbound  |             |            |          | Eastbound  |             |            | Southbound |             |            | Westbound  |             |             |
|--------------|-------------|-------------|------------|----------|------------|-------------|------------|------------|-------------|------------|------------|-------------|-------------|
|              | R           | T           | L          | U        | R          | T           | L          | R          | T           | L          | R          | T           | L           |
| 00:00        | 1           | 10          | 1          |          | 1          | 4           | 2          |            | 6           | 1          |            | 3           | 3           |
| 01:00        | 1           | 5           |            |          | 3          | 4           | 2          | 1          | 10          |            |            | 3           | 4           |
| 02:00        | 1           | 2           |            |          | 1          | 2           | 1          |            | 5           |            |            | 2           |             |
| 03:00        |             | 8           |            |          |            |             |            |            | 2           |            |            | 5           | 3           |
| 04:00        | 1           | 16          | 1          |          | 1          | 4           |            | 2          | 12          | 1          |            | 2           | 9           |
| 05:00        | 4           | 63          | 2          |          | 16         | 16          | 1          |            | 32          | 4          |            | 20          | 36          |
| 06:00        | 59          | 81          | 12         |          | 7          | 66          | 6          | 4          | 68          | 2          | 2          | 37          | 59          |
| 07:00        | 95          | 158         | 7          | 1        | 28         | 129         | 9          | 7          | 124         | 9          | 8          | 88          | 179         |
| 08:00        | 121         | 237         | 45         |          | 49         | 177         | 8          | 16         | 258         | 48         | 24         | 123         | 173         |
| 09:00        | 101         | 228         | 25         |          | 25         | 97          | 13         | 8          | 186         | 5          | 7          | 78          | 134         |
| 10:00        | 107         | 221         | 33         | 1        | 31         | 93          | 6          | 10         | 156         | 7          | 14         | 80          | 136         |
| 11:00        | 110         | 237         | 31         |          | 21         | 92          | 10         | 10         | 180         | 11         | 6          | 86          | 129         |
| 12:00        | 127         | 268         | 49         |          | 33         | 106         | 21         | 6          | 197         | 6          | 14         | 85          | 159         |
| 13:00        | 112         | 203         | 30         |          | 25         | 90          | 16         | 13         | 174         | 10         | 9          | 82          | 142         |
| 14:00        | 93          | 228         | 33         |          | 35         | 114         | 21         | 7          | 211         | 10         | 18         | 85          | 181         |
| 15:00        | 109         | 286         | 54         |          | 35         | 125         | 20         | 12         | 262         | 18         | 23         | 163         | 193         |
| 16:00        | 120         | 269         | 36         |          | 42         | 117         | 12         | 10         | 256         | 10         | 10         | 130         | 163         |
| 17:00        | 121         | 313         | 63         |          | 21         | 122         | 20         | 6          | 266         | 25         | 17         | 93          | 120         |
| 18:00        | 103         | 218         | 30         |          | 28         | 79          | 14         | 6          | 168         | 7          | 7          | 69          | 101         |
| 19:00        | 38          | 145         | 10         |          | 19         | 61          | 14         | 2          | 123         | 8          | 7          | 32          | 44          |
| 20:00        | 31          | 106         | 19         |          | 18         | 39          | 8          | 1          | 82          | 4          | 5          | 18          | 43          |
| 21:00        | 22          | 66          | 4          |          | 10         | 23          | 4          | 1          | 56          | 2          | 1          | 11          | 27          |
| 22:00        | 11          | 38          | 4          |          | 25         | 17          | 4          | 1          | 31          | 1          |            | 9           | 20          |
| 23:00        | 9           | 27          |            |          | 2          | 8           |            |            | 22          |            |            | 9           | 14          |
| <b>Total</b> | <b>1497</b> | <b>3433</b> | <b>489</b> | <b>2</b> | <b>476</b> | <b>1585</b> | <b>212</b> | <b>123</b> | <b>2887</b> | <b>189</b> | <b>172</b> | <b>1313</b> | <b>2072</b> |



# Turning Movement Counts

**Intersection** South & Lafayette

**Date** 3/20/2024

|              | Northbound  |             |            |          | Eastbound  |             |            | Southbound |             |            | Westbound  |             |             |
|--------------|-------------|-------------|------------|----------|------------|-------------|------------|------------|-------------|------------|------------|-------------|-------------|
|              | R           | T           | L          | U        | R          | T           | L          | R          | T           | L          | R          | T           | L           |
| 00:00        |             | 14          |            |          | 2          | 4           | 1          |            | 8           | 1          |            | 5           | 7           |
| 01:00        | 2           | 1           | 1          |          | 1          | 3           |            |            | 6           |            |            | 1           | 5           |
| 02:00        | 1           | 4           |            |          |            | 4           | 1          | 1          | 1           |            | 1          | 1           | 2           |
| 03:00        | 1           | 9           |            |          |            | 1           |            |            | 2           |            | 1          | 3           | 3           |
| 04:00        |             | 17          |            |          | 1          | 3           |            |            | 10          | 1          | 1          | 4           | 11          |
| 05:00        | 7           | 49          | 1          |          | 11         | 12          | 2          | 1          | 36          | 2          | 1          | 12          | 27          |
| 06:00        | 58          | 83          | 11         |          | 8          | 76          | 2          | 1          | 69          | 3          | 1          | 32          | 62          |
| 07:00        | 93          | 142         | 13         | 1        | 28         | 138         | 9          | 10         | 128         | 6          | 6          | 88          | 164         |
| 08:00        | 114         | 263         | 54         |          | 55         | 159         | 13         | 6          | 231         | 39         | 19         | 106         | 163         |
| 09:00        | 93          | 219         | 39         |          | 28         | 103         | 7          | 8          | 178         | 12         | 8          | 56          | 167         |
| 10:00        | 100         | 221         | 27         |          | 24         | 100         | 14         | 8          | 170         | 5          | 14         | 72          | 126         |
| 11:00        | 108         | 227         | 33         |          | 19         | 101         | 11         | 8          | 180         | 9          | 12         | 75          | 140         |
| 12:00        | 130         | 275         | 48         |          | 32         | 93          | 15         | 10         | 224         | 13         | 13         | 84          | 161         |
| 13:00        | 112         | 250         | 28         |          | 25         | 97          | 11         | 13         | 194         | 9          | 13         | 93          | 136         |
| 14:00        | 106         | 224         | 23         |          | 31         | 103         | 13         | 4          | 201         | 11         | 15         | 91          | 150         |
| 15:00        | 112         | 281         | 69         |          | 50         | 132         | 15         | 7          | 228         | 13         | 20         | 149         | 200         |
| 16:00        | 113         | 247         | 53         |          | 27         | 134         | 22         | 6          | 252         | 18         | 22         | 123         | 161         |
| 17:00        | 102         | 297         | 49         |          | 33         | 139         | 20         | 4          | 247         | 15         | 18         | 121         | 135         |
| 18:00        | 83          | 242         | 36         |          | 22         | 84          | 19         | 2          | 166         | 5          | 13         | 37          | 92          |
| 19:00        | 37          | 151         | 10         |          | 29         | 44          | 14         | 6          | 106         | 11         | 9          | 39          | 58          |
| 20:00        | 41          | 107         | 12         |          | 18         | 44          | 5          | 5          | 68          | 2          | 5          | 22          | 43          |
| 21:00        | 13          | 64          | 9          |          | 12         | 21          | 6          | 3          | 67          | 1          | 5          | 24          | 13          |
| 22:00        | 8           | 37          | 7          |          | 17         | 16          | 4          | 2          | 33          |            |            | 11          | 13          |
| 23:00        | 5           | 17          | 3          |          | 4          | 17          | 6          | 1          | 15          | 1          |            | 8           | 20          |
| <b>Total</b> | <b>1439</b> | <b>3441</b> | <b>526</b> | <b>1</b> | <b>477</b> | <b>1628</b> | <b>210</b> | <b>106</b> | <b>2820</b> | <b>177</b> | <b>197</b> | <b>1257</b> | <b>2059</b> |



# Turning Movement Counts

**Intersection** South & Lafayette

**Date** 3/21/2024

|              | Northbound  |             |            |          | Eastbound  |             |            |          | Southbound |             |            |          | Westbound  |             |             |
|--------------|-------------|-------------|------------|----------|------------|-------------|------------|----------|------------|-------------|------------|----------|------------|-------------|-------------|
|              | R           | T           | L          | U        | R          | T           | L          | U        | R          | T           | L          | U        | R          | T           | L           |
| 00:00        | 3           | 16          |            |          | 2          | 5           |            |          |            | 4           |            |          | 1          | 2           | 5           |
| 01:00        |             |             |            |          |            | 1           |            |          |            | 7           |            |          |            | 1           | 4           |
| 02:00        | 2           | 5           |            |          |            | 2           |            |          |            | 5           | 1          |          |            |             | 1           |
| 03:00        |             | 7           |            |          | 1          | 1           |            |          | 1          | 3           |            |          | 1          | 2           | 5           |
| 04:00        |             | 21          | 1          |          |            | 1           | 1          |          |            | 7           | 1          |          | 2          | 2           | 9           |
| 05:00        | 6           | 46          | 1          |          | 6          | 18          | 1          |          | 1          | 28          | 4          |          |            | 12          | 36          |
| 06:00        | 48          | 79          | 9          |          | 10         | 78          | 6          |          | 3          | 62          | 3          |          | 1          | 38          | 57          |
| 07:00        | 89          | 150         | 4          |          | 26         | 116         | 6          |          | 6          | 141         | 9          |          | 6          | 80          | 138         |
| 08:00        | 127         | 236         | 51         |          | 45         | 156         | 12         |          | 10         | 217         | 22         |          | 21         | 105         | 155         |
| 09:00        | 104         | 188         | 21         |          | 29         | 96          | 16         |          | 7          | 152         | 10         |          | 13         | 72          | 107         |
| 10:00        | 91          | 203         | 22         |          | 28         | 79          | 13         | 1        | 4          | 168         | 10         |          | 8          | 75          | 130         |
| 11:00        | 113         | 237         | 35         |          | 31         | 80          | 12         |          | 11         | 177         | 13         |          | 16         | 94          | 102         |
| 12:00        | 111         | 243         | 36         |          | 20         | 100         | 32         |          | 11         | 206         | 15         |          | 21         | 71          | 136         |
| 13:00        | 97          | 219         | 36         |          | 21         | 101         | 22         |          | 9          | 242         | 5          | 1        | 13         | 77          | 134         |
| 14:00        | 106         | 221         | 29         |          | 28         | 118         | 15         |          | 6          | 215         | 11         | 1        | 11         | 113         | 164         |
| 15:00        | 113         | 263         | 63         |          | 42         | 129         | 21         |          | 6          | 249         | 18         |          | 24         | 164         | 192         |
| 16:00        | 125         | 258         | 54         |          | 36         | 123         | 20         |          | 4          | 228         | 12         |          | 14         | 128         | 181         |
| 17:00        | 108         | 257         | 44         | 1        | 31         | 140         | 8          |          | 4          | 241         | 8          |          | 17         | 86          | 131         |
| 18:00        | 116         | 210         | 34         |          | 25         | 95          | 12         |          | 3          | 177         | 10         |          | 12         | 63          | 103         |
| 19:00        | 43          | 189         | 18         |          | 25         | 63          | 8          |          | 4          | 126         | 12         |          | 8          | 49          | 57          |
| 20:00        | 31          | 129         | 10         |          | 17         | 41          | 9          |          | 2          | 83          | 7          |          | 5          | 23          | 58          |
| 21:00        | 22          | 86          | 4          |          | 10         | 28          | 7          |          | 2          | 75          | 8          |          | 1          | 18          | 27          |
| 22:00        | 8           | 40          | 5          |          | 24         | 21          | 3          |          | 2          | 44          | 1          |          |            | 11          | 15          |
| 23:00        | 5           | 23          |            |          | 2          | 9           | 2          |          | 2          | 20          | 2          |          |            | 11          | 22          |
| <b>Total</b> | <b>1468</b> | <b>3326</b> | <b>477</b> | <b>1</b> | <b>459</b> | <b>1601</b> | <b>226</b> | <b>1</b> | <b>98</b>  | <b>2877</b> | <b>182</b> | <b>2</b> | <b>195</b> | <b>1297</b> | <b>1969</b> |



# Turning Movement Counts

**Intersection** South & Lafayette

**Date** 3/23/2024

|              | Northbound |             |            |          | Eastbound  |            |            | Southbound |             |            | Westbound  |            |             |
|--------------|------------|-------------|------------|----------|------------|------------|------------|------------|-------------|------------|------------|------------|-------------|
|              | R          | T           | L          | U        | R          | T          | L          | R          | T           | L          | R          | T          | L           |
| 00:00        | 5          | 21          |            |          | 4          | 8          | 1          | 1          | 21          |            |            | 7          | 11          |
| 01:00        | 2          | 11          |            |          | 3          | 1          | 1          |            | 28          |            |            | 3          | 2           |
| 02:00        | 2          | 12          |            |          | 2          | 8          |            | 1          | 10          | 2          | 1          | 3          | 2           |
| 03:00        | 2          | 5           |            |          |            |            | 1          |            | 6           | 1          |            | 3          | 6           |
| 04:00        | 1          | 5           |            |          | 1          | 1          |            |            | 3           |            | 1          | 2          | 2           |
| 05:00        | 6          | 14          | 10         |          | 6          | 4          | 2          |            | 14          |            |            | 4          | 8           |
| 06:00        | 24         | 33          | 2          |          | 2          | 10         | 1          |            | 24          | 2          | 3          | 9          | 14          |
| 07:00        | 26         | 60          | 2          |          | 4          | 15         | 2          | 3          | 53          | 2          | 4          | 30         | 45          |
| 08:00        | 32         | 100         | 7          |          | 21         | 24         | 4          | 3          | 98          | 1          | 3          | 25         | 62          |
| 09:00        | 35         | 147         | 13         |          | 16         | 36         | 7          | 3          | 109         | 4          | 7          | 35         | 90          |
| 10:00        | 54         | 178         | 19         |          | 25         | 50         | 4          | 6          | 142         | 9          | 11         | 55         | 101         |
| 11:00        | 71         | 222         | 22         | 3        | 28         | 70         | 15         | 4          | 163         | 10         | 8          | 57         | 92          |
| 12:00        | 70         | 210         | 26         | 1        | 22         | 81         | 11         | 7          | 150         | 6          | 9          | 38         | 112         |
| 13:00        | 68         | 215         | 25         |          | 17         | 64         | 9          | 5          | 158         | 8          | 14         | 45         | 82          |
| 14:00        | 80         | 207         | 19         | 1        | 19         | 88         | 16         | 4          | 128         | 5          | 16         | 59         | 101         |
| 15:00        | 78         | 176         | 16         |          | 10         | 69         | 11         | 4          | 134         | 12         | 11         | 57         | 130         |
| 16:00        | 71         | 185         | 24         |          | 19         | 52         | 9          | 2          | 145         | 10         | 5          | 40         | 81          |
| 17:00        | 71         | 163         | 21         |          | 16         | 63         | 11         | 6          | 181         | 7          | 11         | 40         | 73          |
| 18:00        | 69         | 157         | 20         |          | 10         | 58         | 6          | 1          | 96          | 8          | 7          | 40         | 53          |
| 19:00        | 17         | 124         | 10         |          | 16         | 31         | 5          | 2          | 86          | 7          | 3          | 37         | 49          |
| 20:00        | 11         | 93          | 14         |          | 10         | 21         | 6          | 1          | 75          | 6          | 5          | 28         | 25          |
| 21:00        | 9          | 59          | 4          |          | 7          | 19         | 2          | 2          | 56          | 2          | 1          | 27         | 43          |
| 22:00        | 9          | 57          | 4          |          | 21         | 20         | 2          | 1          | 55          | 4          | 3          | 15         | 25          |
| 23:00        | 3          | 33          | 2          |          | 3          | 10         | 3          |            | 32          |            | 3          | 17         | 29          |
| <b>Total</b> | <b>816</b> | <b>2487</b> | <b>260</b> | <b>5</b> | <b>282</b> | <b>803</b> | <b>129</b> | <b>56</b>  | <b>1967</b> | <b>106</b> | <b>126</b> | <b>676</b> | <b>1238</b> |

**APPENDIX D**  
Capacity Analysis Methodology

## CAPACITY ANALYSIS METHODOLOGY

A primary result of capacity analysis is the assignment of levels of service to traffic facilities under various traffic flow conditions. The capacity analysis methodology is based on the concepts and procedures in the *Highway Capacity Manual* (HCM).<sup>1</sup> The concept of level of service (LOS) is defined as a qualitative measure describing operational conditions within a traffic stream and their perception by motorists and/or passengers. A level-of-service definition provides an index to quality of traffic flow in terms of such factors as speed, travel time, freedom to maneuver, traffic interruptions, comfort, convenience, and safety.

Six levels of service are defined for each type of facility. They are given letter designations from A to F, with LOS A representing the best operating conditions and LOS F the worst. Since the level of service of a traffic facility is a function of the traffic flows placed upon it, such a facility may operate at a wide range of levels of service, depending on the time of day, day of week, or period of year. A description of the operating condition under each level of service is provided below:

- *LOS A* describes conditions with little to no delay to motorists.
- *LOS B* represents a desirable level with relatively low delay to motorists.
- *LOS C* describes conditions with average delays to motorists.
- *LOS D* describes operations where the influence of congestion becomes more noticeable. Delays are still within an acceptable range.
- *LOS E* represents operating conditions with high delay values. This level is considered by many agencies to be the limit of acceptable delay.
- *LOS F* is considered to be unacceptable to most drivers with high delay values that often occur, when arrival flow rates exceed the capacity of the intersection.

### Signalized Intersections

Levels of service for signalized intersections are also calculated using the operational analysis methodology of the HCM. The methodology for signalized intersections assesses the effects of signal type, timing, phasing, and progression; vehicle mix; and geometrics on average *control* delay. Control delay is used to establish the operating characteristics for an intersection or an approach to an intersection. Volume-to-capacity (v/c) ratios are also used to help signify the utilization of a lane group's capacity at an intersection. A v/c ratio of  $\geq 1.00$  represents conditions when the traffic signal cycle capacity is fully utilized and indicates a capacity failure. The level-of-service criteria for signalized intersections are shown in Table A-1.

---

<sup>1</sup>*Highway Capacity Manual, 6<sup>TH</sup> Edition: A Guide for Multimodal Mobility Analysis*. Washington, D.C.: Transportation Research Board, 2016.

## Unsignalized Intersections

Levels of service for unsignalized intersections are calculated using the operational analysis methodology of the HCM. The procedure accounts for lane configuration on both the minor and major street approaches, conflicting traffic stream volumes, and the type of intersection control (STOP, YIELD, or all-way STOP control). The definition of level of service for unsignalized intersections is a function of average *control* delay. Control delay at an unsignalized intersection is defined as the total elapsed time from when a vehicle stops at the end of the queue until the vehicle departs from the stop line. This time includes the time required for the vehicle to travel from the last-in-queue position to the first-in-queue position.

Volume-to-capacity (v/c) ratios are also used to help signify the utilization of a movement's capacity at an intersection. A v/c ratio of  $\geq 1.00$  represents conditions when the movement is fully utilized and indicates a capacity failure. The capacity of the movements is based on the distribution of gaps in the major street traffic stream, the selection of gaps to complete the desired movement, and the follow-up headways for each driver in the queue. When an unsignalized intersection is located within 0.25 miles of a signalized intersection, traffic flows may not be random and some platoon structure may exist, thereby affecting the minor street operations. The level-of-service criteria for unsignalized intersections are shown in Table A-1.

**TABLE A-1**  
Level-of-Service Criteria for Intersections

| Level of Service | Signalized Intersection Criteria            | Unsignalized Intersection Criteria          | V/C Ratio >1.00 <sup>a</sup> |
|------------------|---|---|------------------------------|
|                  | Average Control Delay (Seconds per Vehicle) | Average Control Delay (Seconds per Vehicle) |                              |
| A                | $\leq 10$                                   | $\leq 10$                                   | F                            |
| B                | >10 and $\leq 20$                           | >10 and $\leq 15$                           | F                            |
| C                | >20 and $\leq 35$                           | >15 and $\leq 25$                           | F                            |
| D                | >35 and $\leq 55$                           | >25 and $\leq 35$                           | F                            |
| E                | >55 and $\leq 80$                           | >35 and $\leq 50$                           | F                            |
| F                | >80   | >50   | F                            |

Note: <sup>a</sup>For approach-based and intersection-wide assessments, LOS is defined solely by control delay.













Source: *Highway Capacity Manual, 6<sup>th</sup> Edition: A Guide for Multimodal Mobility Analysis*. Washington, D.C.: Transportation Research Board, 2016. Exhibit 19-8, Pg. 19-16.

For signalized intersections, this delay criterion may be applied in assigning level-of-service designations to individual lane groups, to individual intersection approaches, or to the entire intersection. For unsignalized intersections, this delay criterion may be applied in assigning level-of-service designations to individual lane groups on the minor street approaches or to the left turns from the major street approaches.



**APPENDIX E**  
Capacity Analysis Worksheets

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2024 Existing AM Peak Weekday AM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↘   | ↗   | ↗↗  |
| Traffic Volume (vph)              | 0   | 190   | 85  | 88  | 812   | 0   | 0  | 0   | 0   | 400   | 0   | 670   |
| Future Volume (vph)               | 0   | 190   | 85  | 88  | 812   | 0   | 0  | 0   | 0   | 400   | 0   | 670   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 5923  | 1516  | 3173  | 3388  |   |  |   |   | 1698  | 1698  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 5923  | 1516  | 3173  | 3388  |   |  |   |   | 1698  | 1698  | 2814  |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.87  | 0.87  | 0.87  | 0.90   | 0.90  | 0.90  | 0.86  | 0.86  | 0.86  |
| Adj. Flow (vph)                   | 0   | 204   | 91  | 101   | 933   | 0   | 0  | 0   | 0   | 465   | 0   | 779   |
| RTOR Reduction (vph)              | 0   | 0   | 66  | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 207   |
| Lane Group Flow (vph)             | 0   | 204   | 25  | 101   | 933   | 0   | 0  | 0   | 0   | 232   | 233   | 572   |
| Heavy Vehicles (%)                | 3%  | 3%  | 3%  | 3%  | 3%  | 3%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 26.3  | 26.3  | 24.6  | 56.9  |   |  |   |   | 25.1  | 25.1  | 25.1  |
| Effective Green, g (s)            |   | 26.3  | 26.3  | 24.6  | 56.9  |   |  |   |   | 25.1  | 25.1  | 25.1  |
| Actuated g/C Ratio                |   | 0.28  | 0.28  | 0.26  | 0.61  |   |  |   |   | 0.27  | 0.27  | 0.27  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 1657  | 424   | 830   | 2050  |   |  |   |   | 453   | 453   | 751   |
| v/s Ratio Prot                    |   | 0.03  | 0.02  | 0.03  | c0.28   |   |  |   |   | 0.14  | 0.14  | c0.20   |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.12  | 0.06  | 0.12  | 0.46  |   |  |   |   | 0.51  | 0.51  | 0.76  |
| Uniform Delay, d1                 |   | 25.2  | 24.8  | 26.5  | 10.1  |   |  |   |   | 29.3  | 29.3  | 31.7  |
| Progression Factor                |   | 1.00  | 1.00  | 0.88  | 1.63  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.1   | 0.1   | 0.1   | 0.3   |   |  |   |   | 1.9   | 2.0   | 5.4   |
| Delay (s)                         |   | 25.3  | 24.9  | 23.4  | 16.7  |   |  |   |   | 31.2  | 31.2  | 37.1  |
| Level of Service                  |   | C   | C   | C   | B   |   |  |   |   | C   | C   | D   |
| Approach Delay (s)                |   | 25.2  |   |   | 17.4  |   |  | 0.0   |   |   | 34.9  |   |
| Approach LOS                      |   | C   |   |   | B   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 26.7  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.59  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 94.0  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 55.9%   |   |   | ICU Level of Service  |  |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |





















c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2024 Existing AM Peak Weekday AM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL  | WBT   | WBR  | NBL                       | NBT  | NBR  | SBL  | SBT  | SBR  |
|-----------------------------------|-------|-------|-------|------|-------|------|---------------------------|------|------|------|------|------|
| Lane Configurations               |       |       |       |      |       |      |                           |      |      |      |      |      |
| Traffic Volume (vph)              | 75    | 515   | 0     | 0    | 255   | 43   | 645                       | 0    | 255  | 0    | 0    | 0    |
| Future Volume (vph)               | 75    | 515   | 0     | 0    | 255   | 43   | 645                       | 0    | 255  | 0    | 0    | 0    |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900 | 1900  | 1900 | 1900                      | 1900 | 1900 | 1900 | 1900 | 1900 |
| Lane Width                        | 10    | 11    | 12    | 12   | 12    | 12   | 12                        | 12   | 12   | 12   | 12   | 12   |
| Total Lost time (s)               | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Lane Util. Factor                 | 0.97  | 0.95  |       |      | 0.91  |      | 0.97                      | 0.95 | 0.95 |      |      |      |
| Frt                               | 1.00  | 1.00  |       |      | 0.98  |      | 1.00                      | 0.85 | 0.85 |      |      |      |
| Flt Protected                     | 0.95  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (prot)                 | 3236  | 3455  |       |      | 4834  |      | 3400                      | 1490 | 1490 |      |      |      |
| Flt Permitted                     | 0.54  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (perm)                 | 1847  | 3455  |       |      | 4834  |      | 3400                      | 1490 | 1490 |      |      |      |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.89 | 0.89  | 0.89 | 0.91                      | 0.91 | 0.91 | 0.90 | 0.90 | 0.90 |
| Adj. Flow (vph)                   | 81    | 554   | 0     | 0    | 287   | 48   | 709                       | 0    | 280  | 0    | 0    | 0    |
| RTOR Reduction (vph)              | 0     | 0     | 0     | 0    | 20    | 0    | 0                         | 103  | 103  | 0    | 0    | 0    |
| Lane Group Flow (vph)             | 81    | 554   | 0     | 0    | 315   | 0    | 709                       | 37   | 37   | 0    | 0    | 0    |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 5%   | 5%    | 5%   | 3%                        | 3%   | 3%   | 0%   | 0%   | 0%   |
| Turn Type                         | pm+pt | NA    |       |      | NA    |      | Split                     | NA   | Prot |      |      |      |
| Protected Phases                  | 1     | 6     |       |      | 2     |      | 3                         | 3    | 3    |      |      |      |
| Permitted Phases                  | 6     |       |       |      |       |      |                           |      |      |      |      |      |
| Actuated Green, G (s)             | 39.8  | 26.3  |       |      | 37.4  |      | 25.1                      | 25.1 | 25.1 |      |      |      |
| Effective Green, g (s)            | 39.8  | 26.3  |       |      | 37.4  |      | 25.1                      | 25.1 | 25.1 |      |      |      |
| Actuated g/C Ratio                | 0.42  | 0.28  |       |      | 0.40  |      | 0.27                      | 0.27 | 0.27 |      |      |      |
| Clearance Time (s)                | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Vehicle Extension (s)             | 4.0   | 5.0   |       |      | 5.0   |      | 5.0                       | 5.0  | 5.0  |      |      |      |
| Lane Grp Cap (vph)                | 981   | 966   |       |      | 1923  |      | 907                       | 397  | 397  |      |      |      |
| v/s Ratio Prot                    | c0.01 | c0.16 |       |      | c0.07 |      | c0.21                     | 0.03 | 0.03 |      |      |      |
| v/s Ratio Perm                    | 0.02  |       |       |      |       |      |                           |      |      |      |      |      |
| v/c Ratio                         | 0.08  | 0.57  |       |      | 0.16  |      | 0.78                      | 0.09 | 0.09 |      |      |      |
| Uniform Delay, d1                 | 16.0  | 29.0  |       |      | 18.2  |      | 31.9                      | 25.9 | 25.9 |      |      |      |
| Progression Factor                | 1.31  | 1.29  |       |      | 1.00  |      | 1.00                      | 1.00 | 1.00 |      |      |      |
| Incremental Delay, d2             | 0.0   | 1.2   |       |      | 0.1   |      | 5.1                       | 0.2  | 0.2  |      |      |      |
| Delay (s)                         | 21.0  | 38.7  |       |      | 18.3  |      | 37.0                      | 26.1 | 26.1 |      |      |      |
| Level of Service                  | C     | D     |       |      | B     |      | D                         | C    | C    |      |      |      |
| Approach Delay (s)                |       | 36.4  |       |      | 18.3  |      |                           | 34.0 |      |      | 0.0  |      |
| Approach LOS                      |       | D     |       |      | B     |      |                           | C    |      |      | A    |      |
| <b>Intersection Summary</b>       |       |       |       |      |       |      |                           |      |      |      |      |      |
| HCM 2000 Control Delay            |       |       | 32.1  |      |       |      | HCM 2000 Level of Service |      |      | C    |      |      |
| HCM 2000 Volume to Capacity ratio |       |       | 0.49  |      |       |      |                           |      |      |      |      |      |
| Actuated Cycle Length (s)         |       |       | 94.0  |      |       |      | Sum of lost time (s)      |      |      | 18.0 |      |      |
| Intersection Capacity Utilization |       |       | 55.9% |      |       |      | ICU Level of Service      |      |      | B    |      |      |
| Analysis Period (min)             |       |       | 15    |      |       |      |                           |      |      |      |      |      |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
 2024 Existing AM Peak Weekday AM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |  |   |  |   |  |  |   |  |  |  |
| Traffic Volume (vph)              | 90  | 37  | 425   | 26  | 13  | 6   | 185  | 170   | 18  | 35  | 280   | 8   |
| Future Volume (vph)               | 90  | 37  | 425   | 26  | 13  | 6   | 185  | 170   | 18  | 35  | 280   | 8   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frt                               |   | 1.00  | 0.85  |   | 0.98  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 |   | 1706  | 1656  |   | 1605  |   | 3400   | 3455  |   | 1678  | 3355  | 1501  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 |   | 1706  | 1656  |   | 1605  |   | 3400   | 3455  |   | 1678  | 3355  | 1501  |
| Peak-hour factor, PHF             | 0.91  | 0.91  | 0.91  | 0.89  | 0.89  | 0.89  | 0.84   | 0.84  | 0.84  | 0.89  | 0.89  | 0.89  |
| Adj. Flow (vph)                   | 99  | 41  | 467   | 29  | 15  | 7   | 220  | 202   | 21  | 39  | 315   | 9   |
| RTOR Reduction (vph)              | 0   | 0   | 337   | 0   | 6   | 0   | 0  | 4   | 0   | 0   | 0   | 5   |
| Lane Group Flow (vph)             | 0   | 140   | 130   | 0   | 45  | 0   | 220  | 219   | 0   | 39  | 315   | 4   |
| Heavy Vehicles (%)                | 4%  | 4%  | 4%  | 13%   | 13%   | 13%   | 3%   | 3%  | 3%  | 4%  | 4%  | 4%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 9.0   | 20.1  |   | 4.8   |   | 11.1   | 26.6  |   | 2.6   | 17.6  | 32.6  |
| Effective Green, g (s)            |   | 9.0   | 20.1  |   | 4.8   |   | 11.1   | 26.6  |   | 2.6   | 17.6  | 32.6  |
| Actuated g/C Ratio                |   | 0.12  | 0.28  |   | 0.07  |   | 0.15   | 0.37  |   | 0.04  | 0.24  | 0.45  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                |   | 212   | 460   |   | 106   |   | 521  | 1271  |   | 60  | 816   | 676   |
| v/s Ratio Prot                    |   | c0.08   | 0.08  |   | c0.03   |   | c0.06  | 0.06  |   | 0.02  | c0.09   | 0.00  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.66  | 0.28  |   | 0.43  |   | 0.42   | 0.17  |   | 0.65  | 0.39  | 0.01  |
| Uniform Delay, d1                 |   | 30.2  | 20.4  |   | 32.4  |   | 27.7   | 15.4  |   | 34.4  | 22.8  | 10.9  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 7.5   | 0.3   |   | 2.8   |   | 0.6  | 0.1   |   | 22.4  | 0.3   | 0.0   |
| Delay (s)                         |   | 37.7  | 20.8  |   | 35.2  |   | 28.3   | 15.5  |   | 56.8  | 23.1  | 10.9  |
| Level of Service                  |   | D   | C   |   | D   |   | C  | B   |   | E   | C   | B   |
| Approach Delay (s)                |   | 24.7  |   |   | 35.2  |   |  | 21.8  |   |   | 26.5  |   |
| Approach LOS                      |   | C   |   |   | D   |   |  | C   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 24.6  |   |   |   | HCM 2000 Level of Service  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.42  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 72.3  |   |   |   | Sum of lost time (s)   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 55.9%   |   |   |   | ICU Level of Service   |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2024 Existing AM Peak Weekday AM Peak

| Movement                          | EBL   | EBT  | EBR   | WBL   | WBT                       | WBR   | NBL  | NBT  | NBR   | SBL   | SBT   | SBR   |  |
|-----------------------------------|-------|------|-------|-------|---------------------------|-------|------|------|-------|-------|-------|-------|--|
| Lane Configurations               |       |      |       |       |                           |       |      |      |       |       |       |       |  |
| Traffic Volume (vph)              | 23    | 3    | 26    | 26    | 0                         | 33    | 9    | 290  | 37    | 44    | 640   | 49    |  |
| Future Volume (vph)               | 23    | 3    | 26    | 26    | 0                         | 33    | 9    | 290  | 37    | 44    | 640   | 49    |  |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900  | 1900                      | 1900  | 1900 | 1900 | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11    | 11   | 11    | 11    | 11                        | 11    | 11   | 11   | 16    | 11    | 11    | 11    |  |
| Grade (%)                         |       | 3%   |       |       | -5%                       |       |      | 5%   |       |       | -3%   |       |  |
| Total Lost time (s)               | 6.0   | 6.0  | 6.0   | 5.5   | 5.5                       | 5.5   | 6.0  | 6.0  | 5.5   | 5.5   | 6.0   | 6.0   |  |
| Lane Util. Factor                 | 0.95  | 0.95 | 1.00  | 0.95  | 0.95                      | 1.00  | 1.00 | 0.95 | 1.00  | 1.00  | 0.95  | 1.00  |  |
| Frpb, ped/bikes                   | 1.00  | 1.00 | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Flpb, ped/bikes                   | 1.00  | 1.00 | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Frt                               | 1.00  | 1.00 | 0.85  | 1.00  | 1.00                      | 0.85  | 1.00 | 1.00 | 0.85  | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     | 0.95  | 0.96 | 1.00  | 0.95  | 0.95                      | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 | 1570  | 1593 | 1479  | 1634  | 1634                      | 1539  | 1652 | 3303 | 1733  | 1736  | 3473  | 1554  |  |
| Flt Permitted                     | 0.95  | 0.96 | 1.00  | 0.95  | 0.95                      | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 | 1570  | 1593 | 1479  | 1634  | 1634                      | 1539  | 1652 | 3303 | 1733  | 1736  | 3473  | 1554  |  |
| Peak-hour factor, PHF             | 0.82  | 0.82 | 0.82  | 0.65  | 0.65                      | 0.65  | 0.85 | 0.85 | 0.85  | 0.98  | 0.98  | 0.98  |  |
| Adj. Flow (vph)                   | 28    | 4    | 32    | 40    | 0                         | 51    | 11   | 341  | 44    | 45    | 653   | 50    |  |
| RTOR Reduction (vph)              | 0     | 0    | 28    | 0     | 0                         | 0     | 0    | 0    | 25    | 0     | 0     | 23    |  |
| Lane Group Flow (vph)             | 16    | 16   | 4     | 20    | 20                        | 51    | 11   | 341  | 19    | 45    | 653   | 27    |  |
| Confl. Bikes (#/hr)               |       |      |       |       |                           |       |      |      | 1     |       |       |       |  |
| Heavy Vehicles (%)                | 4%    | 4%   | 4%    | 4%    | 4%                        | 4%    | 3%   | 3%   | 3%    | 2%    | 2%    | 2%    |  |
| Turn Type                         | Split | NA   | pt+ov | Split | NA                        | pt+ov | Prot | NA   | pt+ov | Prot  | NA    | pt+ov |  |
| Protected Phases                  | 3     | 3    | 13    | 4     | 4                         | 45    | 1    | 6    | 46    | 5     | 2     | 23    |  |
| Permitted Phases                  |       |      |       |       |                           |       |      |      |       |       |       |       |  |
| Actuated Green, G (s)             | 5.0   | 5.0  | 8.2   | 5.5   | 5.5                       | 12.0  | 3.2  | 24.5 | 30.0  | 6.5   | 27.3  | 38.3  |  |
| Effective Green, g (s)            | 5.0   | 5.0  | 8.2   | 5.5   | 5.5                       | 12.0  | 3.2  | 24.5 | 30.0  | 6.5   | 27.3  | 38.3  |  |
| Actuated g/C Ratio                | 0.07  | 0.07 | 0.12  | 0.08  | 0.08                      | 0.17  | 0.05 | 0.35 | 0.43  | 0.09  | 0.39  | 0.55  |  |
| Clearance Time (s)                | 6.0   | 6.0  |       | 5.5   | 5.5                       |       | 6.0  | 6.0  |       | 5.5   | 6.0   |       |  |
| Vehicle Extension (s)             | 3.0   | 3.0  |       | 3.0   | 3.0                       |       | 3.0  | 3.0  |       | 3.0   | 3.0   |       |  |
| Lane Grp Cap (vph)                | 111   | 113  | 172   | 128   | 128                       | 263   | 75   | 1152 | 740   | 160   | 1350  | 847   |  |
| v/s Ratio Prot                    | c0.01 | 0.01 | 0.00  | 0.01  | 0.01                      | c0.03 | 0.01 | 0.10 | 0.01  | c0.03 | c0.19 | 0.02  |  |
| v/s Ratio Perm                    |       |      |       |       |                           |       |      |      |       |       |       |       |  |
| v/c Ratio                         | 0.14  | 0.14 | 0.02  | 0.16  | 0.16                      | 0.19  | 0.15 | 0.30 | 0.03  | 0.28  | 0.48  | 0.03  |  |
| Uniform Delay, d1                 | 30.6  | 30.6 | 27.4  | 30.2  | 30.2                      | 25.0  | 32.2 | 16.6 | 11.6  | 29.7  | 16.1  | 7.4   |  |
| Progression Factor                | 1.00  | 1.00 | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             | 0.6   | 0.6  | 0.1   | 0.6   | 0.6                       | 0.4   | 0.9  | 0.1  | 0.0   | 1.0   | 0.3   | 0.0   |  |
| Delay (s)                         | 31.2  | 31.2 | 27.5  | 30.8  | 30.8                      | 25.3  | 33.1 | 16.7 | 11.7  | 30.6  | 16.4  | 7.4   |  |
| Level of Service                  | C     | C    | C     | C     | C                         | C     | C    | B    | B     | C     | B     | A     |  |
| Approach Delay (s)                |       | 29.3 |       |       | 27.7                      |       |      | 16.6 |       |       | 16.7  |       |  |
| Approach LOS                      |       | C    |       |       | C                         |       |      | B    |       |       | B     |       |  |
| <b>Intersection Summary</b>       |       |      |       |       |                           |       |      |      |       |       |       |       |  |
| HCM 2000 Control Delay            |       |      | 18.1  |       | HCM 2000 Level of Service |       |      |      |       |       | B     |       |  |
| HCM 2000 Volume to Capacity ratio |       |      | 0.38  |       |                           |       |      |      |       |       |       |       |  |
| Actuated Cycle Length (s)         |       |      | 70.2  |       | Sum of lost time (s)      |       |      |      |       |       | 25.5  |       |  |
| Intersection Capacity Utilization |       |      | 45.1% |       | ICU Level of Service      |       |      |      |       |       | A     |       |  |
| Analysis Period (min)             |       |      | 15    |       |                           |       |      |      |       |       |       |       |  |


c Critical Lane Group

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2024 Existing AM Peak Weekday AM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR  | NBL   | NBT   | NBR  | SBL  | SBT  | SBR   |
|-----------------------------------|-------|-------|-------|-------|-------|------|-------|-------|------|------|------|-------|
| Lane Configurations               |       |       |       |       |       |      |       |       |      |      |      |       |
| Traffic Volume (vph)              | 85    | 38    | 46    | 3     | 31    | 39   | 65    | 270   | 75   | 2    | 250  | 190   |
| Future Volume (vph)               | 85    | 38    | 46    | 3     | 31    | 39   | 65    | 270   | 75   | 2    | 250  | 190   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900 | 1900  | 1900  | 1900 | 1900 | 1900 | 1900  |
| Lane Width                        | 11    | 11    | 11    | 14    | 14    | 14   | 11    | 11    | 11   | 11   | 11   | 11    |
| Grade (%)                         |       | 5%    |       |       | -5%   |      |       | 0%    |      |      | 0%   |       |
| Total Lost time (s)               | 6.5   | 6.5   |       | 6.5   | 6.5   |      | 6.5   | 6.5   |      | 6.5  | 6.5  | 6.5   |
| Lane Util. Factor                 | 0.97  | 1.00  |       | 1.00  | 1.00  |      | 1.00  | 0.95  |      | 1.00 | 0.95 | 1.00  |
| Frpb, ped/bikes                   | 1.00  | 0.99  |       | 1.00  | 1.00  |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |
| Flpb, ped/bikes                   | 1.00  | 1.00  |       | 1.00  | 1.00  |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |
| Frt                               | 1.00  | 0.92  |       | 1.00  | 0.92  |      | 1.00  | 0.97  |      | 1.00 | 1.00 | 0.85  |
| Flt Protected                     | 0.95  | 1.00  |       | 0.95  | 1.00  |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00  |
| Satd. Flow (prot)                 | 3268  | 1615  |       | 1898  | 1831  |      | 1711  | 3295  |      | 1694 | 3388 | 1516  |
| Flt Permitted                     | 0.95  | 1.00  |       | 0.95  | 1.00  |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00  |
| Satd. Flow (perm)                 | 3268  | 1615  |       | 1898  | 1831  |      | 1711  | 3295  |      | 1694 | 3388 | 1516  |
| Peak-hour factor, PHF             | 0.73  | 0.73  | 0.73  | 0.65  | 0.65  | 0.65 | 0.75  | 0.75  | 0.75 | 0.97 | 0.97 | 0.97  |
| Adj. Flow (vph)                   | 116   | 52    | 63    | 5     | 48    | 60   | 87    | 360   | 100  | 2    | 258  | 196   |
| RTOR Reduction (vph)              | 0     | 34    | 0     | 0     | 40    | 0    | 0     | 18    | 0    | 0    | 0    | 98    |
| Lane Group Flow (vph)             | 116   | 81    | 0     | 5     | 68    | 0    | 87    | 442   | 0    | 2    | 258  | 98    |
| Confl. Bikes (#/hr)               |       |       | 1     |       |       |      |       |       | 1    |      |      |       |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 4%    | 4%    | 4%   | 2%    | 2%    | 2%   | 3%   | 3%   | 3%    |
| Turn Type                         | Split | NA    |       | Split | NA    |      | Prot  | NA    |      | Prot | NA   | pt+ov |
| Protected Phases                  | 3     | 3     |       | 4     | 4     |      | 1     | 6     |      | 5    | 2    | 2 3   |
| Permitted Phases                  |       |       |       |       |       |      |       |       |      |      |      |       |
| Actuated Green, G (s)             | 8.9   | 8.9   |       | 6.2   | 6.2   |      | 6.8   | 22.7  |      | 0.9  | 16.8 | 32.2  |
| Effective Green, g (s)            | 8.9   | 8.9   |       | 6.2   | 6.2   |      | 6.8   | 22.7  |      | 0.9  | 16.8 | 32.2  |
| Actuated g/C Ratio                | 0.14  | 0.14  |       | 0.10  | 0.10  |      | 0.11  | 0.35  |      | 0.01 | 0.26 | 0.50  |
| Clearance Time (s)                | 6.5   | 6.5   |       | 6.5   | 6.5   |      | 6.5   | 6.5   |      | 6.5  | 6.5  |       |
| Vehicle Extension (s)             | 3.0   | 3.0   |       | 3.0   | 3.0   |      | 3.0   | 3.0   |      | 3.0  | 3.0  |       |
| Lane Grp Cap (vph)                | 449   | 222   |       | 181   | 175   |      | 179   | 1156  |      | 23   | 879  | 754   |
| v/s Ratio Prot                    | 0.04  | c0.05 |       | 0.00  | c0.04 |      | c0.05 | c0.13 |      | 0.00 | 0.08 | 0.06  |
| v/s Ratio Perm                    |       |       |       |       |       |      |       |       |      |      |      |       |
| v/c Ratio                         | 0.26  | 0.36  |       | 0.03  | 0.39  |      | 0.49  | 0.38  |      | 0.09 | 0.29 | 0.13  |
| Uniform Delay, d1                 | 24.9  | 25.3  |       | 26.5  | 27.5  |      | 27.3  | 15.7  |      | 31.5 | 19.2 | 8.7   |
| Progression Factor                | 1.00  | 1.00  |       | 1.00  | 1.00  |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |
| Incremental Delay, d2             | 0.3   | 1.0   |       | 0.1   | 1.4   |      | 2.1   | 0.2   |      | 1.6  | 0.2  | 0.1   |
| Delay (s)                         | 25.3  | 26.3  |       | 26.6  | 28.9  |      | 29.4  | 16.0  |      | 33.1 | 19.4 | 8.8   |
| Level of Service                  | C     | C     |       | C     | C     |      | C     | B     |      | C    | B    | A     |
| Approach Delay (s)                |       | 25.8  |       |       | 28.8  |      |       | 18.1  |      |      | 14.9 |       |
| Approach LOS                      |       | C     |       |       | C     |      |       | B     |      |      | B    |       |
| <b>Intersection Summary</b>       |       |       |       |       |       |      |       |       |      |      |      |       |
| HCM 2000 Control Delay            |       |       | 19.2  |       |       |      |       |       |      |      |      | B     |
| HCM 2000 Volume to Capacity ratio |       |       | 0.45  |       |       |      |       |       |      |      |      |       |
| Actuated Cycle Length (s)         |       |       | 64.7  |       |       |      |       |       |      |      | 28.0 |       |
| Intersection Capacity Utilization |       |       | 40.2% |       |       |      |       |       |      |      |      | A     |
| Analysis Period (min)             |       |       | 15    |       |       |      |       |       |      |      |      |       |

c Critical Lane Group

201: Motel 6/North Site & Gosling Road  
 2024 Existing AM Peak Weekday AM Peak



| Movement                          | EBT  | EBR  | WBL   | WBT  | NBL                  | NBR  |      |
|-----------------------------------|------|------|-------|------|----------------------|------|------|
| Lane Configurations               | ↑↑↑↑ |      |       | ↑↑   |                      | ↗    |      |
| Traffic Volume (veh/h)            | 685  | 85   | 0     | 298  | 0                    | 13   |      |
| Future Volume (Veh/h)             | 685  | 85   | 0     | 298  | 0                    | 13   |      |
| Sign Control                      | Free |      |       | Free | Stop                 |      |      |
| Grade                             | 0%   |      |       | 0%   | 0%                   |      |      |
| Peak Hour Factor                  | 0.97 | 0.97 | 0.89  | 0.89 | 0.46                 | 0.46 |      |
| Hourly flow rate (vph)            | 706  | 88   | 0     | 335  | 0                    | 28   |      |
| <b>Pedestrians</b>                |      |      |       |      |                      |      |      |
| Lane Width (ft)                   |      |      |       |      |                      |      |      |
| Walking Speed (ft/s)              |      |      |       |      |                      |      |      |
| Percent Blockage                  |      |      |       |      |                      |      |      |
| Right turn flare (veh)            |      |      |       |      |                      |      |      |
| Median type                       | None |      |       | None |                      |      |      |
| Median storage (veh)              |      |      |       |      |                      |      |      |
| Upstream signal (ft)              | 464  |      |       |      |                      |      |      |
| pX, platoon unblocked             |      |      |       |      |                      |      |      |
| vC, conflicting volume            |      |      | 794   |      | 918                  | 220  |      |
| vC1, stage 1 conf vol             |      |      |       |      |                      |      |      |
| vC2, stage 2 conf vol             |      |      |       |      |                      |      |      |
| vCu, unblocked vol                |      |      | 794   |      | 918                  | 220  |      |
| tC, single (s)                    |      |      | 4.2   |      | 6.8                  | 6.9  |      |
| tC, 2 stage (s)                   |      |      |       |      |                      |      |      |
| tF (s)                            |      |      | 2.2   |      | 3.5                  | 3.3  |      |
| p0 queue free %                   |      |      | 100   |      | 100                  | 96   |      |
| cM capacity (veh/h)               |      |      | 804   |      | 275                  | 790  |      |
| Direction, Lane #                 | EB 1 | EB 2 | EB 3  | EB 4 | WB 1                 | WB 2 | NB 1 |
| Volume Total                      | 202  | 202  | 202   | 189  | 168                  | 168  | 28   |
| Volume Left                       | 0    | 0    | 0     | 0    | 0                    | 0    | 0    |
| Volume Right                      | 0    | 0    | 0     | 88   | 0                    | 0    | 28   |
| cSH                               | 1700 | 1700 | 1700  | 1700 | 1700                 | 1700 | 790  |
| Volume to Capacity                | 0.12 | 0.12 | 0.12  | 0.11 | 0.10                 | 0.10 | 0.04 |
| Queue Length 95th (ft)            | 0    | 0    | 0     | 0    | 0                    | 0    | 3    |
| Control Delay (s)                 | 0.0  | 0.0  | 0.0   | 0.0  | 0.0                  | 0.0  | 9.7  |
| Lane LOS                          |      |      |       |      |                      |      | A    |
| Approach Delay (s)                | 0.0  |      |       | 0.0  |                      |      | 9.7  |
| Approach LOS                      |      |      |       |      |                      |      | A    |
| <b>Intersection Summary</b>       |      |      |       |      |                      |      |      |
| Average Delay                     |      |      | 0.2   |      |                      |      |      |
| Intersection Capacity Utilization |      |      | 21.3% |      | ICU Level of Service |      | A    |
| Analysis Period (min)             |      |      | 15    |      |                      |      |      |

202: Arthur F Brady Drive & South Site Driveway  
 2024 Existing AM Peak Weekday AM Peak

| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 4.3  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↕    | ↕     | ↕    | ↕    |
| Traffic Vol, veh/h       | 49   | 85   | 75   | 70    | 80   | 47   |
| Future Vol, veh/h        | 49   | 85   | 75   | 70    | 80   | 47   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 85   | 85   | 84   | 84    | 81   | 81   |
| Heavy Vehicles, %        | 4    | 4    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 58   | 100  | 89   | 83    | 99   | 58   |













| Major/Minor          | Major1 | Major2 | Minor2 |   |         |
|----------------------|--------|--------|--------|---|---------|
| Conflicting Flow All | 90     | 0      | -      | 0 | 306 91  |
| Stage 1              | -      | -      | -      | - | 90 -    |
| Stage 2              | -      | -      | -      | - | 216 -   |
| Critical Hdwy        | 4.14   | -      | -      | - | 6.4 6.2 |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.4 -   |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.4 -   |
| Follow-up Hdwy       | 2.236  | -      | -      | - | 3.5 3.3 |
| Pot Cap-1 Maneuver   | 1493   | -      | -      | - | 690 972 |
| Stage 1              | -      | -      | -      | - | 939 -   |
| Stage 2              | -      | -      | -      | - | 825 -   |
| Platoon blocked, %   |        | -      | -      | - |         |
| Mov Cap-1 Maneuver   | 1492   | -      | -      | - | 660 970 |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 660 -   |
| Stage 1              | -      | -      | -      | - | 900 -   |
| Stage 2              | -      | -      | -      | - | 824 -   |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.7 | 0  | 10.5 |
| HCM LOS              |     |    | B    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1492  | -   | -   | -   | 660   | 970   |
| HCM Lane V/C Ratio    | 0.039 | -   | -   | -   | 0.15  | 0.06  |
| HCM Control Delay (s) | 7.5   | 0   | -   | -   | 11.4  | 8.9   |
| HCM Lane LOS          | A     | A   | -   | -   | B     | A     |
| HCM 95th %tile Q(veh) | 0.1   | -   | -   | -   | 0.5   | 0.2   |


























101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2024 Existing PM Peak Weekday PM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↗↖  |
| Traffic Volume (vph)              | 0   | 1040  | 540   | 454   | 286   | 0   | 0  | 0   | 0   | 225   | 1   | 98  |
| Future Volume (vph)               | 0   | 1040  | 540   | 454   | 286   | 0   | 0  | 0   | 0   | 225   | 1   | 98  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.94  | 0.94  | 0.94  | 0.92   | 0.92  | 0.92  | 0.94  | 0.94  | 0.94  |
| Adj. Flow (vph)                   | 0   | 1238  | 643   | 483   | 304   | 0   | 0  | 0   | 0   | 239   | 1   | 104   |
| RTOR Reduction (vph)              | 0   | 0   | 359   | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 83  |
| Lane Group Flow (vph)             | 0   | 1238  | 284   | 483   | 304   | 0   | 0  | 0   | 0   | 119   | 121   | 21  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 35.4  | 35.4  | 20.4  | 55.9  |   |  |   |   | 18.8  | 18.8  | 18.8  |
| Effective Green, g (s)            |   | 35.4  | 35.4  | 20.4  | 55.9  |   |  |   |   | 18.8  | 18.8  | 18.8  |
| Actuated g/C Ratio                |   | 0.38  | 0.38  | 0.22  | 0.60  |   |  |   |   | 0.20  | 0.20  | 0.20  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 2309  | 591   | 712   | 2085  |   |  |   |   | 344   | 345   | 571   |
| v/s Ratio Prot                    |   | c0.20   | 0.18  | c0.15   | 0.09  |   |  |   |   | 0.07  | c0.07   | 0.01  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.54  | 0.48  | 0.68  | 0.15  |   |  |   |   | 0.35  | 0.35  | 0.04  |
| Uniform Delay, d1                 |   | 22.2  | 21.6  | 33.1  | 8.0   |   |  |   |   | 31.6  | 31.7  | 29.6  |
| Progression Factor                |   | 1.00  | 1.00  | 1.37  | 0.86  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.4   | 1.3   | 2.6   | 0.1   |   |  |   |   | 1.3   | 1.3   | 0.1   |
| Delay (s)                         |   | 22.7  | 22.9  | 47.8  | 6.9   |   |  |   |   | 32.9  | 33.0  | 29.7  |
| Level of Service                  |   | C   | C   | D   | A   |   |  |   |   | C   | C   | C   |
| Approach Delay (s)                |   | 22.8  |   |   | 32.0  |   |  | 0.0   |   |   | 31.9  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 26.2  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.53  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 92.6  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 68.1%   |   |   | ICU Level of Service  |  |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2024 Existing PM Peak Weekday PM Peak

























|                                   |    |    |  |  |    |  |   |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |   |   |   |    |   |   |  |  |   |   |   |
| Traffic Volume (vph)              | 627   | 638   | 0   | 0   | 604   | 324   | 136   | 0   | 506   | 0   | 0   | 0   |
| Future Volume (vph)               | 627   | 638   | 0   | 0   | 604   | 324   | 136   | 0   | 506   | 0   | 0   | 0   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 10  | 11  | 12  | 12  | 12  | 12  | 12  | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               | 6.0   | 6.0   |   |   | 6.0   |   | 6.0   | 6.0   | 6.0   |   |   |   |
| Lane Util. Factor                 | 0.97  | 0.95  |   |   | 0.91  |   | 0.97  | 0.95  | 0.95  |   |   |   |
| Frt                               | 1.00  | 1.00  |   |   | 0.95  |   | 1.00  | 0.85  | 0.85  |   |   |   |
| Flt Protected                     | 0.95  | 1.00  |   |   | 1.00  |   | 0.95  | 1.00  | 1.00  |   |   |   |
| Satd. Flow (prot)                 | 3236  | 3455  |   |   | 4867  |   | 3433  | 1504  | 1504  |   |   |   |
| Flt Permitted                     | 0.21  | 1.00  |   |   | 1.00  |   | 0.95  | 1.00  | 1.00  |   |   |   |
| Satd. Flow (perm)                 | 725   | 3455  |   |   | 4867  |   | 3433  | 1504  | 1504  |   |   |   |
| Peak-hour factor, PHF             | 0.87  | 0.87  | 0.87  | 0.94  | 0.94  | 0.94  | 0.94  | 0.94  | 0.94  | 0.90  | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 721   | 733   | 0   | 0   | 643   | 345   | 145   | 0   | 538   | 0   | 0   | 0   |
| RTOR Reduction (vph)              | 0   | 0   | 0   | 0   | 88  | 0   | 0   | 214   | 214   | 0   | 0   | 0   |
| Lane Group Flow (vph)             | 721   | 733   | 0   | 0   | 900   | 0   | 145   | 55  | 55  | 0   | 0   | 0   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 2%  | 2%  | 2%  | 0%  | 0%  | 0%  |
| Turn Type                         | pm+pt   | NA  |   |   | NA  |   | Split   | NA  | Prot  |   |   |   |
| Protected Phases                  | 1   | 6   |   |   | 2   |   | 3   | 3   | 3   |   |   |   |
| Permitted Phases                  | 6   |   |   |   |   |   |   |   |   |   |   |   |
| Actuated Green, G (s)             | 55.7  | 35.4  |   |   | 35.5  |   | 18.8  | 18.8  | 18.8  |   |   |   |
| Effective Green, g (s)            | 55.7  | 35.4  |   |   | 35.5  |   | 18.8  | 18.8  | 18.8  |   |   |   |
| Actuated g/C Ratio                | 0.60  | 0.38  |   |   | 0.38  |   | 0.20  | 0.20  | 0.20  |   |   |   |
| Clearance Time (s)                | 6.0   | 6.0   |   |   | 6.0   |   | 6.0   | 6.0   | 6.0   |   |   |   |
| Vehicle Extension (s)             | 4.0   | 5.0   |   |   | 5.0   |   | 5.0   | 5.0   | 5.0   |   |   |   |
| Lane Grp Cap (vph)                | 986   | 1320  |   |   | 1865  |   | 696   | 305   | 305   |   |   |   |
| v/s Ratio Prot                    | c0.16   | 0.21  |   |   | 0.18  |   | c0.04   | 0.04  | 0.04  |   |   |   |
| v/s Ratio Perm                    | c0.28   |   |   |   |   |   |   |   |   |   |   |   |
| v/c Ratio                         | 0.73  | 0.56  |   |   | 0.48  |   | 0.21  | 0.18  | 0.18  |   |   |   |
| Uniform Delay, d1                 | 11.0  | 22.4  |   |   | 21.6  |   | 30.7  | 30.5  | 30.5  |   |   |   |
| Progression Factor                | 2.57  | 0.48  |   |   | 1.00  |   | 1.00  | 1.00  | 1.00  |   |   |   |
| Incremental Delay, d2             | 2.7   | 0.8   |   |   | 0.4   |   | 0.3   | 0.6   | 0.6   |   |   |   |
| Delay (s)                         | 31.0  | 11.4  |   |   | 22.0  |   | 31.0  | 31.1  | 31.1  |   |   |   |
| Level of Service                  | C   | B   |   |   | C   |   | C   | C   | C   |   |   |   |
| Approach Delay (s)                |   | 21.1  |   |   | 22.0  |   |   | 31.1  |   |   | 0.0   |   |
| Approach LOS                      |   | C   |   |   | C   |   |   | C   |   |   | A   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 23.6  |   |   |   | HCM 2000 Level of Service   |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.60  |   |   |   |   |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 92.6  |   |   |   | Sum of lost time (s)  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 68.1%   |   |   |   | ICU Level of Service  |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
 2024 Existing PM Peak Weekday PM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT                       | WBR  | NBL   | NBT  | NBR  | SBL  | SBT   | SBR   |  |
|-----------------------------------|-------|-------|-------|-------|---------------------------|------|-------|------|------|------|-------|-------|--|
| Lane Configurations               |       |       |       |       |                           |      |       |      |      |      |       |       |  |
| Traffic Volume (vph)              | 87    | 60    | 463   | 60    | 55                        | 48   | 338   | 474  | 34   | 31   | 463   | 120   |  |
| Future Volume (vph)               | 87    | 60    | 463   | 60    | 55                        | 48   | 338   | 474  | 34   | 31   | 463   | 120   |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900                      | 1900 | 1900  | 1900 | 1900 | 1900 | 1900  | 1900  |  |
| Lane Width                        | 11    | 11    | 14    | 12    | 12                        | 16   | 12    | 12   | 12   | 11   | 11    | 11    |  |
| Total Lost time (s)               |       | 6.0   | 6.0   |       | 5.5                       |      | 6.0   | 6.0  |      | 5.5  | 6.0   | 6.0   |  |
| Lane Util. Factor                 |       | 1.00  | 1.00  |       | 1.00                      |      | 0.97  | 0.95 |      | 1.00 | 0.95  | 1.00  |  |
| Frbp, ped/bikes                   |       | 1.00  | 1.00  |       | 1.00                      |      | 1.00  | 1.00 |      | 1.00 | 1.00  | 1.00  |  |
| Flpb, ped/bikes                   |       | 1.00  | 1.00  |       | 1.00                      |      | 1.00  | 1.00 |      | 1.00 | 1.00  | 1.00  |  |
| Frt                               |       | 1.00  | 0.85  |       | 0.96                      |      | 1.00  | 0.99 |      | 1.00 | 1.00  | 0.85  |  |
| Flt Protected                     |       | 0.97  | 1.00  |       | 0.98                      |      | 0.95  | 1.00 |      | 0.95 | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 |       | 1749  | 1689  |       | 1756                      |      | 3467  | 3534 |      | 1711 | 3421  | 1531  |  |
| Flt Permitted                     |       | 0.97  | 1.00  |       | 0.98                      |      | 0.95  | 1.00 |      | 0.95 | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 |       | 1749  | 1689  |       | 1756                      |      | 3467  | 3534 |      | 1711 | 3421  | 1531  |  |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.80  | 0.80                      | 0.80 | 0.96  | 0.96 | 0.96 | 0.97 | 0.97  | 0.97  |  |
| Adj. Flow (vph)                   | 97    | 67    | 514   | 75    | 69                        | 60   | 352   | 494  | 35   | 32   | 477   | 124   |  |
| RTOR Reduction (vph)              | 0     | 0     | 387   | 0     | 12                        | 0    | 0     | 3    | 0    | 0    | 0     | 73    |  |
| Lane Group Flow (vph)             | 0     | 164   | 127   | 0     | 192                       | 0    | 352   | 526  | 0    | 32   | 477   | 51    |  |
| Confl. Bikes (#/hr)               |       |       |       |       |                           |      |       |      | 2    |      |       |       |  |
| Heavy Vehicles (%)                | 2%    | 2%    | 2%    | 2%    | 2%                        | 2%   | 1%    | 1%   | 1%   | 2%   | 2%    | 2%    |  |
| Turn Type                         | Split | NA    | pt+ov | Split | NA                        |      | Prot  | NA   |      | Prot | NA    | pt+ov |  |
| Protected Phases                  | 3     | 3     | 3 1   | 4     | 4                         |      | 1     | 6    |      | 5    | 2     | 2 3   |  |
| Permitted Phases                  |       |       |       |       |                           |      |       |      |      |      |       |       |  |
| Actuated Green, G (s)             |       | 8.4   | 22.1  |       | 14.8                      |      | 13.7  | 33.7 |      | 2.8  | 22.3  | 36.7  |  |
| Effective Green, g (s)            |       | 8.4   | 22.1  |       | 14.8                      |      | 13.7  | 33.7 |      | 2.8  | 22.3  | 36.7  |  |
| Actuated g/C Ratio                |       | 0.09  | 0.25  |       | 0.16                      |      | 0.15  | 0.38 |      | 0.03 | 0.25  | 0.41  |  |
| Clearance Time (s)                |       | 6.0   |       |       | 5.5                       |      | 6.0   | 6.0  |      | 5.5  | 6.0   |       |  |
| Vehicle Extension (s)             |       | 3.0   |       |       | 3.0                       |      | 3.0   | 3.0  |      | 3.0  | 3.0   |       |  |
| Lane Grp Cap (vph)                |       | 163   | 416   |       | 289                       |      | 529   | 1327 |      | 53   | 850   | 626   |  |
| v/s Ratio Prot                    |       | c0.09 | 0.07  |       | c0.11                     |      | c0.10 | 0.15 |      | 0.02 | c0.14 | 0.03  |  |
| v/s Ratio Perm                    |       |       |       |       |                           |      |       |      |      |      |       |       |  |
| v/c Ratio                         |       | 1.01  | 0.30  |       | 0.67                      |      | 0.67  | 0.40 |      | 0.60 | 0.56  | 0.08  |  |
| Uniform Delay, d1                 |       | 40.6  | 27.5  |       | 35.1                      |      | 35.8  | 20.5 |      | 42.9 | 29.4  | 16.2  |  |
| Progression Factor                |       | 1.00  | 1.00  |       | 1.00                      |      | 1.00  | 1.00 |      | 1.00 | 1.00  | 1.00  |  |
| Incremental Delay, d2             |       | 72.1  | 0.4   |       | 5.7                       |      | 3.2   | 0.2  |      | 17.9 | 0.9   | 0.1   |  |
| Delay (s)                         |       | 112.8 | 28.0  |       | 40.8                      |      | 39.0  | 20.7 |      | 60.8 | 30.3  | 16.3  |  |
| Level of Service                  |       | F     | C     |       | D                         |      | D     | C    |      | E    | C     | B     |  |
| Approach Delay (s)                |       | 48.5  |       |       | 40.8                      |      | 28.0  |      |      | 29.1 |       |       |  |
| Approach LOS                      |       | D     |       |       | D                         |      | C     |      |      | C    |       |       |  |
| <b>Intersection Summary</b>       |       |       |       |       |                           |      |       |      |      |      |       |       |  |
| HCM 2000 Control Delay            |       |       | 35.2  |       | HCM 2000 Level of Service |      |       |      |      |      | D     |       |  |
| HCM 2000 Volume to Capacity ratio |       |       | 0.62  |       |                           |      |       |      |      |      |       |       |  |
| Actuated Cycle Length (s)         |       |       | 89.7  |       | Sum of lost time (s)      |      |       |      |      | 25.5 |       |       |  |
| Intersection Capacity Utilization |       |       | 65.2% |       | ICU Level of Service      |      |       |      |      | C    |       |       |  |
| Analysis Period (min)             |       |       | 15    |       |                           |      |       |      |      |      |       |       |  |
| c Critical Lane Group             |       |       |       |       |                           |      |       |      |      |      |       |       |  |

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2024 Existing PM Peak Weekday PM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |      |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|------|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |      |
| Lane Configurations               |  |  |  |  |  |  |  |  |  |  |  |  |      |
| Traffic Volume (vph)              | 114   | 19  | 60  | 104   | 15  | 93  | 28   | 665   | 98  | 76  | 665   | 28  |      |
| Future Volume (vph)               | 114   | 19  | 60  | 104   | 15  | 93  | 28   | 665   | 98  | 76  | 665   | 28  |      |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |      |
| Lane Width                        | 11  | 11  | 11  | 11  | 11  | 11  | 11   | 11  | 16  | 11  | 11  | 11  |      |
| Grade (%)                         |   | 3%  |   |   | -5%   |   |  | 5%  |   |   | -3%   |   |      |
| Total Lost time (s)               | 6.0   | 6.0   | 6.0   | 5.5   | 5.5   | 5.5   | 6.0  | 6.0   | 5.5   | 5.5   | 6.0   | 6.0   |      |
| Lane Util. Factor                 | 0.95  | 0.95  | 1.00  | 0.95  | 0.95  | 1.00  | 1.00   | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  |      |
| Frt                               | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00   | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  |      |
| Flt Protected                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95   | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |      |
| Satd. Flow (prot)                 | 1633  | 1659  | 1424  | 1682  | 1706  | 1584  | 1684   | 3369  | 1767  | 1753  | 3507  | 1569  |      |
| Flt Permitted                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95   | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |      |
| Satd. Flow (perm)                 | 1633  | 1659  | 1424  | 1682  | 1706  | 1584  | 1684   | 3369  | 1767  | 1753  | 3507  | 1569  |      |
| Peak-hour factor, PHF             | 0.86  | 0.86  | 0.86  | 0.77  | 0.77  | 0.77  | 0.87   | 0.87  | 0.87  | 0.94  | 0.94  | 0.94  |      |
| Adj. Flow (vph)                   | 133   | 22  | 70  | 135   | 19  | 121   | 32   | 764   | 113   | 81  | 707   | 30  |      |
| RTOR Reduction (vph)              | 0   | 0   | 58  | 0   | 0   | 0   | 0  | 0   | 63  | 0   | 0   | 13  |      |
| Lane Group Flow (vph)             | 77  | 78  | 12  | 77  | 77  | 121   | 32   | 764   | 50  | 81  | 707   | 17  |      |
| Heavy Vehicles (%)                | 0%  | 0%  | 8%  | 1%  | 1%  | 1%  | 1%   | 1%  | 1%  | 1%  | 1%  | 1%  |      |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  | pt+ov   | Prot   | NA  | pt+ov   | Prot  | NA  | pt+ov   |      |
| Protected Phases                  | 3   | 3   | 13  | 4   | 4   | 45  | 1  | 6   | 46  | 5   | 2   | 23  |      |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |      |
| Actuated Green, G (s)             | 7.8   | 7.8   | 12.5  | 8.1   | 8.1   | 22.8  | 4.7  | 23.8  | 31.9  | 9.2   | 27.8  | 41.6  |      |
| Effective Green, g (s)            | 7.8   | 7.8   | 12.5  | 8.1   | 8.1   | 22.8  | 4.7  | 23.8  | 31.9  | 9.2   | 27.8  | 41.6  |      |
| Actuated g/C Ratio                | 0.11  | 0.11  | 0.17  | 0.11  | 0.11  | 0.32  | 0.07   | 0.33  | 0.44  | 0.13  | 0.39  | 0.58  |      |
| Clearance Time (s)                | 6.0   | 6.0   |   | 5.5   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |      |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |      |
| Lane Grp Cap (vph)                | 177   | 179   | 247   | 189   | 192   | 502   | 110  | 1115  | 783   | 224   | 1355  | 907   |      |
| v/s Ratio Prot                    | c0.05   | 0.05  | 0.01  | c0.05   | 0.05  | 0.08  | 0.02   | c0.23   | 0.03  | c0.05   | c0.20   | 0.01  |      |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |      |
| v/c Ratio                         | 0.44  | 0.44  | 0.05  | 0.41  | 0.40  | 0.24  | 0.29   | 0.69  | 0.06  | 0.36  | 0.52  | 0.02  |      |
| Uniform Delay, d1                 | 30.0  | 30.0  | 24.7  | 29.7  | 29.6  | 18.2  | 32.0   | 20.8  | 11.5  | 28.7  | 16.9  | 6.5   |      |
| Progression Factor                | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |      |
| Incremental Delay, d2             | 1.7   | 1.7   | 0.1   | 1.4   | 1.4   | 0.3   | 1.5  | 1.8   | 0.0   | 1.0   | 0.4   | 0.0   |      |
| Delay (s)                         | 31.7  | 31.7  | 24.8  | 31.1  | 31.0  | 18.4  | 33.5   | 22.6  | 11.5  | 29.7  | 17.3  | 6.5   |      |
| Level of Service                  | C   | C   | C   | C   | C   | B   | C  | C   | B   | C   | B   | A   |      |
| Approach Delay (s)                |   | 29.6  |   |   | 25.5  |   |  | 21.6  |   |   | 18.1  |   |      |
| Approach LOS                      |   | C   |   |   | C   |   |  | C   |   |   | B   |   |      |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |      |
| HCM 2000 Control Delay            |   |   | 21.6  |   |   |   |  |   |   |   |   | HCM 2000 Level of Service   | C    |
| HCM 2000 Volume to Capacity ratio |   |   | 0.58  |   |   |   |  |   |   |   |   |   |      |
| Actuated Cycle Length (s)         |   |   | 71.9  |   |   |   |  |   |   |   |   | Sum of lost time (s)  | 25.5 |
| Intersection Capacity Utilization |   |   | 50.0%   |   |   |   |  |   |   |   |   | ICU Level of Service  | A    |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |      |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |      |

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2024 Existing PM Peak Weekday PM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT  | WBR  | NBL   | NBT   | NBR  | SBL  | SBT   | SBR                         |
|-----------------------------------|-------|-------|-------|-------|------|------|-------|-------|------|------|-------|-----------------------------|
| Lane Configurations               |       |       |       |       |      |      |       |       |      |      |       |                             |
| Traffic Volume (vph)              | 207   | 71    | 98    | 196   | 93   | 16   | 98    | 452   | 142  | 16   | 627   | 360                         |
| Future Volume (vph)               | 207   | 71    | 98    | 196   | 93   | 16   | 98    | 452   | 142  | 16   | 627   | 360                         |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900 | 1900 | 1900  | 1900  | 1900 | 1900 | 1900  | 1900                        |
| Lane Width                        | 11    | 11    | 11    | 14    | 14   | 14   | 11    | 11    | 11   | 11   | 11    | 11                          |
| Grade (%)                         |       | 5%    |       |       | -5%  |      |       | 0%    |      |      | 0%    |                             |
| Total Lost time (s)               | 6.5   | 6.5   |       | 6.5   | 6.5  |      | 6.5   | 6.5   |      | 6.5  | 6.5   | 6.5                         |
| Lane Util. Factor                 | 0.97  | 1.00  |       | 1.00  | 1.00 |      | 1.00  | 0.95  |      | 1.00 | 0.95  | 1.00                        |
| Frt                               | 1.00  | 0.91  |       | 1.00  | 0.98 |      | 1.00  | 0.96  |      | 1.00 | 1.00  | 0.85                        |
| Flt Protected                     | 0.95  | 1.00  |       | 0.95  | 1.00 |      | 0.95  | 1.00  |      | 0.95 | 1.00  | 1.00                        |
| Satd. Flow (prot)                 | 3268  | 1619  |       | 1954  | 2010 |      | 1728  | 3331  |      | 1728 | 3455  | 1546                        |
| Flt Permitted                     | 0.95  | 1.00  |       | 0.95  | 1.00 |      | 0.95  | 1.00  |      | 0.95 | 1.00  | 1.00                        |
| Satd. Flow (perm)                 | 3268  | 1619  |       | 1954  | 2010 |      | 1728  | 3331  |      | 1728 | 3455  | 1546                        |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.91  | 0.91 | 0.91 | 0.88  | 0.88  | 0.88 | 0.90 | 0.90  | 0.90                        |
| Adj. Flow (vph)                   | 230   | 79    | 109   | 215   | 102  | 18   | 111   | 514   | 161  | 18   | 697   | 400                         |
| RTOR Reduction (vph)              | 0     | 41    | 0     | 0     | 5    | 0    | 0     | 21    | 0    | 0    | 0     | 208                         |
| Lane Group Flow (vph)             | 230   | 147   | 0     | 215   | 115  | 0    | 111   | 654   | 0    | 18   | 697   | 192                         |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 1%    | 1%   | 1%   | 1%    | 1%    | 1%   | 1%   | 1%    | 1%                          |
| Turn Type                         | Split | NA    |       | Split | NA   |      | Prot  | NA    |      | Prot | NA    | pt+ov                       |
| Protected Phases                  | 3     | 3     |       | 4     | 4    |      | 1     | 6     |      | 5    | 2     | 2 3                         |
| Permitted Phases                  |       |       |       |       |      |      |       |       |      |      |       |                             |
| Actuated Green, G (s)             | 11.3  | 11.3  |       | 14.8  | 14.8 |      | 10.5  | 36.8  |      | 2.6  | 28.9  | 46.7                        |
| Effective Green, g (s)            | 11.3  | 11.3  |       | 14.8  | 14.8 |      | 10.5  | 36.8  |      | 2.6  | 28.9  | 46.7                        |
| Actuated g/C Ratio                | 0.12  | 0.12  |       | 0.15  | 0.15 |      | 0.11  | 0.38  |      | 0.03 | 0.30  | 0.48                        |
| Clearance Time (s)                | 6.5   | 6.5   |       | 6.5   | 6.5  |      | 6.5   | 6.5   |      | 6.5  | 6.5   | 6.5                         |
| Vehicle Extension (s)             | 3.0   | 3.0   |       | 3.0   | 3.0  |      | 3.0   | 3.0   |      | 3.0  | 3.0   | 3.0                         |
| Lane Grp Cap (vph)                | 379   | 187   |       | 296   | 305  |      | 186   | 1258  |      | 46   | 1025  | 741                         |
| v/s Ratio Prot                    | 0.07  | c0.09 |       | c0.11 | 0.06 |      | c0.06 | c0.20 |      | 0.01 | c0.20 | 0.12                        |
| v/s Ratio Perm                    |       |       |       |       |      |      |       |       |      |      |       |                             |
| v/c Ratio                         | 0.61  | 0.79  |       | 0.73  | 0.38 |      | 0.60  | 0.52  |      | 0.39 | 0.68  | 0.26                        |
| Uniform Delay, d1                 | 40.9  | 41.9  |       | 39.4  | 37.2 |      | 41.4  | 23.5  |      | 46.6 | 30.2  | 15.1                        |
| Progression Factor                | 1.00  | 1.00  |       | 1.00  | 1.00 |      | 1.00  | 1.00  |      | 1.00 | 1.00  | 1.00                        |
| Incremental Delay, d2             | 2.7   | 19.4  |       | 8.6   | 0.8  |      | 5.1   | 0.4   |      | 5.4  | 1.9   | 0.2                         |
| Delay (s)                         | 43.7  | 61.3  |       | 47.9  | 37.9 |      | 46.5  | 23.9  |      | 52.0 | 32.0  | 15.3                        |
| Level of Service                  | D     | E     |       | D     | D    |      | D     | C     |      | D    | C     | B                           |
| Approach Delay (s)                |       | 51.6  |       |       | 44.4 |      |       | 27.1  |      |      | 26.3  |                             |
| Approach LOS                      |       | D     |       |       | D    |      |       | C     |      |      | C     |                             |
| <b>Intersection Summary</b>       |       |       |       |       |      |      |       |       |      |      |       |                             |
| HCM 2000 Control Delay            |       |       | 32.8  |       |      |      |       |       |      |      |       | HCM 2000 Level of Service C |
| HCM 2000 Volume to Capacity ratio |       |       | 0.66  |       |      |      |       |       |      |      |       |                             |
| Actuated Cycle Length (s)         |       |       | 97.4  |       |      |      |       |       |      |      |       | Sum of lost time (s) 28.0   |
| Intersection Capacity Utilization |       |       | 65.0% |       |      |      |       |       |      |      |       | ICU Level of Service C      |
| Analysis Period (min)             |       |       | 15    |       |      |      |       |       |      |      |       |                             |
| c Critical Lane Group             |       |       |       |       |      |      |       |       |      |      |       |                             |

201: Motel 6/North Site & Gosling Road  
 2024 Existing PM Peak Weekday PM Peak



| Movement                          | EBT         | EBR         | WBL         | WBT         | NBL                  | NBR         |             |
|-----------------------------------|-------------|-------------|-------------|-------------|----------------------|-------------|-------------|
| Lane Configurations               | ↑↑↑↑        |             |             | ↑↑          |                      | ↗           |             |
| Traffic Volume (veh/h)            | 1052        | 93          | 0           | 927         | 0                    | 31          |             |
| Future Volume (Veh/h)             | 1052        | 93          | 0           | 927         | 0                    | 31          |             |
| Sign Control                      | Free        |             |             | Free        | Stop                 |             |             |
| Grade                             | 0%          |             |             | 0%          | 0%                   |             |             |
| Peak Hour Factor                  | 0.94        | 0.94        | 0.98        | 0.97        | 0.72                 | 0.72        |             |
| Hourly flow rate (vph)            | 1119        | 99          | 0           | 956         | 0                    | 43          |             |
| <b>Pedestrians</b>                |             |             |             |             |                      |             |             |
| Lane Width (ft)                   |             |             |             |             |                      |             |             |
| Walking Speed (ft/s)              |             |             |             |             |                      |             |             |
| Percent Blockage                  |             |             |             |             |                      |             |             |
| Right turn flare (veh)            |             |             |             |             |                      |             |             |
| Median type                       | None        |             |             | None        |                      |             |             |
| Median storage (veh)              |             |             |             |             |                      |             |             |
| Upstream signal (ft)              | 464         |             |             |             |                      |             |             |
| pX, platoon unblocked             |             |             |             |             |                      |             |             |
| vC, conflicting volume            |             |             | 1218        |             | 1646                 | 329         |             |
| vC1, stage 1 conf vol             |             |             |             |             |                      |             |             |
| vC2, stage 2 conf vol             |             |             |             |             |                      |             |             |
| vCu, unblocked vol                |             |             | 1218        |             | 1646                 | 329         |             |
| tC, single (s)                    |             |             | 4.1         |             | 6.8                  | 6.9         |             |
| tC, 2 stage (s)                   |             |             |             |             |                      |             |             |
| tF (s)                            |             |             | 2.2         |             | 3.5                  | 3.3         |             |
| p0 queue free %                   |             |             | 100         |             | 100                  | 94          |             |
| cM capacity (veh/h)               |             |             | 574         |             | 92                   | 672         |             |
| <b>Direction, Lane #</b>          | <b>EB 1</b> | <b>EB 2</b> | <b>EB 3</b> | <b>EB 4</b> | <b>WB 1</b>          | <b>WB 2</b> | <b>NB 1</b> |
| Volume Total                      | 320         | 320         | 320         | 259         | 478                  | 478         | 43          |
| Volume Left                       | 0           | 0           | 0           | 0           | 0                    | 0           | 0           |
| Volume Right                      | 0           | 0           | 0           | 99          | 0                    | 0           | 43          |
| cSH                               | 1700        | 1700        | 1700        | 1700        | 1700                 | 1700        | 672         |
| Volume to Capacity                | 0.19        | 0.19        | 0.19        | 0.15        | 0.28                 | 0.28        | 0.06        |
| Queue Length 95th (ft)            | 0           | 0           | 0           | 0           | 0                    | 0           | 5           |
| Control Delay (s)                 | 0.0         | 0.0         | 0.0         | 0.0         | 0.0                  | 0.0         | 10.7        |
| Lane LOS                          |             |             |             |             |                      |             | B           |
| Approach Delay (s)                | 0.0         |             |             |             | 0.0                  |             | 10.7        |
| Approach LOS                      |             |             |             |             |                      |             | B           |
| <b>Intersection Summary</b>       |             |             |             |             |                      |             |             |
| Average Delay                     |             |             | 0.2         |             |                      |             |             |
| Intersection Capacity Utilization |             |             | 29.0%       |             | ICU Level of Service |             | A           |
| Analysis Period (min)             |             |             | 15          |             |                      |             |             |

202: Arthur F Brady Drive & South Site Driveway  
 2024 Existing PM Peak Weekday PM Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 4.7  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↑    | ↗     | ↖    | ↗    |
| Traffic Vol, veh/h       | 65   | 174  | 234  | 71    | 109  | 65   |
| Future Vol, veh/h        | 65   | 174  | 234  | 71    | 109  | 65   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 97   | 97   | 80   | 80    | 74   | 74   |
| Heavy Vehicles, %        | 0    | 0    | 0    | 0     | 1    | 1    |
| Mvmt Flow                | 67   | 179  | 293  | 89    | 147  | 88   |

| Major/Minor          | Major1 | Major2 | Minor2 |       |       |
|----------------------|--------|--------|--------|-------|-------|
| Conflicting Flow All | 294    | 0      | 0      | 607   | 295   |
| Stage 1              | -      | -      | -      | 294   | -     |
| Stage 2              | -      | -      | -      | 313   | -     |
| Critical Hdwy        | 4.1    | -      | -      | 6.41  | 6.21  |
| Critical Hdwy Stg 1  | -      | -      | -      | 5.41  | -     |
| Critical Hdwy Stg 2  | -      | -      | -      | 5.41  | -     |
| Follow-up Hdwy       | 2.2    | -      | -      | 3.509 | 3.309 |
| Pot Cap-1 Maneuver   | 1279   | -      | -      | 461   | 747   |
| Stage 1              | -      | -      | -      | 759   | -     |
| Stage 2              | -      | -      | -      | 744   | -     |
| Platoon blocked, %   | -      | -      | -      | -     | -     |
| Mov Cap-1 Maneuver   | 1278   | -      | -      | 433   | 745   |
| Mov Cap-2 Maneuver   | -      | -      | -      | 433   | -     |
| Stage 1              | -      | -      | -      | 714   | -     |
| Stage 2              | -      | -      | -      | 743   | -     |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.2 | 0  | 14.9 |
| HCM LOS              |     |    | B    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1278  | -   | -   | -   | 433   | 745   |
| HCM Lane V/C Ratio    | 0.052 | -   | -   | -   | 0.34  | 0.118 |
| HCM Control Delay (s) | 8     | 0   | -   | -   | 17.5  | 10.5  |
| HCM Lane LOS          | A     | A   | -   | -   | C     | B     |
| HCM 95th %tile Q(veh) | 0.2   | -   | -   | -   | 1.5   | 0.4   |

























101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2024 Existing SAT Peak Saturday Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↘↗  |
| Traffic Volume (vph)              | 0   | 298   | 67  | 359   | 193   | 0   | 0  | 0   | 0   | 311   | 1   | 51  |
| Future Volume (vph)               | 0   | 298   | 67  | 359   | 193   | 0   | 0  | 0   | 0   | 311   | 1   | 51  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1702  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1702  | 2814  |
| Peak-hour factor, PHF             | 0.92  | 0.92  | 0.92  | 0.85  | 0.85  | 0.85  | 0.92   | 0.92  | 0.92  | 0.87  | 0.87  | 0.87  |
| Adj. Flow (vph)                   | 0   | 324   | 73  | 422   | 227   | 0   | 0  | 0   | 0   | 357   | 1   | 59  |
| RTOR Reduction (vph)              | 0   | 0   | 49  | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 44  |
| Lane Group Flow (vph)             | 0   | 324   | 24  | 422   | 227   | 0   | 0  | 0   | 0   | 178   | 180   | 15  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 27.2  | 27.2  | 18.1  | 50.5  |   |  |   |   | 20.7  | 20.7  | 20.7  |
| Effective Green, g (s)            |   | 27.2  | 27.2  | 18.1  | 50.5  |   |  |   |   | 20.7  | 20.7  | 20.7  |
| Actuated g/C Ratio                |   | 0.32  | 0.32  | 0.22  | 0.60  |   |  |   |   | 0.25  | 0.25  | 0.25  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 1955  | 500   | 697   | 2077  |   |  |   |   | 418   | 419   | 693   |
| v/s Ratio Prot                    |   | c0.05   | 0.02  | c0.13   | c0.07   |   |  |   |   | 0.10  | c0.11   | 0.01  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.17  | 0.05  | 0.61  | 0.11  |   |  |   |   | 0.43  | 0.43  | 0.02  |
| Uniform Delay, d1                 |   | 20.3  | 19.5  | 29.7  | 7.1   |   |  |   |   | 26.6  | 26.7  | 24.0  |
| Progression Factor                |   | 1.00  | 1.00  | 1.43  | 0.79  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.1   | 0.1   | 1.7   | 0.0   |   |  |   |   | 1.5   | 1.5   | 0.0   |
| Delay (s)                         |   | 20.4  | 19.6  | 44.1  | 5.7   |   |  |   |   | 28.1  | 28.2  | 24.0  |
| Level of Service                  |   | C   | B   | D   | A   |   |  |   |   | C   | C   | C   |
| Approach Delay (s)                |   | 20.2  |   |   | 30.6  |   |  | 0.0   |   |   | 27.5  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 26.9  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.36  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 84.0  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 54.3%   |   |   | ICU Level of Service  |  |   |   | A   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group
























102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2024 Existing SAT Peak Saturday Peak

|                                   |    |    |  |  |    |  |    |    |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |   |   |   |    |   |   |   |  |   |   |   |
| Traffic Volume (vph)              | 80  | 529   | 0   | 0   | 472   | 186   | 80   | 3   | 648   | 0   | 0   | 0   |
| Future Volume (vph)               | 80  | 529   | 0   | 0   | 472   | 186   | 80   | 3   | 648   | 0   | 0   | 0   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 10  | 11  | 12  | 12  | 12  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Lane Util. Factor                 | 0.97  | 0.95  |   |   | 0.91  |   | 0.97   | 0.95  | 0.95  |   |   |   |
| Frt                               | 1.00  | 1.00  |   |   | 0.96  |   | 1.00   | 0.85  | 0.85  |   |   |   |
| Flt Protected                     | 0.95  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (prot)                 | 3236  | 3455  |   |   | 4918  |   | 3467   | 1521  | 1519  |   |   |   |
| Flt Permitted                     | 0.38  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (perm)                 | 1283  | 3455  |   |   | 4918  |   | 3467   | 1521  | 1519  |   |   |   |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.95  | 0.95  | 0.95  | 0.96   | 0.96  | 0.96  | 0.90  | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 86  | 569   | 0   | 0   | 497   | 196   | 83   | 3   | 675   | 0   | 0   | 0   |
| RTOR Reduction (vph)              | 0   | 0   | 0   | 0   | 65  | 0   | 0  | 255   | 254   | 0   | 0   | 0   |
| Lane Group Flow (vph)             | 86  | 569   | 0   | 0   | 629   | 0   | 83   | 86  | 83  | 0   | 0   | 0   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%   | 1%  | 1%  | 0%  | 0%  | 0%  |
| Turn Type                         | pm+pt   | NA  |   |   | NA  |   | Split  | NA  | Prot  |   |   |   |
| Protected Phases                  | 1   | 6   |   |   | 2   |   | 3  | 3   | 3   |   |   |   |
| Permitted Phases                  | 6   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             | 40.1  | 27.2  |   |   | 32.4  |   | 20.7   | 20.7  | 20.7  |   |   |   |
| Effective Green, g (s)            | 40.1  | 27.2  |   |   | 32.4  |   | 20.7   | 20.7  | 20.7  |   |   |   |
| Actuated g/C Ratio                | 0.48  | 0.32  |   |   | 0.39  |   | 0.25   | 0.25  | 0.25  |   |   |   |
| Clearance Time (s)                | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Vehicle Extension (s)             | 4.0   | 5.0   |   |   | 5.0   |   | 5.0  | 5.0   | 5.0   |   |   |   |
| Lane Grp Cap (vph)                | 912   | 1118  |   |   | 1896  |   | 854  | 374   | 374   |   |   |   |
| v/s Ratio Prot                    | c0.01   | c0.16   |   |   | c0.13   |   | 0.02   | c0.06   | 0.05  |   |   |   |
| v/s Ratio Perm                    | 0.03  |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         | 0.09  | 0.51  |   |   | 0.33  |   | 0.10   | 0.23  | 0.22  |   |   |   |
| Uniform Delay, d1                 | 11.8  | 23.0  |   |   | 18.2  |   | 24.4   | 25.3  | 25.2  |   |   |   |
| Progression Factor                | 1.19  | 1.05  |   |   | 1.00  |   | 1.00   | 1.00  | 1.00  |   |   |   |
| Incremental Delay, d2             | 0.1   | 0.8   |   |   | 0.2   |   | 0.1  | 0.7   | 0.6   |   |   |   |
| Delay (s)                         | 14.0  | 24.9  |   |   | 18.4  |   | 24.5   | 26.0  | 25.9  |   |   |   |
| Level of Service                  | B   | C   |   |   | B   |   | C  | C   | C   |   |   |   |
| Approach Delay (s)                |   | 23.5  |   |   | 18.4  |   |  | 25.8  |   |   | 0.0   |   |
| Approach LOS                      |   | C   |   |   | B   |   |  | C   |   |   | A   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 22.6  |   |   |   | HCM 2000 Level of Service  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.31  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 84.0  |   |   |   | Sum of lost time (s)   |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 54.3%   |   |   |   | ICU Level of Service   |   |   | A   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
 2024 Existing SAT Peak Saturday Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|--|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |  |
| Lane Configurations               |   |  |  |   |  |   |  |  |  |  |  |  |  |
| Traffic Volume (vph)              | 55  | 37  | 335   | 24  | 43  | 64  | 293  | 386   | 20  | 35  | 439   | 60  |  |
| Future Volume (vph)               | 55  | 37  | 335   | 24  | 43  | 64  | 293  | 386   | 20  | 35  | 439   | 60  |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |  |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |  |
| Frt                               |   | 1.00  | 0.85  |   | 0.93  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 |   | 1766  | 1706  |   | 1759  |   | 3467   | 3548  |   | 1728  | 3455  | 1546  |  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 |   | 1766  | 1706  |   | 1759  |   | 3467   | 3548  |   | 1728  | 3455  | 1546  |  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.85  | 0.85  | 0.85  | 0.91   | 0.91  | 0.91  | 0.88  | 0.88  | 0.88  |  |
| Adj. Flow (vph)                   | 65  | 44  | 399   | 28  | 51  | 75  | 322  | 424   | 22  | 40  | 499   | 68  |  |
| RTOR Reduction (vph)              | 0   | 0   | 298   | 0   | 29  | 0   | 0  | 3   | 0   | 0   | 0   | 39  |  |
| Lane Group Flow (vph)             | 0   | 109   | 101   | 0   | 125   | 0   | 322  | 443   | 0   | 40  | 499   | 29  |  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 0%  | 0%  | 0%  | 1%   | 1%  | 1%  | 1%  | 1%  | 1%  |  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |  |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |  |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |  |
| Actuated Green, G (s)             |   | 8.4   | 21.6  |   | 11.6  |   | 13.2   | 30.8  |   | 4.7   | 21.8  | 36.2  |  |
| Effective Green, g (s)            |   | 8.4   | 21.6  |   | 11.6  |   | 13.2   | 30.8  |   | 4.7   | 21.8  | 36.2  |  |
| Actuated g/C Ratio                |   | 0.10  | 0.25  |   | 0.14  |   | 0.15   | 0.36  |   | 0.05  | 0.25  | 0.42  |  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |  |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |  |
| Lane Grp Cap (vph)                |   | 173   | 430   |   | 238   |   | 534  | 1276  |   | 94  | 879   | 653   |  |
| v/s Ratio Prot                    |   | c0.06   | 0.06  |   | c0.07   |   | c0.09  | 0.12  |   | 0.02  | c0.14   | 0.02  |  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |  |
| v/c Ratio                         |   | 0.63  | 0.23  |   | 0.53  |   | 0.60   | 0.35  |   | 0.43  | 0.57  | 0.04  |  |
| Uniform Delay, d1                 |   | 37.1  | 25.4  |   | 34.4  |   | 33.8   | 20.0  |   | 39.1  | 27.8  | 14.5  |  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             |   | 7.3   | 0.3   |   | 2.1   |   | 1.9  | 0.2   |   | 3.1   | 0.8   | 0.0   |  |
| Delay (s)                         |   | 44.4  | 25.7  |   | 36.6  |   | 35.7   | 20.2  |   | 42.2  | 28.6  | 14.6  |  |
| Level of Service                  |   | D   | C   |   | D   |   | D  | C   |   | D   | C   | B   |  |
| Approach Delay (s)                |   | 29.7  |   |   | 36.6  |   | 26.7   |   |   | 28.0  |   |   |  |
| Approach LOS                      |   | C   |   |   | D   |   | C  |   |   | C   |   |   |  |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |  |
| HCM 2000 Control Delay            |   |   | 28.6  |   | HCM 2000 Level of Service   |   |  |   |   |   | C   |   |  |
| HCM 2000 Volume to Capacity ratio |   |   | 0.53  |   |   |   |  |   |   |   |   |   |  |
| Actuated Cycle Length (s)         |   |   | 85.6  |   | Sum of lost time (s)  |   |  |   |   |   | 25.5  |   |  |
| Intersection Capacity Utilization |   |   | 55.0%   |   | ICU Level of Service  |   |  |   |   |   | A   |   |  |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |  |

c Critical Lane Group

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2024 Existing SAT Peak Saturday Peak


| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT                       | WBR   | NBL  | NBT  | NBR   | SBL   | SBT   | SBR   |  |
|-----------------------------------|-------|-------|-------|-------|---------------------------|-------|------|------|-------|-------|-------|-------|--|
| Lane Configurations               |       |       |       |       |                           |       |      |      |       |       |       |       |  |
| Traffic Volume (vph)              | 120   | 23    | 80    | 120   | 11                        | 59    | 24   | 572  | 106   | 80    | 751   | 160   |  |
| Future Volume (vph)               | 120   | 23    | 80    | 120   | 11                        | 59    | 24   | 572  | 106   | 80    | 751   | 160   |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900                      | 1900  | 1900 | 1900 | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11    | 11    | 11    | 11    | 11                        | 11    | 11   | 11   | 16    | 11    | 11    | 11    |  |
| Grade (%)                         |       | 3%    |       |       | -5%                       |       |      | 5%   |       |       | -3%   |       |  |
| Total Lost time (s)               | 6.0   | 6.0   | 6.0   | 5.5   | 5.5                       | 5.5   | 6.0  | 6.0  | 5.5   | 5.5   | 6.0   | 6.0   |  |
| Lane Util. Factor                 | 0.95  | 0.95  | 1.00  | 0.95  | 0.95                      | 1.00  | 1.00 | 0.95 | 1.00  | 1.00  | 0.95  | 1.00  |  |
| Frpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Flpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Frt                               | 1.00  | 1.00  | 0.85  | 1.00  | 1.00                      | 0.85  | 1.00 | 1.00 | 0.85  | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96                      | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 | 1633  | 1662  | 1538  | 1699  | 1717                      | 1600  | 1684 | 3369 | 1767  | 1753  | 3507  | 1569  |  |
| Flt Permitted                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96                      | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 | 1633  | 1662  | 1538  | 1699  | 1717                      | 1600  | 1684 | 3369 | 1767  | 1753  | 3507  | 1569  |  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.91  | 0.91                      | 0.91  | 0.89 | 0.89 | 0.89  | 0.92  | 0.92  | 0.92  |  |
| Adj. Flow (vph)                   | 143   | 27    | 95    | 132   | 12                        | 65    | 27   | 643  | 119   | 87    | 816   | 174   |  |
| RTOR Reduction (vph)              | 0     | 0     | 77    | 0     | 0                         | 0     | 0    | 0    | 68    | 0     | 0     | 41    |  |
| Lane Group Flow (vph)             | 84    | 86    | 18    | 71    | 73                        | 65    | 27   | 643  | 51    | 87    | 816   | 133   |  |
| Confl. Bikes (#/hr)               |       |       |       |       |                           |       |      |      | 1     |       |       |       |  |
| Heavy Vehicles (%)                | 0%    | 0%    | 0%    | 0%    | 0%                        | 0%    | 1%   | 1%   | 1%    | 1%    | 1%    | 1%    |  |
| Turn Type                         | Split | NA    | pt+ov | Split | NA                        | pt+ov | Prot | NA   | pt+ov | Prot  | NA    | pt+ov |  |
| Protected Phases                  | 3     | 3     | 13    | 4     | 4                         | 45    | 1    | 6    | 46    | 5     | 2     | 23    |  |
| Permitted Phases                  |       |       |       |       |                           |       |      |      |       |       |       |       |  |
| Actuated Green, G (s)             | 8.1   | 8.1   | 12.6  | 8.0   | 8.0                       | 20.7  | 4.5  | 20.4 | 28.4  | 7.2   | 22.6  | 36.7  |  |
| Effective Green, g (s)            | 8.1   | 8.1   | 12.6  | 8.0   | 8.0                       | 20.7  | 4.5  | 20.4 | 28.4  | 7.2   | 22.6  | 36.7  |  |
| Actuated g/C Ratio                | 0.12  | 0.12  | 0.19  | 0.12  | 0.12                      | 0.31  | 0.07 | 0.31 | 0.43  | 0.11  | 0.34  | 0.55  |  |
| Clearance Time (s)                | 6.0   | 6.0   |       | 5.5   | 5.5                       |       | 6.0  | 6.0  |       | 5.5   | 6.0   |       |  |
| Vehicle Extension (s)             | 3.0   | 3.0   |       | 3.0   | 3.0                       |       | 3.0  | 3.0  |       | 3.0   | 3.0   |       |  |
| Lane Grp Cap (vph)                | 198   | 201   | 290   | 203   | 205                       | 496   | 113  | 1030 | 752   | 189   | 1188  | 863   |  |
| v/s Ratio Prot                    | 0.05  | c0.05 | 0.01  | 0.04  | c0.04                     | 0.04  | 0.02 | 0.19 | 0.03  | c0.05 | c0.23 | 0.08  |  |
| v/s Ratio Perm                    |       |       |       |       |                           |       |      |      |       |       |       |       |  |
| v/c Ratio                         | 0.42  | 0.43  | 0.06  | 0.35  | 0.36                      | 0.13  | 0.24 | 0.62 | 0.07  | 0.46  | 0.69  | 0.15  |  |
| Uniform Delay, d1                 | 27.1  | 27.2  | 22.2  | 27.0  | 27.0                      | 16.5  | 29.5 | 19.9 | 11.3  | 27.9  | 19.0  | 7.4   |  |
| Progression Factor                | 1.00  | 1.00  | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             | 1.5   | 1.5   | 0.1   | 1.0   | 1.1                       | 0.1   | 1.1  | 1.2  | 0.0   | 1.8   | 1.7   | 0.1   |  |
| Delay (s)                         | 28.6  | 28.6  | 22.3  | 28.0  | 28.0                      | 16.7  | 30.6 | 21.0 | 11.4  | 29.7  | 20.7  | 7.5   |  |
| Level of Service                  | C     | C     | C     | C     | C                         | B     | C    | C    | B     | C     | C     | A     |  |
| Approach Delay (s)                |       | 26.3  |       |       | 24.5                      |       |      | 19.9 |       |       | 19.3  |       |  |
| Approach LOS                      |       | C     |       |       | C                         |       |      | B    |       |       | B     |       |  |
| <b>Intersection Summary</b>       |       |       |       |       |                           |       |      |      |       |       |       |       |  |
| HCM 2000 Control Delay            |       |       | 20.8  |       | HCM 2000 Level of Service |       |      |      |       | C     |       |       |  |
| HCM 2000 Volume to Capacity ratio |       |       | 0.61  |       |                           |       |      |      |       |       |       |       |  |
| Actuated Cycle Length (s)         |       |       | 66.7  |       | Sum of lost time (s)      |       |      |      |       | 25.5  |       |       |  |
| Intersection Capacity Utilization |       |       | 51.4% |       | ICU Level of Service      |       |      |      |       | A     |       |       |  |
| Analysis Period (min)             |       |       | 15    |       |                           |       |      |      |       |       |       |       |  |

c Critical Lane Group

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2024 Existing SAT Peak Saturday Peak

| Movement                          | EBL   | EBT  | EBR   | WBL   | WBT                       | WBR  | NBL   | NBT   | NBR  | SBL  | SBT  | SBR   |  |
|-----------------------------------|-------|------|-------|-------|---------------------------|------|-------|-------|------|------|------|-------|--|
| Lane Configurations               |       |      |       |       |                           |      |       |       |      |      |      |       |  |
| Traffic Volume (vph)              | 239   | 67   | 49    | 140   | 73                        | 21   | 60    | 459   | 126  | 12   | 539  | 386   |  |
| Future Volume (vph)               | 239   | 67   | 49    | 140   | 73                        | 21   | 60    | 459   | 126  | 12   | 539  | 386   |  |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900  | 1900                      | 1900 | 1900  | 1900  | 1900 | 1900 | 1900 | 1900  |  |
| Lane Width                        | 11    | 11   | 11    | 14    | 14                        | 14   | 11    | 11    | 11   | 11   | 11   | 11    |  |
| Grade (%)                         |       | 5%   |       |       | -5%                       |      |       | 0%    |      |      | 0%   |       |  |
| Total Lost time (s)               | 6.5   | 6.5  |       | 6.5   | 6.5                       |      | 6.5   | 6.5   |      | 6.5  | 6.5  | 6.5   |  |
| Lane Util. Factor                 | 0.97  | 1.00 |       | 1.00  | 1.00                      |      | 1.00  | 0.95  |      | 1.00 | 0.95 | 1.00  |  |
| Frt                               | 1.00  | 0.94 |       | 1.00  | 0.97                      |      | 1.00  | 0.97  |      | 1.00 | 1.00 | 0.85  |  |
| Flt Protected                     | 0.95  | 1.00 |       | 0.95  | 1.00                      |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00  |  |
| Satd. Flow (prot)                 | 3268  | 1660 |       | 1954  | 1988                      |      | 1728  | 3343  |      | 1728 | 3455 | 1546  |  |
| Flt Permitted                     | 0.95  | 1.00 |       | 0.95  | 1.00                      |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00  |  |
| Satd. Flow (perm)                 | 3268  | 1660 |       | 1954  | 1988                      |      | 1728  | 3343  |      | 1728 | 3455 | 1546  |  |
| Peak-hour factor, PHF             | 0.77  | 0.77 | 0.77  | 0.78  | 0.78                      | 0.78 | 0.92  | 0.92  | 0.92 | 0.97 | 0.97 | 0.97  |  |
| Adj. Flow (vph)                   | 310   | 87   | 64    | 179   | 94                        | 27   | 65    | 499   | 137  | 12   | 556  | 398   |  |
| RTOR Reduction (vph)              | 0     | 21   | 0     | 0     | 8                         | 0    | 0     | 18    | 0    | 0    | 0    | 194   |  |
| Lane Group Flow (vph)             | 310   | 130  | 0     | 179   | 113                       | 0    | 65    | 618   | 0    | 12   | 556  | 204   |  |
| Heavy Vehicles (%)                | 1%    | 1%   | 1%    | 1%    | 1%                        | 1%   | 1%    | 1%    | 1%   | 1%   | 1%   | 1%    |  |
| Turn Type                         | Split | NA   |       | Split | NA                        |      | Prot  | NA    |      | Prot | NA   | pt+ov |  |
| Protected Phases                  | 3     | 3    |       | 4     | 4                         |      | 1     | 6     |      | 5    | 2    | 2 3   |  |
| Permitted Phases                  |       |      |       |       |                           |      |       |       |      |      |      |       |  |
| Actuated Green, G (s)             | 11.5  | 11.5 |       | 12.6  | 12.6                      |      | 6.9   | 28.8  |      | 1.2  | 23.1 | 41.1  |  |
| Effective Green, g (s)            | 11.5  | 11.5 |       | 12.6  | 12.6                      |      | 6.9   | 28.8  |      | 1.2  | 23.1 | 41.1  |  |
| Actuated g/C Ratio                | 0.14  | 0.14 |       | 0.16  | 0.16                      |      | 0.09  | 0.36  |      | 0.01 | 0.29 | 0.51  |  |
| Clearance Time (s)                | 6.5   | 6.5  |       | 6.5   | 6.5                       |      | 6.5   | 6.5   |      | 6.5  | 6.5  | 6.5   |  |
| Vehicle Extension (s)             | 3.0   | 3.0  |       | 3.0   | 3.0                       |      | 3.0   | 3.0   |      | 3.0  | 3.0  | 3.0   |  |
| Lane Grp Cap (vph)                | 469   | 238  |       | 307   | 312                       |      | 148   | 1201  |      | 25   | 996  | 793   |  |
| v/s Ratio Prot                    | c0.09 | 0.08 |       | c0.09 | 0.06                      |      | c0.04 | c0.18 |      | 0.01 | 0.16 | 0.13  |  |
| v/s Ratio Perm                    |       |      |       |       |                           |      |       |       |      |      |      |       |  |
| v/c Ratio                         | 0.66  | 0.55 |       | 0.58  | 0.36                      |      | 0.44  | 0.51  |      | 0.48 | 0.56 | 0.26  |  |
| Uniform Delay, d1                 | 32.5  | 31.9 |       | 31.3  | 30.2                      |      | 34.8  | 20.2  |      | 39.1 | 24.2 | 10.9  |  |
| Progression Factor                | 1.00  | 1.00 |       | 1.00  | 1.00                      |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |  |
| Incremental Delay, d2             | 3.5   | 2.6  |       | 2.8   | 0.7                       |      | 2.1   | 0.4   |      | 13.8 | 0.7  | 0.2   |  |
| Delay (s)                         | 35.9  | 34.5 |       | 34.1  | 30.9                      |      | 36.8  | 20.5  |      | 52.9 | 24.9 | 11.1  |  |
| Level of Service                  | D     | C    |       | C     | C                         |      | D     | C     |      | D    | C    | B     |  |
| Approach Delay (s)                |       | 35.5 |       |       | 32.8                      |      |       | 22.0  |      |      | 19.5 |       |  |
| Approach LOS                      |       | D    |       |       | C                         |      |       | C     |      |      | B    |       |  |
| <b>Intersection Summary</b>       |       |      |       |       |                           |      |       |       |      |      |      |       |  |
| HCM 2000 Control Delay            |       |      | 24.9  |       | HCM 2000 Level of Service |      |       |       |      |      | C    |       |  |
| HCM 2000 Volume to Capacity ratio |       |      | 0.61  |       |                           |      |       |       |      |      |      |       |  |
| Actuated Cycle Length (s)         |       |      | 80.1  |       | Sum of lost time (s)      |      |       |       |      | 28.0 |      |       |  |
| Intersection Capacity Utilization |       |      | 52.4% |       | ICU Level of Service      |      |       |       |      | A    |      |       |  |
| Analysis Period (min)             |       |      | 15    |       |                           |      |       |       |      |      |      |       |  |
| c Critical Lane Group             |       |      |       |       |                           |      |       |       |      |      |      |       |  |

201: Motel 6/North Site & Gosling Road  
 2024 Existing SAT Peak Saturday Peak



| Movement                          | EBT         | EBR         | WBL         | WBT         | NBL                  | NBR         |             |
|-----------------------------------|-------------|-------------|-------------|-------------|----------------------|-------------|-------------|
| Lane Configurations               | ↑↑↑↑        |             |             | ↑↑          |                      | ↗           |             |
| Traffic Volume (veh/h)            | 1111        | 67          | 0           | 658         | 0                    | 52          |             |
| Future Volume (Veh/h)             | 1111        | 67          | 0           | 658         | 0                    | 52          |             |
| Sign Control                      | Free        |             |             | Free        | Stop                 |             |             |
| Grade                             | 0%          |             |             | 0%          | 0%                   |             |             |
| Peak Hour Factor                  | 0.93        | 0.93        | 0.95        | 0.95        | 0.55                 | 0.55        |             |
| Hourly flow rate (vph)            | 1195        | 72          | 0           | 693         | 0                    | 95          |             |
| <b>Pedestrians</b>                |             |             |             |             |                      |             |             |
| Lane Width (ft)                   |             |             |             |             |                      |             |             |
| Walking Speed (ft/s)              |             |             |             |             |                      |             |             |
| Percent Blockage                  |             |             |             |             |                      |             |             |
| Right turn flare (veh)            |             |             |             |             |                      |             |             |
| Median type                       | None        |             |             | None        |                      |             |             |
| Median storage (veh)              |             |             |             |             |                      |             |             |
| Upstream signal (ft)              | 464         |             |             |             |                      |             |             |
| pX, platoon unblocked             |             |             |             |             |                      |             |             |
| vC, conflicting volume            |             |             | 1267        |             | 1578                 | 335         |             |
| vC1, stage 1 conf vol             |             |             |             |             |                      |             |             |
| vC2, stage 2 conf vol             |             |             |             |             |                      |             |             |
| vCu, unblocked vol                |             |             | 1267        |             | 1578                 | 335         |             |
| tC, single (s)                    |             |             | 4.1         |             | 6.8                  | 6.9         |             |
| tC, 2 stage (s)                   |             |             |             |             |                      |             |             |
| tF (s)                            |             |             | 2.2         |             | 3.5                  | 3.3         |             |
| p0 queue free %                   |             |             | 100         |             | 100                  | 86          |             |
| cM capacity (veh/h)               |             |             | 550         |             | 102                  | 667         |             |
| <b>Direction, Lane #</b>          | <b>EB 1</b> | <b>EB 2</b> | <b>EB 3</b> | <b>EB 4</b> | <b>WB 1</b>          | <b>WB 2</b> | <b>NB 1</b> |
| Volume Total                      | 341         | 341         | 341         | 243         | 346                  | 346         | 95          |
| Volume Left                       | 0           | 0           | 0           | 0           | 0                    | 0           | 0           |
| Volume Right                      | 0           | 0           | 0           | 72          | 0                    | 0           | 95          |
| cSH                               | 1700        | 1700        | 1700        | 1700        | 1700                 | 1700        | 667         |
| Volume to Capacity                | 0.20        | 0.20        | 0.20        | 0.14        | 0.20                 | 0.20        | 0.14        |
| Queue Length 95th (ft)            | 0           | 0           | 0           | 0           | 0                    | 0           | 12          |
| Control Delay (s)                 | 0.0         | 0.0         | 0.0         | 0.0         | 0.0                  | 0.0         | 11.3        |
| Lane LOS                          |             |             |             |             |                      |             | B           |
| Approach Delay (s)                | 0.0         |             |             |             | 0.0                  |             | 11.3        |
| Approach LOS                      |             |             |             |             |                      |             | B           |
| <b>Intersection Summary</b>       |             |             |             |             |                      |             |             |
| Average Delay                     |             |             | 0.5         |             |                      |             |             |
| Intersection Capacity Utilization |             |             | 27.2%       |             | ICU Level of Service |             | A           |
| Analysis Period (min)             |             |             | 15          |             |                      |             |             |

202: Arthur F Brady Drive & South Site Driveway  
 2024 Existing SAT Peak Saturday Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 5.5  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↕    | ↕     | ↕    | ↕    |
| Traffic Vol, veh/h       | 100  | 200  | 120  | 80    | 146  | 48   |
| Future Vol, veh/h        | 100  | 200  | 120  | 80    | 146  | 48   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 95   | 95   | 81   | 81    | 88   | 88   |
| Heavy Vehicles, %        | 1    | 1    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 105  | 211  | 148  | 99    | 166  | 55   |

| Major/Minor          | Major1 | Major2 | Minor2 |   |         |
|----------------------|--------|--------|--------|---|---------|
| Conflicting Flow All | 149    | 0      | -      | 0 | 570 150 |
| Stage 1              | -      | -      | -      | - | 149 -   |
| Stage 2              | -      | -      | -      | - | 421 -   |
| Critical Hdwy        | 4.11   | -      | -      | - | 6.4 6.2 |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.4 -   |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.4 -   |
| Follow-up Hdwy       | 2.209  | -      | -      | - | 3.5 3.3 |
| Pot Cap-1 Maneuver   | 1439   | -      | -      | - | 486 902 |
| Stage 1              | -      | -      | -      | - | 884 -   |
| Stage 2              | -      | -      | -      | - | 667 -   |
| Platoon blocked, %   |        | -      | -      | - |         |
| Mov Cap-1 Maneuver   | 1438   | -      | -      | - | 445 900 |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 445 -   |
| Stage 1              | -      | -      | -      | - | 810 -   |
| Stage 2              | -      | -      | -      | - | 666 -   |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.6 | 0  | 15.7 |
| HCM LOS              |     |    | C    |


























| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1438  | -   | -   | -   | 445   | 900   |
| HCM Lane V/C Ratio    | 0.073 | -   | -   | -   | 0.373 | 0.061 |
| HCM Control Delay (s) | 7.7   | 0   | -   | -   | 17.8  | 9.3   |
| HCM Lane LOS          | A     | A   | -   | -   | C     | A     |
| HCM 95th %tile Q(veh) | 0.2   | -   | -   | -   | 1.7   | 0.2   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2026 No-Build Weekday AM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↖↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↖↗  |
| Traffic Volume (vph)              | 0   | 239   | 104   | 90  | 896   | 0   | 0  | 0   | 0   | 408   | 0   | 759   |
| Future Volume (vph)               | 0   | 239   | 104   | 90  | 896   | 0   | 0  | 0   | 0   | 408   | 0   | 759   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 5923  | 1516  | 3173  | 3388  |   |  |   |   | 1698  | 1698  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 5923  | 1516  | 3173  | 3388  |   |  |   |   | 1698  | 1698  | 2814  |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.87  | 0.87  | 0.87  | 0.90   | 0.90  | 0.90  | 0.86  | 0.86  | 0.86  |
| Adj. Flow (vph)                   | 0   | 257   | 112   | 103   | 1030  | 0   | 0  | 0   | 0   | 474   | 0   | 883   |
| RTOR Reduction (vph)              | 0   | 0   | 79  | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 170   |
| Lane Group Flow (vph)             | 0   | 257   | 33  | 103   | 1030  | 0   | 0  | 0   | 0   | 237   | 237   | 713   |
| Heavy Vehicles (%)                | 3%  | 3%  | 3%  | 3%  | 3%  | 3%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 27.9  | 27.9  | 24.8  | 58.7  |   |  |   |   | 25.1  | 25.1  | 25.1  |
| Effective Green, g (s)            |   | 27.9  | 27.9  | 24.8  | 58.7  |   |  |   |   | 25.1  | 25.1  | 25.1  |
| Actuated g/C Ratio                |   | 0.29  | 0.29  | 0.26  | 0.61  |   |  |   |   | 0.26  | 0.26  | 0.26  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 1724  | 441   | 821   | 2075  |   |  |   |   | 444   | 444   | 737   |
| v/s Ratio Prot                    |   | 0.04  | 0.02  | 0.03  | c0.30   |   |  |   |   | 0.14  | 0.14  | c0.25   |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.15  | 0.07  | 0.13  | 0.50  |   |  |   |   | 0.53  | 0.53  | 0.97  |
| Uniform Delay, d1                 |   | 25.2  | 24.6  | 27.2  | 10.3  |   |  |   |   | 30.3  | 30.3  | 35.0  |
| Progression Factor                |   | 1.00  | 1.00  | 0.88  | 1.59  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.1   | 0.1   | 0.1   | 0.3   |   |  |   |   | 2.3   | 2.3   | 25.5  |
| Delay (s)                         |   | 25.2  | 24.7  | 24.1  | 16.8  |   |  |   |   | 32.6  | 32.6  | 60.5  |
| Level of Service                  |   | C   | C   | C   | B   |   |  |   |   | C   | C   | E   |
| Approach Delay (s)                |   | 25.1  |   |   | 17.4  |   |  | 0.0   |   |   | 50.7  |   |
| Approach LOS                      |   | C   |   |   | B   |   |  | A   |   |   | D   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 34.2  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.69  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 95.8  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 61.3%   |   |   | ICU Level of Service  |  |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group






















102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2026 No-Build Weekday AM Peak

|                                   |    |    |  |  |    |  |    |    |    |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |   |   |   |    |   |   |   |   |   |   |   |
| Traffic Volume (vph)              | 110   | 537   | 0   | 0   | 293   | 44  | 693  | 0   | 261   | 0   | 0   | 0   |
| Future Volume (vph)               | 110   | 537   | 0   | 0   | 293   | 44  | 693  | 0   | 261   | 0   | 0   | 0   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 10  | 11  | 12  | 12  | 12  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Lane Util. Factor                 | 0.97  | 0.95  |   |   | 0.91  |   | 0.97   | 0.95  | 0.95  |   |   |   |
| Frt                               | 1.00  | 1.00  |   |   | 0.98  |   | 1.00   | 0.85  | 0.85  |   |   |   |
| Flt Protected                     | 0.95  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (prot)                 | 3236  | 3455  |   |   | 4844  |   | 3400   | 1490  | 1490  |   |   |   |
| Flt Permitted                     | 0.52  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (perm)                 | 1768  | 3455  |   |   | 4844  |   | 3400   | 1490  | 1490  |   |   |   |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.89  | 0.89  | 0.89  | 0.91   | 0.91  | 0.91  | 0.90  | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 118   | 577   | 0   | 0   | 329   | 49  | 762  | 0   | 287   | 0   | 0   | 0   |
| RTOR Reduction (vph)              | 0   | 0   | 0   | 0   | 17  | 0   | 0  | 106   | 106   | 0   | 0   | 0   |
| Lane Group Flow (vph)             | 118   | 577   | 0   | 0   | 361   | 0   | 762  | 38  | 37  | 0   | 0   | 0   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 5%  | 5%  | 5%  | 3%   | 3%  | 3%  | 0%  | 0%  | 0%  |
| Turn Type                         | pm+pt   | NA  |   |   | NA  |   | Split  | NA  | Prot  |   |   |   |
| Protected Phases                  | 1   | 6   |   |   | 2   |   | 3  | 3   | 3   |   |   |   |
| Permitted Phases                  | 6   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             | 41.4  | 27.9  |   |   | 39.2  |   | 25.1   | 25.1  | 25.1  |   |   |   |
| Effective Green, g (s)            | 41.4  | 27.9  |   |   | 39.2  |   | 25.1   | 25.1  | 25.1  |   |   |   |
| Actuated g/C Ratio                | 0.43  | 0.29  |   |   | 0.41  |   | 0.26   | 0.26  | 0.26  |   |   |   |
| Clearance Time (s)                | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Vehicle Extension (s)             | 4.0   | 5.0   |   |   | 5.0   |   | 5.0  | 5.0   | 5.0   |   |   |   |
| Lane Grp Cap (vph)                | 970   | 1006  |   |   | 1982  |   | 890  | 390   | 390   |   |   |   |
| v/s Ratio Prot                    | c0.02   | c0.17   |   |   | c0.07   |   | c0.22  | 0.03  | 0.03  |   |   |   |
| v/s Ratio Perm                    | 0.04  |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         | 0.12  | 0.57  |   |   | 0.18  |   | 0.86   | 0.10  | 0.10  |   |   |   |
| Uniform Delay, d1                 | 16.0  | 28.9  |   |   | 18.1  |   | 33.6   | 26.8  | 26.8  |   |   |   |
| Progression Factor                | 1.26  | 1.23  |   |   | 1.00  |   | 1.00   | 1.00  | 1.00  |   |   |   |
| Incremental Delay, d2             | 0.1   | 1.2   |   |   | 0.1   |   | 8.9  | 0.2   | 0.2   |   |   |   |
| Delay (s)                         | 20.2  | 36.7  |   |   | 18.2  |   | 42.5   | 27.0  | 27.0  |   |   |   |
| Level of Service                  | C   | D   |   |   | B   |   | D  | C   | C   |   |   |   |
| Approach Delay (s)                |   | 33.9  |   |   | 18.2  |   |  | 38.3  |   |   | 0.0   |   |
| Approach LOS                      |   | C   |   |   | B   |   |  | D   |   |   | A   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 33.3  |   |   |   | HCM 2000 Level of Service  |   | C   |   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.52  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 95.8  |   |   |   | Sum of lost time (s)   |   | 18.0  |   |   |   |
| Intersection Capacity Utilization |   |   | 61.3%   |   |   |   | ICU Level of Service   |   | B   |   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

























c Critical Lane Group



103: Woodbury Avenue & Gosling Road  
2026 No-Build Weekday AM Peak






























|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |  |   |  |   |  |  |  |  |  |  |
| Traffic Volume (vph)              | 92  | 38  | 446   | 27  | 13  | 6   | 222  | 173   | 18  | 36  | 286   | 8   |
| Future Volume (vph)               | 92  | 38  | 446   | 27  | 13  | 6   | 222  | 173   | 18  | 36  | 286   | 8   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Fr <sub>t</sub>                   |   | 1.00  | 0.85  |   | 0.98  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |
| Fl <sub>t</sub> Protected         |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 |   | 1706  | 1656  |   | 1605  |   | 3400   | 3456  |   | 1678  | 3355  | 1501  |
| Fl <sub>t</sub> Permitted         |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 |   | 1706  | 1656  |   | 1605  |   | 3400   | 3456  |   | 1678  | 3355  | 1501  |
| Peak-hour factor, PHF             | 0.91  | 0.91  | 0.91  | 0.89  | 0.89  | 0.89  | 0.84   | 0.84  | 0.84  | 0.89  | 0.89  | 0.89  |
| Adj. Flow (vph)                   | 101   | 42  | 490   | 30  | 15  | 7   | 264  | 206   | 21  | 40  | 321   | 9   |
| RTOR Reduction (vph)              | 0   | 0   | 346   | 0   | 5   | 0   | 0  | 5   | 0   | 0   | 0   | 5   |
| Lane Group Flow (vph)             | 0   | 143   | 144   | 0   | 47  | 0   | 264  | 222   | 0   | 40  | 321   | 4   |
| Heavy Vehicles (%)                | 4%  | 4%  | 4%  | 13%   | 13%   | 13%   | 3%   | 3%  | 3%  | 4%  | 4%  | 4%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 9.0   | 21.2  |   | 4.8   |   | 12.2   | 24.8  |   | 4.3   | 16.4  | 31.4  |
| Effective Green, g (s)            |   | 9.0   | 21.2  |   | 4.8   |   | 12.2   | 24.8  |   | 4.3   | 16.4  | 31.4  |
| Actuated g/C Ratio                |   | 0.12  | 0.29  |   | 0.07  |   | 0.17   | 0.34  |   | 0.06  | 0.23  | 0.43  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                |   | 212   | 485   |   | 106   |   | 573  | 1185  |   | 99  | 761   | 651   |
| v/s Ratio Prot                    |   | c0.08   | 0.09  |   | c0.03   |   | c0.08  | 0.06  |   | 0.02  | c0.10   | 0.00  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.67  | 0.30  |   | 0.45  |   | 0.46   | 0.19  |   | 0.40  | 0.42  | 0.01  |
| Uniform Delay, d <sub>1</sub>     |   | 30.3  | 19.8  |   | 32.5  |   | 27.1   | 16.7  |   | 32.8  | 23.9  | 11.6  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d <sub>2</sub> |   | 8.2   | 0.3   |   | 3.0   |   | 0.6  | 0.1   |   | 2.7   | 0.4   | 0.0   |
| Delay (s)                         |   | 38.4  | 20.1  |   | 35.5  |   | 27.7   | 16.8  |   | 35.5  | 24.3  | 11.6  |
| Level of Service                  |   | D   | C   |   | D   |   | C  | B   |   | D   | C   | B   |
| Approach Delay (s)                |   | 24.3  |   |   | 35.5  |   | 22.6   |   |   | 25.2  |   |   |
| Approach LOS                      |   | C   |   |   | D   |   | C  |   |   | C   |   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 24.3  |   |   |   | HCM 2000 Level of Service  |   |   |   | C   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.44  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 72.3  |   |   |   | Sum of lost time (s)   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 57.2%   |   |   |   | ICU Level of Service   |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2026 No-Build Weekday AM Peak

|                                   |  |  |  |  |  |  |   |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |  |  |  |  |  |  |  |  |  |  |  |  |
| Traffic Volume (vph)              | 23  | 3   | 27  | 27  | 0   | 34  | 9   | 329   | 38  | 45  | 665   | 50  |
| Future Volume (vph)               | 23  | 3   | 27  | 27  | 0   | 34  | 9   | 329   | 38  | 45  | 665   | 50  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 16  | 11  | 11  | 11  |
| Grade (%)                         |   | 3%  |   |   | -5%   |   |   | 5%  |   |   | -3%   |   |
| Total Lost time (s)               | 6.0   | 6.0   | 6.0   | 5.5   | 5.5   | 5.5   | 6.0   | 6.0   | 5.5   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 | 0.95  | 0.95  | 1.00  | 0.95  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  |
| Frpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Flpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Frt                               | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  |
| Flt Protected                     | 0.95  | 0.96  | 1.00  | 0.95  | 0.95  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 | 1570  | 1593  | 1479  | 1634  | 1634  | 1539  | 1652  | 3303  | 1733  | 1736  | 3473  | 1554  |
| Flt Permitted                     | 0.95  | 0.96  | 1.00  | 0.95  | 0.95  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 | 1570  | 1593  | 1479  | 1634  | 1634  | 1539  | 1652  | 3303  | 1733  | 1736  | 3473  | 1554  |
| Peak-hour factor, PHF             | 0.82  | 0.82  | 0.82  | 0.65  | 0.65  | 0.65  | 0.85  | 0.85  | 0.85  | 0.98  | 0.98  | 0.98  |
| Adj. Flow (vph)                   | 28  | 4   | 33  | 42  | 0   | 52  | 11  | 387   | 45  | 46  | 679   | 51  |
| RTOR Reduction (vph)              | 0   | 0   | 29  | 0   | 0   | 0   | 0   | 0   | 26  | 0   | 0   | 23  |
| Lane Group Flow (vph)             | 16  | 16  | 4   | 21  | 21  | 52  | 11  | 387   | 19  | 46  | 679   | 28  |
| Confl. Bikes (#/hr)               |   |   |   |   |   |   |   |   | 1   |   |   |   |
| Heavy Vehicles (%)                | 4%  | 4%  | 4%  | 4%  | 4%  | 4%  | 3%  | 3%  | 3%  | 2%  | 2%  | 2%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  | pt+ov   | Prot  | NA  | pt+ov   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 13  | 4   | 4   | 45  | 1   | 6   | 46  | 5   | 2   | 23  |
| Permitted Phases                  |   |   |   |   |   |   |   |   |   |   |   |   |
| Actuated Green, G (s)             | 5.0   | 5.0   | 8.2   | 5.5   | 5.5   | 12.0  | 3.2   | 25.2  | 30.7  | 6.5   | 28.0  | 39.0  |
| Effective Green, g (s)            | 5.0   | 5.0   | 8.2   | 5.5   | 5.5   | 12.0  | 3.2   | 25.2  | 30.7  | 6.5   | 28.0  | 39.0  |
| Actuated g/C Ratio                | 0.07  | 0.07  | 0.12  | 0.08  | 0.08  | 0.17  | 0.05  | 0.36  | 0.43  | 0.09  | 0.39  | 0.55  |
| Clearance Time (s)                | 6.0   | 6.0   |   | 5.5   | 5.5   |   | 6.0   | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                | 110   | 112   | 171   | 126   | 126   | 260   | 74  | 1173  | 750   | 159   | 1371  | 854   |
| v/s Ratio Prot                    | c0.01   | 0.01  | 0.00  | 0.01  | 0.01  | c0.03   | 0.01  | 0.12  | 0.01  | c0.03   | c0.20   | 0.02  |
| v/s Ratio Perm                    |   |   |   |   |   |   |   |   |   |   |   |   |
| v/c Ratio                         | 0.15  | 0.14  | 0.02  | 0.17  | 0.17  | 0.20  | 0.15  | 0.33  | 0.03  | 0.29  | 0.50  | 0.03  |
| Uniform Delay, d1                 | 30.9  | 30.9  | 27.8  | 30.6  | 30.6  | 25.3  | 32.5  | 16.7  | 11.5  | 30.0  | 16.1  | 7.3   |
| Progression Factor                | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             | 0.6   | 0.6   | 0.1   | 0.6   | 0.6   | 0.4   | 0.9   | 0.2   | 0.0   | 1.0   | 0.3   | 0.0   |
| Delay (s)                         | 31.6  | 31.5  | 27.8  | 31.2  | 31.2  | 25.7  | 33.5  | 16.9  | 11.5  | 31.1  | 16.4  | 7.3   |
| Level of Service                  | C   | C   | C   | C   | C   | C   | C   | B   | B   | C   | B   | A   |
| Approach Delay (s)                |   | 29.7  |   |   | 28.2  |   |   | 16.7  |   |   | 16.7  |   |
| Approach LOS                      |   | C   |   |   | C   |   |   | B   |   |   | B   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 18.1  |   |   |   |   |   |   |   |   | B   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.39  |   |   |   |   |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 70.9  |   |   |   |   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 45.8%   |   |   |   |   |   |   |   |   | A   |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |

c Critical Lane Group

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2026 No-Build Weekday AM Peak

|                                   |    |  |  |    |    |  |   |    |  |    |    |    |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|--|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |  |
| Lane Configurations               |   |  |   |   |   |   |   |   |   |   |   |   |  |
| Traffic Volume (vph)              | 103   | 39  | 47  | 3   | 32  | 40  | 66  | 292   | 77  | 2   | 261   | 200   |  |
| Future Volume (vph)               | 103   | 39  | 47  | 3   | 32  | 40  | 66  | 292   | 77  | 2   | 261   | 200   |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11  | 11  | 11  | 14  | 14  | 14  | 11  | 11  | 11  | 11  | 11  | 11  |  |
| Grade (%)                         |   | 5%  |   |   | -5%   |   |   | 0%  |   |   | 0%  |   |  |
| Total Lost time (s)               | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   | 6.5   |  |
| Lane Util. Factor                 | 0.97  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 0.95  |   | 1.00  | 0.95  | 1.00  |  |
| Frpb, ped/bikes                   | 1.00  | 0.99  |   | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Flpb, ped/bikes                   | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Frt                               | 1.00  | 0.92  |   | 1.00  | 0.92  |   | 1.00  | 0.97  |   | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 | 3268  | 1615  |   | 1898  | 1830  |   | 1711  | 3299  |   | 1694  | 3388  | 1516  |  |
| Flt Permitted                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 | 3268  | 1615  |   | 1898  | 1830  |   | 1711  | 3299  |   | 1694  | 3388  | 1516  |  |
| Peak-hour factor, PHF             | 0.73  | 0.73  | 0.73  | 0.65  | 0.65  | 0.65  | 0.75  | 0.75  | 0.75  | 0.97  | 0.97  | 0.97  |  |
| Adj. Flow (vph)                   | 141   | 53  | 64  | 5   | 49  | 62  | 88  | 389   | 103   | 2   | 269   | 206   |  |
| RTOR Reduction (vph)              | 0   | 34  | 0   | 0   | 40  | 0   | 0   | 17  | 0   | 0   | 0   | 104   |  |
| Lane Group Flow (vph)             | 141   | 83  | 0   | 5   | 71  | 0   | 88  | 475   | 0   | 2   | 269   | 102   |  |
| Confl. Bikes (#/hr)               |   |   | 1   |   |   |   |   |   | 1   |   |   |   |  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 4%  | 4%  | 4%  | 2%  | 2%  | 2%  | 3%  | 3%  | 3%  |  |
| Turn Type                         | Split   | NA  |   | Split   | NA  |   | Prot  | NA  |   | Prot  | NA  | pt+ov   |  |
| Protected Phases                  | 3   | 3   |   | 4   | 4   |   | 1   | 6   |   | 5   | 2   | 2 3   |  |
| Permitted Phases                  |   |   |   |   |   |   |   |   |   |   |   |   |  |
| Actuated Green, G (s)             | 9.2   | 9.2   |   | 6.3   | 6.3   |   | 6.8   | 22.1  |   | 0.9   | 16.2  | 31.9  |  |
| Effective Green, g (s)            | 9.2   | 9.2   |   | 6.3   | 6.3   |   | 6.8   | 22.1  |   | 0.9   | 16.2  | 31.9  |  |
| Actuated g/C Ratio                | 0.14  | 0.14  |   | 0.10  | 0.10  |   | 0.11  | 0.34  |   | 0.01  | 0.25  | 0.49  |  |
| Clearance Time (s)                | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   |  |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   |  |
| Lane Grp Cap (vph)                | 466   | 230   |   | 185   | 178   |   | 180   | 1130  |   | 23  | 850   | 749   |  |
| v/s Ratio Prot                    | 0.04  | c0.05   |   | 0.00  | c0.04   |   | c0.05   | c0.14   |   | 0.00  | 0.08  | 0.07  |  |
| v/s Ratio Perm                    |   |   |   |   |   |   |   |   |   |   |   |   |  |
| v/c Ratio                         | 0.30  | 0.36  |   | 0.03  | 0.40  |   | 0.49  | 0.42  |   | 0.09  | 0.32  | 0.14  |  |
| Uniform Delay, d1                 | 24.8  | 25.0  |   | 26.3  | 27.3  |   | 27.2  | 16.3  |   | 31.4  | 19.6  | 8.8   |  |
| Progression Factor                | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             | 0.4   | 1.0   |   | 0.1   | 1.5   |   | 2.1   | 0.3   |   | 1.6   | 0.2   | 0.1   |  |
| Delay (s)                         | 25.1  | 26.0  |   | 26.4  | 28.8  |   | 29.3  | 16.5  |   | 33.0  | 19.9  | 8.9   |  |
| Level of Service                  | C   | C   |   | C   | C   |   | C   | B   |   | C   | B   | A   |  |
| Approach Delay (s)                |   | 25.5  |   |   | 28.7  |   |   | 18.5  |   |   | 15.2  |   |  |
| Approach LOS                      |   | C   |   |   | C   |   |   | B   |   |   | B   |   |  |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |  |
| HCM 2000 Control Delay            |   |   | 19.5  |   | HCM 2000 Level of Service   |   |   |   |   |   | B   |   |  |
| HCM 2000 Volume to Capacity ratio |   |   | 0.48  |   |   |   |   |   |   |   |   |   |  |
| Actuated Cycle Length (s)         |   |   | 64.5  |   | Sum of lost time (s)  |   |   |   |   |   | 28.0  |   |  |
| Intersection Capacity Utilization |   |   | 41.4%   |   | ICU Level of Service  |   |   |   |   |   | A   |   |  |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |  |

c Critical Lane Group

201: Motel 6/North Site & Gosling Road  
2026 No-Build Weekday AM Peak



| Movement                          | EBT  | EBR  | WBL   | WBT  | NBL                  | NBR  |      |
|-----------------------------------|------|------|-------|------|----------------------|------|------|
| Lane Configurations               | ↑↑↑↑ |      |       | ↑↑   |                      | ↗    |      |
| Traffic Volume (veh/h)            | 711  | 87   | 0     | 337  | 0                    | 13   |      |
| Future Volume (Veh/h)             | 711  | 87   | 0     | 337  | 0                    | 13   |      |
| Sign Control                      | Free |      |       | Free | Stop                 |      |      |
| Grade                             | 0%   |      |       | 0%   | 0%                   |      |      |
| Peak Hour Factor                  | 0.97 | 0.97 | 0.89  | 0.89 | 0.46                 | 0.46 |      |
| Hourly flow rate (vph)            | 733  | 90   | 0     | 379  | 0                    | 28   |      |
| <b>Pedestrians</b>                |      |      |       |      |                      |      |      |
| Lane Width (ft)                   |      |      |       |      |                      |      |      |
| Walking Speed (ft/s)              |      |      |       |      |                      |      |      |
| Percent Blockage                  |      |      |       |      |                      |      |      |
| Right turn flare (veh)            |      |      |       |      |                      |      |      |
| Median type                       | None |      |       | None |                      |      |      |
| Median storage (veh)              |      |      |       |      |                      |      |      |
| Upstream signal (ft)              | 464  |      |       |      |                      |      |      |
| pX, platoon unblocked             |      |      |       |      |                      |      |      |
| vC, conflicting volume            |      |      | 823   |      | 968                  | 228  |      |
| vC1, stage 1 conf vol             |      |      |       |      |                      |      |      |
| vC2, stage 2 conf vol             |      |      |       |      |                      |      |      |
| vCu, unblocked vol                |      |      | 823   |      | 968                  | 228  |      |
| tC, single (s)                    |      |      | 4.2   |      | 6.8                  | 6.9  |      |
| tC, 2 stage (s)                   |      |      |       |      |                      |      |      |
| tF (s)                            |      |      | 2.2   |      | 3.5                  | 3.3  |      |
| p0 queue free %                   |      |      | 100   |      | 100                  | 96   |      |
| cM capacity (veh/h)               |      |      | 784   |      | 255                  | 781  |      |
| Direction, Lane #                 | EB 1 | EB 2 | EB 3  | EB 4 | WB 1                 | WB 2 | NB 1 |
| Volume Total                      | 209  | 209  | 209   | 195  | 190                  | 190  | 28   |
| Volume Left                       | 0    | 0    | 0     | 0    | 0                    | 0    | 0    |
| Volume Right                      | 0    | 0    | 0     | 90   | 0                    | 0    | 28   |
| cSH                               | 1700 | 1700 | 1700  | 1700 | 1700                 | 1700 | 781  |
| Volume to Capacity                | 0.12 | 0.12 | 0.12  | 0.11 | 0.11                 | 0.11 | 0.04 |
| Queue Length 95th (ft)            | 0    | 0    | 0     | 0    | 0                    | 0    | 3    |
| Control Delay (s)                 | 0.0  | 0.0  | 0.0   | 0.0  | 0.0                  | 0.0  | 9.8  |
| Lane LOS                          |      |      |       |      |                      |      | A    |
| Approach Delay (s)                | 0.0  |      |       |      | 0.0                  |      | 9.8  |
| Approach LOS                      |      |      |       |      |                      |      | A    |
| <b>Intersection Summary</b>       |      |      |       |      |                      |      |      |
| Average Delay                     |      |      | 0.2   |      |                      |      |      |
| Intersection Capacity Utilization |      |      | 21.8% |      | ICU Level of Service |      | A    |
| Analysis Period (min)             |      |      | 15    |      |                      |      |      |

202: Arthur F Brady Drive & South Site Driveway  
 2026 No-Build Weekday AM Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 4.3  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↑    | ↗     | ↖    | ↗    |
| Traffic Vol, veh/h       | 50   | 87   | 77   | 71    | 82   | 48   |
| Future Vol, veh/h        | 50   | 87   | 77   | 71    | 82   | 48   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 85   | 85   | 84   | 84    | 81   | 81   |
| Heavy Vehicles, %        | 4    | 4    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 59   | 102  | 92   | 85    | 101  | 59   |

| Major/Minor          | Major1 | Major2 | Minor2 |     |     |
|----------------------|--------|--------|--------|-----|-----|
| Conflicting Flow All | 93     | 0      | 0      | 313 | 94  |
| Stage 1              | -      | -      | -      | 93  | -   |
| Stage 2              | -      | -      | -      | 220 | -   |
| Critical Hdwy        | 4.14   | -      | -      | 6.4 | 6.2 |
| Critical Hdwy Stg 1  | -      | -      | -      | 5.4 | -   |
| Critical Hdwy Stg 2  | -      | -      | -      | 5.4 | -   |
| Follow-up Hdwy       | 2.236  | -      | -      | 3.5 | 3.3 |
| Pot Cap-1 Maneuver   | 1489   | -      | -      | 684 | 968 |
| Stage 1              | -      | -      | -      | 936 | -   |
| Stage 2              | -      | -      | -      | 821 | -   |
| Platoon blocked, %   | -      | -      | -      | -   | -   |
| Mov Cap-1 Maneuver   | 1488   | -      | -      | 654 | 966 |
| Mov Cap-2 Maneuver   | -      | -      | -      | 654 | -   |
| Stage 1              | -      | -      | -      | 896 | -   |
| Stage 2              | -      | -      | -      | 820 | -   |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.7 | 0  | 10.6 |
| HCM LOS              |     |    | B    |
























| Minor Lane/Major Mvmt | EBL  | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1488 | -   | -   | -   | 654   | 966   |
| HCM Lane V/C Ratio    | 0.04 | -   | -   | -   | 0.155 | 0.061 |
| HCM Control Delay (s) | 7.5  | 0   | -   | -   | 11.5  | 9     |
| HCM Lane LOS          | A    | A   | -   | -   | B     | A     |
| HCM 95th %tile Q(veh) | 0.1  | -   | -   | -   | 0.5   | 0.2   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2026 No-Build Weekday PM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↘↗  |
| Traffic Volume (vph)              | 0   | 1171  | 586   | 463   | 308   | 0   | 0  | 0   | 0   | 230   | 1   | 114   |
| Future Volume (vph)               | 0   | 1171  | 586   | 463   | 308   | 0   | 0  | 0   | 0   | 230   | 1   | 114   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.94  | 0.94  | 0.94  | 0.92   | 0.92  | 0.92  | 0.94  | 0.94  | 0.94  |
| Adj. Flow (vph)                   | 0   | 1394  | 698   | 493   | 328   | 0   | 0  | 0   | 0   | 245   | 1   | 121   |
| RTOR Reduction (vph)              | 0   | 0   | 358   | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 97  |
| Lane Group Flow (vph)             | 0   | 1394  | 340   | 493   | 328   | 0   | 0  | 0   | 0   | 122   | 124   | 24  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 35.9  | 35.9  | 21.1  | 56.2  |   |  |   |   | 18.9  | 18.9  | 18.9  |
| Effective Green, g (s)            |   | 35.9  | 35.9  | 21.1  | 56.2  |   |  |   |   | 18.9  | 18.9  | 18.9  |
| Actuated g/C Ratio                |   | 0.38  | 0.38  | 0.22  | 0.60  |   |  |   |   | 0.20  | 0.20  | 0.20  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 2309  | 591   | 727   | 2067  |   |  |   |   | 341   | 342   | 566   |
| v/s Ratio Prot                    |   | c0.23   | 0.22  | c0.15   | 0.09  |   |  |   |   | 0.07  | c0.07   | 0.01  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.60  | 0.58  | 0.68  | 0.16  |   |  |   |   | 0.36  | 0.36  | 0.04  |
| Uniform Delay, d1                 |   | 23.3  | 23.0  | 33.3  | 8.4   |   |  |   |   | 32.3  | 32.3  | 30.2  |
| Progression Factor                |   | 1.00  | 1.00  | 1.35  | 0.85  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.7   | 2.2   | 2.5   | 0.1   |   |  |   |   | 1.3   | 1.4   | 0.1   |
| Delay (s)                         |   | 24.0  | 25.1  | 47.6  | 7.2   |   |  |   |   | 33.6  | 33.7  | 30.3  |
| Level of Service                  |   | C   | C   | D   | A   |   |  |   |   | C   | C   | C   |
| Approach Delay (s)                |   | 24.3  |   |   | 31.4  |   |  | 0.0   |   |   | 32.5  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 27.0  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.56  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 93.9  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 71.2%   |   |   | ICU Level of Service  |  |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |






















c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2026 No-Build Weekday PM Peak

|                                   |    |    |  |  |    |  |    |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |   |   |   |    |   |   |  |  |   |   |   |
| Traffic Volume (vph)              | 718   | 683   | 0   | 0   | 629   | 330   | 142  | 0   | 517   | 0   | 0   | 0   |
| Future Volume (vph)               | 718   | 683   | 0   | 0   | 629   | 330   | 142  | 0   | 517   | 0   | 0   | 0   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 10  | 11  | 12  | 12  | 12  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Lane Util. Factor                 | 0.97  | 0.95  |   |   | 0.91  |   | 0.97   | 0.95  | 0.95  |   |   |   |
| Frt                               | 1.00  | 1.00  |   |   | 0.95  |   | 1.00   | 0.85  | 0.85  |   |   |   |
| Flt Protected                     | 0.95  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (prot)                 | 3236  | 3455  |   |   | 4871  |   | 3433   | 1504  | 1504  |   |   |   |
| Flt Permitted                     | 0.19  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (perm)                 | 655   | 3455  |   |   | 4871  |   | 3433   | 1504  | 1504  |   |   |   |
| Peak-hour factor, PHF             | 0.87  | 0.87  | 0.87  | 0.94  | 0.94  | 0.94  | 0.94   | 0.94  | 0.94  | 0.90  | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 825   | 785   | 0   | 0   | 669   | 351   | 151  | 0   | 550   | 0   | 0   | 0   |
| RTOR Reduction (vph)              | 0   | 0   | 0   | 0   | 88  | 0   | 0  | 220   | 220   | 0   | 0   | 0   |
| Lane Group Flow (vph)             | 825   | 785   | 0   | 0   | 932   | 0   | 151  | 55  | 55  | 0   | 0   | 0   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 2%   | 2%  | 2%  | 0%  | 0%  | 0%  |
| Turn Type                         | pm+pt   | NA  |   |   | NA  |   | Split  | NA  | Prot  |   |   |   |
| Protected Phases                  | 1   | 6   |   |   | 2   |   | 3  | 3   | 3   |   |   |   |
| Permitted Phases                  | 6   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             | 57.8  | 35.9  |   |   | 35.1  |   | 18.9   | 18.9  | 18.9  |   |   |   |
| Effective Green, g (s)            | 57.8  | 35.9  |   |   | 35.1  |   | 18.9   | 18.9  | 18.9  |   |   |   |
| Actuated g/C Ratio                | 0.62  | 0.38  |   |   | 0.37  |   | 0.20   | 0.20  | 0.20  |   |   |   |
| Clearance Time (s)                | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Vehicle Extension (s)             | 4.0   | 5.0   |   |   | 5.0   |   | 5.0  | 5.0   | 5.0   |   |   |   |
| Lane Grp Cap (vph)                | 1005  | 1320  |   |   | 1820  |   | 690  | 302   | 302   |   |   |   |
| v/s Ratio Prot                    | c0.19   | 0.23  |   |   | 0.19  |   | c0.04  | 0.04  | 0.04  |   |   |   |
| v/s Ratio Perm                    | c0.31   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         | 0.82  | 0.59  |   |   | 0.51  |   | 0.22   | 0.18  | 0.18  |   |   |   |
| Uniform Delay, d1                 | 16.2  | 23.2  |   |   | 22.8  |   | 31.3   | 31.1  | 31.1  |   |   |   |
| Progression Factor                | 2.29  | 0.46  |   |   | 1.00  |   | 1.00   | 1.00  | 1.00  |   |   |   |
| Incremental Delay, d2             | 4.8   | 0.9   |   |   | 0.5   |   | 0.3  | 0.6   | 0.6   |   |   |   |
| Delay (s)                         | 41.8  | 11.5  |   |   | 23.3  |   | 31.7   | 31.7  | 31.7  |   |   |   |
| Level of Service                  | D   | B   |   |   | C   |   | C  | C   | C   |   |   |   |
| Approach Delay (s)                |   | 27.1  |   |   | 23.3  |   |  | 31.7  |   |   | 0.0   |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | C   |   |   | A   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 26.9  |   |   |   | HCM 2000 Level of Service  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.68  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 93.9  |   |   |   | Sum of lost time (s)   |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 71.2%   |   |   |   | ICU Level of Service   |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2026 No-Build Weekday PM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |  |   |  |   |  |  |  |  |  |  |
| Traffic Volume (vph)              | 89  | 61  | 505   | 61  | 56  | 49  | 358  | 484   | 34  | 31  | 473   | 122   |
| Future Volume (vph)               | 89  | 61  | 505   | 61  | 56  | 49  | 358  | 484   | 34  | 31  | 473   | 122   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frbp, ped/bikes                   |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Flpb, ped/bikes                   |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Frt                               |   | 1.00  | 0.85  |   | 0.96  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.98  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 |   | 1749  | 1689  |   | 1756  |   | 3467   | 3534  |   | 1711  | 3421  | 1531  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.98  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 |   | 1749  | 1689  |   | 1756  |   | 3467   | 3534  |   | 1711  | 3421  | 1531  |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.80  | 0.80  | 0.80  | 0.96   | 0.96  | 0.96  | 0.97  | 0.97  | 0.97  |
| Adj. Flow (vph)                   | 99  | 68  | 561   | 76  | 70  | 61  | 373  | 504   | 35  | 32  | 488   | 126   |
| RTOR Reduction (vph)              | 0   | 0   | 424   | 0   | 13  | 0   | 0  | 3   | 0   | 0   | 0   | 74  |
| Lane Group Flow (vph)             | 0   | 167   | 137   | 0   | 194   | 0   | 373  | 536   | 0   | 32  | 488   | 52  |
| Confl. Bikes (#/hr)               |   |   |   |   |   |   |  |   | 2   |   |   |   |
| Heavy Vehicles (%)                | 2%  | 2%  | 2%  | 2%  | 2%  | 2%  | 1%   | 1%  | 1%  | 2%  | 2%  | 2%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 8.4   | 22.1  |   | 15.0  |   | 13.7   | 34.3  |   | 2.9   | 23.0  | 37.4  |
| Effective Green, g (s)            |   | 8.4   | 22.1  |   | 15.0  |   | 13.7   | 34.3  |   | 2.9   | 23.0  | 37.4  |
| Actuated g/C Ratio                |   | 0.09  | 0.24  |   | 0.17  |   | 0.15   | 0.38  |   | 0.03  | 0.25  | 0.41  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                |   | 162   | 411   |   | 290   |   | 524  | 1337  |   | 54  | 868   | 632   |
| v/s Ratio Prot                    |   | c0.10   | 0.08  |   | c0.11   |   | c0.11  | 0.15  |   | 0.02  | c0.14   | 0.03  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 1.03  | 0.33  |   | 0.67  |   | 0.71   | 0.40  |   | 0.59  | 0.56  | 0.08  |
| Uniform Delay, d1                 |   | 41.1  | 28.2  |   | 35.5  |   | 36.6   | 20.6  |   | 43.3  | 29.4  | 16.2  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 79.1  | 0.5   |   | 6.0   |   | 4.5  | 0.2   |   | 16.2  | 0.8   | 0.1   |
| Delay (s)                         |   | 120.2   | 28.7  |   | 41.5  |   | 41.1   | 20.8  |   | 59.5  | 30.3  | 16.2  |
| Level of Service                  |   | F   | C   |   | D   |   | D  | C   |   | E   | C   | B   |
| Approach Delay (s)                |   | 49.7  |   |   | 41.5  |   | 29.1   |   |   | 29.0  |   |   |
| Approach LOS                      |   | D   |   |   | D   |   | C  |   |   | C   |   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 36.1  |   |   |   | HCM 2000 Level of Service  |   |   |   | D   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.64  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 90.6  |   |   |   | Sum of lost time (s)   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 68.2%   |   |   |   | ICU Level of Service   |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |




104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2026 No-Build Weekday PM Peak

| Movement                          | EBL   | EBT  | EBR   | WBL   | WBT  | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR                       |      |
|-----------------------------------|-------|------|-------|-------|------|-------|------|-------|-------|-------|-------|---------------------------|------|
| Lane Configurations               |       |      |       |       |      |       |      |       |       |       |       |                           |      |
| Traffic Volume (vph)              | 117   | 19   | 61    | 106   | 16   | 95    | 29   | 691   | 100   | 78    | 710   | 29                        |      |
| Future Volume (vph)               | 117   | 19   | 61    | 106   | 16   | 95    | 29   | 691   | 100   | 78    | 710   | 29                        |      |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900  | 1900 | 1900  | 1900 | 1900  | 1900  | 1900  | 1900  | 1900                      |      |
| Lane Width                        | 11    | 11   | 11    | 11    | 11   | 11    | 11   | 11    | 16    | 11    | 11    | 11                        |      |
| Grade (%)                         |       | 3%   |       |       | -5%  |       |      | 5%    |       |       | -3%   |                           |      |
| Total Lost time (s)               | 6.0   | 6.0  | 6.0   | 5.5   | 5.5  | 5.5   | 6.0  | 6.0   | 5.5   | 5.5   | 6.0   | 6.0                       |      |
| Lane Util. Factor                 | 0.95  | 0.95 | 1.00  | 0.95  | 0.95 | 1.00  | 1.00 | 0.95  | 1.00  | 1.00  | 0.95  | 1.00                      |      |
| Frt                               | 1.00  | 1.00 | 0.85  | 1.00  | 1.00 | 0.85  | 1.00 | 1.00  | 0.85  | 1.00  | 1.00  | 0.85                      |      |
| Flt Protected                     | 0.95  | 0.97 | 1.00  | 0.95  | 0.96 | 1.00  | 0.95 | 1.00  | 1.00  | 0.95  | 1.00  | 1.00                      |      |
| Satd. Flow (prot)                 | 1633  | 1659 | 1424  | 1682  | 1708 | 1584  | 1684 | 3369  | 1767  | 1753  | 3507  | 1569                      |      |
| Flt Permitted                     | 0.95  | 0.97 | 1.00  | 0.95  | 0.96 | 1.00  | 0.95 | 1.00  | 1.00  | 0.95  | 1.00  | 1.00                      |      |
| Satd. Flow (perm)                 | 1633  | 1659 | 1424  | 1682  | 1708 | 1584  | 1684 | 3369  | 1767  | 1753  | 3507  | 1569                      |      |
| Peak-hour factor, PHF             | 0.86  | 0.86 | 0.86  | 0.77  | 0.77 | 0.77  | 0.87 | 0.87  | 0.87  | 0.94  | 0.94  | 0.94                      |      |
| Adj. Flow (vph)                   | 136   | 22   | 71    | 138   | 21   | 123   | 33   | 794   | 115   | 83    | 755   | 31                        |      |
| RTOR Reduction (vph)              | 0     | 0    | 59    | 0     | 0    | 0     | 0    | 0     | 63    | 0     | 0     | 13                        |      |
| Lane Group Flow (vph)             | 79    | 79   | 12    | 79    | 80   | 123   | 33   | 794   | 52    | 83    | 755   | 18                        |      |
| Heavy Vehicles (%)                | 0%    | 0%   | 8%    | 1%    | 1%   | 1%    | 1%   | 1%    | 1%    | 1%    | 1%    | 1%                        |      |
| Turn Type                         | Split | NA   | pt+ov | Split | NA   | pt+ov | Prot | NA    | pt+ov | Prot  | NA    | pt+ov                     |      |
| Protected Phases                  | 3     | 3    | 13    | 4     | 4    | 45    | 1    | 6     | 46    | 5     | 2     | 23                        |      |
| Permitted Phases                  |       |      |       |       |      |       |      |       |       |       |       |                           |      |
| Actuated Green, G (s)             | 7.9   | 7.9  | 12.6  | 8.1   | 8.1  | 22.8  | 4.7  | 24.6  | 32.7  | 9.2   | 28.6  | 42.5                      |      |
| Effective Green, g (s)            | 7.9   | 7.9  | 12.6  | 8.1   | 8.1  | 22.8  | 4.7  | 24.6  | 32.7  | 9.2   | 28.6  | 42.5                      |      |
| Actuated g/C Ratio                | 0.11  | 0.11 | 0.17  | 0.11  | 0.11 | 0.31  | 0.06 | 0.34  | 0.45  | 0.13  | 0.39  | 0.58                      |      |
| Clearance Time (s)                | 6.0   | 6.0  |       | 5.5   | 5.5  |       | 6.0  | 6.0   |       | 5.5   | 6.0   |                           |      |
| Vehicle Extension (s)             | 3.0   | 3.0  |       | 3.0   | 3.0  |       | 3.0  | 3.0   |       | 3.0   | 3.0   |                           |      |
| Lane Grp Cap (vph)                | 177   | 180  | 246   | 187   | 190  | 496   | 108  | 1138  | 793   | 221   | 1377  | 915                       |      |
| v/s Ratio Prot                    | c0.05 | 0.05 | 0.01  | c0.05 | 0.05 | 0.08  | 0.02 | c0.24 | 0.03  | c0.05 | c0.22 | 0.01                      |      |
| v/s Ratio Perm                    |       |      |       |       |      |       |      |       |       |       |       |                           |      |
| v/c Ratio                         | 0.45  | 0.44 | 0.05  | 0.42  | 0.42 | 0.25  | 0.31 | 0.70  | 0.07  | 0.38  | 0.55  | 0.02                      |      |
| Uniform Delay, d1                 | 30.4  | 30.4 | 25.1  | 30.2  | 30.2 | 18.6  | 32.5 | 20.9  | 11.4  | 29.2  | 17.1  | 6.4                       |      |
| Progression Factor                | 1.00  | 1.00 | 1.00  | 1.00  | 1.00 | 1.00  | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  | 1.00                      |      |
| Incremental Delay, d2             | 1.8   | 1.7  | 0.1   | 1.5   | 1.5  | 0.3   | 1.6  | 1.9   | 0.0   | 1.1   | 0.4   | 0.0                       |      |
| Delay (s)                         | 32.2  | 32.1 | 25.2  | 31.7  | 31.7 | 18.9  | 34.1 | 22.8  | 11.4  | 30.2  | 17.6  | 6.4                       |      |
| Level of Service                  | C     | C    | C     | C     | C    | B     | C    | C     | B     | C     | B     | A                         |      |
| Approach Delay (s)                |       | 30.0 |       |       | 26.1 |       |      | 21.8  |       |       | 18.4  |                           |      |
| Approach LOS                      |       | C    |       |       | C    |       |      | C     |       |       | B     |                           |      |
| <b>Intersection Summary</b>       |       |      |       |       |      |       |      |       |       |       |       |                           |      |
| HCM 2000 Control Delay            |       |      | 21.8  |       |      |       |      |       |       |       |       | HCM 2000 Level of Service | C    |
| HCM 2000 Volume to Capacity ratio |       |      | 0.59  |       |      |       |      |       |       |       |       |                           |      |
| Actuated Cycle Length (s)         |       |      | 72.8  |       |      |       |      |       |       |       |       | Sum of lost time (s)      | 25.5 |
| Intersection Capacity Utilization |       |      | 50.8% |       |      |       |      |       |       |       |       | ICU Level of Service      | A    |
| Analysis Period (min)             |       |      | 15    |       |      |       |      |       |       |       |       |                           |      |
| c Critical Lane Group             |       |      |       |       |      |       |      |       |       |       |       |                           |      |

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2026 No-Build Weekday PM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT  | WBR  | NBL                       | NBT   | NBR  | SBL  | SBT   | SBR   |
|-----------------------------------|-------|-------|-------|-------|------|------|---------------------------|-------|------|------|-------|-------|
| Lane Configurations               |       |       |       |       |      |      |                           |       |      |      |       |       |
| Traffic Volume (vph)              | 217   | 72    | 100   | 200   | 95   | 17   | 100                       | 468   | 145  | 17   | 655   | 383   |
| Future Volume (vph)               | 217   | 72    | 100   | 200   | 95   | 17   | 100                       | 468   | 145  | 17   | 655   | 383   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900 | 1900 | 1900                      | 1900  | 1900 | 1900 | 1900  | 1900  |
| Lane Width                        | 11    | 11    | 11    | 14    | 14   | 14   | 11                        | 11    | 11   | 11   | 11    | 11    |
| Grade (%)                         |       | 5%    |       |       | -5%  |      |                           | 0%    |      |      | 0%    |       |
| Total Lost time (s)               | 6.5   | 6.5   |       | 6.5   | 6.5  |      | 6.5                       | 6.5   |      | 6.5  | 6.5   | 6.5   |
| Lane Util. Factor                 | 0.97  | 1.00  |       | 1.00  | 1.00 |      | 1.00                      | 0.95  |      | 1.00 | 0.95  | 1.00  |
| Frt                               | 1.00  | 0.91  |       | 1.00  | 0.98 |      | 1.00                      | 0.96  |      | 1.00 | 1.00  | 0.85  |
| Flt Protected                     | 0.95  | 1.00  |       | 0.95  | 1.00 |      | 0.95                      | 1.00  |      | 0.95 | 1.00  | 1.00  |
| Satd. Flow (prot)                 | 3268  | 1618  |       | 1954  | 2009 |      | 1728                      | 3332  |      | 1728 | 3455  | 1546  |
| Flt Permitted                     | 0.95  | 1.00  |       | 0.95  | 1.00 |      | 0.95                      | 1.00  |      | 0.95 | 1.00  | 1.00  |
| Satd. Flow (perm)                 | 3268  | 1618  |       | 1954  | 2009 |      | 1728                      | 3332  |      | 1728 | 3455  | 1546  |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.91  | 0.91 | 0.91 | 0.88                      | 0.88  | 0.88 | 0.90 | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 241   | 80    | 111   | 220   | 104  | 19   | 114                       | 532   | 165  | 19   | 728   | 426   |
| RTOR Reduction (vph)              | 0     | 41    | 0     | 0     | 5    | 0    | 0                         | 20    | 0    | 0    | 0     | 220   |
| Lane Group Flow (vph)             | 241   | 150   | 0     | 220   | 118  | 0    | 114                       | 677   | 0    | 19   | 728   | 206   |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 1%    | 1%   | 1%   | 1%                        | 1%    | 1%   | 1%   | 1%    | 1%    |
| Turn Type                         | Split | NA    |       | Split | NA   |      | Prot                      | NA    |      | Prot | NA    | pt+ov |
| Protected Phases                  | 3     | 3     |       | 4     | 4    |      | 1                         | 6     |      | 5    | 2     | 2 3   |
| Permitted Phases                  |       |       |       |       |      |      |                           |       |      |      |       |       |
| Actuated Green, G (s)             | 11.2  | 11.2  |       | 15.0  | 15.0 |      | 10.6                      | 37.9  |      | 2.7  | 30.0  | 47.7  |
| Effective Green, g (s)            | 11.2  | 11.2  |       | 15.0  | 15.0 |      | 10.6                      | 37.9  |      | 2.7  | 30.0  | 47.7  |
| Actuated g/C Ratio                | 0.11  | 0.11  |       | 0.15  | 0.15 |      | 0.11                      | 0.38  |      | 0.03 | 0.30  | 0.48  |
| Clearance Time (s)                | 6.5   | 6.5   |       | 6.5   | 6.5  |      | 6.5                       | 6.5   |      | 6.5  | 6.5   | 6.5   |
| Vehicle Extension (s)             | 3.0   | 3.0   |       | 3.0   | 3.0  |      | 3.0                       | 3.0   |      | 3.0  | 3.0   | 3.0   |
| Lane Grp Cap (vph)                | 370   | 183   |       | 296   | 305  |      | 185                       | 1279  |      | 47   | 1050  | 747   |
| v/s Ratio Prot                    | 0.07  | c0.09 |       | c0.11 | 0.06 |      | c0.07                     | c0.20 |      | 0.01 | c0.21 | 0.13  |
| v/s Ratio Perm                    |       |       |       |       |      |      |                           |       |      |      |       |       |
| v/c Ratio                         | 0.65  | 0.82  |       | 0.74  | 0.39 |      | 0.62                      | 0.53  |      | 0.40 | 0.69  | 0.28  |
| Uniform Delay, d1                 | 41.9  | 42.8  |       | 40.0  | 37.7 |      | 42.1                      | 23.5  |      | 47.2 | 30.3  | 15.2  |
| Progression Factor                | 1.00  | 1.00  |       | 1.00  | 1.00 |      | 1.00                      | 1.00  |      | 1.00 | 1.00  | 1.00  |
| Incremental Delay, d2             | 4.1   | 24.6  |       | 9.7   | 0.8  |      | 6.0                       | 0.4   |      | 5.6  | 2.0   | 0.2   |
| Delay (s)                         | 46.0  | 67.4  |       | 49.7  | 38.5 |      | 48.1                      | 23.9  |      | 52.8 | 32.3  | 15.4  |
| Level of Service                  | D     | E     |       | D     | D    |      | D                         | C     |      | D    | C     | B     |
| Approach Delay (s)                |       | 55.4  |       |       | 45.7 |      |                           | 27.3  |      |      | 26.5  |       |
| Approach LOS                      |       | E     |       |       | D    |      |                           | C     |      |      | C     |       |
| <b>Intersection Summary</b>       |       |       |       |       |      |      |                           |       |      |      |       |       |
| HCM 2000 Control Delay            |       |       | 33.6  |       |      |      | HCM 2000 Level of Service |       |      |      | C     |       |
| HCM 2000 Volume to Capacity ratio |       |       | 0.68  |       |      |      |                           |       |      |      |       |       |
| Actuated Cycle Length (s)         |       |       | 98.7  |       |      |      | Sum of lost time (s)      |       |      | 28.0 |       |       |
| Intersection Capacity Utilization |       |       | 66.3% |       |      |      | ICU Level of Service      |       |      | C    |       |       |
| Analysis Period (min)             |       |       | 15    |       |      |      |                           |       |      |      |       |       |
| c Critical Lane Group             |       |       |       |       |      |      |                           |       |      |      |       |       |

201: Motel 6/North Site & Gosling Road  
 2026 No-Build Weekday PM Peak



| Movement                          | EBT  | EBR  | WBL   | WBT  | NBL                  | NBR  |      |
|-----------------------------------|------|------|-------|------|----------------------|------|------|
| Lane Configurations               | ↑↑↑↑ |      |       | ↑↑   |                      | ↗    |      |
| Traffic Volume (veh/h)            | 1105 | 95   | 0     | 959  | 0                    | 31   |      |
| Future Volume (Veh/h)             | 1105 | 95   | 0     | 959  | 0                    | 31   |      |
| Sign Control                      | Free |      |       | Free | Stop                 |      |      |
| Grade                             | 0%   |      |       | 0%   | 0%                   |      |      |
| Peak Hour Factor                  | 0.94 | 0.94 | 0.98  | 0.97 | 0.72                 | 0.72 |      |
| Hourly flow rate (vph)            | 1176 | 101  | 0     | 989  | 0                    | 43   |      |
| <b>Pedestrians</b>                |      |      |       |      |                      |      |      |
| Lane Width (ft)                   |      |      |       |      |                      |      |      |
| Walking Speed (ft/s)              |      |      |       |      |                      |      |      |
| Percent Blockage                  |      |      |       |      |                      |      |      |
| Right turn flare (veh)            |      |      |       |      |                      |      |      |
| Median type                       | None |      |       | None |                      |      |      |
| Median storage (veh)              |      |      |       |      |                      |      |      |
| Upstream signal (ft)              | 464  |      |       |      |                      |      |      |
| pX, platoon unblocked             |      |      |       |      |                      |      |      |
| vC, conflicting volume            |      |      | 1277  |      | 1721                 | 344  |      |
| vC1, stage 1 conf vol             |      |      |       |      |                      |      |      |
| vC2, stage 2 conf vol             |      |      |       |      |                      |      |      |
| vCu, unblocked vol                |      |      | 1277  |      | 1721                 | 344  |      |
| tC, single (s)                    |      |      | 4.1   |      | 6.8                  | 6.9  |      |
| tC, 2 stage (s)                   |      |      |       |      |                      |      |      |
| tF (s)                            |      |      | 2.2   |      | 3.5                  | 3.3  |      |
| p0 queue free %                   |      |      | 100   |      | 100                  | 93   |      |
| cM capacity (veh/h)               |      |      | 545   |      | 82                   | 657  |      |
| Direction, Lane #                 | EB 1 | EB 2 | EB 3  | EB 4 | WB 1                 | WB 2 | NB 1 |
| Volume Total                      | 336  | 336  | 336   | 269  | 494                  | 494  | 43   |
| Volume Left                       | 0    | 0    | 0     | 0    | 0                    | 0    | 0    |
| Volume Right                      | 0    | 0    | 0     | 101  | 0                    | 0    | 43   |
| cSH                               | 1700 | 1700 | 1700  | 1700 | 1700                 | 1700 | 657  |
| Volume to Capacity                | 0.20 | 0.20 | 0.20  | 0.16 | 0.29                 | 0.29 | 0.07 |
| Queue Length 95th (ft)            | 0    | 0    | 0     | 0    | 0                    | 0    | 5    |
| Control Delay (s)                 | 0.0  | 0.0  | 0.0   | 0.0  | 0.0                  | 0.0  | 10.9 |
| Lane LOS                          |      |      |       |      |                      |      | B    |
| Approach Delay (s)                | 0.0  |      |       |      | 0.0                  |      | 10.9 |
| Approach LOS                      |      |      |       |      |                      |      | B    |
| <b>Intersection Summary</b>       |      |      |       |      |                      |      |      |
| Average Delay                     |      |      | 0.2   |      |                      |      |      |
| Intersection Capacity Utilization |      |      | 29.8% |      | ICU Level of Service |      | A    |
| Analysis Period (min)             |      |      | 15    |      |                      |      |      |

202: Arthur F Brady Drive & South Site Driveway  
 2026 No-Build Weekday PM Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 4.8  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↕    | ↕     | ↕    | ↕    |
| Traffic Vol, veh/h       | 67   | 178  | 239  | 72    | 111  | 67   |
| Future Vol, veh/h        | 67   | 178  | 239  | 72    | 111  | 67   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 97   | 97   | 80   | 80    | 74   | 74   |
| Heavy Vehicles, %        | 0    | 0    | 0    | 0     | 1    | 1    |
| Mvmt Flow                | 69   | 184  | 299  | 90    | 150  | 91   |

| Major/Minor          | Major1 | Major2 | Minor2 |   |             |
|----------------------|--------|--------|--------|---|-------------|
| Conflicting Flow All | 300    | 0      | -      | 0 | 622 301     |
| Stage 1              | -      | -      | -      | - | 300 -       |
| Stage 2              | -      | -      | -      | - | 322 -       |
| Critical Hdwy        | 4.1    | -      | -      | - | 6.41 6.21   |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.41 -      |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.41 -      |
| Follow-up Hdwy       | 2.2    | -      | -      | - | 3.509 3.309 |
| Pot Cap-1 Maneuver   | 1273   | -      | -      | - | 452 741     |
| Stage 1              | -      | -      | -      | - | 754 -       |
| Stage 2              | -      | -      | -      | - | 737 -       |
| Platoon blocked, %   |        | -      | -      | - |             |
| Mov Cap-1 Maneuver   | 1272   | -      | -      | - | 424 739     |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 424 -       |
| Stage 1              | -      | -      | -      | - | 708 -       |
| Stage 2              | -      | -      | -      | - | 736 -       |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.2 | 0  | 15.3 |
| HCM LOS              |     |    | C    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1272  | -   | -   | -   | 424   | 739   |
| HCM Lane V/C Ratio    | 0.054 | -   | -   | -   | 0.354 | 0.123 |
| HCM Control Delay (s) | 8     | 0   | -   | -   | 18.1  | 10.6  |
| HCM Lane LOS          | A     | A   | -   | -   | C     | B     |
| HCM 95th %tile Q(veh) | 0.2   | -   | -   | -   | 1.6   | 0.4   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2026 No-Build Saturday Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↘↗  |
| Traffic Volume (vph)              | 0   | 304   | 68  | 366   | 197   | 0   | 0  | 0   | 0   | 317   | 1   | 52  |
| Future Volume (vph)               | 0   | 304   | 68  | 366   | 197   | 0   | 0  | 0   | 0   | 317   | 1   | 52  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1702  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1702  | 2814  |
| Peak-hour factor, PHF             | 0.92  | 0.92  | 0.92  | 0.85  | 0.85  | 0.85  | 0.92   | 0.92  | 0.92  | 0.87  | 0.87  | 0.87  |
| Adj. Flow (vph)                   | 0   | 330   | 74  | 431   | 232   | 0   | 0  | 0   | 0   | 364   | 1   | 60  |
| RTOR Reduction (vph)              | 0   | 0   | 50  | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 45  |
| Lane Group Flow (vph)             | 0   | 330   | 24  | 431   | 232   | 0   | 0  | 0   | 0   | 182   | 183   | 15  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 27.5  | 27.5  | 18.4  | 51.4  |   |  |   |   | 21.0  | 21.0  | 21.0  |
| Effective Green, g (s)            |   | 27.5  | 27.5  | 18.4  | 51.4  |   |  |   |   | 21.0  | 21.0  | 21.0  |
| Actuated g/C Ratio                |   | 0.32  | 0.32  | 0.22  | 0.61  |   |  |   |   | 0.25  | 0.25  | 0.25  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 1956  | 500   | 701   | 2091  |   |  |   |   | 420   | 420   | 696   |
| v/s Ratio Prot                    |   | c0.05   | 0.02  | c0.13   | c0.07   |   |  |   |   | 0.11  | c0.11   | 0.01  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.17  | 0.05  | 0.61  | 0.11  |   |  |   |   | 0.43  | 0.44  | 0.02  |
| Uniform Delay, d1                 |   | 20.5  | 19.7  | 30.0  | 7.1   |   |  |   |   | 26.9  | 27.0  | 24.2  |
| Progression Factor                |   | 1.00  | 1.00  | 1.43  | 0.79  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.1   | 0.1   | 1.8   | 0.0   |   |  |   |   | 1.5   | 1.5   | 0.0   |
| Delay (s)                         |   | 20.6  | 19.8  | 44.6  | 5.6   |   |  |   |   | 28.4  | 28.5  | 24.2  |
| Level of Service                  |   | C   | B   | D   | A   |   |  |   |   | C   | C   | C   |
| Approach Delay (s)                |   | 20.5  |   |   | 31.0  |   |  | 0.0   |   |   | 27.8  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 27.2  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.36  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 84.9  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 54.9%   |   |   | ICU Level of Service  |  |   |   | A   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |






















c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2026 No-Build Saturday Peak

| Movement                          | EBL   | EBT   | EBR   | WBL  | WBT   | WBR  | NBL                       | NBT   | NBR  | SBL  | SBT  | SBR  |
|-----------------------------------|-------|-------|-------|------|-------|------|---------------------------|-------|------|------|------|------|
| Lane Configurations               |       |       |       |      |       |      |                           |       |      |      |      |      |
| Traffic Volume (vph)              | 81    | 540   | 0     | 0    | 482   | 190  | 81                        | 3     | 661  | 0    | 0    | 0    |
| Future Volume (vph)               | 81    | 540   | 0     | 0    | 482   | 190  | 81                        | 3     | 661  | 0    | 0    | 0    |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900 | 1900  | 1900 | 1900                      | 1900  | 1900 | 1900 | 1900 | 1900 |
| Lane Width                        | 10    | 11    | 12    | 12   | 12    | 12   | 12                        | 12    | 12   | 12   | 12   | 12   |
| Total Lost time (s)               | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0   | 6.0  |      |      |      |
| Lane Util. Factor                 | 0.97  | 0.95  |       |      | 0.91  |      | 0.97                      | 0.95  | 0.95 |      |      |      |
| Frt                               | 1.00  | 1.00  |       |      | 0.96  |      | 1.00                      | 0.85  | 0.85 |      |      |      |
| Flt Protected                     | 0.95  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00  | 1.00 |      |      |      |
| Satd. Flow (prot)                 | 3236  | 3455  |       |      | 4918  |      | 3467                      | 1521  | 1519 |      |      |      |
| Flt Permitted                     | 0.37  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00  | 1.00 |      |      |      |
| Satd. Flow (perm)                 | 1265  | 3455  |       |      | 4918  |      | 3467                      | 1521  | 1519 |      |      |      |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.95 | 0.95  | 0.95 | 0.96                      | 0.96  | 0.96 | 0.90 | 0.90 | 0.90 |
| Adj. Flow (vph)                   | 87    | 581   | 0     | 0    | 507   | 200  | 84                        | 3     | 689  | 0    | 0    | 0    |
| RTOR Reduction (vph)              | 0     | 0     | 0     | 0    | 64    | 0    | 0                         | 260   | 259  | 0    | 0    | 0    |
| Lane Group Flow (vph)             | 87    | 581   | 0     | 0    | 643   | 0    | 84                        | 88    | 85   | 0    | 0    | 0    |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 1%   | 1%    | 1%   | 1%                        | 1%    | 1%   | 0%   | 0%   | 0%   |
| Turn Type                         | pm+pt | NA    |       |      | NA    |      | Split                     | NA    | Prot |      |      |      |
| Protected Phases                  | 1     | 6     |       |      | 2     |      | 3                         | 3     | 3    |      |      |      |
| Permitted Phases                  | 6     |       |       |      |       |      |                           |       |      |      |      |      |
| Actuated Green, G (s)             | 40.4  | 27.5  |       |      | 33.0  |      | 21.0                      | 21.0  | 21.0 |      |      |      |
| Effective Green, g (s)            | 40.4  | 27.5  |       |      | 33.0  |      | 21.0                      | 21.0  | 21.0 |      |      |      |
| Actuated g/C Ratio                | 0.48  | 0.32  |       |      | 0.39  |      | 0.25                      | 0.25  | 0.25 |      |      |      |
| Clearance Time (s)                | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0   | 6.0  |      |      |      |
| Vehicle Extension (s)             | 4.0   | 5.0   |       |      | 5.0   |      | 5.0                       | 5.0   | 5.0  |      |      |      |
| Lane Grp Cap (vph)                | 901   | 1119  |       |      | 1911  |      | 857                       | 376   | 375  |      |      |      |
| v/s Ratio Prot                    | c0.01 | c0.17 |       |      | c0.13 |      | 0.02                      | c0.06 | 0.06 |      |      |      |
| v/s Ratio Perm                    | 0.03  |       |       |      |       |      |                           |       |      |      |      |      |
| v/c Ratio                         | 0.10  | 0.52  |       |      | 0.34  |      | 0.10                      | 0.23  | 0.23 |      |      |      |
| Uniform Delay, d1                 | 12.0  | 23.3  |       |      | 18.2  |      | 24.6                      | 25.5  | 25.5 |      |      |      |
| Progression Factor                | 1.18  | 1.05  |       |      | 1.00  |      | 1.00                      | 1.00  | 1.00 |      |      |      |
| Incremental Delay, d2             | 0.1   | 0.8   |       |      | 0.2   |      | 0.1                       | 0.7   | 0.6  |      |      |      |
| Delay (s)                         | 14.3  | 25.3  |       |      | 18.5  |      | 24.7                      | 26.2  | 26.1 |      |      |      |
| Level of Service                  | B     | C     |       |      | B     |      | C                         | C     | C    |      |      |      |
| Approach Delay (s)                |       | 23.9  |       |      | 18.5  |      |                           | 26.0  |      |      | 0.0  |      |
| Approach LOS                      |       | C     |       |      | B     |      |                           | C     |      |      | A    |      |
| <b>Intersection Summary</b>       |       |       |       |      |       |      |                           |       |      |      |      |      |
| HCM 2000 Control Delay            |       |       | 22.9  |      |       |      | HCM 2000 Level of Service |       |      | C    |      |      |
| HCM 2000 Volume to Capacity ratio |       |       | 0.32  |      |       |      |                           |       |      |      |      |      |
| Actuated Cycle Length (s)         |       |       | 84.9  |      |       |      | Sum of lost time (s)      |       |      | 18.0 |      |      |
| Intersection Capacity Utilization |       |       | 54.9% |      |       |      | ICU Level of Service      |       |      | A    |      |      |
| Analysis Period (min)             |       |       | 15    |      |       |      |                           |       |      |      |      |      |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2026 No-Build Saturday Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|--|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |  |
| Lane Configurations               |   |  |  |   |  |   |  |  |  |  |  |  |  |
| Traffic Volume (vph)              | 56  | 38  | 342   | 24  | 43  | 65  | 298  | 393   | 20  | 35  | 448   | 61  |  |
| Future Volume (vph)               | 56  | 38  | 342   | 24  | 43  | 65  | 298  | 393   | 20  | 35  | 448   | 61  |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |  |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |  |
| Frt                               |   | 1.00  | 0.85  |   | 0.93  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 |   | 1766  | 1706  |   | 1758  |   | 3467   | 3548  |   | 1728  | 3455  | 1546  |  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 |   | 1766  | 1706  |   | 1758  |   | 3467   | 3548  |   | 1728  | 3455  | 1546  |  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.85  | 0.85  | 0.85  | 0.91   | 0.91  | 0.91  | 0.88  | 0.88  | 0.88  |  |
| Adj. Flow (vph)                   | 67  | 45  | 407   | 28  | 51  | 76  | 327  | 432   | 22  | 40  | 509   | 69  |  |
| RTOR Reduction (vph)              | 0   | 0   | 305   | 0   | 29  | 0   | 0  | 2   | 0   | 0   | 0   | 40  |  |
| Lane Group Flow (vph)             | 0   | 112   | 102   | 0   | 126   | 0   | 327  | 452   | 0   | 40  | 509   | 29  |  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 0%  | 0%  | 0%  | 1%   | 1%  | 1%  | 1%  | 1%  | 1%  |  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |  |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |  |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |  |
| Actuated Green, G (s)             |   | 8.4   | 21.7  |   | 11.6  |   | 13.3   | 31.5  |   | 4.7   | 22.4  | 36.8  |  |
| Effective Green, g (s)            |   | 8.4   | 21.7  |   | 11.6  |   | 13.3   | 31.5  |   | 4.7   | 22.4  | 36.8  |  |
| Actuated g/C Ratio                |   | 0.10  | 0.25  |   | 0.13  |   | 0.15   | 0.37  |   | 0.05  | 0.26  | 0.43  |  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |  |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |  |
| Lane Grp Cap (vph)                |   | 171   | 428   |   | 236   |   | 534  | 1295  |   | 94  | 896   | 659   |  |
| v/s Ratio Prot                    |   | c0.06   | 0.06  |   | c0.07   |   | c0.09  | 0.13  |   | 0.02  | c0.15   | 0.02  |  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |  |
| v/c Ratio                         |   | 0.65  | 0.24  |   | 0.54  |   | 0.61   | 0.35  |   | 0.43  | 0.57  | 0.04  |  |
| Uniform Delay, d1                 |   | 37.6  | 25.7  |   | 34.8  |   | 34.1   | 19.9  |   | 39.5  | 27.7  | 14.5  |  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             |   | 8.7   | 0.3   |   | 2.3   |   | 2.1  | 0.2   |   | 3.1   | 0.8   | 0.0   |  |
| Delay (s)                         |   | 46.3  | 26.0  |   | 37.2  |   | 36.2   | 20.1  |   | 42.6  | 28.6  | 14.5  |  |
| Level of Service                  |   | D   | C   |   | D   |   | D  | C   |   | D   | C   | B   |  |
| Approach Delay (s)                |   | 30.4  |   |   | 37.2  |   | 26.8   |   |   | 27.9  |   |   |  |
| Approach LOS                      |   | C   |   |   | D   |   | C  |   |   | C   |   |   |  |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |  |
| HCM 2000 Control Delay            |   |   | 28.8  |   | HCM 2000 Level of Service   |   |  |   |   |   | C   |   |  |
| HCM 2000 Volume to Capacity ratio |   |   | 0.54  |   |   |   |  |   |   |   |   |   |  |
| Actuated Cycle Length (s)         |   |   | 86.3  |   | Sum of lost time (s)  |   |  |   |   |   | 25.5  |   |  |
| Intersection Capacity Utilization |   |   | 55.7%   |   | ICU Level of Service  |   |  |   |   |   | B   |   |  |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |  |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |  |






























104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2026 No-Build Saturday Peak

| Movement                          | EBL   | EBT  | EBR   | WBL   | WBT   | WBR   | NBL  | NBT  | NBR   | SBL   | SBT   | SBR   |
|-----------------------------------|-------|------|-------|-------|-------|-------|------|------|-------|-------|-------|-------|
| Lane Configurations               |       |      |       |       |       |       |      |      |       |       |       |       |
| Traffic Volume (vph)              | 122   | 23   | 81    | 122   | 11    | 60    | 24   | 583  | 109   | 81    | 767   | 163   |
| Future Volume (vph)               | 122   | 23   | 81    | 122   | 11    | 60    | 24   | 583  | 109   | 81    | 767   | 163   |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900  | 1900  | 1900  | 1900 | 1900 | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11    | 11   | 11    | 11    | 11    | 11    | 11   | 11   | 16    | 11    | 11    | 11    |
| Grade (%)                         |       | 3%   |       |       | -5%   |       |      | 5%   |       |       | -3%   |       |
| Total Lost time (s)               | 6.0   | 6.0  | 6.0   | 5.5   | 5.5   | 5.5   | 6.0  | 6.0  | 5.5   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 | 0.95  | 0.95 | 1.00  | 0.95  | 0.95  | 1.00  | 1.00 | 0.95 | 1.00  | 1.00  | 0.95  | 1.00  |
| Frpb, ped/bikes                   | 1.00  | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |
| Flpb, ped/bikes                   | 1.00  | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |
| Frt                               | 1.00  | 1.00 | 0.85  | 1.00  | 1.00  | 0.85  | 1.00 | 1.00 | 0.85  | 1.00  | 1.00  | 0.85  |
| Flt Protected                     | 0.95  | 0.97 | 1.00  | 0.95  | 0.96  | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 | 1633  | 1662 | 1538  | 1699  | 1717  | 1600  | 1684 | 3369 | 1767  | 1753  | 3507  | 1569  |
| Flt Permitted                     | 0.95  | 0.97 | 1.00  | 0.95  | 0.96  | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 | 1633  | 1662 | 1538  | 1699  | 1717  | 1600  | 1684 | 3369 | 1767  | 1753  | 3507  | 1569  |
| Peak-hour factor, PHF             | 0.84  | 0.84 | 0.84  | 0.91  | 0.91  | 0.91  | 0.89 | 0.89 | 0.89  | 0.92  | 0.92  | 0.92  |
| Adj. Flow (vph)                   | 145   | 27   | 96    | 134   | 12    | 66    | 27   | 655  | 122   | 88    | 834   | 177   |
| RTOR Reduction (vph)              | 0     | 0    | 78    | 0     | 0     | 0     | 0    | 0    | 70    | 0     | 0     | 41    |
| Lane Group Flow (vph)             | 86    | 86   | 18    | 72    | 74    | 66    | 27   | 655  | 52    | 88    | 834   | 136   |
| Confl. Bikes (#/hr)               |       |      |       |       |       |       |      |      | 1     |       |       |       |
| Heavy Vehicles (%)                | 0%    | 0%   | 0%    | 0%    | 0%    | 0%    | 1%   | 1%   | 1%    | 1%    | 1%    | 1%    |
| Turn Type                         | Split | NA   | pt+ov | Split | NA    | pt+ov | Prot | NA   | pt+ov | Prot  | NA    | pt+ov |
| Protected Phases                  | 3     | 3    | 1 3   | 4     | 4     | 4 5   | 1    | 6    | 4 6   | 5     | 2     | 2 3   |
| Permitted Phases                  |       |      |       |       |       |       |      |      |       |       |       |       |
| Actuated Green, G (s)             | 8.1   | 8.1  | 12.6  | 8.0   | 8.0   | 20.7  | 4.5  | 20.8 | 28.8  | 7.2   | 23.0  | 37.1  |
| Effective Green, g (s)            | 8.1   | 8.1  | 12.6  | 8.0   | 8.0   | 20.7  | 4.5  | 20.8 | 28.8  | 7.2   | 23.0  | 37.1  |
| Actuated g/C Ratio                | 0.12  | 0.12 | 0.19  | 0.12  | 0.12  | 0.31  | 0.07 | 0.31 | 0.43  | 0.11  | 0.34  | 0.55  |
| Clearance Time (s)                | 6.0   | 6.0  |       | 5.5   | 5.5   |       | 6.0  | 6.0  |       | 5.5   | 6.0   |       |
| Vehicle Extension (s)             | 3.0   | 3.0  |       | 3.0   | 3.0   |       | 3.0  | 3.0  |       | 3.0   | 3.0   |       |
| Lane Grp Cap (vph)                | 197   | 200  | 288   | 202   | 204   | 493   | 112  | 1044 | 758   | 188   | 1202  | 867   |
| v/s Ratio Prot                    | c0.05 | 0.05 | 0.01  | 0.04  | c0.04 | 0.04  | 0.02 | 0.19 | 0.03  | c0.05 | c0.24 | 0.09  |
| v/s Ratio Perm                    |       |      |       |       |       |       |      |      |       |       |       |       |
| v/c Ratio                         | 0.44  | 0.43 | 0.06  | 0.36  | 0.36  | 0.13  | 0.24 | 0.63 | 0.07  | 0.47  | 0.69  | 0.16  |
| Uniform Delay, d1                 | 27.4  | 27.4 | 22.4  | 27.2  | 27.2  | 16.7  | 29.7 | 19.8 | 11.3  | 28.2  | 19.0  | 7.3   |
| Progression Factor                | 1.00  | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             | 1.5   | 1.5  | 0.1   | 1.1   | 1.1   | 0.1   | 1.1  | 1.2  | 0.0   | 1.8   | 1.8   | 0.1   |
| Delay (s)                         | 28.9  | 28.8 | 22.5  | 28.3  | 28.3  | 16.9  | 30.8 | 21.0 | 11.3  | 30.0  | 20.8  | 7.4   |
| Level of Service                  | C     | C    | C     | C     | C     | B     | C    | C    | B     | C     | C     | A     |
| Approach Delay (s)                |       | 26.6 |       |       | 24.7  |       |      | 19.9 |       |       | 19.4  |       |
| Approach LOS                      |       | C    |       |       | C     |       |      | B    |       |       | B     |       |
| <b>Intersection Summary</b>       |       |      |       |       |       |       |      |      |       |       |       |       |
| HCM 2000 Control Delay            |       |      | 20.8  |       |       |       |      |      |       |       |       | C     |
| HCM 2000 Volume to Capacity ratio |       |      | 0.62  |       |       |       |      |      |       |       |       |       |
| Actuated Cycle Length (s)         |       |      | 67.1  |       |       |       |      |      |       | 25.5  |       |       |
| Intersection Capacity Utilization |       |      | 51.9% |       |       |       |      |      |       |       |       | A     |
| Analysis Period (min)             |       |      | 15    |       |       |       |      |      |       |       |       |       |


c Critical Lane Group



105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2026 No-Build Saturday Peak

|                                   |    |  |  |    |    |  |   |    |  |    |    |    |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |   |   |   |   |   |   |   |   |   |   |
| Traffic Volume (vph)              | 244   | 68  | 50  | 142   | 75  | 22  | 61  | 468   | 129   | 12  | 549   | 393   |
| Future Volume (vph)               | 244   | 68  | 50  | 142   | 75  | 22  | 61  | 468   | 129   | 12  | 549   | 393   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 11  | 14  | 14  | 14  | 11  | 11  | 11  | 11  | 11  | 11  |
| Grade (%)                         |   | 5%  |   |   | -5%   |   |   | 0%  |   |   | 0%  |   |
| Total Lost time (s)               | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   | 6.5   |
| Lane Util. Factor                 | 0.97  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frt                               | 1.00  | 0.94  |   | 1.00  | 0.97  |   | 1.00  | 0.97  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 | 3268  | 1660  |   | 1954  | 1987  |   | 1728  | 3343  |   | 1728  | 3455  | 1546  |
| Flt Permitted                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 | 3268  | 1660  |   | 1954  | 1987  |   | 1728  | 3343  |   | 1728  | 3455  | 1546  |
| Peak-hour factor, PHF             | 0.77  | 0.77  | 0.77  | 0.78  | 0.78  | 0.78  | 0.92  | 0.92  | 0.92  | 0.97  | 0.97  | 0.97  |
| Adj. Flow (vph)                   | 317   | 88  | 65  | 182   | 96  | 28  | 66  | 509   | 140   | 12  | 566   | 405   |
| RTOR Reduction (vph)              | 0   | 21  | 0   | 0   | 8   | 0   | 0   | 18  | 0   | 0   | 0   | 197   |
| Lane Group Flow (vph)             | 317   | 132   | 0   | 182   | 116   | 0   | 66  | 631   | 0   | 12  | 566   | 208   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  |
| Turn Type                         | Split   | NA  |   | Split   | NA  |   | Prot  | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   |   | 4   | 4   |   | 1   | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |   |   |   |   |   |   |
| Actuated Green, G (s)             | 11.5  | 11.5  |   | 12.8  | 12.8  |   | 6.9   | 29.2  |   | 1.2   | 23.5  | 41.5  |
| Effective Green, g (s)            | 11.5  | 11.5  |   | 12.8  | 12.8  |   | 6.9   | 29.2  |   | 1.2   | 23.5  | 41.5  |
| Actuated g/C Ratio                | 0.14  | 0.14  |   | 0.16  | 0.16  |   | 0.09  | 0.36  |   | 0.01  | 0.29  | 0.51  |
| Clearance Time (s)                | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   | 6.5   |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   | 3.0   |
| Lane Grp Cap (vph)                | 465   | 236   |   | 309   | 315   |   | 147   | 1209  |   | 25  | 1006  | 795   |
| v/s Ratio Prot                    | c0.10   | 0.08  |   | c0.09   | 0.06  |   | c0.04   | c0.19   |   | 0.01  | 0.16  | 0.13  |
| v/s Ratio Perm                    |   |   |   |   |   |   |   |   |   |   |   |   |
| v/c Ratio                         | 0.68  | 0.56  |   | 0.59  | 0.37  |   | 0.45  | 0.52  |   | 0.48  | 0.56  | 0.26  |
| Uniform Delay, d1                 | 32.9  | 32.2  |   | 31.5  | 30.3  |   | 35.1  | 20.3  |   | 39.4  | 24.2  | 11.0  |
| Progression Factor                | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             | 4.1   | 3.0   |   | 2.9   | 0.7   |   | 2.2   | 0.4   |   | 13.8  | 0.7   | 0.2   |
| Delay (s)                         | 37.0  | 35.3  |   | 34.4  | 31.1  |   | 37.3  | 20.7  |   | 53.2  | 25.0  | 11.2  |
| Level of Service                  | D   | D   |   | C   | C   |   | D   | C   |   | D   | C   | B   |
| Approach Delay (s)                |   | 36.4  |   |   | 33.0  |   |   | 22.2  |   |   | 19.6  |   |
| Approach LOS                      |   | D   |   |   | C   |   |   | C   |   |   | B   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 25.2  |   |   |   | HCM 2000 Level of Service   |   |   |   | C   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.62  |   |   |   |   |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 80.7  |   |   |   | Sum of lost time (s)  |   |   | 28.0  |   |   |
| Intersection Capacity Utilization |   |   | 52.8%   |   |   |   | ICU Level of Service  |   |   | A   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |   |   |   |   |   |   |

201: Motel 6/North Site & Gosling Road  
 2026 No-Build Saturday Peak



| Movement                          | EBT         | EBR         | WBL         | WBT         | NBL                  | NBR         |             |
|-----------------------------------|-------------|-------------|-------------|-------------|----------------------|-------------|-------------|
| Lane Configurations               | ↑↑↑↑        |             |             | ↑↑          |                      | ↗           |             |
| Traffic Volume (veh/h)            | 1133        | 68          | 0           | 672         | 0                    | 53          |             |
| Future Volume (Veh/h)             | 1133        | 68          | 0           | 672         | 0                    | 53          |             |
| Sign Control                      | Free        |             |             | Free        | Stop                 |             |             |
| Grade                             | 0%          |             |             | 0%          | 0%                   |             |             |
| Peak Hour Factor                  | 0.93        | 0.93        | 0.95        | 0.95        | 0.55                 | 0.55        |             |
| Hourly flow rate (vph)            | 1218        | 73          | 0           | 707         | 0                    | 96          |             |
| <b>Pedestrians</b>                |             |             |             |             |                      |             |             |
| Lane Width (ft)                   |             |             |             |             |                      |             |             |
| Walking Speed (ft/s)              |             |             |             |             |                      |             |             |
| Percent Blockage                  |             |             |             |             |                      |             |             |
| Right turn flare (veh)            |             |             |             |             |                      |             |             |
| Median type                       | None        |             |             | None        |                      |             |             |
| Median storage (veh)              |             |             |             |             |                      |             |             |
| Upstream signal (ft)              | 464         |             |             |             |                      |             |             |
| <b>pX, platoon unblocked</b>      |             |             |             |             |                      |             |             |
| vC, conflicting volume            |             |             | 1291        |             | 1608                 | 341         |             |
| vC1, stage 1 conf vol             |             |             |             |             |                      |             |             |
| vC2, stage 2 conf vol             |             |             |             |             |                      |             |             |
| vCu, unblocked vol                |             |             | 1291        |             | 1608                 | 341         |             |
| tC, single (s)                    |             |             | 4.1         |             | 6.8                  | 6.9         |             |
| tC, 2 stage (s)                   |             |             |             |             |                      |             |             |
| tF (s)                            |             |             | 2.2         |             | 3.5                  | 3.3         |             |
| p0 queue free %                   |             |             | 100         |             | 100                  | 85          |             |
| cM capacity (veh/h)               |             |             | 538         |             | 98                   | 661         |             |
| <b>Direction, Lane #</b>          | <b>EB 1</b> | <b>EB 2</b> | <b>EB 3</b> | <b>EB 4</b> | <b>WB 1</b>          | <b>WB 2</b> | <b>NB 1</b> |
| Volume Total                      | 348         | 348         | 348         | 247         | 354                  | 354         | 96          |
| Volume Left                       | 0           | 0           | 0           | 0           | 0                    | 0           | 0           |
| Volume Right                      | 0           | 0           | 0           | 73          | 0                    | 0           | 96          |
| cSH                               | 1700        | 1700        | 1700        | 1700        | 1700                 | 1700        | 661         |
| Volume to Capacity                | 0.20        | 0.20        | 0.20        | 0.15        | 0.21                 | 0.21        | 0.15        |
| Queue Length 95th (ft)            | 0           | 0           | 0           | 0           | 0                    | 0           | 13          |
| Control Delay (s)                 | 0.0         | 0.0         | 0.0         | 0.0         | 0.0                  | 0.0         | 11.4        |
| Lane LOS                          |             |             |             |             |                      |             | B           |
| Approach Delay (s)                | 0.0         |             |             |             | 0.0                  |             | 11.4        |
| Approach LOS                      |             |             |             |             |                      |             | B           |
| <b>Intersection Summary</b>       |             |             |             |             |                      |             |             |
| Average Delay                     |             |             | 0.5         |             |                      |             |             |
| Intersection Capacity Utilization |             |             | 27.6%       |             | ICU Level of Service |             | A           |
| Analysis Period (min)             |             |             | 15          |             |                      |             |             |

202: Arthur F Brady Drive & South Site Driveway  
 2026 No-Build Saturday Peak

| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 5.6  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↕    | ↕     | ↕    | ↕    |
| Traffic Vol, veh/h       | 102  | 204  | 122  | 81    | 149  | 49   |
| Future Vol, veh/h        | 102  | 204  | 122  | 81    | 149  | 49   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 95   | 95   | 81   | 81    | 88   | 88   |
| Heavy Vehicles, %        | 1    | 1    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 107  | 215  | 151  | 100   | 169  | 56   |

| Major/Minor          | Major1 | Major2 | Minor2 |   |         |
|----------------------|--------|--------|--------|---|---------|
| Conflicting Flow All | 152    | 0      | -      | 0 | 581 153 |
| Stage 1              | -      | -      | -      | - | 152 -   |
| Stage 2              | -      | -      | -      | - | 429 -   |
| Critical Hdwy        | 4.11   | -      | -      | - | 6.4 6.2 |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.4 -   |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.4 -   |
| Follow-up Hdwy       | 2.209  | -      | -      | - | 3.5 3.3 |
| Pot Cap-1 Maneuver   | 1435   | -      | -      | - | 479 898 |
| Stage 1              | -      | -      | -      | - | 881 -   |
| Stage 2              | -      | -      | -      | - | 661 -   |
| Platoon blocked, %   |        | -      | -      | - |         |
| Mov Cap-1 Maneuver   | 1434   | -      | -      | - | 437 896 |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 437 -   |
| Stage 1              | -      | -      | -      | - | 805 -   |
| Stage 2              | -      | -      | -      | - | 660 -   |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.6 | 0  | 16.1 |
| HCM LOS              |     |    | C    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1434  | -   | -   | -   | 437   | 896   |
| HCM Lane V/C Ratio    | 0.075 | -   | -   | -   | 0.387 | 0.062 |
| HCM Control Delay (s) | 7.7   | 0   | -   | -   | 18.4  | 9.3   |
| HCM Lane LOS          | A     | A   | -   | -   | C     | A     |
| HCM 95th %tile Q(veh) | 0.2   | -   | -   | -   | 1.8   | 0.2   |



























101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2036 No-Build Weekday AM Peak



| Movement                          | EBL  | EBT  | EBR   | WBL  | WBT   | WBR                       | NBL  | NBT  | NBR  | SBL   | SBT  | SBR   |
|-----------------------------------|------|------|-------|------|-------|---------------------------|------|------|------|-------|------|-------|
| Lane Configurations               |      | ↑↑↑  | ↗     | ↘    | ↑↑    |                           |      |      |      | ↖     | ↗    | ↘     |
| Traffic Volume (vph)              | 0    | 259  | 113   | 99   | 984   | 0                         | 0    | 0    | 0    | 451   | 0    | 831   |
| Future Volume (vph)               | 0    | 259  | 113   | 99   | 984   | 0                         | 0    | 0    | 0    | 451   | 0    | 831   |
| Ideal Flow (vphpl)                | 1900 | 1900 | 1900  | 1900 | 1900  | 1900                      | 1900 | 1900 | 1900 | 1900  | 1900 | 1900  |
| Lane Width                        | 12   | 10   | 11    | 10   | 11    | 12                        | 12   | 12   | 12   | 12    | 12   | 12    |
| Total Lost time (s)               |      | 6.0  | 6.0   | 6.0  | 6.0   |                           |      |      |      | 6.0   | 6.0  | 6.0   |
| Lane Util. Factor                 |      | 0.86 | 1.00  | 0.97 | 0.95  |                           |      |      |      | 0.95  | 0.95 | 0.88  |
| Frt                               |      | 1.00 | 0.85  | 1.00 | 1.00  |                           |      |      |      | 1.00  | 1.00 | 0.85  |
| Flt Protected                     |      | 1.00 | 1.00  | 0.95 | 1.00  |                           |      |      |      | 0.95  | 0.95 | 1.00  |
| Satd. Flow (prot)                 |      | 5923 | 1516  | 3173 | 3388  |                           |      |      |      | 1698  | 1698 | 2814  |
| Flt Permitted                     |      | 1.00 | 1.00  | 0.95 | 1.00  |                           |      |      |      | 0.95  | 0.95 | 1.00  |
| Satd. Flow (perm)                 |      | 5923 | 1516  | 3173 | 3388  |                           |      |      |      | 1698  | 1698 | 2814  |
| Peak-hour factor, PHF             | 0.93 | 0.93 | 0.93  | 0.87 | 0.87  | 0.87                      | 0.90 | 0.90 | 0.90 | 0.86  | 0.86 | 0.86  |
| Adj. Flow (vph)                   | 0    | 278  | 122   | 114  | 1131  | 0                         | 0    | 0    | 0    | 524   | 0    | 966   |
| RTOR Reduction (vph)              | 0    | 0    | 86    | 0    | 0     | 0                         | 0    | 0    | 0    | 0     | 0    | 137   |
| Lane Group Flow (vph)             | 0    | 278  | 36    | 114  | 1131  | 0                         | 0    | 0    | 0    | 262   | 262  | 829   |
| Heavy Vehicles (%)                | 3%   | 3%   | 3%    | 3%   | 3%    | 3%                        | 0%   | 0%   | 0%   | 1%    | 1%   | 1%    |
| Turn Type                         |      | NA   | Prot  | Prot | NA    |                           |      |      |      | Split | NA   | Prot  |
| Protected Phases                  |      | 6    | 6     | 5    | 2 5   |                           |      |      |      | 3     | 3    | 3     |
| Permitted Phases                  |      |      |       |      |       |                           |      |      |      |       |      |       |
| Actuated Green, G (s)             |      | 28.7 | 28.7  | 25.1 | 59.8  |                           |      |      |      | 25.1  | 25.1 | 25.1  |
| Effective Green, g (s)            |      | 28.7 | 28.7  | 25.1 | 59.8  |                           |      |      |      | 25.1  | 25.1 | 25.1  |
| Actuated g/C Ratio                |      | 0.30 | 0.30  | 0.26 | 0.62  |                           |      |      |      | 0.26  | 0.26 | 0.26  |
| Clearance Time (s)                |      | 6.0  | 6.0   | 6.0  |       |                           |      |      |      | 6.0   | 6.0  | 6.0   |
| Vehicle Extension (s)             |      | 5.0  | 5.0   | 4.0  |       |                           |      |      |      | 5.0   | 5.0  | 5.0   |
| Lane Grp Cap (vph)                |      | 1754 | 449   | 821  | 2090  |                           |      |      |      | 439   | 439  | 728   |
| v/s Ratio Prot                    |      | 0.05 | 0.02  | 0.04 | c0.33 |                           |      |      |      | 0.15  | 0.15 | c0.29 |
| v/s Ratio Perm                    |      |      |       |      |       |                           |      |      |      |       |      |       |
| v/c Ratio                         |      | 0.16 | 0.08  | 0.14 | 0.54  |                           |      |      |      | 0.60  | 0.60 | 1.14  |
| Uniform Delay, d1                 |      | 25.2 | 24.6  | 27.6 | 10.7  |                           |      |      |      | 31.5  | 31.5 | 35.9  |
| Progression Factor                |      | 1.00 | 1.00  | 0.87 | 1.60  |                           |      |      |      | 1.00  | 1.00 | 1.00  |
| Incremental Delay, d2             |      | 0.1  | 0.2   | 0.1  | 0.4   |                           |      |      |      | 3.3   | 3.3  | 78.5  |
| Delay (s)                         |      | 25.3 | 24.7  | 24.1 | 17.4  |                           |      |      |      | 34.7  | 34.7 | 114.4 |
| Level of Service                  |      | C    | C     | C    | B     |                           |      |      |      | C     | C    | F     |
| Approach Delay (s)                |      | 25.1 |       |      | 18.0  |                           |      | 0.0  |      |       | 86.4 |       |
| Approach LOS                      |      | C    |       |      | B     |                           |      | A    |      |       | F    |       |
| <b>Intersection Summary</b>       |      |      |       |      |       |                           |      |      |      |       |      |       |
| HCM 2000 Control Delay            |      |      | 51.4  |      |       | HCM 2000 Level of Service |      |      |      | D     |      |       |
| HCM 2000 Volume to Capacity ratio |      |      | 0.77  |      |       |                           |      |      |      |       |      |       |
| Actuated Cycle Length (s)         |      |      | 96.9  |      |       | Sum of lost time (s)      |      |      | 18.0 |       |      |       |
| Intersection Capacity Utilization |      |      | 66.3% |      |       | ICU Level of Service      |      |      | C    |       |      |       |
| Analysis Period (min)             |      |      | 15    |      |       |                           |      |      |      |       |      |       |






















c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
2036 No-Build Weekday AM Peak

|                                   |    |    |  |  |    |  |    |    |  |    |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |   |   |   |    |   |   |   |  |   |   |   |
| Traffic Volume (vph)              | 118   | 592   | 0   | 0   | 321   | 48  | 762  | 0   | 288   | 0   | 0   | 0   |
| Future Volume (vph)               | 118   | 592   | 0   | 0   | 321   | 48  | 762  | 0   | 288   | 0   | 0   | 0   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 10  | 11  | 12  | 12  | 12  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Lane Util. Factor                 | 0.97  | 0.95  |   |   | 0.91  |   | 0.97   | 0.95  | 0.95  |   |   |   |
| Frt                               | 1.00  | 1.00  |   |   | 0.98  |   | 1.00   | 0.85  | 0.85  |   |   |   |
| Flt Protected                     | 0.95  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (prot)                 | 3236  | 3455  |   |   | 4844  |   | 3400   | 1490  | 1490  |   |   |   |
| Flt Permitted                     | 0.50  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (perm)                 | 1703  | 3455  |   |   | 4844  |   | 3400   | 1490  | 1490  |   |   |   |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.89  | 0.89  | 0.89  | 0.91   | 0.91  | 0.91  | 0.90  | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 127   | 637   | 0   | 0   | 361   | 54  | 837  | 0   | 316   | 0   | 0   | 0   |
| RTOR Reduction (vph)              | 0   | 0   | 0   | 0   | 18  | 0   | 0  | 117   | 117   | 0   | 0   | 0   |
| Lane Group Flow (vph)             | 127   | 637   | 0   | 0   | 397   | 0   | 837  | 41  | 41  | 0   | 0   | 0   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 5%  | 5%  | 5%  | 3%   | 3%  | 3%  | 0%  | 0%  | 0%  |
| Turn Type                         | pm+pt   | NA  |   |   | NA  |   | Split  | NA  | Prot  |   |   |   |
| Protected Phases                  | 1   | 6   |   |   | 2   |   | 3  | 3   | 3   |   |   |   |
| Permitted Phases                  | 6   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             | 45.6  | 28.7  |   |   | 36.9  |   | 25.1   | 25.1  | 25.1  |   |   |   |
| Effective Green, g (s)            | 45.6  | 28.7  |   |   | 36.9  |   | 25.1   | 25.1  | 25.1  |   |   |   |
| Actuated g/C Ratio                | 0.47  | 0.30  |   |   | 0.38  |   | 0.26   | 0.26  | 0.26  |   |   |   |
| Clearance Time (s)                | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Vehicle Extension (s)             | 4.0   | 5.0   |   |   | 5.0   |   | 5.0  | 5.0   | 5.0   |   |   |   |
| Lane Grp Cap (vph)                | 1068  | 1023  |   |   | 1844  |   | 880  | 385   | 385   |   |   |   |
| v/s Ratio Prot                    | c0.02   | c0.18   |   |   | c0.08   |   | c0.25  | 0.03  | 0.03  |   |   |   |
| v/s Ratio Perm                    | 0.04  |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         | 0.12  | 0.62  |   |   | 0.22  |   | 0.95   | 0.11  | 0.11  |   |   |   |
| Uniform Delay, d1                 | 14.1  | 29.4  |   |   | 20.2  |   | 35.3   | 27.4  | 27.4  |   |   |   |
| Progression Factor                | 1.24  | 1.25  |   |   | 1.00  |   | 1.00   | 1.00  | 1.00  |   |   |   |
| Incremental Delay, d2             | 0.1   | 1.5   |   |   | 0.1   |   | 19.9   | 0.3   | 0.3   |   |   |   |
| Delay (s)                         | 17.6  | 38.2  |   |   | 20.4  |   | 55.2   | 27.6  | 27.6  |   |   |   |
| Level of Service                  | B   | D   |   |   | C   |   | E  | C   | C   |   |   |   |
| Approach Delay (s)                |   | 34.8  |   |   | 20.4  |   |  | 47.6  |   |   | 0.0   |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | D   |   |   | A   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 38.6  |   |   |   | HCM 2000 Level of Service  |   |   | D   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.57  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 96.9  |   |   |   | Sum of lost time (s)   |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 66.3%   |   |   |   | ICU Level of Service   |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2036 No-Build Weekday AM Peak

























|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |  |   |  |   |  |  |  |  |  |  |
| Traffic Volume (vph)              | 101   | 42  | 491   | 29  | 15  | 7   | 241  | 192   | 20  | 39  | 316   | 9   |
| Future Volume (vph)               | 101   | 42  | 491   | 29  | 15  | 7   | 241  | 192   | 20  | 39  | 316   | 9   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frt                               |   | 1.00  | 0.85  |   | 0.98  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 |   | 1706  | 1656  |   | 1604  |   | 3400   | 3455  |   | 1678  | 3355  | 1501  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 |   | 1706  | 1656  |   | 1604  |   | 3400   | 3455  |   | 1678  | 3355  | 1501  |
| Peak-hour factor, PHF             | 0.91  | 0.91  | 0.91  | 0.89  | 0.89  | 0.89  | 0.84   | 0.84  | 0.84  | 0.89  | 0.89  | 0.89  |
| Adj. Flow (vph)                   | 111   | 46  | 540   | 33  | 17  | 8   | 287  | 229   | 24  | 44  | 355   | 10  |
| RTOR Reduction (vph)              | 0   | 0   | 380   | 0   | 6   | 0   | 0  | 5   | 0   | 0   | 0   | 6   |
| Lane Group Flow (vph)             | 0   | 157   | 160   | 0   | 52  | 0   | 287  | 248   | 0   | 44  | 355   | 4   |
| Heavy Vehicles (%)                | 4%  | 4%  | 4%  | 13%   | 13%   | 13%   | 3%   | 3%  | 3%  | 4%  | 4%  | 4%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 9.0   | 21.8  |   | 4.9   |   | 12.8   | 25.9  |   | 4.3   | 16.9  | 31.9  |
| Effective Green, g (s)            |   | 9.0   | 21.8  |   | 4.9   |   | 12.8   | 25.9  |   | 4.3   | 16.9  | 31.9  |
| Actuated g/C Ratio                |   | 0.12  | 0.30  |   | 0.07  |   | 0.17   | 0.35  |   | 0.06  | 0.23  | 0.43  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                |   | 208   | 491   |   | 106   |   | 592  | 1217  |   | 98  | 771   | 651   |
| v/s Ratio Prot                    |   | c0.09   | 0.10  |   | c0.03   |   | c0.08  | 0.07  |   | 0.03  | c0.11   | 0.00  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.75  | 0.33  |   | 0.49  |   | 0.48   | 0.20  |   | 0.45  | 0.46  | 0.01  |
| Uniform Delay, d1                 |   | 31.2  | 20.1  |   | 33.1  |   | 27.4   | 16.6  |   | 33.5  | 24.4  | 11.8  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 14.4  | 0.4   |   | 3.6   |   | 0.6  | 0.1   |   | 3.2   | 0.4   | 0.0   |
| Delay (s)                         |   | 45.6  | 20.5  |   | 36.7  |   | 28.0   | 16.7  |   | 36.7  | 24.8  | 11.8  |
| Level of Service                  |   | D   | C   |   | D   |   | C  | B   |   | D   | C   | B   |
| Approach Delay (s)                |   | 26.2  |   |   | 36.7  |   | 22.7   |   |   | 25.8  |   |   |
| Approach LOS                      |   | C   |   |   | D   |   | C  |   |   | C   |   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 25.3  |   |   |   | HCM 2000 Level of Service  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.48  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 73.5  |   |   |   | Sum of lost time (s)   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 60.4%   |   |   |   | ICU Level of Service   |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2036 No-Build Weekday AM Peak

| Movement                          | EBL   | EBT  | EBR   | WBL   | WBT                       | WBR   | NBL  | NBT  | NBR   | SBL   | SBT   | SBR   |  |
|-----------------------------------|-------|------|-------|-------|---------------------------|-------|------|------|-------|-------|-------|-------|--|
| Lane Configurations               |       |      |       |       |                           |       |      |      |       |       |       |       |  |
| Traffic Volume (vph)              | 26    | 3    | 29    | 29    | 0                         | 37    | 10   | 360  | 42    | 50    | 733   | 55    |  |
| Future Volume (vph)               | 26    | 3    | 29    | 29    | 0                         | 37    | 10   | 360  | 42    | 50    | 733   | 55    |  |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900  | 1900                      | 1900  | 1900 | 1900 | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11    | 11   | 11    | 11    | 11                        | 11    | 11   | 11   | 16    | 11    | 11    | 11    |  |
| Grade (%)                         |       | 3%   |       |       | -5%                       |       |      | 5%   |       |       | -3%   |       |  |
| Total Lost time (s)               | 6.0   | 6.0  | 6.0   | 5.5   | 5.5                       | 5.5   | 6.0  | 6.0  | 5.5   | 5.5   | 6.0   | 6.0   |  |
| Lane Util. Factor                 | 0.95  | 0.95 | 1.00  | 0.95  | 0.95                      | 1.00  | 1.00 | 0.95 | 1.00  | 1.00  | 0.95  | 1.00  |  |
| Frpb, ped/bikes                   | 1.00  | 1.00 | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Flpb, ped/bikes                   | 1.00  | 1.00 | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Frt                               | 1.00  | 1.00 | 0.85  | 1.00  | 1.00                      | 0.85  | 1.00 | 1.00 | 0.85  | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     | 0.95  | 0.96 | 1.00  | 0.95  | 0.95                      | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 | 1570  | 1591 | 1479  | 1634  | 1634                      | 1539  | 1652 | 3303 | 1733  | 1736  | 3473  | 1554  |  |
| Flt Permitted                     | 0.95  | 0.96 | 1.00  | 0.95  | 0.95                      | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 | 1570  | 1591 | 1479  | 1634  | 1634                      | 1539  | 1652 | 3303 | 1733  | 1736  | 3473  | 1554  |  |
| Peak-hour factor, PHF             | 0.82  | 0.82 | 0.82  | 0.65  | 0.65                      | 0.65  | 0.85 | 0.85 | 0.85  | 0.98  | 0.98  | 0.98  |  |
| Adj. Flow (vph)                   | 32    | 4    | 35    | 45    | 0                         | 57    | 12   | 424  | 49    | 51    | 748   | 56    |  |
| RTOR Reduction (vph)              | 0     | 0    | 31    | 0     | 0                         | 0     | 0    | 0    | 27    | 0     | 0     | 25    |  |
| Lane Group Flow (vph)             | 18    | 18   | 4     | 22    | 23                        | 57    | 12   | 424  | 22    | 51    | 748   | 31    |  |
| Confl. Bikes (#/hr)               |       |      |       |       |                           |       |      |      | 1     |       |       |       |  |
| Heavy Vehicles (%)                | 4%    | 4%   | 4%    | 4%    | 4%                        | 4%    | 3%   | 3%   | 3%    | 2%    | 2%    | 2%    |  |
| Turn Type                         | Split | NA   | pt+ov | Split | NA                        | pt+ov | Prot | NA   | pt+ov | Prot  | NA    | pt+ov |  |
| Protected Phases                  | 3     | 3    | 1 3   | 4     | 4                         | 4 5   | 1    | 6    | 4 6   | 5     | 2     | 2 3   |  |
| Permitted Phases                  |       |      |       |       |                           |       |      |      |       |       |       |       |  |
| Actuated Green, G (s)             | 5.1   | 5.1  | 8.3   | 5.6   | 5.6                       | 12.2  | 3.2  | 26.9 | 32.5  | 6.6   | 29.8  | 40.9  |  |
| Effective Green, g (s)            | 5.1   | 5.1  | 8.3   | 5.6   | 5.6                       | 12.2  | 3.2  | 26.9 | 32.5  | 6.6   | 29.8  | 40.9  |  |
| Actuated g/C Ratio                | 0.07  | 0.07 | 0.11  | 0.08  | 0.08                      | 0.17  | 0.04 | 0.37 | 0.45  | 0.09  | 0.41  | 0.56  |  |
| Clearance Time (s)                | 6.0   | 6.0  |       | 5.5   | 5.5                       |       | 6.0  | 6.0  |       | 5.5   | 6.0   |       |  |
| Vehicle Extension (s)             | 3.0   | 3.0  |       | 3.0   | 3.0                       |       | 3.0  | 3.0  |       | 3.0   | 3.0   |       |  |
| Lane Grp Cap (vph)                | 109   | 111  | 168   | 125   | 125                       | 257   | 72   | 1218 | 772   | 157   | 1419  | 871   |  |
| v/s Ratio Prot                    | c0.01 | 0.01 | 0.00  | 0.01  | 0.01                      | c0.04 | 0.01 | 0.13 | 0.01  | c0.03 | c0.22 | 0.02  |  |
| v/s Ratio Perm                    |       |      |       |       |                           |       |      |      |       |       |       |       |  |
| v/c Ratio                         | 0.17  | 0.16 | 0.02  | 0.18  | 0.18                      | 0.22  | 0.17 | 0.35 | 0.03  | 0.32  | 0.53  | 0.04  |  |
| Uniform Delay, d1                 | 31.9  | 31.9 | 28.7  | 31.5  | 31.5                      | 26.2  | 33.6 | 16.7 | 11.3  | 31.1  | 16.2  | 7.2   |  |
| Progression Factor                | 1.00  | 1.00 | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             | 0.7   | 0.7  | 0.1   | 0.7   | 0.7                       | 0.4   | 1.1  | 0.2  | 0.0   | 1.2   | 0.4   | 0.0   |  |
| Delay (s)                         | 32.6  | 32.6 | 28.8  | 32.2  | 32.2                      | 26.7  | 34.7 | 16.8 | 11.4  | 32.3  | 16.6  | 7.2   |  |
| Level of Service                  | C     | C    | C     | C     | C                         | C     | C    | B    | B     | C     | B     | A     |  |
| Approach Delay (s)                |       | 30.7 |       |       | 29.1                      |       |      | 16.7 |       |       | 16.9  |       |  |
| Approach LOS                      |       | C    |       |       | C                         |       |      | B    |       |       | B     |       |  |
| <b>Intersection Summary</b>       |       |      |       |       |                           |       |      |      |       |       |       |       |  |
| HCM 2000 Control Delay            |       |      | 18.3  |       | HCM 2000 Level of Service |       |      |      |       | B     |       |       |  |
| HCM 2000 Volume to Capacity ratio |       |      | 0.42  |       |                           |       |      |      |       |       |       |       |  |
| Actuated Cycle Length (s)         |       |      | 72.9  |       | Sum of lost time (s)      |       |      |      |       | 25.5  |       |       |  |
| Intersection Capacity Utilization |       |      | 47.7% |       | ICU Level of Service      |       |      |      |       | A     |       |       |  |
| Analysis Period (min)             |       |      | 15    |       |                           |       |      |      |       |       |       |       |  |

c Critical Lane Group


105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2036 No-Build Weekday AM Peak

|                                   |    |  |  |  |  |  |  |    |  |  |    |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|--|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |  |
| Lane Configurations               |   |  |   |  |  |   |  |   |   |  |   |  |  |
| Traffic Volume (vph)              | 112   | 43  | 52  | 3   | 35  | 44  | 73   | 321   | 85  | 2   | 288   | 220   |  |
| Future Volume (vph)               | 112   | 43  | 52  | 3   | 35  | 44  | 73   | 321   | 85  | 2   | 288   | 220   |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11  | 11  | 11  | 14  | 14  | 14  | 11   | 11  | 11  | 11  | 11  | 11  |  |
| Grade (%)                         |   | 5%  |   |   | -5%   |   |  | 0%  |   |   | 0%  |   |  |
| Total Lost time (s)               | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5  | 6.5   |   | 6.5   | 6.5   | 6.5   |  |
| Lane Util. Factor                 | 0.97  | 1.00  |   | 1.00  | 1.00  |   | 1.00   | 0.95  |   | 1.00  | 0.95  | 1.00  |  |
| Frbp, ped/bikes                   | 1.00  | 0.99  |   | 1.00  | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Flpb, ped/bikes                   | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Frt                               | 1.00  | 0.92  |   | 1.00  | 0.92  |   | 1.00   | 0.97  |   | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 | 3268  | 1616  |   | 1898  | 1830  |   | 1711   | 3299  |   | 1694  | 3388  | 1516  |  |
| Flt Permitted                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 | 3268  | 1616  |   | 1898  | 1830  |   | 1711   | 3299  |   | 1694  | 3388  | 1516  |  |
| Peak-hour factor, PHF             | 0.73  | 0.73  | 0.73  | 0.65  | 0.65  | 0.65  | 0.75   | 0.75  | 0.75  | 0.97  | 0.97  | 0.97  |  |
| Adj. Flow (vph)                   | 153   | 59  | 71  | 5   | 54  | 68  | 97   | 428   | 113   | 2   | 297   | 227   |  |
| RTOR Reduction (vph)              | 0   | 34  | 0   | 0   | 40  | 0   | 0  | 17  | 0   | 0   | 0   | 114   |  |
| Lane Group Flow (vph)             | 153   | 96  | 0   | 5   | 82  | 0   | 97   | 524   | 0   | 2   | 297   | 113   |  |
| Confl. Bikes (#/hr)               |   |   | 1   |   |   |   |  |   | 1   |   |   |   |  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 4%  | 4%  | 4%  | 2%   | 2%  | 2%  | 3%  | 3%  | 3%  |  |
| Turn Type                         | Split   | NA  |   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |  |
| Protected Phases                  | 3   | 3   |   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |  |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |  |
| Actuated Green, G (s)             | 9.8   | 9.8   |   | 6.7   | 6.7   |   | 7.1  | 23.0  |   | 0.9   | 16.8  | 33.1  |  |
| Effective Green, g (s)            | 9.8   | 9.8   |   | 6.7   | 6.7   |   | 7.1  | 23.0  |   | 0.9   | 16.8  | 33.1  |  |
| Actuated g/C Ratio                | 0.15  | 0.15  |   | 0.10  | 0.10  |   | 0.11   | 0.35  |   | 0.01  | 0.25  | 0.50  |  |
| Clearance Time (s)                | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5  | 6.5   |   | 6.5   | 6.5   |   |  |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |  |
| Lane Grp Cap (vph)                | 482   | 238   |   | 191   | 184   |   | 182  | 1142  |   | 22  | 857   | 755   |  |
| v/s Ratio Prot                    | 0.05  | c0.06   |   | 0.00  | c0.05   |   | c0.06  | c0.16   |   | 0.00  | 0.09  | 0.07  |  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |  |
| v/c Ratio                         | 0.32  | 0.40  |   | 0.03  | 0.45  |   | 0.53   | 0.46  |   | 0.09  | 0.35  | 0.15  |  |
| Uniform Delay, d1                 | 25.3  | 25.6  |   | 26.9  | 28.1  |   | 28.1   | 16.9  |   | 32.3  | 20.3  | 9.0   |  |
| Progression Factor                | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             | 0.4   | 1.1   |   | 0.1   | 1.7   |   | 3.0  | 0.3   |   | 1.8   | 0.2   | 0.1   |  |
| Delay (s)                         | 25.7  | 26.8  |   | 27.0  | 29.8  |   | 31.1   | 17.2  |   | 34.1  | 20.6  | 9.1   |  |
| Level of Service                  | C   | C   |   | C   | C   |   | C  | B   |   | C   | C   | A   |  |
| Approach Delay (s)                |   | 26.2  |   |   | 29.7  |   |  | 19.3  |   |   | 15.7  |   |  |
| Approach LOS                      |   | C   |   |   | C   |   |  | B   |   |   | B   |   |  |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |  |
| HCM 2000 Control Delay            |   |   | 20.2  |   | HCM 2000 Level of Service   |   |  |   |   |   | C   |   |  |
| HCM 2000 Volume to Capacity ratio |   |   | 0.52  |   |   |   |  |   |   |   |   |   |  |
| Actuated Cycle Length (s)         |   |   | 66.4  |   | Sum of lost time (s)  |   |  |   |   |   | 28.0  |   |  |
| Intersection Capacity Utilization |   |   | 42.7%   |   | ICU Level of Service  |   |  |   |   |   | A   |   |  |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |  |

c Critical Lane Group



201: Motel 6/North Site & Gosling Road  
2036 No-Build Weekday AM Peak



| Movement                          | EBT  | EBR  | WBL   | WBT                  | NBL  | NBR  |      |
|-----------------------------------|------|------|-------|----------------------|------|------|------|
| Lane Configurations               | ↑↑↑↑ |      |       | ↑↑                   |      | ↗    |      |
| Traffic Volume (veh/h)            | 784  | 96   | 0     | 369                  | 0    | 15   |      |
| Future Volume (Veh/h)             | 784  | 96   | 0     | 369                  | 0    | 15   |      |
| Sign Control                      | Free |      |       | Free                 | Stop |      |      |
| Grade                             | 0%   |      |       | 0%                   | 0%   |      |      |
| Peak Hour Factor                  | 0.97 | 0.97 | 0.89  | 0.89                 | 0.46 | 0.46 |      |
| Hourly flow rate (vph)            | 808  | 99   | 0     | 415                  | 0    | 33   |      |
| Pedestrians                       |      |      |       |                      |      |      |      |
| Lane Width (ft)                   |      |      |       |                      |      |      |      |
| Walking Speed (ft/s)              |      |      |       |                      |      |      |      |
| Percent Blockage                  |      |      |       |                      |      |      |      |
| Right turn flare (veh)            |      |      |       |                      |      |      |      |
| Median type                       | None |      |       | None                 |      |      |      |
| Median storage (veh)              |      |      |       |                      |      |      |      |
| Upstream signal (ft)              | 464  |      |       |                      |      |      |      |
| pX, platoon unblocked             |      |      |       |                      |      |      |      |
| vC, conflicting volume            |      |      | 907   | 1065                 | 252  |      |      |
| vC1, stage 1 conf vol             |      |      |       |                      |      |      |      |
| vC2, stage 2 conf vol             |      |      |       |                      |      |      |      |
| vCu, unblocked vol                |      |      | 907   | 1065                 | 252  |      |      |
| tC, single (s)                    |      |      | 4.2   | 6.8                  | 6.9  |      |      |
| tC, 2 stage (s)                   |      |      |       |                      |      |      |      |
| tF (s)                            |      |      | 2.2   | 3.5                  | 3.3  |      |      |
| p0 queue free %                   |      |      | 100   | 100                  | 96   |      |      |
| cM capacity (veh/h)               |      |      | 728   | 221                  | 754  |      |      |
| Direction, Lane #                 | EB 1 | EB 2 | EB 3  | EB 4                 | WB 1 | WB 2 | NB 1 |
| Volume Total                      | 231  | 231  | 231   | 214                  | 208  | 208  | 33   |
| Volume Left                       | 0    | 0    | 0     | 0                    | 0    | 0    | 0    |
| Volume Right                      | 0    | 0    | 0     | 99                   | 0    | 0    | 33   |
| cSH                               | 1700 | 1700 | 1700  | 1700                 | 1700 | 1700 | 754  |
| Volume to Capacity                | 0.14 | 0.14 | 0.14  | 0.13                 | 0.12 | 0.12 | 0.04 |
| Queue Length 95th (ft)            | 0    | 0    | 0     | 0                    | 0    | 0    | 3    |
| Control Delay (s)                 | 0.0  | 0.0  | 0.0   | 0.0                  | 0.0  | 0.0  | 10.0 |
| Lane LOS                          |      |      |       |                      |      |      | A    |
| Approach Delay (s)                | 0.0  |      |       |                      | 0.0  |      | 10.0 |
| Approach LOS                      |      |      |       |                      |      |      | A    |
| Intersection Summary              |      |      |       |                      |      |      |      |
| Average Delay                     |      |      | 0.2   |                      |      |      |      |
| Intersection Capacity Utilization |      |      | 23.0% | ICU Level of Service |      |      | A    |
| Analysis Period (min)             |      |      | 15    |                      |      |      |      |

202: Arthur F Brady Drive & South Site Driveway  
 2036 No-Build Weekday AM Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 4.4  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↕    | ↕     | ↕    | ↕    |
| Traffic Vol, veh/h       | 55   | 96   | 85   | 79    | 90   | 53   |
| Future Vol, veh/h        | 55   | 96   | 85   | 79    | 90   | 53   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 85   | 85   | 84   | 84    | 81   | 81   |
| Heavy Vehicles, %        | 4    | 4    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 65   | 113  | 101  | 94    | 111  | 65   |

| Major/Minor          | Major1 | Major2 | Minor2 |   |         |
|----------------------|--------|--------|--------|---|---------|
| Conflicting Flow All | 102    | 0      | -      | 0 | 345 103 |
| Stage 1              | -      | -      | -      | - | 102 -   |
| Stage 2              | -      | -      | -      | - | 243 -   |
| Critical Hdwy        | 4.14   | -      | -      | - | 6.4 6.2 |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.4 -   |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.4 -   |
| Follow-up Hdwy       | 2.236  | -      | -      | - | 3.5 3.3 |
| Pot Cap-1 Maneuver   | 1478   | -      | -      | - | 656 957 |
| Stage 1              | -      | -      | -      | - | 927 -   |
| Stage 2              | -      | -      | -      | - | 802 -   |
| Platoon blocked, %   |        | -      | -      | - |         |
| Mov Cap-1 Maneuver   | 1477   | -      | -      | - | 624 955 |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 624 -   |
| Stage 1              | -      | -      | -      | - | 883 -   |
| Stage 2              | -      | -      | -      | - | 801 -   |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.7 | 0  | 10.9 |
| HCM LOS              |     |    | B    |
























| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1477  | -   | -   | -   | 624   | 955   |
| HCM Lane V/C Ratio    | 0.044 | -   | -   | -   | 0.178 | 0.069 |
| HCM Control Delay (s) | 7.5   | 0   | -   | -   | 12    | 9     |
| HCM Lane LOS          | A     | A   | -   | -   | B     | A     |
| HCM 95th %tile Q(veh) | 0.1   | -   | -   | -   | 0.6   | 0.2   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2036 No-Build Weekday PM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↗↗  |
| Traffic Volume (vph)              | 0   | 1282  | 644   | 511   | 339   | 0   | 0  | 0   | 0   | 254   | 1   | 125   |
| Future Volume (vph)               | 0   | 1282  | 644   | 511   | 339   | 0   | 0  | 0   | 0   | 254   | 1   | 125   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.94  | 0.94  | 0.94  | 0.92   | 0.92  | 0.92  | 0.94  | 0.94  | 0.94  |
| Adj. Flow (vph)                   | 0   | 1526  | 767   | 544   | 361   | 0   | 0  | 0   | 0   | 270   | 1   | 133   |
| RTOR Reduction (vph)              | 0   | 0   | 359   | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 105   |
| Lane Group Flow (vph)             | 0   | 1526  | 408   | 544   | 361   | 0   | 0  | 0   | 0   | 135   | 136   | 28  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 35.8  | 35.8  | 22.4  | 56.3  |   |  |   |   | 20.4  | 20.4  | 20.4  |
| Effective Green, g (s)            |   | 35.8  | 35.8  | 22.4  | 56.3  |   |  |   |   | 20.4  | 20.4  | 20.4  |
| Actuated g/C Ratio                |   | 0.37  | 0.37  | 0.23  | 0.58  |   |  |   |   | 0.21  | 0.21  | 0.21  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 2238  | 572   | 750   | 2013  |   |  |   |   | 358   | 359   | 594   |
| v/s Ratio Prot                    |   | 0.25  | c0.26   | c0.17   | 0.10  |   |  |   |   | 0.08  | c0.08   | 0.01  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.68  | 0.71  | 0.73  | 0.18  |   |  |   |   | 0.38  | 0.38  | 0.05  |
| Uniform Delay, d1                 |   | 25.6  | 26.0  | 34.3  | 9.4   |   |  |   |   | 32.7  | 32.7  | 30.4  |
| Progression Factor                |   | 1.00  | 1.00  | 1.35  | 0.84  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 1.1   | 5.2   | 3.2   | 0.1   |   |  |   |   | 1.4   | 1.4   | 0.1   |
| Delay (s)                         |   | 26.7  | 31.2  | 49.6  | 7.9   |   |  |   |   | 34.0  | 34.1  | 30.4  |
| Level of Service                  |   | C   | C   | D   | A   |   |  |   |   | C   | C   | C   |
| Approach Delay (s)                |   | 28.2  |   |   | 33.0  |   |  | 0.0   |   |   | 32.9  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 29.9  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.63  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 96.6  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 76.5%   |   |   | ICU Level of Service  |  |   |   | D   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |





















c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2036 No-Build Weekday PM Peak

























|                                   |    |    |  |  |    |  |    |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |   |   |   |    |   |   |  |  |   |   |   |
| Traffic Volume (vph)              | 785   | 751   | 0   | 0   | 693   | 365   | 157  | 0   | 571   | 0   | 0   | 0   |
| Future Volume (vph)               | 785   | 751   | 0   | 0   | 693   | 365   | 157  | 0   | 571   | 0   | 0   | 0   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 10  | 11  | 12  | 12  | 12  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Lane Util. Factor                 | 0.97  | 0.95  |   |   | 0.91  |   | 0.97   | 0.95  | 0.95  |   |   |   |
| Frt                               | 1.00  | 1.00  |   |   | 0.95  |   | 1.00   | 0.85  | 0.85  |   |   |   |
| Flt Protected                     | 0.95  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (prot)                 | 3236  | 3455  |   |   | 4870  |   | 3433   | 1504  | 1504  |   |   |   |
| Flt Permitted                     | 0.14  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (perm)                 | 488   | 3455  |   |   | 4870  |   | 3433   | 1504  | 1504  |   |   |   |
| Peak-hour factor, PHF             | 0.87  | 0.87  | 0.87  | 0.94  | 0.94  | 0.94  | 0.94   | 0.94  | 0.94  | 0.90  | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 902   | 863   | 0   | 0   | 737   | 388   | 167  | 0   | 607   | 0   | 0   | 0   |
| RTOR Reduction (vph)              | 0   | 0   | 0   | 0   | 91  | 0   | 0  | 240   | 239   | 0   | 0   | 0   |
| Lane Group Flow (vph)             | 902   | 863   | 0   | 0   | 1034  | 0   | 167  | 64  | 64  | 0   | 0   | 0   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 2%   | 2%  | 2%  | 0%  | 0%  | 0%  |
| Turn Type                         | pm+pt   | NA  |   |   | NA  |   | Split  | NA  | Prot  |   |   |   |
| Protected Phases                  | 1   | 6   |   |   | 2   |   | 3  | 3   | 3   |   |   |   |
| Permitted Phases                  | 6   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             | 60.1  | 35.8  |   |   | 33.9  |   | 20.4   | 20.4  | 20.4  |   |   |   |
| Effective Green, g (s)            | 60.1  | 35.8  |   |   | 33.9  |   | 20.4   | 20.4  | 20.4  |   |   |   |
| Actuated g/C Ratio                | 0.62  | 0.37  |   |   | 0.35  |   | 0.21   | 0.21  | 0.21  |   |   |   |
| Clearance Time (s)                | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Vehicle Extension (s)             | 4.0   | 5.0   |   |   | 5.0   |   | 5.0  | 5.0   | 5.0   |   |   |   |
| Lane Grp Cap (vph)                | 994   | 1280  |   |   | 1709  |   | 724  | 317   | 317   |   |   |   |
| v/s Ratio Prot                    | c0.23   | 0.25  |   |   | 0.21  |   | c0.05  | 0.04  | 0.04  |   |   |   |
| v/s Ratio Perm                    | c0.34   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         | 0.91  | 0.67  |   |   | 0.61  |   | 0.23   | 0.20  | 0.20  |   |   |   |
| Uniform Delay, d1                 | 23.2  | 25.5  |   |   | 25.8  |   | 31.6   | 31.4  | 31.4  |   |   |   |
| Progression Factor                | 1.94  | 0.48  |   |   | 1.00  |   | 1.00   | 1.00  | 1.00  |   |   |   |
| Incremental Delay, d2             | 9.6   | 1.4   |   |   | 0.9   |   | 0.3  | 0.7   | 0.7   |   |   |   |
| Delay (s)                         | 54.6  | 13.7  |   |   | 26.7  |   | 31.9   | 32.1  | 32.1  |   |   |   |
| Level of Service                  | D   | B   |   |   | C   |   | C  | C   | C   |   |   |   |
| Approach Delay (s)                |   | 34.6  |   |   | 26.7  |   |  | 32.0  |   |   | 0.0   |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | C   |   |   | A   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 31.6  |   | HCM 2000 Level of Service   |   |  |   | C   |   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.75  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 96.6  |   | Sum of lost time (s)  |   |  |   | 18.0  |   |   |   |
| Intersection Capacity Utilization |   |   | 76.5%   |   | ICU Level of Service  |   |  |   | D   |   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2036 No-Build Weekday PM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |  |   |  |   |  |  |   |  |  |  |
| Traffic Volume (vph)              | 98  | 68  | 554   | 68  | 61  | 54  | 394  | 534   | 38  | 34  | 522   | 135   |
| Future Volume (vph)               | 98  | 68  | 554   | 68  | 61  | 54  | 394  | 534   | 38  | 34  | 522   | 135   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frbp, ped/bikes                   |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Flpb, ped/bikes                   |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Frt                               |   | 1.00  | 0.85  |   | 0.96  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.98  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 |   | 1749  | 1689  |   | 1755  |   | 3467   | 3533  |   | 1711  | 3421  | 1531  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.98  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 |   | 1749  | 1689  |   | 1755  |   | 3467   | 3533  |   | 1711  | 3421  | 1531  |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.80  | 0.80  | 0.80  | 0.96   | 0.96  | 0.96  | 0.97  | 0.97  | 0.97  |
| Adj. Flow (vph)                   | 109   | 76  | 616   | 85  | 76  | 68  | 410  | 556   | 40  | 35  | 538   | 139   |
| RTOR Reduction (vph)              | 0   | 0   | 467   | 0   | 12  | 0   | 0  | 3   | 0   | 0   | 0   | 83  |
| Lane Group Flow (vph)             | 0   | 185   | 149   | 0   | 217   | 0   | 410  | 593   | 0   | 35  | 538   | 56  |
| Confl. Bikes (#/hr)               |   |   |   |   |   |   |  |   | 2   |   |   |   |
| Heavy Vehicles (%)                | 2%  | 2%  | 2%  | 2%  | 2%  | 2%  | 1%   | 1%  | 1%  | 2%  | 2%  | 2%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 8.4   | 22.0  |   | 15.8  |   | 13.6   | 31.9  |   | 4.7   | 22.5  | 36.9  |
| Effective Green, g (s)            |   | 8.4   | 22.0  |   | 15.8  |   | 13.6   | 31.9  |   | 4.7   | 22.5  | 36.9  |
| Actuated g/C Ratio                |   | 0.09  | 0.24  |   | 0.17  |   | 0.15   | 0.35  |   | 0.05  | 0.25  | 0.41  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                |   | 161   | 408   |   | 305   |   | 518  | 1239  |   | 88  | 846   | 621   |
| v/s Ratio Prot                    |   | c0.11   | 0.09  |   | c0.12   |   | c0.12  | 0.17  |   | 0.02  | c0.16   | 0.04  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 1.15  | 0.37  |   | 0.71  |   | 0.79   | 0.48  |   | 0.40  | 0.64  | 0.09  |
| Uniform Delay, d1                 |   | 41.2  | 28.6  |   | 35.4  |   | 37.3   | 23.0  |   | 41.7  | 30.5  | 16.7  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 116.6   | 0.6   |   | 7.6   |   | 8.1  | 0.3   |   | 2.9   | 1.6   | 0.1   |
| Delay (s)                         |   | 157.9   | 29.2  |   | 43.0  |   | 45.4   | 23.3  |   | 44.7  | 32.1  | 16.7  |
| Level of Service                  |   | F   | C   |   | D   |   | D  | C   |   | D   | C   | B   |
| Approach Delay (s)                |   | 58.9  |   |   | 43.0  |   | 32.3   |   |   | 29.7  |   |   |
| Approach LOS                      |   | E   |   |   | D   |   | C  |   |   | C   |   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 40.3  |   |   |   | HCM 2000 Level of Service  |   |   |   | D   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.70  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 90.9  |   |   |   | Sum of lost time (s)   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 73.6%   |   |   |   | ICU Level of Service   |   |   | D   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2036 No-Build Weekday PM Peak

|                                   |  |  |  |  |  |  |   |  |  |  |  |  |                      |   |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|----------------------|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |                      |   |
| Lane Configurations               |  |  |  |  |  |  |  |  |  |  |  |  |                      |   |
| Traffic Volume (vph)              | 129   | 21  | 68  | 117   | 17  | 104   | 32  | 762   | 111   | 86  | 781   | 32  |                      |   |
| Future Volume (vph)               | 129   | 21  | 68  | 117   | 17  | 104   | 32  | 762   | 111   | 86  | 781   | 32  |                      |   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |                      |   |
| Lane Width                        | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 16  | 11  | 11  | 11  |                      |   |
| Grade (%)                         |   | 3%  |   |   | -5%   |   |   | 5%  |   |   | -3%   |   |                      |   |
| Total Lost time (s)               | 6.0   | 6.0   | 6.0   | 5.5   | 5.5   | 5.5   | 6.0   | 6.0   | 5.5   | 5.5   | 6.0   | 6.0   |                      |   |
| Lane Util. Factor                 | 0.95  | 0.95  | 1.00  | 0.95  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  |                      |   |
| Frt                               | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  |                      |   |
| Flt Protected                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |                      |   |
| Satd. Flow (prot)                 | 1633  | 1659  | 1424  | 1682  | 1707  | 1584  | 1684  | 3369  | 1767  | 1753  | 3507  | 1569  |                      |   |
| Flt Permitted                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |                      |   |
| Satd. Flow (perm)                 | 1633  | 1659  | 1424  | 1682  | 1707  | 1584  | 1684  | 3369  | 1767  | 1753  | 3507  | 1569  |                      |   |
| Peak-hour factor, PHF             | 0.86  | 0.86  | 0.86  | 0.77  | 0.77  | 0.77  | 0.87  | 0.87  | 0.87  | 0.94  | 0.94  | 0.94  |                      |   |
| Adj. Flow (vph)                   | 150   | 24  | 79  | 152   | 22  | 135   | 37  | 876   | 128   | 91  | 831   | 34  |                      |   |
| RTOR Reduction (vph)              | 0   | 0   | 66  | 0   | 0   | 0   | 0   | 0   | 68  | 0   | 0   | 14  |                      |   |
| Lane Group Flow (vph)             | 87  | 87  | 13  | 87  | 87  | 135   | 37  | 876   | 60  | 91  | 831   | 20  |                      |   |
| Heavy Vehicles (%)                | 0%  | 0%  | 8%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  |                      |   |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  | pt+ov   | Prot  | NA  | pt+ov   | Prot  | NA  | pt+ov   |                      |   |
| Protected Phases                  | 3   | 3   | 13  | 4   | 4   | 45  | 1   | 6   | 46  | 5   | 2   | 23  |                      |   |
| Permitted Phases                  |   |   |   |   |   |   |   |   |   |   |   |   |                      |   |
| Actuated Green, G (s)             | 8.1   | 8.1   | 12.8  | 8.3   | 8.3   | 23.3  | 4.7   | 27.6  | 35.9  | 9.5   | 31.9  | 46.0  |                      |   |
| Effective Green, g (s)            | 8.1   | 8.1   | 12.8  | 8.3   | 8.3   | 23.3  | 4.7   | 27.6  | 35.9  | 9.5   | 31.9  | 46.0  |                      |   |
| Actuated g/C Ratio                | 0.11  | 0.11  | 0.17  | 0.11  | 0.11  | 0.30  | 0.06  | 0.36  | 0.47  | 0.12  | 0.42  | 0.60  |                      |   |
| Clearance Time (s)                | 6.0   | 6.0   |   | 5.5   | 5.5   |   | 6.0   | 6.0   |   | 5.5   | 6.0   |   |                      |   |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   |                      |   |
| Lane Grp Cap (vph)                | 172   | 175   | 238   | 182   | 185   | 482   | 103   | 1215  | 829   | 217   | 1462  | 943   |                      |   |
| v/s Ratio Prot                    | c0.05   | 0.05  | 0.01  | c0.05   | 0.05  | 0.09  | 0.02  | c0.26   | 0.03  | c0.05   | c0.24   | 0.01  |                      |   |
| v/s Ratio Perm                    |   |   |   |   |   |   |   |   |   |   |   |   |                      |   |
| v/c Ratio                         | 0.51  | 0.50  | 0.06  | 0.48  | 0.47  | 0.28  | 0.36  | 0.72  | 0.07  | 0.42  | 0.57  | 0.02  |                      |   |
| Uniform Delay, d1                 | 32.3  | 32.3  | 26.8  | 32.1  | 32.0  | 20.2  | 34.5  | 21.1  | 11.2  | 31.0  | 17.0  | 6.2   |                      |   |
| Progression Factor                | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |                      |   |
| Incremental Delay, d2             | 2.3   | 2.2   | 0.1   | 2.0   | 1.9   | 0.3   | 2.1   | 2.1   | 0.0   | 1.3   | 0.5   | 0.0   |                      |   |
| Delay (s)                         | 34.6  | 34.5  | 26.9  | 34.0  | 33.9  | 20.5  | 36.6  | 23.3  | 11.2  | 32.3  | 17.6  | 6.2   |                      |   |
| Level of Service                  | C   | C   | C   | C   | C   | C   | D   | C   | B   | C   | B   | A   |                      |   |
| Approach Delay (s)                |   | 32.2  |   |   | 28.1  |   |   | 22.3  |   |   | 18.5  |   |                      |   |
| Approach LOS                      |   | C   |   |   | C   |   |   | C   |   |   | B   |   |                      |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |                      |   |
| HCM 2000 Control Delay            |   |   | 22.6  |   |   |   |   |   |   |   |   | HCM 2000 Level of Service   | C                    |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.63  |   |   |   |   |   |   |   |   |   |                      |   |
| Actuated Cycle Length (s)         |   |   | 76.5  |   |   |   |   |   |   |   | 25.5  |   |                      |   |
| Intersection Capacity Utilization |   |   | 53.1%   |   |   |   |   |   |   |   |   |   | ICU Level of Service | A |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |                      |   |
| c Critical Lane Group             |   |   |   |   |   |   |   |   |   |   |   |   |                      |   |

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2036 No-Build Weekday PM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT  | WBR  | NBL   | NBT   | NBR  | SBL  | SBT   | SBR                       |      |
|-----------------------------------|-------|-------|-------|-------|------|------|-------|-------|------|------|-------|---------------------------|------|
| Lane Configurations               |       |       |       |       |      |      |       |       |      |      |       |                           |      |
| Traffic Volume (vph)              | 239   | 80    | 111   | 221   | 104  | 18   | 111   | 517   | 160  | 18   | 722   | 421                       |      |
| Future Volume (vph)               | 239   | 80    | 111   | 221   | 104  | 18   | 111   | 517   | 160  | 18   | 722   | 421                       |      |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900 | 1900 | 1900  | 1900  | 1900 | 1900 | 1900  | 1900                      |      |
| Lane Width                        | 11    | 11    | 11    | 14    | 14   | 14   | 11    | 11    | 11   | 11   | 11    | 11                        |      |
| Grade (%)                         |       | 5%    |       |       | -5%  |      |       | 0%    |      |      | 0%    |                           |      |
| Total Lost time (s)               | 6.5   | 6.5   |       | 6.5   | 6.5  |      | 6.5   | 6.5   |      | 6.5  | 6.5   | 6.5                       |      |
| Lane Util. Factor                 | 0.97  | 1.00  |       | 1.00  | 1.00 |      | 1.00  | 0.95  |      | 1.00 | 0.95  | 1.00                      |      |
| Frt                               | 1.00  | 0.91  |       | 1.00  | 0.98 |      | 1.00  | 0.96  |      | 1.00 | 1.00  | 0.85                      |      |
| Flt Protected                     | 0.95  | 1.00  |       | 0.95  | 1.00 |      | 0.95  | 1.00  |      | 0.95 | 1.00  | 1.00                      |      |
| Satd. Flow (prot)                 | 3268  | 1619  |       | 1954  | 2011 |      | 1728  | 3333  |      | 1728 | 3455  | 1546                      |      |
| Flt Permitted                     | 0.95  | 1.00  |       | 0.95  | 1.00 |      | 0.95  | 1.00  |      | 0.95 | 1.00  | 1.00                      |      |
| Satd. Flow (perm)                 | 3268  | 1619  |       | 1954  | 2011 |      | 1728  | 3333  |      | 1728 | 3455  | 1546                      |      |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.91  | 0.91 | 0.91 | 0.88  | 0.88  | 0.88 | 0.90 | 0.90  | 0.90                      |      |
| Adj. Flow (vph)                   | 266   | 89    | 123   | 243   | 114  | 20   | 126   | 588   | 182  | 20   | 802   | 468                       |      |
| RTOR Reduction (vph)              | 0     | 41    | 0     | 0     | 5    | 0    | 0     | 20    | 0    | 0    | 0     | 244                       |      |
| Lane Group Flow (vph)             | 266   | 171   | 0     | 243   | 129  | 0    | 126   | 750   | 0    | 20   | 802   | 224                       |      |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 1%    | 1%   | 1%   | 1%    | 1%    | 1%   | 1%   | 1%    | 1%                        |      |
| Turn Type                         | Split | NA    |       | Split | NA   |      | Prot  | NA    |      | Prot | NA    | pt+ov                     |      |
| Protected Phases                  | 3     | 3     |       | 4     | 4    |      | 1     | 6     |      | 5    | 2     | 2 3                       |      |
| Permitted Phases                  |       |       |       |       |      |      |       |       |      |      |       |                           |      |
| Actuated Green, G (s)             | 11.2  | 11.2  |       | 16.1  | 16.1 |      | 11.1  | 38.9  |      | 2.8  | 30.6  | 48.3                      |      |
| Effective Green, g (s)            | 11.2  | 11.2  |       | 16.1  | 16.1 |      | 11.1  | 38.9  |      | 2.8  | 30.6  | 48.3                      |      |
| Actuated g/C Ratio                | 0.11  | 0.11  |       | 0.16  | 0.16 |      | 0.11  | 0.39  |      | 0.03 | 0.30  | 0.48                      |      |
| Clearance Time (s)                | 6.5   | 6.5   |       | 6.5   | 6.5  |      | 6.5   | 6.5   |      | 6.5  | 6.5   | 6.5                       |      |
| Vehicle Extension (s)             | 3.0   | 3.0   |       | 3.0   | 3.0  |      | 3.0   | 3.0   |      | 3.0  | 3.0   | 3.0                       |      |
| Lane Grp Cap (vph)                | 362   | 179   |       | 311   | 320  |      | 189   | 1283  |      | 47   | 1046  | 739                       |      |
| v/s Ratio Prot                    | 0.08  | c0.11 |       | c0.12 | 0.06 |      | c0.07 | c0.22 |      | 0.01 | c0.23 | 0.14                      |      |
| v/s Ratio Perm                    |       |       |       |       |      |      |       |       |      |      |       |                           |      |
| v/c Ratio                         | 0.73  | 0.96  |       | 0.78  | 0.40 |      | 0.67  | 0.58  |      | 0.43 | 0.77  | 0.30                      |      |
| Uniform Delay, d1                 | 43.5  | 44.7  |       | 40.8  | 38.1 |      | 43.2  | 24.6  |      | 48.3 | 32.0  | 16.1                      |      |
| Progression Factor                | 1.00  | 1.00  |       | 1.00  | 1.00 |      | 1.00  | 1.00  |      | 1.00 | 1.00  | 1.00                      |      |
| Incremental Delay, d2             | 7.5   | 53.9  |       | 12.0  | 0.8  |      | 8.6   | 0.7   |      | 6.1  | 3.4   | 0.2                       |      |
| Delay (s)                         | 51.0  | 98.6  |       | 52.8  | 39.0 |      | 51.7  | 25.3  |      | 54.4 | 35.4  | 16.3                      |      |
| Level of Service                  | D     | F     |       | D     | D    |      | D     | C     |      | D    | D     | B                         |      |
| Approach Delay (s)                |       | 72.1  |       |       | 47.9 |      |       | 29.0  |      |      | 28.8  |                           |      |
| Approach LOS                      |       | E     |       |       | D    |      |       | C     |      |      | C     |                           |      |
| <b>Intersection Summary</b>       |       |       |       |       |      |      |       |       |      |      |       |                           |      |
| HCM 2000 Control Delay            |       |       | 38.0  |       |      |      |       |       |      |      |       | HCM 2000 Level of Service | D    |
| HCM 2000 Volume to Capacity ratio |       |       | 0.75  |       |      |      |       |       |      |      |       |                           |      |
| Actuated Cycle Length (s)         |       |       | 101.0 |       |      |      |       |       |      |      |       | Sum of lost time (s)      | 28.0 |
| Intersection Capacity Utilization |       |       | 71.0% |       |      |      |       |       |      |      |       | ICU Level of Service      | C    |
| Analysis Period (min)             |       |       | 15    |       |      |      |       |       |      |      |       |                           |      |
| c Critical Lane Group             |       |       |       |       |      |      |       |       |      |      |       |                           |      |

201: Motel 6/North Site & Gosling Road  
2036 No-Build Weekday PM Peak



| Movement                          | EBT         | EBR         | WBL         | WBT         | NBL                  | NBR         |             |
|-----------------------------------|-------------|-------------|-------------|-------------|----------------------|-------------|-------------|
| Lane Configurations               | ↑↑↑↑        |             |             | ↑↑          |                      | ↗           |             |
| Traffic Volume (veh/h)            | 1218        | 104         | 0           | 1058        | 0                    | 34          |             |
| Future Volume (Veh/h)             | 1218        | 104         | 0           | 1058        | 0                    | 34          |             |
| Sign Control                      | Free        |             |             | Free        | Stop                 |             |             |
| Grade                             | 0%          |             |             | 0%          | 0%                   |             |             |
| Peak Hour Factor                  | 0.94        | 0.94        | 0.98        | 0.97        | 0.72                 | 0.72        |             |
| Hourly flow rate (vph)            | 1296        | 111         | 0           | 1091        | 0                    | 47          |             |
| <b>Pedestrians</b>                |             |             |             |             |                      |             |             |
| Lane Width (ft)                   |             |             |             |             |                      |             |             |
| Walking Speed (ft/s)              |             |             |             |             |                      |             |             |
| Percent Blockage                  |             |             |             |             |                      |             |             |
| Right turn flare (veh)            |             |             |             |             |                      |             |             |
| Median type                       | None        |             |             | None        |                      |             |             |
| Median storage (veh)              |             |             |             |             |                      |             |             |
| Upstream signal (ft)              | 464         |             |             |             |                      |             |             |
| pX, platoon unblocked             |             |             |             |             |                      |             |             |
| vC, conflicting volume            |             |             | 1407        |             | 1897                 | 380         |             |
| vC1, stage 1 conf vol             |             |             |             |             |                      |             |             |
| vC2, stage 2 conf vol             |             |             |             |             |                      |             |             |
| vCu, unblocked vol                |             |             | 1407        |             | 1897                 | 380         |             |
| tC, single (s)                    |             |             | 4.1         |             | 6.8                  | 6.9         |             |
| tC, 2 stage (s)                   |             |             |             |             |                      |             |             |
| tF (s)                            |             |             | 2.2         |             | 3.5                  | 3.3         |             |
| p0 queue free %                   |             |             | 100         |             | 100                  | 92          |             |
| cM capacity (veh/h)               |             |             | 486         |             | 63                   | 624         |             |
| <b>Direction, Lane #</b>          | <b>EB 1</b> | <b>EB 2</b> | <b>EB 3</b> | <b>EB 4</b> | <b>WB 1</b>          | <b>WB 2</b> | <b>NB 1</b> |
| Volume Total                      | 370         | 370         | 370         | 296         | 546                  | 546         | 47          |
| Volume Left                       | 0           | 0           | 0           | 0           | 0                    | 0           | 0           |
| Volume Right                      | 0           | 0           | 0           | 111         | 0                    | 0           | 47          |
| cSH                               | 1700        | 1700        | 1700        | 1700        | 1700                 | 1700        | 624         |
| Volume to Capacity                | 0.22        | 0.22        | 0.22        | 0.17        | 0.32                 | 0.32        | 0.08        |
| Queue Length 95th (ft)            | 0           | 0           | 0           | 0           | 0                    | 0           | 6           |
| Control Delay (s)                 | 0.0         | 0.0         | 0.0         | 0.0         | 0.0                  | 0.0         | 11.2        |
| Lane LOS                          |             |             |             |             |                      |             | B           |
| Approach Delay (s)                | 0.0         |             |             |             | 0.0                  |             | 11.2        |
| Approach LOS                      |             |             |             |             |                      |             | B           |
| <b>Intersection Summary</b>       |             |             |             |             |                      |             |             |
| Average Delay                     |             |             | 0.2         |             |                      |             |             |
| Intersection Capacity Utilization |             |             | 32.6%       |             | ICU Level of Service |             | A           |
| Analysis Period (min)             |             |             | 15          |             |                      |             |             |



202: Arthur F Brady Drive & South Site Driveway  
 2036 No-Build Weekday PM Peak

| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 5.4  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↑    | ↗     | ↖    | ↗    |
| Traffic Vol, veh/h       | 74   | 197  | 264  | 80    | 123  | 74   |
| Future Vol, veh/h        | 74   | 197  | 264  | 80    | 123  | 74   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 97   | 97   | 80   | 80    | 74   | 74   |
| Heavy Vehicles, %        | 0    | 0    | 0    | 0     | 1    | 1    |
| Mvmt Flow                | 76   | 203  | 330  | 100   | 166  | 100  |

| Major/Minor          | Major1 | Major2 | Minor2 |   |             |
|----------------------|--------|--------|--------|---|-------------|
| Conflicting Flow All | 331    | 0      | -      | 0 | 686 332     |
| Stage 1              | -      | -      | -      | - | 331 -       |
| Stage 2              | -      | -      | -      | - | 355 -       |
| Critical Hdwy        | 4.1    | -      | -      | - | 6.41 6.21   |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.41 -      |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.41 -      |
| Follow-up Hdwy       | 2.2    | -      | -      | - | 3.509 3.309 |
| Pot Cap-1 Maneuver   | 1240   | -      | -      | - | 415 712     |
| Stage 1              | -      | -      | -      | - | 730 -       |
| Stage 2              | -      | -      | -      | - | 712 -       |
| Platoon blocked, %   |        | -      | -      | - |             |
| Mov Cap-1 Maneuver   | 1239   | -      | -      | - | 386 710     |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 386 -       |
| Stage 1              | -      | -      | -      | - | 679 -       |
| Stage 2              | -      | -      | -      | - | 711 -       |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.2 | 0  | 17.3 |
| HCM LOS              |     |    | C    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1239  | -   | -   | -   | 386   | 710   |
| HCM Lane V/C Ratio    | 0.062 | -   | -   | -   | 0.431 | 0.141 |
| HCM Control Delay (s) | 8.1   | 0   | -   | -   | 21.2  | 10.9  |
| HCM Lane LOS          | A     | A   | -   | -   | C     | B     |
| HCM 95th %tile Q(veh) | 0.2   | -   | -   | -   | 2.1   | 0.5   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2036 No-Build Saturday Peak



| Movement                          | EBL  | EBT   | EBR   | WBL   | WBT  | WBR                       | NBL  | NBT  | NBR  | SBL   | SBT   | SBR  |
|-----------------------------------|------|-------|-------|-------|------|---------------------------|------|------|------|-------|-------|------|
| Lane Configurations               |      | ↑↑↑   | ↗     | ↘     | ↑↑   |                           |      |      |      | ↖     | ↗     | ↘    |
| Traffic Volume (vph)              | 0    | 336   | 75    | 405   | 217  | 0                         | 0    | 0    | 0    | 350   | 1     | 57   |
| Future Volume (vph)               | 0    | 336   | 75    | 405   | 217  | 0                         | 0    | 0    | 0    | 350   | 1     | 57   |
| Ideal Flow (vphpl)                | 1900 | 1900  | 1900  | 1900  | 1900 | 1900                      | 1900 | 1900 | 1900 | 1900  | 1900  | 1900 |
| Lane Width                        | 12   | 10    | 11    | 10    | 11   | 12                        | 12   | 12   | 12   | 12    | 12    | 12   |
| Total Lost time (s)               |      | 6.0   | 6.0   | 6.0   | 6.0  |                           |      |      |      | 6.0   | 6.0   | 6.0  |
| Lane Util. Factor                 |      | 0.86  | 1.00  | 0.97  | 0.95 |                           |      |      |      | 0.95  | 0.95  | 0.88 |
| Frt                               |      | 1.00  | 0.85  | 1.00  | 1.00 |                           |      |      |      | 1.00  | 1.00  | 0.85 |
| Flt Protected                     |      | 1.00  | 1.00  | 0.95  | 1.00 |                           |      |      |      | 0.95  | 0.95  | 1.00 |
| Satd. Flow (prot)                 |      | 6040  | 1546  | 3236  | 3455 |                           |      |      |      | 1698  | 1702  | 2814 |
| Flt Permitted                     |      | 1.00  | 1.00  | 0.95  | 1.00 |                           |      |      |      | 0.95  | 0.95  | 1.00 |
| Satd. Flow (perm)                 |      | 6040  | 1546  | 3236  | 3455 |                           |      |      |      | 1698  | 1702  | 2814 |
| Peak-hour factor, PHF             | 0.92 | 0.92  | 0.92  | 0.85  | 0.85 | 0.85                      | 0.92 | 0.92 | 0.92 | 0.87  | 0.87  | 0.87 |
| Adj. Flow (vph)                   | 0    | 365   | 82    | 476   | 255  | 0                         | 0    | 0    | 0    | 402   | 1     | 66   |
| RTOR Reduction (vph)              | 0    | 0     | 55    | 0     | 0    | 0                         | 0    | 0    | 0    | 0     | 0     | 50   |
| Lane Group Flow (vph)             | 0    | 365   | 27    | 476   | 255  | 0                         | 0    | 0    | 0    | 201   | 202   | 16   |
| Heavy Vehicles (%)                | 1%   | 1%    | 1%    | 1%    | 1%   | 1%                        | 0%   | 0%   | 0%   | 1%    | 1%    | 1%   |
| Turn Type                         |      | NA    | Prot  | Prot  | NA   |                           |      |      |      | Split | NA    | Prot |
| Protected Phases                  |      | 6     | 6     | 5     | 2 5  |                           |      |      |      | 3     | 3     | 3    |
| Permitted Phases                  |      |       |       |       |      |                           |      |      |      |       |       |      |
| Actuated Green, G (s)             |      | 30.1  | 30.1  | 20.1  | 56.2 |                           |      |      |      | 21.9  | 21.9  | 21.9 |
| Effective Green, g (s)            |      | 30.1  | 30.1  | 20.1  | 56.2 |                           |      |      |      | 21.9  | 21.9  | 21.9 |
| Actuated g/C Ratio                |      | 0.33  | 0.33  | 0.22  | 0.62 |                           |      |      |      | 0.24  | 0.24  | 0.24 |
| Clearance Time (s)                |      | 6.0   | 6.0   | 6.0   |      |                           |      |      |      | 6.0   | 6.0   | 6.0  |
| Vehicle Extension (s)             |      | 5.0   | 5.0   | 4.0   |      |                           |      |      |      | 5.0   | 5.0   | 5.0  |
| Lane Grp Cap (vph)                |      | 2017  | 516   | 721   | 2155 |                           |      |      |      | 412   | 413   | 683  |
| v/s Ratio Prot                    |      | c0.06 | 0.02  | c0.15 | 0.07 |                           |      |      |      | 0.12  | c0.12 | 0.01 |
| v/s Ratio Perm                    |      |       |       |       |      |                           |      |      |      |       |       |      |
| v/c Ratio                         |      | 0.18  | 0.05  | 0.66  | 0.12 |                           |      |      |      | 0.49  | 0.49  | 0.02 |
| Uniform Delay, d1                 |      | 21.3  | 20.3  | 31.9  | 6.9  |                           |      |      |      | 29.3  | 29.3  | 26.0 |
| Progression Factor                |      | 1.00  | 1.00  | 1.45  | 0.79 |                           |      |      |      | 1.00  | 1.00  | 1.00 |
| Incremental Delay, d2             |      | 0.1   | 0.1   | 2.4   | 0.1  |                           |      |      |      | 1.9   | 1.9   | 0.0  |
| Delay (s)                         |      | 21.4  | 20.4  | 48.7  | 5.5  |                           |      |      |      | 31.2  | 31.2  | 26.0 |
| Level of Service                  |      | C     | C     | D     | A    |                           |      |      |      | C     | C     | C    |
| Approach Delay (s)                |      | 21.2  |       |       | 33.6 |                           |      | 0.0  |      |       | 30.5  |      |
| Approach LOS                      |      | C     |       |       | C    |                           |      | A    |      |       | C     |      |
| <b>Intersection Summary</b>       |      |       |       |       |      |                           |      |      |      |       |       |      |
| HCM 2000 Control Delay            |      |       | 29.4  |       |      | HCM 2000 Level of Service |      |      |      | C     |       |      |
| HCM 2000 Volume to Capacity ratio |      |       | 0.41  |       |      |                           |      |      |      |       |       |      |
| Actuated Cycle Length (s)         |      |       | 90.1  |       |      | Sum of lost time (s)      |      |      |      | 18.0  |       |      |
| Intersection Capacity Utilization |      |       | 57.7% |       |      | ICU Level of Service      |      |      |      | B     |       |      |
| Analysis Period (min)             |      |       | 15    |       |      |                           |      |      |      |       |       |      |






















c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
2036 No-Build Saturday Peak

| Movement                          | EBL   | EBT   | EBR   | WBL  | WBT   | WBR  | NBL                       | NBT   | NBR  | SBL  | SBT  | SBR  |
|-----------------------------------|-------|-------|-------|------|-------|------|---------------------------|-------|------|------|------|------|
| Lane Configurations               |       |       |       |      |       |      |                           |       |      |      |      |      |
| Traffic Volume (vph)              | 90    | 596   | 0     | 0    | 532   | 210  | 90                        | 3     | 730  | 0    | 0    | 0    |
| Future Volume (vph)               | 90    | 596   | 0     | 0    | 532   | 210  | 90                        | 3     | 730  | 0    | 0    | 0    |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900 | 1900  | 1900 | 1900                      | 1900  | 1900 | 1900 | 1900 | 1900 |
| Lane Width                        | 10    | 11    | 12    | 12   | 12    | 12   | 12                        | 12    | 12   | 12   | 12   | 12   |
| Total Lost time (s)               | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0   | 6.0  |      |      |      |
| Lane Util. Factor                 | 0.97  | 0.95  |       |      | 0.91  |      | 0.97                      | 0.95  | 0.95 |      |      |      |
| Frt                               | 1.00  | 1.00  |       |      | 0.96  |      | 1.00                      | 0.85  | 0.85 |      |      |      |
| Flt Protected                     | 0.95  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00  | 1.00 |      |      |      |
| Satd. Flow (prot)                 | 3236  | 3455  |       |      | 4918  |      | 3467                      | 1521  | 1519 |      |      |      |
| Flt Permitted                     | 0.34  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00  | 1.00 |      |      |      |
| Satd. Flow (perm)                 | 1172  | 3455  |       |      | 4918  |      | 3467                      | 1521  | 1519 |      |      |      |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.95 | 0.95  | 0.95 | 0.96                      | 0.96  | 0.96 | 0.90 | 0.90 | 0.90 |
| Adj. Flow (vph)                   | 97    | 641   | 0     | 0    | 560   | 221  | 94                        | 3     | 760  | 0    | 0    | 0    |
| RTOR Reduction (vph)              | 0     | 0     | 0     | 0    | 61    | 0    | 0                         | 288   | 288  | 0    | 0    | 0    |
| Lane Group Flow (vph)             | 97    | 641   | 0     | 0    | 720   | 0    | 94                        | 95    | 92   | 0    | 0    | 0    |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 1%   | 1%    | 1%   | 1%                        | 1%    | 1%   | 0%   | 0%   | 0%   |
| Turn Type                         | pm+pt | NA    |       |      | NA    |      | Split                     | NA    | Prot |      |      |      |
| Protected Phases                  | 1     | 6     |       |      | 2     |      | 3                         | 3     | 3    |      |      |      |
| Permitted Phases                  | 6     |       |       |      |       |      |                           |       |      |      |      |      |
| Actuated Green, G (s)             | 43.1  | 30.1  |       |      | 37.2  |      | 21.9                      | 21.9  | 21.9 |      |      |      |
| Effective Green, g (s)            | 43.1  | 30.1  |       |      | 37.2  |      | 21.9                      | 21.9  | 21.9 |      |      |      |
| Actuated g/C Ratio                | 0.48  | 0.33  |       |      | 0.41  |      | 0.24                      | 0.24  | 0.24 |      |      |      |
| Clearance Time (s)                | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0   | 6.0  |      |      |      |
| Vehicle Extension (s)             | 4.0   | 5.0   |       |      | 5.0   |      | 5.0                       | 5.0   | 5.0  |      |      |      |
| Lane Grp Cap (vph)                | 858   | 1154  |       |      | 2030  |      | 842                       | 369   | 369  |      |      |      |
| v/s Ratio Prot                    | c0.02 | c0.19 |       |      | c0.15 |      | 0.03                      | c0.06 | 0.06 |      |      |      |
| v/s Ratio Perm                    | 0.04  |       |       |      |       |      |                           |       |      |      |      |      |
| v/c Ratio                         | 0.11  | 0.56  |       |      | 0.35  |      | 0.11                      | 0.26  | 0.25 |      |      |      |
| Uniform Delay, d1                 | 12.6  | 24.5  |       |      | 18.2  |      | 26.5                      | 27.5  | 27.5 |      |      |      |
| Progression Factor                | 1.16  | 1.06  |       |      | 1.00  |      | 1.00                      | 1.00  | 1.00 |      |      |      |
| Incremental Delay, d2             | 0.1   | 1.0   |       |      | 0.2   |      | 0.1                       | 0.8   | 0.7  |      |      |      |
| Delay (s)                         | 14.7  | 27.1  |       |      | 18.4  |      | 26.7                      | 28.3  | 28.2 |      |      |      |
| Level of Service                  | B     | C     |       |      | B     |      | C                         | C     | C    |      |      |      |
| Approach Delay (s)                |       | 25.4  |       |      | 18.4  |      |                           | 28.1  |      |      | 0.0  |      |
| Approach LOS                      |       | C     |       |      | B     |      |                           | C     |      |      | A    |      |
| <b>Intersection Summary</b>       |       |       |       |      |       |      |                           |       |      |      |      |      |
| HCM 2000 Control Delay            |       |       | 24.1  |      |       |      | HCM 2000 Level of Service |       |      | C    |      |      |
| HCM 2000 Volume to Capacity ratio |       |       | 0.35  |      |       |      |                           |       |      |      |      |      |
| Actuated Cycle Length (s)         |       |       | 90.1  |      |       |      | Sum of lost time (s)      |       |      | 18.0 |      |      |
| Intersection Capacity Utilization |       |       | 57.7% |      |       |      | ICU Level of Service      |       |      | B    |      |      |
| Analysis Period (min)             |       |       | 15    |      |       |      |                           |       |      |      |      |      |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2036 No-Build Saturday Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |  |   |  |   |  |  |  |  |  |  |
| Traffic Volume (vph)              | 62  | 42  | 377   | 27  | 48  | 72  | 330  | 435   | 22  | 39  | 495   | 67  |
| Future Volume (vph)               | 62  | 42  | 377   | 27  | 48  | 72  | 330  | 435   | 22  | 39  | 495   | 67  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frt                               |   | 1.00  | 0.85  |   | 0.93  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 |   | 1766  | 1706  |   | 1758  |   | 3467   | 3549  |   | 1728  | 3455  | 1546  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 |   | 1766  | 1706  |   | 1758  |   | 3467   | 3549  |   | 1728  | 3455  | 1546  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.85  | 0.85  | 0.85  | 0.91   | 0.91  | 0.91  | 0.88  | 0.88  | 0.88  |
| Adj. Flow (vph)                   | 74  | 50  | 449   | 32  | 56  | 85  | 363  | 478   | 24  | 44  | 562   | 76  |
| RTOR Reduction (vph)              | 0   | 0   | 336   | 0   | 29  | 0   | 0  | 2   | 0   | 0   | 0   | 44  |
| Lane Group Flow (vph)             | 0   | 124   | 113   | 0   | 144   | 0   | 363  | 500   | 0   | 44  | 563   | 32  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 0%  | 0%  | 0%  | 1%   | 1%  | 1%  | 1%  | 1%  | 1%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 8.4   | 22.0  |   | 12.4  |   | 13.6   | 31.8  |   | 4.8   | 22.5  | 36.9  |
| Effective Green, g (s)            |   | 8.4   | 22.0  |   | 12.4  |   | 13.6   | 31.8  |   | 4.8   | 22.5  | 36.9  |
| Actuated g/C Ratio                |   | 0.10  | 0.25  |   | 0.14  |   | 0.16   | 0.36  |   | 0.05  | 0.26  | 0.42  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                |   | 169   | 428   |   | 249   |   | 538  | 1289  |   | 94  | 888   | 651   |
| v/s Ratio Prot                    |   | c0.07   | 0.07  |   | c0.08   |   | c0.10  | 0.14  |   | 0.03  | c0.16   | 0.02  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.73  | 0.26  |   | 0.58  |   | 0.67   | 0.39  |   | 0.47  | 0.63  | 0.05  |
| Uniform Delay, d1                 |   | 38.5  | 26.3  |   | 35.1  |   | 34.9   | 20.6  |   | 40.1  | 28.8  | 14.9  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 15.2  | 0.3   |   | 3.2   |   | 3.3  | 0.2   |   | 3.7   | 1.5   | 0.0   |
| Delay (s)                         |   | 53.6  | 26.6  |   | 38.3  |   | 38.2   | 20.8  |   | 43.8  | 30.3  | 15.0  |
| Level of Service                  |   | D   | C   |   | D   |   | D  | C   |   | D   | C   | B   |
| Approach Delay (s)                |   | 32.4  |   |   | 38.3  |   | 28.1   |   |   | 29.5  |   |   |
| Approach LOS                      |   | C   |   |   | D   |   | C  |   |   | C   |   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 30.4  |   |   |   | HCM 2000 Level of Service  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.59  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 87.5  |   |   |   | Sum of lost time (s)   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 60.0%   |   |   |   | ICU Level of Service   |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2036 No-Build Saturday Peak


| Movement                          | EBL   | EBT  | EBR   | WBL   | WBT   | WBR   | NBL  | NBT  | NBR   | SBL   | SBT   | SBR                         |
|-----------------------------------|-------|------|-------|-------|-------|-------|------|------|-------|-------|-------|-----------------------------|
| Lane Configurations               |       |      |       |       |       |       |      |      |       |       |       |                             |
| Traffic Volume (vph)              | 135   | 25   | 90    | 135   | 12    | 66    | 27   | 644  | 120   | 90    | 847   | 180                         |
| Future Volume (vph)               | 135   | 25   | 90    | 135   | 12    | 66    | 27   | 644  | 120   | 90    | 847   | 180                         |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900  | 1900  | 1900  | 1900 | 1900 | 1900  | 1900  | 1900  | 1900                        |
| Lane Width                        | 11    | 11   | 11    | 11    | 11    | 11    | 11   | 11   | 16    | 11    | 11    | 11                          |
| Grade (%)                         |       | 3%   |       |       | -5%   |       |      | 5%   |       |       | -3%   |                             |
| Total Lost time (s)               | 6.0   | 6.0  | 6.0   | 5.5   | 5.5   | 5.5   | 6.0  | 6.0  | 5.5   | 5.5   | 6.0   | 6.0                         |
| Lane Util. Factor                 | 0.95  | 0.95 | 1.00  | 0.95  | 0.95  | 1.00  | 1.00 | 0.95 | 1.00  | 1.00  | 0.95  | 1.00                        |
| Frpb, ped/bikes                   | 1.00  | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00                        |
| Flpb, ped/bikes                   | 1.00  | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00                        |
| Frt                               | 1.00  | 1.00 | 0.85  | 1.00  | 1.00  | 0.85  | 1.00 | 1.00 | 0.85  | 1.00  | 1.00  | 0.85                        |
| Flt Protected                     | 0.95  | 0.97 | 1.00  | 0.95  | 0.96  | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00                        |
| Satd. Flow (prot)                 | 1633  | 1662 | 1538  | 1699  | 1716  | 1600  | 1684 | 3369 | 1767  | 1753  | 3507  | 1569                        |
| Flt Permitted                     | 0.95  | 0.97 | 1.00  | 0.95  | 0.96  | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00                        |
| Satd. Flow (perm)                 | 1633  | 1662 | 1538  | 1699  | 1716  | 1600  | 1684 | 3369 | 1767  | 1753  | 3507  | 1569                        |
| Peak-hour factor, PHF             | 0.84  | 0.84 | 0.84  | 0.91  | 0.91  | 0.91  | 0.89 | 0.89 | 0.89  | 0.92  | 0.92  | 0.92                        |
| Adj. Flow (vph)                   | 161   | 30   | 107   | 148   | 13    | 73    | 30   | 724  | 135   | 98    | 921   | 196                         |
| RTOR Reduction (vph)              | 0     | 0    | 88    | 0     | 0     | 0     | 0    | 0    | 76    | 0     | 0     | 38                          |
| Lane Group Flow (vph)             | 95    | 96   | 19    | 80    | 81    | 73    | 30   | 724  | 59    | 98    | 921   | 158                         |
| Confl. Bikes (#/hr)               |       |      |       |       |       |       |      |      | 1     |       |       |                             |
| Heavy Vehicles (%)                | 0%    | 0%   | 0%    | 0%    | 0%    | 0%    | 1%   | 1%   | 1%    | 1%    | 1%    | 1%                          |
| Turn Type                         | Split | NA   | pt+ov | Split | NA    | pt+ov | Prot | NA   | pt+ov | Prot  | NA    | pt+ov                       |
| Protected Phases                  | 3     | 3    | 13    | 4     | 4     | 45    | 1    | 6    | 46    | 5     | 2     | 23                          |
| Permitted Phases                  |       |      |       |       |       |       |      |      |       |       |       |                             |
| Actuated Green, G (s)             | 8.1   | 8.1  | 12.7  | 8.1   | 8.1   | 23.2  | 4.6  | 23.4 | 31.5  | 9.6   | 27.9  | 42.0                        |
| Effective Green, g (s)            | 8.1   | 8.1  | 12.7  | 8.1   | 8.1   | 23.2  | 4.6  | 23.4 | 31.5  | 9.6   | 27.9  | 42.0                        |
| Actuated g/C Ratio                | 0.11  | 0.11 | 0.18  | 0.11  | 0.11  | 0.32  | 0.06 | 0.32 | 0.44  | 0.13  | 0.39  | 0.58                        |
| Clearance Time (s)                | 6.0   | 6.0  |       | 5.5   | 5.5   |       | 6.0  | 6.0  |       | 5.5   | 6.0   |                             |
| Vehicle Extension (s)             | 3.0   | 3.0  |       | 3.0   | 3.0   |       | 3.0  | 3.0  |       | 3.0   | 3.0   |                             |
| Lane Grp Cap (vph)                | 183   | 186  | 270   | 190   | 192   | 514   | 107  | 1091 | 770   | 233   | 1355  | 912                         |
| v/s Ratio Prot                    | c0.06 | 0.06 | 0.01  | 0.05  | c0.05 | 0.05  | 0.02 | 0.21 | 0.03  | c0.06 | c0.26 | 0.10                        |
| v/s Ratio Perm                    |       |      |       |       |       |       |      |      |       |       |       |                             |
| v/c Ratio                         | 0.52  | 0.52 | 0.07  | 0.42  | 0.42  | 0.14  | 0.28 | 0.66 | 0.08  | 0.42  | 0.68  | 0.17                        |
| Uniform Delay, d1                 | 30.2  | 30.2 | 24.8  | 29.9  | 29.9  | 17.4  | 32.2 | 21.0 | 11.9  | 28.7  | 18.4  | 7.0                         |
| Progression Factor                | 1.00  | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00                        |
| Incremental Delay, d2             | 2.5   | 2.4  | 0.1   | 1.5   | 1.5   | 0.1   | 1.4  | 1.5  | 0.0   | 1.2   | 1.4   | 0.1                         |
| Delay (s)                         | 32.7  | 32.6 | 24.9  | 31.4  | 31.4  | 17.6  | 33.7 | 22.5 | 11.9  | 30.0  | 19.8  | 7.1                         |
| Level of Service                  | C     | C    | C     | C     | C     | B     | C    | C    | B     | C     | B     | A                           |
| Approach Delay (s)                |       | 29.9 |       |       | 27.1  |       |      | 21.3 |       |       | 18.6  |                             |
| Approach LOS                      |       | C    |       |       | C     |       |      | C    |       |       | B     |                             |
| <b>Intersection Summary</b>       |       |      |       |       |       |       |      |      |       |       |       |                             |
| HCM 2000 Control Delay            |       |      | 21.5  |       |       |       |      |      |       |       |       | HCM 2000 Level of Service C |
| HCM 2000 Volume to Capacity ratio |       |      | 0.64  |       |       |       |      |      |       |       |       |                             |
| Actuated Cycle Length (s)         |       |      | 72.2  |       |       |       |      |      |       |       |       | Sum of lost time (s) 25.5   |
| Intersection Capacity Utilization |       |      | 54.5% |       |       |       |      |      |       |       |       | ICU Level of Service A      |
| Analysis Period (min)             |       |      | 15    |       |       |       |      |      |       |       |       |                             |

c Critical Lane Group

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2036 No-Build Saturday Peak

| Movement                          | EBL   | EBT  | EBR   | WBL   | WBT  | WBR  | NBL   | NBT   | NBR  | SBL  | SBT  | SBR                         |
|-----------------------------------|-------|------|-------|-------|------|------|-------|-------|------|------|------|-----------------------------|
| Lane Configurations               |       |      |       |       |      |      |       |       |      |      |      |                             |
| Traffic Volume (vph)              | 270   | 75   | 55    | 157   | 82   | 24   | 67    | 517   | 142  | 13   | 607  | 435                         |
| Future Volume (vph)               | 270   | 75   | 55    | 157   | 82   | 24   | 67    | 517   | 142  | 13   | 607  | 435                         |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900  | 1900 | 1900 | 1900  | 1900  | 1900 | 1900 | 1900 | 1900                        |
| Lane Width                        | 11    | 11   | 11    | 14    | 14   | 14   | 11    | 11    | 11   | 11   | 11   | 11                          |
| Grade (%)                         |       | 5%   |       |       | -5%  |      |       | 0%    |      |      | 0%   |                             |
| Total Lost time (s)               | 6.5   | 6.5  |       | 6.5   | 6.5  |      | 6.5   | 6.5   |      | 6.5  | 6.5  | 6.5                         |
| Lane Util. Factor                 | 0.97  | 1.00 |       | 1.00  | 1.00 |      | 1.00  | 0.95  |      | 1.00 | 0.95 | 1.00                        |
| Frt                               | 1.00  | 0.94 |       | 1.00  | 0.97 |      | 1.00  | 0.97  |      | 1.00 | 1.00 | 0.85                        |
| Flt Protected                     | 0.95  | 1.00 |       | 0.95  | 1.00 |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00                        |
| Satd. Flow (prot)                 | 3268  | 1661 |       | 1954  | 1986 |      | 1728  | 3344  |      | 1728 | 3455 | 1546                        |
| Flt Permitted                     | 0.95  | 1.00 |       | 0.95  | 1.00 |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00                        |
| Satd. Flow (perm)                 | 3268  | 1661 |       | 1954  | 1986 |      | 1728  | 3344  |      | 1728 | 3455 | 1546                        |
| Peak-hour factor, PHF             | 0.77  | 0.77 | 0.77  | 0.78  | 0.78 | 0.78 | 0.92  | 0.92  | 0.92 | 0.97 | 0.97 | 0.97                        |
| Adj. Flow (vph)                   | 351   | 97   | 71    | 201   | 105  | 31   | 73    | 562   | 154  | 13   | 626  | 448                         |
| RTOR Reduction (vph)              | 0     | 21   | 0     | 0     | 8    | 0    | 0     | 18    | 0    | 0    | 0    | 216                         |
| Lane Group Flow (vph)             | 351   | 147  | 0     | 201   | 128  | 0    | 73    | 698   | 0    | 13   | 626  | 232                         |
| Heavy Vehicles (%)                | 1%    | 1%   | 1%    | 1%    | 1%   | 1%   | 1%    | 1%    | 1%   | 1%   | 1%   | 1%                          |
| Turn Type                         | Split | NA   |       | Split | NA   |      | Prot  | NA    |      | Prot | NA   | pt+ov                       |
| Protected Phases                  | 3     | 3    |       | 4     | 4    |      | 1     | 6     |      | 5    | 2    | 2 3                         |
| Permitted Phases                  |       |      |       |       |      |      |       |       |      |      |      |                             |
| Actuated Green, G (s)             | 11.4  | 11.4 |       | 13.9  | 13.9 |      | 7.2   | 31.5  |      | 1.3  | 25.6 | 43.5                        |
| Effective Green, g (s)            | 11.4  | 11.4 |       | 13.9  | 13.9 |      | 7.2   | 31.5  |      | 1.3  | 25.6 | 43.5                        |
| Actuated g/C Ratio                | 0.14  | 0.14 |       | 0.17  | 0.17 |      | 0.09  | 0.37  |      | 0.02 | 0.30 | 0.52                        |
| Clearance Time (s)                | 6.5   | 6.5  |       | 6.5   | 6.5  |      | 6.5   | 6.5   |      | 6.5  | 6.5  | 6.5                         |
| Vehicle Extension (s)             | 3.0   | 3.0  |       | 3.0   | 3.0  |      | 3.0   | 3.0   |      | 3.0  | 3.0  | 3.0                         |
| Lane Grp Cap (vph)                | 442   | 225  |       | 322   | 328  |      | 147   | 1252  |      | 26   | 1051 | 799                         |
| v/s Ratio Prot                    | c0.11 | 0.09 |       | c0.10 | 0.06 |      | c0.04 | c0.21 |      | 0.01 | 0.18 | 0.15                        |
| v/s Ratio Perm                    |       |      |       |       |      |      |       |       |      |      |      |                             |
| v/c Ratio                         | 0.79  | 0.65 |       | 0.62  | 0.39 |      | 0.50  | 0.56  |      | 0.50 | 0.60 | 0.29                        |
| Uniform Delay, d1                 | 35.2  | 34.5 |       | 32.7  | 31.3 |      | 36.7  | 20.8  |      | 41.1 | 24.9 | 11.5                        |
| Progression Factor                | 1.00  | 1.00 |       | 1.00  | 1.00 |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00                        |
| Incremental Delay, d2             | 9.5   | 6.7  |       | 3.7   | 0.8  |      | 2.6   | 0.5   |      | 14.3 | 0.9  | 0.2                         |
| Delay (s)                         | 44.7  | 41.2 |       | 36.4  | 32.1 |      | 39.3  | 21.3  |      | 55.4 | 25.8 | 11.7                        |
| Level of Service                  | D     | D    |       | D     | C    |      | D     | C     |      | E    | C    | B                           |
| Approach Delay (s)                |       | 43.6 |       |       | 34.7 |      |       | 23.0  |      |      | 20.3 |                             |
| Approach LOS                      |       | D    |       |       | C    |      |       | C     |      |      | C    |                             |
| <b>Intersection Summary</b>       |       |      |       |       |      |      |       |       |      |      |      |                             |
| HCM 2000 Control Delay            |       |      | 27.3  |       |      |      |       |       |      |      |      | HCM 2000 Level of Service C |
| HCM 2000 Volume to Capacity ratio |       |      | 0.67  |       |      |      |       |       |      |      |      |                             |
| Actuated Cycle Length (s)         |       |      | 84.1  |       |      |      |       |       |      |      |      | Sum of lost time (s) 28.0   |
| Intersection Capacity Utilization |       |      | 61.5% |       |      |      |       |       |      |      |      | ICU Level of Service B      |
| Analysis Period (min)             |       |      | 15    |       |      |      |       |       |      |      |      |                             |
| c Critical Lane Group             |       |      |       |       |      |      |       |       |      |      |      |                             |

201: Motel 6/North Site & Gosling Road  
 2036 No-Build Saturday Peak



| Movement                          | EBT         | EBR         | WBL         | WBT         | NBL                  | NBR         |             |
|-----------------------------------|-------------|-------------|-------------|-------------|----------------------|-------------|-------------|
| Lane Configurations               | ↑↑↑↑        |             |             | ↑↑          |                      | ↗           |             |
| Traffic Volume (veh/h)            | 1251        | 75          | 0           | 742         | 0                    | 58          |             |
| Future Volume (Veh/h)             | 1251        | 75          | 0           | 742         | 0                    | 58          |             |
| Sign Control                      | Free        |             |             | Free        | Stop                 |             |             |
| Grade                             | 0%          |             |             | 0%          | 0%                   |             |             |
| Peak Hour Factor                  | 0.93        | 0.93        | 0.95        | 0.95        | 0.55                 | 0.55        |             |
| Hourly flow rate (vph)            | 1345        | 81          | 0           | 781         | 0                    | 105         |             |
| <b>Pedestrians</b>                |             |             |             |             |                      |             |             |
| Lane Width (ft)                   |             |             |             |             |                      |             |             |
| Walking Speed (ft/s)              |             |             |             |             |                      |             |             |
| Percent Blockage                  |             |             |             |             |                      |             |             |
| Right turn flare (veh)            |             |             |             |             |                      |             |             |
| Median type                       | None        |             |             | None        |                      |             |             |
| Median storage (veh)              |             |             |             |             |                      |             |             |
| Upstream signal (ft)              | 464         |             |             |             |                      |             |             |
| pX, platoon unblocked             |             |             |             |             |                      |             |             |
| vC, conflicting volume            |             |             | 1426        |             | 1776                 | 377         |             |
| vC1, stage 1 conf vol             |             |             |             |             |                      |             |             |
| vC2, stage 2 conf vol             |             |             |             |             |                      |             |             |
| vCu, unblocked vol                |             |             | 1426        |             | 1776                 | 377         |             |
| tC, single (s)                    |             |             | 4.1         |             | 6.8                  | 6.9         |             |
| tC, 2 stage (s)                   |             |             |             |             |                      |             |             |
| tF (s)                            |             |             | 2.2         |             | 3.5                  | 3.3         |             |
| p0 queue free %                   |             |             | 100         |             | 100                  | 83          |             |
| cM capacity (veh/h)               |             |             | 478         |             | 75                   | 627         |             |
| <b>Direction, Lane #</b>          | <b>EB 1</b> | <b>EB 2</b> | <b>EB 3</b> | <b>EB 4</b> | <b>WB 1</b>          | <b>WB 2</b> | <b>NB 1</b> |
| Volume Total                      | 384         | 384         | 384         | 273         | 390                  | 390         | 105         |
| Volume Left                       | 0           | 0           | 0           | 0           | 0                    | 0           | 0           |
| Volume Right                      | 0           | 0           | 0           | 81          | 0                    | 0           | 105         |
| cSH                               | 1700        | 1700        | 1700        | 1700        | 1700                 | 1700        | 627         |
| Volume to Capacity                | 0.23        | 0.23        | 0.23        | 0.16        | 0.23                 | 0.23        | 0.17        |
| Queue Length 95th (ft)            | 0           | 0           | 0           | 0           | 0                    | 0           | 15          |
| Control Delay (s)                 | 0.0         | 0.0         | 0.0         | 0.0         | 0.0                  | 0.0         | 11.9        |
| Lane LOS                          |             |             |             |             |                      |             | B           |
| Approach Delay (s)                | 0.0         |             |             |             | 0.0                  |             | 11.9        |
| Approach LOS                      |             |             |             |             |                      |             | B           |
| <b>Intersection Summary</b>       |             |             |             |             |                      |             |             |
| Average Delay                     |             |             | 0.5         |             |                      |             |             |
| Intersection Capacity Utilization |             |             | 29.6%       |             | ICU Level of Service |             | A           |
| Analysis Period (min)             |             |             | 15          |             |                      |             |             |

202: Arthur F Brady Drive & South Site Driveway  
 2036 No-Build Saturday Peak

| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 6.3  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↕    | ↕     | ↕    | ↕    |
| Traffic Vol, veh/h       | 112  | 225  | 135  | 90    | 165  | 54   |
| Future Vol, veh/h        | 112  | 225  | 135  | 90    | 165  | 54   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 95   | 95   | 81   | 81    | 88   | 88   |
| Heavy Vehicles, %        | 1    | 1    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 118  | 237  | 167  | 111   | 188  | 61   |













| Major/Minor          | Major1 | Major2 | Minor2 |   |     |
|----------------------|--------|--------|--------|---|-----|
| Conflicting Flow All | 168    | 0      | -      | 0 | 641 |
| Stage 1              | -      | -      | -      | - | 168 |
| Stage 2              | -      | -      | -      | - | 473 |
| Critical Hdwy        | 4.11   | -      | -      | - | 6.4 |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.4 |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.4 |
| Follow-up Hdwy       | 2.209  | -      | -      | - | 3.5 |
| Pot Cap-1 Maneuver   | 1416   | -      | -      | - | 442 |
| Stage 1              | -      | -      | -      | - | 867 |
| Stage 2              | -      | -      | -      | - | 631 |
| Platoon blocked, %   |        | -      | -      | - |     |
| Mov Cap-1 Maneuver   | 1415   | -      | -      | - | 399 |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 399 |
| Stage 1              | -      | -      | -      | - | 783 |
| Stage 2              | -      | -      | -      | - | 630 |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.6 | 0  | 18.7 |
| HCM LOS              |     |    | C    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1415  | -   | -   | -   | 399   | 878   |
| HCM Lane V/C Ratio    | 0.083 | -   | -   | -   | 0.47  | 0.07  |
| HCM Control Delay (s) | 7.8   | 0   | -   | -   | 21.8  | 9.4   |
| HCM Lane LOS          | A     | A   | -   | -   | C     | A     |
| HCM 95th %tile Q(veh) | 0.3   | -   | -   | -   | 2.4   | 0.2   |



101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2026 Build Weekday AM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↘↗  |
| Traffic Volume (vph)              | 0   | 239   | 104   | 102   | 896   | 0   | 0  | 0   | 0   | 415   | 0   | 759   |
| Future Volume (vph)               | 0   | 239   | 104   | 102   | 896   | 0   | 0  | 0   | 0   | 415   | 0   | 759   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 5923  | 1516  | 3173  | 3388  |   |  |   |   | 1698  | 1698  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 5923  | 1516  | 3173  | 3388  |   |  |   |   | 1698  | 1698  | 2814  |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.87  | 0.87  | 0.87  | 0.90   | 0.90  | 0.90  | 0.86  | 0.86  | 0.86  |
| Adj. Flow (vph)                   | 0   | 257   | 112   | 117   | 1030  | 0   | 0  | 0   | 0   | 483   | 0   | 883   |
| RTOR Reduction (vph)              | 0   | 0   | 79  | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 170   |
| Lane Group Flow (vph)             | 0   | 257   | 33  | 117   | 1030  | 0   | 0  | 0   | 0   | 241   | 242   | 713   |
| Heavy Vehicles (%)                | 3%  | 3%  | 3%  | 3%  | 3%  | 3%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 28.3  | 28.3  | 24.7  | 59.0  |   |  |   |   | 25.1  | 25.1  | 25.1  |
| Effective Green, g (s)            |   | 28.3  | 28.3  | 24.7  | 59.0  |   |  |   |   | 25.1  | 25.1  | 25.1  |
| Actuated g/C Ratio                |   | 0.29  | 0.29  | 0.26  | 0.61  |   |  |   |   | 0.26  | 0.26  | 0.26  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 1744  | 446   | 815   | 2080  |   |  |   |   | 443   | 443   | 734   |
| v/s Ratio Prot                    |   | 0.04  | 0.02  | 0.04  | c0.30   |   |  |   |   | 0.14  | 0.14  | c0.25   |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.15  | 0.07  | 0.14  | 0.50  |   |  |   |   | 0.54  | 0.55  | 0.97  |
| Uniform Delay, d1                 |   | 25.0  | 24.4  | 27.5  | 10.3  |   |  |   |   | 30.6  | 30.6  | 35.1  |
| Progression Factor                |   | 1.00  | 1.00  | 0.89  | 1.58  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.1   | 0.1   | 0.1   | 0.3   |   |  |   |   | 2.4   | 2.4   | 26.5  |
| Delay (s)                         |   | 25.1  | 24.6  | 24.7  | 16.5  |   |  |   |   | 33.0  | 33.0  | 61.6  |
| Level of Service                  |   | C   | C   | C   | B   |   |  |   |   | C   | C   | E   |
| Approach Delay (s)                |   | 24.9  |   |   | 17.3  |   |  | 0.0   |   |   | 51.5  |   |
| Approach LOS                      |   | C   |   |   | B   |   |  | A   |   |   | D   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 34.5  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.69  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 96.1  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 61.3%   |   |   | ICU Level of Service  |  |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |






















c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2026 Build Weekday AM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL  | WBT   | WBR  | NBL                       | NBT  | NBR  | SBL  | SBT  | SBR  |
|-----------------------------------|-------|-------|-------|------|-------|------|---------------------------|------|------|------|------|------|
| Lane Configurations               |       |       |       |      |       |      |                           |      |      |      |      |      |
| Traffic Volume (vph)              | 110   | 544   | 0     | 0    | 305   | 44   | 693                       | 0    | 268  | 0    | 0    | 0    |
| Future Volume (vph)               | 110   | 544   | 0     | 0    | 305   | 44   | 693                       | 0    | 268  | 0    | 0    | 0    |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900 | 1900  | 1900 | 1900                      | 1900 | 1900 | 1900 | 1900 | 1900 |
| Lane Width                        | 10    | 11    | 12    | 12   | 12    | 12   | 12                        | 12   | 12   | 12   | 12   | 12   |
| Total Lost time (s)               | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Lane Util. Factor                 | 0.97  | 0.95  |       |      | 0.91  |      | 0.97                      | 0.95 | 0.95 |      |      |      |
| Frt                               | 1.00  | 1.00  |       |      | 0.98  |      | 1.00                      | 0.85 | 0.85 |      |      |      |
| Flt Protected                     | 0.95  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (prot)                 | 3236  | 3455  |       |      | 4847  |      | 3400                      | 1490 | 1490 |      |      |      |
| Flt Permitted                     | 0.51  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (perm)                 | 1743  | 3455  |       |      | 4847  |      | 3400                      | 1490 | 1490 |      |      |      |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.89 | 0.89  | 0.89 | 0.91                      | 0.91 | 0.91 | 0.90 | 0.90 | 0.90 |
| Adj. Flow (vph)                   | 118   | 585   | 0     | 0    | 343   | 49   | 762                       | 0    | 295  | 0    | 0    | 0    |
| RTOR Reduction (vph)              | 0     | 0     | 0     | 0    | 16    | 0    | 0                         | 109  | 109  | 0    | 0    | 0    |
| Lane Group Flow (vph)             | 118   | 585   | 0     | 0    | 376   | 0    | 762                       | 39   | 38   | 0    | 0    | 0    |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 5%   | 5%    | 5%   | 3%                        | 3%   | 3%   | 0%   | 0%   | 0%   |
| Turn Type                         | pm+pt | NA    |       |      | NA    |      | Split                     | NA   | Prot |      |      |      |
| Protected Phases                  | 1     | 6     |       |      | 2     |      | 3                         | 3    | 3    |      |      |      |
| Permitted Phases                  | 6     |       |       |      |       |      |                           |      |      |      |      |      |
| Actuated Green, G (s)             | 41.8  | 28.3  |       |      | 39.5  |      | 25.1                      | 25.1 | 25.1 |      |      |      |
| Effective Green, g (s)            | 41.8  | 28.3  |       |      | 39.5  |      | 25.1                      | 25.1 | 25.1 |      |      |      |
| Actuated g/C Ratio                | 0.43  | 0.29  |       |      | 0.41  |      | 0.26                      | 0.26 | 0.26 |      |      |      |
| Clearance Time (s)                | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Vehicle Extension (s)             | 4.0   | 5.0   |       |      | 5.0   |      | 5.0                       | 5.0  | 5.0  |      |      |      |
| Lane Grp Cap (vph)                | 967   | 1017  |       |      | 1992  |      | 888                       | 389  | 389  |      |      |      |
| v/s Ratio Prot                    | c0.02 | c0.17 |       |      | c0.08 |      | c0.22                     | 0.03 | 0.03 |      |      |      |
| v/s Ratio Perm                    | 0.04  |       |       |      |       |      |                           |      |      |      |      |      |
| v/c Ratio                         | 0.12  | 0.58  |       |      | 0.19  |      | 0.86                      | 0.10 | 0.10 |      |      |      |
| Uniform Delay, d1                 | 15.9  | 28.8  |       |      | 18.1  |      | 33.8                      | 26.9 | 26.9 |      |      |      |
| Progression Factor                | 1.26  | 1.24  |       |      | 1.00  |      | 1.00                      | 1.00 | 1.00 |      |      |      |
| Incremental Delay, d2             | 0.1   | 1.2   |       |      | 0.1   |      | 9.0                       | 0.2  | 0.2  |      |      |      |
| Delay (s)                         | 20.1  | 36.8  |       |      | 18.2  |      | 42.8                      | 27.2 | 27.2 |      |      |      |
| Level of Service                  | C     | D     |       |      | B     |      | D                         | C    | C    |      |      |      |
| Approach Delay (s)                |       | 34.0  |       |      | 18.2  |      |                           | 38.5 |      |      | 0.0  |      |
| Approach LOS                      |       | C     |       |      | B     |      |                           | D    |      |      | A    |      |
| <b>Intersection Summary</b>       |       |       |       |      |       |      |                           |      |      |      |      |      |
| HCM 2000 Control Delay            |       |       | 33.3  |      |       |      | HCM 2000 Level of Service |      |      | C    |      |      |
| HCM 2000 Volume to Capacity ratio |       |       | 0.53  |      |       |      |                           |      |      |      |      |      |
| Actuated Cycle Length (s)         |       |       | 96.1  |      |       |      | Sum of lost time (s)      |      |      | 18.0 |      |      |
| Intersection Capacity Utilization |       |       | 61.3% |      |       |      | ICU Level of Service      |      |      | B    |      |      |
| Analysis Period (min)             |       |       | 15    |      |       |      |                           |      |      |      |      |      |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2026 Build Weekday AM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |  |   |  |   |  |  |  |  |  |  |
| Traffic Volume (vph)              | 92  | 38  | 446   | 27  | 13  | 6   | 234  | 173   | 18  | 36  | 286   | 8   |
| Future Volume (vph)               | 92  | 38  | 446   | 27  | 13  | 6   | 234  | 173   | 18  | 36  | 286   | 8   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frt                               |   | 1.00  | 0.85  |   | 0.98  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 |   | 1706  | 1656  |   | 1605  |   | 3400   | 3456  |   | 1678  | 3355  | 1501  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 |   | 1706  | 1656  |   | 1605  |   | 3400   | 3456  |   | 1678  | 3355  | 1501  |
| Peak-hour factor, PHF             | 0.91  | 0.91  | 0.91  | 0.89  | 0.89  | 0.89  | 0.84   | 0.84  | 0.84  | 0.89  | 0.89  | 0.89  |
| Adj. Flow (vph)                   | 101   | 42  | 490   | 30  | 15  | 7   | 279  | 206   | 21  | 40  | 321   | 9   |
| RTOR Reduction (vph)              | 0   | 0   | 345   | 0   | 5   | 0   | 0  | 5   | 0   | 0   | 0   | 5   |
| Lane Group Flow (vph)             | 0   | 143   | 145   | 0   | 47  | 0   | 279  | 222   | 0   | 40  | 321   | 4   |
| Heavy Vehicles (%)                | 4%  | 4%  | 4%  | 13%   | 13%   | 13%   | 3%   | 3%  | 3%  | 4%  | 4%  | 4%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 9.0   | 21.5  |   | 4.8   |   | 12.5   | 25.0  |   | 4.3   | 16.3  | 31.3  |
| Effective Green, g (s)            |   | 9.0   | 21.5  |   | 4.8   |   | 12.5   | 25.0  |   | 4.3   | 16.3  | 31.3  |
| Actuated g/C Ratio                |   | 0.12  | 0.30  |   | 0.07  |   | 0.17   | 0.34  |   | 0.06  | 0.22  | 0.43  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                |   | 211   | 491   |   | 106   |   | 586  | 1191  |   | 99  | 754   | 648   |
| v/s Ratio Prot                    |   | c0.08   | 0.09  |   | c0.03   |   | c0.08  | 0.06  |   | 0.02  | c0.10   | 0.00  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.68  | 0.30  |   | 0.45  |   | 0.48   | 0.19  |   | 0.40  | 0.43  | 0.01  |
| Uniform Delay, d1                 |   | 30.4  | 19.7  |   | 32.6  |   | 27.0   | 16.6  |   | 32.9  | 24.1  | 11.7  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 8.3   | 0.3   |   | 3.0   |   | 0.6  | 0.1   |   | 2.7   | 0.4   | 0.0   |
| Delay (s)                         |   | 38.7  | 20.0  |   | 35.6  |   | 27.7   | 16.7  |   | 35.6  | 24.5  | 11.7  |
| Level of Service                  |   | D   | C   |   | D   |   | C  | B   |   | D   | C   | B   |
| Approach Delay (s)                |   | 24.2  |   |   | 35.6  |   |  | 22.7  |   |   | 25.4  |   |
| Approach LOS                      |   | C   |   |   | D   |   |  | C   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 24.4  |   |   |   | HCM 2000 Level of Service  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.45  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 72.5  |   |   |   | Sum of lost time (s)   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 57.2%   |   |   |   | ICU Level of Service   |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2026 Build Weekday AM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT  | WBR   | NBL  | NBT  | NBR   | SBL   | SBT   | SBR                         |
|-----------------------------------|-------|-------|-------|-------|------|-------|------|------|-------|-------|-------|-----------------------------|
| Lane Configurations               |       |       |       |       |      |       |      |      |       |       |       |                             |
| Traffic Volume (vph)              | 35    | 3     | 108   | 27    | 0    | 34    | 21   | 329  | 38    | 45    | 665   | 50                          |
| Future Volume (vph)               | 35    | 3     | 108   | 27    | 0    | 34    | 21   | 329  | 38    | 45    | 665   | 50                          |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900 | 1900  | 1900 | 1900 | 1900  | 1900  | 1900  | 1900                        |
| Lane Width                        | 11    | 11    | 11    | 11    | 11   | 11    | 11   | 11   | 16    | 11    | 11    | 11                          |
| Grade (%)                         |       | 3%    |       |       | -5%  |       |      | 5%   |       |       | -3%   |                             |
| Total Lost time (s)               | 6.0   | 6.0   | 6.0   | 5.5   | 5.5  | 5.5   | 6.0  | 6.0  | 5.5   | 5.5   | 6.0   | 6.0                         |
| Lane Util. Factor                 | 0.95  | 0.95  | 1.00  | 0.95  | 0.95 | 1.00  | 1.00 | 0.95 | 1.00  | 1.00  | 0.95  | 1.00                        |
| Frpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00 | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00                        |
| Flpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00 | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00                        |
| Frt                               | 1.00  | 1.00  | 0.85  | 1.00  | 1.00 | 0.85  | 1.00 | 1.00 | 0.85  | 1.00  | 1.00  | 0.85                        |
| Flt Protected                     | 0.95  | 0.96  | 1.00  | 0.95  | 0.95 | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00                        |
| Satd. Flow (prot)                 | 1570  | 1586  | 1479  | 1634  | 1634 | 1539  | 1652 | 3303 | 1733  | 1736  | 3473  | 1554                        |
| Flt Permitted                     | 0.95  | 0.96  | 1.00  | 0.95  | 0.95 | 1.00  | 0.95 | 1.00 | 1.00  | 0.95  | 1.00  | 1.00                        |
| Satd. Flow (perm)                 | 1570  | 1586  | 1479  | 1634  | 1634 | 1539  | 1652 | 3303 | 1733  | 1736  | 3473  | 1554                        |
| Peak-hour factor, PHF             | 0.82  | 0.82  | 0.82  | 0.65  | 0.65 | 0.65  | 0.85 | 0.85 | 0.85  | 0.98  | 0.98  | 0.98                        |
| Adj. Flow (vph)                   | 43    | 4     | 132   | 42    | 0    | 52    | 25   | 387  | 45    | 46    | 679   | 51                          |
| RTOR Reduction (vph)              | 0     | 0     | 108   | 0     | 0    | 0     | 0    | 0    | 26    | 0     | 0     | 25                          |
| Lane Group Flow (vph)             | 23    | 24    | 24    | 21    | 21   | 52    | 25   | 387  | 19    | 46    | 679   | 26                          |
| Confl. Bikes (#/hr)               |       |       |       |       |      |       |      |      | 1     |       |       |                             |
| Heavy Vehicles (%)                | 4%    | 4%    | 4%    | 4%    | 4%   | 4%    | 3%   | 3%   | 3%    | 2%    | 2%    | 2%                          |
| Turn Type                         | Split | NA    | pt+ov | Split | NA   | pt+ov | Prot | NA   | pt+ov | Prot  | NA    | pt+ov                       |
| Protected Phases                  | 3     | 3     | 1 3   | 4     | 4    | 4 5   | 1    | 6    | 4 6   | 5     | 2     | 2 3                         |
| Permitted Phases                  |       |       |       |       |      |       |      |      |       |       |       |                             |
| Actuated Green, G (s)             | 7.1   | 7.1   | 13.6  | 5.9   | 5.9  | 12.8  | 6.5  | 24.7 | 30.6  | 6.9   | 24.6  | 37.7                        |
| Effective Green, g (s)            | 7.1   | 7.1   | 13.6  | 5.9   | 5.9  | 12.8  | 6.5  | 24.7 | 30.6  | 6.9   | 24.6  | 37.7                        |
| Actuated g/C Ratio                | 0.10  | 0.10  | 0.18  | 0.08  | 0.08 | 0.17  | 0.09 | 0.34 | 0.42  | 0.09  | 0.33  | 0.51                        |
| Clearance Time (s)                | 6.0   | 6.0   |       | 5.5   | 5.5  |       | 6.0  | 6.0  |       | 5.5   | 6.0   |                             |
| Vehicle Extension (s)             | 3.0   | 3.0   |       | 3.0   | 3.0  |       | 3.0  | 3.0  |       | 3.0   | 3.0   |                             |
| Lane Grp Cap (vph)                | 151   | 152   | 273   | 130   | 130  | 267   | 145  | 1108 | 720   | 162   | 1160  | 796                         |
| v/s Ratio Prot                    | 0.01  | c0.02 | 0.02  | 0.01  | 0.01 | c0.03 | 0.02 | 0.12 | 0.01  | c0.03 | c0.20 | 0.02                        |
| v/s Ratio Perm                    |       |       |       |       |      |       |      |      |       |       |       |                             |
| v/c Ratio                         | 0.15  | 0.16  | 0.09  | 0.16  | 0.16 | 0.19  | 0.17 | 0.35 | 0.03  | 0.28  | 0.59  | 0.03                        |
| Uniform Delay, d1                 | 30.5  | 30.5  | 24.9  | 31.5  | 31.5 | 26.0  | 31.1 | 18.4 | 12.7  | 31.0  | 20.3  | 8.9                         |
| Progression Factor                | 1.00  | 1.00  | 1.00  | 1.00  | 1.00 | 1.00  | 1.00 | 1.00 | 1.00  | 1.00  | 1.00  | 1.00                        |
| Incremental Delay, d2             | 0.5   | 0.5   | 0.1   | 0.6   | 0.6  | 0.4   | 0.6  | 0.2  | 0.0   | 1.0   | 0.8   | 0.0                         |
| Delay (s)                         | 31.0  | 31.0  | 25.0  | 32.1  | 32.1 | 26.4  | 31.6 | 18.6 | 12.7  | 32.0  | 21.0  | 8.9                         |
| Level of Service                  | C     | C     | C     | C     | C    | C     | C    | B    | B     | C     | C     | A                           |
| Approach Delay (s)                |       | 26.6  |       |       | 28.9 |       |      | 18.7 |       |       | 20.9  |                             |
| Approach LOS                      |       | C     |       |       | C    |       |      | B    |       |       | C     |                             |
| <b>Intersection Summary</b>       |       |       |       |       |      |       |      |      |       |       |       |                             |
| HCM 2000 Control Delay            |       |       | 21.4  |       |      |       |      |      |       |       |       | HCM 2000 Level of Service C |
| HCM 2000 Volume to Capacity ratio |       |       | 0.39  |       |      |       |      |      |       |       |       |                             |
| Actuated Cycle Length (s)         |       |       | 73.6  |       |      |       |      |      |       |       |       | Sum of lost time (s) 25.5   |
| Intersection Capacity Utilization |       |       | 46.1% |       |      |       |      |      |       |       |       | ICU Level of Service A      |
| Analysis Period (min)             |       |       | 15    |       |      |       |      |      |       |       |       |                             |


c Critical Lane Group

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2026 Build Weekday AM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR  | NBL   | NBT   | NBR  | SBL  | SBT  | SBR   |
|-----------------------------------|-------|-------|-------|-------|-------|------|-------|-------|------|------|------|-------|
| Lane Configurations               |       |       |       |       |       |      |       |       |      |      |      |       |
| Traffic Volume (vph)              | 108   | 39    | 47    | 3     | 32    | 40   | 66    | 299   | 77   | 2    | 296  | 246   |
| Future Volume (vph)               | 108   | 39    | 47    | 3     | 32    | 40   | 66    | 299   | 77   | 2    | 296  | 246   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900 | 1900  | 1900  | 1900 | 1900 | 1900 | 1900  |
| Lane Width                        | 11    | 11    | 11    | 14    | 14    | 14   | 11    | 11    | 11   | 11   | 11   | 11    |
| Grade (%)                         |       | 5%    |       |       | -5%   |      |       | 0%    |      |      | 0%   |       |
| Total Lost time (s)               | 6.5   | 6.5   |       | 6.5   | 6.5   |      | 6.5   | 6.5   |      | 6.5  | 6.5  | 6.5   |
| Lane Util. Factor                 | 0.97  | 1.00  |       | 1.00  | 1.00  |      | 1.00  | 0.95  |      | 1.00 | 0.95 | 1.00  |
| Frpb, ped/bikes                   | 1.00  | 0.99  |       | 1.00  | 1.00  |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |
| Flpb, ped/bikes                   | 1.00  | 1.00  |       | 1.00  | 1.00  |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |
| Frt                               | 1.00  | 0.92  |       | 1.00  | 0.92  |      | 1.00  | 0.97  |      | 1.00 | 1.00 | 0.85  |
| Flt Protected                     | 0.95  | 1.00  |       | 0.95  | 1.00  |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00  |
| Satd. Flow (prot)                 | 3268  | 1615  |       | 1898  | 1830  |      | 1711  | 3302  |      | 1694 | 3388 | 1516  |
| Flt Permitted                     | 0.95  | 1.00  |       | 0.95  | 1.00  |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00  |
| Satd. Flow (perm)                 | 3268  | 1615  |       | 1898  | 1830  |      | 1711  | 3302  |      | 1694 | 3388 | 1516  |
| Peak-hour factor, PHF             | 0.73  | 0.73  | 0.73  | 0.65  | 0.65  | 0.65 | 0.75  | 0.75  | 0.75 | 0.97 | 0.97 | 0.97  |
| Adj. Flow (vph)                   | 148   | 53    | 64    | 5     | 49    | 62   | 88    | 399   | 103  | 2    | 305  | 254   |
| RTOR Reduction (vph)              | 0     | 34    | 0     | 0     | 40    | 0    | 0     | 17    | 0    | 0    | 0    | 127   |
| Lane Group Flow (vph)             | 148   | 83    | 0     | 5     | 71    | 0    | 88    | 485   | 0    | 2    | 305  | 127   |
| Confl. Bikes (#/hr)               |       |       | 1     |       |       |      |       |       | 1    |      |      |       |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 4%    | 4%    | 4%   | 2%    | 2%    | 2%   | 3%   | 3%   | 3%    |
| Turn Type                         | Split | NA    |       | Split | NA    |      | Prot  | NA    |      | Prot | NA   | pt+ov |
| Protected Phases                  | 3     | 3     |       | 4     | 4     |      | 1     | 6     |      | 5    | 2    | 2 3   |
| Permitted Phases                  |       |       |       |       |       |      |       |       |      |      |      |       |
| Actuated Green, G (s)             | 9.4   | 9.4   |       | 6.3   | 6.3   |      | 6.9   | 22.7  |      | 0.9  | 16.7 | 32.6  |
| Effective Green, g (s)            | 9.4   | 9.4   |       | 6.3   | 6.3   |      | 6.9   | 22.7  |      | 0.9  | 16.7 | 32.6  |
| Actuated g/C Ratio                | 0.14  | 0.14  |       | 0.10  | 0.10  |      | 0.11  | 0.35  |      | 0.01 | 0.26 | 0.50  |
| Clearance Time (s)                | 6.5   | 6.5   |       | 6.5   | 6.5   |      | 6.5   | 6.5   |      | 6.5  | 6.5  | 6.5   |
| Vehicle Extension (s)             | 3.0   | 3.0   |       | 3.0   | 3.0   |      | 3.0   | 3.0   |      | 3.0  | 3.0  | 3.0   |
| Lane Grp Cap (vph)                | 470   | 232   |       | 183   | 176   |      | 180   | 1147  |      | 23   | 866  | 756   |
| v/s Ratio Prot                    | 0.05  | c0.05 |       | 0.00  | c0.04 |      | c0.05 | c0.15 |      | 0.00 | 0.09 | 0.08  |
| v/s Ratio Perm                    |       |       |       |       |       |      |       |       |      |      |      |       |
| v/c Ratio                         | 0.31  | 0.36  |       | 0.03  | 0.40  |      | 0.49  | 0.42  |      | 0.09 | 0.35 | 0.17  |
| Uniform Delay, d1                 | 25.1  | 25.2  |       | 26.7  | 27.7  |      | 27.5  | 16.3  |      | 31.8 | 19.9 | 8.9   |
| Progression Factor                | 1.00  | 1.00  |       | 1.00  | 1.00  |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |
| Incremental Delay, d2             | 0.4   | 0.9   |       | 0.1   | 1.5   |      | 2.1   | 0.3   |      | 1.6  | 0.2  | 0.1   |
| Delay (s)                         | 25.4  | 26.2  |       | 26.8  | 29.3  |      | 29.6  | 16.5  |      | 33.4 | 20.1 | 9.0   |
| Level of Service                  | C     | C     |       | C     | C     |      | C     | B     |      | C    | C    | A     |
| Approach Delay (s)                |       | 25.8  |       |       | 29.2  |      |       | 18.5  |      |      | 15.2 |       |
| Approach LOS                      |       | C     |       |       | C     |      |       | B     |      |      | B    |       |
| <b>Intersection Summary</b>       |       |       |       |       |       |      |       |       |      |      |      |       |
| HCM 2000 Control Delay            |       |       | 19.3  |       |       |      |       |       |      |      |      | B     |
| HCM 2000 Volume to Capacity ratio |       |       | 0.48  |       |       |      |       |       |      |      |      |       |
| Actuated Cycle Length (s)         |       |       | 65.3  |       |       |      |       |       |      | 28.0 |      |       |
| Intersection Capacity Utilization |       |       | 41.7% |       |       |      |       |       |      |      |      | A     |
| ICU Level of Service              |       |       |       |       |       |      |       |       |      |      |      |       |
| Analysis Period (min)             |       |       | 15    |       |       |      |       |       |      |      |      |       |

c Critical Lane Group

201: Motel 6/North Site & Gosling Road  
2026 Build Weekday AM Peak



| Movement                          | EBT         | EBR         | WBL         | WBT         | NBL                  | NBR         |             |
|-----------------------------------|-------------|-------------|-------------|-------------|----------------------|-------------|-------------|
| Lane Configurations               | ↑↑↑↑        |             |             | ↑↑          |                      | ↗           |             |
| Traffic Volume (veh/h)            | 711         | 101         | 0           | 349         | 0                    | 13          |             |
| Future Volume (Veh/h)             | 711         | 101         | 0           | 349         | 0                    | 13          |             |
| Sign Control                      | Free        |             |             | Free        | Stop                 |             |             |
| Grade                             | 0%          |             |             | 0%          | 0%                   |             |             |
| Peak Hour Factor                  | 0.97        | 0.97        | 0.89        | 0.89        | 0.46                 | 0.46        |             |
| Hourly flow rate (vph)            | 733         | 104         | 0           | 392         | 0                    | 28          |             |
| <b>Pedestrians</b>                |             |             |             |             |                      |             |             |
| Lane Width (ft)                   |             |             |             |             |                      |             |             |
| Walking Speed (ft/s)              |             |             |             |             |                      |             |             |
| Percent Blockage                  |             |             |             |             |                      |             |             |
| Right turn flare (veh)            |             |             |             |             |                      |             |             |
| Median type                       | None        |             |             | None        |                      |             |             |
| Median storage (veh)              |             |             |             |             |                      |             |             |
| Upstream signal (ft)              | 464         |             |             |             |                      |             |             |
| pX, platoon unblocked             |             |             |             |             |                      |             |             |
| vC, conflicting volume            |             |             | 837         |             | 981                  | 235         |             |
| vC1, stage 1 conf vol             |             |             |             |             |                      |             |             |
| vC2, stage 2 conf vol             |             |             |             |             |                      |             |             |
| vCu, unblocked vol                |             |             | 837         |             | 981                  | 235         |             |
| tC, single (s)                    |             |             | 4.2         |             | 6.8                  | 6.9         |             |
| tC, 2 stage (s)                   |             |             |             |             |                      |             |             |
| tF (s)                            |             |             | 2.2         |             | 3.5                  | 3.3         |             |
| p0 queue free %                   |             |             | 100         |             | 100                  | 96          |             |
| cM capacity (veh/h)               |             |             | 774         |             | 250                  | 773         |             |
| <b>Direction, Lane #</b>          | <b>EB 1</b> | <b>EB 2</b> | <b>EB 3</b> | <b>EB 4</b> | <b>WB 1</b>          | <b>WB 2</b> | <b>NB 1</b> |
| Volume Total                      | 209         | 209         | 209         | 209         | 196                  | 196         | 28          |
| Volume Left                       | 0           | 0           | 0           | 0           | 0                    | 0           | 0           |
| Volume Right                      | 0           | 0           | 0           | 104         | 0                    | 0           | 28          |
| cSH                               | 1700        | 1700        | 1700        | 1700        | 1700                 | 1700        | 773         |
| Volume to Capacity                | 0.12        | 0.12        | 0.12        | 0.12        | 0.12                 | 0.12        | 0.04        |
| Queue Length 95th (ft)            | 0           | 0           | 0           | 0           | 0                    | 0           | 3           |
| Control Delay (s)                 | 0.0         | 0.0         | 0.0         | 0.0         | 0.0                  | 0.0         | 9.8         |
| Lane LOS                          |             |             |             |             |                      |             | A           |
| Approach Delay (s)                | 0.0         |             |             |             | 0.0                  |             | 9.8         |
| Approach LOS                      |             |             |             |             |                      |             | A           |
| <b>Intersection Summary</b>       |             |             |             |             |                      |             |             |
| Average Delay                     |             |             | 0.2         |             |                      |             |             |
| Intersection Capacity Utilization |             |             | 22.0%       |             | ICU Level of Service |             | A           |
| Analysis Period (min)             |             |             | 15          |             |                      |             |             |

202: Arthur F Brady Drive & South Site Driveway  
 2026 Build Weekday AM Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 4.7  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↑    | ↗     | ↖    | ↗    |
| Traffic Vol, veh/h       | 59   | 87   | 77   | 71    | 82   | 71   |
| Future Vol, veh/h        | 59   | 87   | 77   | 71    | 82   | 71   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 85   | 85   | 84   | 84    | 81   | 81   |
| Heavy Vehicles, %        | 4    | 4    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 69   | 102  | 92   | 85    | 101  | 88   |

| Major/Minor          | Major1 | Major2 | Minor2 |   |         |
|----------------------|--------|--------|--------|---|---------|
| Conflicting Flow All | 93     | 0      | -      | 0 | 333 94  |
| Stage 1              | -      | -      | -      | - | 93 -    |
| Stage 2              | -      | -      | -      | - | 240 -   |
| Critical Hdwy        | 4.14   | -      | -      | - | 6.4 6.2 |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.4 -   |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.4 -   |
| Follow-up Hdwy       | 2.236  | -      | -      | - | 3.5 3.3 |
| Pot Cap-1 Maneuver   | 1489   | -      | -      | - | 666 968 |
| Stage 1              | -      | -      | -      | - | 936 -   |
| Stage 2              | -      | -      | -      | - | 805 -   |
| Platoon blocked, %   |        | -      | -      | - |         |
| Mov Cap-1 Maneuver   | 1488   | -      | -      | - | 632 966 |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 632 -   |
| Stage 1              | -      | -      | -      | - | 889 -   |
| Stage 2              | -      | -      | -      | - | 804 -   |

| Approach             | EB | WB | SB   |
|----------------------|----|----|------|
| HCM Control Delay, s | 3  | 0  | 10.5 |
| HCM LOS              |    |    | B    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1488  | -   | -   | -   | 632   | 966   |
| HCM Lane V/C Ratio    | 0.047 | -   | -   | -   | 0.16  | 0.091 |
| HCM Control Delay (s) | 7.5   | 0   | -   | -   | 11.8  | 9.1   |
| HCM Lane LOS          | A     | A   | -   | -   | B     | A     |
| HCM 95th %tile Q(veh) | 0.1   | -   | -   | -   | 0.6   | 0.3   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2026 Build Weekday PM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↘↗  |
| Traffic Volume (vph)              | 0   | 1171  | 586   | 469   | 308   | 0   | 0  | 0   | 0   | 251   | 1   | 114   |
| Future Volume (vph)               | 0   | 1171  | 586   | 469   | 308   | 0   | 0  | 0   | 0   | 251   | 1   | 114   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.94  | 0.94  | 0.94  | 0.92   | 0.92  | 0.92  | 0.94  | 0.94  | 0.94  |
| Adj. Flow (vph)                   | 0   | 1394  | 698   | 499   | 328   | 0   | 0  | 0   | 0   | 267   | 1   | 121   |
| RTOR Reduction (vph)              | 0   | 0   | 361   | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 96  |
| Lane Group Flow (vph)             | 0   | 1394  | 337   | 499   | 328   | 0   | 0  | 0   | 0   | 133   | 135   | 25  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 35.6  | 35.6  | 21.5  | 56.6  |   |  |   |   | 19.6  | 19.6  | 19.6  |
| Effective Green, g (s)            |   | 35.6  | 35.6  | 21.5  | 56.6  |   |  |   |   | 19.6  | 19.6  | 19.6  |
| Actuated g/C Ratio                |   | 0.38  | 0.38  | 0.23  | 0.60  |   |  |   |   | 0.21  | 0.21  | 0.21  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 2270  | 581   | 734   | 2064  |   |  |   |   | 351   | 352   | 582   |
| v/s Ratio Prot                    |   | c0.23   | 0.22  | c0.15   | 0.09  |   |  |   |   | 0.08  | c0.08   | 0.01  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.61  | 0.58  | 0.68  | 0.16  |   |  |   |   | 0.38  | 0.38  | 0.04  |
| Uniform Delay, d1                 |   | 24.0  | 23.6  | 33.5  | 8.5   |   |  |   |   | 32.3  | 32.3  | 30.0  |
| Progression Factor                |   | 1.00  | 1.00  | 1.37  | 0.85  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.7   | 2.3   | 2.5   | 0.1   |   |  |   |   | 1.4   | 1.5   | 0.1   |
| Delay (s)                         |   | 24.7  | 25.9  | 48.3  | 7.3   |   |  |   |   | 33.7  | 33.8  | 30.1  |
| Level of Service                  |   | C   | C   | D   | A   |   |  |   |   | C   | C   | C   |
| Approach Delay (s)                |   | 25.1  |   |   | 32.0  |   |  | 0.0   |   |   | 32.6  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 27.7  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.57  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 94.7  |   |   | Sum of lost time (s)  |  |   | 18.0  |   |   |   |
| Intersection Capacity Utilization |   |   | 71.6%   |   |   | ICU Level of Service  |  |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group























102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2026 Build Weekday PM Peak

| Movement                          | EBL   | EBT  | EBR   | WBL  | WBT  | WBR  | NBL                       | NBT  | NBR  | SBL  | SBT  | SBR  |
|-----------------------------------|-------|------|-------|------|------|------|---------------------------|------|------|------|------|------|
| Lane Configurations               |       |      |       |      |      |      |                           |      |      |      |      |      |
| Traffic Volume (vph)              | 718   | 704  | 0     | 0    | 635  | 330  | 142                       | 0    | 538  | 0    | 0    | 0    |
| Future Volume (vph)               | 718   | 704  | 0     | 0    | 635  | 330  | 142                       | 0    | 538  | 0    | 0    | 0    |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900 | 1900 | 1900 | 1900                      | 1900 | 1900 | 1900 | 1900 | 1900 |
| Lane Width                        | 10    | 11   | 12    | 12   | 12   | 12   | 12                        | 12   | 12   | 12   | 12   | 12   |
| Total Lost time (s)               | 6.0   | 6.0  |       |      | 6.0  |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Lane Util. Factor                 | 0.97  | 0.95 |       |      | 0.91 |      | 0.97                      | 0.95 | 0.95 |      |      |      |
| Frt                               | 1.00  | 1.00 |       |      | 0.95 |      | 1.00                      | 0.85 | 0.85 |      |      |      |
| Flt Protected                     | 0.95  | 1.00 |       |      | 1.00 |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (prot)                 | 3236  | 3455 |       |      | 4872 |      | 3433                      | 1504 | 1504 |      |      |      |
| Flt Permitted                     | 0.19  | 1.00 |       |      | 1.00 |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (perm)                 | 647   | 3455 |       |      | 4872 |      | 3433                      | 1504 | 1504 |      |      |      |
| Peak-hour factor, PHF             | 0.87  | 0.87 | 0.87  | 0.94 | 0.94 | 0.94 | 0.94                      | 0.94 | 0.94 | 0.90 | 0.90 | 0.90 |
| Adj. Flow (vph)                   | 825   | 809  | 0     | 0    | 676  | 351  | 151                       | 0    | 572  | 0    | 0    | 0    |
| RTOR Reduction (vph)              | 0     | 0    | 0     | 0    | 87   | 0    | 0                         | 227  | 227  | 0    | 0    | 0    |
| Lane Group Flow (vph)             | 825   | 809  | 0     | 0    | 940  | 0    | 151                       | 59   | 59   | 0    | 0    | 0    |
| Heavy Vehicles (%)                | 1%    | 1%   | 1%    | 1%   | 1%   | 1%   | 2%                        | 2%   | 2%   | 0%   | 0%   | 0%   |
| Turn Type                         | pm+pt | NA   |       |      | NA   |      | Split                     | NA   | Prot |      |      |      |
| Protected Phases                  | 1     | 6    |       |      | 2    |      | 3                         | 3    | 3    |      |      |      |
| Permitted Phases                  | 6     |      |       |      |      |      |                           |      |      |      |      |      |
| Actuated Green, G (s)             | 57.6  | 35.6 |       |      | 35.1 |      | 19.6                      | 19.6 | 19.6 |      |      |      |
| Effective Green, g (s)            | 57.6  | 35.6 |       |      | 35.1 |      | 19.6                      | 19.6 | 19.6 |      |      |      |
| Actuated g/C Ratio                | 0.61  | 0.38 |       |      | 0.37 |      | 0.21                      | 0.21 | 0.21 |      |      |      |
| Clearance Time (s)                | 6.0   | 6.0  |       |      | 6.0  |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Vehicle Extension (s)             | 4.0   | 5.0  |       |      | 5.0  |      | 5.0                       | 5.0  | 5.0  |      |      |      |
| Lane Grp Cap (vph)                | 994   | 1298 |       |      | 1805 |      | 710                       | 311  | 311  |      |      |      |
| v/s Ratio Prot                    | c0.19 | 0.23 |       |      | 0.19 |      | c0.04                     | 0.04 | 0.04 |      |      |      |
| v/s Ratio Perm                    | c0.31 |      |       |      |      |      |                           |      |      |      |      |      |
| v/c Ratio                         | 0.83  | 0.62 |       |      | 0.52 |      | 0.21                      | 0.19 | 0.19 |      |      |      |
| Uniform Delay, d1                 | 16.9  | 24.1 |       |      | 23.2 |      | 31.1                      | 31.0 | 31.0 |      |      |      |
| Progression Factor                | 2.22  | 0.47 |       |      | 1.00 |      | 1.00                      | 1.00 | 1.00 |      |      |      |
| Incremental Delay, d2             | 5.1   | 1.1  |       |      | 0.5  |      | 0.3                       | 0.6  | 0.6  |      |      |      |
| Delay (s)                         | 42.6  | 12.3 |       |      | 23.8 |      | 31.5                      | 31.6 | 31.6 |      |      |      |
| Level of Service                  | D     | B    |       |      | C    |      | C                         | C    | C    |      |      |      |
| Approach Delay (s)                |       | 27.6 |       |      | 23.8 |      |                           | 31.6 |      |      | 0.0  |      |
| Approach LOS                      |       | C    |       |      | C    |      |                           | C    |      |      | A    |      |
| <b>Intersection Summary</b>       |       |      |       |      |      |      |                           |      |      |      |      |      |
| HCM 2000 Control Delay            |       |      | 27.3  |      |      |      | HCM 2000 Level of Service |      |      | C    |      |      |
| HCM 2000 Volume to Capacity ratio |       |      | 0.68  |      |      |      |                           |      |      |      |      |      |
| Actuated Cycle Length (s)         |       |      | 94.7  |      |      |      | Sum of lost time (s)      |      |      | 18.0 |      |      |
| Intersection Capacity Utilization |       |      | 71.6% |      |      |      | ICU Level of Service      |      |      | C    |      |      |
| Analysis Period (min)             |       |      | 15    |      |      |      |                           |      |      |      |      |      |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2026 Build Weekday PM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |  |   |  |   |  |  |   |  |  |  |
| Traffic Volume (vph)              | 89  | 61  | 505   | 61  | 56  | 49  | 364  | 484   | 34  | 31  | 473   | 122   |
| Future Volume (vph)               | 89  | 61  | 505   | 61  | 56  | 49  | 364  | 484   | 34  | 31  | 473   | 122   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frbp, ped/bikes                   |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Flpb, ped/bikes                   |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Frt                               |   | 1.00  | 0.85  |   | 0.96  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.98  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 |   | 1749  | 1689  |   | 1756  |   | 3467   | 3534  |   | 1711  | 3421  | 1531  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.98  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 |   | 1749  | 1689  |   | 1756  |   | 3467   | 3534  |   | 1711  | 3421  | 1531  |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.80  | 0.80  | 0.80  | 0.96   | 0.96  | 0.96  | 0.97  | 0.97  | 0.97  |
| Adj. Flow (vph)                   | 99  | 68  | 561   | 76  | 70  | 61  | 379  | 504   | 35  | 32  | 488   | 126   |
| RTOR Reduction (vph)              | 0   | 0   | 424   | 0   | 13  | 0   | 0  | 3   | 0   | 0   | 0   | 74  |
| Lane Group Flow (vph)             | 0   | 167   | 137   | 0   | 194   | 0   | 379  | 536   | 0   | 32  | 488   | 52  |
| Confl. Bikes (#/hr)               |   |   |   |   |   |   |  |   | 2   |   |   |   |
| Heavy Vehicles (%)                | 2%  | 2%  | 2%  | 2%  | 2%  | 2%  | 1%   | 1%  | 1%  | 2%  | 2%  | 2%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 8.4   | 22.1  |   | 15.0  |   | 13.7   | 34.3  |   | 2.9   | 23.0  | 37.4  |
| Effective Green, g (s)            |   | 8.4   | 22.1  |   | 15.0  |   | 13.7   | 34.3  |   | 2.9   | 23.0  | 37.4  |
| Actuated g/C Ratio                |   | 0.09  | 0.24  |   | 0.17  |   | 0.15   | 0.38  |   | 0.03  | 0.25  | 0.41  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                |   | 162   | 411   |   | 290   |   | 524  | 1337  |   | 54  | 868   | 632   |
| v/s Ratio Prot                    |   | c0.10   | 0.08  |   | c0.11   |   | c0.11  | 0.15  |   | 0.02  | c0.14   | 0.03  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 1.03  | 0.33  |   | 0.67  |   | 0.72   | 0.40  |   | 0.59  | 0.56  | 0.08  |
| Uniform Delay, d1                 |   | 41.1  | 28.2  |   | 35.5  |   | 36.6   | 20.6  |   | 43.3  | 29.4  | 16.2  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 79.1  | 0.5   |   | 6.0   |   | 4.9  | 0.2   |   | 16.2  | 0.8   | 0.1   |
| Delay (s)                         |   | 120.2   | 28.7  |   | 41.5  |   | 41.6   | 20.8  |   | 59.5  | 30.3  | 16.2  |
| Level of Service                  |   | F   | C   |   | D   |   | D  | C   |   | E   | C   | B   |
| Approach Delay (s)                |   | 49.7  |   |   | 41.5  |   | 29.4   |   |   | 29.0  |   |   |
| Approach LOS                      |   | D   |   |   | D   |   | C  |   |   | C   |   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 36.2  |   |   |   | HCM 2000 Level of Service  |   |   |   | D   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.64  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 90.6  |   |   |   | Sum of lost time (s)   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 68.2%   |   |   |   | ICU Level of Service   |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |


104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
2026 Build Weekday PM Peak

| Movement                          | EBL   | EBT  | EBR   | WBL   | WBT                       | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |  |
|-----------------------------------|-------|------|-------|-------|---------------------------|-------|------|-------|-------|-------|-------|-------|--|
| Lane Configurations               |       |      |       |       |                           |       |      |       |       |       |       |       |  |
| Traffic Volume (vph)              | 123   | 19   | 105   | 106   | 16                        | 95    | 65   | 691   | 100   | 78    | 710   | 29    |  |
| Future Volume (vph)               | 123   | 19   | 105   | 106   | 16                        | 95    | 65   | 691   | 100   | 78    | 710   | 29    |  |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900  | 1900                      | 1900  | 1900 | 1900  | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11    | 11   | 11    | 11    | 11                        | 11    | 11   | 11    | 16    | 11    | 11    | 11    |  |
| Grade (%)                         |       | 3%   |       |       | -5%                       |       |      | 5%    |       |       | -3%   |       |  |
| Total Lost time (s)               | 6.0   | 6.0  | 6.0   | 5.5   | 5.5                       | 5.5   | 6.0  | 6.0   | 5.5   | 5.5   | 6.0   | 6.0   |  |
| Lane Util. Factor                 | 0.95  | 0.95 | 1.00  | 0.95  | 0.95                      | 1.00  | 1.00 | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  |  |
| Frt                               | 1.00  | 1.00 | 0.85  | 1.00  | 1.00                      | 0.85  | 1.00 | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     | 0.95  | 0.96 | 1.00  | 0.95  | 0.96                      | 1.00  | 0.95 | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 | 1633  | 1658 | 1424  | 1682  | 1708                      | 1584  | 1684 | 3369  | 1767  | 1753  | 3507  | 1569  |  |
| Flt Permitted                     | 0.95  | 0.96 | 1.00  | 0.95  | 0.96                      | 1.00  | 0.95 | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 | 1633  | 1658 | 1424  | 1682  | 1708                      | 1584  | 1684 | 3369  | 1767  | 1753  | 3507  | 1569  |  |
| Peak-hour factor, PHF             | 0.86  | 0.86 | 0.86  | 0.77  | 0.77                      | 0.77  | 0.87 | 0.87  | 0.87  | 0.94  | 0.94  | 0.94  |  |
| Adj. Flow (vph)                   | 143   | 22   | 122   | 138   | 21                        | 123   | 75   | 794   | 115   | 83    | 755   | 31    |  |
| RTOR Reduction (vph)              | 0     | 0    | 98    | 0     | 0                         | 0     | 0    | 0     | 65    | 0     | 0     | 14    |  |
| Lane Group Flow (vph)             | 82    | 83   | 24    | 79    | 80                        | 123   | 75   | 794   | 50    | 83    | 755   | 17    |  |
| Heavy Vehicles (%)                | 0%    | 0%   | 8%    | 1%    | 1%                        | 1%    | 1%   | 1%    | 1%    | 1%    | 1%    | 1%    |  |
| Turn Type                         | Split | NA   | pt+ov | Split | NA                        | pt+ov | Prot | NA    | pt+ov | Prot  | NA    | pt+ov |  |
| Protected Phases                  | 3     | 3    | 13    | 4     | 4                         | 45    | 1    | 6     | 46    | 5     | 2     | 23    |  |
| Permitted Phases                  |       |      |       |       |                           |       |      |       |       |       |       |       |  |
| Actuated Green, G (s)             | 7.9   | 7.9  | 13.9  | 8.1   | 8.1                       | 22.8  | 6.0  | 23.2  | 31.3  | 9.2   | 25.9  | 39.8  |  |
| Effective Green, g (s)            | 7.9   | 7.9  | 13.9  | 8.1   | 8.1                       | 22.8  | 6.0  | 23.2  | 31.3  | 9.2   | 25.9  | 39.8  |  |
| Actuated g/C Ratio                | 0.11  | 0.11 | 0.19  | 0.11  | 0.11                      | 0.32  | 0.08 | 0.32  | 0.44  | 0.13  | 0.36  | 0.56  |  |
| Clearance Time (s)                | 6.0   | 6.0  |       | 5.5   | 5.5                       |       | 6.0  | 6.0   |       | 5.5   | 6.0   |       |  |
| Vehicle Extension (s)             | 3.0   | 3.0  |       | 3.0   | 3.0                       |       | 3.0  | 3.0   |       | 3.0   | 3.0   |       |  |
| Lane Grp Cap (vph)                | 180   | 183  | 277   | 190   | 193                       | 505   | 141  | 1094  | 774   | 225   | 1272  | 874   |  |
| v/s Ratio Prot                    | c0.05 | 0.05 | 0.02  | c0.05 | 0.05                      | 0.08  | 0.04 | c0.24 | 0.03  | c0.05 | c0.22 | 0.01  |  |
| v/s Ratio Perm                    |       |      |       |       |                           |       |      |       |       |       |       |       |  |
| v/c Ratio                         | 0.46  | 0.45 | 0.09  | 0.42  | 0.41                      | 0.24  | 0.53 | 0.73  | 0.07  | 0.37  | 0.59  | 0.02  |  |
| Uniform Delay, d1                 | 29.7  | 29.7 | 23.5  | 29.4  | 29.4                      | 17.9  | 31.4 | 21.3  | 11.6  | 28.4  | 18.5  | 7.1   |  |
| Progression Factor                | 1.00  | 1.00 | 1.00  | 1.00  | 1.00                      | 1.00  | 1.00 | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             | 1.8   | 1.8  | 0.1   | 1.5   | 1.4                       | 0.3   | 3.8  | 2.4   | 0.0   | 1.0   | 0.7   | 0.0   |  |
| Delay (s)                         | 31.6  | 31.5 | 23.7  | 30.9  | 30.9                      | 18.2  | 35.2 | 23.7  | 11.6  | 29.5  | 19.2  | 7.1   |  |
| Level of Service                  | C     | C    | C     | C     | C                         | B     | D    | C     | B     | C     | B     | A     |  |
| Approach Delay (s)                |       | 28.2 |       |       | 25.4                      |       |      | 23.2  |       |       | 19.8  |       |  |
| Approach LOS                      |       | C    |       |       | C                         |       |      | C     |       |       | B     |       |  |
| <b>Intersection Summary</b>       |       |      |       |       |                           |       |      |       |       |       |       |       |  |
| HCM 2000 Control Delay            |       |      | 22.8  |       | HCM 2000 Level of Service |       |      |       | C     |       |       |       |  |
| HCM 2000 Volume to Capacity ratio |       |      | 0.59  |       |                           |       |      |       |       |       |       |       |  |
| Actuated Cycle Length (s)         |       |      | 71.4  |       | Sum of lost time (s)      |       |      |       | 25.5  |       |       |       |  |
| Intersection Capacity Utilization |       |      | 50.9% |       | ICU Level of Service      |       |      |       | A     |       |       |       |  |
| Analysis Period (min)             |       |      | 15    |       |                           |       |      |       |       |       |       |       |  |
| c Critical Lane Group             |       |      |       |       |                           |       |      |       |       |       |       |       |  |

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2026 Build Weekday PM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT  | WBR  | NBL   | NBT   | NBR  | SBL  | SBT   | SBR                         |
|-----------------------------------|-------|-------|-------|-------|------|------|-------|-------|------|------|-------|-----------------------------|
| Lane Configurations               |       |       |       |       |      |      |       |       |      |      |       |                             |
| Traffic Volume (vph)              | 233   | 72    | 100   | 200   | 95   | 17   | 100   | 488   | 145  | 17   | 674   | 408                         |
| Future Volume (vph)               | 233   | 72    | 100   | 200   | 95   | 17   | 100   | 488   | 145  | 17   | 674   | 408                         |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900 | 1900 | 1900  | 1900  | 1900 | 1900 | 1900  | 1900                        |
| Lane Width                        | 11    | 11    | 11    | 14    | 14   | 14   | 11    | 11    | 11   | 11   | 11    | 11                          |
| Grade (%)                         |       | 5%    |       |       | -5%  |      |       | 0%    |      |      | 0%    |                             |
| Total Lost time (s)               | 6.5   | 6.5   |       | 6.5   | 6.5  |      | 6.5   | 6.5   |      | 6.5  | 6.5   | 6.5                         |
| Lane Util. Factor                 | 0.97  | 1.00  |       | 1.00  | 1.00 |      | 1.00  | 0.95  |      | 1.00 | 0.95  | 1.00                        |
| Frt                               | 1.00  | 0.91  |       | 1.00  | 0.98 |      | 1.00  | 0.97  |      | 1.00 | 1.00  | 0.85                        |
| Flt Protected                     | 0.95  | 1.00  |       | 0.95  | 1.00 |      | 0.95  | 1.00  |      | 0.95 | 1.00  | 1.00                        |
| Satd. Flow (prot)                 | 3268  | 1618  |       | 1954  | 2009 |      | 1728  | 3336  |      | 1728 | 3455  | 1546                        |
| Flt Permitted                     | 0.95  | 1.00  |       | 0.95  | 1.00 |      | 0.95  | 1.00  |      | 0.95 | 1.00  | 1.00                        |
| Satd. Flow (perm)                 | 3268  | 1618  |       | 1954  | 2009 |      | 1728  | 3336  |      | 1728 | 3455  | 1546                        |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.91  | 0.91 | 0.91 | 0.88  | 0.88  | 0.88 | 0.90 | 0.90  | 0.90                        |
| Adj. Flow (vph)                   | 259   | 80    | 111   | 220   | 104  | 19   | 114   | 555   | 165  | 19   | 749   | 453                         |
| RTOR Reduction (vph)              | 0     | 41    | 0     | 0     | 5    | 0    | 0     | 19    | 0    | 0    | 0     | 232                         |
| Lane Group Flow (vph)             | 259   | 150   | 0     | 220   | 118  | 0    | 114   | 701   | 0    | 19   | 749   | 221                         |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 1%    | 1%   | 1%   | 1%    | 1%    | 1%   | 1%   | 1%    | 1%                          |
| Turn Type                         | Split | NA    |       | Split | NA   |      | Prot  | NA    |      | Prot | NA    | pt+ov                       |
| Protected Phases                  | 3     | 3     |       | 4     | 4    |      | 1     | 6     |      | 5    | 2     | 2 3                         |
| Permitted Phases                  |       |       |       |       |      |      |       |       |      |      |       |                             |
| Actuated Green, G (s)             | 11.2  | 11.2  |       | 15.0  | 15.0 |      | 10.6  | 38.6  |      | 2.7  | 30.7  | 48.4                        |
| Effective Green, g (s)            | 11.2  | 11.2  |       | 15.0  | 15.0 |      | 10.6  | 38.6  |      | 2.7  | 30.7  | 48.4                        |
| Actuated g/C Ratio                | 0.11  | 0.11  |       | 0.15  | 0.15 |      | 0.11  | 0.39  |      | 0.03 | 0.31  | 0.49                        |
| Clearance Time (s)                | 6.5   | 6.5   |       | 6.5   | 6.5  |      | 6.5   | 6.5   |      | 6.5  | 6.5   | 6.5                         |
| Vehicle Extension (s)             | 3.0   | 3.0   |       | 3.0   | 3.0  |      | 3.0   | 3.0   |      | 3.0  | 3.0   | 3.0                         |
| Lane Grp Cap (vph)                | 368   | 182   |       | 294   | 303  |      | 184   | 1295  |      | 46   | 1067  | 752                         |
| v/s Ratio Prot                    | 0.08  | c0.09 |       | c0.11 | 0.06 |      | c0.07 | c0.21 |      | 0.01 | c0.22 | 0.14                        |
| v/s Ratio Perm                    |       |       |       |       |      |      |       |       |      |      |       |                             |
| v/c Ratio                         | 0.70  | 0.83  |       | 0.75  | 0.39 |      | 0.62  | 0.54  |      | 0.41 | 0.70  | 0.29                        |
| Uniform Delay, d1                 | 42.5  | 43.1  |       | 40.4  | 38.1 |      | 42.5  | 23.5  |      | 47.6 | 30.3  | 15.3                        |
| Progression Factor                | 1.00  | 1.00  |       | 1.00  | 1.00 |      | 1.00  | 1.00  |      | 1.00 | 1.00  | 1.00                        |
| Incremental Delay, d2             | 6.0   | 25.2  |       | 10.0  | 0.8  |      | 6.1   | 0.5   |      | 5.9  | 2.1   | 0.2                         |
| Delay (s)                         | 48.5  | 68.3  |       | 50.4  | 38.9 |      | 48.6  | 24.0  |      | 53.5 | 32.4  | 15.5                        |
| Level of Service                  | D     | E     |       | D     | D    |      | D     | C     |      | D    | C     | B                           |
| Approach Delay (s)                |       | 56.9  |       |       | 46.3 |      |       | 27.4  |      |      | 26.5  |                             |
| Approach LOS                      |       | E     |       |       | D    |      |       | C     |      |      | C     |                             |
| <b>Intersection Summary</b>       |       |       |       |       |      |      |       |       |      |      |       |                             |
| HCM 2000 Control Delay            |       |       | 33.9  |       |      |      |       |       |      |      |       | HCM 2000 Level of Service C |
| HCM 2000 Volume to Capacity ratio |       |       | 0.69  |       |      |      |       |       |      |      |       |                             |
| Actuated Cycle Length (s)         |       |       | 99.4  |       |      |      |       |       |      |      |       | Sum of lost time (s) 28.0   |
| Intersection Capacity Utilization |       |       | 66.8% |       |      |      |       |       |      |      |       | ICU Level of Service C      |
| Analysis Period (min)             |       |       | 15    |       |      |      |       |       |      |      |       |                             |
| c Critical Lane Group             |       |       |       |       |      |      |       |       |      |      |       |                             |

201: Motel 6/North Site & Gosling Road  
 2026 Build Weekday PM Peak



| Movement                          | EBT         | EBR         | WBL         | WBT         | NBL                  | NBR         |             |
|-----------------------------------|-------------|-------------|-------------|-------------|----------------------|-------------|-------------|
| Lane Configurations               | ↑↑↑↑        |             |             | ↑↑          |                      | ↗           |             |
| Traffic Volume (veh/h)            | 1105        | 137         | 0           | 965         | 0                    | 31          |             |
| Future Volume (Veh/h)             | 1105        | 137         | 0           | 965         | 0                    | 31          |             |
| Sign Control                      | Free        |             |             | Free        | Stop                 |             |             |
| Grade                             | 0%          |             |             | 0%          | 0%                   |             |             |
| Peak Hour Factor                  | 0.94        | 0.94        | 0.98        | 0.97        | 0.72                 | 0.72        |             |
| Hourly flow rate (vph)            | 1176        | 146         | 0           | 995         | 0                    | 43          |             |
| <b>Pedestrians</b>                |             |             |             |             |                      |             |             |
| Lane Width (ft)                   |             |             |             |             |                      |             |             |
| Walking Speed (ft/s)              |             |             |             |             |                      |             |             |
| Percent Blockage                  |             |             |             |             |                      |             |             |
| Right turn flare (veh)            |             |             |             |             |                      |             |             |
| Median type                       | None        |             |             | None        |                      |             |             |
| Median storage (veh)              |             |             |             |             |                      |             |             |
| Upstream signal (ft)              | 464         |             |             |             |                      |             |             |
| pX, platoon unblocked             |             |             |             |             |                      |             |             |
| vC, conflicting volume            |             |             | 1322        |             | 1746                 | 367         |             |
| vC1, stage 1 conf vol             |             |             |             |             |                      |             |             |
| vC2, stage 2 conf vol             |             |             |             |             |                      |             |             |
| vCu, unblocked vol                |             |             | 1322        |             | 1746                 | 367         |             |
| tC, single (s)                    |             |             | 4.1         |             | 6.8                  | 6.9         |             |
| tC, 2 stage (s)                   |             |             |             |             |                      |             |             |
| tF (s)                            |             |             | 2.2         |             | 3.5                  | 3.3         |             |
| p0 queue free %                   |             |             | 100         |             | 100                  | 93          |             |
| cM capacity (veh/h)               |             |             | 524         |             | 79                   | 636         |             |
| <b>Direction, Lane #</b>          | <b>EB 1</b> | <b>EB 2</b> | <b>EB 3</b> | <b>EB 4</b> | <b>WB 1</b>          | <b>WB 2</b> | <b>NB 1</b> |
| Volume Total                      | 336         | 336         | 336         | 314         | 498                  | 498         | 43          |
| Volume Left                       | 0           | 0           | 0           | 0           | 0                    | 0           | 0           |
| Volume Right                      | 0           | 0           | 0           | 146         | 0                    | 0           | 43          |
| cSH                               | 1700        | 1700        | 1700        | 1700        | 1700                 | 1700        | 636         |
| Volume to Capacity                | 0.20        | 0.20        | 0.20        | 0.18        | 0.29                 | 0.29        | 0.07        |
| Queue Length 95th (ft)            | 0           | 0           | 0           | 0           | 0                    | 0           | 5           |
| Control Delay (s)                 | 0.0         | 0.0         | 0.0         | 0.0         | 0.0                  | 0.0         | 11.1        |
| Lane LOS                          |             |             |             |             |                      |             | B           |
| Approach Delay (s)                | 0.0         |             |             |             | 0.0                  |             | 11.1        |
| Approach LOS                      |             |             |             |             |                      |             | B           |
| <b>Intersection Summary</b>       |             |             |             |             |                      |             |             |
| Average Delay                     |             |             | 0.2         |             |                      |             |             |
| Intersection Capacity Utilization |             |             | 30.0%       |             | ICU Level of Service |             | A           |
| Analysis Period (min)             |             |             | 15          |             |                      |             |             |

202: Arthur F Brady Drive & South Site Driveway  
 2026 Build Weekday PM Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 5.4  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↔    | ↑    | ↔     | ↔    | ↔    |
| Traffic Vol, veh/h       | 93   | 178  | 239  | 72    | 111  | 80   |
| Future Vol, veh/h        | 93   | 178  | 239  | 72    | 111  | 80   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 97   | 97   | 80   | 80    | 74   | 74   |
| Heavy Vehicles, %        | 0    | 0    | 0    | 0     | 1    | 1    |
| Mvmt Flow                | 96   | 184  | 299  | 90    | 150  | 108  |

| Major/Minor          | Major1 | Major2 | Minor2 |   |       |
|----------------------|--------|--------|--------|---|-------|
| Conflicting Flow All | 300    | 0      | -      | 0 | 676   |
| Stage 1              | -      | -      | -      | - | 300   |
| Stage 2              | -      | -      | -      | - | 376   |
| Critical Hdwy        | 4.1    | -      | -      | - | 6.41  |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.41  |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.41  |
| Follow-up Hdwy       | 2.2    | -      | -      | - | 3.509 |
| Pot Cap-1 Maneuver   | 1273   | -      | -      | - | 420   |
| Stage 1              | -      | -      | -      | - | 754   |
| Stage 2              | -      | -      | -      | - | 696   |
| Platoon blocked, %   |        | -      | -      | - |       |
| Mov Cap-1 Maneuver   | 1272   | -      | -      | - | 384   |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 384   |
| Stage 1              | -      | -      | -      | - | 690   |
| Stage 2              | -      | -      | -      | - | 695   |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.8 | 0  | 16.3 |
| HCM LOS              |     |    | C    |

























| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1272  | -   | -   | -   | 384   | 739   |
| HCM Lane V/C Ratio    | 0.075 | -   | -   | -   | 0.391 | 0.146 |
| HCM Control Delay (s) | 8.1   | 0   | -   | -   | 20.3  | 10.7  |
| HCM Lane LOS          | A     | A   | -   | -   | C     | B     |
| HCM 95th %tile Q(veh) | 0.2   | -   | -   | -   | 1.8   | 0.5   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2026 Build Weekend Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↗↗  |
| Traffic Volume (vph)              | 0   | 304   | 68  | 373   | 197   | 0   | 0  | 0   | 0   | 332   | 1   | 52  |
| Future Volume (vph)               | 0   | 304   | 68  | 373   | 197   | 0   | 0  | 0   | 0   | 332   | 1   | 52  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1702  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1702  | 2814  |
| Peak-hour factor, PHF             | 0.92  | 0.92  | 0.92  | 0.85  | 0.85  | 0.85  | 0.92   | 0.92  | 0.92  | 0.87  | 0.87  | 0.87  |
| Adj. Flow (vph)                   | 0   | 330   | 74  | 439   | 232   | 0   | 0  | 0   | 0   | 382   | 1   | 60  |
| RTOR Reduction (vph)              | 0   | 0   | 50  | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 45  |
| Lane Group Flow (vph)             | 0   | 330   | 24  | 439   | 232   | 0   | 0  | 0   | 0   | 191   | 192   | 15  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 28.0  | 28.0  | 18.7  | 52.5  |   |  |   |   | 21.1  | 21.1  | 21.1  |
| Effective Green, g (s)            |   | 28.0  | 28.0  | 18.7  | 52.5  |   |  |   |   | 21.1  | 21.1  | 21.1  |
| Actuated g/C Ratio                |   | 0.33  | 0.33  | 0.22  | 0.61  |   |  |   |   | 0.25  | 0.25  | 0.25  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 1971  | 504   | 705   | 2114  |   |  |   |   | 417   | 418   | 692   |
| v/s Ratio Prot                    |   | c0.05   | 0.02  | c0.14   | c0.07   |   |  |   |   | 0.11  | c0.11   | 0.01  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.17  | 0.05  | 0.62  | 0.11  |   |  |   |   | 0.46  | 0.46  | 0.02  |
| Uniform Delay, d1                 |   | 20.6  | 19.8  | 30.4  | 6.9   |   |  |   |   | 27.5  | 27.5  | 24.5  |
| Progression Factor                |   | 1.00  | 1.00  | 1.43  | 0.79  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.1   | 0.1   | 1.9   | 0.0   |   |  |   |   | 1.7   | 1.7   | 0.0   |
| Delay (s)                         |   | 20.7  | 19.9  | 45.4  | 5.5   |   |  |   |   | 29.2  | 29.2  | 24.5  |
| Level of Service                  |   | C   | B   | D   | A   |   |  |   |   | C   | C   | C   |
| Approach Delay (s)                |   | 20.5  |   |   | 31.6  |   |  | 0.0   |   |   | 28.5  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 27.8  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.37  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 85.8  |   |   | Sum of lost time (s)  |  |   | 18.0  |   |   |   |
| Intersection Capacity Utilization |   |   | 55.3%   |   |   | ICU Level of Service  |  |   | B   |   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group






















102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
2026 Build Weekend Peak

|                                   |    |    |  |  |    |  |    |    |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |   |   |   |    |   |   |   |  |   |   |   |
| Traffic Volume (vph)              | 81  | 555   | 0   | 0   | 489   | 190   | 81   | 3   | 676   | 0   | 0   | 0   |
| Future Volume (vph)               | 81  | 555   | 0   | 0   | 489   | 190   | 81   | 3   | 676   | 0   | 0   | 0   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 10  | 11  | 12  | 12  | 12  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Lane Util. Factor                 | 0.97  | 0.95  |   |   | 0.91  |   | 0.97   | 0.95  | 0.95  |   |   |   |
| Frt                               | 1.00  | 1.00  |   |   | 0.96  |   | 1.00   | 0.85  | 0.85  |   |   |   |
| Flt Protected                     | 0.95  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (prot)                 | 3236  | 3455  |   |   | 4920  |   | 3467   | 1521  | 1519  |   |   |   |
| Flt Permitted                     | 0.37  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (perm)                 | 1254  | 3455  |   |   | 4920  |   | 3467   | 1521  | 1519  |   |   |   |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.95  | 0.95  | 0.95  | 0.96   | 0.96  | 0.96  | 0.90  | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 87  | 597   | 0   | 0   | 515   | 200   | 84   | 3   | 704   | 0   | 0   | 0   |
| RTOR Reduction (vph)              | 0   | 0   | 0   | 0   | 62  | 0   | 0  | 265   | 265   | 0   | 0   | 0   |
| Lane Group Flow (vph)             | 87  | 597   | 0   | 0   | 653   | 0   | 84   | 90  | 87  | 0   | 0   | 0   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%   | 1%  | 1%  | 0%  | 0%  | 0%  |
| Turn Type                         | pm+pt   | NA  |   |   | NA  |   | Split  | NA  | Prot  |   |   |   |
| Protected Phases                  | 1   | 6   |   |   | 2   |   | 3  | 3   | 3   |   |   |   |
| Permitted Phases                  | 6   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             | 40.9  | 28.0  |   |   | 33.8  |   | 21.1   | 21.1  | 21.1  |   |   |   |
| Effective Green, g (s)            | 40.9  | 28.0  |   |   | 33.8  |   | 21.1   | 21.1  | 21.1  |   |   |   |
| Actuated g/C Ratio                | 0.48  | 0.33  |   |   | 0.39  |   | 0.25   | 0.25  | 0.25  |   |   |   |
| Clearance Time (s)                | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Vehicle Extension (s)             | 4.0   | 5.0   |   |   | 5.0   |   | 5.0  | 5.0   | 5.0   |   |   |   |
| Lane Grp Cap (vph)                | 895   | 1127  |   |   | 1938  |   | 852  | 374   | 373   |   |   |   |
| v/s Ratio Prot                    | c0.01   | c0.17   |   |   | c0.13   |   | 0.02   | c0.06   | 0.06  |   |   |   |
| v/s Ratio Perm                    | 0.03  |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         | 0.10  | 0.53  |   |   | 0.34  |   | 0.10   | 0.24  | 0.23  |   |   |   |
| Uniform Delay, d1                 | 12.1  | 23.5  |   |   | 18.2  |   | 25.0   | 25.9  | 25.9  |   |   |   |
| Progression Factor                | 1.19  | 1.07  |   |   | 1.00  |   | 1.00   | 1.00  | 1.00  |   |   |   |
| Incremental Delay, d2             | 0.1   | 0.8   |   |   | 0.2   |   | 0.1  | 0.7   | 0.7   |   |   |   |
| Delay (s)                         | 14.5  | 26.1  |   |   | 18.4  |   | 25.1   | 26.6  | 26.5  |   |   |   |
| Level of Service                  | B   | C   |   |   | B   |   | C  | C   | C   |   |   |   |
| Approach Delay (s)                |   | 24.6  |   |   | 18.4  |   |  | 26.4  |   |   | 0.0   |   |
| Approach LOS                      |   | C   |   |   | B   |   |  | C   |   |   | A   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 23.2  |   |   |   | HCM 2000 Level of Service  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.33  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 85.8  |   |   |   | Sum of lost time (s)   |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 55.3%   |   |   |   | ICU Level of Service   |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

























c Critical Lane Group



103: Woodbury Avenue & Gosling Road  
2026 Build Weekend Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |  |   |  |   |  |  |  |  |  |  |
| Traffic Volume (vph)              | 56  | 38  | 342   | 24  | 43  | 65  | 305  | 393   | 20  | 35  | 448   | 61  |
| Future Volume (vph)               | 56  | 38  | 342   | 24  | 43  | 65  | 305  | 393   | 20  | 35  | 448   | 61  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frt                               |   | 1.00  | 0.85  |   | 0.93  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 |   | 1766  | 1706  |   | 1758  |   | 3467   | 3548  |   | 1728  | 3455  | 1546  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 |   | 1766  | 1706  |   | 1758  |   | 3467   | 3548  |   | 1728  | 3455  | 1546  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.85  | 0.85  | 0.85  | 0.91   | 0.91  | 0.91  | 0.88  | 0.88  | 0.88  |
| Adj. Flow (vph)                   | 67  | 45  | 407   | 28  | 51  | 76  | 335  | 432   | 22  | 40  | 509   | 69  |
| RTOR Reduction (vph)              | 0   | 0   | 304   | 0   | 29  | 0   | 0  | 2   | 0   | 0   | 0   | 40  |
| Lane Group Flow (vph)             | 0   | 112   | 103   | 0   | 126   | 0   | 335  | 452   | 0   | 40  | 509   | 29  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 0%  | 0%  | 0%  | 1%   | 1%  | 1%  | 1%  | 1%  | 1%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 8.4   | 21.9  |   | 11.6  |   | 13.5   | 31.7  |   | 4.7   | 22.4  | 36.8  |
| Effective Green, g (s)            |   | 8.4   | 21.9  |   | 11.6  |   | 13.5   | 31.7  |   | 4.7   | 22.4  | 36.8  |
| Actuated g/C Ratio                |   | 0.10  | 0.25  |   | 0.13  |   | 0.16   | 0.37  |   | 0.05  | 0.26  | 0.43  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                |   | 171   | 431   |   | 235   |   | 541  | 1300  |   | 93  | 894   | 657   |
| v/s Ratio Prot                    |   | c0.06   | 0.06  |   | c0.07   |   | c0.10  | 0.13  |   | 0.02  | c0.15   | 0.02  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.65  | 0.24  |   | 0.54  |   | 0.62   | 0.35  |   | 0.43  | 0.57  | 0.04  |
| Uniform Delay, d1                 |   | 37.7  | 25.7  |   | 34.9  |   | 34.1   | 19.9  |   | 39.6  | 27.9  | 14.6  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 8.7   | 0.3   |   | 2.4   |   | 2.1  | 0.2   |   | 3.2   | 0.8   | 0.0   |
| Delay (s)                         |   | 46.4  | 26.0  |   | 37.3  |   | 36.2   | 20.1  |   | 42.8  | 28.7  | 14.6  |
| Level of Service                  |   | D   | C   |   | D   |   | D  | C   |   | D   | C   | B   |
| Approach Delay (s)                |   | 30.4  |   |   | 37.3  |   | 26.9   |   |   | 28.0  |   |   |
| Approach LOS                      |   | C   |   |   | D   |   | C  |   |   | C   |   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 28.9  |   |   |   | HCM 2000 Level of Service  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.54  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 86.5  |   |   |   | Sum of lost time (s)   |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 55.7%   |   |   |   | ICU Level of Service   |   |   | B   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
2026 Build Weekend Peak

|                                   |  |  |  |  |  |  |   |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |  |  |  |  |  |  |  |  |  |  |  |  |
| Traffic Volume (vph)              | 129   | 23  | 132   | 122   | 11  | 60  | 50  | 583   | 109   | 81  | 767   | 163   |
| Future Volume (vph)               | 129   | 23  | 132   | 122   | 11  | 60  | 50  | 583   | 109   | 81  | 767   | 163   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 16  | 11  | 11  | 11  |
| Grade (%)                         |   | 3%  |   |   | -5%   |   |   | 5%  |   |   | -3%   |   |
| Total Lost time (s)               | 6.0   | 6.0   | 6.0   | 5.5   | 5.5   | 5.5   | 6.0   | 6.0   | 5.5   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 | 0.95  | 0.95  | 1.00  | 0.95  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  |
| Frpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Flpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Frt                               | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  |
| Flt Protected                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 | 1633  | 1660  | 1538  | 1699  | 1717  | 1600  | 1684  | 3369  | 1767  | 1753  | 3507  | 1569  |
| Flt Permitted                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 | 1633  | 1660  | 1538  | 1699  | 1717  | 1600  | 1684  | 3369  | 1767  | 1753  | 3507  | 1569  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.91  | 0.91  | 0.91  | 0.89  | 0.89  | 0.89  | 0.92  | 0.92  | 0.92  |
| Adj. Flow (vph)                   | 154   | 27  | 157   | 134   | 12  | 66  | 56  | 655   | 122   | 88  | 834   | 177   |
| RTOR Reduction (vph)              | 0   | 0   | 125   | 0   | 0   | 0   | 0   | 0   | 67  | 0   | 0   | 41  |
| Lane Group Flow (vph)             | 89  | 92  | 32  | 72  | 74  | 66  | 56  | 655   | 55  | 88  | 834   | 136   |
| Confl. Bikes (#/hr)               |   |   |   |   |   |   |   |   | 1   |   |   |   |
| Heavy Vehicles (%)                | 0%  | 0%  | 0%  | 0%  | 0%  | 0%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  | pt+ov   | Prot  | NA  | pt+ov   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 13  | 4   | 4   | 45  | 1   | 6   | 46  | 5   | 2   | 23  |
| Permitted Phases                  |   |   |   |   |   |   |   |   |   |   |   |   |
| Actuated Green, G (s)             | 8.0   | 8.0   | 14.0  | 8.0   | 8.0   | 21.0  | 6.0   | 23.2  | 31.2  | 7.5   | 24.2  | 38.2  |
| Effective Green, g (s)            | 8.0   | 8.0   | 14.0  | 8.0   | 8.0   | 21.0  | 6.0   | 23.2  | 31.2  | 7.5   | 24.2  | 38.2  |
| Actuated g/C Ratio                | 0.11  | 0.11  | 0.20  | 0.11  | 0.11  | 0.30  | 0.09  | 0.33  | 0.45  | 0.11  | 0.35  | 0.55  |
| Clearance Time (s)                | 6.0   | 6.0   |   | 5.5   | 5.5   |   | 6.0   | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                | 187   | 190   | 308   | 195   | 197   | 482   | 144   | 1121  | 790   | 188   | 1217  | 859   |
| v/s Ratio Prot                    | 0.05  | c0.06   | 0.02  | 0.04  | c0.04   | 0.04  | 0.03  | 0.19  | 0.03  | c0.05   | c0.24   | 0.09  |
| v/s Ratio Perm                    |   |   |   |   |   |   |   |   |   |   |   |   |
| v/c Ratio                         | 0.48  | 0.48  | 0.10  | 0.37  | 0.38  | 0.14  | 0.39  | 0.58  | 0.07  | 0.47  | 0.69  | 0.16  |
| Uniform Delay, d1                 | 28.9  | 28.9  | 22.7  | 28.5  | 28.5  | 17.7  | 30.1  | 19.3  | 11.0  | 29.2  | 19.5  | 7.8   |
| Progression Factor                | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             | 1.9   | 1.9   | 0.1   | 1.2   | 1.2   | 0.1   | 1.7   | 0.8   | 0.0   | 1.8   | 1.6   | 0.1   |
| Delay (s)                         | 30.8  | 30.9  | 22.9  | 29.7  | 29.7  | 17.9  | 31.9  | 20.0  | 11.0  | 31.1  | 21.1  | 7.9   |
| Level of Service                  | C   | C   | C   | C   | C   | B   | C   | C   | B   | C   | C   | A   |
| Approach Delay (s)                |   | 27.1  |   |   | 26.0  |   |   | 19.5  |   |   | 19.8  |   |
| Approach LOS                      |   | C   |   |   | C   |   |   | B   |   |   | B   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 21.2  |   |   |   |   |   |   |   |   | C   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.61  |   |   |   |   |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 69.7  |   |   |   |   |   | 25.5  |   |   |   |
| Intersection Capacity Utilization |   |   | 52.0%   |   |   |   |   |   |   |   |   | A   |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |

c Critical Lane Group

105: Market Street & Woodbury Avenue & Market Basket Driveway  
2026 Build Weekend Peak

| Movement                          | EBL   | EBT  | EBR   | WBL   | WBT  | WBR  | NBL                       | NBT   | NBR  | SBL  | SBT  | SBR   |
|-----------------------------------|-------|------|-------|-------|------|------|---------------------------|-------|------|------|------|-------|
| Lane Configurations               |       |      |       |       |      |      |                           |       |      |      |      |       |
| Traffic Volume (vph)              | 255   | 68   | 50    | 142   | 75   | 22   | 61                        | 483   | 129  | 12   | 571  | 422   |
| Future Volume (vph)               | 255   | 68   | 50    | 142   | 75   | 22   | 61                        | 483   | 129  | 12   | 571  | 422   |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900  | 1900 | 1900 | 1900                      | 1900  | 1900 | 1900 | 1900 | 1900  |
| Lane Width                        | 11    | 11   | 11    | 14    | 14   | 14   | 11                        | 11    | 11   | 11   | 11   | 11    |
| Grade (%)                         |       | 5%   |       |       | -5%  |      |                           | 0%    |      |      | 0%   |       |
| Total Lost time (s)               | 6.5   | 6.5  |       | 6.5   | 6.5  |      | 6.5                       | 6.5   |      | 6.5  | 6.5  | 6.5   |
| Lane Util. Factor                 | 0.97  | 1.00 |       | 1.00  | 1.00 |      | 1.00                      | 0.95  |      | 1.00 | 0.95 | 1.00  |
| Frt                               | 1.00  | 0.94 |       | 1.00  | 0.97 |      | 1.00                      | 0.97  |      | 1.00 | 1.00 | 0.85  |
| Flt Protected                     | 0.95  | 1.00 |       | 0.95  | 1.00 |      | 0.95                      | 1.00  |      | 0.95 | 1.00 | 1.00  |
| Satd. Flow (prot)                 | 3268  | 1660 |       | 1954  | 1987 |      | 1728                      | 3346  |      | 1728 | 3455 | 1546  |
| Flt Permitted                     | 0.95  | 1.00 |       | 0.95  | 1.00 |      | 0.95                      | 1.00  |      | 0.95 | 1.00 | 1.00  |
| Satd. Flow (perm)                 | 3268  | 1660 |       | 1954  | 1987 |      | 1728                      | 3346  |      | 1728 | 3455 | 1546  |
| Peak-hour factor, PHF             | 0.77  | 0.77 | 0.77  | 0.78  | 0.78 | 0.78 | 0.92                      | 0.92  | 0.92 | 0.97 | 0.97 | 0.97  |
| Adj. Flow (vph)                   | 331   | 88   | 65    | 182   | 96   | 28   | 66                        | 525   | 140  | 12   | 589  | 435   |
| RTOR Reduction (vph)              | 0     | 21   | 0     | 0     | 8    | 0    | 0                         | 17    | 0    | 0    | 0    | 209   |
| Lane Group Flow (vph)             | 331   | 132  | 0     | 182   | 116  | 0    | 66                        | 648   | 0    | 12   | 589  | 226   |
| Heavy Vehicles (%)                | 1%    | 1%   | 1%    | 1%    | 1%   | 1%   | 1%                        | 1%    | 1%   | 1%   | 1%   | 1%    |
| Turn Type                         | Split | NA   |       | Split | NA   |      | Prot                      | NA    |      | Prot | NA   | pt+ov |
| Protected Phases                  | 3     | 3    |       | 4     | 4    |      | 1                         | 6     |      | 5    | 2    | 2 3   |
| Permitted Phases                  |       |      |       |       |      |      |                           |       |      |      |      |       |
| Actuated Green, G (s)             | 11.5  | 11.5 |       | 12.8  | 12.8 |      | 6.9                       | 29.9  |      | 1.2  | 24.2 | 42.2  |
| Effective Green, g (s)            | 11.5  | 11.5 |       | 12.8  | 12.8 |      | 6.9                       | 29.9  |      | 1.2  | 24.2 | 42.2  |
| Actuated g/C Ratio                | 0.14  | 0.14 |       | 0.16  | 0.16 |      | 0.08                      | 0.37  |      | 0.01 | 0.30 | 0.52  |
| Clearance Time (s)                | 6.5   | 6.5  |       | 6.5   | 6.5  |      | 6.5                       | 6.5   |      | 6.5  | 6.5  | 6.5   |
| Vehicle Extension (s)             | 3.0   | 3.0  |       | 3.0   | 3.0  |      | 3.0                       | 3.0   |      | 3.0  | 3.0  | 3.0   |
| Lane Grp Cap (vph)                | 461   | 234  |       | 307   | 312  |      | 146                       | 1229  |      | 25   | 1027 | 801   |
| v/s Ratio Prot                    | c0.10 | 0.08 |       | c0.09 | 0.06 |      | c0.04                     | c0.19 |      | 0.01 | 0.17 | 0.15  |
| v/s Ratio Perm                    |       |      |       |       |      |      |                           |       |      |      |      |       |
| v/c Ratio                         | 0.72  | 0.57 |       | 0.59  | 0.37 |      | 0.45                      | 0.53  |      | 0.48 | 0.57 | 0.28  |
| Uniform Delay, d1                 | 33.4  | 32.6 |       | 31.9  | 30.7 |      | 35.5                      | 20.2  |      | 39.8 | 24.2 | 11.1  |
| Progression Factor                | 1.00  | 1.00 |       | 1.00  | 1.00 |      | 1.00                      | 1.00  |      | 1.00 | 1.00 | 1.00  |
| Incremental Delay, d2             | 5.3   | 3.1  |       | 3.1   | 0.7  |      | 2.2                       | 0.4   |      | 13.8 | 0.8  | 0.2   |
| Delay (s)                         | 38.7  | 35.7 |       | 34.9  | 31.4 |      | 37.7                      | 20.6  |      | 53.6 | 25.0 | 11.2  |
| Level of Service                  | D     | D    |       | C     | C    |      | D                         | C     |      | D    | C    | B     |
| Approach Delay (s)                |       | 37.8 |       |       | 33.5 |      |                           | 22.2  |      |      | 19.6 |       |
| Approach LOS                      |       | D    |       |       | C    |      |                           | C     |      |      | B    |       |
| <b>Intersection Summary</b>       |       |      |       |       |      |      |                           |       |      |      |      |       |
| HCM 2000 Control Delay            |       |      | 25.4  |       |      |      | HCM 2000 Level of Service |       |      |      | C    |       |
| HCM 2000 Volume to Capacity ratio |       |      | 0.64  |       |      |      |                           |       |      |      |      |       |
| Actuated Cycle Length (s)         |       |      | 81.4  |       |      |      | Sum of lost time (s)      |       |      | 28.0 |      |       |
| Intersection Capacity Utilization |       |      | 53.3% |       |      |      | ICU Level of Service      |       |      | A    |      |       |
| Analysis Period (min)             |       |      | 15    |       |      |      |                           |       |      |      |      |       |
| c Critical Lane Group             |       |      |       |       |      |      |                           |       |      |      |      |       |

201: Motel 6/North Site & Gosling Road  
2026 Build Weekend Peak



| Movement                          | EBT  | EBR  | WBL   | WBT  | NBL                  | NBR  |      |
|-----------------------------------|------|------|-------|------|----------------------|------|------|
| Lane Configurations               | ↑↑↑↑ |      |       | ↑↑   |                      | ↗    |      |
| Traffic Volume (veh/h)            | 1133 | 98   | 0     | 679  | 0                    | 53   |      |
| Future Volume (Veh/h)             | 1133 | 98   | 0     | 679  | 0                    | 53   |      |
| Sign Control                      | Free |      |       | Free | Stop                 |      |      |
| Grade                             | 0%   |      |       | 0%   | 0%                   |      |      |
| Peak Hour Factor                  | 0.93 | 0.93 | 0.95  | 0.95 | 0.55                 | 0.55 |      |
| Hourly flow rate (vph)            | 1218 | 105  | 0     | 715  | 0                    | 96   |      |
| Pedestrians                       |      |      |       |      |                      |      |      |
| Lane Width (ft)                   |      |      |       |      |                      |      |      |
| Walking Speed (ft/s)              |      |      |       |      |                      |      |      |
| Percent Blockage                  |      |      |       |      |                      |      |      |
| Right turn flare (veh)            |      |      |       |      |                      |      |      |
| Median type                       | None |      |       | None |                      |      |      |
| Median storage (veh)              |      |      |       |      |                      |      |      |
| Upstream signal (ft)              | 464  |      |       |      |                      |      |      |
| pX, platoon unblocked             |      |      |       |      |                      |      |      |
| vC, conflicting volume            |      |      | 1323  |      | 1628                 | 357  |      |
| vC1, stage 1 conf vol             |      |      |       |      |                      |      |      |
| vC2, stage 2 conf vol             |      |      |       |      |                      |      |      |
| vCu, unblocked vol                |      |      | 1323  |      | 1628                 | 357  |      |
| tC, single (s)                    |      |      | 4.1   |      | 6.8                  | 6.9  |      |
| tC, 2 stage (s)                   |      |      |       |      |                      |      |      |
| tF (s)                            |      |      | 2.2   |      | 3.5                  | 3.3  |      |
| p0 queue free %                   |      |      | 100   |      | 100                  | 85   |      |
| cM capacity (veh/h)               |      |      | 523   |      | 95                   | 645  |      |
| Direction, Lane #                 | EB 1 | EB 2 | EB 3  | EB 4 | WB 1                 | WB 2 | NB 1 |
| Volume Total                      | 348  | 348  | 348   | 279  | 358                  | 358  | 96   |
| Volume Left                       | 0    | 0    | 0     | 0    | 0                    | 0    | 0    |
| Volume Right                      | 0    | 0    | 0     | 105  | 0                    | 0    | 96   |
| cSH                               | 1700 | 1700 | 1700  | 1700 | 1700                 | 1700 | 645  |
| Volume to Capacity                | 0.20 | 0.20 | 0.20  | 0.16 | 0.21                 | 0.21 | 0.15 |
| Queue Length 95th (ft)            | 0    | 0    | 0     | 0    | 0                    | 0    | 13   |
| Control Delay (s)                 | 0.0  | 0.0  | 0.0   | 0.0  | 0.0                  | 0.0  | 11.6 |
| Lane LOS                          |      |      |       |      |                      |      | B    |
| Approach Delay (s)                | 0.0  |      |       |      | 0.0                  |      | 11.6 |
| Approach LOS                      |      |      |       |      |                      |      | B    |
| Intersection Summary              |      |      |       |      |                      |      |      |
| Average Delay                     |      |      | 0.5   |      |                      |      |      |
| Intersection Capacity Utilization |      |      | 28.1% |      | ICU Level of Service |      | A    |
| Analysis Period (min)             |      |      | 15    |      |                      |      |      |

202: Arthur F Brady Drive & South Site Driveway  
2026 Build Weekend Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 6    |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↕    | ↕     | ↕    | ↕    |
| Traffic Vol, veh/h       | 120  | 204  | 122  | 81    | 149  | 63   |
| Future Vol, veh/h        | 120  | 204  | 122  | 81    | 149  | 63   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 95   | 95   | 81   | 81    | 88   | 88   |
| Heavy Vehicles, %        | 1    | 1    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 126  | 215  | 151  | 100   | 169  | 72   |

| Major/Minor          | Major1 | Major2 | Minor2 |   |         |
|----------------------|--------|--------|--------|---|---------|
| Conflicting Flow All | 152    | 0      | -      | 0 | 619 153 |
| Stage 1              | -      | -      | -      | - | 152 -   |
| Stage 2              | -      | -      | -      | - | 467 -   |
| Critical Hdwy        | 4.11   | -      | -      | - | 6.4 6.2 |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.4 -   |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.4 -   |
| Follow-up Hdwy       | 2.209  | -      | -      | - | 3.5 3.3 |
| Pot Cap-1 Maneuver   | 1435   | -      | -      | - | 455 898 |
| Stage 1              | -      | -      | -      | - | 881 -   |
| Stage 2              | -      | -      | -      | - | 635 -   |
| Platoon blocked, %   |        | -      | -      | - |         |
| Mov Cap-1 Maneuver   | 1434   | -      | -      | - | 409 896 |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 409 -   |
| Stage 1              | -      | -      | -      | - | 792 -   |
| Stage 2              | -      | -      | -      | - | 634 -   |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.9 | 0  | 16.8 |
| HCM LOS              |     |    | C    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1434  | -   | -   | -   | 409   | 896   |
| HCM Lane V/C Ratio    | 0.088 | -   | -   | -   | 0.414 | 0.08  |
| HCM Control Delay (s) | 7.8   | 0   | -   | -   | 19.9  | 9.4   |
| HCM Lane LOS          | A     | A   | -   | -   | C     | A     |
| HCM 95th %tile Q(veh) | 0.3   | -   | -   | -   | 2     | 0.3   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2036 Build Weekday AM Peak





















|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↖↗  | ↑↑  |   |  |   |   | ↘   | ↖   | ↗↘  |
| Traffic Volume (vph)              | 0   | 259   | 113   | 111   | 984   | 0   | 0  | 0   | 0   | 458   | 0   | 831   |
| Future Volume (vph)               | 0   | 259   | 113   | 111   | 984   | 0   | 0  | 0   | 0   | 458   | 0   | 831   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 5923  | 1516  | 3173  | 3388  |   |  |   |   | 1698  | 1698  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 5923  | 1516  | 3173  | 3388  |   |  |   |   | 1698  | 1698  | 2814  |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.87  | 0.87  | 0.87  | 0.90   | 0.90  | 0.90  | 0.86  | 0.86  | 0.86  |
| Adj. Flow (vph)                   | 0   | 278   | 122   | 128   | 1131  | 0   | 0  | 0   | 0   | 533   | 0   | 966   |
| RTOR Reduction (vph)              | 0   | 0   | 86  | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 137   |
| Lane Group Flow (vph)             | 0   | 278   | 36  | 128   | 1131  | 0   | 0  | 0   | 0   | 266   | 267   | 829   |
| Heavy Vehicles (%)                | 3%  | 3%  | 3%  | 3%  | 3%  | 3%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 29.0  | 29.0  | 25.1  | 60.1  |   |  |   |   | 25.1  | 25.1  | 25.1  |
| Effective Green, g (s)            |   | 29.0  | 29.0  | 25.1  | 60.1  |   |  |   |   | 25.1  | 25.1  | 25.1  |
| Actuated g/C Ratio                |   | 0.30  | 0.30  | 0.26  | 0.62  |   |  |   |   | 0.26  | 0.26  | 0.26  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 1767  | 452   | 819   | 2094  |   |  |   |   | 438   | 438   | 726   |
| v/s Ratio Prot                    |   | 0.05  | 0.02  | 0.04  | c0.33   |   |  |   |   | 0.16  | 0.16  | c0.29   |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.16  | 0.08  | 0.16  | 0.54  |   |  |   |   | 0.61  | 0.61  | 1.14  |
| Uniform Delay, d1                 |   | 25.1  | 24.5  | 27.9  | 10.6  |   |  |   |   | 31.7  | 31.7  | 36.0  |
| Progression Factor                |   | 1.00  | 1.00  | 0.89  | 1.58  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.1   | 0.2   | 0.1   | 0.4   |   |  |   |   | 3.5   | 3.5   | 79.7  |
| Delay (s)                         |   | 25.2  | 24.7  | 24.8  | 17.2  |   |  |   |   | 35.2  | 35.3  | 115.7   |
| Level of Service                  |   | C   | C   | C   | B   |   |  |   |   | D   | D   | F   |
| Approach Delay (s)                |   | 25.0  |   |   | 18.0  |   |  | 0.0   |   |   | 87.1  |   |
| Approach LOS                      |   | C   |   |   | B   |   |  | A   |   |   | F   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 51.7  |   |   | HCM 2000 Level of Service   |  |   |   | D   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.77  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 97.2  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 66.3%   |   |   | ICU Level of Service  |  |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2036 Build Weekday AM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL  | WBT   | WBR  | NBL                       | NBT  | NBR  | SBL  | SBT  | SBR  |
|-----------------------------------|-------|-------|-------|------|-------|------|---------------------------|------|------|------|------|------|
| Lane Configurations               |       |       |       |      |       |      |                           |      |      |      |      |      |
| Traffic Volume (vph)              | 118   | 599   | 0     | 0    | 333   | 48   | 762                       | 0    | 295  | 0    | 0    | 0    |
| Future Volume (vph)               | 118   | 599   | 0     | 0    | 333   | 48   | 762                       | 0    | 295  | 0    | 0    | 0    |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900 | 1900  | 1900 | 1900                      | 1900 | 1900 | 1900 | 1900 | 1900 |
| Lane Width                        | 10    | 11    | 12    | 12   | 12    | 12   | 12                        | 12   | 12   | 12   | 12   | 12   |
| Total Lost time (s)               | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Lane Util. Factor                 | 0.97  | 0.95  |       |      | 0.91  |      | 0.97                      | 0.95 | 0.95 |      |      |      |
| Frt                               | 1.00  | 1.00  |       |      | 0.98  |      | 1.00                      | 0.85 | 0.85 |      |      |      |
| Flt Protected                     | 0.95  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (prot)                 | 3236  | 3455  |       |      | 4847  |      | 3400                      | 1490 | 1490 |      |      |      |
| Flt Permitted                     | 0.49  | 1.00  |       |      | 1.00  |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (perm)                 | 1681  | 3455  |       |      | 4847  |      | 3400                      | 1490 | 1490 |      |      |      |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.89 | 0.89  | 0.89 | 0.91                      | 0.91 | 0.91 | 0.90 | 0.90 | 0.90 |
| Adj. Flow (vph)                   | 127   | 644   | 0     | 0    | 374   | 54   | 837                       | 0    | 324  | 0    | 0    | 0    |
| RTOR Reduction (vph)              | 0     | 0     | 0     | 0    | 17    | 0    | 0                         | 120  | 120  | 0    | 0    | 0    |
| Lane Group Flow (vph)             | 127   | 644   | 0     | 0    | 411   | 0    | 837                       | 42   | 42   | 0    | 0    | 0    |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 5%   | 5%    | 5%   | 3%                        | 3%   | 3%   | 0%   | 0%   | 0%   |
| Turn Type                         | pm+pt | NA    |       |      | NA    |      | Split                     | NA   | Prot |      |      |      |
| Protected Phases                  | 1     | 6     |       |      | 2     |      | 3                         | 3    | 3    |      |      |      |
| Permitted Phases                  | 6     |       |       |      |       |      |                           |      |      |      |      |      |
| Actuated Green, G (s)             | 45.9  | 29.0  |       |      | 37.2  |      | 25.1                      | 25.1 | 25.1 |      |      |      |
| Effective Green, g (s)            | 45.9  | 29.0  |       |      | 37.2  |      | 25.1                      | 25.1 | 25.1 |      |      |      |
| Actuated g/C Ratio                | 0.47  | 0.30  |       |      | 0.38  |      | 0.26                      | 0.26 | 0.26 |      |      |      |
| Clearance Time (s)                | 6.0   | 6.0   |       |      | 6.0   |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Vehicle Extension (s)             | 4.0   | 5.0   |       |      | 5.0   |      | 5.0                       | 5.0  | 5.0  |      |      |      |
| Lane Grp Cap (vph)                | 1064  | 1030  |       |      | 1855  |      | 877                       | 384  | 384  |      |      |      |
| v/s Ratio Prot                    | c0.02 | c0.19 |       |      | c0.08 |      | c0.25                     | 0.03 | 0.03 |      |      |      |
| v/s Ratio Perm                    | 0.04  |       |       |      |       |      |                           |      |      |      |      |      |
| v/c Ratio                         | 0.12  | 0.63  |       |      | 0.22  |      | 0.95                      | 0.11 | 0.11 |      |      |      |
| Uniform Delay, d1                 | 14.1  | 29.4  |       |      | 20.2  |      | 35.5                      | 27.5 | 27.5 |      |      |      |
| Progression Factor                | 1.24  | 1.25  |       |      | 1.00  |      | 1.00                      | 1.00 | 1.00 |      |      |      |
| Incremental Delay, d2             | 0.1   | 1.5   |       |      | 0.1   |      | 20.4                      | 0.3  | 0.3  |      |      |      |
| Delay (s)                         | 17.5  | 38.4  |       |      | 20.4  |      | 55.9                      | 27.8 | 27.8 |      |      |      |
| Level of Service                  | B     | D     |       |      | C     |      | E                         | C    | C    |      |      |      |
| Approach Delay (s)                |       | 35.0  |       |      | 20.4  |      |                           | 48.1 |      |      | 0.0  |      |
| Approach LOS                      |       | C     |       |      | C     |      |                           | D    |      |      | A    |      |
| <b>Intersection Summary</b>       |       |       |       |      |       |      |                           |      |      |      |      |      |
| HCM 2000 Control Delay            |       |       | 38.8  |      |       |      | HCM 2000 Level of Service |      |      | D    |      |      |
| HCM 2000 Volume to Capacity ratio |       |       | 0.57  |      |       |      |                           |      |      |      |      |      |
| Actuated Cycle Length (s)         |       |       | 97.2  |      |       |      | Sum of lost time (s)      |      |      | 18.0 |      |      |
| Intersection Capacity Utilization |       |       | 66.3% |      |       |      | ICU Level of Service      |      |      | C    |      |      |
| Analysis Period (min)             |       |       | 15    |      |       |      |                           |      |      |      |      |      |

























c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2036 Build Weekday AM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|--|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |  |
| Lane Configurations               |   |  |  |   |  |   |  |  |   |  |  |  |  |
| Traffic Volume (vph)              | 101   | 42  | 491   | 29  | 15  | 7   | 253  | 192   | 20  | 39  | 316   | 9   |  |
| Future Volume (vph)               | 101   | 42  | 491   | 29  | 15  | 7   | 253  | 192   | 20  | 39  | 316   | 9   |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |  |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |  |
| Frt                               |   | 1.00  | 0.85  |   | 0.98  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 |   | 1706  | 1656  |   | 1604  |   | 3400   | 3455  |   | 1678  | 3355  | 1501  |  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.97  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 |   | 1706  | 1656  |   | 1604  |   | 3400   | 3455  |   | 1678  | 3355  | 1501  |  |
| Peak-hour factor, PHF             | 0.91  | 0.91  | 0.91  | 0.89  | 0.89  | 0.89  | 0.84   | 0.84  | 0.84  | 0.89  | 0.89  | 0.89  |  |
| Adj. Flow (vph)                   | 111   | 46  | 540   | 33  | 17  | 8   | 301  | 229   | 24  | 44  | 355   | 10  |  |
| RTOR Reduction (vph)              | 0   | 0   | 379   | 0   | 6   | 0   | 0  | 5   | 0   | 0   | 0   | 6   |  |
| Lane Group Flow (vph)             | 0   | 157   | 161   | 0   | 52  | 0   | 301  | 248   | 0   | 44  | 355   | 4   |  |
| Heavy Vehicles (%)                | 4%  | 4%  | 4%  | 13%   | 13%   | 13%   | 3%   | 3%  | 3%  | 4%  | 4%  | 4%  |  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |  |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |  |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |  |
| Actuated Green, G (s)             |   | 8.9   | 22.0  |   | 5.0   |   | 13.1   | 26.1  |   | 4.4   | 16.9  | 31.8  |  |
| Effective Green, g (s)            |   | 8.9   | 22.0  |   | 5.0   |   | 13.1   | 26.1  |   | 4.4   | 16.9  | 31.8  |  |
| Actuated g/C Ratio                |   | 0.12  | 0.30  |   | 0.07  |   | 0.18   | 0.35  |   | 0.06  | 0.23  | 0.43  |  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |  |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |  |
| Lane Grp Cap (vph)                |   | 205   | 492   |   | 108   |   | 602  | 1220  |   | 99  | 767   | 645   |  |
| v/s Ratio Prot                    |   | c0.09   | 0.10  |   | c0.03   |   | c0.09  | 0.07  |   | 0.03  | c0.11   | 0.00  |  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |  |
| v/c Ratio                         |   | 0.77  | 0.33  |   | 0.49  |   | 0.50   | 0.20  |   | 0.44  | 0.46  | 0.01  |  |
| Uniform Delay, d1                 |   | 31.5  | 20.2  |   | 33.2  |   | 27.4   | 16.7  |   | 33.6  | 24.6  | 12.0  |  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             |   | 15.6  | 0.4   |   | 3.4   |   | 0.7  | 0.1   |   | 3.2   | 0.4   | 0.0   |  |
| Delay (s)                         |   | 47.1  | 20.6  |   | 36.6  |   | 28.1   | 16.7  |   | 36.7  | 25.0  | 12.0  |  |
| Level of Service                  |   | D   | C   |   | D   |   | C  | B   |   | D   | C   | B   |  |
| Approach Delay (s)                |   | 26.6  |   |   | 36.6  |   | 22.9   |   |   | 26.0  |   |   |  |
| Approach LOS                      |   | C   |   |   | D   |   | C  |   |   | C   |   |   |  |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |  |
| HCM 2000 Control Delay            |   |   | 25.6  |   | HCM 2000 Level of Service   |   |  |   |   |   | C   |   |  |
| HCM 2000 Volume to Capacity ratio |   |   | 0.49  |   |   |   |  |   |   |   |   |   |  |
| Actuated Cycle Length (s)         |   |   | 73.9  |   | Sum of lost time (s)  |   |  |   |   | 25.5  |   |   |  |
| Intersection Capacity Utilization |   |   | 60.4%   |   | ICU Level of Service  |   |  |   |   | B   |   |   |  |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |  |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |  |



104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2036 Build Weekday AM Peak

|                                   |  |  |  |  |  |  |   |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |  |  |  |  |  |  |  |  |  |  |  |  |
| Traffic Volume (vph)              | 38  | 3   | 110   | 29  | 0   | 37  | 22  | 360   | 42  | 50  | 733   | 55  |
| Future Volume (vph)               | 38  | 3   | 110   | 29  | 0   | 37  | 22  | 360   | 42  | 50  | 733   | 55  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 16  | 11  | 11  | 11  |
| Grade (%)                         |   | 3%  |   |   | -5%   |   |   | 5%  |   |   | -3%   |   |
| Total Lost time (s)               | 6.0   | 6.0   | 6.0   | 5.5   | 5.5   | 5.5   | 6.0   | 6.0   | 5.5   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 | 0.95  | 0.95  | 1.00  | 0.95  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  |
| Frpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Flpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Frt                               | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  |
| Flt Protected                     | 0.95  | 0.96  | 1.00  | 0.95  | 0.95  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 | 1570  | 1586  | 1479  | 1634  | 1634  | 1539  | 1652  | 3303  | 1733  | 1736  | 3473  | 1554  |
| Flt Permitted                     | 0.95  | 0.96  | 1.00  | 0.95  | 0.95  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 | 1570  | 1586  | 1479  | 1634  | 1634  | 1539  | 1652  | 3303  | 1733  | 1736  | 3473  | 1554  |
| Peak-hour factor, PHF             | 0.82  | 0.82  | 0.82  | 0.65  | 0.65  | 0.65  | 0.85  | 0.85  | 0.85  | 0.98  | 0.98  | 0.98  |
| Adj. Flow (vph)                   | 46  | 4   | 134   | 45  | 0   | 57  | 26  | 424   | 49  | 51  | 748   | 56  |
| RTOR Reduction (vph)              | 0   | 0   | 110   | 0   | 0   | 0   | 0   | 0   | 28  | 0   | 0   | 27  |
| Lane Group Flow (vph)             | 25  | 25  | 24  | 22  | 23  | 57  | 26  | 424   | 21  | 51  | 748   | 29  |
| Confl. Bikes (#/hr)               |   |   |   |   |   |   |   |   | 1   |   |   |   |
| Heavy Vehicles (%)                | 4%  | 4%  | 4%  | 4%  | 4%  | 4%  | 3%  | 3%  | 3%  | 2%  | 2%  | 2%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  | pt+ov   | Prot  | NA  | pt+ov   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 1 3   | 4   | 4   | 4 5   | 1   | 6   | 4 6   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |   |   |   |   |   |   |
| Actuated Green, G (s)             | 7.1   | 7.1   | 13.6  | 6.0   | 6.0   | 13.0  | 6.5   | 26.8  | 32.8  | 7.0   | 26.8  | 39.9  |
| Effective Green, g (s)            | 7.1   | 7.1   | 13.6  | 6.0   | 6.0   | 13.0  | 6.5   | 26.8  | 32.8  | 7.0   | 26.8  | 39.9  |
| Actuated g/C Ratio                | 0.09  | 0.09  | 0.18  | 0.08  | 0.08  | 0.17  | 0.09  | 0.35  | 0.43  | 0.09  | 0.35  | 0.53  |
| Clearance Time (s)                | 6.0   | 6.0   |   | 5.5   | 5.5   |   | 6.0   | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                | 146   | 148   | 265   | 129   | 129   | 263   | 141   | 1166  | 748   | 160   | 1226  | 816   |
| v/s Ratio Prot                    | c0.02   | 0.02  | 0.02  | 0.01  | 0.01  | c0.04   | 0.02  | 0.13  | 0.01  | c0.03   | c0.22   | 0.02  |
| v/s Ratio Perm                    |   |   |   |   |   |   |   |   |   |   |   |   |
| v/c Ratio                         | 0.17  | 0.17  | 0.09  | 0.17  | 0.18  | 0.22  | 0.18  | 0.36  | 0.03  | 0.32  | 0.61  | 0.04  |
| Uniform Delay, d1                 | 31.7  | 31.7  | 26.0  | 32.6  | 32.6  | 27.1  | 32.2  | 18.2  | 12.4  | 32.2  | 20.2  | 8.7   |
| Progression Factor                | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             | 0.6   | 0.5   | 0.1   | 0.6   | 0.7   | 0.4   | 0.6   | 0.2   | 0.0   | 1.2   | 0.9   | 0.0   |
| Delay (s)                         | 32.2  | 32.2  | 26.1  | 33.3  | 33.3  | 27.5  | 32.9  | 18.4  | 12.4  | 33.4  | 21.1  | 8.7   |
| Level of Service                  | C   | C   | C   | C   | C   | C   | C   | B   | B   | C   | C   | A   |
| Approach Delay (s)                |   | 27.8  |   |   | 30.0  |   |   | 18.6  |   |   | 21.1  |   |
| Approach LOS                      |   | C   |   |   | C   |   |   | B   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 21.6  |   |   |   |   |   |   |   |   | C   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.42  |   |   |   |   |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 75.9  |   |   |   |   |   |   |   | 25.5  |   |
| Intersection Capacity Utilization |   |   | 48.1%   |   |   |   |   |   |   |   |   | A   |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |


c Critical Lane Group

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2036 Build Weekday AM Peak

| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT                       | WBR  | NBL   | NBT   | NBR  | SBL  | SBT  | SBR   |  |
|-----------------------------------|-------|-------|-------|-------|---------------------------|------|-------|-------|------|------|------|-------|--|
| Lane Configurations               |       |       |       |       |                           |      |       |       |      |      |      |       |  |
| Traffic Volume (vph)              | 117   | 43    | 52    | 3     | 35                        | 44   | 73    | 328   | 85   | 2    | 323  | 266   |  |
| Future Volume (vph)               | 117   | 43    | 52    | 3     | 35                        | 44   | 73    | 328   | 85   | 2    | 323  | 266   |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900                      | 1900 | 1900  | 1900  | 1900 | 1900 | 1900 | 1900  |  |
| Lane Width                        | 11    | 11    | 11    | 14    | 14                        | 14   | 11    | 11    | 11   | 11   | 11   | 11    |  |
| Grade (%)                         |       | 5%    |       |       | -5%                       |      |       | 0%    |      |      | 0%   |       |  |
| Total Lost time (s)               | 6.5   | 6.5   |       | 6.5   | 6.5                       |      | 6.5   | 6.5   |      | 6.5  | 6.5  | 6.5   |  |
| Lane Util. Factor                 | 0.97  | 1.00  |       | 1.00  | 1.00                      |      | 1.00  | 0.95  |      | 1.00 | 0.95 | 1.00  |  |
| Frpb, ped/bikes                   | 1.00  | 0.99  |       | 1.00  | 1.00                      |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |  |
| Flpb, ped/bikes                   | 1.00  | 1.00  |       | 1.00  | 1.00                      |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |  |
| Frt                               | 1.00  | 0.92  |       | 1.00  | 0.92                      |      | 1.00  | 0.97  |      | 1.00 | 1.00 | 0.85  |  |
| Flt Protected                     | 0.95  | 1.00  |       | 0.95  | 1.00                      |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00  |  |
| Satd. Flow (prot)                 | 3268  | 1616  |       | 1898  | 1830                      |      | 1711  | 3301  |      | 1694 | 3388 | 1516  |  |
| Flt Permitted                     | 0.95  | 1.00  |       | 0.95  | 1.00                      |      | 0.95  | 1.00  |      | 0.95 | 1.00 | 1.00  |  |
| Satd. Flow (perm)                 | 3268  | 1616  |       | 1898  | 1830                      |      | 1711  | 3301  |      | 1694 | 3388 | 1516  |  |
| Peak-hour factor, PHF             | 0.73  | 0.73  | 0.73  | 0.65  | 0.65                      | 0.65 | 0.75  | 0.75  | 0.75 | 0.97 | 0.97 | 0.97  |  |
| Adj. Flow (vph)                   | 160   | 59    | 71    | 5     | 54                        | 68   | 97    | 437   | 113  | 2    | 333  | 274   |  |
| RTOR Reduction (vph)              | 0     | 34    | 0     | 0     | 40                        | 0    | 0     | 17    | 0    | 0    | 0    | 135   |  |
| Lane Group Flow (vph)             | 160   | 96    | 0     | 5     | 82                        | 0    | 97    | 533   | 0    | 2    | 333  | 139   |  |
| Confl. Bikes (#/hr)               |       |       | 1     |       |                           |      |       |       | 1    |      |      |       |  |
| Heavy Vehicles (%)                | 1%    | 1%    | 1%    | 4%    | 4%                        | 4%   | 2%    | 2%    | 2%   | 3%   | 3%   | 3%    |  |
| Turn Type                         | Split | NA    |       | Split | NA                        |      | Prot  | NA    |      | Prot | NA   | pt+ov |  |
| Protected Phases                  | 3     | 3     |       | 4     | 4                         |      | 1     | 6     |      | 5    | 2    | 2 3   |  |
| Permitted Phases                  |       |       |       |       |                           |      |       |       |      |      |      |       |  |
| Actuated Green, G (s)             | 9.9   | 9.9   |       | 6.7   | 6.7                       |      | 7.1   | 23.9  |      | 0.9  | 17.7 | 34.1  |  |
| Effective Green, g (s)            | 9.9   | 9.9   |       | 6.7   | 6.7                       |      | 7.1   | 23.9  |      | 0.9  | 17.7 | 34.1  |  |
| Actuated g/C Ratio                | 0.15  | 0.15  |       | 0.10  | 0.10                      |      | 0.11  | 0.35  |      | 0.01 | 0.26 | 0.51  |  |
| Clearance Time (s)                | 6.5   | 6.5   |       | 6.5   | 6.5                       |      | 6.5   | 6.5   |      | 6.5  | 6.5  |       |  |
| Vehicle Extension (s)             | 3.0   | 3.0   |       | 3.0   | 3.0                       |      | 3.0   | 3.0   |      | 3.0  | 3.0  |       |  |
| Lane Grp Cap (vph)                | 480   | 237   |       | 188   | 181                       |      | 180   | 1170  |      | 22   | 889  | 766   |  |
| v/s Ratio Prot                    | 0.05  | c0.06 |       | 0.00  | c0.05                     |      | c0.06 | c0.16 |      | 0.00 | 0.10 | 0.09  |  |
| v/s Ratio Perm                    |       |       |       |       |                           |      |       |       |      |      |      |       |  |
| v/c Ratio                         | 0.33  | 0.40  |       | 0.03  | 0.46                      |      | 0.54  | 0.46  |      | 0.09 | 0.37 | 0.18  |  |
| Uniform Delay, d1                 | 25.8  | 26.1  |       | 27.4  | 28.6                      |      | 28.6  | 16.7  |      | 32.8 | 20.3 | 9.1   |  |
| Progression Factor                | 1.00  | 1.00  |       | 1.00  | 1.00                      |      | 1.00  | 1.00  |      | 1.00 | 1.00 | 1.00  |  |
| Incremental Delay, d2             | 0.4   | 1.1   |       | 0.1   | 1.8                       |      | 3.1   | 0.3   |      | 1.8  | 0.3  | 0.1   |  |
| Delay (s)                         | 26.2  | 27.2  |       | 27.5  | 30.4                      |      | 31.7  | 17.0  |      | 34.6 | 20.6 | 9.2   |  |
| Level of Service                  | C     | C     |       | C     | C                         |      | C     | B     |      | C    | C    | A     |  |
| Approach Delay (s)                |       | 26.7  |       |       | 30.3                      |      |       | 19.2  |      |      | 15.5 |       |  |
| Approach LOS                      |       | C     |       |       | C                         |      |       | B     |      |      | B    |       |  |
| <b>Intersection Summary</b>       |       |       |       |       |                           |      |       |       |      |      |      |       |  |
| HCM 2000 Control Delay            |       |       | 20.0  |       | HCM 2000 Level of Service |      |       |       |      |      | B    |       |  |
| HCM 2000 Volume to Capacity ratio |       |       | 0.52  |       |                           |      |       |       |      |      |      |       |  |
| Actuated Cycle Length (s)         |       |       | 67.4  |       | Sum of lost time (s)      |      |       |       |      |      | 28.0 |       |  |
| Intersection Capacity Utilization |       |       | 43.0% |       | ICU Level of Service      |      |       |       |      |      | A    |       |  |
| Analysis Period (min)             |       |       | 15    |       |                           |      |       |       |      |      |      |       |  |

c Critical Lane Group

201: Motel 6/North Site & Gosling Road  
2036 Build Weekday AM Peak



| Movement                          | EBT  | EBR  | WBL   | WBT  | NBL                  | NBR  |      |
|-----------------------------------|------|------|-------|------|----------------------|------|------|
| Lane Configurations               | ↑↑↑↑ |      |       | ↑↑   |                      | ↗    |      |
| Traffic Volume (veh/h)            | 784  | 110  | 0     | 381  | 0                    | 15   |      |
| Future Volume (Veh/h)             | 784  | 110  | 0     | 381  | 0                    | 15   |      |
| Sign Control                      | Free |      |       | Free | Stop                 |      |      |
| Grade                             | 0%   |      |       | 0%   | 0%                   |      |      |
| Peak Hour Factor                  | 0.97 | 0.97 | 0.89  | 0.89 | 0.46                 | 0.46 |      |
| Hourly flow rate (vph)            | 808  | 113  | 0     | 428  | 0                    | 33   |      |
| Pedestrians                       |      |      |       |      |                      |      |      |
| Lane Width (ft)                   |      |      |       |      |                      |      |      |
| Walking Speed (ft/s)              |      |      |       |      |                      |      |      |
| Percent Blockage                  |      |      |       |      |                      |      |      |
| Right turn flare (veh)            |      |      |       |      |                      |      |      |
| Median type                       | None |      |       | None |                      |      |      |
| Median storage (veh)              |      |      |       |      |                      |      |      |
| Upstream signal (ft)              | 464  |      |       |      |                      |      |      |
| pX, platoon unblocked             |      |      |       |      |                      |      |      |
| vC, conflicting volume            |      |      | 921   |      | 1078                 | 258  |      |
| vC1, stage 1 conf vol             |      |      |       |      |                      |      |      |
| vC2, stage 2 conf vol             |      |      |       |      |                      |      |      |
| vCu, unblocked vol                |      |      | 921   |      | 1078                 | 258  |      |
| tC, single (s)                    |      |      | 4.2   |      | 6.8                  | 6.9  |      |
| tC, 2 stage (s)                   |      |      |       |      |                      |      |      |
| tF (s)                            |      |      | 2.2   |      | 3.5                  | 3.3  |      |
| p0 queue free %                   |      |      | 100   |      | 100                  | 96   |      |
| cM capacity (veh/h)               |      |      | 719   |      | 217                  | 747  |      |
| Direction, Lane #                 | EB 1 | EB 2 | EB 3  | EB 4 | WB 1                 | WB 2 | NB 1 |
| Volume Total                      | 231  | 231  | 231   | 228  | 214                  | 214  | 33   |
| Volume Left                       | 0    | 0    | 0     | 0    | 0                    | 0    | 0    |
| Volume Right                      | 0    | 0    | 0     | 113  | 0                    | 0    | 33   |
| cSH                               | 1700 | 1700 | 1700  | 1700 | 1700                 | 1700 | 747  |
| Volume to Capacity                | 0.14 | 0.14 | 0.14  | 0.13 | 0.13                 | 0.13 | 0.04 |
| Queue Length 95th (ft)            | 0    | 0    | 0     | 0    | 0                    | 0    | 3    |
| Control Delay (s)                 | 0.0  | 0.0  | 0.0   | 0.0  | 0.0                  | 0.0  | 10.0 |
| Lane LOS                          |      |      |       |      |                      |      | B    |
| Approach Delay (s)                | 0.0  |      |       |      | 0.0                  |      | 10.0 |
| Approach LOS                      |      |      |       |      |                      |      | B    |
| Intersection Summary              |      |      |       |      |                      |      |      |
| Average Delay                     |      |      | 0.2   |      |                      |      |      |
| Intersection Capacity Utilization |      |      | 23.2% |      | ICU Level of Service |      | A    |
| Analysis Period (min)             |      |      | 15    |      |                      |      |      |

202: Arthur F Brady Drive & South Site Driveway  
 2036 Build Weekday AM Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 4.8  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↕    | ↕     | ↕    | ↕    |
| Traffic Vol, veh/h       | 64   | 96   | 85   | 79    | 90   | 76   |
| Future Vol, veh/h        | 64   | 96   | 85   | 79    | 90   | 76   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 85   | 85   | 84   | 84    | 81   | 81   |
| Heavy Vehicles, %        | 4    | 4    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 75   | 113  | 101  | 94    | 111  | 94   |

| Major/Minor          | Major1 | Major2 | Minor2 |   |         |
|----------------------|--------|--------|--------|---|---------|
| Conflicting Flow All | 102    | 0      | -      | 0 | 365 103 |
| Stage 1              | -      | -      | -      | - | 102 -   |
| Stage 2              | -      | -      | -      | - | 263 -   |
| Critical Hdwy        | 4.14   | -      | -      | - | 6.4 6.2 |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.4 -   |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.4 -   |
| Follow-up Hdwy       | 2.236  | -      | -      | - | 3.5 3.3 |
| Pot Cap-1 Maneuver   | 1478   | -      | -      | - | 639 957 |
| Stage 1              | -      | -      | -      | - | 927 -   |
| Stage 2              | -      | -      | -      | - | 786 -   |
| Platoon blocked, %   |        | -      | -      | - |         |
| Mov Cap-1 Maneuver   | 1477   | -      | -      | - | 603 955 |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 603 -   |
| Stage 1              | -      | -      | -      | - | 876 -   |
| Stage 2              | -      | -      | -      | - | 785 -   |

| Approach             | EB | WB | SB   |
|----------------------|----|----|------|
| HCM Control Delay, s | 3  | 0  | 10.9 |
| HCM LOS              |    |    | B    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1477  | -   | -   | -   | 603   | 955   |
| HCM Lane V/C Ratio    | 0.051 | -   | -   | -   | 0.184 | 0.098 |
| HCM Control Delay (s) | 7.6   | 0   | -   | -   | 12.3  | 9.2   |
| HCM Lane LOS          | A     | A   | -   | -   | B     | A     |
| HCM 95th %tile Q(veh) | 0.2   | -   | -   | -   | 0.7   | 0.3   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
 2036 Build Weekday PM Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↘   | ↗   | ↗↗  |
| Traffic Volume (vph)              | 0   | 1282  | 644   | 517   | 339   | 0   | 0  | 0   | 0   | 275   | 1   | 125   |
| Future Volume (vph)               | 0   | 1282  | 644   | 517   | 339   | 0   | 0  | 0   | 0   | 275   | 1   | 125   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1703  | 2814  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.94  | 0.94  | 0.94  | 0.92   | 0.92  | 0.92  | 0.94  | 0.94  | 0.94  |
| Adj. Flow (vph)                   | 0   | 1526  | 767   | 550   | 361   | 0   | 0  | 0   | 0   | 293   | 1   | 133   |
| RTOR Reduction (vph)              | 0   | 0   | 359   | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 104   |
| Lane Group Flow (vph)             | 0   | 1526  | 408   | 550   | 361   | 0   | 0  | 0   | 0   | 146   | 148   | 29  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 35.8  | 35.8  | 22.5  | 56.4  |   |  |   |   | 20.9  | 20.9  | 20.9  |
| Effective Green, g (s)            |   | 35.8  | 35.8  | 22.5  | 56.4  |   |  |   |   | 20.9  | 20.9  | 20.9  |
| Actuated g/C Ratio                |   | 0.37  | 0.37  | 0.23  | 0.58  |   |  |   |   | 0.22  | 0.22  | 0.22  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 2224  | 569   | 749   | 2004  |   |  |   |   | 365   | 366   | 605   |
| v/s Ratio Prot                    |   | 0.25  | c0.26   | c0.17   | 0.10  |   |  |   |   | 0.09  | c0.09   | 0.01  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.69  | 0.72  | 0.73  | 0.18  |   |  |   |   | 0.40  | 0.40  | 0.05  |
| Uniform Delay, d1                 |   | 26.0  | 26.3  | 34.6  | 9.6   |   |  |   |   | 32.8  | 32.8  | 30.3  |
| Progression Factor                |   | 1.00  | 1.00  | 1.36  | 0.83  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 1.2   | 5.3   | 3.4   | 0.1   |   |  |   |   | 1.5   | 1.5   | 0.1   |
| Delay (s)                         |   | 27.1  | 31.6  | 50.4  | 8.0   |   |  |   |   | 34.3  | 34.3  | 30.3  |
| Level of Service                  |   | C   | C   | D   | A   |   |  |   |   | C   | C   | C   |
| Approach Delay (s)                |   | 28.6  |   |   | 33.6  |   |  | 0.0   |   |   | 33.1  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 30.4  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.64  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 97.2  |   |   | Sum of lost time (s)  |  |   |   | 18.0  |   |   |
| Intersection Capacity Utilization |   |   | 77.3%   |   |   | ICU Level of Service  |  |   |   | D   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
 2036 Build Weekday PM Peak

























| Movement                          | EBL   | EBT  | EBR   | WBL  | WBT  | WBR  | NBL                       | NBT  | NBR  | SBL  | SBT  | SBR  |
|-----------------------------------|-------|------|-------|------|------|------|---------------------------|------|------|------|------|------|
| Lane Configurations               |       |      |       |      |      |      |                           |      |      |      |      |      |
| Traffic Volume (vph)              | 785   | 772  | 0     | 0    | 699  | 365  | 157                       | 0    | 592  | 0    | 0    | 0    |
| Future Volume (vph)               | 785   | 772  | 0     | 0    | 699  | 365  | 157                       | 0    | 592  | 0    | 0    | 0    |
| Ideal Flow (vphpl)                | 1900  | 1900 | 1900  | 1900 | 1900 | 1900 | 1900                      | 1900 | 1900 | 1900 | 1900 | 1900 |
| Lane Width                        | 10    | 11   | 12    | 12   | 12   | 12   | 12                        | 12   | 12   | 12   | 12   | 12   |
| Total Lost time (s)               | 6.0   | 6.0  |       |      | 6.0  |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Lane Util. Factor                 | 0.97  | 0.95 |       |      | 0.91 |      | 0.97                      | 0.95 | 0.95 |      |      |      |
| Frt                               | 1.00  | 1.00 |       |      | 0.95 |      | 1.00                      | 0.85 | 0.85 |      |      |      |
| Flt Protected                     | 0.95  | 1.00 |       |      | 1.00 |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (prot)                 | 3236  | 3455 |       |      | 4872 |      | 3433                      | 1504 | 1504 |      |      |      |
| Flt Permitted                     | 0.14  | 1.00 |       |      | 1.00 |      | 0.95                      | 1.00 | 1.00 |      |      |      |
| Satd. Flow (perm)                 | 477   | 3455 |       |      | 4872 |      | 3433                      | 1504 | 1504 |      |      |      |
| Peak-hour factor, PHF             | 0.87  | 0.87 | 0.87  | 0.94 | 0.94 | 0.94 | 0.94                      | 0.94 | 0.94 | 0.90 | 0.90 | 0.90 |
| Adj. Flow (vph)                   | 902   | 887  | 0     | 0    | 744  | 388  | 167                       | 0    | 630  | 0    | 0    | 0    |
| RTOR Reduction (vph)              | 0     | 0    | 0     | 0    | 91   | 0    | 0                         | 247  | 247  | 0    | 0    | 0    |
| Lane Group Flow (vph)             | 902   | 887  | 0     | 0    | 1041 | 0    | 167                       | 68   | 68   | 0    | 0    | 0    |
| Heavy Vehicles (%)                | 1%    | 1%   | 1%    | 1%   | 1%   | 1%   | 2%                        | 2%   | 2%   | 0%   | 0%   | 0%   |
| Turn Type                         | pm+pt | NA   |       |      | NA   |      | Split                     | NA   | Prot |      |      |      |
| Protected Phases                  | 1     | 6    |       |      | 2    |      | 3                         | 3    | 3    |      |      |      |
| Permitted Phases                  | 6     |      |       |      |      |      |                           |      |      |      |      |      |
| Actuated Green, G (s)             | 60.2  | 35.8 |       |      | 33.9 |      | 20.9                      | 20.9 | 20.9 |      |      |      |
| Effective Green, g (s)            | 60.2  | 35.8 |       |      | 33.9 |      | 20.9                      | 20.9 | 20.9 |      |      |      |
| Actuated g/C Ratio                | 0.62  | 0.37 |       |      | 0.35 |      | 0.22                      | 0.22 | 0.22 |      |      |      |
| Clearance Time (s)                | 6.0   | 6.0  |       |      | 6.0  |      | 6.0                       | 6.0  | 6.0  |      |      |      |
| Vehicle Extension (s)             | 4.0   | 5.0  |       |      | 5.0  |      | 5.0                       | 5.0  | 5.0  |      |      |      |
| Lane Grp Cap (vph)                | 988   | 1272 |       |      | 1699 |      | 738                       | 323  | 323  |      |      |      |
| v/s Ratio Prot                    | c0.23 | 0.26 |       |      | 0.21 |      | c0.05                     | 0.05 | 0.05 |      |      |      |
| v/s Ratio Perm                    | c0.34 |      |       |      |      |      |                           |      |      |      |      |      |
| v/c Ratio                         | 0.91  | 0.70 |       |      | 0.61 |      | 0.23                      | 0.21 | 0.21 |      |      |      |
| Uniform Delay, d1                 | 23.8  | 26.1 |       |      | 26.2 |      | 31.5                      | 31.4 | 31.4 |      |      |      |
| Progression Factor                | 1.90  | 0.49 |       |      | 1.00 |      | 1.00                      | 1.00 | 1.00 |      |      |      |
| Incremental Delay, d2             | 10.2  | 1.7  |       |      | 1.0  |      | 0.3                       | 0.7  | 0.7  |      |      |      |
| Delay (s)                         | 55.5  | 14.5 |       |      | 27.2 |      | 31.8                      | 32.0 | 32.0 |      |      |      |
| Level of Service                  | E     | B    |       |      | C    |      | C                         | C    | C    |      |      |      |
| Approach Delay (s)                |       | 35.2 |       |      | 27.2 |      |                           | 32.0 |      |      | 0.0  |      |
| Approach LOS                      |       | D    |       |      | C    |      |                           | C    |      |      | A    |      |
| <b>Intersection Summary</b>       |       |      |       |      |      |      |                           |      |      |      |      |      |
| HCM 2000 Control Delay            |       |      | 32.0  |      |      |      | HCM 2000 Level of Service |      |      | C    |      |      |
| HCM 2000 Volume to Capacity ratio |       |      | 0.75  |      |      |      |                           |      |      |      |      |      |
| Actuated Cycle Length (s)         |       |      | 97.2  |      |      |      | Sum of lost time (s)      |      |      | 18.0 |      |      |
| Intersection Capacity Utilization |       |      | 77.3% |      |      |      | ICU Level of Service      |      |      | D    |      |      |
| Analysis Period (min)             |       |      | 15    |      |      |      |                           |      |      |      |      |      |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2036 Build Weekday PM Peak

























| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT                       | WBR  | NBL   | NBT  | NBR  | SBL  | SBT   | SBR   |  |
|-----------------------------------|-------|-------|-------|-------|---------------------------|------|-------|------|------|------|-------|-------|--|
| Lane Configurations               |       |       |       |       |                           |      |       |      |      |      |       |       |  |
| Traffic Volume (vph)              | 98    | 68    | 554   | 68    | 61                        | 54   | 400   | 534  | 38   | 34   | 522   | 135   |  |
| Future Volume (vph)               | 98    | 68    | 554   | 68    | 61                        | 54   | 400   | 534  | 38   | 34   | 522   | 135   |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900                      | 1900 | 1900  | 1900 | 1900 | 1900 | 1900  | 1900  |  |
| Lane Width                        | 11    | 11    | 14    | 12    | 12                        | 16   | 12    | 12   | 12   | 11   | 11    | 11    |  |
| Total Lost time (s)               |       | 6.0   | 6.0   |       | 5.5                       |      | 6.0   | 6.0  |      | 5.5  | 6.0   | 6.0   |  |
| Lane Util. Factor                 |       | 1.00  | 1.00  |       | 1.00                      |      | 0.97  | 0.95 |      | 1.00 | 0.95  | 1.00  |  |
| Frbp, ped/bikes                   |       | 1.00  | 1.00  |       | 1.00                      |      | 1.00  | 1.00 |      | 1.00 | 1.00  | 1.00  |  |
| Flpb, ped/bikes                   |       | 1.00  | 1.00  |       | 1.00                      |      | 1.00  | 1.00 |      | 1.00 | 1.00  | 1.00  |  |
| Frt                               |       | 1.00  | 0.85  |       | 0.96                      |      | 1.00  | 0.99 |      | 1.00 | 1.00  | 0.85  |  |
| Flt Protected                     |       | 0.97  | 1.00  |       | 0.98                      |      | 0.95  | 1.00 |      | 0.95 | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 |       | 1749  | 1689  |       | 1755                      |      | 3467  | 3533 |      | 1711 | 3421  | 1531  |  |
| Flt Permitted                     |       | 0.97  | 1.00  |       | 0.98                      |      | 0.95  | 1.00 |      | 0.95 | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 |       | 1749  | 1689  |       | 1755                      |      | 3467  | 3533 |      | 1711 | 3421  | 1531  |  |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.80  | 0.80                      | 0.80 | 0.96  | 0.96 | 0.96 | 0.97 | 0.97  | 0.97  |  |
| Adj. Flow (vph)                   | 109   | 76    | 616   | 85    | 76                        | 68   | 417   | 556  | 40   | 35   | 538   | 139   |  |
| RTOR Reduction (vph)              | 0     | 0     | 467   | 0     | 12                        | 0    | 0     | 3    | 0    | 0    | 0     | 83    |  |
| Lane Group Flow (vph)             | 0     | 185   | 149   | 0     | 217                       | 0    | 417   | 593  | 0    | 35   | 538   | 56    |  |
| Confl. Bikes (#/hr)               |       |       |       |       |                           |      |       |      | 2    |      |       |       |  |
| Heavy Vehicles (%)                | 2%    | 2%    | 2%    | 2%    | 2%                        | 2%   | 1%    | 1%   | 1%   | 2%   | 2%    | 2%    |  |
| Turn Type                         | Split | NA    | pt+ov | Split | NA                        |      | Prot  | NA   |      | Prot | NA    | pt+ov |  |
| Protected Phases                  | 3     | 3     | 3 1   | 4     | 4                         |      | 1     | 6    |      | 5    | 2     | 2 3   |  |
| Permitted Phases                  |       |       |       |       |                           |      |       |      |      |      |       |       |  |
| Actuated Green, G (s)             |       | 8.4   | 22.0  |       | 15.8                      |      | 13.6  | 31.9 |      | 4.7  | 22.5  | 36.9  |  |
| Effective Green, g (s)            |       | 8.4   | 22.0  |       | 15.8                      |      | 13.6  | 31.9 |      | 4.7  | 22.5  | 36.9  |  |
| Actuated g/C Ratio                |       | 0.09  | 0.24  |       | 0.17                      |      | 0.15  | 0.35 |      | 0.05 | 0.25  | 0.41  |  |
| Clearance Time (s)                |       | 6.0   |       |       | 5.5                       |      | 6.0   | 6.0  |      | 5.5  | 6.0   |       |  |
| Vehicle Extension (s)             |       | 3.0   |       |       | 3.0                       |      | 3.0   | 3.0  |      | 3.0  | 3.0   |       |  |
| Lane Grp Cap (vph)                |       | 161   | 408   |       | 305                       |      | 518   | 1239 |      | 88   | 846   | 621   |  |
| v/s Ratio Prot                    |       | c0.11 | 0.09  |       | c0.12                     |      | c0.12 | 0.17 |      | 0.02 | c0.16 | 0.04  |  |
| v/s Ratio Perm                    |       |       |       |       |                           |      |       |      |      |      |       |       |  |
| v/c Ratio                         |       | 1.15  | 0.37  |       | 0.71                      |      | 0.81  | 0.48 |      | 0.40 | 0.64  | 0.09  |  |
| Uniform Delay, d1                 |       | 41.2  | 28.6  |       | 35.4                      |      | 37.4  | 23.0 |      | 41.7 | 30.5  | 16.7  |  |
| Progression Factor                |       | 1.00  | 1.00  |       | 1.00                      |      | 1.00  | 1.00 |      | 1.00 | 1.00  | 1.00  |  |
| Incremental Delay, d2             |       | 116.6 | 0.6   |       | 7.6                       |      | 8.9   | 0.3  |      | 2.9  | 1.6   | 0.1   |  |
| Delay (s)                         |       | 157.9 | 29.2  |       | 43.0                      |      | 46.2  | 23.3 |      | 44.7 | 32.1  | 16.7  |  |
| Level of Service                  |       | F     | C     |       | D                         |      | D     | C    |      | D    | C     | B     |  |
| Approach Delay (s)                |       | 58.9  |       |       | 43.0                      |      | 32.7  |      |      | 29.7 |       |       |  |
| Approach LOS                      |       | E     |       |       | D                         |      | C     |      |      | C    |       |       |  |
| <b>Intersection Summary</b>       |       |       |       |       |                           |      |       |      |      |      |       |       |  |
| HCM 2000 Control Delay            |       |       | 40.4  |       | HCM 2000 Level of Service |      |       |      |      |      | D     |       |  |
| HCM 2000 Volume to Capacity ratio |       |       | 0.70  |       |                           |      |       |      |      |      |       |       |  |
| Actuated Cycle Length (s)         |       |       | 90.9  |       | Sum of lost time (s)      |      |       |      |      | 25.5 |       |       |  |
| Intersection Capacity Utilization |       |       | 73.6% |       | ICU Level of Service      |      |       |      |      | D    |       |       |  |
| Analysis Period (min)             |       |       | 15    |       |                           |      |       |      |      |      |       |       |  |
| c Critical Lane Group             |       |       |       |       |                           |      |       |      |      |      |       |       |  |

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
 2036 Build Weekday PM Peak

|                                   |  |  |  |  |  |  |   |  |  |  |  |  |      |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|------|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |      |
| Lane Configurations               |  |  |  |  |  |  |  |  |  |  |  |  |      |
| Traffic Volume (vph)              | 135   | 21  | 112   | 117   | 17  | 104   | 68  | 762   | 111   | 86  | 781   | 32  |      |
| Future Volume (vph)               | 135   | 21  | 112   | 117   | 17  | 104   | 68  | 762   | 111   | 86  | 781   | 32  |      |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |      |
| Lane Width                        | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 11  | 16  | 11  | 11  | 11  |      |
| Grade (%)                         |   | 3%  |   |   | -5%   |   |   | 5%  |   |   | -3%   |   |      |
| Total Lost time (s)               | 6.0   | 6.0   | 6.0   | 5.5   | 5.5   | 5.5   | 6.0   | 6.0   | 5.5   | 5.5   | 6.0   | 6.0   |      |
| Lane Util. Factor                 | 0.95  | 0.95  | 1.00  | 0.95  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  |      |
| Frt                               | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  |      |
| Flt Protected                     | 0.95  | 0.96  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |      |
| Satd. Flow (prot)                 | 1633  | 1657  | 1424  | 1682  | 1707  | 1584  | 1684  | 3369  | 1767  | 1753  | 3507  | 1569  |      |
| Flt Permitted                     | 0.95  | 0.96  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |      |
| Satd. Flow (perm)                 | 1633  | 1657  | 1424  | 1682  | 1707  | 1584  | 1684  | 3369  | 1767  | 1753  | 3507  | 1569  |      |
| Peak-hour factor, PHF             | 0.86  | 0.86  | 0.86  | 0.77  | 0.77  | 0.77  | 0.87  | 0.87  | 0.87  | 0.94  | 0.94  | 0.94  |      |
| Adj. Flow (vph)                   | 157   | 24  | 130   | 152   | 22  | 135   | 78  | 876   | 128   | 91  | 831   | 34  |      |
| RTOR Reduction (vph)              | 0   | 0   | 106   | 0   | 0   | 0   | 0   | 0   | 69  | 0   | 0   | 14  |      |
| Lane Group Flow (vph)             | 89  | 92  | 24  | 87  | 87  | 135   | 78  | 876   | 59  | 91  | 831   | 20  |      |
| Heavy Vehicles (%)                | 0%  | 0%  | 8%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  |      |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  | pt+ov   | Prot  | NA  | pt+ov   | Prot  | NA  | pt+ov   |      |
| Protected Phases                  | 3   | 3   | 13  | 4   | 4   | 45  | 1   | 6   | 46  | 5   | 2   | 23  |      |
| Permitted Phases                  |   |   |   |   |   |   |   |   |   |   |   |   |      |
| Actuated Green, G (s)             | 8.1   | 8.1   | 14.1  | 8.3   | 8.3   | 23.3  | 6.0   | 26.2  | 34.5  | 9.5   | 29.2  | 43.3  |      |
| Effective Green, g (s)            | 8.1   | 8.1   | 14.1  | 8.3   | 8.3   | 23.3  | 6.0   | 26.2  | 34.5  | 9.5   | 29.2  | 43.3  |      |
| Actuated g/C Ratio                | 0.11  | 0.11  | 0.19  | 0.11  | 0.11  | 0.31  | 0.08  | 0.35  | 0.46  | 0.13  | 0.39  | 0.58  |      |
| Clearance Time (s)                | 6.0   | 6.0   |   | 5.5   | 5.5   |   | 6.0   | 6.0   |   | 5.5   | 6.0   |   |      |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   |      |
| Lane Grp Cap (vph)                | 176   | 178   | 267   | 185   | 188   | 491   | 134   | 1175  | 811   | 221   | 1363  | 904   |      |
| v/s Ratio Prot                    | 0.05  | c0.06   | 0.02  | c0.05   | 0.05  | 0.09  | 0.05  | c0.26   | 0.03  | c0.05   | c0.24   | 0.01  |      |
| v/s Ratio Perm                    |   |   |   |   |   |   |   |   |   |   |   |   |      |
| v/c Ratio                         | 0.51  | 0.52  | 0.09  | 0.47  | 0.46  | 0.27  | 0.58  | 0.75  | 0.07  | 0.41  | 0.61  | 0.02  |      |
| Uniform Delay, d1                 | 31.6  | 31.7  | 25.2  | 31.3  | 31.3  | 19.5  | 33.3  | 21.5  | 11.4  | 30.2  | 18.4  | 6.8   |      |
| Progression Factor                | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |      |
| Incremental Delay, d2             | 2.3   | 2.5   | 0.1   | 1.9   | 1.8   | 0.3   | 6.3   | 2.6   | 0.0   | 1.2   | 0.8   | 0.0   |      |
| Delay (s)                         | 33.9  | 34.2  | 25.4  | 33.2  | 33.1  | 19.8  | 39.6  | 24.1  | 11.4  | 31.5  | 19.2  | 6.8   |      |
| Level of Service                  | C   | C   | C   | C   | C   | B   | D   | C   | B   | C   | B   | A   |      |
| Approach Delay (s)                |   | 30.4  |   |   | 27.3  |   |   | 23.7  |   |   | 19.9  |   |      |
| Approach LOS                      |   | C   |   |   | C   |   |   | C   |   |   | B   |   |      |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |      |
| HCM 2000 Control Delay            |   |   | 23.6  |   |   |   |   |   |   |   |   | HCM 2000 Level of Service   | C    |
| HCM 2000 Volume to Capacity ratio |   |   | 0.64  |   |   |   |   |   |   |   |   |   |      |
| Actuated Cycle Length (s)         |   |   | 75.1  |   |   |   |   |   |   |   |   | Sum of lost time (s)  | 25.5 |
| Intersection Capacity Utilization |   |   | 53.3%   |   |   |   |   |   |   |   |   | ICU Level of Service  | A    |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |      |
| c Critical Lane Group             |   |   |   |   |   |   |   |   |   |   |   |   |      |



105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2036 Build Weekday PM Peak

|                                   |    |  |  |  |  |  |   |    |  |  |    |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |  |   |  |  |   |  |   |   |  |   |  |
| Traffic Volume (vph)              | 255   | 80  | 111   | 221   | 104   | 18  | 111   | 537   | 160   | 18  | 741   | 446   |
| Future Volume (vph)               | 255   | 80  | 111   | 221   | 104   | 18  | 111   | 537   | 160   | 18  | 741   | 446   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 11  | 14  | 14  | 14  | 11  | 11  | 11  | 11  | 11  | 11  |
| Grade (%)                         |   | 5%  |   |   | -5%   |   |   | 0%  |   |   | 0%  |   |
| Total Lost time (s)               | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   | 6.5   |
| Lane Util. Factor                 | 0.97  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frt                               | 1.00  | 0.91  |   | 1.00  | 0.98  |   | 1.00  | 0.97  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 | 3268  | 1619  |   | 1954  | 2011  |   | 1728  | 3336  |   | 1728  | 3455  | 1546  |
| Flt Permitted                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 | 3268  | 1619  |   | 1954  | 2011  |   | 1728  | 3336  |   | 1728  | 3455  | 1546  |
| Peak-hour factor, PHF             | 0.90  | 0.90  | 0.90  | 0.91  | 0.91  | 0.91  | 0.88  | 0.88  | 0.88  | 0.90  | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 283   | 89  | 123   | 243   | 114   | 20  | 126   | 610   | 182   | 20  | 823   | 496   |
| RTOR Reduction (vph)              | 0   | 41  | 0   | 0   | 5   | 0   | 0   | 19  | 0   | 0   | 0   | 259   |
| Lane Group Flow (vph)             | 283   | 171   | 0   | 243   | 129   | 0   | 126   | 773   | 0   | 20  | 823   | 237   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  |
| Turn Type                         | Split   | NA  |   | Split   | NA  |   | Prot  | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   |   | 4   | 4   |   | 1   | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |   |   |   |   |   |   |
| Actuated Green, G (s)             | 11.2  | 11.2  |   | 16.1  | 16.1  |   | 11.1  | 38.9  |   | 2.8   | 30.6  | 48.3  |
| Effective Green, g (s)            | 11.2  | 11.2  |   | 16.1  | 16.1  |   | 11.1  | 38.9  |   | 2.8   | 30.6  | 48.3  |
| Actuated g/C Ratio                | 0.11  | 0.11  |   | 0.16  | 0.16  |   | 0.11  | 0.39  |   | 0.03  | 0.30  | 0.48  |
| Clearance Time (s)                | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                | 362   | 179   |   | 311   | 320   |   | 189   | 1284  |   | 47  | 1046  | 739   |
| v/s Ratio Prot                    | 0.09  | c0.11   |   | c0.12   | 0.06  |   | c0.07   | c0.23   |   | 0.01  | c0.24   | 0.15  |
| v/s Ratio Perm                    |   |   |   |   |   |   |   |   |   |   |   |   |
| v/c Ratio                         | 0.78  | 0.96  |   | 0.78  | 0.40  |   | 0.67  | 0.60  |   | 0.43  | 0.79  | 0.32  |
| Uniform Delay, d1                 | 43.7  | 44.7  |   | 40.8  | 38.1  |   | 43.2  | 24.9  |   | 48.3  | 32.2  | 16.2  |
| Progression Factor                | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             | 10.5  | 53.9  |   | 12.0  | 0.8   |   | 8.6   | 0.8   |   | 6.1   | 4.0   | 0.3   |
| Delay (s)                         | 54.2  | 98.6  |   | 52.8  | 39.0  |   | 51.7  | 25.7  |   | 54.4  | 36.2  | 16.5  |
| Level of Service                  | D   | F   |   | D   | D   |   | D   | C   |   | D   | D   | B   |
| Approach Delay (s)                |   | 73.2  |   |   | 47.9  |   |   | 29.2  |   |   | 29.2  |   |
| Approach LOS                      |   | E   |   |   | D   |   |   | C   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 38.4  |   |   |   | HCM 2000 Level of Service   |   |   |   | D   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.76  |   |   |   |   |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 101.0   |   |   |   | Sum of lost time (s)  |   |   | 28.0  |   |   |
| Intersection Capacity Utilization |   |   | 71.6%   |   |   |   | ICU Level of Service  |   |   | C   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |   |   |   |   |   |   |

201: Motel 6/North Site & Gosling Road  
 2036 Build Weekday PM Peak



| Movement                          | EBT  | EBR  | WBL   | WBT  | NBL                  | NBR  |      |
|-----------------------------------|------|------|-------|------|----------------------|------|------|
| Lane Configurations               | ↑↑↑↑ |      |       | ↑↑   |                      | ↗    |      |
| Traffic Volume (veh/h)            | 1218 | 146  | 0     | 1064 | 0                    | 34   |      |
| Future Volume (Veh/h)             | 1218 | 146  | 0     | 1064 | 0                    | 34   |      |
| Sign Control                      | Free |      |       | Free | Stop                 |      |      |
| Grade                             | 0%   |      |       | 0%   | 0%                   |      |      |
| Peak Hour Factor                  | 0.94 | 0.94 | 0.98  | 0.97 | 0.72                 | 0.72 |      |
| Hourly flow rate (vph)            | 1296 | 155  | 0     | 1097 | 0                    | 47   |      |
| <b>Pedestrians</b>                |      |      |       |      |                      |      |      |
| Lane Width (ft)                   |      |      |       |      |                      |      |      |
| Walking Speed (ft/s)              |      |      |       |      |                      |      |      |
| Percent Blockage                  |      |      |       |      |                      |      |      |
| Right turn flare (veh)            |      |      |       |      |                      |      |      |
| Median type                       | None |      |       | None |                      |      |      |
| Median storage (veh)              |      |      |       |      |                      |      |      |
| Upstream signal (ft)              | 464  |      |       |      |                      |      |      |
| pX, platoon unblocked             |      |      |       |      |                      |      |      |
| vC, conflicting volume            |      |      | 1451  |      | 1922                 | 402  |      |
| vC1, stage 1 conf vol             |      |      |       |      |                      |      |      |
| vC2, stage 2 conf vol             |      |      |       |      |                      |      |      |
| vCu, unblocked vol                |      |      | 1451  |      | 1922                 | 402  |      |
| tC, single (s)                    |      |      | 4.1   |      | 6.8                  | 6.9  |      |
| tC, 2 stage (s)                   |      |      |       |      |                      |      |      |
| tF (s)                            |      |      | 2.2   |      | 3.5                  | 3.3  |      |
| p0 queue free %                   |      |      | 100   |      | 100                  | 92   |      |
| cM capacity (veh/h)               |      |      | 468   |      | 60                   | 604  |      |
| Direction, Lane #                 | EB 1 | EB 2 | EB 3  | EB 4 | WB 1                 | WB 2 | NB 1 |
| Volume Total                      | 370  | 370  | 370   | 340  | 548                  | 548  | 47   |
| Volume Left                       | 0    | 0    | 0     | 0    | 0                    | 0    | 0    |
| Volume Right                      | 0    | 0    | 0     | 155  | 0                    | 0    | 47   |
| cSH                               | 1700 | 1700 | 1700  | 1700 | 1700                 | 1700 | 604  |
| Volume to Capacity                | 0.22 | 0.22 | 0.22  | 0.20 | 0.32                 | 0.32 | 0.08 |
| Queue Length 95th (ft)            | 0    | 0    | 0     | 0    | 0                    | 0    | 6    |
| Control Delay (s)                 | 0.0  | 0.0  | 0.0   | 0.0  | 0.0                  | 0.0  | 11.5 |
| Lane LOS                          |      |      |       |      |                      |      | B    |
| Approach Delay (s)                | 0.0  |      |       |      | 0.0                  |      | 11.5 |
| Approach LOS                      |      |      |       |      |                      |      | B    |
| <b>Intersection Summary</b>       |      |      |       |      |                      |      |      |
| Average Delay                     |      |      | 0.2   |      |                      |      |      |
| Intersection Capacity Utilization |      |      | 32.7% |      | ICU Level of Service |      | A    |
| Analysis Period (min)             |      |      | 15    |      |                      |      |      |

202: Arthur F Brady Drive & South Site Driveway  
 2036 Build Weekday PM Peak













| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 6.1  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↑    | ↗     | ↖    | ↗    |
| Traffic Vol, veh/h       | 100  | 197  | 264  | 80    | 123  | 87   |
| Future Vol, veh/h        | 100  | 197  | 264  | 80    | 123  | 87   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 97   | 97   | 80   | 80    | 74   | 74   |
| Heavy Vehicles, %        | 0    | 0    | 0    | 0     | 1    | 1    |
| Mvmt Flow                | 103  | 203  | 330  | 100   | 166  | 118  |

| Major/Minor          | Major1 | Major2 | Minor2 |   |             |
|----------------------|--------|--------|--------|---|-------------|
| Conflicting Flow All | 331    | 0      | -      | 0 | 740 332     |
| Stage 1              | -      | -      | -      | - | 331 -       |
| Stage 2              | -      | -      | -      | - | 409 -       |
| Critical Hdwy        | 4.1    | -      | -      | - | 6.41 6.21   |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.41 -      |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.41 -      |
| Follow-up Hdwy       | 2.2    | -      | -      | - | 3.509 3.309 |
| Pot Cap-1 Maneuver   | 1240   | -      | -      | - | 386 712     |
| Stage 1              | -      | -      | -      | - | 730 -       |
| Stage 2              | -      | -      | -      | - | 673 -       |
| Platoon blocked, %   |        | -      | -      | - |             |
| Mov Cap-1 Maneuver   | 1239   | -      | -      | - | 349 710     |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 349 -       |
| Stage 1              | -      | -      | -      | - | 661 -       |
| Stage 2              | -      | -      | -      | - | 672 -       |

| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.8 | 0  | 18.8 |
| HCM LOS              |     |    | C    |




























| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1239  | -   | -   | -   | 349   | 710   |
| HCM Lane V/C Ratio    | 0.083 | -   | -   | -   | 0.476 | 0.166 |
| HCM Control Delay (s) | 8.2   | 0   | -   | -   | 24.3  | 11.1  |
| HCM Lane LOS          | A     | A   | -   | -   | C     | B     |
| HCM 95th %tile Q(veh) | 0.3   | -   | -   | -   | 2.5   | 0.6   |

101: US Route 4 SB On-Ramp/US Route 4 SB Off-Ramp & Pease Blvd  
2036 Build Weekend Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   | ↑↑↑   | ↗   | ↘↗  | ↑↑  |   |  |   |   | ↖   | ↗   | ↘↗  |
| Traffic Volume (vph)              | 0   | 336   | 75  | 412   | 217   | 0   | 0  | 0   | 0   | 365   | 1   | 57  |
| Future Volume (vph)               | 0   | 336   | 75  | 412   | 217   | 0   | 0  | 0   | 0   | 365   | 1   | 57  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 12  | 10  | 11  | 10  | 11  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               |   | 6.0   | 6.0   | 6.0   | 6.0   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Lane Util. Factor                 |   | 0.86  | 1.00  | 0.97  | 0.95  |   |  |   |   | 0.95  | 0.95  | 0.88  |
| Frt                               |   | 1.00  | 0.85  | 1.00  | 1.00  |   |  |   |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (prot)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1702  | 2814  |
| Flt Permitted                     |   | 1.00  | 1.00  | 0.95  | 1.00  |   |  |   |   | 0.95  | 0.95  | 1.00  |
| Satd. Flow (perm)                 |   | 6040  | 1546  | 3236  | 3455  |   |  |   |   | 1698  | 1702  | 2814  |
| Peak-hour factor, PHF             | 0.92  | 0.92  | 0.92  | 0.85  | 0.85  | 0.85  | 0.92   | 0.92  | 0.92  | 0.87  | 0.87  | 0.87  |
| Adj. Flow (vph)                   | 0   | 365   | 82  | 485   | 255   | 0   | 0  | 0   | 0   | 420   | 1   | 66  |
| RTOR Reduction (vph)              | 0   | 0   | 55  | 0   | 0   | 0   | 0  | 0   | 0   | 0   | 0   | 50  |
| Lane Group Flow (vph)             | 0   | 365   | 27  | 485   | 255   | 0   | 0  | 0   | 0   | 210   | 211   | 16  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 0%   | 0%  | 0%  | 1%  | 1%  | 1%  |
| Turn Type                         |   | NA  | Prot  | Prot  | NA  |   |  |   |   | Split   | NA  | Prot  |
| Protected Phases                  |   | 6   | 6   | 5   | 2 5   |   |  |   |   | 3   | 3   | 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             |   | 30.5  | 30.5  | 20.3  | 56.8  |   |  |   |   | 22.2  | 22.2  | 22.2  |
| Effective Green, g (s)            |   | 30.5  | 30.5  | 20.3  | 56.8  |   |  |   |   | 22.2  | 22.2  | 22.2  |
| Actuated g/C Ratio                |   | 0.34  | 0.34  | 0.22  | 0.62  |   |  |   |   | 0.24  | 0.24  | 0.24  |
| Clearance Time (s)                |   | 6.0   | 6.0   | 6.0   |   |   |  |   |   | 6.0   | 6.0   | 6.0   |
| Vehicle Extension (s)             |   | 5.0   | 5.0   | 4.0   |   |   |  |   |   | 5.0   | 5.0   | 5.0   |
| Lane Grp Cap (vph)                |   | 2024  | 518   | 721   | 2156  |   |  |   |   | 414   | 415   | 686   |
| v/s Ratio Prot                    |   | c0.06   | 0.02  | c0.15   | 0.07  |   |  |   |   | 0.12  | c0.12   | 0.01  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         |   | 0.18  | 0.05  | 0.67  | 0.12  |   |  |   |   | 0.51  | 0.51  | 0.02  |
| Uniform Delay, d1                 |   | 21.4  | 20.5  | 32.3  | 6.9   |   |  |   |   | 29.7  | 29.7  | 26.2  |
| Progression Factor                |   | 1.00  | 1.00  | 1.45  | 0.79  |   |  |   |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             |   | 0.1   | 0.1   | 2.6   | 0.1   |   |  |   |   | 2.0   | 2.0   | 0.0   |
| Delay (s)                         |   | 21.5  | 20.6  | 49.6  | 5.5   |   |  |   |   | 31.7  | 31.7  | 26.2  |
| Level of Service                  |   | C   | C   | D   | A   |   |  |   |   | C   | C   | C   |
| Approach Delay (s)                |   | 21.3  |   |   | 34.4  |   |  | 0.0   |   |   | 31.0  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | A   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 29.9  |   |   | HCM 2000 Level of Service   |  |   |   | C   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.42  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 91.0  |   |   | Sum of lost time (s)  |  |   | 18.0  |   |   |   |
| Intersection Capacity Utilization |   |   | 58.1%   |   |   | ICU Level of Service  |  |   | B   |   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |






















c Critical Lane Group

102: US Route 4 NB Off-ramp/US Route 4 NB On-Ramp & Pease Blvd/Gosling Road  
2036 Build Weekend Peak

























|                                   |    |    |  |  |    |  |    |    |    |    |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |   |   |   |   |    |   |   |   |   |   |   |   |
| Traffic Volume (vph)              | 90  | 611   | 0   | 0   | 539   | 210   | 90   | 3   | 745   | 0   | 0   | 0   |
| Future Volume (vph)               | 90  | 611   | 0   | 0   | 539   | 210   | 90   | 3   | 745   | 0   | 0   | 0   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 10  | 11  | 12  | 12  | 12  | 12  | 12   | 12  | 12  | 12  | 12  | 12  |
| Total Lost time (s)               | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Lane Util. Factor                 | 0.97  | 0.95  |   |   | 0.91  |   | 0.97   | 0.95  | 0.95  |   |   |   |
| Frt                               | 1.00  | 1.00  |   |   | 0.96  |   | 1.00   | 0.85  | 0.85  |   |   |   |
| Flt Protected                     | 0.95  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (prot)                 | 3236  | 3455  |   |   | 4920  |   | 3467   | 1521  | 1519  |   |   |   |
| Flt Permitted                     | 0.34  | 1.00  |   |   | 1.00  |   | 0.95   | 1.00  | 1.00  |   |   |   |
| Satd. Flow (perm)                 | 1164  | 3455  |   |   | 4920  |   | 3467   | 1521  | 1519  |   |   |   |
| Peak-hour factor, PHF             | 0.93  | 0.93  | 0.93  | 0.95  | 0.95  | 0.95  | 0.96   | 0.96  | 0.96  | 0.90  | 0.90  | 0.90  |
| Adj. Flow (vph)                   | 97  | 657   | 0   | 0   | 567   | 221   | 94   | 3   | 776   | 0   | 0   | 0   |
| RTOR Reduction (vph)              | 0   | 0   | 0   | 0   | 61  | 0   | 0  | 293   | 293   | 0   | 0   | 0   |
| Lane Group Flow (vph)             | 97  | 657   | 0   | 0   | 727   | 0   | 94   | 98  | 95  | 0   | 0   | 0   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%   | 1%  | 1%  | 0%  | 0%  | 0%  |
| Turn Type                         | pm+pt   | NA  |   |   | NA  |   | Split  | NA  | Prot  |   |   |   |
| Protected Phases                  | 1   | 6   |   |   | 2   |   | 3  | 3   | 3   |   |   |   |
| Permitted Phases                  | 6   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             | 43.5  | 30.5  |   |   | 37.8  |   | 22.2   | 22.2  | 22.2  |   |   |   |
| Effective Green, g (s)            | 43.5  | 30.5  |   |   | 37.8  |   | 22.2   | 22.2  | 22.2  |   |   |   |
| Actuated g/C Ratio                | 0.48  | 0.34  |   |   | 0.42  |   | 0.24   | 0.24  | 0.24  |   |   |   |
| Clearance Time (s)                | 6.0   | 6.0   |   |   | 6.0   |   | 6.0  | 6.0   | 6.0   |   |   |   |
| Vehicle Extension (s)             | 4.0   | 5.0   |   |   | 5.0   |   | 5.0  | 5.0   | 5.0   |   |   |   |
| Lane Grp Cap (vph)                | 852   | 1157  |   |   | 2043  |   | 845  | 371   | 370   |   |   |   |
| v/s Ratio Prot                    | c0.02   | c0.19   |   |   | c0.15   |   | 0.03   | c0.06   | 0.06  |   |   |   |
| v/s Ratio Perm                    | 0.04  |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         | 0.11  | 0.57  |   |   | 0.36  |   | 0.11   | 0.26  | 0.26  |   |   |   |
| Uniform Delay, d1                 | 12.8  | 24.8  |   |   | 18.2  |   | 26.7   | 27.8  | 27.7  |   |   |   |
| Progression Factor                | 1.16  | 1.08  |   |   | 1.00  |   | 1.00   | 1.00  | 1.00  |   |   |   |
| Incremental Delay, d2             | 0.1   | 1.0   |   |   | 0.2   |   | 0.1  | 0.8   | 0.8   |   |   |   |
| Delay (s)                         | 14.9  | 27.9  |   |   | 18.5  |   | 26.9   | 28.6  | 28.5  |   |   |   |
| Level of Service                  | B   | C   |   |   | B   |   | C  | C   | C   |   |   |   |
| Approach Delay (s)                |   | 26.2  |   |   | 18.5  |   |  | 28.4  |   |   | 0.0   |   |
| Approach LOS                      |   | C   |   |   | B   |   |  | C   |   |   | A   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 24.5  |   | HCM 2000 Level of Service   |   |  |   | C   |   |   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.36  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 91.0  |   | Sum of lost time (s)  |   |  |   | 18.0  |   |   |   |
| Intersection Capacity Utilization |   |   | 58.1%   |   | ICU Level of Service  |   |  |   | B   |   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |

c Critical Lane Group

103: Woodbury Avenue & Gosling Road  
2036 Build Weekend Peak























|                                   |  |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|--|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |  |
| Lane Configurations               |   |  |  |   |  |   |  |  |  |  |  |  |  |
| Traffic Volume (vph)              | 62  | 42  | 377   | 27  | 48  | 72  | 337  | 435   | 22  | 39  | 495   | 67  |  |
| Future Volume (vph)               | 62  | 42  | 377   | 27  | 48  | 72  | 337  | 435   | 22  | 39  | 495   | 67  |  |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |  |
| Lane Width                        | 11  | 11  | 14  | 12  | 12  | 16  | 12   | 12  | 12  | 11  | 11  | 11  |  |
| Total Lost time (s)               |   | 6.0   | 6.0   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   | 6.0   |  |
| Lane Util. Factor                 |   | 1.00  | 1.00  |   | 1.00  |   | 0.97   | 0.95  |   | 1.00  | 0.95  | 1.00  |  |
| Frt                               |   | 1.00  | 0.85  |   | 0.93  |   | 1.00   | 0.99  |   | 1.00  | 1.00  | 0.85  |  |
| Flt Protected                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (prot)                 |   | 1766  | 1706  |   | 1758  |   | 3467   | 3549  |   | 1728  | 3455  | 1546  |  |
| Flt Permitted                     |   | 0.97  | 1.00  |   | 0.99  |   | 0.95   | 1.00  |   | 0.95  | 1.00  | 1.00  |  |
| Satd. Flow (perm)                 |   | 1766  | 1706  |   | 1758  |   | 3467   | 3549  |   | 1728  | 3455  | 1546  |  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.85  | 0.85  | 0.85  | 0.91   | 0.91  | 0.91  | 0.88  | 0.88  | 0.88  |  |
| Adj. Flow (vph)                   | 74  | 50  | 449   | 32  | 56  | 85  | 370  | 478   | 24  | 44  | 562   | 76  |  |
| RTOR Reduction (vph)              | 0   | 0   | 336   | 0   | 29  | 0   | 0  | 2   | 0   | 0   | 0   | 44  |  |
| Lane Group Flow (vph)             | 0   | 124   | 113   | 0   | 144   | 0   | 370  | 500   | 0   | 44  | 563   | 32  |  |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 0%  | 0%  | 0%  | 1%   | 1%  | 1%  | 1%  | 1%  | 1%  |  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  |   | Prot   | NA  |   | Prot  | NA  | pt+ov   |  |
| Protected Phases                  | 3   | 3   | 3 1   | 4   | 4   |   | 1  | 6   |   | 5   | 2   | 2 3   |  |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |  |
| Actuated Green, G (s)             |   | 8.4   | 22.0  |   | 12.4  |   | 13.6   | 31.8  |   | 4.8   | 22.5  | 36.9  |  |
| Effective Green, g (s)            |   | 8.4   | 22.0  |   | 12.4  |   | 13.6   | 31.8  |   | 4.8   | 22.5  | 36.9  |  |
| Actuated g/C Ratio                |   | 0.10  | 0.25  |   | 0.14  |   | 0.16   | 0.36  |   | 0.05  | 0.26  | 0.42  |  |
| Clearance Time (s)                |   | 6.0   |   |   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |  |
| Vehicle Extension (s)             |   | 3.0   |   |   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |  |
| Lane Grp Cap (vph)                |   | 169   | 428   |   | 249   |   | 538  | 1289  |   | 94  | 888   | 651   |  |
| v/s Ratio Prot                    |   | c0.07   | 0.07  |   | c0.08   |   | c0.11  | 0.14  |   | 0.03  | c0.16   | 0.02  |  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |  |
| v/c Ratio                         |   | 0.73  | 0.26  |   | 0.58  |   | 0.69   | 0.39  |   | 0.47  | 0.63  | 0.05  |  |
| Uniform Delay, d1                 |   | 38.5  | 26.3  |   | 35.1  |   | 34.9   | 20.6  |   | 40.1  | 28.8  | 14.9  |  |
| Progression Factor                |   | 1.00  | 1.00  |   | 1.00  |   | 1.00   | 1.00  |   | 1.00  | 1.00  | 1.00  |  |
| Incremental Delay, d2             |   | 15.2  | 0.3   |   | 3.2   |   | 3.6  | 0.2   |   | 3.7   | 1.5   | 0.0   |  |
| Delay (s)                         |   | 53.6  | 26.6  |   | 38.3  |   | 38.6   | 20.8  |   | 43.8  | 30.3  | 15.0  |  |
| Level of Service                  |   | D   | C   |   | D   |   | D  | C   |   | D   | C   | B   |  |
| Approach Delay (s)                |   | 32.4  |   |   | 38.3  |   | 28.4   |   |   | 29.5  |   |   |  |
| Approach LOS                      |   | C   |   |   | D   |   | C  |   |   | C   |   |   |  |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |  |
| HCM 2000 Control Delay            |   |   | 30.5  |   | HCM 2000 Level of Service   |   |  |   |   |   | C   |   |  |
| HCM 2000 Volume to Capacity ratio |   |   | 0.60  |   |   |   |  |   |   |   |   |   |  |
| Actuated Cycle Length (s)         |   |   | 87.5  |   | Sum of lost time (s)  |   |  |   |   | 25.5  |   |   |  |
| Intersection Capacity Utilization |   |   | 60.0%   |   | ICU Level of Service  |   |  |   |   | B   |   |   |  |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |  |
| c Critical Lane Group             |   |   |   |   |   |   |  |   |   |   |   |   |  |

104: Woodbury Avenue & Durgin Lane/BJ's Driveway  
2036 Build Weekend Peak

|                                   |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL  | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |  |  |  |  |  |  |  |  |  |  |  |  |
| Traffic Volume (vph)              | 142   | 25  | 141   | 135   | 12  | 66  | 53   | 644   | 120   | 90  | 847   | 180   |
| Future Volume (vph)               | 142   | 25  | 141   | 135   | 12  | 66  | 53   | 644   | 120   | 90  | 847   | 180   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900   | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 11  | 11  | 11  | 11  | 11   | 11  | 16  | 11  | 11  | 11  |
| Grade (%)                         |   | 3%  |   |   | -5%   |   |  | 5%  |   |   | -3%   |   |
| Total Lost time (s)               | 6.0   | 6.0   | 6.0   | 5.5   | 5.5   | 5.5   | 6.0  | 6.0   | 5.5   | 5.5   | 6.0   | 6.0   |
| Lane Util. Factor                 | 0.95  | 0.95  | 1.00  | 0.95  | 0.95  | 1.00  | 1.00   | 0.95  | 1.00  | 1.00  | 0.95  | 1.00  |
| Frpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Flpb, ped/bikes                   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Frt                               | 1.00  | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  | 1.00   | 1.00  | 0.85  | 1.00  | 1.00  | 0.85  |
| Flt Protected                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95   | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 | 1633  | 1660  | 1538  | 1699  | 1716  | 1600  | 1684   | 3369  | 1767  | 1753  | 3507  | 1569  |
| Flt Permitted                     | 0.95  | 0.97  | 1.00  | 0.95  | 0.96  | 1.00  | 0.95   | 1.00  | 1.00  | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 | 1633  | 1660  | 1538  | 1699  | 1716  | 1600  | 1684   | 3369  | 1767  | 1753  | 3507  | 1569  |
| Peak-hour factor, PHF             | 0.84  | 0.84  | 0.84  | 0.91  | 0.91  | 0.91  | 0.89   | 0.89  | 0.89  | 0.92  | 0.92  | 0.92  |
| Adj. Flow (vph)                   | 169   | 30  | 168   | 148   | 13  | 73  | 60   | 724   | 135   | 98  | 921   | 196   |
| RTOR Reduction (vph)              | 0   | 0   | 135   | 0   | 0   | 0   | 0  | 0   | 77  | 0   | 0   | 40  |
| Lane Group Flow (vph)             | 98  | 101   | 33  | 80  | 81  | 73  | 60   | 724   | 58  | 98  | 921   | 156   |
| Confl. Bikes (#/hr)               |   |   |   |   |   |   |  |   | 1   |   |   |   |
| Heavy Vehicles (%)                | 0%  | 0%  | 0%  | 0%  | 0%  | 0%  | 1%   | 1%  | 1%  | 1%  | 1%  | 1%  |
| Turn Type                         | Split   | NA  | pt+ov   | Split   | NA  | pt+ov   | Prot   | NA  | pt+ov   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   | 1 3   | 4   | 4   | 4 5   | 1  | 6   | 4 6   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |  |   |   |   |   |   |
| Actuated Green, G (s)             | 8.1   | 8.1   | 14.1  | 8.1   | 8.1   | 23.2  | 6.0  | 22.5  | 30.6  | 9.6   | 25.6  | 39.7  |
| Effective Green, g (s)            | 8.1   | 8.1   | 14.1  | 8.1   | 8.1   | 23.2  | 6.0  | 22.5  | 30.6  | 9.6   | 25.6  | 39.7  |
| Actuated g/C Ratio                | 0.11  | 0.11  | 0.20  | 0.11  | 0.11  | 0.33  | 0.08   | 0.32  | 0.43  | 0.13  | 0.36  | 0.56  |
| Clearance Time (s)                | 6.0   | 6.0   |   | 5.5   | 5.5   |   | 6.0  | 6.0   |   | 5.5   | 6.0   |   |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0  | 3.0   |   | 3.0   | 3.0   |   |
| Lane Grp Cap (vph)                | 185   | 188   | 304   | 193   | 194   | 520   | 141  | 1063  | 758   | 236   | 1259  | 873   |
| v/s Ratio Prot                    | 0.06  | c0.06   | 0.02  | 0.05  | c0.05   | 0.05  | 0.04   | 0.21  | 0.03  | c0.06   | c0.26   | 0.10  |
| v/s Ratio Perm                    |   |   |   |   |   |   |  |   |   |   |   |   |
| v/c Ratio                         | 0.53  | 0.54  | 0.11  | 0.41  | 0.42  | 0.14  | 0.43   | 0.68  | 0.08  | 0.42  | 0.73  | 0.18  |
| Uniform Delay, d1                 | 29.8  | 29.8  | 23.5  | 29.4  | 29.4  | 17.0  | 31.0   | 21.3  | 12.0  | 28.3  | 19.9  | 7.8   |
| Progression Factor                | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  | 1.00   | 1.00  | 1.00  | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             | 2.7   | 2.9   | 0.2   | 1.4   | 1.5   | 0.1   | 2.1  | 1.8   | 0.0   | 1.2   | 2.2   | 0.1   |
| Delay (s)                         | 32.5  | 32.8  | 23.6  | 30.8  | 30.9  | 17.1  | 33.1   | 23.1  | 12.1  | 29.5  | 22.1  | 7.9   |
| Level of Service                  | C   | C   | C   | C   | C   | B   | C  | C   | B   | C   | C   | A   |
| Approach Delay (s)                |   | 28.5  |   |   | 26.6  |   |  | 22.1  |   |   | 20.4  |   |
| Approach LOS                      |   | C   |   |   | C   |   |  | C   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |  |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 22.6  |   |   |   | HCM 2000 Level of Service  |   |   |   | C   |   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.66  |   |   |   |  |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 71.3  |   |   | Sum of lost time (s)  |  |   |   | 25.5  |   |   |
| Intersection Capacity Utilization |   |   | 54.7%   |   |   | ICU Level of Service  |  |   |   | A   |   |   |
| Analysis Period (min)             |   |   | 15  |   |   |   |  |   |   |   |   |   |


c Critical Lane Group

105: Market Street & Woodbury Avenue & Market Basket Driveway  
 2036 Build Weekend Peak

|                                   |  |  |  |  |  |  |   |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement                          | EBL   | EBT   | EBR   | WBL   | WBT   | WBR   | NBL   | NBT   | NBR   | SBL   | SBT   | SBR   |
| Lane Configurations               |  |  |   |  |  |   |  |  |  |  |  |  |
| Traffic Volume (vph)              | 281   | 75  | 55  | 157   | 82  | 24  | 67  | 532   | 142   | 13  | 629   | 464   |
| Future Volume (vph)               | 281   | 75  | 55  | 157   | 82  | 24  | 67  | 532   | 142   | 13  | 629   | 464   |
| Ideal Flow (vphpl)                | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  | 1900  |
| Lane Width                        | 11  | 11  | 11  | 14  | 14  | 14  | 11  | 11  | 11  | 11  | 11  | 11  |
| Grade (%)                         |   | 5%  |   |   | -5%   |   |   | 0%  |   |   | 0%  |   |
| Total Lost time (s)               | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   | 6.5   |
| Lane Util. Factor                 | 0.97  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 0.95  |   | 1.00  | 0.95  | 1.00  |
| Frt                               | 1.00  | 0.94  |   | 1.00  | 0.97  |   | 1.00  | 0.97  |   | 1.00  | 1.00  | 0.85  |
| Flt Protected                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (prot)                 | 3268  | 1661  |   | 1954  | 1986  |   | 1728  | 3346  |   | 1728  | 3455  | 1546  |
| Flt Permitted                     | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  |   | 0.95  | 1.00  | 1.00  |
| Satd. Flow (perm)                 | 3268  | 1661  |   | 1954  | 1986  |   | 1728  | 3346  |   | 1728  | 3455  | 1546  |
| Peak-hour factor, PHF             | 0.77  | 0.77  | 0.77  | 0.78  | 0.78  | 0.78  | 0.92  | 0.92  | 0.92  | 0.97  | 0.97  | 0.97  |
| Adj. Flow (vph)                   | 365   | 97  | 71  | 201   | 105   | 31  | 73  | 578   | 154   | 13  | 648   | 478   |
| RTOR Reduction (vph)              | 0   | 21  | 0   | 0   | 8   | 0   | 0   | 17  | 0   | 0   | 0   | 230   |
| Lane Group Flow (vph)             | 365   | 147   | 0   | 201   | 128   | 0   | 73  | 715   | 0   | 13  | 648   | 248   |
| Heavy Vehicles (%)                | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  | 1%  |
| Turn Type                         | Split   | NA  |   | Split   | NA  |   | Prot  | NA  |   | Prot  | NA  | pt+ov   |
| Protected Phases                  | 3   | 3   |   | 4   | 4   |   | 1   | 6   |   | 5   | 2   | 2 3   |
| Permitted Phases                  |   |   |   |   |   |   |   |   |   |   |   |   |
| Actuated Green, G (s)             | 11.4  | 11.4  |   | 13.9  | 13.9  |   | 7.2   | 31.9  |   | 1.3   | 26.0  | 43.9  |
| Effective Green, g (s)            | 11.4  | 11.4  |   | 13.9  | 13.9  |   | 7.2   | 31.9  |   | 1.3   | 26.0  | 43.9  |
| Actuated g/C Ratio                | 0.13  | 0.13  |   | 0.16  | 0.16  |   | 0.09  | 0.38  |   | 0.02  | 0.31  | 0.52  |
| Clearance Time (s)                | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   |   | 6.5   | 6.5   | 6.5   |
| Vehicle Extension (s)             | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   |   | 3.0   | 3.0   | 3.0   |
| Lane Grp Cap (vph)                | 440   | 224   |   | 321   | 326   |   | 147   | 1263  |   | 26  | 1063  | 803   |
| v/s Ratio Prot                    | c0.11   | 0.09  |   | c0.10   | 0.06  |   | c0.04   | c0.21   |   | 0.01  | 0.19  | 0.16  |
| v/s Ratio Perm                    |   |   |   |   |   |   |   |   |   |   |   |   |
| v/c Ratio                         | 0.83  | 0.66  |   | 0.63  | 0.39  |   | 0.50  | 0.57  |   | 0.50  | 0.61  | 0.31  |
| Uniform Delay, d1                 | 35.6  | 34.7  |   | 32.9  | 31.5  |   | 36.9  | 20.8  |   | 41.3  | 24.9  | 11.6  |
| Progression Factor                | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  |   | 1.00  | 1.00  | 1.00  |
| Incremental Delay, d2             | 12.2  | 6.8   |   | 3.8   | 0.8   |   | 2.6   | 0.6   |   | 14.3  | 1.0   | 0.2   |
| Delay (s)                         | 47.8  | 41.5  |   | 36.7  | 32.3  |   | 39.5  | 21.4  |   | 55.6  | 25.9  | 11.8  |
| Level of Service                  | D   | D   |   | D   | C   |   | D   | C   |   | E   | C   | B   |
| Approach Delay (s)                |   | 45.8  |   |   | 34.9  |   |   | 23.1  |   |   | 20.4  |   |
| Approach LOS                      |   | D   |   |   | C   |   |   | C   |   |   | C   |   |
| <b>Intersection Summary</b>       |   |   |   |   |   |   |   |   |   |   |   |   |
| HCM 2000 Control Delay            |   |   | 27.7  |   |   |   |   |   |   |   |   | HCM 2000 Level of Service C   |
| HCM 2000 Volume to Capacity ratio |   |   | 0.69  |   |   |   |   |   |   |   |   |   |
| Actuated Cycle Length (s)         |   |   | 84.5  |   |   |   |   |   |   |   | 28.0  | Sum of lost time (s)  |
| Intersection Capacity Utilization |   |   | 61.9%   |   |   |   |   |   |   |   |   | ICU Level of Service B  |
| Analysis Period (min)             |   |   | 15  |   |   |   |   |   |   |   |   |   |
| c Critical Lane Group             |   |   |   |   |   |   |   |   |   |   |   |   |



201: Motel 6/North Site & Gosling Road  
2036 Build Weekend Peak



| Movement                          | EBT         | EBR         | WBL         | WBT         | NBL                  | NBR         |             |
|-----------------------------------|-------------|-------------|-------------|-------------|----------------------|-------------|-------------|
| Lane Configurations               | ↑↑↑↑        |             |             | ↑↑          |                      | ↗           |             |
| Traffic Volume (veh/h)            | 1251        | 105         | 0           | 749         | 0                    | 58          |             |
| Future Volume (Veh/h)             | 1251        | 105         | 0           | 749         | 0                    | 58          |             |
| Sign Control                      | Free        |             |             | Free        | Stop                 |             |             |
| Grade                             | 0%          |             |             | 0%          | 0%                   |             |             |
| Peak Hour Factor                  | 0.93        | 0.93        | 0.95        | 0.95        | 0.55                 | 0.55        |             |
| Hourly flow rate (vph)            | 1345        | 113         | 0           | 788         | 0                    | 105         |             |
| <b>Pedestrians</b>                |             |             |             |             |                      |             |             |
| Lane Width (ft)                   |             |             |             |             |                      |             |             |
| Walking Speed (ft/s)              |             |             |             |             |                      |             |             |
| Percent Blockage                  |             |             |             |             |                      |             |             |
| Right turn flare (veh)            |             |             |             |             |                      |             |             |
| Median type                       | None        |             |             | None        |                      |             |             |
| Median storage (veh)              |             |             |             |             |                      |             |             |
| Upstream signal (ft)              | 464         |             |             |             |                      |             |             |
| pX, platoon unblocked             |             |             |             |             |                      |             |             |
| vC, conflicting volume            |             |             | 1458        |             | 1796                 | 393         |             |
| vC1, stage 1 conf vol             |             |             |             |             |                      |             |             |
| vC2, stage 2 conf vol             |             |             |             |             |                      |             |             |
| vCu, unblocked vol                |             |             | 1458        |             | 1796                 | 393         |             |
| tC, single (s)                    |             |             | 4.1         |             | 6.8                  | 6.9         |             |
| tC, 2 stage (s)                   |             |             |             |             |                      |             |             |
| tF (s)                            |             |             | 2.2         |             | 3.5                  | 3.3         |             |
| p0 queue free %                   |             |             | 100         |             | 100                  | 83          |             |
| cM capacity (veh/h)               |             |             | 465         |             | 73                   | 612         |             |
| <b>Direction, Lane #</b>          | <b>EB 1</b> | <b>EB 2</b> | <b>EB 3</b> | <b>EB 4</b> | <b>WB 1</b>          | <b>WB 2</b> | <b>NB 1</b> |
| Volume Total                      | 384         | 384         | 384         | 305         | 394                  | 394         | 105         |
| Volume Left                       | 0           | 0           | 0           | 0           | 0                    | 0           | 0           |
| Volume Right                      | 0           | 0           | 0           | 113         | 0                    | 0           | 105         |
| cSH                               | 1700        | 1700        | 1700        | 1700        | 1700                 | 1700        | 612         |
| Volume to Capacity                | 0.23        | 0.23        | 0.23        | 0.18        | 0.23                 | 0.23        | 0.17        |
| Queue Length 95th (ft)            | 0           | 0           | 0           | 0           | 0                    | 0           | 15          |
| Control Delay (s)                 | 0.0         | 0.0         | 0.0         | 0.0         | 0.0                  | 0.0         | 12.1        |
| Lane LOS                          |             |             |             |             |                      |             | B           |
| Approach Delay (s)                | 0.0         |             |             |             | 0.0                  |             | 12.1        |
| Approach LOS                      |             |             |             |             |                      |             | B           |
| <b>Intersection Summary</b>       |             |             |             |             |                      |             |             |
| Average Delay                     |             |             | 0.5         |             |                      |             |             |
| Intersection Capacity Utilization |             |             | 30.1%       |             | ICU Level of Service |             | A           |
| Analysis Period (min)             |             |             | 15          |             |                      |             |             |

202: Arthur F Brady Drive & South Site Driveway  
2036 Build Weekend Peak

| Intersection             |      |      |      |       |      |      |
|--------------------------|------|------|------|-------|------|------|
| Int Delay, s/veh         | 6.9  |      |      |       |      |      |
| Movement                 | EBL  | EBT  | WBT  | WBR   | SBL  | SBR  |
| Lane Configurations      |      | ↕    | ↕    | ↕     | ↕    | ↕    |
| Traffic Vol, veh/h       | 130  | 225  | 135  | 90    | 165  | 68   |
| Future Vol, veh/h        | 130  | 225  | 135  | 90    | 165  | 68   |
| Conflicting Peds, #/hr   | 1    | 0    | 0    | 1     | 0    | 1    |
| Sign Control             | Free | Free | Free | Free  | Stop | Stop |
| RT Channelized           | -    | None | -    | Yield | -    | None |
| Storage Length           | -    | -    | -    | 60    | 200  | 0    |
| Veh in Median Storage, # | -    | 0    | 0    | -     | 0    | -    |
| Grade, %                 | -    | 0    | 0    | -     | 0    | -    |
| Peak Hour Factor         | 95   | 95   | 81   | 81    | 88   | 88   |
| Heavy Vehicles, %        | 1    | 1    | 2    | 2     | 0    | 0    |
| Mvmt Flow                | 137  | 237  | 167  | 111   | 188  | 77   |

| Major/Minor          | Major1 | Major2 | Minor2 |   |     |
|----------------------|--------|--------|--------|---|-----|
| Conflicting Flow All | 168    | 0      | -      | 0 | 679 |
| Stage 1              | -      | -      | -      | - | 168 |
| Stage 2              | -      | -      | -      | - | 511 |
| Critical Hdwy        | 4.11   | -      | -      | - | 6.4 |
| Critical Hdwy Stg 1  | -      | -      | -      | - | 5.4 |
| Critical Hdwy Stg 2  | -      | -      | -      | - | 5.4 |
| Follow-up Hdwy       | 2.209  | -      | -      | - | 3.5 |
| Pot Cap-1 Maneuver   | 1416   | -      | -      | - | 420 |
| Stage 1              | -      | -      | -      | - | 867 |
| Stage 2              | -      | -      | -      | - | 606 |
| Platoon blocked, %   |        | -      | -      | - |     |
| Mov Cap-1 Maneuver   | 1415   | -      | -      | - | 373 |
| Mov Cap-2 Maneuver   | -      | -      | -      | - | 373 |
| Stage 1              | -      | -      | -      | - | 770 |
| Stage 2              | -      | -      | -      | - | 605 |


| Approach             | EB  | WB | SB   |
|----------------------|-----|----|------|
| HCM Control Delay, s | 2.9 | 0  | 19.8 |
| HCM LOS              |     |    | C    |

| Minor Lane/Major Mvmt | EBL   | EBT | WBT | WBR | SBLn1 | SBLn2 |
|-----------------------|-------|-----|-----|-----|-------|-------|
| Capacity (veh/h)      | 1415  | -   | -   | -   | 373   | 878   |
| HCM Lane V/C Ratio    | 0.097 | -   | -   | -   | 0.503 | 0.088 |
| HCM Control Delay (s) | 7.8   | 0   | -   | -   | 24    | 9.5   |
| HCM Lane LOS          | A     | A   | -   | -   | C     | A     |
| HCM 95th %tile Q(veh) | 0.3   | -   | -   | -   | 2.7   | 0.3   |

**APPENDIX F**  
COAST & Wildcat Transit Bus Schedule & Map

# 43

## Route 43 Map Portsmouth · Newington



## Ride Information

### COAST BUS FARES

**Base Cash Fare** **\$1.50**  
All passengers ages 5 and up are required to pay this fare each time they board a COAST bus.

**Half-Fare** **\$ 0.75**  
Passengers 65 and older, or passengers with a disability are entitled to pay half the cash fare. Proof of eligibility is required by showing a Medicare card, photo ID with birth date, COAST ADA Paratransit Card, or COAST Half-Fare Card. Please contact COAST to apply for a Half-Fare Card.

**Multi-Ride Tickets and Passes**  
Available at [www.coastbus.org](http://www.coastbus.org) or call 603-743-5777, TTY 711.

**Unlimited Monthly Pass** **\$ 52**  
Unlimited rides on COAST Routes for the month.

### YOUR RIGHTS

COAST adheres to all Federal regulations regarding Civil Rights. If you need to request an ADA Reasonable Modification/ Accommodation, or if you believe you have been discriminated against or would like to file a complaint under the ADA or Title VI, please contact COAST's Civil Rights Officer at 603-516-0788, TTY 711 or email [CivilRights@coastbus.org](mailto:CivilRights@coastbus.org).

### NO SERVICE DAYS

COAST does not operate on the following holidays:

- New Year's Day
- Labor Day
- Martin Luther King Jr./ Civil Rights Day
- Thanksgiving Day
- Memorial Day
- Christmas Eve Day
- Independence Day
- Christmas Day



42 Sumner Drive · Dover, NH 03820  
603-743-5777 · TTY 711 · [www.coastbus.org](http://www.coastbus.org)  
This brochure is available in alternative formats upon request.

## Bus Schedule & Map 43



Effective  
09.17.22

# ROUTE 43

Portsmouth · Newington



Find all of the full COAST schedules online at [coastbus.org](http://coastbus.org)

## MAP OUT YOUR GAME PLAN

Planning your trip has never been easier!

[www.coastbus.org](http://www.coastbus.org)



# COAST SYSTEM MAP



## EXPRESS • INBOUND • OUTBOUND Route 43 Portsmouth • Newington

### How to Read the Schedule

Printed bus schedules only show the timepoints ● (major bus stops where the bus will hold until the scheduled departure time). In between those timepoints are many other stops that you can use. For a full listing of bus stops, visit [www.coastbus.org](http://www.coastbus.org), or use the Passio GO! App.

The times shown represent the number of minutes after the hour that the bus will depart from that stop. Last stop times are arrivals. Any exceptions will be noted.

| EXPRESS (M-Sat)               | Single Run Only |                   |          |
|-------------------------------|-----------------|-------------------|----------|
| DOVER - NEWINGTON             | First Bus       | Minutes Past Hour | Last Bus |
| ● Dover Transportation Center | 6:30am          | --                | --       |
| ● Fox Run Mall                | 6:45am          | --                | --       |

| INBOUND (M-Sat)                  | Service On Every Hour |                   |          |
|----------------------------------|-----------------------|-------------------|----------|
| NEWINGTON - PORTSMOUTH           | First Bus             | Minutes Past Hour | Last Bus |
| ● Fox Run Mall                   | 6:30am                | :30               | 8:30pm   |
| ● Commerce Way (Marshalls Plaza) | 6:36am                | :36               | 8:36pm   |
| ● Hanover Station                | 6:57am                | :57               | 8:57pm   |

| OUTBOUND (M-Sat)                 | Service On Every Hour |                   |          |
|----------------------------------|-----------------------|-------------------|----------|
| PORTSMOUTH - NEWINGTON           | First Bus             | Minutes Past Hour | Last Bus |
| ● Hanover Station                | 7:00am                | :00               | 8:00pm   |
| ● Commerce Way (Marshalls Plaza) | 7:09am                | :09               | 8:09pm   |
| ● Fox Run Mall                   | 7:22am                | :22               | 8:22pm   |




### MAP IT!



For a full listing of bus stops, visit [www.coastbus.org](http://www.coastbus.org) or use the Passio GO! App.



Travel Direction



# Wildcat Transit - Portsmouth Route 4



Downtown Portsmouth



**Legend**

- Wildcat Transit Route 4
- Wildcat Transit Route 4 Express
- COAST Route to Portsmouth & Rochester
- Bus Stop
- Intermodal Transit Station

0.25 0 0.25 Miles

# Route 4A Weekday UNH/Durham to Malls & Portsmouth Market Square

# Portsmouth 4A Monday - Friday

| Stop ID # & Location                               | AM Express  |                | AM Express             |                |                        |                |                 |
|--|---|----------------|------------------------|----------------|------------------------|----------------|-----------------|
|  | Run 1   | Run 2          | Run 3                  | Run 4          | Run 5                  | Run 6          | Run 7           |
| <b>Outbound</b>                                    |   |                |                        |                |                        |                |                 |
| 101 DEPART UNH McCONNELL HALL                      | 6:40 AM   | 7:45 AM        | 12:05 PM               | 2:05 PM        | 6:05 PM                | 7:05 PM        | 9:35 PM         |
| 102 DEPART UNH KINGSBURY HALL                      | 6:42 AM   | 7:47 AM        | 12:07 PM               | 2:07 PM        | 6:07 PM                | 7:07 PM        | 9:37 PM         |
| 103 DEPART UNH HEWITT HALL                         | 6:42 AM   | 7:47 AM        | 12:07 PM               | 2:07 PM        | 6:07 PM                | 7:07 PM        | 9:37 PM         |
| 104 DEPART MAIN STREET @ UNH THOMPSON HALL         | 6:45 AM   | 7:50 AM        | 12:10 PM               | 2:10 PM        | 6:10 PM                | 7:10 PM        | 9:40 PM         |
| 106 DEPART MAIN STREET @ UNH HETZEL HALL           | 6:47 AM   | 7:52 AM        | 12:12 PM               | 2:12 PM        | 6:12 PM                | 7:12 PM        | 9:42 PM         |
| 107 Rte 108 @ Old Landing Rd                       | 6:49 AM   | 7:54 AM        | 12:14 PM               | 2:14 PM        | 6:14 PM                | 7:14 PM        | 9:44 PM         |
| 109 Rte 108 @ Old Piscataqua Rd                    | 6:49 AM   | 7:54 AM        | 12:14 PM               | 2:14 PM        | 6:14 PM                | 7:14 PM        | 9:44 PM         |
| 121 Rte 4 @ 68 Piscataqua Rd                       | <b>Depending on traffic, stops on Route 4 may not be serviced outbound before 9 am. Please call 603-862-2328 for daily information.</b> |                | 12:15 PM               | 2:15 PM        | 6:15 PM                | 7:15 PM        | 9:45 PM         |
| 122 Rte 4 @ Riverview Rd                           |   |                | 12:16 PM               | 2:16 PM        | 6:16 PM                | 7:16 PM        | 9:46 PM         |
| 192 Rte 4 @ 116 Piscataqua Rd                      |   |                | 12:16 PM               | 2:16 PM        | 6:16 PM                | 7:16 PM        | 9:46 PM         |
| 123 Rte 4 @ Wagon Hill Farm                        |   |                | 12:17 PM               | 2:17 PM        | 6:17 PM                | 7:17 PM        | 9:47 PM         |
| 124 Rte 4 @ Cedar Point Rd                         |   |                | 12:18 PM               | 2:18 PM        | 6:18 PM                | 7:18 PM        | 9:48 PM         |
| 201 Boston Harbor Road @ DMV                       | <b>On Request Only</b>  |                | <b>On Request Only</b> |                | <b>On Request Only</b> |                |                 |
| 604 Newington Wal-Mart                             | <b>Not Serviced on These Runs</b>   |                | 12:26 PM               | 2:26 PM        | 6:26 PM                | 7:26 PM        | 9:56 PM         |
| 603 Fox Run Mall (to Portsmouth)                   | <b>Not Serviced on These Runs</b>   |                | 12:28 PM               | 2:28 PM        | 6:28 PM                | 7:28 PM        | 9:58 PM         |
| 601 Crossings at Fox Run @ Cold Stone Creamery     | <b>Not Serviced on These Runs</b>   |                | 12:31 PM               | 2:31 PM        | 6:31 PM                | 7:31 PM        | 10:01 PM        |
| 302 Gosling Rd @ Gosling Meadows                   | <b>Not Serviced on These Runs</b>   |                | 12:33 PM               | 2:33 PM        | 6:33 PM                | 7:33 PM        | 10:03 PM        |
| 314 1840 Woodbury Ave                              | 7:01 AM   | 8:06 AM        | 12:34 PM               | 2:34 PM        | 6:34 PM                | 7:34 PM        | 10:04 PM        |
| 312 Marshall's Plaza @ Commerce Way                | 7:03 AM   | 8:08 AM        | 12:37 PM               | 2:37 PM        | 6:37 PM                | 7:37 PM        | 10:07 PM        |
| 336 170 Commerce Way                               | 7:04 AM   | 8:09 AM        | 12:38 PM               | 2:38 PM        | 6:38 PM                | 7:38 PM        | 10:08 PM        |
| 338 Commerce Way / Portsmouth Blvd                 | 7:05 AM   | 8:10 AM        | 12:38 PM               | 2:38 PM        | 6:38 PM                | 7:38 PM        | 10:08 PM        |
| 316 Maplewood Ave @ Fairview Drive                 | 7:08 AM   | 8:13 AM        | 12:42 PM               | 2:42 PM        | 6:42 PM                | 7:42 PM        | 10:10 PM        |
| 317 Maplewood Ave @ I-95 Overpass                  | 7:10 AM   | 8:15 AM        | 12:44 PM               | 2:44 PM        | 6:44 PM                | 7:44 PM        | 10:12 PM        |
| 318 Maplewood Ave @ Dearborn Street                | 7:11 AM   | 8:16 AM        | 12:45 PM               | 2:45 PM        | 6:45 PM                | 7:45 PM        | 10:13 PM        |
| 319 Maplewood Ave @ North Cemetery                 | 7:12 AM   | 8:17 AM        | 12:46 PM               | 2:46 PM        | 6:46 PM                | 7:46 PM        | 10:14 PM        |
| 303 Hanover Street @ High-Hanover Parking Facility | 7:14 AM   | 8:19 AM        | 12:48 PM               | 2:48 PM        | 6:48 PM                | 7:48 PM        | 10:16 PM        |
| <b>311 Arrive Market Square</b>                    | <b>7:16 AM</b>  | <b>8:21 AM</b> | <b>12:50 PM</b>        | <b>2:50 PM</b> | <b>6:50 PM</b>         | <b>7:50 PM</b> | <b>10:18 PM</b> |
| <b>Inbound</b>                                     |   |                |                        |                |                        |                |                 |
| <b>311 Depart Market Square</b>                    | <b>7:16 AM</b>  | <b>8:21 AM</b> | <b>12:50 PM</b>        | <b>2:50 PM</b> | <b>6:50 PM</b>         | <b>7:50 PM</b> | <b>10:18 PM</b> |
| 310 Islington Street @ Tanner Street               | 7:18 AM   | 8:23 AM        | 12:51 PM               | 2:51 PM        | 6:51 PM                | 7:51 PM        | 10:19 PM        |
| 308 Islington Street @ Cornwall Street             | 7:19 AM   | 8:24 AM        | 12:52 PM               | 2:52 PM        | 6:52 PM                | 7:52 PM        | 10:20 PM        |
| 307 Islington Street @ Dunkin Donuts               | 7:20 AM   | 8:25 AM        | 12:54 PM               | 2:54 PM        | 6:54 PM                | 7:54 PM        | 10:22 PM        |
| 305 Plaza 800                                      | 7:22 AM   | 8:27 AM        | 12:55 PM               | 2:55 PM        | 6:55 PM                | 7:55 PM        | 10:23 PM        |
| 320 Bartlett Street @ Meredith Way                 | 7:25 AM   | 8:30 AM        | 12:58 PM               | 2:58 PM        | 6:58 PM                | 7:58 PM        | 10:26 PM        |
| 321 Dennett Street @ Woodbury Ave                  | 7:26 AM   | 8:31 AM        | 12:59 PM               | 2:59 PM        | 6:59 PM                | 7:59 PM        | 10:27 PM        |
| 201 Boston Harbor Road @ DMV                       | <b>On Request Only</b>  |                | <b>On Request Only</b> |                | <b>On Request Only</b> |                |                 |
| 125 Rte 4 @ Scammel Bridge (West Side)             | 7:35 AM   | 8:40 AM        | 1:09 PM                | 3:09 PM        | 7:09 PM                | 8:09 PM        | 10:36 PM        |
| 126 Rte 4 @ Emery Farm                             | 7:37 AM   | 8:42 AM        | 1:10 PM                | 3:10 PM        | 7:10 PM                | 8:10 PM        | 10:38 PM        |
| 193 Rte 4 @ Morgan Way                             | 7:37 AM   | 8:42 AM        | 1:11 PM                | 3:11 PM        | 7:11 PM                | 8:11 PM        | 10:38 PM        |
| 127 Rte 4 @ Shearwater Street                      | 7:38 AM   | 8:43 AM        | 1:11 PM                | 3:11 PM        | 7:11 PM                | 8:11 PM        | 10:39 PM        |
| 120 Rte 4 @ 65 Piscataqua Rd                       | 7:38 AM   | 8:43 AM        | 1:11 PM                | 3:11 PM        | 7:11 PM                | 8:11 PM        | 10:39 PM        |
| 119 Rte 108 @ The Pines Inn (#47)                  | 7:41 AM   | 8:46 AM        | 1:14 PM                | 3:14 PM        | 7:14 PM                | 8:14 PM        | 10:42 PM        |
| 108 Rte 108 @ Young Drive                          | 7:41 AM   | 8:46 AM        | 1:15 PM                | 3:15 PM        | 7:15 PM                | 8:15 PM        | 10:42 PM        |
| 117 Madbury Road @ Woodman Rd                      | 7:44 AM   | 8:49 AM        | 1:18 PM                | 3:17 PM        | 7:17 PM                | 8:17 PM        | 10:44 PM        |
| <b>116 ARRIVE Garrison Ave @ Sawyer Hall</b>       | <b>7:45 AM</b>  | <b>8:50 AM</b> | <b>1:19 PM</b>         | <b>3:19 PM</b> | <b>7:19 PM</b>         | <b>8:19 PM</b> | <b>10:46 PM</b> |
| <b>105 ARRIVE Holloway Commons Main Street</b>     | <b>7:47 AM</b>  | <b>8:52 AM</b> | <b>1:21 PM</b>         | <b>3:20 PM</b> | <b>7:20 PM</b>         | <b>8:20 PM</b> | <b>10:47 PM</b> |
| <b>1001 ARRIVE UNH McConnell Hall</b>              | <b>7:49 AM</b>  | <b>8:54 AM</b> | <b>1:23 PM</b>         | <b>3:22 PM</b> | <b>7:22 PM</b>         | <b>8:22 PM</b> | <b>10:49 PM</b> |

These times are approximate. Please be at the bus stop 5 minutes before the scheduled time.

**Route 4A WEEKEND Portsmouth 4A**  
**UNH/Durham to Malls & Portsmouth Market Square Saturday - Sunday**

| <b>Stop ID # &amp; Location</b>                    |                        |              |              |
|--|------------------------|--------------|--------------|
| <b>Outbound</b>                                    | <b>Run 1</b>           | <b>Run 2</b> | <b>Run 3</b> |
| 101 DEPART UNH McCONNELL HALL                      | 11:35 AM               | 2:35 PM      | 7:05 PM      |
| 102 DEPART UNH KINGSBURY HALL                      | 11:37 AM               | 2:37 PM      | 7:07 PM      |
| 103 DEPART UNH HEWITT HALL                         | 11:37 AM               | 2:37 PM      | 7:07 PM      |
| 104 DEPART MAIN STREET @ UNH THOMPSON HALL         | 11:40 AM               | 2:40 PM      | 7:10 PM      |
| 106 DEPART MAIN STREET @ UNH HETZEL HALL           | 11:42 AM               | 2:42 PM      | 7:12 PM      |
| 107 Rte 108 @ Old Landing Rd                       | 11:44 AM               | 2:44 PM      | 7:14 PM      |
| 109 Rte 108 @ Old Piscataqua Rd                    | 11:44 AM               | 2:44 PM      | 7:14 PM      |
| 121 Rte 4 @ 68 Piscataqua Rd                       | 11:45 AM               | 2:45 PM      | 7:15 PM      |
| 122 Rte 4 @ Riverview Rd                           | 11:46 AM               | 2:46 PM      | 7:16 PM      |
| 192 Rte 4 @ 116 Piscataqua Rd                      | 11:46 AM               | 2:46 PM      | 7:16 PM      |
| 123 Rte 4 @ Wagon Hill Farm                        | 11:47 AM               | 2:47 PM      | 7:17 PM      |
| 124 Rte 4 @ Cedar Point Rd                         | 11:48 AM               | 2:48 PM      | 7:18 PM      |
| 201 Boston Harbor Road @ DMV                       | <b>On Request Only</b> |              |              |
| 604 Newington Wal-Mart                             | 11:56 AM               | 2:56 PM      | 7:26 PM      |
| 603 Fox Run Mall (to Portsmouth)                   | 11:58 AM               | 2:58 PM      | 7:28 PM      |
| 601 Crossings at Fox Run @ Cold Stone Creamery     | 12:01 PM               | 3:01 PM      | 7:30 PM      |
| 302 Gosling Rd @ Gosling Meadows                   | 12:03 PM               | 3:03 PM      | 7:32 PM      |
| 314 1840 Woodbury Ave                              | 12:04 PM               | 3:04 PM      | 7:33 PM      |
| 312 Marshall's Plaza @ Commerce Way                | 12:07 PM               | 3:07 PM      | 7:36 PM      |
| 336 170 Commerce Way                               | 12:08 PM               | 3:08 PM      | 7:37 PM      |
| 338 Commerce Way / Portsmouth Blvd                 | 12:08 PM               | 3:08 PM      | 7:37 PM      |
| 316 Maplewood Ave @ Fairview Drive                 | 12:12 PM               | 3:12 PM      | 7:39 PM      |
| 317 Maplewood Ave @ I-95 Overpass                  | 12:14 PM               | 3:14 PM      | 7:41 PM      |
| 318 Maplewood Ave @ Dearborn Street                | 12:15 PM               | 3:15 PM      | 7:42 PM      |
| 319 Maplewood Ave @ North Cemetery                 | 12:16 PM               | 3:16 PM      | 7:43 PM      |
| 303 Hanover Street @ High-Hanover Parking Facility | 12:18 PM               | 3:18 PM      | 7:45 PM      |
| 311 Arrive Market Square                           | 12:20 PM               | 3:20 PM      | 7:47 PM      |
| <b>Inbound</b>                                     |                        |              |              |
| 311 Depart Market Square                           | 12:20 PM               | 3:20 PM      | 7:47 PM      |
| 310 Islington Street @ Tanner Street               | 12:21 PM               | 3:21 PM      | 7:49 PM      |
| 308 Islington Street @ Cornwall Street             | 12:22 PM               | 3:22 PM      | 7:50 PM      |
| 307 Islington Street @ Dunkin Donuts               | 12:24 PM               | 3:24 PM      | 7:51 PM      |
| 305 Plaza 800                                      | 12:25 PM               | 3:25 PM      | 7:53 PM      |
| 320 Bartlett Street @ Meredith Way                 | 12:28 PM               | 3:28 PM      | 7:56 PM      |
| 321 Dennett Street @ Woodbury Ave                  | 12:29 PM               | 3:29 PM      | 7:56 PM      |
| 602 Crossings at Fox Run @ Regal Cinemas           | 12:36 PM               | 3:36 PM      | 8:01 PM      |
| 606 Fox Run Mall (to UNH)                          | 12:40 PM               | 3:40 PM      | 8:05 PM      |
| 605 Fox Run Rd @ Wal-Mart                          | 12:42 PM               | 3:42 PM      | 8:07 PM      |
| 607 2299 Woodbury Ave                              | 12:42 PM               | 3:42 PM      | 8:08 PM      |
| 201 Boston Harbor Road @ DMV                       | <b>On Request Only</b> |              |              |
| 125 Rte 4 @ Scammel Bridge (West Side)             | 12:48 PM               | 3:48 PM      | 8:14 PM      |
| 126 Rte 4 @ Emery Farm                             | 12:50 PM               | 3:50 PM      | 8:15 PM      |
| 193 Rte 4 @ Morgan Way                             | 12:50 PM               | 3:50 PM      | 8:16 PM      |
| 127 Rte 4 @ Shearwater Street                      | 12:51 PM               | 3:51 PM      | 8:17 PM      |
| 120 Rte 4 @ 65 Piscataqua Road                     | 12:52 PM               | 3:52 PM      | 8:17 PM      |
| 119 Rte 108 @ The Pines Inn (#47)                  | 12:55 PM               | 3:55 PM      | 8:20 PM      |
| 108 Rte 108 @ Young Drive                          | 12:55 PM               | 3:55 PM      | 8:21 PM      |
| 117 Madbury Road @ Woodman Rd                      | 12:57 PM               | 3:57 PM      | 8:23 PM      |
| 116 ARRIVE Garrison Ave @ Sawyer Hall              | 12:59 PM               | 3:59 PM      | 8:24 PM      |
| 105 ARRIVE Holloway Commons Main Street            | 1:00 PM                | 4:00 PM      | 8:26 PM      |
| 1001 ARRIVE UNH McConnell Hall                     | 1:02 PM                | 4:02 PM      | 8:28 PM      |

These times are approximate. Please be at the bus stop 5 minutes before the scheduled time.

There is no weekend service during periods of "Reduced Service"



# Route 4B Weekday

# Portsmouth 4B

## UNH/Durham to Malls & Portsmouth Market Square

## Monday - Friday

| Stop ID # & Location                               |                        |                 |                |                |                |                |
|--|------------------------|-----------------|----------------|----------------|----------------|----------------|
| Outbound   | Run 1                  | Run 2           | Run 3          | Run 4          | Run 5          | Run 6          |
| 101 DEPART UNH McCONNELL HALL                      | 8:45 AM                | 10:35 AM        | 1:05 PM        | 3:05 PM        | 4:35 PM        | 8:05 PM        |
| 102 DEPART UNH KINGSBURY HALL                      | 8:47 AM                | 10:37 AM        | 1:07 PM        | 3:07 PM        | 4:37 PM        | 8:07 PM        |
| 103 DEPART UNH HEWITT HALL                         | 8:47 AM                | 10:37 AM        | 1:07 PM        | 3:07 PM        | 4:37 PM        | 8:07 PM        |
| 104 DEPART MAIN STREET @ UNH THOMPSON HALL         | 8:50 AM                | 10:40 AM        | 1:10 PM        | 3:10 PM        | 4:40 PM        | 8:10 PM        |
| 106 DEPART MAIN STREET @ UNH HETZEL HALL           | 8:52 AM                | 10:42 AM        | 1:12 PM        | 3:12 PM        | 4:42 PM        | 8:12 PM        |
| 107 Rte 108 @ Old Landing Rd                       | 8:54 AM                | 10:44 AM        | 1:14 PM        | 3:14 PM        | 4:44 PM        | 8:14 PM        |
| 109 Rte 108 @ Old Piscataqua Rd                    | 8:54 AM                | 10:44 AM        | 1:14 PM        | 3:14 PM        | 4:44 PM        | 8:14 PM        |
| 121 Rte 4 @ 68 Piscataqua Rd                       | 8:55 AM                | 10:45 AM        | 1:15 PM        | 3:15 PM        | 4:45 PM        | 8:15 PM        |
| 122 Rte 4 @ Riverview Rd                           | 8:56 AM                | 10:46 AM        | 1:16 PM        | 3:16 PM        | 4:46 PM        | 8:16 PM        |
| 192 Rte 4 @ 116 Piscataqua Rd                      | 8:56 AM                | 10:46 AM        | 1:16 PM        | 3:16 PM        | 4:46 PM        | 8:16 PM        |
| 123 Rte 4 @ Wagon Hill Farm                        | 8:57 AM                | 10:47 AM        | 1:17 PM        | 3:17 PM        | 4:47 PM        | 8:17 PM        |
| 124 Rte 4 @ Cedar Point Rd                         | 8:58 AM                | 10:48 AM        | 1:18 PM        | 3:18 PM        | 4:48 PM        | 8:18 PM        |
| 201 Boston Harbor Road @ DMV                       | <b>On Request Only</b> |                 |                |                |                |                |
| 322 676 Dennett Street                             | 9:09 AM                | 10:57 AM        | 1:27 PM        | 3:27 PM        | 4:57 PM        | 8:27 PM        |
| 323 Bartlett Street @ Thornton Street              | 9:10 AM                | 10:58 AM        | 1:28 PM        | 3:28 PM        | 4:58 PM        | 8:28 PM        |
| 305 Plaza 800                                      | 9:13 AM                | 11:01 AM        | 1:31 PM        | 3:31 PM        | 5:01 PM        | 8:30 PM        |
| 306 Islington Street @ Cass Street                 | 9:15 AM                | 11:03 AM        | 1:33 PM        | 3:33 PM        | 5:03 PM        | 8:32 PM        |
| 304 Islington Street @ Goodwin Park                | 9:16 AM                | 11:04 AM        | 1:34 PM        | 3:34 PM        | 5:04 PM        | 8:33 PM        |
| 309 Islington Street @ Keefe House                 | 9:17 AM                | 11:05 AM        | 1:35 PM        | 3:35 PM        | 5:05 PM        | 8:34 PM        |
| 303 Hanover Street @ High-Hanover Parking Facility | 9:19 AM                | 11:07 AM        | 1:37 PM        | 3:37 PM        | 5:07 PM        | 8:36 PM        |
| <b>311 Arrive Market Square</b>                    | <b>9:21 AM</b>         | <b>11:09 AM</b> | <b>1:39 PM</b> | <b>3:39 PM</b> | <b>5:09 PM</b> | <b>8:38 PM</b> |
| <b>Inbound</b>                                     |                        |                 |                |                |                |                |
| <b>311 Depart Market Square</b>                    | <b>9:21 AM</b>         | <b>11:09 AM</b> | <b>1:39 PM</b> | <b>3:39 PM</b> | <b>5:09 PM</b> | <b>8:38 PM</b> |
| 324 Maplewood Ave @ Vaughan Street                 | 9:23 AM                | 11:11 AM        | 1:41 PM        | 3:41 PM        | 5:11 PM        | 8:40 PM        |
| 325 Maplewood Ave @ Jackson Hill St                | 9:24 AM                | 11:12 AM        | 1:42 PM        | 3:42 PM        | 5:12 PM        | 8:41 PM        |
| 326 651 Maplewood Ave (Odd Fellow's Lodge)         | 9:25 AM                | 11:13 AM        | 1:43 PM        | 3:43 PM        | 5:13 PM        | 8:42 PM        |
| 327 Maplewood Ave @ Heritage Hill                  | 9:26 AM                | 11:14 AM        | 1:44 PM        | 3:44 PM        | 5:14 PM        | 8:43 PM        |
| 333 Portsmouth Blvd @ Shearwater Drive             | 9:31 AM                | 11:19 AM        | 1:49 PM        | 3:49 PM        | 5:19 PM        | 8:48 PM        |
| 334 215 Commerce Way                               | 9:31 AM                | 11:19 AM        | 1:49 PM        | 3:49 PM        | 5:19 PM        | 8:48 PM        |
| 335 175 Commerce Way                               | 9:32 AM                | 11:20 AM        | 1:50 PM        | 3:50 PM        | 5:20 PM        | 8:49 PM        |
| 339 Commerce Way @ Marshall's Plaza                | 9:33 AM                | 11:21 AM        | 1:51 PM        | 3:51 PM        | 5:21 PM        | 8:49 PM        |
| 313 1855 Woodbury Ave @ Starbucks                  | 9:34 AM                | 11:22 AM        | 1:52 PM        | 3:52 PM        | 5:22 PM        | 8:50 PM        |
| 301 Gosling Road @ Winsor Rd                       | 9:36 AM                | 11:24 AM        | 1:54 PM        | 3:54 PM        | 5:24 PM        | 8:52 PM        |
| 602 Crossings at Fox Run @ Regal Cinemas           | 9:38 AM                | 11:26 AM        | 1:56 PM        | 3:56 PM        | 5:26 PM        | 8:53 PM        |
| 606 Fox Run Mall (to UNH)                          | 9:41 AM                | 11:29 AM        | 1:59 PM        | 3:59 PM        | 5:29 PM        | 8:56 PM        |
| 605 Fox Run Rd @ Wal-Mart                          | 9:43 AM                | 11:31 AM        | 2:01 PM        | 4:01 PM        | 5:31 PM        | 8:58 PM        |
| 607 2299 Woodbury Ave                              | 9:45 AM                | 11:32 AM        | 2:02 PM        | 4:02 PM        | 5:32 PM        | 8:59 PM        |
| 201 Boston Harbor Road @ DMV                       | <b>On Request Only</b> |                 |                |                |                |                |
| 125 Rte 4 @ Scammel Bridge (West Side)             | 9:53 AM                | 11:40 AM        | 2:10 PM        | 4:10 PM        | 5:40 PM        | 9:06 PM        |
| 126 Rte 4 @ Emery Farm                             | 9:54 AM                | 11:41 AM        | 2:12 PM        | 4:12 PM        | 5:42 PM        | 9:07 PM        |
| 193 Rte 4 @ Morgan Way                             | 9:55 AM                | 11:42 AM        | 2:12 PM        | 4:12 PM        | 5:42 PM        | 9:07 PM        |
| 127 Rte 4 @ Shearwater Street                      | 9:55 AM                | 11:42 AM        | 2:13 PM        | 4:13 PM        | 5:43 PM        | 9:08 PM        |
| 120 Rte 4 @ 65 Piscataqua Rd                       | 9:56 AM                | 11:43 AM        | 2:13 PM        | 4:13 PM        | 5:43 PM        | 9:08 PM        |
| 119 Rte 108 @ The Pines Inn (#47)                  | 9:59 AM                | 11:46 AM        | 2:16 PM        | 4:16 PM        | 5:46 PM        | 9:11 PM        |
| 108 Rte 108 @ Young Drive                          | 9:59 AM                | 11:46 AM        | 2:17 PM        | 4:17 PM        | 5:47 PM        | 9:12 PM        |
| 117 Madbury Road @ Woodman Rd                      | 10:01 AM               | 11:48 AM        | 2:19 PM        | 4:19 PM        | 5:49 PM        | 9:14 PM        |
| <b>116 ARRIVE Garrison Ave @ Sawyer Hall</b>       | <b>10:03 AM</b>        | <b>11:50 AM</b> | <b>2:20 PM</b> | <b>4:20 PM</b> | <b>5:50 PM</b> | <b>9:15 PM</b> |
| <b>105 ARRIVE Holloway Commons Main Street</b>     | <b>10:04 AM</b>        | <b>11:51 AM</b> | <b>2:21 PM</b> | <b>4:21 PM</b> | <b>5:51 PM</b> | <b>9:16 PM</b> |
| <b>1001 ARRIVE UNH McConnell Hall</b>              | <b>10:06 AM</b>        | <b>11:53 AM</b> | <b>2:23 PM</b> | <b>4:23 PM</b> | <b>5:53 PM</b> | <b>9:18 PM</b> |

**These times are approximate. Please be at the bus stop 5 minutes before the scheduled time.**

# Route 4B WEEKEND

# Portsmouth 4B

UNH / Durham to Malls & Portsmouth Market Square

Saturday - Sunday

| Stop ID # & Location                               |                        |                |                |                 |
|--|------------------------|----------------|----------------|-----------------|
| Outbound   | Run 1                  | Run 2          | Run 3          | Run 4           |
| 101 DEPART UNH McCONNELL HALL                      | 1:05 PM                | 3:35 PM        | 5:05 PM        | 9:05 PM         |
| 102 DEPART UNH KINGSBURY HALL                      | 1:07 PM                | 3:37 PM        | 5:07 PM        | 9:07 PM         |
| 103 DEPART UNH HEWITT HALL                         | 1:07 PM                | 3:37 PM        | 5:07 PM        | 9:07 PM         |
| HALL   | 1:10 PM                | 3:40 PM        | 5:10 PM        | 9:10 PM         |
| 106 DEPART MAIN STREET @ UNH HETZEL HALL           | 1:12 PM                | 3:42 PM        | 5:12 PM        | 9:12 PM         |
| 107 Rte 108 @ Old Landing Rd                       | 1:14 PM                | 3:44 PM        | 5:14 PM        | 9:14 PM         |
| 109 Rte 108 @ Old Piscataqua Rd                    | 1:14 PM                | 3:44 PM        | 5:14 PM        | 9:14 PM         |
| 121 Rte 4 @ 68 Piscataqua Rd                       | 1:15 PM                | 3:45 PM        | 5:15 PM        | 9:15 PM         |
| 122 Rte 4 @ Riverview Rd                           | 1:16 PM                | 3:46 PM        | 5:16 PM        | 9:16 PM         |
| 192 Rte 4 @ 116 Piscataqua Rd                      | 1:16 PM                | 3:46 PM        | 5:16 PM        | 9:16 PM         |
| 123 Rte 4 @ Wagon Hill Farm                        | 1:17 PM                | 3:47 PM        | 5:17 PM        | 9:17 PM         |
| 124 Rte 4 @ Cedar Point Rd                         | 1:18 PM                | 3:48 PM        | 5:18 PM        | 9:18 PM         |
| 201 Boston Harbor Road @ DMV                       | <b>On Request Only</b> |                |                |                 |
| 604 Newington Wal-Mart                             | 1:26 PM                | 3:56 PM        | 5:26 PM        | 9:26 PM         |
| 603 Fox Run Mall (To Portsmouth)                   | 1:28 PM                | 3:58 PM        | 5:28 PM        | 9:28 PM         |
| 601 Crossings at Fox Run @ Cold Stone Creamery     | 1:31 PM                | 4:01 PM        | 5:31 PM        | 9:31 PM         |
| 322 676 Dennett Street                             | 1:38 PM                | 4:08 PM        | 5:38 PM        | 9:38 PM         |
| 323 Bartlett Street @ Thornton Street              | 1:39 PM                | 4:09 PM        | 5:39 PM        | 9:39 PM         |
| 305 Plaza 800                                      | 1:42 PM                | 4:12 PM        | 5:42 PM        | 9:42 PM         |
| 306 Islington Street @ Cass Street                 | 1:44 PM                | 4:14 PM        | 5:44 PM        | 9:44 PM         |
| 304 Islington Street @ Goodwin Park                | 1:45 PM                | 4:15 PM        | 5:45 PM        | 9:45 PM         |
| 309 Islington Street @ Keefe House                 | 1:46 PM                | 4:16 PM        | 5:46 PM        | 9:46 PM         |
| 303 Hanover Street @ High-Hanover Parking Facility | 1:48 PM                | 4:18 PM        | 5:48 PM        | 9:48 PM         |
| <b>311 Arrive Market Square</b>                    | <b>1:50 PM</b>         | <b>4:20 PM</b> | <b>5:50 PM</b> | <b>9:50 PM</b>  |
| Inbound  |                        |                |                |                 |
| <b>311 Depart Market Square</b>                    | <b>1:50 PM</b>         | <b>4:20 PM</b> | <b>5:50 PM</b> | <b>9:50 PM</b>  |
| 324 Maplewood Ave @ Vaughan Street                 | 1:52 PM                | 4:22 PM        | 5:52 PM        | 9:52 PM         |
| 325 Maplewood Ave @ Jackson Hill St                | 1:53 PM                | 4:23 PM        | 5:53 PM        | 9:53 PM         |
| 326 651 Maplewood Ave (Odd Fellow's Lodge)         | 1:54 PM                | 4:24 PM        | 5:54 PM        | 9:54 PM         |
| 327 Maplewood Ave @ Heritage Hill                  | 1:55 PM                | 4:25 PM        | 5:55 PM        | 9:55 PM         |
| 333 Portsmouth Blvd @ Shearwater Drive             | 2:00 PM                | 4:30 PM        | 6:00 PM        | 10:00 PM        |
| 334 215 Commerce Way                               | 2:00 PM                | 4:30 PM        | 6:00 PM        | 10:00 PM        |
| 335 175 Commerce Way                               | 2:01 PM                | 4:31 PM        | 6:01 PM        | 10:01 PM        |
| 339 Commerce Way @ Marshall's Plaza                | 2:02 PM                | 4:32 PM        | 6:02 PM        | 10:02 PM        |
| 313 1855 Woodbury Ave @ Starbucks                  | 2:03 PM                | 4:33 PM        | 6:03 PM        | 10:03 PM        |
| 301 Gosling Road @ Winsor Rd                       | 2:05 PM                | 4:35 PM        | 6:05 PM        | 10:05 PM        |
| 602 Crossings at Fox Run @ Regal Cinemas           | 2:07 PM                | 4:37 PM        | 6:07 PM        | 10:06 PM        |
| 606 Fox Run Mall (to UNH)                          | 2:10 PM                | 4:40 PM        | 6:10 PM        | 10:09 PM        |
| 605 Fox Run Rd @ Wal-Mart                          | 2:12 PM                | 4:42 PM        | 6:12 PM        | 10:11 PM        |
| 607 2299 Wodbury Ave                               | 2:13 PM                | 4:43 PM        | 6:13 PM        | 10:12 PM        |
| 201 Boston Harbor Road @ DMV                       | <b>On Request Only</b> |                |                |                 |
| 125 Rte 4 @ Scammel Bridge (West Side)             | 2:20 PM                | 4:50 PM        | 6:20 PM        | 10:19 PM        |
| 126 Rte 4 @ Emery Farm                             | 2:22 PM                | 4:52 PM        | 6:22 PM        | 10:21 PM        |
| 193 Rte 4 @ Morgan Way                             | 2:22 PM                | 4:52 PM        | 6:22 PM        | 10:22 PM        |
| 127 Rte 4 @ Shearwater Street                      | 2:23 PM                | 4:53 PM        | 6:23 PM        | 10:22 PM        |
| 120 Rte 4 @ 65 Piscataqua Road                     | 2:24 PM                | 4:54 PM        | 6:24 PM        | 10:23 PM        |
| 119 Rte 108 @ The Pines Inn (#47)                  | 2:27 PM                | 4:57 PM        | 6:27 PM        | 10:26 PM        |
| 108 Rte 108 @ Young Drive                          | 2:27 PM                | 4:57 PM        | 6:27 PM        | 10:27 PM        |
| 117 Madbury Road @ Woodman Rd                      | 2:29 PM                | 4:59 PM        | 6:29 PM        | 10:29 PM        |
| <b>116 ARRIVE Garrison Ave @ Sawyer Hall</b>       | <b>2:31 PM</b>         | <b>5:01 PM</b> | <b>6:31 PM</b> | <b>10:30 PM</b> |
| <b>105 ARRIVE Holloway Commons Main Street</b>     | <b>2:32 PM</b>         | <b>5:02 PM</b> | <b>6:32 PM</b> | <b>10:31 PM</b> |
| <b>1001 ARRIVE UNH McConnell Hall</b>              | <b>2:34 PM</b>         | <b>5:04 PM</b> | <b>6:34 PM</b> | <b>10:33 PM</b> |

These times are approximate. Please be at the bus stop 5 minutes before the scheduled time.

There is no weekend service during periods of "Reduced Service"

**APPENDIX G**

US Census Journey-to-Work Data

**Table 3. Residence MCD/County to Workplace MCD/County Commuting Flows for the United States and Puerto R**

For more information on sampling and estimation methods, confidentiality protection, and sampling and nonsampling errors, see Universe: Workers 16 years and over.

Commuting flows are sorted by residence state, residence county, and residence minor civil division.


| Residence     |                           | Place of Work |                           | Commuting Flow            |
|---------------|---------------------------|---------------|---------------------------|---------------------------|
| State Name    | Minor Civil Division Name | State Name    | Minor Civil Division Name | Workers in Commuting Flow |
| New Hampshire | Portsmouth city           | New Hampshire | Portsmouth city           | 6,310                     |
| New Hampshire | Portsmouth city           | New Hampshire | Dover city                | 643                       |
| New Hampshire | Portsmouth city           | New Hampshire | Durham town               | 470                       |
| New Hampshire | Portsmouth city           | New Hampshire | Exeter town               | 437                       |
| New Hampshire | Portsmouth city           | Maine         | Kittery town              | 379                       |
| New Hampshire | Portsmouth city           | New Hampshire | Newington town            | 360                       |
| New Hampshire | Portsmouth city           | New Hampshire | Hampton town              | 354                       |
| New Hampshire | Portsmouth city           | Massachusetts | Boston city               | 164                       |
| New Hampshire | Portsmouth city           | New Hampshire | North Hampton town        | 162                       |
| New Hampshire | Portsmouth city           | New Hampshire | Salem town                | 159                       |
| New Hampshire | Portsmouth city           | Maine         | York town                 | 142                       |
| New Hampshire | Portsmouth city           | New Hampshire | New Castle town           | 134                       |
| New Hampshire | Portsmouth city           | New Hampshire | Manchester city           | 129                       |
| New Hampshire | Portsmouth city           | New Hampshire | Somersworth city          | 125                       |
| New Hampshire | Portsmouth city           | New Hampshire | Rye town                  | 123                       |
| New Hampshire | Portsmouth city           | New Hampshire | Stratham town             | 123                       |
| New Hampshire | Portsmouth city           | New Hampshire | Greenland town            | 112                       |
| New Hampshire | Portsmouth city           | New Hampshire | Londonderry town          | 92                        |
| New Hampshire | Portsmouth city           | New Hampshire | Concord city              | 89                        |
| New Hampshire | Portsmouth city           | Massachusetts | Newburyport city          | 86                        |
| New Hampshire | Portsmouth city           | New Hampshire | Seabrook town             | 85                        |
| New Hampshire | Portsmouth city           | New Hampshire | Rochester city            | 80                        |
| New Hampshire | Portsmouth city           | Massachusetts | Peabody city              | 78                        |
| New Hampshire | Portsmouth city           | New Hampshire | Brentwood town            | 77                        |
| New Hampshire | Portsmouth city           | New Hampshire | Raymond town              | 75                        |
| New Hampshire | Portsmouth city           | Maine         | North Berwick town        | 72                        |
| New Hampshire | Portsmouth city           | New Hampshire | Bedford town              | 69                        |
| New Hampshire | Portsmouth city           | New Hampshire | Barrington town           | 56                        |
| New Hampshire | Portsmouth city           | New Hampshire | Hampton Falls town        | 53                        |
| New Hampshire | Portsmouth city           | New Hampshire | Plymouth town             | 51                        |
| New Hampshire | Portsmouth city           | Massachusetts | North Andover town        | 49                        |
| New Hampshire | Portsmouth city           | New Hampshire | Wolfeboro town            | 49                        |
| New Hampshire | Portsmouth city           | Maine         | Eliot town                | 48                        |
| New Hampshire | Portsmouth city           | Massachusetts | Amesbury Town city        | 48                        |
| New Hampshire | Portsmouth city           | Massachusetts | Quincy city               | 43                        |
| New Hampshire | Portsmouth city           | Massachusetts | Andover town              | 41                        |
| New Hampshire | Portsmouth city           | Massachusetts | Methuen Town city         | 40                        |
| New Hampshire | Portsmouth city           | Massachusetts | Stoneham town             | 39                        |
| New Hampshire | Portsmouth city           | New Hampshire | Plaistow town             | 39                        |
| New Hampshire | Portsmouth city           | New Hampshire | Nashua city               | 38                        |
| New Hampshire | Portsmouth city           | Massachusetts | Burlington town           | 37                        |
| New Hampshire | Portsmouth city           | New Hampshire | Hooksett town             | 37                        |
| New Hampshire | Portsmouth city           | New Hampshire | Rollinsford town          | 37                        |
| New Hampshire | Portsmouth city           | New Hampshire | Newmarket town            | 33                        |
| New Hampshire | Portsmouth city           | Massachusetts | Haverhill city            | 32                        |
| New Hampshire | Portsmouth city           | Maine         | South Portland city       | 25                        |
| New Hampshire | Portsmouth city           | Massachusetts | Groveland town            | 25                        |
| New Hampshire | Portsmouth city           | Massachusetts | Cambridge city            | 25                        |
| New Hampshire | Portsmouth city           | Massachusetts | Chelmsford town           | 24                        |
| New Hampshire | Portsmouth city           | Maine         | South Berwick town        | 23                        |
| New Hampshire | Portsmouth city           | New Hampshire | Hampstead town            | 22                        |
| New Hampshire | Portsmouth city           | Maine         | Portland city             | 21                        |
| New Hampshire | Portsmouth city           | Massachusetts | Boxborough town           | 21                        |
| New Hampshire | Portsmouth city           | Massachusetts | BillERICA town            | 20                        |

| TO / FROM      |                |                          |                          |                                       |
|----------------|----------------|--------------------------|--------------------------|---------------------------------------|
| North via I-95 | South via I-95 | North via Spaulding Tpke | South via Route 1 Bypass | Portsmouth Center via Woodbury/Market |
| 315.5          | 315.5          | 315.5                    | 1893                     | 3470.5                                |
|                |                | 643                      |                          |                                       |
|                | 117.5          | 376                      |                          |                                       |
|                | 437            |                          |                          |                                       |
| 151.6          |                |                          |                          | 227.4                                 |
|                | 36             | 324                      |                          |                                       |
|                | 106.2          |                          | 247.8                    |                                       |
|                | 82             |                          | 82                       |                                       |
|                | 48.6           |                          | 113.4                    |                                       |
|                | 159            |                          |                          |                                       |
| 71             |                |                          |                          | 71                                    |
|                |                |                          |                          | 134                                   |
|                | 90.3           | 38.7                     |                          |                                       |
|                |                | 125                      |                          |                                       |
|                |                |                          |                          | 123                                   |
|                | 30.75          |                          | 92.25                    |                                       |
|                | 28             |                          | 84                       |                                       |
|                | 92             |                          |                          |                                       |
|                |                | 89                       |                          |                                       |
|                | 43             |                          | 43                       |                                       |
|                | 42.5           |                          | 42.5                     |                                       |
|                |                | 80                       |                          |                                       |
|                | 39             |                          | 39                       |                                       |
|                | 77             |                          |                          |                                       |
|                | 75             |                          |                          |                                       |
| 36             |                | 36                       |                          |                                       |
|                | 69             |                          |                          |                                       |
|                |                | 56                       |                          |                                       |
|                | 26.5           |                          | 26.5                     |                                       |
|                | 45.9           | 5.1                      |                          |                                       |
|                | 36.75          |                          | 12.25                    |                                       |
|                |                | 49                       |                          |                                       |
| 24             |                |                          |                          | 24                                    |
|                | 24             |                          | 24                       |                                       |
|                | 21.5           |                          | 21.5                     |                                       |
|                | 20.5           |                          | 20.5                     |                                       |
|                | 20             |                          | 20                       |                                       |
|                | 19.5           |                          | 19.5                     |                                       |
|                | 39             |                          |                          |                                       |
|                | 38             |                          |                          |                                       |
|                | 18.5           |                          | 18.5                     |                                       |
|                | 33.3           | 3.7                      |                          |                                       |
|                |                | 37                       |                          |                                       |
|                | 33             |                          |                          |                                       |
|                | 16             |                          | 16                       |                                       |
| 25             |                |                          |                          |                                       |
|                | 12.5           |                          | 12.5                     |                                       |
|                | 12.5           |                          | 12.5                     |                                       |
|                | 12             |                          | 12                       |                                       |
|                |                | 5.75                     |                          |                                       |
| 17.25          |                |                          |                          |                                       |
|                | 22             |                          |                          |                                       |
| 21             |                |                          |                          |                                       |
|                | 10.5           |                          | 10.5                     |                                       |
|                | 10             |                          | 10                       |                                       |

TOTAL 12,105

|     |       |       |       |       |
|-----|-------|-------|-------|-------|
| 661 | 2,360 | 2,184 | 2,996 | 3,927 |
| 5%  | 20%   | 20%   | 25%   | 30%   |

**APPENDIX H**  
Site Development Plan



**SITE DATA:**  
 LOCATION: TAX MAP 239, LOT 13-2, MAP 239 LOT 16, MAP 239 LOT 18  
 OWNER: 100 DURGIN LANE OWNER LLC  
 ONE MARINA PARK DRIVE, SUITE 1500  
 BOSTON, MA 02210

ZONING DISTRICT: GATEWAY NEIGHBORHOOD MIXED USE CORRIDOR (G1)  
 HIGHWAY NOISE OVERLAY DISTRICT

PROPOSED USE: MULTI-FAMILY RESIDENTIAL DEVELOPMENT  
 EXISTING LOT SIZE: ±1,139,161 SF / 26.15 ACRES (MAP 239 LOT 13-2, LOT 16, LOT 18)

**DEVELOPMENT STANDARDS**

| GENERAL RESIDENTIAL DEVELOPMENT (10.5B42.30) | REQUIRED  | PROPOSED      |
|--|-----------|---------------|
| MINIMUM SITE DEVELOPMENT AREA:               | 10,000 SF | ±1,139,161 SF |
| MINIMUM SITE WIDTH:                          | 75 FT     | >75 FT        |
| MINIMUM SITE LENGTH:                         | 100 FT    | >100 FT       |
| MINIMUM PERIMETER BUFFER:                    | N/A       | -             |
| MAXIMUM DEVELOPMENT BLOCK DIMS:              |           |               |
| BLOCK LENGTH:                                | 500 FT    | <500 FT       |
| BLOCK PERIMETER:                             | 1,500 FT  | <1,500 FT     |
| MAXIMUM BUILDING COVERAGE:                   | 50%       | 8.6%          |
| MINIMUM OPEN SPACE COVERAGE:                 | 20%       | 62%           |

| APARTMENT BUILDING (10.5B34.40)         | REQUIRED         | PROPOSED  |
|---|------------------|---|
| MINIMUM LOT DEPTH:                      | NR               | -   |
| MINIMUM STREET FRONTAGE:                | 50 FT            | 200.6 FT  |
| FRONT YARD SETBACK:                     | 10-30 FT         | ±225.1 FT <sup>(1)</sup>  |
| MIN. SIDE YARD SETBACK:                 | 15 FT            | 52.7 FT   |
| MIN. REAR YARD SETBACK:                 | 20 FT            | 85.0 FT   |
| DWELLING UNITS PER BUILDING:            | 4-24             | VARIES (24 MAX.)  |
| MAXIMUM DWELLING UNIT SIZE:             | NR               | -   |
| MAXIMUM BUILDING HEIGHT:                | NR               | 4 STORIES OR 50 FT  |
| MINIMUM STREET-FACING FACADE HEIGHT:    | 24 FT            | >24 FT  |
| MAX. FINISH FLOOR ABOVE SIDEWALK:       | 36"              | VARIES  |
| MAXIMUM BUILDING COVERAGE:              | 50%              | 7.8%  |
| MAXIMUM BUILDING FOOTPRINT:             | NR               | -   |
| MAXIMUM FACADE MODULATION LENGTH:       | 50 FT            | <50 FT  |
| MINIMUM STREET FACING FACADE GLAZING:   | 20% GROUND FLOOR | >20%  |
| MAXIMUM STREET FACING ENTRANCE SPACING: | NR               | -   |
| ALLOWED ROOF TYPES:                     | ALL              | SHED  |
| ALLOWED FACADE TYPES:                   |                  | FORECOURT, RECESSED, DOORYARD, RECESSED, ENTRY, DOORYARD, STEP, PORCH |

| COMMUNITY BUILDING (10.5B34.100)        | REQUIRED         | PROPOSED   |
|---|------------------|--|
| MINIMUM LOT DEPTH:                      | NR               | -  |
| MINIMUM STREET FRONTAGE:                | 50 FT            | 200.6 FT   |
| FRONT YARD SETBACK:                     | 10-40 FT         | ±225.1 FT <sup>(1)</sup>   |
| MIN. SIDE YARD SETBACK:                 | 15 FT            | 756.4 FT   |
| MIN. REAR YARD SETBACK:                 | 20 FT            | 478.2 FT   |
| DWELLING UNITS PER BUILDING:            | NR               | -  |
| MAXIMUM DWELLING UNIT SIZE:             | NR               | -  |
| MAXIMUM BUILDING HEIGHT:                | NR               | 3 STORIES OR 45 FT   |
| MINIMUM STREET-FACING FACADE HEIGHT:    | 18 FT            | 18 FT  |
| FINISH FLOOR GRADE ABOVE SIDEWALK:      | 2 FT - 6 FT      | VARIES   |
| MAXIMUM BUILDING COVERAGE:              | NR               | -  |
| MAXIMUM BUILDING FOOTPRINT:             | NR               | -  |
| MAXIMUM FACADE MODULATION LENGTH:       | 100 FT           | 100 FT   |
| MINIMUM STREET FACING FACADE GLAZING:   | 30% GROUND FLOOR | 30%  |
| MAXIMUM STREET FACING ENTRANCE SPACING: | NR               | -  |
| ALLOWED ROOF TYPES:                     | ALL              | SHED   |
| ALLOWED FACADE TYPES:                   |                  | DOORYARD, FORECOURT, STOOP, RECESSED, ENTRY, STEP, PORCH, TERRACE, GALLERY, ARCADE PORCH, FORECOURT, TERRACE |

(1) - THE APPLICANT IS REQUESTING THE PLANNING BOARD TO ALLOW AN INCREASE OF BUILDING SETBACK FROM THE FRONT LOT LINE AS ALLOWED BY SECTION 10.5B41.60.

| COMMUNITY SPACE: | REQUIRED   | PROPOSED   |
|------------------|------------|------------|
|                  | 10%        | 11.6%      |
|                  | 113,916 SF | 131,942 SF |

**PARKING REQUIREMENTS**

|   |                        |            |
|---|------------------------|------------|
| RESIDENTIAL UNITS (<750 SF)             | 227 UNITS X 1.0 SPACES | 227 SPACES |
| RESIDENTIAL UNITS (>750 SF)             | 133 UNITS X 1.3 SPACES | 173 SPACES |
| VISITOR SPACES                          | 1 SPACE / 5 UNITS      | 72 SPACES  |
| TOTAL MINIMUM PARKING SPACES REQUIRED = |                        | 472 SPACES |

| PARKING SPACES | REQUIRED   | PROPOSED   |
|----------------|------------|------------|
|                | 472 SPACES | 567 SPACES |

| ADA PARKING SPACES | REQUIRED <sup>(2)</sup> | PROPOSED  |
|--------------------|-------------------------|-----------|
|                    | 25 SPACES               | 34 SPACES |

(2) - PER THE AMERICANS WITH DISABILITIES ACT (ADA) STANDARDS, LATEST EDITION.


**PARKING SPACE DIMENSIONAL REQUIREMENTS:**

|                      |            |        |
|----------------------|------------|--------|
| STANDARD 90° STALL : |            |        |
| WIDTH                | 8.5 FT MIN | 8.5 FT |
| LENGTH               | 19 FT MIN  | 19 FT  |
| STANDARD 0° STALL :  |            |        |
| WIDTH                | 8.5 FT MIN | 8.5 FT |
| LENGTH               | 20 FT MIN  | 20 FT  |
| DRIVE AISLE WIDTH:   |            |        |
| 90° (2-WAY TRAFFIC)  | 24 FT      | 24 FT  |
| 0° (2-WAY TRAFFIC)   | 24 FT      | 24 FT  |


| BICYCLE SPACES                       | REQUIRED         | PROPOSED   |
|--------------------------------------|------------------|------------|
| 1 BICYCLE SPACE / 10 PARKING SPACES: | 30 SPACES (MAX.) | >58 SPACES |

(INDOOR BIKE STORAGE WILL BE PROVIDED THAT MEETS OR EXCEEDS REQUIRED.)

- SITE RECORDING NOTES:**
- THIS SITE PLAN SHALL BE RECORDED IN THE ROCKINGHAM COUNTY REGISTRY OF DEEDS.
  - ALL IMPROVEMENTS SHOWN ON THIS SITE PLAN SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES SHALL BE MADE TO THIS SITE PLAN WITHOUT THE EXPRESS APPROVAL OF THE PORTSMOUTH PLANNING DIRECTOR.
  - THIS IS NOT A BOUNDARY SURVEY AND SHALL NOT BE USED AS SUCH.



SEE SHEET C-101 FOR SITE PLAN NOTES & LEGEND



**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC

100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE      | DESCRIPTION    |
|------|-----------|----------------|
| A    | 4/22/2024 | TAC SUBMISSION |

|                      |                      |
|----------------------|----------------------|
| PROJECT NO:          | E5071-001            |
| DATE:                | 4/22/2024            |
| FILE:                | E5071-001-C-DSGN.dwg |
| DRAWN BY:            | BKC/NHW              |
| DESIGNED/CHECKED BY: | NAH                  |
| APPROVED BY:         | PMC                  |

**OVERALL SITE PLAN**

SCALE: AS SHOWN

**C-300**


Last Saved: 4/19/2024  
 Plotted On: Apr 22, 2024 9:15am By: f0cric01  
 Tighe & Bond \Vigil\external\dwg\001\Projects\E5071 Eastern Real Estate\001 Portsmouth, NH 100 Durgin Lane Drawings\AutoCAD\Sheet\E5071-001-C-DSGN.dwg

**APPENDIX I**


Background Development Traffic Volumes


**LEGEND**

VOLUMES: AM (PM)

 TRAFFIC SIGNAL



 STOP SIGN



|                                       |   |
|---------------------------------------|---|
| <b>LONZA TRAFFIC STUDY</b>            |   |
| <b>PORTSMOUTH, NH</b>                 |   |
| <b>SITE GENERATED TRAFFIC VOLUMES</b> |   |
| DATE: 06/01/2023                      |  |
| SCALE: NTS                            |   |
| FIGURE 6                              |   |

Jun 01, 2023-10:34am Plotted By: RCase Tighe & Bond, Inc.: J:\L07000 Lonza Biologics Expansion was 1576F\026\_Project Albacore\Drawings\AutoCAD\Figures\L0700-026 Traffic Volume Figures.dwg





|  |  |
|--|--|
| <b>100 NEW HAMPSHIRE AVENUE<br/>PORTSMOUTH, NH</b> |  |
| SITE GENERATED<br>TRAFFIC VOLUMES - PASSENGER CARS |  |
| DATE: 02/16/2023                                   |  |
| SCALE: NTS   |  |
| FIGURE 7   |  |

**APPENDIX J**  
Collision History Summary

**Intersection Collision History Summary**Intersection: **Pease Boulevard** at **US Route 4 Southbound Ramps****COLLISION TYPE**

|                      | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|----------------------|-------------|-------------|-------------|--------------|----------------|
| Angle                | 1           | 0           | 0           | 1            | 50.0%          |
| Single Vehicle Crash | 1           | 0           | 0           | 1            | 50.0%          |
| <b>TOTAL</b>         | <b>2</b>    | <b>0</b>    | <b>0</b>    | <b>2</b>     | <b>100%</b>    |

**COLLISION EVENT**

|               | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------|-------------|-------------|-------------|--------------|----------------|
| Motor Vehicle | 2           | 0           | 0           | 2            | 100.0%         |
| <b>TOTAL</b>  | <b>2</b>    | <b>0</b>    | <b>0</b>    | <b>2</b>     | <b>100%</b>    |

**SEVERITY**

|                            | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|----------------------------|-------------|-------------|-------------|--------------|----------------|
| Property Damage Only (PDO) | 2           | 0           | 0           | 2            | 100.0%         |
| <b>TOTAL</b>               | <b>2</b>    | <b>0</b>    | <b>0</b>    | <b>2</b>     | <b>100%</b>    |

**Day & Time**

|                  | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|------------------|-------------|-------------|-------------|--------------|----------------|
| Weekday Off-Peak | 2           | 0           | 0           | 2            | 100.0%         |
| <b>TOTAL</b>     | <b>2</b>    | <b>0</b>    | <b>0</b>    | <b>2</b>     | <b>100%</b>    |

**Intersection Collision History Summary**

Intersection:

Gosling Road

at

US Route 4 Northbound Ramps

**COLLISION TYPE**

|              | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|--------------|-------------|-------------|-------------|--------------|----------------|
| Angle        | 1           | 0           | 0           | 1            | 25.0%          |
| Rear-End     | 1           | 1           | 1           | 3            | 75.0%          |
| <b>TOTAL</b> | <b>2</b>    | <b>1</b>    | <b>1</b>    | <b>4</b>     | <b>100%</b>    |

**COLLISION EVENT**

|               | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------|-------------|-------------|-------------|--------------|----------------|
| Motor Vehicle | 2           | 1           | 1           | 4            | 100.0%         |
| <b>TOTAL</b>  | <b>2</b>    | <b>1</b>    | <b>1</b>    | <b>4</b>     | <b>100%</b>    |

**SEVERITY**

|                            | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|----------------------------|-------------|-------------|-------------|--------------|----------------|
| Property Damage Only (PDO) | 2           | 1           | 1           | 4            | 100.0%         |
| <b>TOTAL</b>               | <b>2</b>    | <b>1</b>    | <b>1</b>    | <b>4</b>     | <b>100%</b>    |

**Day & Time**

|                  | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|------------------|-------------|-------------|-------------|--------------|----------------|
| Weekday 6-9 A.M. | 0           | 1           | 0           | 1            | 25.0%          |
| Weekday 3-6 P.M. | 1           | 0           | 0           | 1            | 25.0%          |
| Weekday Off-Peak | 0           | 0           | 1           | 1            | 25.0%          |
| Weekend Off-Peak | 1           | 0           | 0           | 1            | 25.0%          |
| <b>TOTAL</b>     | <b>2</b>    | <b>1</b>    | <b>1</b>    | <b>4</b>     | <b>100%</b>    |

**Intersection Collision History Summary**Intersection: **Woodbury Avenue** at **Gosling Road****COLLISION TYPE**

|                           | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------------------|-------------|-------------|-------------|--------------|----------------|
| Angle                     | 0           | 1           | 2           | <b>3</b>     | <b>37.5%</b>   |
| Fixed Object              | 0           | 1           | 0           | <b>1</b>     | <b>12.5%</b>   |
| Rear-End                  | 0           | 1           | 0           | <b>1</b>     | <b>12.5%</b>   |
| Sideswipe, Same Direction | 0           | 1           | 2           | <b>3</b>     | <b>37.5%</b>   |
| <b>TOTAL</b>              | <b>0</b>    | <b>4</b>    | <b>4</b>    | <b>8</b>     | <b>100%</b>    |

**COLLISION EVENT**

|               | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------|-------------|-------------|-------------|--------------|----------------|
| Motor Vehicle | 0           | 4           | 4           | <b>8</b>     | <b>100.0%</b>  |
| <b>TOTAL</b>  | <b>0</b>    | <b>4</b>    | <b>4</b>    | <b>8</b>     | <b>100%</b>    |

**SEVERITY**

|                            | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|----------------------------|-------------|-------------|-------------|--------------|----------------|
| Property Damage Only (PDO) | 0           | 4           | 4           | <b>8</b>     | <b>100.0%</b>  |
| <b>TOTAL</b>               | <b>0</b>    | <b>4</b>    | <b>4</b>    | <b>8</b>     | <b>100%</b>    |

**Day & Time**

|                           | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------------------|-------------|-------------|-------------|--------------|----------------|
| Weekday Off-Peak          | 0           | 3           | 3           | <b>6</b>     | <b>75.0%</b>   |
| Saturday 11 A.M. - 2 P.M. | 0           | 0           | 1           | <b>1</b>     | <b>12.5%</b>   |
| Weekend Off-Peak          | 0           | 1           | 0           | <b>1</b>     | <b>12.5%</b>   |
| <b>TOTAL</b>              | <b>0</b>    | <b>4</b>    | <b>4</b>    | <b>8</b>     | <b>100%</b>    |

**Intersection Collision History Summary**Intersection: **Woodbury Avenue** at **Durgin Lane****COLLISION TYPE**

|              | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|--------------|-------------|-------------|-------------|--------------|----------------|
| Fixed Object | 0           | 1           | 0           | <b>1</b>     | <b>20.0%</b>   |
| Rear-End     | 2           | 1           | 1           | <b>4</b>     | <b>80.0%</b>   |
| <b>TOTAL</b> | <b>2</b>    | <b>2</b>    | <b>1</b>    | <b>5</b>     | <b>100%</b>    |

**COLLISION EVENT**

|               | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------|-------------|-------------|-------------|--------------|----------------|
| Motor Vehicle | 2           | 2           | 1           | <b>5</b>     | <b>100.0%</b>  |
| <b>TOTAL</b>  | <b>2</b>    | <b>2</b>    | <b>1</b>    | <b>5</b>     | <b>100%</b>    |

**SEVERITY**

|                            | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|----------------------------|-------------|-------------|-------------|--------------|----------------|
| Personal Injury            | 0           | 1           | 1           | <b>2</b>     | <b>40.0%</b>   |
| Property Damage Only (PDO) | 2           | 1           | 0           | <b>3</b>     | <b>60.0%</b>   |
| <b>TOTAL</b>               | <b>2</b>    | <b>2</b>    | <b>1</b>    | <b>5</b>     | <b>100%</b>    |

**Day & Time**

|                           | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------------------|-------------|-------------|-------------|--------------|----------------|
| Weekday 6-9 A.M.          | 0           | 0           | 1           | <b>1</b>     | <b>20.0%</b>   |
| Weekday 3-6 P.M.          | 0           | 1           | 0           | <b>1</b>     | <b>20.0%</b>   |
| Saturday 11 A.M. - 2 P.M. | 2           | 0           | 0           | <b>2</b>     | <b>40.0%</b>   |
| Weekend Off-Peak          | 0           | 1           | 0           | <b>1</b>     | <b>20.0%</b>   |
| <b>TOTAL</b>              | <b>2</b>    | <b>2</b>    | <b>1</b>    | <b>5</b>     | <b>100%</b>    |

**Intersection Collision History Summary**Intersection: **Woodbury Avenue** at **Market Street****COLLISION TYPE**

|                           | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------------------|-------------|-------------|-------------|--------------|----------------|
| Angle                     | 1           | 0           | 3           | <b>4</b>     | <b>80.0%</b>   |
| Sideswipe, Same Direction | 0           | 0           | 1           | <b>1</b>     | <b>20.0%</b>   |
| <b>TOTAL</b>              | <b>1</b>    | <b>0</b>    | <b>4</b>    | <b>5</b>     | <b>100%</b>    |

**COLLISION EVENT**

|               | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|---------------|-------------|-------------|-------------|--------------|----------------|
| Motor Vehicle | 1           | 0           | 4           | <b>5</b>     | <b>100.0%</b>  |
| <b>TOTAL</b>  | <b>1</b>    | <b>0</b>    | <b>4</b>    | <b>5</b>     | <b>100%</b>    |

**SEVERITY**

|                            | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|----------------------------|-------------|-------------|-------------|--------------|----------------|
| Personal Injury            | 0           | 0           | 1           | <b>1</b>     | <b>20.0%</b>   |
| Property Damage Only (PDO) | 1           | 0           | 3           | <b>4</b>     | <b>80.0%</b>   |
| <b>TOTAL</b>               | <b>1</b>    | <b>0</b>    | <b>4</b>    | <b>5</b>     | <b>100%</b>    |

**Day & Time**

|                  | <b>2021</b> | <b>2022</b> | <b>2023</b> | <b>Total</b> | <b>Percent</b> |
|------------------|-------------|-------------|-------------|--------------|----------------|
| Weekday 3-6 P.M. | 0           | 0           | 1           | <b>1</b>     | <b>20.0%</b>   |
| Weekday Off-Peak | 0           | 0           | 3           | <b>3</b>     | <b>60.0%</b>   |
| Weekend Off-Peak | 1           | 0           | 0           | <b>1</b>     | <b>20.0%</b>   |
| <b>TOTAL</b>     | <b>1</b>    | <b>0</b>    | <b>4</b>    | <b>5</b>     | <b>100%</b>    |







# City of Portsmouth, New Hampshire

## Site Plan Application Checklist

This site plan application checklist is a tool designed to assist the applicant in the planning process and for preparing the application for Planning Board review. The checklist is required to be completed and uploaded to the Site Plan application in the City's online permitting system. A pre-application conference with a member of the planning department is strongly encouraged as additional project information may be required depending on the size and scope. The applicant is cautioned that this checklist is only a guide and is not intended to be a complete list of all site plan review requirements. Please refer to the Site Plan review regulations for full details.

**Applicant Responsibilities (Section 2.5.2):** Applicable fees are due upon application submittal along with required attachments. The application shall be complete as submitted and provide adequate information for evaluation of the proposed site development. Waiver requests must be submitted in writing with appropriate justification.

Name of Applicant: 100 Durgin Lane Owner, LLC Date Submitted: June 17, 2024

Application # (in City's online permitting): LU 24-62

Site Address: 100 Durgin Lane Map: 239 Lot: 13-2, 16, & 18

| Application Requirements            |  |  |                     |
|-------------------------------------|--|--|---------------------|
| <input checked="" type="checkbox"/> | Required Items for Submittal   | Item Location<br>(e.g. Page or<br>Plan Sheet/Note #) | Waiver<br>Requested |
| <input checked="" type="checkbox"/> | Complete <a href="#">application</a> form submitted via the City's web-based permitting program (2.5.2.1(2.5.2.3A))  | Enclosed   | N/A                 |
| <input checked="" type="checkbox"/> | All application documents, plans, supporting documentation and other materials uploaded to the application form in viewpoint in digital Portable Document Format (PDF). One hard copy of all plans and materials shall be submitted to the Planning Department by the published deadline.<br>(2.5.2.8) | Enclosed   | N/A                 |

| Site Plan Review Application Required Information |   |   |                     |
|---|---|---|---------------------|
| <input checked="" type="checkbox"/>               | Required Items for Submittal  | Item Location<br>(e.g. Page/line or<br>Plan Sheet/Note #) | Waiver<br>Requested |
| <input checked="" type="checkbox"/>               | Statement that lists and describes "green" building components and systems.<br>(2.5.3.1B)   | Enclosed  |                     |
| <input checked="" type="checkbox"/>               | Existing and proposed gross floor area and dimensions of all buildings and statement of uses and floor area for each floor.<br>(2.5.3.1C) | Existing Conditions &<br>Building Floor Plans             | N/A                 |
| <input checked="" type="checkbox"/>               | Tax map and lot number, and current zoning of all parcels under Site Plan Review.<br>(2.5.3.1D)   | Site Plan C-300   | N/A                 |

| <b>Site Plan Review Application Required Information</b> |   |  |                             |
|--|---|--|-----------------------------|
| <input checked="" type="checkbox"/>                      | <b>Required Items for Submittal</b>   | <b>Item Location<br/>(e.g. Page/line or<br/>Plan Sheet/Note #)</b> | <b>Waiver<br/>Requested</b> |
| <input checked="" type="checkbox"/>                      | Owner's name, address, telephone number, and signature. Name, address, and telephone number of applicant if different from owner.<br><b>(2.5.3.1E)</b>  | Enclosed   | N/A                         |
| <input checked="" type="checkbox"/>                      | Names and addresses (including Tax Map and Lot number and zoning districts) of all direct abutting property owners (including properties located across abutting streets) and holders of existing conservation, preservation or agricultural preservation restrictions affecting the subject property.<br><b>(2.5.3.1F)</b> | Existing<br>Conditions Plans                                       | N/A                         |
| <input checked="" type="checkbox"/>                      | Names, addresses and telephone numbers of all professionals involved in the site plan design.<br><b>(2.5.3.1G)</b>  | Cover Sheet  | N/A                         |
| <input checked="" type="checkbox"/>                      | List of reference plans.<br><b>(2.5.3.1H)</b>   | Existing<br>Conditions Plans                                       | N/A                         |
| <input checked="" type="checkbox"/>                      | List of names and contact information of all public or private utilities servicing the site.<br><b>(2.5.3.1I)</b>   | General Notes<br>Sheet G-100                                       | N/A                         |

| <b>Site Plan Specifications</b>     |   |  |                             |
|-------------------------------------|---|--|-----------------------------|
| <input checked="" type="checkbox"/> | <b>Required Items for Submittal</b>   | <b>Item Location<br/>(e.g. Page/line or<br/>Plan Sheet/Note #)</b> | <b>Waiver<br/>Requested</b> |
| <input checked="" type="checkbox"/> | Full size plans shall not be larger than 22 inches by 34 inches with match lines as required, unless approved by the Planning Director..<br><b>(2.5.4.1A)</b> | Required on all plan sheets  | N/A                         |
| <input checked="" type="checkbox"/> | Scale: Not less than 1 inch = 60 feet and a graphic bar scale shall be included on all plans.<br><b>(2.5.4.1B)</b>  | Required on all plan sheets  | N/A                         |
| <input checked="" type="checkbox"/> | GIS data should be referenced to the coordinate system New Hampshire State Plane, NAD83 (1996), with units in feet.<br><b>(2.5.4.1C)</b>                      | Existing<br>Conditions Plans                                       | N/A                         |
| <input checked="" type="checkbox"/> | Plans shall be drawn to scale and stamped by a NH licensed civil engineer.<br><b>(2.5.4.1D)</b>   | Required on all plan sheets  | N/A                         |
| <input checked="" type="checkbox"/> | Wetlands shall be delineated by a NH certified wetlands scientist and so stamped. <b>(2.5.4.1E)</b>   | Wetlands Delineation Report  | N/A                         |
| <input checked="" type="checkbox"/> | Title (name of development project), north point, scale, legend.<br><b>(2.5.4.2A)</b>   | Required on all plan sheets  | N/A                         |
| <input checked="" type="checkbox"/> | Date plans first submitted, date and explanation of revisions.<br><b>(2.5.4.2B)</b>   | Required on all plan sheets  | N/A                         |
| <input checked="" type="checkbox"/> | Individual plan sheet title that clearly describes the information that is displayed.<br><b>(2.5.4.2C)</b>  | Required on all plan sheets  | N/A                         |
| <input checked="" type="checkbox"/> | Source and date of data displayed on the plan.<br><b>(2.5.4.2D)</b>   | Required on all plan sheets  | N/A                         |

**Site Plan Specifications – Required Exhibits and Data**

| <input checked="" type="checkbox"/> | Required Items for Submittal   | Item Location<br>(e.g. Page/line or<br>Plan Sheet/Note #) | Waiver<br>Requested |
|-------------------------------------|--|---|---------------------|
| <input checked="" type="checkbox"/> | <p><b>1. Existing Conditions: (2.5.4.3A)</b></p> <ul style="list-style-type: none"> <li>• Surveyed plan of site showing existing natural and built features;</li> <li>• Existing building footprints and gross floor area;</li> <li>• Existing parking areas and number of parking spaces provided;</li> <li>• Zoning district boundaries;</li> <li>• Existing, required, and proposed dimensional zoning requirements including building and open space coverage, yards and/or setbacks, and dwelling units per acre;</li> <li>• Existing impervious and disturbed areas;</li> <li>• Limits and type of existing vegetation;</li> <li>• Wetland delineation, wetland function and value assessment (including vernal pools);</li> <li>• SFHA, 100-year flood elevation line and BFE data, as required.</li> </ul> | Existing Conditions<br>Plan Sheets                        |                     |
| <input checked="" type="checkbox"/> | <p><b>2. Buildings and Structures: (2.5.4.3B)</b></p> <ul style="list-style-type: none"> <li>• Plan view: Use, size, dimensions, footings, overhangs, 1st fl. elevation;</li> <li>• Elevations: Height, massing, placement, materials, lighting, façade treatments;</li> <li>• Total Floor Area;</li> <li>• Number of Usable Floors;</li> <li>• Gross floor area by floor and use.</li> </ul>  | Site Plans<br>C-300, C-301, C-302                         |                     |
| <input checked="" type="checkbox"/> | <p><b>3. Access and Circulation: (2.5.4.3C)</b></p> <ul style="list-style-type: none"> <li>• Location/width of access ways within site;</li> <li>• Location of curbing, right of ways, edge of pavement and sidewalks;</li> <li>• Location, type, size and design of traffic signing (pavement markings);</li> <li>• Names/layout of existing abutting streets;</li> <li>• Driveway curb cuts for abutting prop. and public roads;</li> <li>• If subdivision; Names of all roads, right of way lines and easements noted;</li> <li>• AASHTO truck turning templates, description of minimum vehicle allowed being a WB-50 (unless otherwise approved by TAC).</li> </ul>   | Site Plans<br>C-300, C-301, C-302                         |                     |
| <input checked="" type="checkbox"/> | <p><b>4. Parking and Loading: (2.5.4.3D)</b></p> <ul style="list-style-type: none"> <li>• Location of off street parking/loading areas, landscaped areas/buffers;</li> <li>• Parking Calculations (# required and the # provided).</li> </ul>  | Site Plans<br>C-300, C-301, C-302                         |                     |
| <input checked="" type="checkbox"/> | <p><b>5. Water Infrastructure: (2.5.4.3E)</b></p> <ul style="list-style-type: none"> <li>• Size, type and location of water mains, shut-offs, hydrants &amp; Engineering data;</li> <li>• Location of wells and monitoring wells (include protective radii).</li> </ul>  | Utility Plans<br>C-501, C-502                             |                     |
| <input checked="" type="checkbox"/> | <p><b>6. Sewer Infrastructure: (2.5.4.3F)</b></p> <ul style="list-style-type: none"> <li>• Size, type and location of sanitary sewage facilities &amp; Engineering data, including any onsite temporary facilities during construction period.</li> </ul>  | Utility Plans<br>C-501, C-502                             |                     |


|                                     |  |   |  |
|-------------------------------------|--|---|--|
| <input checked="" type="checkbox"/> | <b>7. Utilities: (2.5.4.3G)</b> <ul style="list-style-type: none"> <li>The size, type and location of all above &amp; below ground utilities;</li> <li>Size type and location of generator pads, transformers and other fixtures.</li> </ul>   | Utility Plans<br>C-501, C-502               |  |
| <input checked="" type="checkbox"/> | <b>8. Solid Waste Facilities: (2.5.4.3H)</b> <ul style="list-style-type: none"> <li>The size, type and location of solid waste facilities.</li> </ul>  | Building Floor Plans                        |  |
| <input checked="" type="checkbox"/> | <b>9. Storm water Management: (2.5.4.3I)</b> <ul style="list-style-type: none"> <li>The location, elevation and layout of all storm-water drainage.</li> <li>The location of onsite snow storage areas and/or proposed off-site snow removal provisions.</li> <li>Location and containment measures for any salt storage facilities</li> <li>Location of proposed temporary and permanent material storage locations and distance from wetlands, water bodies, and stormwater structures.</li> </ul> | Grading &<br>Drainage Plans<br>C-401, C-402 |  |
| <input checked="" type="checkbox"/> | <b>10. Outdoor Lighting: (2.5.4.3J)</b> <ul style="list-style-type: none"> <li>Type and placement of all lighting (exterior of building, parking lot and any other areas of the site) and photometric plan.</li> </ul>   | Photometrics Plan<br>L4-00                  |  |
| <input checked="" type="checkbox"/> | <b>11. Indicate where dark sky friendly lighting measures have been implemented. (10.1)</b>  | Photometrics Plans<br>L4-00                 |  |
| <input checked="" type="checkbox"/> | <b>12. Landscaping: (2.5.4.3K)</b> <ul style="list-style-type: none"> <li>Identify all undisturbed area, existing vegetation and that which is to be retained;</li> <li>Location of any irrigation system and water source.</li> </ul>   | Landscape Plans<br>L3-00                    |  |
| <input checked="" type="checkbox"/> | <b>13. Contours and Elevation: (2.5.4.3L)</b> <ul style="list-style-type: none"> <li>Existing/Proposed contours (2 foot minimum) and finished grade elevations.</li> </ul>   | Grading & Drainage Plans<br>C-401, C-402    |  |
| <input checked="" type="checkbox"/> | <b>14. Open Space: (2.5.4.3M)</b> <ul style="list-style-type: none"> <li>Type, extent and location of all existing/proposed open space.</li> </ul>   | Site Plans<br>C-300, C-301, C-302           |  |
| <input checked="" type="checkbox"/> | <b>15. All easements, deed restrictions and non-public rights of ways. (2.5.4.3N)</b>  | Existing Conditions<br>Plan Sheets          |  |
| <input checked="" type="checkbox"/> | <b>16. Character/Civic District (All following information shall be included): (2.5.4.3P)</b> <ul style="list-style-type: none"> <li>Applicable Building Height (10.5A21.20 &amp; 10.5A43.30);</li> <li>Applicable Special Requirements (10.5A21.30);</li> <li>Proposed building form/type (10.5A43);</li> <li>Proposed community space (10.5A46).</li> </ul>  | N/A   |  |
| <input checked="" type="checkbox"/> | <b>17. Special Flood Hazard Areas (2.5.4.3Q)</b> <ul style="list-style-type: none"> <li>The proposed development is consistent with the need to minimize flood damage;</li> <li>All public utilities and facilities are located and construction to minimize or eliminate flood damage;</li> <li>Adequate drainage is provided so as to reduce exposure to flood hazards.</li> </ul>   | N/A   |  |

| <b>Other Required Information</b>   |   |  |                             |
|-------------------------------------|---|--|-----------------------------|
| <input checked="" type="checkbox"/> | <b>Required Items for Submittal</b>   | <b>Item Location<br/>(e.g. Page/line or<br/>Plan Sheet/Note #)</b> | <b>Waiver<br/>Requested</b> |
| <input checked="" type="checkbox"/> | Traffic Impact Study or Trip Generation Report, as required.<br><b>(3.2.1-2)</b>  | Enclosed   |                             |
| <input checked="" type="checkbox"/> | Indicate where Low Impact Development Design practices have been incorporated. <b>(7.1)</b>   | Grading and Drainage<br>Plan Sheet C-401, C-402                    |                             |
| <input checked="" type="checkbox"/> | Indicate whether the proposed development is located in a wellhead protection or aquifer protection area. Such determination shall be approved by the Director of the Dept. of Public Works. <b>(7.3.1)</b> | N/A  |                             |
| <input checked="" type="checkbox"/> | Stormwater Management and Erosion Control Plan.<br><b>(7.4)</b>   | Enclosed   |                             |
| <input checked="" type="checkbox"/> | Inspection and Maintenance Plan <b>(7.6.5)</b>  | Enclosed   |                             |

| <b>Final Site Plan Approval Required Information</b> |  |  |                             |
|--|--|--|-----------------------------|
| <input checked="" type="checkbox"/>                  | <b>Required Items for Submittal</b>  | <b>Item Location<br/>(e.g. Page/line or<br/>Plan Sheet/Note #)</b> | <b>Waiver<br/>Requested</b> |
| <input checked="" type="checkbox"/>                  | All local approvals, permits, easements and licenses required, including but not limited to: <ul style="list-style-type: none"> <li>• Waivers;</li> <li>• Driveway permits;</li> <li>• Special exceptions;</li> <li>• Variances granted;</li> <li>• Easements;</li> <li>• Licenses.</li> </ul> <b>(2.5.3.2A)</b>   | Cover Sheet  |                             |
| <input checked="" type="checkbox"/>                  | Exhibits, data, reports or studies that may have been required as part of the approval process, including but not limited to: <ul style="list-style-type: none"> <li>• Calculations relating to stormwater runoff;</li> <li>• Information on composition and quantity of water demand and wastewater generated;</li> <li>• Information on air, water or land pollutants to be discharged, including standards, quantity, treatment and/or controls;</li> <li>• Estimates of traffic generation and counts pre- and post-construction;</li> <li>• Estimates of noise generation;</li> <li>• A Stormwater Management and Erosion Control Plan;</li> <li>• Endangered species and archaeological / historical studies;</li> <li>• Wetland and water body (coastal and inland) delineations;</li> <li>• Environmental impact studies.</li> </ul> <b>(2.5.3.2B)</b> | Enclosed   |                             |
| <input checked="" type="checkbox"/>                  | A document from each of the required private utility service providers indicating approval of the proposed site plan and indicating an ability to provide all required private utilities to the site.<br><b>(2.5.3.2D)</b>   | Enclosed   |                             |

**Final Site Plan Approval Required Information**

| <input checked="" type="checkbox"/> | Required Items for Submittal   | Item Location<br>(e.g. Page/line or<br>Plan Sheet/Note #) | Waiver<br>Requested |
|-------------------------------------|--|---|---------------------|
| <input checked="" type="checkbox"/> | A list of any required state and federal permit applications required for the project and the status of same.<br><b>(2.5.3.2E)</b>   | Cover Sheet   |                     |
| <input checked="" type="checkbox"/> | A note shall be provided on the Site Plan stating: "All conditions on this Plan shall remain in effect in perpetuity pursuant to the requirements of the Site Plan Review Regulations."<br><b>(2.5.4.2E)</b>   | Site Plan<br>Sheet C-300                                  | N/A                 |
| <input checked="" type="checkbox"/> | For site plans that involve land designated as "Special Flood Hazard Areas" (SFHA) by the National Flood Insurance Program (NFIP) confirmation that all necessary permits have been received from those governmental agencies from which approval is required by Federal or State law, including Section 404 of the Federal Water Pollution Control Act Amendments of 1972, 33 U.S.C. 1334.<br><b>(2.5.4.2F)</b>   | N/A   |                     |
| <input checked="" type="checkbox"/> | Plan sheets submitted for recording shall include the following notes:<br>a. "This Site Plan shall be recorded in the Rockingham County Registry of Deeds."<br>b. "All improvements shown on this Site Plan shall be constructed and maintained in accordance with the Plan by the property owner and all future property owners. No changes shall be made to this Site Plan without the express approval of the Portsmouth Planning Director."<br><b>(2.13.3)</b> | Site Plan<br>Sheet C-300                                  | N/A                 |

Applicant's Signature:  Date: 6/17/24



# City of Portsmouth, New Hampshire

## *Subdivision Application Checklist*

This subdivision application checklist is a tool designed to assist the applicant in the planning process and for preparing the application for Planning Board review. A pre-application conference with a member of the planning department is strongly encouraged as additional project information may be required depending on the size and scope. The applicant is cautioned that this checklist is only a guide and is not intended to be a complete list of all subdivision review requirements. Please refer to the Subdivision review regulations for full details.

**Applicant Responsibilities (Section III.C):** Applicable fees are due upon application submittal along with required number of copies of the Preliminary or final plat and supporting documents and studies. Please consult with Planning staff for submittal requirements.

Owner: Oak Street Investment Grade Net Lease Fund Series 2021-2 LLC Date Submitted: \_\_\_\_\_

Applicant: \_\_\_\_\_

Phone Number: \_\_\_\_\_ E-mail: \_\_\_\_\_

Site Address 1: \_\_\_\_\_ Map: \_\_\_\_\_ Lot: \_\_\_\_\_

Site Address 2: \_\_\_\_\_ Map: \_\_\_\_\_ Lot: \_\_\_\_\_

Lots 13-2, 16, & 18

| Application Requirements            |  |   |                  |
|-------------------------------------|--|---|------------------|
| <input checked="" type="checkbox"/> | Required Items for Submittal   | Item Location<br>(e.g. Page or Plan Sheet/Note #) | Waiver Requested |
| <input type="checkbox"/>            | Completed Application form.<br><b>(III.C.2-3)</b>  |   | N/A              |
| <input type="checkbox"/>            | All application documents, plans, supporting documentation and other materials provided in digital Portable Document Format (PDF) on compact disc, DVD or flash drive.<br><b>(III.C.4)</b> |   | N/A              |

| Requirements for Preliminary/Final Plat |   |  |  |                  |
|---|---|--|--|------------------|
| <input checked="" type="checkbox"/>     | Required Items for Submittal  | Item Location<br>(e.g. Page/line or Plan Sheet/Note #) | Required for Preliminary / Final Plat  | Waiver Requested |
| <input type="checkbox"/>                | Name and address of record owner, any option holders, descriptive name of subdivision, engineer and/or surveyor or name of person who prepared the plat.<br><b>(Section IV.1/V.1)</b> | Cover Sheet  | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat | N/A              |

| Requirements for Preliminary/Final Plat |   |   |  |                     |
|---|---|---|--|---------------------|
| <input checked="" type="checkbox"/>     | Required Items for Submittal  | Item Location<br>(e.g. Page/line or<br>Plan Sheet/Note #)                                   | Required for<br>Preliminary / Final<br>Plat  | Waiver<br>Requested |
| <input type="checkbox"/>                | <p><b>Preliminary Plat</b><br/>Names and addresses of all adjoining property owners. <b>(Section IV.2)</b></p> <p><b>Final Plat</b><br/>Names and addresses of all abutting property owners, locations of buildings within one hundred (100) feet of the parcel, and any new house numbers within the subdivision. <b>(Section V.2)</b></p>   | Existing Conditions Plans   | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat | N/A                 |
| <input type="checkbox"/>                | North point, date, and bar scale. <b>(Section IV.3/V3)</b>  | Required on all Plan Sheets   | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat | N/A                 |
| <input type="checkbox"/>                | Zoning classification and minimum yard dimensions required. <b>(Section IV.4/V.4)</b>   | Site Plan C-300   | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat | N/A                 |
| <input type="checkbox"/>                | <p><b>Preliminary Plat</b><br/>Scale (not to be smaller than one hundred (100) feet = 1 inch) and location map (at a scale of 1" = 1000'). <b>(Section IV.5)</b></p> <p><b>Final Plat</b><br/>Scale (not to be smaller than 1"=100'), Location map (at a scale of 1"=1,000') showing the property being subdivided and its relation to the surrounding area within a radius of 2,000 feet. Said location map shall delineate all streets and other major physical features that my either affect or be affected by the proposed development. <b>(Section V.5)</b></p> | <p>Existing Conditions Plans</p> <p>Lot Line Adjustment Exhibit</p>                         | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat | N/A                 |
| <input type="checkbox"/>                | Location and approximate dimensions of all existing and proposed property lines including the entire area proposed to be subdivided, the areas of proposed lots, and any adjacent parcels in the same ownership. <b>(Section IV.6)</b>  | <p>Existing Conditions Plans</p> <p>Lot Line Adjustment Exhibit</p>                         | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |
| <input type="checkbox"/>                | Dimensions and areas of all lots and any and all property to be dedicated or reserved for schools, parks, playgrounds, or other public purpose. Dimensions shall include radii and length of all arcs and calculated bearing for all straight lines. <b>(Section V.6/ IV.7)</b>   | Lot Line Adjustment Exhibit   | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat | N/A                 |
| <input type="checkbox"/>                | Location, names, and present widths of all adjacent streets, with a designation as to whether public or private and approximate location of existing utilities to be used. Curbs and sidewalks shall be shown. <b>(Section IV.8/V.7)</b>  | <p>Existing Conditions Plan<br/>Site Plan C-300</p> <p>Utilities Plans C-501,<br/>C-502</p> | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |



| Requirements for Preliminary/Final Plat |  |  |  |                     |
|---|--|--|--|---------------------|
| <input checked="" type="checkbox"/>     | Required Items for Submittal   | Item Location<br>(e.g. Page/line or<br>Plan Sheet/Note #)  | Required for<br>Preliminary / Final<br>Plat  | Waiver<br>Requested |
| <input type="checkbox"/>                | Location of significant physical features, including bodies of water, watercourses, wetlands, railroads, important vegetation, stone walls and soils types that may influence the design of the subdivision.<br><b>(Section IV.9/V.8)</b>  | Existing Conditions Plans  | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |
| <input type="checkbox"/>                | <b>Preliminary Plat</b><br>Proposed locations, widths and other dimensions of all new streets and utilities, including water mains, storm and sanitary sewer mains, catch basins and culverts, street lights, fire hydrants, sewerage pump stations, etc. <b>(Section IV.10)</b><br><b>Final Plat</b><br>Proposed locations and profiles of all proposed streets and utilities, including water mains, storm and sanitary sewer mains, catchbasins and culverts, together with typical cross sections. Profiles shall be drawn to a horizontal scale of 1"=50' and a vertical scale of 1"=5', showing existing centerline grade, existing left and right sideline grades, and proposed centerline grade.<br><b>(Section V.9)</b> | Existing Conditions Plans<br><br>Site Plan Sheet<br>C-301, C-302<br>Grading, Drainage, &<br>Erosion Control Plan<br>C-401, C-402<br>Utilities Plan Sheet<br>C-501, C-502 | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |
| <input type="checkbox"/>                | When required by the Board, the plat shall be accompanied by profiles of proposed street grades, including extensions for a reasonable distance beyond the subject land; also grades and sizes of proposed utilities.<br><b>(Section IV.10)</b>  | N/A  | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |
| <input type="checkbox"/>                | Base flood elevation (BFE) for subdivisions involving greater than five (5) acres or fifty (50) lots.<br><b>(Section IV.11)</b>  | N/A  | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |
| <input type="checkbox"/>                | For subdivisions of five (5) lots or more, or at the discretion of the Board otherwise, the preliminary plat shall show contours at intervals no greater than two (2) feet. Contours shall be shown in dotted lines for existing natural surface and in solid lines for proposed final grade, together with the final grade elevations shown in figures at all lot corners. If existing grades are not to be changed, then the contours in these areas shall be solid lines.<br><b>(Section IV.12/ V.12)</b>   | Existing Conditions Plans<br><br>Grading, Drainage,<br>and Erosion<br>Control Plans<br>C-401, C-402  | <input checked="" type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |

| Requirements for Preliminary/Final Plat |   |   |   |                     |
|---|---|---|---|---------------------|
| <input checked="" type="checkbox"/>     | Required Items for Submittal  | Item Location<br>(e.g. Page/line or<br>Plan Sheet/Note #) | Required for<br>Preliminary / Final<br>Plat   | Waiver<br>Requested |
| <input type="checkbox"/>                | Dates and permit numbers of all necessary permits from governmental agencies from which approval is required by Federal or State law.<br><b>(Section V.10)</b>                                      | Cover Sheet   | <input type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |
| <input type="checkbox"/>                | For subdivisions involving greater than five (5) acres or fifty (50) lots, the final plat shall show hazard zones and shall include elevation data for flood hazard zones.<br><b>(Section V.11)</b> | N/A   | <input type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |
| <input type="checkbox"/>                | Location of all permanent monuments.<br><b>(Section V.12)</b>   |   | <input type="checkbox"/> Preliminary Plat<br><input checked="" type="checkbox"/> Final Plat |                     |



| <input checked="" type="checkbox"/> | Required Items for Submittal                                | Item Location<br>(e.g. Page/line or<br>Plan Sheet/Note #) | Waiver<br>Requested |
|-------------------------------------|---|---|---------------------|
| <input type="checkbox"/>            | <b>15. Easements (VI.15)</b><br>a. Utilities<br>b. Drainage | Utility & Drainage<br>Easement Plan Sheet<br>C-601        |                     |
| <input type="checkbox"/>            | <b>16. Monuments: (VI.16)</b>                               |   |                     |
| <input type="checkbox"/>            | <b>17. Benchmarks: (VI.17)</b>                              |   |                     |
| <input type="checkbox"/>            | <b>18. House Numbers (VI.18)</b>                            |   |                     |

| Design Standards         |  |  |                     |
|--------------------------|--|--|---------------------|
|                          | Required Items for Submittal   | Indicate compliance and/or<br>provide explanation as to<br>alternative design  | Waiver<br>Requested |
| <input type="checkbox"/> | <b>1. Streets have been designed according to the design standards required under Section (VII.1).</b><br>a. Clearing<br>b. Excavation<br>c. Rough Grade and Preparation of Sub-Grade<br>d. Base Course<br>e. Street Paving<br>f. Side Slopes<br>g. Approval Specifications<br>h. Curbing<br>i. Sidewalks<br>j. Inspection and Methods | Site Plan Sheet<br>C-300 - C-302<br>Grading, Drainage, &<br>Erosion Control Plan<br>C-401, C-402<br>Utilities Plan Sheet<br>C-501, C-502 |                     |
| <input type="checkbox"/> | <b>2. Storm water Sewers and Other Drainage Appurtenances have been designed according to the design standards required under Section (VII.2).</b><br>a. Design<br>b. Standards of Construction  | Grading, Drainage, &<br>Erosion Control Plan<br>C-401, C-402   |                     |
| <input type="checkbox"/> | <b>3. Sanitary Sewers have been designed according to the design standards required under Section (VII.3).</b><br>a. Design<br>b. Lift Stations<br>c. Materials<br>d. Construction Standards   | Utilities Plan Sheet<br>C-501, C-502   |                     |
| <input type="checkbox"/> | <b>4. Water Mains and Fire Hydrants have been designed according to the design standards required under Section (VII.4).</b><br>a. Connections to Lots<br>b. Design and Construction<br>c. Materials<br>d. Notification Prior to Construction  | Utilities Plan Sheet<br>C-501, C-502   |                     |

Applicant's/Representative's Signature:  Date: \_\_\_\_\_

<sup>1</sup> See City of Portsmouth, NH Subdivision Rules and Regulations for details.  
Subdivision Application Checklist/January 2018

May 21, 2024

1700 Lafayette Road  
Portsmouth, NH 03801

Trevor S Emmons  
603-332-7515  
Trevor.emmons@eversource.com

Benjamin Curcio, PE  
Tighe & Bond, Inc.  
177 Corporate Drive  
Portsmouth, NH 03801

Dear Mr. Curcio:

I am responding to your request to confirm the availability of electric service for the proposed 100 Durgin Lane project being constructed for/by 100 Durgin Lane Owner, LLC.

The proposed project consists of sixteen (16) 3-story and 4-story buildings with 360 residential units, in addition to a single-story community building. The proposed development will be constructed off of Durgin Lane in Portsmouth, NH.

The developer will be responsible for the installation of all underground/overhead facilities and infrastructure required to service the new buildings. The service will be as shown on attached marked up Utility Plans C-501 and C-502. The proposed building service will be fed from adjacent existing overhead services to be determined by Eversource Engineering and as depicted on utility plans C-501 and C-502. The developer will work with Eversource to obtain all necessary easements and licenses for the proposed underground/overhead facilities listed above.

This letter serves as confirmation that Eversource has sufficient capacity in the area to provide service to this proposed development. The cost of extending service to the aforementioned location and any associated infrastructure improvements necessary to provide service will be borne by the developer unless otherwise agreed upon.

The attached drawings titled "Proposed Multi-Family Development – Utilities Plan" dated 4/22/2024, shows revised transformer locations to service your proposed project.

Eversource approves the locations shown; assuming the final installed locations meet all clearances, physical protection, and access requirements as outlined in Eversource's "Information & Requirements For Electric Supply" (<https://www.eversource.com/content/docs/default-source/pdfs/requirements-for-electric-service-connections.pdf?sfvrsn=2>).

If you require additional information or I can be of further assistance please do not hesitate to contact me at our Rochester Office, 603-332-7515

Respectfully,

Trevor Emmons  
Eastern Regional Engineer, Eversource



cc: Sam Bosse, Distribution Engineering Manager, Eversource  
Thomas Boulter, Eastern Region Operations Manager, Eversource  
Nickolai Kosko, Field Supervisor, Electric Design, Eversource



**PROPOSED  
MULTI-FAMILY  
DEVELOPMENT**

**100 DURGIN  
LANE OWNER,  
LLC**


**100 DURGIN LANE  
PORTSMOUTH,  
NEW HAMPSHIRE**

| MARK | DATE     | DESCRIPTION       |
|------|----------|-------------------|
| 1    | 03/20/24 | ISSUE FOR PERMITS |
| 2    | 03/20/24 | ISSUE FOR PERMITS |
| 3    | 03/20/24 | ISSUE FOR PERMITS |
| 4    | 03/20/24 | ISSUE FOR PERMITS |
| 5    | 03/20/24 | ISSUE FOR PERMITS |
| 6    | 03/20/24 | ISSUE FOR PERMITS |
| 7    | 03/20/24 | ISSUE FOR PERMITS |
| 8    | 03/20/24 | ISSUE FOR PERMITS |
| 9    | 03/20/24 | ISSUE FOR PERMITS |
| 10   | 03/20/24 | ISSUE FOR PERMITS |
| 11   | 03/20/24 | ISSUE FOR PERMITS |
| 12   | 03/20/24 | ISSUE FOR PERMITS |
| 13   | 03/20/24 | ISSUE FOR PERMITS |
| 14   | 03/20/24 | ISSUE FOR PERMITS |
| 15   | 03/20/24 | ISSUE FOR PERMITS |
| 16   | 03/20/24 | ISSUE FOR PERMITS |
| 17   | 03/20/24 | ISSUE FOR PERMITS |
| 18   | 03/20/24 | ISSUE FOR PERMITS |
| 19   | 03/20/24 | ISSUE FOR PERMITS |
| 20   | 03/20/24 | ISSUE FOR PERMITS |
| 21   | 03/20/24 | ISSUE FOR PERMITS |
| 22   | 03/20/24 | ISSUE FOR PERMITS |
| 23   | 03/20/24 | ISSUE FOR PERMITS |
| 24   | 03/20/24 | ISSUE FOR PERMITS |
| 25   | 03/20/24 | ISSUE FOR PERMITS |
| 26   | 03/20/24 | ISSUE FOR PERMITS |
| 27   | 03/20/24 | ISSUE FOR PERMITS |
| 28   | 03/20/24 | ISSUE FOR PERMITS |
| 29   | 03/20/24 | ISSUE FOR PERMITS |
| 30   | 03/20/24 | ISSUE FOR PERMITS |
| 31   | 03/20/24 | ISSUE FOR PERMITS |
| 32   | 03/20/24 | ISSUE FOR PERMITS |
| 33   | 03/20/24 | ISSUE FOR PERMITS |
| 34   | 03/20/24 | ISSUE FOR PERMITS |
| 35   | 03/20/24 | ISSUE FOR PERMITS |
| 36   | 03/20/24 | ISSUE FOR PERMITS |
| 37   | 03/20/24 | ISSUE FOR PERMITS |
| 38   | 03/20/24 | ISSUE FOR PERMITS |
| 39   | 03/20/24 | ISSUE FOR PERMITS |
| 40   | 03/20/24 | ISSUE FOR PERMITS |
| 41   | 03/20/24 | ISSUE FOR PERMITS |
| 42   | 03/20/24 | ISSUE FOR PERMITS |
| 43   | 03/20/24 | ISSUE FOR PERMITS |
| 44   | 03/20/24 | ISSUE FOR PERMITS |
| 45   | 03/20/24 | ISSUE FOR PERMITS |
| 46   | 03/20/24 | ISSUE FOR PERMITS |
| 47   | 03/20/24 | ISSUE FOR PERMITS |
| 48   | 03/20/24 | ISSUE FOR PERMITS |
| 49   | 03/20/24 | ISSUE FOR PERMITS |
| 50   | 03/20/24 | ISSUE FOR PERMITS |
| 51   | 03/20/24 | ISSUE FOR PERMITS |
| 52   | 03/20/24 | ISSUE FOR PERMITS |
| 53   | 03/20/24 | ISSUE FOR PERMITS |
| 54   | 03/20/24 | ISSUE FOR PERMITS |
| 55   | 03/20/24 | ISSUE FOR PERMITS |
| 56   | 03/20/24 | ISSUE FOR PERMITS |
| 57   | 03/20/24 | ISSUE FOR PERMITS |
| 58   | 03/20/24 | ISSUE FOR PERMITS |
| 59   | 03/20/24 | ISSUE FOR PERMITS |
| 60   | 03/20/24 | ISSUE FOR PERMITS |
| 61   | 03/20/24 | ISSUE FOR PERMITS |
| 62   | 03/20/24 | ISSUE FOR PERMITS |
| 63   | 03/20/24 | ISSUE FOR PERMITS |
| 64   | 03/20/24 | ISSUE FOR PERMITS |
| 65   | 03/20/24 | ISSUE FOR PERMITS |
| 66   | 03/20/24 | ISSUE FOR PERMITS |
| 67   | 03/20/24 | ISSUE FOR PERMITS |
| 68   | 03/20/24 | ISSUE FOR PERMITS |
| 69   | 03/20/24 | ISSUE FOR PERMITS |
| 70   | 03/20/24 | ISSUE FOR PERMITS |
| 71   | 03/20/24 | ISSUE FOR PERMITS |
| 72   | 03/20/24 | ISSUE FOR PERMITS |
| 73   | 03/20/24 | ISSUE FOR PERMITS |
| 74   | 03/20/24 | ISSUE FOR PERMITS |
| 75   | 03/20/24 | ISSUE FOR PERMITS |
| 76   | 03/20/24 | ISSUE FOR PERMITS |
| 77   | 03/20/24 | ISSUE FOR PERMITS |
| 78   | 03/20/24 | ISSUE FOR PERMITS |
| 79   | 03/20/24 | ISSUE FOR PERMITS |
| 80   | 03/20/24 | ISSUE FOR PERMITS |
| 81   | 03/20/24 | ISSUE FOR PERMITS |
| 82   | 03/20/24 | ISSUE FOR PERMITS |
| 83   | 03/20/24 | ISSUE FOR PERMITS |
| 84   | 03/20/24 | ISSUE FOR PERMITS |
| 85   | 03/20/24 | ISSUE FOR PERMITS |
| 86   | 03/20/24 | ISSUE FOR PERMITS |
| 87   | 03/20/24 | ISSUE FOR PERMITS |
| 88   | 03/20/24 | ISSUE FOR PERMITS |
| 89   | 03/20/24 | ISSUE FOR PERMITS |
| 90   | 03/20/24 | ISSUE FOR PERMITS |
| 91   | 03/20/24 | ISSUE FOR PERMITS |
| 92   | 03/20/24 | ISSUE FOR PERMITS |
| 93   | 03/20/24 | ISSUE FOR PERMITS |
| 94   | 03/20/24 | ISSUE FOR PERMITS |
| 95   | 03/20/24 | ISSUE FOR PERMITS |
| 96   | 03/20/24 | ISSUE FOR PERMITS |
| 97   | 03/20/24 | ISSUE FOR PERMITS |
| 98   | 03/20/24 | ISSUE FOR PERMITS |
| 99   | 03/20/24 | ISSUE FOR PERMITS |
| 100  | 03/20/24 | ISSUE FOR PERMITS |

UTILITIES PLAN

SCALE: AS SHOWN

C-501



SEE SHEET C-501 FOR DEVELOPMENT PLAN NOTES & LEGEND



**PROPOSED MULTI-FAMILY DEVELOPMENT**

100 DURGIN LANE OWNER, LLC


100 DURGIN LANE PORTSMOUTH, NEW HAMPSHIRE

| MARK | DATE     | DESCRIPTION     |
|------|----------|-----------------|
| A    | 11/20/24 | FILE SUBMISSION |
| B    | 11/20/24 | REVISION        |
| C    | 11/20/24 | REVISION        |
| D    | 11/20/24 | REVISION        |
| E    | 11/20/24 | REVISION        |
| F    | 11/20/24 | REVISION        |
| G    | 11/20/24 | REVISION        |
| H    | 11/20/24 | REVISION        |
| I    | 11/20/24 | REVISION        |
| J    | 11/20/24 | REVISION        |
| K    | 11/20/24 | REVISION        |
| L    | 11/20/24 | REVISION        |
| M    | 11/20/24 | REVISION        |
| N    | 11/20/24 | REVISION        |
| O    | 11/20/24 | REVISION        |
| P    | 11/20/24 | REVISION        |
| Q    | 11/20/24 | REVISION        |
| R    | 11/20/24 | REVISION        |
| S    | 11/20/24 | REVISION        |
| T    | 11/20/24 | REVISION        |
| U    | 11/20/24 | REVISION        |
| V    | 11/20/24 | REVISION        |
| W    | 11/20/24 | REVISION        |
| X    | 11/20/24 | REVISION        |
| Y    | 11/20/24 | REVISION        |
| Z    | 11/20/24 | REVISION        |

UTILITIES PLAN

SCALE: AS SHOWN

C-502



SEE SHEET C-101 FOR DIMENSIONS, PLAN NOTES & LEGEND



GRAPHIC SCALE

Small text at the bottom of the page containing project details, dates, and contact information for Tight & Bonk.

|             |  |           |  |      |  |
|-------------|--|-----------|--|------|--|
| Project     |  | Catalog # |  | Type |  |
| Prepared by |  | Notes     |  | Date |  |



# McGraw-Edison

## GALN Galleon II

Area / Site Luminaire

### Product Features



### Product Certifications



### Interactive Menu

- Ordering Information [page 2](#)
- Mounting Details [page 3](#)
- Optical Distributions [page 6](#)
- Product Specifications [page 6](#)
- Energy and Performance Data [page 7](#)
- Control Options [page 12](#)

### Quick Facts


- Lumen packages range from 3,300 - 73,500 (33W - 552W)
- 17 optical distributions
- Efficacy up to 159 lumens per watt

### Connected Systems


- WaveLinx Lite
- WaveLinx

### Dimensional Details

Standard Pole Mount Arm



Pole Drilling Pattern  
Type "N"



| Number of Light Squares | Width "A" | Housing Length "B" | Weight with Standard or QM Arm | EPA with Standard or QM Arm |
|-------------------------|-----------|--------------------|--------------------------------|-----------------------------|
| 1-4                     | 16"       | 22"                | 29 lb                          | 0.95                        |
| 5-6                     | 22"       | 22"                | 39 lb                          | 0.95                        |
| 7-9                     | 22"       | 28-1/8"            | 48 lb                          | 1.1                         |

**NOTES:**  
For arm selection requirements and additional line art, see Mounting Details section.

**NOTES:**  
1. Visit <https://www.designlights.org/search/> to confirm qualification. Not all product variations are DLC qualified.  
2. IDA Certified (3000K CCT and warmer only, fixed mounting options)




Ordering Information

SAMPLE NUMBER: GALN-SA4C-740-U-T4FT-GM


| Product Family <sup>1,2</sup>  | Light Engine   |  | Color Temperature   | Voltage   | Distribution   | Mounting  | Finish   |
|--|--|--|---|---|--|---|--|
|  | Configuration  | Drive Current  |   |   |  |   |  |
| <b>GALN</b> =Galleon II<br><b>BAA-GALN</b> =Galleon II Buy American Act Compliant <sup>26</sup><br><b>TAA-GALN</b> =Galleon II Trade Agreements Act Compliant <sup>26</sup>  | <b>SA1</b> =1 Square<br><b>SA2</b> =2 Squares<br><b>SA3</b> =3 Squares<br><b>SA4</b> =4 Squares<br><b>SA5</b> =5 Squares<br><b>SA6</b> =6 Squares<br><b>SA7</b> =7 Squares<br><b>SA8</b> =8 Squares<br><b>SA9</b> =9 Squares | <b>A</b> =600mA<br><b>B</b> =800mA<br><b>C</b> =1000mA<br><b>D</b> =1200mA <sup>4,16</sup><br><b>Z</b> =Configured <sup>22</sup> | <b>722</b> =70CRI, 2200K<br><b>727</b> =70CRI, 2700K<br><b>730</b> =70CRI, 3000K<br><b>735</b> =70CRI, 3500K<br><b>740</b> =70CRI, 4000K<br><b>750</b> =70CRI, 5000K<br><b>760</b> =70CRI, 6000K<br><b>827</b> =80CRI, 2700K<br><b>830</b> =80CRI, 3000K<br><b>835</b> =80CRI, 3500K<br><b>840</b> =80CRI, 4000K<br><b>930</b> =90CRI, 3000K<br><b>935</b> =90CRI, 3500K<br><b>940</b> =90CRI, 4000K<br><b>950</b> =90CRI, 5000K<br><b>AMB</b> =Amber, 590nm <sup>14,16</sup>   | <b>U</b> =120-277V<br><b>H</b> =347V-480V <sup>7,29</sup><br>1=120V<br>2=208V<br>3=240V<br>4=277V<br>8=480V <sup>7,29</sup><br>9=347V <sup>7</sup><br><b>DV</b> =277V-480V DuraVolt Drivers <sup>28,29,30</sup> | <b>T1</b> =Type I<br><b>T2</b> =Type II<br><b>T2R</b> =Type II Roadway<br><b>T3</b> =Type III<br><b>T3R</b> =Type III Roadway<br><b>T4FT</b> =Type IV Forward Throw<br><b>T4W</b> =Type IV Wide<br><b>5N</b> =Type V Narrow<br><b>5MQ</b> =Type V Square Medium<br><b>5W</b> =Type V Square Wide<br><b>SL2</b> =Type II w/Spill Control<br><b>SL3</b> =Type III w/Spill Control<br><b>SL4</b> =Type IV w/Spill Control<br><b>SL</b> =90° Spill Light Eliminator Left<br><b>SLR</b> =90° Spill Light Eliminator Right<br><b>RW</b> =Rectangular Wide Type I<br><b>AF</b> =Automotive Frontline  | <b>[Blank]</b> =Standard Pole Mount Arm<br><b>QU</b> =Quick Mount Universal Arm<br><b>QM</b> =Pole Mount Arm with Quick Mount Adaptor<br><b>PA</b> =Pole Mount, Adjustable<br><b>SP</b> =3" Slipfitter, Adjustable <sup>8</sup><br><b>SP2</b> =2-3/8" Slipfitter, Adjustable <sup>8</sup><br><b>QMA</b> =Quick Mount Mast Arm, Fixed<br><b>MA</b> =Mast Arm, Fixed<br><b>WM</b> =Wall Mount, Fixed<br><b>WA</b> =Wall Mount, Adjustable<br><b>UP</b> =Upswept Arm | <b>AP</b> =Grey<br><b>BZ</b> =Bronze<br><b>BK</b> =Black<br><b>DP</b> =Dark Platinum<br><b>GM</b> =Graphite Metallic<br><b>WH</b> =White<br><b>RALXX</b> =Custom Color |
| Options (Add as Suffix)  |  |  | Controls and Systems Options (Add as Suffix)  |   | Accessories (Order Separately) <sup>27</sup>   |   |  |
| <b>DIM</b> =External 0-10V Dimming Leads <sup>19</sup><br><b>F</b> =Single Fuse (120, 277 or 347V Specify Voltage)<br><b>FF</b> =Double Fuse (208, 240 or 480V Specify Voltage)<br><b>2K</b> =20kV UL 1449 fused surge protective device <sup>10</sup><br><b>2L</b> =Two Circuits <sup>10</sup><br><b>HA</b> =50°C High Ambient<br><b>HSS</b> =Installed House Side Shield <sup>17</sup><br><b>GRSBK</b> =Glare Reducing Shield, Black <sup>22</sup><br><b>GRSWH</b> =Glare Reducing Shield, White <sup>22</sup><br><b>LCF</b> =Light Square Trim Painted to Match Housing <sup>25</sup><br><b>TH</b> =Tool-less Door Hardware <sup>5</sup><br><b>CC</b> =Coastal Construction finish <sup>3</sup><br><b>L90</b> =Optics Rotated 90° Left<br><b>R90</b> =Optics Rotated 90° Right<br><b>AHD145</b> =After Hours Dim, 5 Hours <sup>21</sup><br><b>AHD245</b> =After Hours Dim, 6 Hours <sup>21</sup><br><b>AHD255</b> =After Hours Dim, 7 Hours <sup>21</sup><br><b>AHD355</b> =After Hours Dim, 8 Hours <sup>21</sup><br><b>DALI</b> =DALI Drivers   |  |  | <b>BPC</b> =Button Type Photocontrol. Must specify voltage 120V, 208V, 240V or 277V. <sup>6</sup><br><b>PR</b> =NEMA 3-PIN Photocontrol Receptacle<br><b>PR7</b> =NEMA 7-PIN Photocontrol Receptacle <sup>20</sup><br><b>FADC</b> =Field Adjustable Dimming Controller <sup>31</sup><br><b>PSC</b> =Photocontrol Shorting Cap<br><b>SPB2</b> =Dimming Motion Sensor, 9'-20' mounting <sup>23</sup><br><b>SPB4</b> =Dimming Motion Sensor, 21'-40' mounting <sup>23</sup><br><b>SPB2/X</b> =Dimming Motion Sensor, limited square count, 9'-20' mounting <sup>23</sup><br><b>SPB4/X</b> =Dimming Motion Sensor, limited square count, 21'-40' mounting <sup>23</sup><br><b>MS/DIM-L20</b> =Motion Sensor for Dimming Operation, 9'-20' Mounting <sup>33</sup><br><b>MS/DIM-L40</b> =Motion Sensor for Dimming Operation, 21'-40' Mounting <sup>33</sup><br><b>WLS2XX</b> =WaveLinX Lite, SR Driver, Dimming Motion and Daylight, Bluetooth Programmable, 7' - 15' Mounting <sup>18,12,34</sup><br><b>WLS4XX</b> =WaveLinX Lite, SR Driver, Dimming Motion and Daylight, Bluetooth Programmable, 15' - 40' Mounting <sup>18,12,34</sup><br><b>WPS2XX</b> =WaveLinX Pro, SR Driver, Dimming Motion and Daylight, WAC Programmable, 7' - 15' Mounting <sup>18,12,13,34</sup><br><b>WPS4XX</b> =WaveLinX Pro, SR Driver, Dimming Motion and Daylight, WAC Programmable, 15' - 40' Mounting <sup>18,12,13,34</sup><br><b>DIM10-L20</b> =Synapse Occupancy Sensor (9'-20' Mounting) <sup>18</sup><br><b>DIM10-L40</b> =Synapse Occupancy Sensor (21'-40' Mounting) <sup>18</sup> |   | <b>OA/RA1016</b> =NEMA Photocontrol Multi-Tap - 105-285V<br><b>OA/RA1027</b> =NEMA Photocontrol - 480V<br><b>OA/RA1201</b> =NEMA Photocontrol - 347V<br><b>OA/RA1013</b> =Photocontrol Shorting Cap<br><b>OA/RA1014</b> =120V Photocontrol<br><b>MA1252</b> =10kV Surge Module Replacement<br><b>MA1036-XX</b> =Single Tenon Adapter for 2-3/8" O.D. Tenon<br><b>MA1037-XX</b> =2@180° Tenon Adapter for 2-3/8" O.D. Tenon<br><b>MA1197-XX</b> =3@120° Tenon Adapter for 2-3/8" O.D. Tenon<br><b>MA1188-XX</b> =4@90° Tenon Adapter for 2-3/8" O.D. Tenon<br><b>MA1189-XX</b> =2@90° Tenon Adapter for 2-3/8" O.D. Tenon<br><b>MA1190-XX</b> =3@90° Tenon Adapter for 2-3/8" O.D. Tenon<br><b>MA1191-XX</b> =2@120° Tenon Adapter for 2-3/8" O.D. Tenon<br><b>MA1038-XX</b> =Single Tenon Adapter for 3-1/2" O.D. Tenon<br><b>MA1039-XX</b> =2@180° Tenon Adapter for 3-1/2" O.D. Tenon<br><b>MA1192-XX</b> =3@120° Tenon Adapter for 3-1/2" O.D. Tenon<br><b>MA1193-XX</b> =4@90° Tenon Adapter for 3-1/2" O.D. Tenon<br><b>MA1194-XX</b> =2@90° Tenon Adapter for 3-1/2" O.D. Tenon<br><b>MA1195-XX</b> =3@90° Tenon Adapter for 3-1/2" O.D. Tenon<br><b>SRA238</b> =Adapter kit for mounting 3" SP arm to 2-3/8" O.D. vertical tenon<br><b>FSIR-100</b> =Wireless Configuration Tool for MS/DIM <sup>33</sup><br><b>LS/HSS</b> =Field Installed House Side Shield <sup>9,17</sup><br><b>LS/GRSBK-2PK</b> =Glare Reducing Shield, Black <sup>9,22</sup><br><b>LS/GRSWH-2PK</b> =Glare Reducing Shield, White <sup>9,22</sup><br><b>LS/PFS</b> =Perimeter Shield, Black <sup>15</sup><br><b>WOLC-7P-10A</b> =WaveLinX Outdoor Control Module <sup>11,18</sup> |   |  |
| <p><b>NOTES:</b></p> <ol style="list-style-type: none"> <li>Customer is responsible for engineering analysis to confirm pole and fixture compatibility for all applications. Refer to our white paper WP513001EN for additional support information.</li> <li>DesignLights Consortium® Qualified. Refer to <a href="http://www.designlights.org">www.designlights.org</a> Qualified Products List under Family Models for details.</li> <li>Coastal construction finish salt spray tested to over 5,000-hours per ASTM B117, with a scribe rating of 9 per ASTM D1654.</li> <li>Not available with TH option.</li> <li>Drive current 1200mA not available with color temperatures 722, 727, 827, 830 or 930 when the HSS option is selected</li> <li>TH option not 3G rated. Not available with Coastal Construction (CC) option.</li> <li>Not available with voltage options H, 8 or 9.</li> <li>Requires the use of an internal step down transformer when combined with sensor options. Not available in combination with the HA high ambient and sensor options at 1A.</li> <li>SP arm limited to 3" O.D. vertical tenon. SP2 limited to 2-3/8" O.D. vertical tenon.</li> <li>One required for each Light Square.</li> <li>2L is not available with SPB at 347V or 480V. Not available with WaveLinX or Enlighted sensors, or 20kV surge option</li> <li>Requires PR7.</li> <li>Replace XX with sensor color (WH, BZ or BK.)</li> <li>WAC Gateway required to enable field-configurability. Order WAC-PoE and WPOE-120 (10V to PoE injector) power supply if needed. WAC not required for LC Bluetooth sensors.</li> <li>Narrow-band 590nm +/-5nm for wildlife and observatory use. Choose drive current A; supplied at 500mA drive current only. Exact luminaire wattage available in IES files. Available with 5WQ, 5MQ, SL2, SL3 and SL4 distributions. Can be used with HSS option.</li> <li>Set of 4 pcs. One set required per Light Square.</li> <li>Not available with HA option.</li> <li>Not for use with T1, 5N, 5MQ, 5W or RW optics.</li> <li>Cannot be used with other control options.</li> <li>Low voltage control lead brought out 18" outside fixture. Not available with DALI or integrated controls options</li> <li>Not available if any SPB, LWR, or WaveLinX sensor is selected. Motion sensor has an integral photocell.</li> <li>Requires the use of BPC photocontrol or the PR7 or PR photocontrol receptacle with photocontrol accessory.</li> <li>Not for use with T1, T4FT, T4W or SL4 optics.</li> <li>Sensor configuration mobile application required for configuration. See controls page for details.</li> <li>Replace X with number of Light Squares controlled by the SPB, referencing the "SPB/X Availability Table" on the controls page.</li> <li>Not available with HSS, GRSWH or GRSBK.</li> <li>Only product configurations with these designated prefixes are built to be compliant with the Buy American Act of 1933 (BAA) or Trade Agreements Act of 1979 (TAA), respectively. Please refer to <a href="http://www.designlights.org">www.designlights.org</a> website for more information. Components shipped separately may be separately analyzed under domestic preference requirements.</li> <li>For BAA or TAA requirements, Accessories sold separately will be separately analyzed under domestic preference requirements. Consult factory for further information.</li> <li>DuraVolt drivers feature added protection from power quality issues such as loss of neutral, transients and voltage fluctuations. Visit <a href="http://www.sigify.com/duravolt">www.sigify.com/duravolt</a> for more information.</li> <li>480V not to be used with ungrounded or impedance grounded systems.</li> <li>Not available in 1 square configuration at 800mA or below. Not available with any control option except SPB.</li> <li>Cannot be used with PR7 or other motion response control options.</li> <li>Use GALN Product Configurator to specify lumen output, drive current and wattage. Not available with AMB.</li> <li>Uses the FSP-211 motion sensor. The FSIR-100 configuration tool is required to adjust parameters including high and low modes, sensitivity, time delay, cutoff and more. Consult your lighting representative at Cooper Lighting Solutions for more information.</li> <li>Controls system is not available with photocontrol receptacles (PR, PR7) or other controls systems (FADC, SPBx).</li> </ol> |  |  |   |   |  |   |  |

LumenSafe Integrated Network Security Camera Technology Options (Add as Suffix)

| Product Family  | Camera Type   | Data Backhaul  |
|---|---|--|
| <b>L</b> =LumenSafe Technology<br> | <b>D</b> =Standard Dome Camera<br><b>H</b> =Hi-Res Dome Camera<br><b>Z</b> =Remote PTZ Camera | <b>C</b> =Cellular, No SIM<br><b>A</b> =Cellular, AT&T<br><b>V</b> =Cellular, Verizon<br><b>S</b> =Cellular, Sprint<br><br><b>R</b> =Cellular, Rogers<br><b>W</b> =Wi-Fi Networking w/ Omni-Directional Antenna<br><b>E</b> =Ethernet Networking |


Mounting Details

Pole Configuration Options




Pole Drilling Patterns


Type "N"




Type "R"




Type "M"




Quick Mount Universal Arm (QU)




\*NOTE: Universal bolt pattern compatible with Type N through Type M drilling patterns




Quick Mount Mast Arm (QMA)




\*NOTE: Fits 2-3/8" O.D. tenon



Pole Mount Arm with Quick Mount Adaptor (QM)




\*NOTE: Use Type N drilling pattern




Mast Arm, Fixed (MA)




\*NOTE: Fits 2-3/8" O.D. tenon





Upswept Arm (UP)



\*NOTE: Universal bolt pattern compatible with Type N through Type M drilling patterns




Wall Mount, Fixed (WM)




Mounting Details


SA=QM Pole Mount Arm




SA=QM Pole Mount Arm




WM=QM Wall Mount Arm




WM=QM Wall Mount Arm




MA=QM Mast Arm




MA=QM Mast Arm




ADJA=Adjustable Arm Pole Mount




ADJA=Adjustable Arm Pole Mount




ADJA-WM=Adjustable Arm Wall Mount




ADJA-WM=Adjustable Arm Wall Mount



ADJS=Adjustable Slipfitter 3




ADJS=Adjustable Slipfitter 3




Mounting Details

Wall Mount, Adjustable (WA)




Adjustable Arm Range of Motion


- Includes WA, SP, SP2 and PA mounting options
- Adjustable in increments of 5°
- Must maintain downward facing orientation




3" Slipfitter, Adjustable (SP)



2-3/8" Slipfitter, Adjustable (SP2)




Pole Mount, Adjustable Arm (PA)



Fixture Weights and EPAs

| Tilt Angle (Degrees) | Number of Light Squares | Weight            | 1 @ 90° | 2 @ 180° | 2 @ 90° | 2 @ 120° | 3 @ 90° | 3 @ 120° | 4 @ 90° |
|----------------------|-------------------------|-------------------|---------|----------|---------|----------|---------|----------|---------|
| 0°                   | 1-4                     | 33.5 lb (15.2 kg) | 0.85    | 1.70     | 1.46    | 1.66     | 2.31    | 2.25     | 2.35    |
|                      | 5-6                     | 43.5 lb (19.7 kg) | 0.86    | 1.71     | 1.62    | 1.80     | 2.49    | 2.35     | 2.50    |
|                      | 7-9                     | 52.5 lb (23.8 kg) | 0.98    | 1.95     | 1.75    | 1.98     | 2.73    | 2.55     | 2.76    |
| 15°                  | 1-4                     | 33.5 lb (15.2 kg) | 1.10    | 1.71     | 1.95    | 2.26     | 2.81    | 3.30     | 2.87    |
|                      | 5-6                     | 43.5 lb (19.7 kg) | 1.42    | 1.71     | 2.27    | 2.72     | 3.13    | 3.63     | 3.15    |
|                      | 7-9                     | 52.5 lb (23.8 kg) | 1.69    | 1.96     | 2.67    | 3.22     | 3.65    | 4.38     | 3.72    |
| 30°                  | 1-4                     | 33.5 lb (15.2 kg) | 1.72    | 1.81     | 2.58    | 3.21     | 3.44    | 4.59     | 3.53    |
|                      | 5-6                     | 43.5 lb (19.7 kg) | 2.26    | 2.29     | 3.11    | 4.00     | 3.97    | 5.27     | 4.00    |
|                      | 7-9                     | 52.5 lb (23.8 kg) | 2.75    | 2.85     | 3.73    | 4.83     | 4.71    | 6.45     | 4.81    |
| 45°                  | 1-4                     | 33.5 lb (15.2 kg) | 2.25    | 2.36     | 3.10    | 4.00     | 3.96    | 5.63     | 4.08    |
|                      | 5-6                     | 43.5 lb (19.7 kg) | 2.96    | 2.99     | 3.81    | 5.06     | 4.67    | 6.49     | 4.71    |
|                      | 7-9                     | 52.5 lb (23.8 kg) | 3.63    | 3.76     | 3.73    | 6.17     | 5.59    | 8.03     | 5.73    |
| 60°                  | 1-4                     | 33.5 lb (15.2 kg) | 2.63    | 2.77     | 3.49    | 4.58     | 4.34    | 6.21     | 4.48    |
|                      | 5-6                     | 43.5 lb (19.7 kg) | 3.46    | 3.51     | 4.32    | 5.84     | 5.19    | 7.01     | 5.22    |
|                      | 7-9                     | 52.5 lb (23.8 kg) | 4.27    | 4.44     | 5.25    | 7.15     | 6.23    | 8.80     | 6.40    |

Optical Distributions



Product Specifications

Construction

- Die-cast aluminum housing and heat sink
- Three housing sizes, using 1 to 9 light squares

Optics

- High-efficiency injection-molded AccuLED Optics technology
- 17 optical distributions for area site and roadway applications
- 3 shielding options include HSS, GRS and PFS
- IDA Certified (3000K CCT and warmer only, fixed mounting options)

Electrical

- Removable power tray assembly includes drivers, surge modules and control modules for ease of maintenance and serviceability
- Standard with 0-10V dimming
- Standard with 10kV surge module, optional 20kV surge module
- Suitable for operation in -40°C to 40°C ambient

environments. Optional 50°C high ambient (HA) configuration

- Luminaire available with the field adjustable dimming controller (FADC) to manually adjust wattage and reduce the total lumen output and light levels. Comes pre-set to the highest position at the lumen output selected

Mounting

- Arms are factory installed, enabling closed-housing installation
- All arms suitable for round or square pole installation
- All arms provide clearance for multiple fixture installations at 90°

Finish

- 6 standard finishes use super durable TGIC polyester powder coat paint, providing 2.5 mil nominal thickness and salt-spray tested to 3,000 hours per ASTM B117
- RAL and custom color matches available

- Coastal Construction (CC) option salt-spray tested to 5,000 hours per ASTM B117, achieving a scribe rating of 9 per ASTM D1654

Typical Applications

- Outdoor, Parking Lots, Walkways, Roadways, Building Areas

Warranty

- Five year limited warranty

Energy and Performance Data

Lumen Maintenance (TM-21)

| Drive Current | Ambient Temperature | 25,000 hours* | 50,000 hours* | 60,000 hours* | 100,000 hours** | Theoretical L70 hours** |
|---------------|---------------------|---------------|---------------|---------------|-----------------|-------------------------|
| Up to 1A      | 25°C                | 99.4%         | 99.0%         | 98.9%         | 98.3%           | > 2.4M                  |
|               | 40°C                | 98.7%         | 98.3%         | 98.1%         | 97.4%           | > 1.9M                  |
|               | 50°C                | 98.2%         | 97.2%         | 96.8%         | 95.2%           | > 851,000               |
| 1.2A          | 25°C                | 99.4%         | 99.0%         | 98.9%         | 98.3%           | > 2.4M                  |
|               | 40°C                | 98.5%         | 97.9%         | 97.7%         | 96.7%           | > 1.3M                  |

Lumen Multiplier

| Ambient Temperature | Lumen Multiplier |
|---------------------|------------------|
| 0°C                 | 1.02             |
| 10°C                | 1.01             |
| 25°C                | 1.00             |
| 40°C                | 0.99             |
| 50°C                | 0.97             |

\* Supported by IES TM-21 standards  
 \*\* Theoretical values represent estimations commonly used; however, refer to the IES position on LED Product Lifetime Prediction, IES PS-10-18, explaining proper use of IES TM-21 and LM-80.

FADC Settings  
 SA1-SA3 (A, B, C, D Drive Current)

| FADC Position | Percent of Typical Lumen Output |
|---------------|---------------------------------|
| 1             | 25%                             |
| 2             | 48%                             |
| 3             | 56%                             |
| 4             | 65%                             |
| 5             | 75%                             |
| 6             | 80%                             |
| 7             | 85%                             |
| 8             | 90%                             |
| 9             | 95%                             |
| 10            | 100%                            |

Note: +/-5% typical value

FADC Settings  
 SA4-SA6 (A, B, C, D Drive Current)

| FADC Position | Percent of Typical Lumen Output |
|---------------|---------------------------------|
| 1             | 14%                             |
| 2             | 25%                             |
| 3             | 32%                             |
| 4             | 43%                             |
| 5             | 49%                             |
| 6             | 57%                             |
| 7             | 65%                             |
| 8             | 72%                             |
| 9             | 80%                             |
| 10            | 100%                            |

Note: +/-5% typical value

FADC Settings  
 SA7-SA9 (A, B, C, D Drive Current)

| FADC Position | Percent of Typical Lumen Output |
|---------------|---------------------------------|
| 1             | 19%                             |
| 2             | 38%                             |
| 3             | 47%                             |
| 4             | 63%                             |
| 5             | 74%                             |
| 6             | 85%                             |
| 7             | 95%                             |
| 8             | 97%                             |
| 9             | 100%                            |
| 10            | 100%                            |

Note: +/-5% typical value

Performance Table, Drive Current "A" (615mA)

| Number of Light Squares |                 | 1        | 2        | 3        | 4        | 5        | 6        | 7        | 8        | 9        |
|-------------------------|-----------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Nominal Power (Watts)   |                 | 33       | 63       | 93       | 121      | 154      | 182      | 215      | 244      | 274      |
| Input Current @ 120V    |                 | 0.283    | 0.529    | 0.778    | 1.058    | 1.310    | 1.556    | 1.839    | 2.089    | 2.335    |
| Input Current @ 208V    |                 | 0.165    | 0.309    | 0.460    | 0.618    | 0.771    | 0.919    | 1.082    | 1.240    | 1.379    |
| Input Current @ 240V    |                 | 0.143    | 0.270    | 0.398    | 0.540    | 0.671    | 0.796    | 0.944    | 1.078    | 1.194    |
| Input Current @ 277V    |                 | 0.125    | 0.237    | 0.352    | 0.473    | 0.581    | 0.705    | 0.818    | 0.962    | 1.057    |
| Input Current @ 347V    |                 | 0.098    | 0.181    | 0.272    | 0.362    | 0.454    | 0.544    | 0.636    | 0.738    | 0.816    |
| Input Current @ 480V    |                 | 0.073    | 0.133    | 0.200    | 0.267    | 0.335    | 0.400    | 0.470    | 0.554    | 0.600    |
| Optics                  |                 |          |          |          |          |          |          |          |          |          |
| T1                      | 4000K Lumens    | 4,619    | 9,180    | 13,628   | 18,059   | 22,861   | 27,070   | 31,796   | 36,863   | 41,385   |
|                         | BUG Rating      | B2-U0-G1 | B3-U0-G1 | B3-U0-G2 | B4-U0-G2 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G3 |
|                         | Lumens per Watt | 140      | 146      | 147      | 149      | 148      | 149      | 148      | 151      | 151      |
| T2                      | 4000K Lumens    | 4,654    | 9,249    | 13,730   | 18,194   | 23,032   | 27,273   | 32,034   | 37,138   | 41,694   |
|                         | BUG Rating      | B1-U0-G1 | B1-U0-G2 | B2-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 |
|                         | Lumens per Watt | 141      | 147      | 148      | 150      | 150      | 150      | 149      | 152      | 152      |
| T2R                     | 4000K Lumens    | 4,716    | 9,372    | 13,913   | 18,437   | 23,340   | 27,637   | 32,462   | 37,634   | 42,251   |
|                         | BUG Rating      | B1-U0-G1 | B1-U0-G2 | B2-U0-G2 | B2-U0-G2 | B3-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 |
|                         | Lumens per Watt | 143      | 149      | 150      | 152      | 152      | 152      | 151      | 154      | 154      |
| T3                      | 4000K Lumens    | 4,589    | 9,120    | 13,538   | 17,940   | 22,711   | 26,892   | 31,587   | 36,620   | 41,112   |
|                         | BUG Rating      | B1-U0-G1 | B2-U0-G2 | B2-U0-G2 | B3-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 | B4-U0-G4 |
|                         | Lumens per Watt | 139      | 145      | 146      | 148      | 147      | 148      | 147      | 150      | 150      |
| T3R                     | 4000K Lumens    | 4,735    | 9,411    | 13,970   | 18,513   | 23,436   | 27,751   | 32,596   | 37,790   | 42,425   |
|                         | BUG Rating      | B1-U0-G1 | B1-U0-G2 | B2-U0-G3 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 |
|                         | Lumens per Watt | 143      | 149      | 150      | 153      | 152      | 152      | 152      | 155      | 155      |
| T4FT                    | 4000K Lumens    | 4,617    | 9,176    | 13,622   | 18,051   | 22,851   | 27,058   | 31,782   | 36,847   | 41,366   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G2 | B2-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 |
|                         | Lumens per Watt | 140      | 146      | 146      | 149      | 148      | 149      | 148      | 151      | 151      |
| T4W                     | 4000K Lumens    | 4,631    | 9,203    | 13,662   | 18,104   | 22,918   | 27,138   | 31,876   | 36,955   | 41,488   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G2 | B2-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 140      | 146      | 147      | 150      | 149      | 149      | 148      | 151      | 151      |
| SL2                     | 4000K Lumens    | 4,619    | 9,180    | 13,627   | 18,058   | 22,860   | 27,069   | 31,795   | 36,861   | 41,383   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G2 | B2-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 140      | 146      | 147      | 149      | 148      | 149      | 148      | 151      | 151      |
| SL3                     | 4000K Lumens    | 4,586    | 9,115    | 13,531   | 17,931   | 22,699   | 26,879   | 31,571   | 36,602   | 41,091   |
|                         | BUG Rating      | B1-U0-G1 | B1-U0-G2 | B2-U0-G3 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 |
|                         | Lumens per Watt | 139      | 145      | 145      | 148      | 147      | 148      | 147      | 150      | 150      |
| SL4                     | 4000K Lumens    | 4,529    | 9,002    | 13,363   | 17,708   | 22,417   | 26,544   | 31,178   | 36,146   | 40,580   |
|                         | BUG Rating      | B1-U0-G2 | B1-U0-G3 | B2-U0-G3 | B2-U0-G4 | B2-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 |
|                         | Lumens per Watt | 137      | 143      | 144      | 146      | 146      | 146      | 145      | 148      | 148      |
| 5NQ                     | 4000K Lumens    | 4,829    | 9,598    | 14,247   | 18,880   | 23,901   | 28,301   | 33,242   | 38,539   | 43,266   |
|                         | BUG Rating      | B2-U0-G1 | B3-U0-G1 | B3-U0-G2 | B4-U0-G2 | B4-U0-G2 | B4-U0-G2 | B5-U0-G2 | B5-U0-G3 | B5-U0-G3 |
|                         | Lumens per Watt | 146      | 152      | 153      | 156      | 155      | 155      | 155      | 158      | 158      |
| 5MQ                     | 4000K Lumens    | 4,853    | 9,645    | 14,318   | 18,974   | 24,020   | 28,442   | 33,407   | 38,731   | 43,482   |
|                         | BUG Rating      | B3-U0-G1 | B3-U0-G2 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 |
|                         | Lumens per Watt | 147      | 153      | 154      | 157      | 156      | 156      | 155      | 159      | 159      |
| 5WQ                     | 4000K Lumens    | 4,843    | 9,625    | 14,288   | 18,934   | 23,969   | 28,382   | 33,337   | 38,649   | 43,390   |
|                         | BUG Rating      | B3-U0-G1 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 | B5-U0-G5 |
|                         | Lumens per Watt | 147      | 153      | 154      | 156      | 156      | 156      | 155      | 158      | 158      |
| SLL/<br>SLR             | 4000K Lumens    | 3,989    | 7,927    | 11,768   | 15,594   | 19,741   | 23,375   | 27,456   | 31,831   | 35,736   |
|                         | BUG Rating      | B1-U0-G2 | B1-U0-G2 | B2-U0-G3 | B2-U0-G3 | B2-U0-G4 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 |
|                         | Lumens per Watt | 121      | 126      | 127      | 129      | 128      | 128      | 128      | 130      | 130      |
| RW                      | 4000K Lumens    | 4,774    | 9,488    | 14,085   | 18,665   | 23,628   | 27,979   | 32,863   | 38,100   | 42,774   |
|                         | BUG Rating      | B2-U0-G1 | B3-U0-G1 | B3-U0-G2 | B4-U0-G2 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G3 |
|                         | Lumens per Watt | 145      | 151      | 151      | 154      | 153      | 154      | 153      | 156      | 156      |
| AFL                     | 4000K Lumens    | 4,673    | 9,286    | 13,785   | 18,268   | 23,126   | 27,384   | 32,164   | 37,290   | 41,864   |
|                         | BUG Rating      | B1-U0-G1 | B1-U0-G1 | B2-U0-G2 | B2-U0-G2 | B3-U0-G2 | B3-U0-G2 | B3-U0-G3 | B3-U0-G3 | B3-U0-G3 |
|                         | Lumens per Watt | 142      | 147      | 148      | 151      | 150      | 150      | 150      | 153      | 153      |

\* Nominal data for 70 CRI. \*\* For additional performance data, please reference the Galleon Supplemental Performance Guide.

Performance Table, Drive Current "B" (800mA)

| Number of Light Squares |                 | 1        | 2        | 3        | 4        | 5        | 6        | 7        | 8        | 9        |
|-------------------------|-----------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Nominal Power (Watts)   |                 | 44       | 82       | 121      | 164      | 204      | 243      | 286      | 325      | 364      |
| Input Current @ 120V    |                 | 0.367    | 0.689    | 1.014    | 1.378    | 1.704    | 2.027    | 2.393    | 2.716    | 3.041    |
| Input Current @ 208V    |                 | 0.213    | 0.401    | 0.594    | 0.802    | 0.997    | 1.188    | 1.400    | 1.605    | 1.782    |
| Input Current @ 240V    |                 | 0.184    | 0.347    | 0.510    | 0.694    | 0.860    | 1.021    | 1.210    | 1.386    | 1.531    |
| Input Current @ 277V    |                 | 0.160    | 0.303    | 0.449    | 0.605    | 0.757    | 0.898    | 1.065    | 1.242    | 1.347    |
| Input Current @ 347V    |                 | 0.125    | 0.235    | 0.355    | 0.471    | 0.592    | 0.710    | 0.828    | 0.958    | 1.065    |
| Input Current @ 480V    |                 | 0.092    | 0.172    | 0.258    | 0.344    | 0.432    | 0.517    | 0.605    | 0.706    | 0.775    |
| Optics                  |                 |          |          |          |          |          |          |          |          |          |
| T1                      | 4000K Lumens    | 5,748    | 11,423   | 16,957   | 22,470   | 28,446   | 33,683   | 39,563   | 45,867   | 51,494   |
|                         | BUG Rating      | B2-U0-G1 | B3-U0-G2 | B4-U0-G2 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 |
|                         | Lumens per Watt | 131      | 139      | 140      | 137      | 139      | 139      | 138      | 141      | 141      |
| T2                      | 4000K Lumens    | 5,790    | 11,508   | 17,083   | 22,638   | 28,658   | 33,935   | 39,859   | 46,210   | 51,879   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 132      | 140      | 141      | 138      | 140      | 140      | 139      | 142      | 143      |
| T2R                     | 4000K Lumens    | 5,868    | 11,662   | 17,311   | 22,941   | 29,041   | 34,388   | 40,391   | 46,827   | 52,572   |
|                         | BUG Rating      | B1-U0-G1 | B2-U0-G2 | B2-U0-G2 | B3-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 |
|                         | Lumens per Watt | 133      | 142      | 143      | 140      | 142      | 142      | 141      | 144      | 144      |
| T3                      | 4000K Lumens    | 5,710    | 11,347   | 16,845   | 22,322   | 28,258   | 33,461   | 39,303   | 45,565   | 51,155   |
|                         | BUG Rating      | B1-U0-G1 | B2-U0-G2 | B3-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B4-U0-G4 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 130      | 138      | 139      | 136      | 139      | 138      | 137      | 140      | 141      |
| T3R                     | 4000K Lumens    | 5,892    | 11,710   | 17,383   | 23,035   | 29,161   | 34,530   | 40,558   | 47,020   | 52,788   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 134      | 143      | 144      | 140      | 143      | 142      | 142      | 145      | 145      |
| T4FT                    | 4000K Lumens    | 5,745    | 11,418   | 16,949   | 22,460   | 28,433   | 33,668   | 39,546   | 45,847   | 51,471   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 131      | 139      | 140      | 137      | 139      | 139      | 138      | 141      | 141      |
| T4W                     | 4000K Lumens    | 5,762    | 11,451   | 16,999   | 22,526   | 28,517   | 33,767   | 39,662   | 45,982   | 51,622   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G2 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 131      | 140      | 140      | 137      | 140      | 139      | 139      | 141      | 142      |
| SL2                     | 4000K Lumens    | 5,747    | 11,422   | 16,956   | 22,469   | 28,444   | 33,681   | 39,561   | 45,865   | 51,491   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 131      | 139      | 140      | 137      | 139      | 139      | 138      | 141      | 141      |
| SL3                     | 4000K Lumens    | 5,707    | 11,342   | 16,836   | 22,311   | 28,244   | 33,444   | 39,283   | 45,542   | 51,129   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 |
|                         | Lumens per Watt | 130      | 138      | 139      | 136      | 138      | 138      | 137      | 140      | 140      |
| SL4                     | 4000K Lumens    | 5,636    | 11,201   | 16,627   | 22,034   | 27,893   | 33,028   | 38,794   | 44,976   | 50,493   |
|                         | BUG Rating      | B1-U0-G2 | B1-U0-G3 | B2-U0-G4 | B2-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 |
|                         | Lumens per Watt | 128      | 137      | 137      | 134      | 137      | 136      | 136      | 138      | 139      |
| 5NQ                     | 4000K Lumens    | 6,009    | 11,942   | 17,727   | 23,492   | 29,739   | 35,214   | 41,362   | 47,953   | 53,835   |
|                         | BUG Rating      | B2-U0-G1 | B3-U0-G1 | B4-U0-G2 | B4-U0-G2 | B5-U0-G2 | B5-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G3 |
|                         | Lumens per Watt | 137      | 146      | 147      | 143      | 146      | 145      | 145      | 148      | 148      |
| 5MQ                     | 4000K Lumens    | 6,039    | 12,001   | 17,816   | 23,609   | 29,887   | 35,389   | 41,568   | 48,191   | 54,103   |
|                         | BUG Rating      | B3-U0-G1 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 | B5-U0-G5 |
|                         | Lumens per Watt | 137      | 146      | 147      | 144      | 147      | 146      | 145      | 148      | 149      |
| 5WQ                     | 4000K Lumens    | 6,026    | 11,976   | 17,778   | 23,559   | 29,824   | 35,315   | 41,480   | 48,090   | 53,989   |
|                         | BUG Rating      | B3-U0-G1 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 | B5-U0-G5 | B5-U0-G5 |
|                         | Lumens per Watt | 137      | 146      | 147      | 144      | 146      | 145      | 145      | 148      | 148      |
| SLL/<br>SLR             | 4000K Lumens    | 4,963    | 9,863    | 14,642   | 19,403   | 24,563   | 29,085   | 34,163   | 39,607   | 44,465   |
|                         | BUG Rating      | B1-U0-G2 | B1-U0-G3 | B2-U0-G3 | B2-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 |
|                         | Lumens per Watt | 113      | 120      | 121      | 118      | 120      | 120      | 119      | 122      | 122      |
| RW                      | 4000K Lumens    | 5,940    | 11,806   | 17,526   | 23,224   | 29,400   | 34,813   | 40,891   | 47,407   | 53,222   |
|                         | BUG Rating      | B3-U0-G1 | B3-U0-G2 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 |
|                         | Lumens per Watt | 135      | 144      | 145      | 142      | 144      | 143      | 143      | 146      | 146      |
| AFL                     | 4000K Lumens    | 5,814    | 11,555   | 17,153   | 22,730   | 28,775   | 34,073   | 40,021   | 46,398   | 52,090   |
|                         | BUG Rating      | B1-U0-G1 | B2-U0-G1 | B2-U0-G2 | B2-U0-G2 | B3-U0-G3 | B3-U0-G3 | B3-U0-G3 | B3-U0-G3 | B3-U0-G4 |
|                         | Lumens per Watt | 132      | 141      | 142      | 139      | 141      | 140      | 140      | 143      | 143      |

\* Nominal data for 70 CRI. \*\* For additional performance data, please reference the Galleon Supplemental Performance Guide.



Performance Table, Drive Current "C" (1050mA)

| Number of Light Squares      |                 | 1        | 2        | 3        | 4        | 5        | 6        | 7        | 8        | 9        |
|------------------------------|-----------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| <b>Nominal Power (Watts)</b> |                 | 57       | 108      | 160      | 213      | 269      | 321      | 377      | 429      | 481      |
| <b>Input Current @ 120V</b>  |                 | 0.478    | 0.905    | 1.338    | 1.810    | 2.244    | 2.675    | 3.150    | 3.584    | 4.013    |
| <b>Input Current @ 208V</b>  |                 | 0.279    | 0.532    | 0.780    | 1.064    | 1.313    | 1.559    | 1.845    | 2.093    | 2.339    |
| <b>Input Current @ 240V</b>  |                 | 0.243    | 0.458    | 0.664    | 0.916    | 1.123    | 1.328    | 1.582    | 1.788    | 1.991    |
| <b>Input Current @ 277V</b>  |                 | 0.213    | 0.404    | 0.582    | 0.808    | 0.997    | 1.164    | 1.401    | 1.589    | 1.745    |
| <b>Input Current @ 347V</b>  |                 | 0.164    | 0.322    | 0.471    | 0.644    | 0.795    | 0.943    | 1.117    | 1.269    | 1.414    |
| <b>Input Current @ 480V</b>  |                 | 0.121    | 0.235    | 0.341    | 0.469    | 0.579    | 0.681    | 0.814    | 0.923    | 1.022    |
| Optics                       |                 |          |          |          |          |          |          |          |          |          |
| <b>T1</b>                    | 4000K Lumens    | 7,101    | 14,113   | 20,950   | 27,763   | 35,146   | 41,616   | 48,882   | 56,671   | 63,623   |
|                              | BUG Rating      | B3-U0-G1 | B3-U0-G2 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 |
|                              | Lumens per Watt | 125      | 131      | 131      | 130      | 131      | 130      | 130      | 132      | 132      |
| <b>T2</b>                    | 4000K Lumens    | 7,154    | 14,219   | 21,107   | 27,970   | 35,408   | 41,927   | 49,247   | 57,094   | 64,098   |
|                              | BUG Rating      | B1-U0-G2 | B2-U0-G2 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                              | Lumens per Watt | 126      | 132      | 132      | 131      | 132      | 131      | 131      | 133      | 133      |
| <b>T2R</b>                   | 4000K Lumens    | 7,250    | 14,408   | 21,389   | 28,344   | 35,881   | 42,487   | 49,905   | 57,857   | 64,954   |
|                              | BUG Rating      | B1-U0-G1 | B2-U0-G2 | B2-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                              | Lumens per Watt | 127      | 133      | 134      | 133      | 133      | 132      | 132      | 135      | 135      |
| <b>T3</b>                    | 4000K Lumens    | 7,054    | 14,020   | 20,812   | 27,580   | 34,914   | 41,342   | 48,560   | 56,297   | 63,203   |
|                              | BUG Rating      | B1-U0-G2 | B2-U0-G2 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B4-U0-G4 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                              | Lumens per Watt | 124      | 130      | 130      | 129      | 130      | 129      | 129      | 131      | 131      |
| <b>T3R</b>                   | 4000K Lumens    | 7,280    | 14,468   | 21,477   | 28,461   | 36,029   | 42,663   | 50,111   | 58,096   | 65,222   |
|                              | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                              | Lumens per Watt | 128      | 134      | 134      | 134      | 134      | 133      | 133      | 135      | 136      |
| <b>T4FT</b>                  | 4000K Lumens    | 7,098    | 14,107   | 20,941   | 27,751   | 35,130   | 41,598   | 48,860   | 56,646   | 63,594   |
|                              | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                              | Lumens per Watt | 125      | 131      | 131      | 130      | 131      | 130      | 130      | 132      | 132      |
| <b>T4W</b>                   | 4000K Lumens    | 7,119    | 14,148   | 21,003   | 27,832   | 35,233   | 41,720   | 49,004   | 56,812   | 63,781   |
|                              | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                              | Lumens per Watt | 125      | 131      | 131      | 131      | 131      | 130      | 130      | 132      | 133      |
| <b>SL2</b>                   | 4000K Lumens    | 7,101    | 14,112   | 20,949   | 27,761   | 35,144   | 41,614   | 48,879   | 56,668   | 63,619   |
|                              | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                              | Lumens per Watt | 125      | 131      | 131      | 130      | 131      | 130      | 130      | 132      | 132      |
| <b>SL3</b>                   | 4000K Lumens    | 7,051    | 14,013   | 20,802   | 27,566   | 34,897   | 41,321   | 48,535   | 56,269   | 63,172   |
|                              | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B2-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                              | Lumens per Watt | 124      | 130      | 130      | 129      | 130      | 129      | 129      | 131      | 131      |
| <b>SL4</b>                   | 4000K Lumens    | 6,963    | 13,839   | 20,543   | 27,223   | 34,463   | 40,808   | 47,932   | 55,569   | 62,386   |
|                              | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B2-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 |
|                              | Lumens per Watt | 122      | 128      | 128      | 128      | 128      | 127      | 127      | 130      | 130      |
| <b>5NQ</b>                   | 4000K Lumens    | 7,424    | 14,755   | 21,903   | 29,025   | 36,743   | 43,508   | 51,104   | 59,247   | 66,515   |
|                              | BUG Rating      | B3-U0-G1 | B3-U0-G2 | B4-U0-G2 | B5-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 |
|                              | Lumens per Watt | 130      | 137      | 137      | 136      | 137      | 136      | 136      | 138      | 138      |
| <b>5MQ</b>                   | 4000K Lumens    | 7,461    | 14,828   | 22,012   | 29,169   | 36,926   | 43,725   | 51,359   | 59,542   | 66,846   |
|                              | BUG Rating      | B3-U0-G1 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 | B5-U0-G5 | B5-U0-G5 |
|                              | Lumens per Watt | 131      | 137      | 138      | 137      | 137      | 136      | 136      | 139      | 139      |
| <b>5WQ</b>                   | 4000K Lumens    | 7,445    | 14,797   | 21,966   | 29,108   | 36,849   | 43,633   | 51,250   | 59,417   | 66,705   |
|                              | BUG Rating      | B3-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G5 | B5-U0-G5 | B5-U0-G5 | B5-U0-G5 |
|                              | Lumens per Watt | 131      | 137      | 137      | 137      | 137      | 136      | 136      | 139      | 139      |
| <b>SLL/SLR</b>               | 4000K Lumens    | 6,132    | 12,187   | 18,091   | 23,973   | 30,348   | 35,936   | 42,210   | 48,935   | 54,938   |
|                              | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B2-U0-G3 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 |
|                              | Lumens per Watt | 108      | 113      | 113      | 113      | 113      | 112      | 112      | 114      | 114      |
| <b>RW</b>                    | 4000K Lumens    | 7,340    | 14,587   | 21,653   | 28,694   | 36,325   | 43,013   | 50,522   | 58,573   | 65,757   |
|                              | BUG Rating      | B3-U0-G1 | B3-U0-G2 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 |
|                              | Lumens per Watt | 129      | 135      | 135      | 135      | 135      | 134      | 134      | 137      | 137      |
| <b>AFL</b>                   | 4000K Lumens    | 7,183    | 14,276   | 21,193   | 28,084   | 35,552   | 42,098   | 49,448   | 57,327   | 64,359   |
|                              | BUG Rating      | B1-U0-G1 | B2-U0-G2 | B2-U0-G2 | B3-U0-G2 | B3-U0-G3 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B4-U0-G4 |
|                              | Lumens per Watt | 126      | 132      | 132      | 132      | 132      | 131      | 131      | 134      | 134      |

\* Nominal data for 70 CRI. \*\* For additional performance data, please reference the Galleon Supplemental Performance Guide.

Performance Table, Drive Current "D" (1200mA)

| Number of Light Squares |                 | 1        | 2        | 3        | 4        | 5        | 6        | 7        | 8        | 9        |
|-------------------------|-----------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Nominal Power (Watts)   |                 | 65       | 125      | 184      | 245      | 309      | 368      | 433      | 493      | 552      |
| Input Current @ 120V    |                 | 0.546    | 1.041    | 1.535    | 2.082    | 2.578    | 3.070    | 3.619    | 4.114    | 4.605    |
| Input Current @ 208V    |                 | 0.318    | 0.610    | 0.893    | 1.219    | 1.504    | 1.786    | 2.113    | 2.397    | 2.679    |
| Input Current @ 240V    |                 | 0.276    | 0.523    | 0.758    | 1.046    | 1.282    | 1.516    | 1.806    | 2.041    | 2.274    |
| Input Current @ 277V    |                 | 0.241    | 0.460    | 0.662    | 0.920    | 1.133    | 1.325    | 1.593    | 1.807    | 1.987    |
| Input Current @ 347V    |                 | 0.187    | 0.370    | 0.543    | 0.740    | 0.915    | 1.085    | 1.285    | 1.459    | 1.628    |
| Input Current @ 480V    |                 | 0.138    | 0.269    | 0.391    | 0.537    | 0.663    | 0.782    | 0.932    | 1.057    | 1.173    |
| Optics                  |                 |          |          |          |          |          |          |          |          |          |
| T1                      | 4000K Lumens    | 7,814    | 15,529   | 23,053   | 30,549   | 38,672   | 45,793   | 53,787   | 62,358   | 70,007   |
|                         | BUG Rating      | B3-U0-G1 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 |
|                         | Lumens per Watt | 120      | 124      | 125      | 125      | 125      | 124      | 124      | 126      | 127      |
| T2                      | 4000K Lumens    | 7,872    | 15,645   | 23,225   | 30,777   | 38,962   | 46,135   | 54,189   | 62,824   | 70,530   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 121      | 125      | 126      | 126      | 126      | 125      | 125      | 127      | 128      |
| T2R                     | 4000K Lumens    | 7,977    | 15,854   | 23,535   | 31,188   | 39,482   | 46,751   | 54,913   | 63,663   | 71,472   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G2 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G4 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 123      | 127      | 128      | 127      | 128      | 127      | 127      | 129      | 129      |
| T3                      | 4000K Lumens    | 7,762    | 15,427   | 22,901   | 30,348   | 38,418   | 45,491   | 53,433   | 61,947   | 69,546   |
|                         | BUG Rating      | B2-U0-G2 | B3-U0-G3 | B3-U0-G3 | B3-U0-G4 | B4-U0-G4 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 119      | 123      | 124      | 124      | 124      | 124      | 123      | 126      | 126      |
| T3R                     | 4000K Lumens    | 8,010    | 15,920   | 23,632   | 31,317   | 39,645   | 46,944   | 55,139   | 63,925   | 71,767   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 123      | 127      | 128      | 128      | 128      | 128      | 127      | 130      | 130      |
| T4FT                    | 4000K Lumens    | 7,810    | 15,522   | 23,043   | 30,535   | 38,655   | 45,772   | 53,763   | 62,330   | 69,976   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 120      | 124      | 125      | 125      | 125      | 124      | 124      | 126      | 127      |
| T4W                     | 4000K Lumens    | 7,833    | 15,568   | 23,110   | 30,625   | 38,769   | 45,907   | 53,921   | 62,513   | 70,182   |
|                         | BUG Rating      | B2-U0-G2 | B3-U0-G3 | B3-U0-G4 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 121      | 125      | 126      | 125      | 125      | 125      | 125      | 127      | 127      |
| SL2                     | 4000K Lumens    | 7,813    | 15,528   | 23,052   | 30,547   | 38,670   | 45,790   | 53,784   | 62,354   | 70,003   |
|                         | BUG Rating      | B2-U0-G2 | B3-U0-G3 | B3-U0-G4 | B3-U0-G4 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 120      | 124      | 125      | 125      | 125      | 124      | 124      | 126      | 127      |
| SL3                     | 4000K Lumens    | 7,758    | 15,419   | 22,889   | 30,332   | 38,398   | 45,468   | 53,406   | 61,916   | 69,511   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B3-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 119      | 123      | 124      | 124      | 124      | 124      | 123      | 126      | 126      |
| SL4                     | 4000K Lumens    | 7,662    | 15,228   | 22,605   | 29,955   | 37,921   | 44,903   | 52,742   | 61,146   | 68,646   |
|                         | BUG Rating      | B1-U0-G3 | B2-U0-G3 | B2-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 118      | 122      | 123      | 122      | 123      | 122      | 122      | 124      | 124      |
| 5NQ                     | 4000K Lumens    | 8,169    | 16,235   | 24,101   | 31,938   | 40,431   | 47,874   | 56,232   | 65,193   | 73,190   |
|                         | BUG Rating      | B3-U0-G1 | B3-U0-G2 | B4-U0-G2 | B5-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 |
|                         | Lumens per Watt | 126      | 130      | 131      | 130      | 131      | 130      | 130      | 132      | 133      |
| 5MQ                     | 4000K Lumens    | 8,210    | 16,316   | 24,221   | 32,097   | 40,632   | 48,113   | 56,512   | 65,517   | 73,554   |
|                         | BUG Rating      | B3-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G5 | B5-U0-G5 | B5-U0-G5 |
|                         | Lumens per Watt | 126      | 131      | 132      | 131      | 131      | 131      | 131      | 133      | 133      |
| 5WQ                     | 4000K Lumens    | 8,192    | 16,282   | 24,170   | 32,029   | 40,546   | 48,011   | 56,393   | 65,379   | 73,399   |
|                         | BUG Rating      | B3-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G5 | B5-U0-G5 | B5-U0-G5 | B5-U0-G5 |
|                         | Lumens per Watt | 126      | 130      | 131      | 131      | 131      | 130      | 130      | 133      | 133      |
| SLL/<br>SLR             | 4000K Lumens    | 6,747    | 13,410   | 19,906   | 26,379   | 33,394   | 39,542   | 46,445   | 53,846   | 60,451   |
|                         | BUG Rating      | B1-U0-G2 | B2-U0-G3 | B2-U0-G4 | B3-U0-G4 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B3-U0-G5 | B4-U0-G5 |
|                         | Lumens per Watt | 104      | 107      | 108      | 108      | 108      | 107      | 107      | 109      | 110      |
| RW                      | 4000K Lumens    | 8,076    | 16,050   | 23,826   | 31,574   | 39,970   | 47,329   | 55,592   | 64,450   | 72,356   |
|                         | BUG Rating      | B3-U0-G1 | B4-U0-G2 | B4-U0-G2 | B5-U0-G3 | B5-U0-G3 | B5-U0-G4 | B5-U0-G4 | B5-U0-G4 | B5-U0-G5 |
|                         | Lumens per Watt | 124      | 128      | 129      | 129      | 129      | 129      | 128      | 131      | 131      |
| AFL                     | 4000K Lumens    | 7,904    | 15,709   | 23,320   | 30,902   | 39,120   | 46,323   | 54,410   | 63,079   | 70,817   |
|                         | BUG Rating      | B1-U0-G1 | B2-U0-G2 | B3-U0-G2 | B3-U0-G3 | B3-U0-G3 | B3-U0-G3 | B3-U0-G4 | B4-U0-G4 | B4-U0-G4 |
|                         | Lumens per Watt | 122      | 126      | 127      | 126      | 127      | 126      | 126      | 128      | 128      |

\* Nominal data for 70 CRI. \*\* For additional performance data, please reference the Galleon Supplemental Performance Guide.

## Control Options

### 0-10V (DIM)

This fixture is offered standard with 0-10V dimming driver(s). The DIM option provides 0-10V dimming wire leads for use with a lighting control panel or other control method.

### Photocontrol (BPC, PR and PR7)

Optional button-type photocontrol (BPC) and photocontrol receptacles (PR and PR7) provide a flexible solution to enable "dusk-to-dawn" lighting by sensing light levels. Advanced control systems compatible with NEMA 7-pin standards can be utilized with the PR7 receptacle.

### After Hours Dim (AHD)

This feature allows photocontrol-enabled luminaires to achieve additional energy savings by dimming during scheduled portions of the night. The dimming profile will automatically take effect after a "dusk-to-dawn" period has been calculated from the photocontrol input. Specify the desired dimming profile for a simple, factory-shipped dimming solution requiring no external control wiring. Reference the After Hours Dim supplemental guide for additional information.

### Dimming Occupancy Sensor (SPB and MS/DIM-LXX)

These passive infrared (PIR) sensors are factory installed in the luminaire housing. When the SPB (FSP-321 or FSP-311) or MS/DIM (FSP-211) sensor options are selected, the occupancy sensor is connected to a dimming driver and the luminaire dims when no motion is detected. After a set period of time, the luminaire turns off, and when motion is detected, the luminaire returns to full light output. Both sensors are factory preset to dim down to approximately 10% power with a time delay of five minutes. The MS/DIM sensor requires the FSIR-100 programming tool to adjust factory defaults. The SPB sensor default parameters are listed in the table below and can be configured utilizing the Sensor Configuration mobile application for iOS and Android devices. The SPB/X is configured to control only the specified number of light squares (See SPB/X Availability Table below.) An integral photocontrol can be activated with the app for "dusk-to-dawn" control or daylight harvesting - the factory default is off. Four sensor colors are available; Bronze, Black, Gray and White, and are automatically selected based on the luminaire finish as indicated by the table below.

| SPB sensor finish matched to luminaire finish |                   |                    |
|---|-------------------|--------------------|
| Luminaire Finish                              |                   | SPB Sensor Finish* |
| WH  | White             | White              |
| BK  | Black             | Black              |
| GM  | Graphite Metallic | Black              |
| BZ  | Bronze            | Bronze             |
| AP  | Gray              | Gray               |
| DP  | Dark Platinum     | Gray               |

\*SPB bezel color automatically selected based on luminaire finish

| SPB/X Availability Table |                              |
|--------------------------|------------------------------|
| Fixture Square Count     | Available SPB/X Square Count |
| 1                        | Not Available                |
| 2                        | Not Available                |
| 3                        | Not Available                |
| 4                        | 2                            |
| 5                        | 2 or 3                       |
| 6                        | 3                            |
| 7                        | 2, 3, 4 or 5                 |
| 8                        | 2, 3, 5 or 6                 |
| 9                        | 3 or 6                       |


### Default Program Settings (Out of the Box Functionality)

| Occupancy Sensor  |        |       |                             |                |
|-------------------|--------|-------|-----------------------------|----------------|
| Setting           | MS/DIM | SPB   | WaveLinX Lite (WLS4 / WLS2) | WaveLinX (WPS) |
| High Mode %       | 100%   | 100%  | 100%                        | 100%           |
| Low Mode %        | 10%    | 10%   | 50%                         | 50%            |
| Time Delay        | 5 min  | 5 min | 15 min                      | 15 min         |
| Cut Off Delay     | 1 hr   | 1 hr  | Disabled                    | Disabled       |
| Photocell Enabled | No     | No    | Yes                         | Yes            |


### WaveLinX Wireless Control and Monitoring System

Operates on a wireless mesh network based on IEEE 802.15.4 standards enabling wireless control of outdoor lighting. WaveLinX (WPS2 to WPS4) outdoor wireless sensors offer passive infrared (PIR) occupancy and photocell for closed loop daylight harvesting, and can be factory or field-installed. Sensors are factory preset to dim down to 50% after 15 minutes of no motion detected. Two lens options are available for mounting heights of 7' to 40'. Use the WaveLinX mobile application for set-up and configuration. At least one Wireless Area Controller (WAC) is required for full functionality and remote communication (including adjustment of any factory pre-sets). WaveLinX Lite (WLS4 and WLS2) outdoor wireless sensors provide PIR occupancy and photocell for closed loop daylight harvesting, and can be factory or field-installed. Sensors are factory preset to dim down to 50% after 15 minutes of no motion detected. Two lens options are available for mounting heights of 7' to 40'. Use the WaveLinX Lite mobile application for set-up and configuration. WAC not required. WaveLinX Outdoor Control Module (WOLC-7P-10A) accessory provides a photocontrol enabling astronomic or time-based schedules to provide ON, OFF and dimming control of fixtures utilizing a 7-PIN receptacle. The out-of-box functionality is ON at dusk and OFF at dawn.

#### For mounting heights up to 15' (WPS2 and WLS2)



#### For mounting heights up to 40' (WPS4 and WLS4)



### LumenSafe Integrated Network Security Camera (LD)

Cooper Lighting Solutions brings ease of camera deployment to a whole new level. No additional wiring is needed beyond providing line power to the luminaire. A variety of networking options allows security integrators to design the optimal solution for active surveillance. As the ideal solution to meet the needs for active surveillance, the LumenSafe integrated network camera is a streamlined, outdoor-ready fixed dome that provides HDTV 1080p video. This IP camera is optimally designed for deployment in the video management system or security software platform of choice.

### Synapse (DIM10)

SimplySNAP integrated wireless controls system by Synapse. Includes factory installed DIM10 Synapse control module and FSP-201 motion sensor; requires additional Synapse system components for operation. Contact Synapse at [www.synapsewireless.com](http://www.synapsewireless.com) for product support, warranty and terms and conditions.

FA

BODY OF LIGHT



SHAPE OF LIGHT




INTELLIGENCE OF LIGHT




FA770  
FA770-W  
FA1070



FA170




FA100-C,  
FA100-WD,  
FA100-U




A  
SERIES

Precision lens optics  
\* also available in satiné version



T  
SERIES

ewoLighTile: low glare light-guiding panels



A  
SERIES

Control protocols

|               |           |
|---------------|-----------|
| ON/OFF        | ON<br>OFF |
| DALI 2        | DALI      |
| 1-10 V        | 1-10V     |
| ewo connexx   | XX        |
| Zhaga Book 18 | Z         |
| Line Switch   | LS        |

Programming options

|             |                        |
|-------------|------------------------|
| CLO         | Constant Lumen Output  |
| AC/DC       | Emergency power supply |
| Stand-alone |                        |

T  
SERIES

Control protocols

|           |            |
|-----------|------------|
| DALI 2 T8 | T8<br>DALI |
|-----------|------------|

Programming options


|               |
|---------------|
| Night dimming |
|---------------|

FA770  
FA770-W  
FA1070

Public space  
Roads and traffic  
Pedestrian path  
Accent lighting




- DB 703 Anthracite
- ewo colours



A-Series 1-6 lighting units  
T-Series 2-6 lighting units

Configurator

IP66 RoHS IK08



Precision lens optics  
\* also available in satiné version



ewoLightTile: low glare light-guiding panels

- 2,200 K CRI ≥ 70
- 2,700 K CRI ≥ 70
- 3,000 K CRI ≥ 80
- 4,000 K CRI ≥ 70
- 5,700 K CRI ≥ 70
- CRI ≥ 80 on request
- Tunable White CRI ≥ 80
- RGBW

Housing

|                        |   |  |
|------------------------|---|--|
| Housing material       | Extruded aluminium profile (optional COR-TEN steel)   |  |
| Housing finish         | Polyester powder coating (ewoECP upon request**)  |  |
| Finish standard colour | Silver grey (RAL 9007 / DB 702)*  |  |
| Glass                  | Safety glass (ESG)  |  |
| Mounting options       | Pole, wall  |  |
|                        | * other colours on request  |  |
|                        | ** ewo three steps process (high quality alloy, pre-treatment, primer) to ensure extreme corrosion resistance (except 1070) |  |

Measurements

| Model   | LPH [m] ① | l <sub>p</sub> ② | -l <sub>p</sub> ③ | Weight [kg] ④ |
|---------|-----------|------------------|-------------------|---------------|
| FA770   | 2.5-6     | 0.18             | 1.38              | 95.0*         |
| FA770-W | /         | 0.16             | 0.06              | 14.5          |
| FA1070  | 6-8       | 0.29             | 2.14              | 176.0**       |

① in 0.5 m steps    ② projected windage area [m<sup>2</sup>]    ③ max. weight  
④ lateral windage area [m<sup>2</sup>]    ④④ pole included

\* single version with aluminium pole LPH = 6 m and telescopic element with anchor cage  
\*\* single version with aluminium pole LPH = 8 m and telescopic element with anchor cage

Performance

| Optics                  | AH02 | AP07 | AS06 | AS07     | AS08 | AS09 | AS10-L | AS10-R | TS11     | TP08 |
|-------------------------|------|------|------|----------|------|------|--------|--------|----------|------|
| MacAdam ellipses (SDCM) |      |      |      | ≤ 5 SDCM |      |      |        |        | ≤ 5 SDCM |      |

| Model              | FA770/-W     | FA1070       | FA770/-W | FA1070 |
|--------------------|--------------|--------------|----------|--------|
| Light units        | 1-5          | 5-6          | 2-4      | 5-6    |
| Luminous flux [lm] | 1,000-18,800 | 4,700-19,100 | 4,100    | 5,500  |

Electrical

|                        | A-Series       | T-Series       |
|------------------------|----------------|----------------|
| Protection class       | I/II           | I              |
| Voltage [V], [Hz]      | 220-240, 50/60 | 220-240, 50/60 |
| Current feed max. [mA] | 700*           | 225            |
| LED power max. [W]     | 160            | 71             |

\* FA1070 max. 550 mA


Operating conditions

|          |  |
|----------|--|
| Lifetime | Visit the <a href="#">configurator</a> for specific lifetime options |
|----------|--|

Driver

|                        | A-Series  | T-Series |
|------------------------|---|----------|
| Control options        | ON OFF DALI 1-10V X Z Lys   | T8 DALI  |
| Programming [optional] | Constant Lumen Output (CLO)<br>Emergency power supply (AC/DC)<br>Stand-alone              |          |
| Control accessories    | Further accessories on request  |          |
| Software               | connexx light management software for remote management of intelligent luminaire clusters |          |

Available designs (also available as pendant)






Product variations



BOLLARDS  
FA170

Pedestrian path  
Accent lighting



Configurator

CE RoHS IK09\*  
\*(IK10 on request, COR-TEN IK08)

Housing

|                        |   |
|------------------------|---|
| Housing material       | Aluminum die-cast* (A-Series: optional COR-TEN)   |
| Housing finish         | Polyester powder coating (ewoECP upon request***)   |
| Finish standard colour | Silver grey (RAL 9007 / DB 702)**   |
| Glass                  | Safety glass (ESG)  |
| Mounting options       | Pole  |
| Installation           | Gelbox for throughwiring upon request<br>* pole made of extruded aluminium profile<br>** other colours on request<br>*** ewo three steps process (high quality alloy, pre-treatment, primer) to ensure extreme corrosion resistance |

Measurements

| Model | LPH [m] ① | l <sub>p</sub> ② | -l <sub>p</sub> ③ | Weight [kg] ④ |
|-------|-----------|------------------|-------------------|---------------|
| FA170 | 1         | 0.04             | 0.20              | 18.5*         |
| FA170 | 1-4       | 0.04             | 0.80              | 46.5**        |

① in 0.5 m steps    ② projected windage area [m<sup>2</sup>]    ③ max. weight  
④ lateral windage area [m<sup>2</sup>]    ⑤ pole included

\* single version with aluminium pole LPH = 1 m and buried base  
\*\* single version with aluminium pole LPH = 4 m and buried base

Electrical

|                        | A-Series       | T-Series       |
|------------------------|----------------|----------------|
| Protection class       | I/II           | I/II           |
| Voltage [V], [Hz]      | 220-240, 50/60 | 220-240, 50/60 |
| Current feed max. [mA] | 500            | 225            |
| LED power max. [W]     | 26             | 12             |

Operating conditions

|          |  |
|----------|--|
| Lifetime | Visit the <a href="#">configurator</a> for specific lifetime options |
|----------|--|

Driver

|                        | A-Series  | T-Series |
|------------------------|---|----------|
| Control options        | ON OFF DALI 1-10V L/S   | T8 DALI  |
| Programming [optional] | Constant Lumen Output (CLO)<br>Emergency power supply (AC/DC)<br>Stand-alone              |          |
| Control accessories    | Further accessories on request  |          |
| Software               | connexx light management software for remote management of intelligent luminaire clusters |          |



Precision lens optics  
\* also available in satiné version



ewoLighTile: low glare  
light-guiding panels

Shape your own light by combining any light distribution

2,200 K CRI ≥ 70    2,700 K CRI ≥ 70    3,000 K CRI ≥ 80    4,000 K CRI ≥ 70    CRI ≥ 80 on request    Tunable White CRI ≥ 80    RGBW


Performance

| Optics                  | AH02 | AP07 | AS06 | AS07 | AS08     | AS09 | TS11 | TP08     |
|-------------------------|------|------|------|------|----------|------|------|----------|
| MacAdam ellipses (SDCM) |      |      |      |      | ≤ 5 SDCM |      |      | ≤ 5 SDCM |


| Model              | FA170     | FA170 |
|--------------------|-----------|-------|
| Light units        | 1         | 1     |
| Luminous flux [lm] | 340-2,590 | 1,000 |

Accessories

ewoLightLayers (optical accessories)



Surface





Available designs




FA

WALL / CEILING

FA100-C  
FA100-WD  
FA100-WU



Configurator



IP66 RoHS IK09\*  
\*(IK10 on request)

Housing

|                        |  |
|------------------------|--|
| Housing material       | Aluminum die-cast                                |
| Housing finish         | Polyester powder coating (ewoECP upon request**) |
| Finish standard colour | Silver grey (RAL 9007 / DB 702)*                 |
| Glass                  | Safety glass (ESG)                               |
| Mounting options       | Wall, ceiling                                    |
| Installation           | Gelbox for throughwiring upon request            |

\* other colours on request  
\*\* ewo three steps process (high quality alloy, pre-treatment, primer) to ensure extreme corrosion resistance

Measurements

| Model    | LPH [m] ① | ⊕ <sup>Ⓜ</sup> ② | -⊖ <sup>Ⓜ</sup> ③ | Weight [kg] ④ |
|----------|-----------|------------------|-------------------|---------------|
| FA100-WD | /         | 0.02             | 0.02              | 2.5           |
| FA100-WU | /         | 0.02             | 0.02              | 2.5           |
| FA100-C  | /         | /                | 0.02              | 2.5           |

② projected windage area [m<sup>2</sup>]    ④ max. weight  
③ lateral windage area [m<sup>2</sup>]

Electrical

|                        | A-Series       | T-Series       |
|------------------------|----------------|----------------|
| Protection class       | I/II           | I/II           |
| Voltage [V], [Hz]      | 220-240, 50/60 | 220-240, 50/60 |
| Current feed max. [mA] | 500            | 225            |
| LED power max. [W]     | 26             | 12             |

Operating conditions

|          |  |
|----------|--|
| Lifetime | Visit the <a href="#">configurator</a> for specific lifetime options |
|----------|--|

Driver

|                        | A-Series  | T-Series |
|------------------------|---|----------|
| Control options        | ON OFF DALI 1-10V LS  | T8 DALI  |
| Programming [optional] | Constant Lumen Output (CLO)<br>Emergency power supply (AC/DC)<br>Stand-alone              |          |
| Control accessories    | Further accessories on request  |          |
| Software               | connexx light management software for remote management of intelligent luminaire clusters |          |



Precision lens optics  
\* also available in satiné version



ewoLightTile: low glare  
light-guiding panels

2,200 K CRI ≥ 70    2,700 K CRI ≥ 70    3,000 K CRI ≥ 80    4,000 K CRI ≥ 70

CRI ≥ 80 on request    Tunable White CRI ≥ 80    RGBW

Performance


| Optics                  | AH02 | AP07 | APC07 | AS06 | AS07 | AS08     | AS09 | TS11 | TP08     |
|-------------------------|------|------|-------|------|------|----------|------|------|----------|
| MacAdam ellipses (SDCM) |      |      |       |      |      | ≤ 5 SDCM |      |      | ≤ 5 SDCM |

| Model              | FA100-WD  | FA100-WU  | FA100-C   | FA100-WD | FA100-WU | FA100-C |
|--------------------|-----------|-----------|-----------|----------|----------|---------|
| Light units        | 1         | 1         | 1         | 1        | 1        | 1       |
| Luminous flux [lm] | 315-3,250 | 315-3,250 | 420-3,300 | 1,000    | 1,000    | 1,000   |

Accessories

ewoLightLayers (optical accessories)



Available designs





LED WATTAGE CHART

|                | 16L                    | 32L                       |
|----------------|------------------------|---------------------------|
| 700 milliamps  | 36w (4385-4720 Lumens) | 71w (8770-9439 Lumens)    |
| 1050 milliamps | 56w (6022-6482 Lumens) | 106w (11797-12698 Lumens) |

**Form**

- Elegant Rectilinear Extruded Aluminum Housing
- Corrosion Resistant Stainless Steel External Hardware
- Sleek, Low Profile Housing
- Spec Grade Performance
- Engineered For Optimum Thermal Management
- Anchor Base Plate For Easy Installation
- 8 Architectural Finishes  
Standard, RAL Colors Available

**Function**

- Micro Optics IES Distributions T2, T3, T4, T5
- 0-10V Dimming Drivers  
THD @ Max Load < 15%
- Power factor @ Max Load < 0.95
- Amber, 2700K, 3000K, 3500K, 4000K, Or 5000K
- 16L to 32L LED Configuration
- 36-106 Watts (Single Head Wattage)
- CRI 70, 80, or 90
- Extruded Aluminum Heat Sink
- 5 Mils Powder Coat
- Aluminum Pole .250 Wall

**Reliability**

- Silicone Micro Optics
- 5 Year Standard Warranty
- IP67 Optics
- Reduces Energy Consumption And Costs Up To 65%
- Dark Sky Approved

**BUY AMERICAN**

To ensure the latest BAA/TAA/BABA Standards are being met, please select BAA, TAA, or BABA in the options section. Please contact the factory before placing an order for any NLS products requesting BAA (Buy American Act), TAA (Trade American Act), or BABA (Build America, Buy America).





Project Name:

Type:

# TRC-2 ORDERING GUIDE

\*Ordering information for Pole & Fixture

| Cat#                     | Light Dist.           | No. of LEDs        | Milliamps          | Kelvin Temp                              | Volts                   |
|--------------------------|-----------------------|--------------------|--------------------|--|-------------------------|
| Trac 2<br><b>(TRC-2)</b> | Type 2<br><b>(T2)</b> | 16<br><b>(16L)</b> | 700<br><b>(7)</b>  | Amber<br>585-600nm<br><b>(AMBER) ⑤ ⑦</b> | 120-277<br><b>(UNV)</b> |
|                          | Type 3<br><b>(T3)</b> | 32<br><b>(32L)</b> | 1050<br><b>(1)</b> | 2700K, 70 CRI<br><b>(27K7) ⑤</b>         | 340-480<br><b>(HV)</b>  |
|                          | Type 4<br><b>(T4)</b> |                    |                    | 2700K, 80 CRI<br><b>(27K8) ① ⑤</b>       |                         |
|                          | Type 5<br><b>(T5)</b> |                    |                    | 3000K, 70 CRI<br><b>(30K7) ⑤</b>         |                         |
|                          |                       |                    |                    | 3000K, 80 CRI<br><b>(30K8) ① ⑤</b>       |                         |
|                          |                       |                    |                    | 3500K, 80 CRI<br><b>(35K8)</b>           |                         |
|                          |                       |                    |                    | 4000K, 70 CRI<br><b>(40K7)</b>           |                         |
|                          |                       |                    |                    | 4000K, 80 CRI<br><b>(40K8) ①</b>         |                         |
|                          |                       |                    |                    | 5000K, 70 CRI<br><b>(50K7)</b>           |                         |
|                          |                       |                    |                    | 5000K, 80 CRI<br><b>(50K8) ①</b>         |                         |

| Config.                             | Color                                 | Control Options                                    | Options  | Pole Height   |
|-------------------------------------|---------------------------------------|--|--|---|
| Single<br><b>(SGL)</b><br>└         | Bronze Textured<br><b>(BRZ)</b>       | Nema 7-Pin<br>Receptacle<br><b>(PE7) ⑥</b>         | Marine Grade<br>Finish<br><b>(MGF)</b>           | 10'<br><b>(10)</b>  |
| Double<br><b>(D-180)</b><br>└└      | White Textured<br><b>(WHT)</b>        | Button Photocell<br><b>(PC) ⑥</b>                  | House Side Shield<br><b>(HSS)</b>                | 12'<br><b>(12)</b>  |
| MPF Triple<br><b>(TRI) ②</b><br>└└└ | Smooth White<br>Gloss<br><b>(SWT)</b> | FSP-211 with<br>Motion Sensor<br><b>(FSP-20) ④</b> | Rotated Optic Left<br><b>(ROL)</b>               | 14'<br><b>(14)</b>  |
| MPF Quad<br><b>(QD) ②</b><br>└└└└   | Silver Textured<br><b>(SVR)</b>       | 9'-20" Heights<br><b>(FSP-40) ④</b>                | Rotated Optic Right<br><b>(ROR)</b>              | 16'<br><b>(16)</b>  |
| MPF<br><b>(MPF) ②</b><br>└└└└└      | Black Textured<br><b>(BLK)</b>        | 21'-40' Heights                                    | Buy American<br><b>(BAA) ③</b>                   | No Pole<br><b>(NO)</b>  |
| Wall Mount<br><b>(WM)</b><br>└└└└└└ | Smooth Black<br>Gloss<br><b>(SBK)</b> | Custom Controls<br>Integration<br><b>(CCI) ⑥</b>   | Trade American<br><b>(TAA) ③</b>                 | Aluminum Pole<br>250 Wall<br>Comes With 12" Anchor<br>Base 1" Thick,<br>1" Anchor Bolts |
|                                     | Graphite<br>Textured<br><b>(GPH)</b>  | No Options<br><b>(NO)</b>                          | Build America<br>Buy American<br><b>(BABA) ③</b> |   |
|                                     | Grey<br><b>(GRY)</b>                  |  | No Options<br><b>(NO)</b>                        |   |
|                                     | Custom<br><b>(CS)</b>                 |  |  |   |

**Notes:**

- ① Consult Factory For Lead Time. Consult Factory For 90 CRI Requests.
- ② MPF Mid Pole Fixture. Consult Factory
- ③ Only Available When Ordering NLS Pole
- ④ Universal Voltage 120-277
- ⑤ 3000k or lower must be selected to meet International Dark-Sky Association certification.
- ⑥ Please contact Factory for Custom Control Integration requests (nLight, NX, WaveLinX, Crestron, DMX/RDM, Synapse, Casambi, Dali II, Avi-On, or other control systems)
- ⑦ Turtle Safe
- ⑧ Consult factory for all BAA/TAA/BABA requests



701 Kingshill Place, Carson, CA 90746  
P: (310) 341-2037

nslighting.com

# PRODUCT SPECIFICATIONS

## ELECTRICAL

- 120-277 Volts (UNV) or 347-480 Volts (HV)
- 0-10V dimming driver
- Driver power factor at maximum load is  $\geq .95$ , THD maximum load is 15%
- LED Drivers Ambient Temp. Min is  $-40^{\circ}\text{C}$  and Ambient Temp. Max ranges from  $50^{\circ}\text{C}$  to  $55^{\circ}\text{C}$  and, in some cases, even higher. Consult the factory for revalidation by providing the fixture catalog string before quoting and specifying it.
- All drivers, controls, and sensors housed in enclosed compartment
- CRI 70, 80, or 90
- Color temperatures: Amber, 2700K, 3000K, 3500K, 4000K, 5000K
- Surge Protection: 20KA supplied as standard.

## CONSTRUCTION

- Extruded Aluminum
- Internal cooling fins
- Corrosion resistant external hardware
- One-piece silicone gasket ensures water tight seal for electronics compartment
- Two-piece silicone Micro Optic system ensures IP67 seal around each PCB

## OPTIONS

- NEMA 7-Pin Receptacle (PE7). Only available when ordering NLS pole.
- PHOTO CELL (PC)
- DIMMING CONTROL (FSP-20) (FSP-40)
- MARINE GRADE FINISH (MGF)—A multi-step process creating protective finishing coat against harsh environments. Chemically washed in a 5 stage cleaning system. Pre-baked, Powder coated 3-5 mils of Zinc Rich Super Durable Polyester Primer. Oven Baked. Finished Powder Coating of Super Durable Polyester Powder Coat 3-5 mil thickness.
- SHIELD (HSS)—House Side Shield is designed for full property line cut-off.
- ROTATED OPTICS (ROL) (ROR)

## CONTROL OPTIONS

- FSP-211 with Motion Sensor (FSP-XX)—Passive infrared (PIR) sensor providing multi-level control based on motion/daylight contribution.
- All control parameters adjustable via wireless configuration remote storing and transmitting sensor profiles.
  - FSP-20 mounting heights 9-20 feet
  - FSP-40 mounting heights 21-40 feet.
  - Includes 5 dimming event cycles, 0-10V dimming with motion sensing, re-programmable in the field.
  - Motion sensor mounted to access cover
  - FSIR-100 commissioning remote is required to change sensor settings. Please contact factory for ordering.
- NEMA 7-PIN RECEPTACLE (PE7)—An ANSI C136.41-2013 receptacle provides electrical and mechanical interconnection between photo control cell and luminaire. Dimming receptacle available two or four dimming contacts supports 0-10 VDC dimming methods or Digital Addressable Lighting Interface (DALI), providing reliable power interconnect.
- Controls Agnostic: Please contact factory for your preferred controls option. (nLight, NX, WaveLinX, Crestron, DMX/RDM, Synapse, Casambi, DALI II, Avi-On, or other control systems)

## FINISH

- 3-5 mils electrostatic powder coat.
- NLS Lighting standard high-quality finishes prevent corrosion and protects against extreme environmental conditions

## WARRANTY

Five-year limited warranty for drivers and LEDs.

## OPTICS

Silicone optics high thermal stability and light output provide higher powered LEDs with minimized lumen depreciation. UV stability with scratch resistance increases exterior application durability. Silicone optics do not yellow, crack or brittle over time

## LISTINGS

- Certified to UL 1598
- UL 8750
- CSA C22.2 No. 250.0
- IP65/ IP67 Rated
- IK10 Rated

## BUY AMERICAN OPTION

While all of the NLS Lighting products listed in this document qualify for the Buy America(n) Act of 1933, we reserve the right to change our listings without notice.

The information provided above is for general informational purposes only. We encourage you to consult legal professionals for advice particular to your projects concerning BAA, TAA, BABA or Buy America.

Additional NLS Products that meet BAA, TAA standards can be found at the following link:

<https://nslighting.com/buy-american/>



The information and specifications on this document are subject to change without any notification. All values are design, nominal, typical or prorated values when measured under internal and external laboratory conditions.



701 Kingshill Place, Carson, CA 90746  
P: (310) 341-2037

[nslighting.com](http://nslighting.com)

# PRODUCT SPECIFICATIONS

## TRAC 2 LUMEN CHART

TRAC LUMEN CHART

| PART NUMBER      | T2     | LM/W | BUG      | T3     | LM/W | BUG      | T4     | LM/W | BUG      | T5     | LM/W | BUG      | WATTS |
|------------------|--------|------|----------|--------|------|----------|--------|------|----------|--------|------|----------|-------|
| TRC-2-16L-7-30K7 | 4,385  | 122  | B1-U0-G1 | 4,409  | 122  | B1-U0-G1 | 4,409  | 122  | B1-U0-G1 | 4,495  | 125  | B3-U0-G1 | 36    |
| TRC-2-16L-7-40K7 | 4,604  | 128  | B1-U0-G1 | 4,630  | 129  | B1-U0-G1 | 4,630  | 129  | B1-U0-G1 | 4,720  | 131  | B3-U0-G1 | 36    |
| TRC-2-16L-7-50K7 | 4,604  | 128  | B1-U0-G1 | 4,630  | 129  | B1-U0-G1 | 4,630  | 129  | B1-U0-G1 | 4,720  | 131  | B3-U0-G1 | 36    |
| TRC-2-16L-1-30K7 | 6,022  | 108  | B1-U0-G1 | 6,056  | 108  | B1-U0-G1 | 6,056  | 108  | B1-U0-G1 | 6,174  | 110  | B3-U0-G1 | 56    |
| TRC-2-16L-1-40K7 | 6,323  | 113  | B1-U0-G1 | 6,359  | 114  | B1-U0-G1 | 6,359  | 114  | B1-U0-G1 | 6,482  | 116  | B3-U0-G1 | 56    |
| TRC-2-16L-1-50K7 | 6,323  | 113  | B1-U0-G1 | 6,359  | 114  | B1-U0-G1 | 6,359  | 114  | B1-U0-G2 | 6,482  | 116  | B3-U0-G1 | 56    |
| TRC-2-32L-7-30K7 | 8,770  | 124  | B2-U0-G2 | 8,819  | 124  | B2-U0-G2 | 8,819  | 124  | B2-U0-G2 | 8,990  | 127  | B3-U0-G2 | 71    |
| TRC-2-32L-7-40K7 | 9,208  | 130  | B2-U0-G2 | 9,259  | 130  | B2-U0-G2 | 9,259  | 130  | B2-U0-G2 | 9,439  | 133  | B3-U0-G2 | 71    |
| TRC-2-32L-7-50K7 | 9,208  | 130  | B2-U0-G2 | 9,259  | 130  | B2-U0-G2 | 9,259  | 130  | B2-U0-G2 | 9,439  | 133  | B3-U0-G2 | 71    |
| TRC-2-32L-1-30K7 | 11,797 | 111  | B2-U0-G2 | 11,863 | 112  | B2-U0-G2 | 11,863 | 112  | B2-U0-G2 | 12,094 | 114  | B4-U0-G2 | 106   |
| TRC-2-32L-1-40K7 | 12,387 | 117  | B2-U0-G2 | 12,456 | 118  | B2-U0-G2 | 12,456 | 118  | B2-U0-G2 | 12,698 | 120  | B4-U0-G2 | 106   |
| TRC-2-32L-1-50K7 | 12,387 | 117  | B2-U0-G2 | 12,456 | 118  | B2-U0-G2 | 12,456 | 118  | B2-U0-G2 | 12,698 | 120  | B4-U0-G2 | 106   |

3000k or lower must be selected to meet International Dark-Sky Association certification.

## TRAC 2 LUMEN CHART HSS

| PART NUMBER      | T2 HSS | LM/W | BUG      | T3 HSS | LM/W | BUG      | T4 HSS | LM/W | BUG      | WATTS |
|------------------|--------|------|----------|--------|------|----------|--------|------|----------|-------|
| TRC-2-16L-7-30K7 | 3,227  | 90   | B1-U0-G1 | 3,120  | 87   | B0-U0-G1 | 3,018  | 84   | B0-U0-G1 | 36    |
| TRC-2-16L-7-40K7 | 3,389  | 94   | B1-U0-G1 | 3,276  | 91   | B0-U0-G1 | 3,169  | 88   | B0-U0-G1 | 36    |
| TRC-2-16L-7-50K7 | 3,389  | 94   | B1-U0-G1 | 3,276  | 91   | B0-U0-G1 | 3,169  | 88   | B0-U0-G1 | 36    |
| TRC-2-16L-1-30K7 | 4,433  | 79   | B1-U0-G1 | 4,285  | 77   | B0-U0-G1 | 4,145  | 74   | B1-U0-G1 | 56    |
| TRC-2-16L-1-40K7 | 4,654  | 83   | B1-U0-G1 | 4,499  | 80   | B1-U0-G1 | 4,353  | 78   | B1-U0-G1 | 56    |
| TRC-2-16L-1-50K7 | 4,654  | 83   | B1-U0-G1 | 4,499  | 80   | B1-U0-G1 | 4,353  | 78   | B1-U0-G1 | 56    |
| TRC-2-32L-7-30K7 | 6,454  | 91   | B1-U0-G1 | 6,239  | 88   | B1-U0-G2 | 6,036  | 85   | B1-U0-G2 | 71    |
| TRC-2-32L-7-40K7 | 6,777  | 95   | B1-U0-G2 | 6,551  | 92   | B1-U0-G2 | 6,338  | 89   | B1-U0-G2 | 71    |
| TRC-2-32L-7-50K7 | 6,777  | 95   | B1-U0-G2 | 6,551  | 92   | B1-U0-G2 | 6,338  | 89   | B1-U0-G2 | 71    |
| TRC-2-32L-1-30K7 | 8,683  | 82   | B1-U0-G2 | 8,394  | 79   | B1-U0-G2 | 8,120  | 77   | B1-U0-G2 | 106   |
| TRC-2-32L-1-40K7 | 9,117  | 86   | B1-U0-G2 | 8,813  | 83   | B1-U0-G2 | 8,526  | 80   | B1-U0-G2 | 106   |
| TRC-2-32L-1-50K7 | 9,117  | 86   | B1-U0-G2 | 8,813  | 83   | B1-U0-G2 | 8,526  | 80   | B1-U0-G2 | 106   |

Lumen Maintenance Data

| Ambient Temperature | Drive Current | L90 Hours* | L70 Hours** | 30,000 Hours* | 50,000 Hours* | 60,000 Hours* | 100,000 Hours** |
|---------------------|---------------|------------|-------------|---------------|---------------|---------------|-----------------|
| 25°C                | Up to 700mA   | 58,000     | 173,000     | 95.7%         | 91.6%         | 89.6%         | 82.1%           |
|                     | 1050mA        | 48,000     | 143,000     | 94.3%         | 89.5%         | 87.2%         | 78.5%           |

\*Reported extrapolations per IESNA TM-21      \*\*Projected extrapolations per IESNA TM-21

## POLE EPA DATA

| Catalog Number       | Shaft Length, ft | Wall thickness, in. | Shaft dim., in. | Base Plate, in. | Bolt Circle, in. | Bolts  | 80 mph | Max. wt. (lb) | 90 mph | Max. wt. (lb) | 100 mph | Max. wt. (lb) | 110 mph | Max. wt. (lb) | 115 mph | Max. wt. (lb) | 120 mph | Max. wt. (lb) | 130 mph | Max. wt. (lb) | 140 mph | Max. wt. (lb) | 150 mph | Max. wt. (lb) | 160 mph | Max. wt. (lb) | 170 mph | Max. wt. (lb) | 180 mph | Max. wt. (lb) |
|----------------------|------------------|---------------------|-----------------|-----------------|------------------|--------|--------|---------------|--------|---------------|---------|---------------|---------|---------------|---------|---------------|---------|---------------|---------|---------------|---------|---------------|---------|---------------|---------|---------------|---------|---------------|---------|---------------|
| TRAC-10-250-12BC-136 | 10               | 0.250               | 4x6             | 12" sq          | 12               | 1"x36" | 20.0   | 500           | 20.0   | 500           | 20.0    | 500           | 20.0    | 500           | 20.0    | 500           | 20.0    | 500           | 18.0    | 450           | 14.9    | 373           | 12.6    | 315           | 10.7    | 268           | 9.2     | 230           | 7.6     | 190           |
| TRAC-12-250-12BC-136 | 12               | 0.250               | 4x6             | 12" sq          | 12               | 1"x36" | 20.0   | 500           | 20.0   | 500           | 20.0    | 500           | 20.0    | 500           | 18.9    | 473           | 17.1    | 428           | 14.0    | 350           | 11.5    | 288           | 9.4     | 235           | 7.7     | 193           | 6.5     | 163           | 5.3     | 133           |
| TRAC-14-250-12BC-136 | 14               | 0.250               | 4x6             | 12" sq          | 12               | 1"x36" | 20.0   | 500           | 20.0   | 500           | 20.0    | 500           | 16.9    | 423           | 15.2    | 380           | 13.5    | 338           | 10.8    | 270           | 8.6     | 215           | 6.9     | 173           | 5.6     | 140           | 4.5     | 113           | 3.5     | 88            |
| TRAC-16-250-12BC-136 | 16               | 0.250               | 4x6             | 12" sq          | 12               | 1"x36" | 20.0   | 500           | 20.0   | 500           | 16.6    | 415           | 12.9    | 323           | 11.4    | 285           | 10.0    | 250           | 7.8     | 195           | 6.0     | 150           | 4.4     | 110           | 3.5     | 88            | 2.4     | 60            | 1.8     | -             |




701 Kingshill Place, Carson, CA 90746  
P: (310) 341-2037

nslighting.com

# PRODUCT SPECIFICATIONS


| MODEL    | WIDTH | DEPTH | LENGTH | WEIGHT | EPA | SGL | DBL |
|----------|-------|-------|--------|--------|-----|-----|-----|
| TRAC - 2 | 6"    | 4"    | 23"    | 16     |     | .8  | 1.5 |

## DIMENSIONS




## OPTICAL CONFIGURATIONS

Rotatable Optics (ROR) Rotated Right, (ROL) Rotated Left options available. Optics field and factory rotatable.





## LED KELVIN RANGE



| Color | Dominant or Peak Wavelength Range (nm) |         |
|-------|--|---------|
|       | Minimum                                | Maximum |
| Amber | 585                                    | 600     |



# PRODUCT SPECIFICATIONS

## IES DISTRIBUTIONS



### T2 Optic



The Type II distribution is used for narrow pathways and trails, narrow entrances of shopping centers, parking lots and office complex's.



### T3 Optic

The type III distribution is meant for roadway lighting, general parking areas and other areas where a larger area of lighting is required. Type III lighting needs to be placed to the side of the area, allowing the light to project outward and fill the area. This produces a filling light flow.



Type III light distributions have a preferred lateral width of 40 degrees. This distribution is intended for luminaires mounted at or near the side of medium width roadways or areas, where the width of the roadway or area does not exceed 2.75 times the mounting height.



### T4 Optic

The type IV distribution produces a semicircular light meant for mounting on the sides of buildings and walls. It's best for illuminating the perimeter of parking areas and businesses. The intensity of the Type IV lighting has the same intensity at angles from 90 degrees to 270 degrees.

Type IV light distributions have a preferred lateral width of 60 degrees. This distribution is intended for side-of-road mounting and is generally used on wide roadways where the roadway width does not exceed 3.7 times the mounting height.



### T5 Optic - Symmetrical


Type V produces a symmetrical distribution that has the same intensity at all angles. This distribution has a uniform symmetry of candlepower that is essentially the same at all lateral angles. It is meant for large, commercial parking lot lighting as well as areas where sufficient, evenly distributed light is necessary

## SILICONE OPTICS

NLS Lighting Silicone Micro Optical System technology takes quality and performance to the highest level. Vandal resistant, superior clarity—Micro Optics have become the best and lasting solution in the industry.


### BENEFITS

- Produces superior 96% clarity
- Heat resistant to 150° C, 50% higher than acrylic
- Ecologically friendly—no glare
- Vandal-resistant
- Does not brittle, crack, or yellow over time




# PRODUCT SPECIFICATIONS


## HOUSE SIDE SHIELD




## AUTOMOTIVE HOUSE SIDE SHIELD



## FSP-211



## Motion Sensor Placement



## TRAC POLE RECTANGULAR ALUMINUM POLE

### SHAFT

Rectangular Aluminum Pole (RAP) shaft (.250 Wall) is 6061 T6 Extruded Aluminum, 4 X 6 inch to provide a seamless transition into the Trac fixture. Poles have ground lug welded inside hand-hole opposite side of the pole extrusion. Pole Extrusion is conjoined to Anchor Base by welding internal and external to pole shaft. For custom configuration consult Factory.

### ANCHOR BOLTS

All anchor bolts are fully hot dipped galvanized and come with two galvanized nuts and washers per bolt. Anchor bolts are not included for Custom Bolt Circle. Anchor Bolts are "J" style, with a 4" hook at the end for added strength. 1" Anchor Bolts are 1" diameter x 36" long with a 4" long "J" hook.

### ANCHOR BASE

Base plates are machined from 6061 Aluminum, 12" square, 1" thick with 1" anchor bolts.


### HAND HOLE COVER AND POLE CAP

All poles come with removable machined aluminum pole cap. All poles caps are powder coated to match the pole. All base covers are made of aluminum and powder coated to match the pole. Hand Hole is constructed of 3"x 5" rectangular aluminum tubing which is welded to pole shaft for added strength. Hand Hole covers are provided with internal bridge support and also powder coated to match pole finish.



### FINISH

All poles have minimum 3 to 5 mils powder coat finish. All poles are sandblasted prior to powder coat application.

### RECTANGULAR ALUMINUM POLE DETAIL



- \* Anchor Bolts are NOT included with Custom Bolt Circle.
- \* Do NOT pour concrete referencing this drawing. Consult Factory.
- \* Must Specify 4-Bolt Pattern.
- \* Customer responsible for doing calculations if NLS pole is not ordered.



12" Base

\*Consult Factory for Bolt Circle Template

| DIMENSION | RAP                        |
|-----------|----------------------------|
| A         | 10-16 ft. or Custom Height |
| B         | 6 in.                      |
| C         | 4 in.                      |

|   |                                      |
|---|--------------------------------------|
| Job Name: _____                         | Client Name: _____                   |
| Job Location - City: _____ State: _____ | Created By: _____ Date: _____        |
| Product: DS330 Quote: _____             | Customer Approval: _____ Date: _____ |

## SPECIFICATIONS

**Pole Shaft** - The pole shaft is fabricated from hot rolled welded steel tubing of one-piece construction with a minimum yield strength of 55 KSI.

**Pole Top** - A removable pole cap is provided for poles receiving drilling patterns for side-mount luminaire arm assemblies. For top mount luminaire and/or bracket consult the factory. Consult the luminaire manufacturer for correct tenon size or drill pattern. Other pole top options include pole cap only (PC) or plain top (PL) which is typical when the pole top diameter matches the necessary slip fit dimensions.

**Handhole** - A reinforced handhole with grounding provision is provided at 1'-6" from the base end of the pole assembly. Each handhole includes an easy to install, self-contained Swing Latch handhole cover assembly. U.S. Patent Swing Latch cover is fabricated from durable polycarbonate/ABS blend plastic. All pole assemblies are provided with a 2.50" x 5.00" rectangular handhole. Handhole dimensions are nominal.


**Base Cover** - A two-piece full base cover fabricated from ABS plastic is provided with each pole assembly. Additional base cover options, including the dart square (2T) cast aluminum cover, are available upon request.

**Anchor Bolts** - Anchor bolts conform to ASTM F1554 Grade 55 and are provided with two hex nuts and two flat washers. Bolts have an "L" bend on one end and are galvanized a minimum of 12" on the threaded end.

**Hardware** - All structural fasteners are galvanized high strength carbon steel. All non-structural fasteners are galvanized or zinc-plated carbon steel or stainless steel.

**Finish** - Standard finishes are either Galvanized (GV) or Finish Painted (FP). Additional finish options including Finish Paint over Galvanizing (FPGV) or any of the V-PRO™ Finish Coating Systems are available upon request. See the product ordering code for color options.

**Design Criteria** - Please reference Design Criteria Specification for appropriate design conditions.



\*Consult factory on loading criteria for pole top mounted luminaires and/or brackets.




# DS330

## Fatigue Resistant Soft Square Steel Post

|   |                                      |
|---|--------------------------------------|
| Job Name: _____                         | Client Name: _____                   |
| Job Location - City: _____ State: _____ | Created By: _____ Date: _____        |
| Product: DS330 Quote: _____             | Customer Approval: _____ Date: _____ |

### ANCHORAGE DATA

| POLE                           |                     | BASE PLATE  |           |                |             | ANCHOR BOLTS                |                    |           |  |
|--------------------------------|---------------------|-------------|-----------|----------------|-------------|-----------------------------|--------------------|-----------|--|
| POLE<br>BASE<br>SQUARE<br>(IN) | WALL<br>THK<br>(GA) | BOLT CIRCLE |           | SQUARE<br>(IN) | THK<br>(IN) | DIA x LENGTH x HOOK<br>(IN) | PROJECTION<br>(IN) | ±<br>(IN) |  |
|                                |                     | DIA<br>(IN) | ±<br>(IN) |                |             |                             |                    |           |  |
| 4.00                           | 11                  | 8.50        | 0.50      | 8.25           | 0.750       | 0.75 x 17.00 x 3.00         | 3.50               | 0.25      |  |
| 4.00                           | 7                   | 8.50        | 0.50      | 8.25           | 0.875       | 0.75 x 17.00 x 3.00         | 3.63               | 0.25      |  |
| 5.00                           | 11                  | 11.00       | 1.00      | 11.00          | 1.000       | 0.75 x 17.00 x 3.00         | 3.75               | 0.25      |  |
| 5.00                           | 7                   | 11.00       | 1.00      | 11.00          | 1.000       | 0.75 x 17.00 x 3.00         | 3.75               | 0.25      |  |
| 6.00                           | 7                   | 12.00       | 1.00      | 12.50          | 1.000       | 1.00 x 36.00 x 4.00         | 4.25               | 0.25      |  |



### DESIGNATION, LOAD AND DIMENSIONAL DATA






| NOMINAL<br>MOUNTING<br>HEIGHT | DESIGN INFORMATION                |                                     |                                   |                                     |                                   |                                     | POLE DIMENSIONS <sup>3</sup>                 |                                |                     |   | DESIGNATION |
|-------------------------------|-----------------------------------|-------------------------------------|-----------------------------------|-------------------------------------|-----------------------------------|-------------------------------------|--|--------------------------------|---------------------|---|-------------|
|                               | 80 MPH<br>w/1.3 GUST              |                                     | 90 MPH<br>w/1.3 GUST              |                                     | 100 MPH<br>w/1.3 GUST             |                                     | SHAFT<br>BASE<br>SQUARE <sup>3</sup><br>(IN) | SHAFT<br>TOP<br>SQUARE<br>(IN) | WALL<br>THK<br>(GA) | STRUCTURE<br>WEIGHT <sup>2</sup><br>(LBS) |             |
|                               | MAX<br>EPA <sup>1</sup><br>(SQFT) | MAX<br>WEIGHT <sup>1</sup><br>(LBS) | MAX<br>EPA <sup>1</sup><br>(SQFT) | MAX<br>WEIGHT <sup>1</sup><br>(LBS) | MAX<br>EPA <sup>1</sup><br>(SQFT) | MAX<br>WEIGHT <sup>1</sup><br>(LBS) |  |                                |                     |   |             |
| 10'-0"                        | 30.6                              | 765                                 | 23.8                              | 595                                 | 18.9                              | 473                                 | 4.00   | 4.00                           | 11                  | 75  | 400Q100     |
| 12'-0"                        | 24.4                              | 610                                 | 18.8                              | 470                                 | 14.8                              | 370                                 | 4.00   | 4.00                           | 11                  | 90  | 400Q120     |
| 14'-0"                        | 19.9                              | 498                                 | 15.1                              | 378                                 | 11.7                              | 293                                 | 4.00   | 4.00                           | 11                  | 100                                       | 400Q140     |
| 16'-0"                        | 15.9                              | 398                                 | 11.8                              | 295                                 | 8.9                               | 223                                 | 4.00   | 4.00                           | 11                  | 115                                       | 400Q160     |
| 18'-0"                        | 12.6                              | 315                                 | 9.2                               | 230                                 | 6.7                               | 168                                 | 4.00   | 4.00                           | 11                  | 125                                       | 400Q180     |
| 20'-0"                        | 9.6                               | 240                                 | 6.7                               | 167                                 | 4.5                               | 150                                 | 4.00   | 4.00                           | 11                  | 140                                       | 400Q200     |
|                               | 17.7                              | 443                                 | 12.7                              | 343                                 | 9.4                               | 235                                 | 5.00   | 5.00                           | 11                  | 185                                       | 500Q200     |
|                               | 28.1                              | 703                                 | 21.4                              | 535                                 | 16.2                              | 405                                 | 5.00   | 5.00                           | 7                   | 265                                       | 500W200     |
| 25'-0"                        | 4.8                               | 150                                 | 2.6                               | 100                                 | 1.0                               | 50                                  | 4.00   | 4.00                           | 11                  | 170                                       | 400Q250     |
|                               | 10.8                              | 270                                 | 7.7                               | 188                                 | 5.4                               | 135                                 | 4.00   | 4.00                           | 7                   | 245                                       | 400W250     |
|                               | 9.8                               | 245                                 | 6.3                               | 157                                 | 3.7                               | 150                                 | 5.00   | 5.00                           | 11                  | 225                                       | 500Q250     |
|                               | 18.5                              | 463                                 | 13.3                              | 333                                 | 9.5                               | 238                                 | 5.00   | 5.00                           | 7                   | 360                                       | 500W250     |
| 30'-0"                        | 6.7                               | 168                                 | 4.4                               | 110                                 | 2.6                               | 65                                  | 4.00   | 4.00                           | 7                   | 291                                       | 400W300     |
|                               | 4.7                               | 150                                 | 2.0                               | 50                                  | N/A                               | N/A                                 | 5.00   | 5.00                           | 11                  | 265                                       | 500Q300     |
|                               | 10.7                              | 267                                 | 6.7                               | 167                                 | 3.9                               | 100                                 | 5.00   | 5.00                           | 7                   | 380                                       | 500W300     |
|                               | 19.0                              | 475                                 | 13.2                              | 330                                 | 9.0                               | 225                                 | 6.00   | 6.00                           | 7                   | 520                                       | 600W300     |
| 35'-0"                        | 5.9                               | 150                                 | 2.5                               | 100                                 | N/A                               | N/A                                 | 5.00   | 5.00                           | 7                   | 440                                       | 500W350     |
|                               | 12.4                              | 310                                 | 7.6                               | 190                                 | 4.2                               | 105                                 | 6.00   | 6.00                           | 7                   | 540                                       | 600W350     |
| 40'-0"                        | 7.2                               | 180                                 | 3.0                               | 75                                  | N/A                               | N/A                                 | 6.00   | 6.00                           | 7                   | 605                                       | 600W400     |

- Maximum EPA (Effective Projected Area) and weight values are based on side mounted fixtures only. Consult factory on loading criteria for pole mounted luminaires and/or brackets. Variations from sizes above are available upon inquiry at the factory. Satisfactory performance of poles is dependent upon the pole being properly attached to a supporting foundation of adequate design.
- Structure weight is a nominal value which includes the shaft and base plate only.
- Belled-bottom will have reduced thickness due to the cold-working process. However, the belled-bottom meets or exceeds the structural capacity of the original square section. In addition, the rounded section provides better fatigue resistance.

### PRODUCT ORDERING CODES

| MODEL | DESIGNATION  | FIXTURE MOUNTING  | FINISH SYSTEM  | STANDARD COLOR OPTIONS   | BASE COVER  | ANCHOR BOLTS   | SUPPLEMENTAL INFO |
|-------|--|---|--|--|---|--|-------------------|
| DS330 | Select Correct Designation from the Load and Dimensional Data Chart. | <b>Drill Mounting (See Orientation)</b><br>D1 = (1) Drillings @ 270°<br>D2 = (2) Drillings @ 90° & 270°<br>D4 = (4) Drillings @ 0°, 90°, 180°, & 270°<br>D5 = (2) Drillings @ 180° & 270°<br>D6 = (3) Drillings @ 90°, 180°, & 270°<br><b>Tenon Mounting</b><br>P2 = 2.38" OD x 4" tenon<br>P4 = 4.00" OD x 6" tenon<br>P5 = 2.88" OD x 4" tenon<br>P6 = 2.88" OD x 5" tenon<br>P7 = 2.38" OD x 5" tenon<br>P9 = Special Size (Specify)<br><b>Other Options</b><br>PC = Pole Cap<br>PL = Plain Top (No Cap) | GV = Galvanized<br>FP = Finish Painted<br>-----<br>-----OPTIONAL-----<br>FPGV = Finish Paint over Galvanizing<br>VP30 = V-PRO™ 30 System<br>VP32 = V-PRO™ 32 System<br>VP53 = V-PRO™ 53 System<br>VP54 = V-PRO™ 54 System<br>VP57 = V-PRO™ 57 System<br>VP100 = V-PRO™ 100 System<br>VP105 = V-PRO™ 105 System | GV = Galvanized<br>BK = Black<br>DB = Dark Bronze<br>MB = Medium Bronze<br>WH = White<br>LG = Light Gray<br>CB = Bronze<br>DG = Dark Green<br>ST = Sandstone<br>HTG = Hunter Green<br>SG = Slate Gray<br>SL = Silver<br>SC = Special Color (Specify) | FBC = Full Base Cover<br>-----OPTIONAL-----<br>2T = Square Dart Cover | AB = With Anchor Bolts<br>LAB = Without Anchor Bolts |                   |

# DS330 - Fatigue Resistant Square Non-Tapered Steel Pole



SPC7207 12/17 valmontstructures.com carries the most current spec information and supersedes these guidelines.

# LITESPHERE 2.0



tivoli®




Project: \_\_\_\_\_ TYPE: \_\_\_\_\_

## Product Features


- Tivoli's next evolution of Litesphere delivers a robust specification-grade strand with factory molded standard spacing for consistent quality from start to finish
- Litesphere 2.0 design provides optional suspended mounting or a twist-off cap for surface applications
- 12V DC Low voltage system for long runs
- IP67
- cULus
- 3 Year warranty



## Dimensions



## System Configuration Example



## Strand Order Guide

**Note:** For suspension application, a catenary cable is required for proper installation. Please contact Tivoli for recommendations on unique mounting applications.

| Product                       | Wire                             | Spacing   | LED Type  | LED Color   | Globe  | Voltage          |
|-------------------------------|----------------------------------|---|---|---|--|------------------|
| <b>LSL2</b><br>Litesphere 2.0 | <b>B</b> Black<br><b>W</b> White | <b>06</b> 6" OC<br><b>12</b> 12" OC<br><b>18</b> 18" OC<br><b>24</b> 24" OC<br><b>36</b> 36" OC<br><b>48</b> 48" OC | <b>V</b> Very High Output<br><b>H</b> High Output<br><b>S</b> Standard Output | <b>19</b> 1900K<br><b>27</b> 2700K<br><b>30</b> 3000K<br><b>35</b> 3500K<br><b>40</b> 4000K<br><b>50</b> 5000K*<br><b>AM</b> Amber*<br><b>RB</b> Royal Blue*<br><b>RD</b> Red*<br><b>GN</b> Green*<br><b>YL</b> Yellow* | <b>C</b> Clear<br><b>F</b> Frosted<br><b>O</b> Opal<br><b>R</b> Red<br><b>N</b> Orange<br><b>Y</b> Yellow<br><b>G</b> Green<br><b>B</b> Blue<br><b>P</b> Purple<br><b>Z</b> Varried Colors | <b>12</b> 12V DC |

\*Available in VHO LED only

### Power Lead Order Guide

Figure A - All Litesphere 2.0 are evenly cut between globes according to specified spacing.  
 Figure B - Power leads are added to the end cut, extending the total length of the power lead.

**LSL2-XEP-X-XX**

X = B (Black), W (White)  
 XX = 05 (5'), 10 (10'), 15 (15'), 20 (20'), 25 (25')  
 For custom length consult factory

Figure A





Figure B



### Jumper Order Guide

Figure A - All Litesphere 2.0 are evenly cut between globes according to specified spacing.  
 Figure B - Jumpers are added between the cuts, extending the total length of wire between globes.

**LSL2-JUMPER-X-XX**

X = B (Black), W (White)  
 XX = 05 (5'), 10 (10')  
 For custom length, consult factory

Figure A





Figure B



## Specifications

| <b>Output - Standard Brightness</b>        | 6"  | 12"  | 18"  | 24"  | 36"  | 48"  |
|--|---|------|------|------|------|------|
| Lumens/ft                                  | 11  | 6    | 4    | 3    | 2    | N/A  |
| Watts/ft                                   | 0.17  | 0.09 | 0.06 | 0.04 | 0.03 | 0.02 |
| Maximun Electrical Run                     | 130'  | 180' | 230' | 250' | 275' | 275' |
| <b>Output - High Output</b>                | 6"  | 12"  | 18"  | 24"  | 36"  | 48"  |
| Lumens/ft                                  | 29.9  | 15   | 10   | 7    | 5    | N/A  |
| Watts/ft                                   | 0.46  | 0.23 | 0.15 | 0.12 | 0.08 | 0.05 |
| Maximun Electrical Run                     | 80'   | 110' | 130' | 150' | 175' | 200' |
| <b>Output - Very High Output</b>           | 6"  | 12"  | 18"  | 24"  | 36"  | 48"  |
| Lumens/ft                                  | 180   | 90.2 | 60   | 45   | 30   | N/A  |
| Watts/ft                                   | 1.92  | 0.96 | 0.64 | 0.48 | 0.32 | 0.24 |
| Maximun Electrical Run                     | 30'   | 55'  | 70'  | 80'  | 90   | 100' |
| <b>Output - Based on 3000K Clear Globe</b> |   |      |      |      |      |      |
| Efficacy                                   | Standard Brightness (40), High Output (46), Very High Output (94)                                 |      |      |      |      |      |
| <b>Electrical</b>                          |   |      |      |      |      |      |
| Input Voltage                              | 12V DC  |      |      |      |      |      |
| Power Consumption (W/LED)                  | Standard Brightness (.09), High Output (.23), Very High Output (.96)                              |      |      |      |      |      |
| <b>Control</b>                             |   |      |      |      |      |      |
| Control System                             | 0-10V, ELV, MLV, DMX 512 (Dim to 1% with an Infinity power supply and a 0-10V Lutron Diva dimmer) |      |      |      |      |      |
| <b>Physical</b>                            |   |      |      |      |      |      |
| Dimensions                                 | 2.5"W x 3.8"H   |      |      |      |      |      |
| Socket Housing                             | PVC   |      |      |      |      |      |
| American Wire Gauge                        | 14 AWG  |      |      |      |      |      |
| Globe                                      | PE  |      |      |      |      |      |
| Mounting                                   | Surface Mount, Suspended  |      |      |      |      |      |
| Operating Temperature                      | -20°C to 50°C (-4°F to 122°F)   |      |      |      |      |      |
| Storage Temperature                        | -40°C to 80°C (-40°F to 176°F)  |      |      |      |      |      |
| <b>Certification and Testing</b>           |   |      |      |      |      |      |
| Certification                              | cULus   |      |      |      |      |      |
| Environment                                | Wet Location  |      |      |      |      |      |
| Lumen Maintenance (L70) Hours              | 70,000  |      |      |      |      |      |
| IP Rating                                  | IP67  |      |      |      |      |      |
| Warranty                                   | 3 Years   |      |      |      |      |      |

**Specifications**

| <b>EPA</b> | <b>6"</b> | <b>12"</b> | <b>18"</b> | <b>24"</b> | <b>36"</b> | <b>48"</b> |
|------------|-----------|------------|------------|------------|------------|------------|
| Standard   | 0.10      | 0.06       | 0.05       | 0.04       | N/A        | N/A        |
| Hat 8"     | N/A       | 0.53       | 0.37       | 0.28       | N/A        | N/A        |
| Hat 13"    | N/A       | N/A        | 0.93       | 0.71       | N/A        | N/A        |
| Dish 10"   | N/A       | 0.82       | 0.55       | 0.42       | N/A        | N/A        |
| Flower 10" | N/A       | 0.82       | 0.55       | 0.42       | N/A        | N/A        |
| Flower 13" | N/A       | N/A        | 0.93       | 0.71       | N/A        | N/A        |

| <b>Weights</b>            | <b>6"</b> | <b>12"</b> | <b>18"</b> | <b>24"</b> | <b>36"</b> | <b>48"</b> |
|---------------------------|-----------|------------|------------|------------|------------|------------|
| lb/ft                     | 0.33      | 0.28       | 0.24       | 0.20       | 0.17       | 0.13       |
| lb/ft with catenary cable | 0.35      | 0.30       | 0.26       | 0.22       | 0.19       | 0.15       |



## Mounting Options

### SURFACE/FLUSH

For surface mount applications, remove the top suspension-plate by turning counter-clockwise until off. Place socket flush against the desired surface and mount using proper screws according to substrate.



### SUSPENDED

Suspended mounting will use a combination of LS-Cable, LS-Locks with LS-UVZP. Tension the cable wire with our LS-TT (Tension Tool) for desired sag (Please adhere to local city code for suspended application).

**Note:** For suspension application, a catenary cable is required for proper installation. Please contact Tivoli for recommendations on unique mounting applications.



## Mounting Accessories



**LS-CABLE-60 Catenary Cable Kit - 60'**  
 (1/8" galvanized cable includes 2 cable locks for use with loads up to 200lbs)

**LS-CABLE-110 Catenary Cable Kit - 110'**  
 (1/8" galvanized cable includes 2 cable locks for use with loads up to 200lbs)

**LS-CABLE-500 Catenary Cable Kit - 500'**  
 (1/8" galvanized cable for use with loads up to 200lbs)



**LS-LOCK-X Cable Lock**  
 X = 2 (2 Locks), 4 (4 locks) Includes (1) cable release key. Cable Lock for 1/8th inch cable, Heavy-duty lockable fasteners support loads up to 200 lbs. Can be easily adjusted without the use of tools.




**LS-TT**  
 Catenary Cable Tensioning Tool up to 880lbs with minimal effort due to the 6:1 gear drive mechanism. Integral torque gauge controls the load applied to the wire, giving consistent tension every time and optimizing the life of the wire.




**LS-UVZP-BK-XX**  
 XX = 30 (30pcs), 50 (50pcs)  
 Black UV resistant, heavy duty ties.  
 Maximum weight up to 100 lbs./per tie.

Light Shades

HAT



**SHADE-HT-BK-BK-8**  
Light Shade - HAT  
8.3" Black Top, Black Bottom  
Weight: 0.38 lb




**SHADE-HT-BK-BK-13\***  
Light Shade - HAT  
12.6" Black Top, Black Bottom  
Weight: 1.06 lb

**SHADE-HT-BK-CO-13 \***  
Light Shade - HAT  
12.6" Black Top, Copper Bottom  
Weight: 1.06 lb


\*Consult factory for lead time and MOQ

DISH




**SHADE-DS-BK-BK-10**  
Light Shade - DISH  
10.2" Black Top, Black Bottom  
Weight: 0.72 lb

FLOWER




**SHADE-FL-BK-BK-10**  
Light Shade - FLOWER  
9.8" Light Shade, Black Top, Black Bottom  
Weight: 0.54 lb



**SHADE-FL-BK-BK-13**  
Light Shade - FLOWER  
13.8" Light Shade, Black Top, Black Bottom  
Weight: 1.1 lb

Accessories



**SHADE-ADP-LSL2-XX-01** 2.0 Light Shade Adapter

X = BK (Black), WH (White)  
PVC Black Adapter - Sold individually.

**SHADE-ADP-LSL2-XX-25** 2.0 Light Shade Adapter

X = BK (Black), WH (White)  
PVC Black Adapter Kit - Sold in packs of 25

**SHADE-ADP-LSL2-XX-50** 2.0 Light Shade Adapter

X = BK (Black), WH (White)  
PVC Black Adapter Kit - Sold in packs of 50

## Replacement Parts



Very High Output



Standard & High Output



**LSL-19-V-12**  
12V Wedge base  
1900K  
**LSL-27-V-12**  
12V Wedge base  
2700K  
**LSL-30-V-12**  
12V Wedge base  
3000K  
**LSL-35-V-12**  
12V Wedge base  
3500K  
**LSL-40-V-12**  
12V Wedge base  
4000K  
**LSL-50-V-12**  
12V Wedge base  
5000K

**LSL-AM-V-12**  
12V Wedge base  
Amber  
**LSL-RD-V-12**  
12V Wedge base  
Red  
**LSL-RB-V-12**  
12V Wedge base  
Royal Blue  
**LSL-GN-V-12**  
12V Wedge base  
Green  
**LSL-YL-V-12**  
12V Wedge base  
Yellow

**STANDARD**  
**LSL-19-S-12**  
12V Wedge base  
1900K  
**LSL-27-S-12**  
12V Wedge base  
2700K  
**LSL-30-S-12**  
12V Wedge base  
3000K  
**LSL-35-S-12**  
12V Wedge base  
3500K  
**LSL-40-S-12**  
12V Wedge base  
4000K

**HIGH OUTPUT**  
**LSL-19-H-12**  
12V Wedge base  
1900K  
**LSL-27-H-12**  
12V Wedge base  
2700K  
**LSL-30-H-12**  
12V Wedge base  
3000K  
**LSL-35-H-12**  
12V Wedge base  
3500K  
**LSL-40-H-12**  
12V Wedge base  
4000K

**LST-CG**  
Clear globe  
**LST-FG**  
Frosted globe  
**LST-OG**  
Opal globe  
**LST-OR**  
Orange globe  
**LST-YG**  
Yellow globe  
**LST-GG**  
Green globe  
**LST-BG**  
Blue globe  
**LST-PG**  
Purple globe

**LSL2-EC-X**  
X = B (black), W (white)  
Litesphere 2.0 End-Cap  
Weight: 0.0375 lb  
sold each


## Photometrics

### Frosted Globe - Based on 3000K LED

#### Standard Brightness

PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| POLAR GRAPH AND MAXIMUM CANDELA INTENSITY |                             |                           |
|---|-----------------------------|---------------------------|
| Maximum Candela                           | Location - Horizontal Angle | Location - Vertical Angle |
| 1.6                                       | 0                           | 7.5                       |




Maximum Candela = 1.6 Located At Horizontal Angle = 0, Vertical Angle = 7.5  
# 1 - Vertical Plane Through Horizontal Angles (0 - 180) (Through Max. Cd.)  
# 2 - Horizontal Cone Through Vertical Angle (7.5) (Through Max. Cd.)

#### High Output

PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| POLAR GRAPH AND MAXIMUM CANDELA INTENSITY |                             |                           |
|---|-----------------------------|---------------------------|
| Maximum Candela                           | Location - Horizontal Angle | Location - Vertical Angle |
| 4   | 0                           | 10                        |




Maximum Candela = 4 Located At Horizontal Angle = 0, Vertical Angle = 10  
# 1 - Vertical Plane Through Horizontal Angles (0 - 180) (Through Max. Cd.)  
# 2 - Horizontal Cone Through Vertical Angle (10) (Through Max. Cd.)

#### Very High Output

PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| POLAR GRAPH AND MAXIMUM CANDELA INTENSITY |                             |                           |
|---|-----------------------------|---------------------------|
| Maximum Candela                           | Location - Horizontal Angle | Location - Vertical Angle |
| 18.5                                      | 0                           | 7.5                       |



Maximum Candela = 18.5 Located At Horizontal Angle = 0, Vertical Angle = 7.5  
# 1 - Vertical Plane Through Horizontal Angles (0 - 180) (Through Max. Cd.)  
# 2 - Horizontal Cone Through Vertical Angle (7.5) (Through Max. Cd.)


## Photometrics

### Opal Globe - Based on 3000K LED

#### Standard Brightness

PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| POLAR GRAPH AND MAXIMUM CANDELA INTENSITY |                             |                           |
|---|-----------------------------|---------------------------|
| Maximum Candela                           | Location - Horizontal Angle | Location - Vertical Angle |
| 0.5                                       | 0                           | 7.5                       |




Maximum Candela = .5 Located At Horizontal Angle = 0, Vertical Angle = 7.5  
 # 1 - Vertical Plane Through Horizontal Angles (0 - 180) (Through Max. Cd.)  
 # 2 - Horizontal Cone Through Vertical Angle (7.5) (Through Max. Cd.)

#### High Output

PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| POLAR GRAPH AND MAXIMUM CANDELA INTENSITY |                             |                           |
|---|-----------------------------|---------------------------|
| Maximum Candela                           | Location - Horizontal Angle | Location - Vertical Angle |
| 1   | 0                           | 50                        |




Maximum Candela = 1 Located At Horizontal Angle = 0, Vertical Angle = 50  
 # 1 - Vertical Plane Through Horizontal Angles (0 - 180) (Through Max. Cd.)  
 # 2 - Horizontal Cone Through Vertical Angle (50) (Through Max. Cd.)

#### Very High Output

PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| POLAR GRAPH AND MAXIMUM CANDELA INTENSITY |                             |                           |
|---|-----------------------------|---------------------------|
| Maximum Candela                           | Location - Horizontal Angle | Location - Vertical Angle |
| 5.9                                       | 0                           | 77.5                      |




Maximum Candela = 5.9 Located At Horizontal Angle = 0, Vertical Angle = 77.5  
 # 1 - Vertical Plane Through Horizontal Angles (0 - 180) (Through Max. Cd.)  
 # 2 - Horizontal Cone Through Vertical Angle (77.5) (Through Max. Cd.)

### Clear Globe - Based on 3000K LED

#### Standard Brightness

PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| POLAR GRAPH AND MAXIMUM CANDELA INTENSITY |                             |                           |
|---|-----------------------------|---------------------------|
| Maximum Candela                           | Location - Horizontal Angle | Location - Vertical Angle |
| 2.3                                       | 0                           | 10                        |




Maximum Candela = 2.3 Located At Horizontal Angle = 0, Vertical Angle = 10  
 # 1 - Vertical Plane Through Horizontal Angles (0 - 180) (Through Max. Cd.)  
 # 2 - Horizontal Cone Through Vertical Angle (10) (Through Max. Cd.)

#### High Output

PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| POLAR GRAPH AND MAXIMUM CANDELA INTENSITY |                             |                           |
|---|-----------------------------|---------------------------|
| Maximum Candela                           | Location - Horizontal Angle | Location - Vertical Angle |
| 6.1                                       | 0                           | 10                        |




Maximum Candela = 6.1 Located At Horizontal Angle = 0, Vertical Angle = 10  
 # 1 - Vertical Plane Through Horizontal Angles (0 - 180) (Through Max. Cd.)  
 # 2 - Horizontal Cone Through Vertical Angle (10) (Through Max. Cd.)

#### Very High Output

PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| POLAR GRAPH AND MAXIMUM CANDELA INTENSITY |                             |                           |
|---|-----------------------------|---------------------------|
| Maximum Candela                           | Location - Horizontal Angle | Location - Vertical Angle |
| 25.3                                      | 22.5                        | 12.5                      |



Maximum Candela = 25.3 Located At Horizontal Angle = 22.5, Vertical Angle = 12.5  
 # 1 - Vertical Plane Through Horizontal Angles (22.5 - 202.5) (Through Max. Cd.)  
 # 2 - Horizontal Cone Through Vertical Angle (12.5) (Through Max. Cd.)

## Power Supplies

### ADNM - NON DIMMING

| DESCRIPTION                        | CAT NO            | APPLICATION         | PRIMARY VOLTAGE         | SECONDARY VOLTAGE | CIRCUIT BREAKERS | MAX LOAD | CIRCUIT CAPACITY |
|------------------------------------|-------------------|---------------------|-------------------------|-------------------|------------------|----------|------------------|
| ADNM Series<br>Class 2 Transformer | ADNM-60-1-5-12-D  | Indoor /<br>Outdoor | 100-277V AC<br>50/60 HZ | 12V DC            | 1                | 60W      | 5A               |
|                                    | ADNM-80-1-5-12-D  |                     |                         |                   | 1                | 60W      | 5A               |
|                                    | ADNM-150-2-5-12-D |                     |                         |                   | 2                | 2x60W    | 2x5A             |
|                                    | ADNM-240-3-5-12-D |                     |                         |                   | 3                | 3x60W    | 3x5A             |
|                                    | ADNM-320-4-5-12-D |                     |                         |                   | 4                | 4x60W    | 4x5A             |

### ADNM - 0-10V DIMMING

| DESCRIPTION                        | CAT NO              | APPLICATION         | PRIMARY VOLTAGE         | SECONDARY VOLTAGE | CIRCUIT BREAKERS | MAX LOAD | CIRCUIT CAPACITY |
|------------------------------------|---------------------|---------------------|-------------------------|-------------------|------------------|----------|------------------|
| ADNM Series<br>Class 2 Transformer | ADNM-60-1-5-12-DOT  | Indoor /<br>Outdoor | 100-277V AC<br>50/60 HZ | 12V DC            | 1                | 60W      | 5A               |
|                                    | ADNM-80-1-5-12-DOT  |                     |                         |                   | 1                | 60W      | 5A               |
|                                    | ADNM-150-2-5-12-DOT |                     |                         |                   | 2                | 2x60W    | 2x5A             |
|                                    | ADNM-240-3-5-12-DOT |                     |                         |                   | 3                | 3x60W    | 3x5A             |
|                                    | ADNM-320-4-5-12-DOT |                     |                         |                   | 4                | 4x60W    | 4x5A             |

### ADNM - DMX SINGLE ADDRESS

| DESCRIPTION                        | CAT NO              | APPLICATION         | PRIMARY VOLTAGE         | SECONDARY VOLTAGE | CIRCUIT BREAKERS | MAX LOAD | CIRCUIT CAPACITY |
|------------------------------------|---------------------|---------------------|-------------------------|-------------------|------------------|----------|------------------|
| ADNM Series<br>Class 2 Transformer | ADNM-60-1-5-12-DIN  | Indoor /<br>Outdoor | 100-277V AC<br>50/60 HZ | 12V DC            | 1                | 60W      | 5A               |
|                                    | ADNM-80-1-5-12-DIN  |                     |                         |                   | 1                | 60W      | 5A               |
|                                    | ADNM-150-2-5-12-DIN |                     |                         |                   | 2                | 2x60W    | 2x5A             |
|                                    | ADNM-240-3-5-12-DIN |                     |                         |                   | 3                | 3x60W    | 3x5A             |
|                                    | ADNM-320-4-5-12-DIN |                     |                         |                   | 4                | 4x60W    | 4x5A             |

### ADNM - DMX MULTI ADDRESS

| DESCRIPTION                        | CAT NO                | APPLICATION      | PRIMARY VOLTAGE         | SECONDARY VOLTAGE | CIRCUIT BREAKERS | MAX LOAD | CIRCUIT CAPACITY |
|------------------------------------|-----------------------|------------------|-------------------------|-------------------|------------------|----------|------------------|
| ADNM Series<br>Class 2 Transformer | ADNM-150-2-5-12-DIN-2 | Indoor /<br>Damp | 100-277V AC<br>50/60 Hz | 12V DC            | 2                | 2x60W    | 5A               |
|                                    | ADNM-240-3-5-12-din-3 |                  |                         |                   | 3                | 3x60W    | 3x5A             |

### INFINITY - MLV / ELV / 0-10V / PWM / TRIAC


Dim to 1% with a 0-10V Lutron Diva dimmer (by others)

| DESCRIPTION                            | CAT NO            | APPLICATION         | PRIMARY VOLTAGE | SECONDARY VOLTAGE | CIRCUIT BREAKERS | MAX LOAD | MIN LOAD | CIRCUIT CAPACITY |
|--|-------------------|---------------------|-----------------|-------------------|------------------|----------|----------|------------------|
| Infinity Series<br>Class 2 Transformer | INF-J-30-1-2.5-12 | Indoor /<br>Outdoor | 100 - 277V AC   | 12V DC            | 1                | 30W      | 3W       | 2.5A             |
|  | INF-J-60-1-5-12   |                     |                 |                   | 1                | 60W      | 6W       | 5A               |
|  | INF-J-180-3-5-12  |                     |                 |                   | 3                | 3x60W    | 3x6W     | 3x5A             |
|  | INF-J-300-5-5-12  |                     |                 |                   | 5                | 5x60W    | 5x6W     | 5x5A             |


**Controls**



**TVOQ-1-WH**  
 White  
 512 DMX channel, 16 scene,  
 4 zone, glass touch screen



**TVOQ-10-XX-7**  
 XX = BK (Black), WH (White)  
 1024 DMX channel, 500 scene,  
 10 zone, glass touch screen



**TVOQ-2-BK**  
 Black  
 512 DMX channel, 99 scene,  
 1 zone, glass touch screen

# WAC LIGHTING

## Cubix

Wall Mount 3000K

Fixture Type: \_\_\_\_\_

Catalog Number: \_\_\_\_\_

Project: \_\_\_\_\_

Location: \_\_\_\_\_

| Model      | Color Temp & CRI | Lumens | Finish                            |
|------------|------------------|--------|-----------------------------------|
| WS-W220208 | 30 3000K - 80    | 285    | BK Black<br>BZ Bronze<br>WT White |

Example: **WS-W220208-30-WT**

For custom requests please contact [customs@wacighting.com](mailto:customs@wacighting.com)

### DESCRIPTION

Available in single and double directions, Cylinder is ideal for illuminating outdoor entrances and walkways.

### FEATURES


- Multiple LED array for uniform illumination
- WS-W220208 is one direction, WS-W220212 is an up & down light
- ACLED driverless technology
- 5 Year warranty

### SPECIFICATIONS

|               |  |
|---------------|--|
| Color Temp:   | 3000K  |
| Input:        | 120 VAC,50/60Hz  |
| CRI:          | 80   |
| Dimming:      | ELV: 100-10%   |
| Rated Life:   | 50000 Hours  |
| Mounting:     | Installs over a 3" or 4" Junction Box,Can be mounted on wall in all orientations |
| Standards:    | ETL, cETL<br>Wet Location Listed   |
| Construction: | Die-cast aluminum  |




### FINISHES:



White      Black      Bronze

### LINE DRAWING:



# WAC LIGHTING

## Cubix

Wall Mount 3000K

Fixture Type: \_\_\_\_\_

Catalog Number: \_\_\_\_\_

Project: \_\_\_\_\_

Location: \_\_\_\_\_

| Model      | Color Temp & CRI | Lumens | Finish                            |
|------------|------------------|--------|-----------------------------------|
| WS-W220212 | 30 3000K - 80    | 765    | BK Black<br>BZ Bronze<br>WT White |

Example: **WS-W220212-30-WT**

For custom requests please contact [customs@wacighting.com](mailto:customs@wacighting.com)

### DESCRIPTION

Available in single and double directions, Cylinder is ideal for illuminating outdoor entrances and walkways.

### FEATURES


- Multiple LED array for uniform illumination
- WS-W220208 is one direction, WS-W220212 is an up & down light
- ACLED driverless technology
- 5 Year warranty

### SPECIFICATIONS

|               |  |
|---------------|--|
| Color Temp:   | 3000K  |
| Input:        | 120 VAC,50/60Hz  |
| CRI:          | 80   |
| Dimming:      | ELV: 100-10%   |
| Rated Life:   | 50000 Hours  |
| Mounting:     | Installs over a 3" or 4" Junction Box,Can be mounted on wall in all orientations |
| Standards:    | ETL, cETL<br>Wet Location Listed   |
| Construction: | Die-cast aluminum  |




### FINISHES:



White      Black      Bronze

### LINE DRAWING:





**Site Plan Review Application Fee**

**Project:** 100 Durgin Lane

**Map/Lot:** Map 239, Lots 13, 16, & 18

**Applicant:** 100 Durgin Lane Owner, LLC

All development

*Base fee \$600* \$600.00

*Plus \$5.00 per \$1,000 of site costs*  
Site costs \$5,600,000 + \$28,000.00

*Plus \$10.00 per 1,000 S.F. of site development area*  
Site development area 660,000 S.F. + \$6,600.00

**Fee** **\$20,000.00**

Maximum fee: \$20,000.00

Fee received by: \_\_\_\_\_ Date: \_\_\_\_\_

*Note: Initial application fee may be based on the applicant's estimates of site costs and site development area. Following site plan approval, the application fee will be recalculated based on the approved site plan and site engineer's corresponding site cost estimate as approved by the Department of Public Works, and any additional fee shall be paid prior to the issuance of a building permit.*




**AUTHORIZATION**  
**100 Durgin Lane, Portsmouth**  
**Map 239, Lots 13, 16 & 18**

The undersigned owner and applicant of the above referenced property hereby authorize representatives of Bosen & Associates, PLLC, and Tighe & Bond Civil Engineering to represent their interests before the Portsmouth land use boards and to submit any and all applications and materials related thereto on their behalf solely in connection with the multifamily development thereof.


Oak Street Investment Grade Net Lease  
Fund Series 2021-2, LLC

Date: April 23, 2024

By:   
Name: Ryan Phelan  
Title: Managing Director - Delegatee

100 Durgin Lane Owner, LLC

Date: 4/24/24

By:   
Name: ANDREW HAMER  
Title: AUTHORIZED SIGNER