
CITY OF PORTSMOUTH, NEW HAMPSHIRE PEIRCE ISLAND WASTEWATER TREATMENT FACILITY UPGRADE DECEMBER 2015

VOLUME I OF II



AND

PROJECT NO: **60301525**

DRAWN BY: N. YEE

CAD DWG FILE: 00 G-001 DESIGNED BY: T. WASSELL


DEPT CHECK: C. BENZIGER PROJ CHECK: E. MESERVE

DECEMBER 2015

AS NOTED

00 G-001

| SHEET NO. TITLE | SHEET NO. TITLE | SHEET NO. TITLE | SHEET NO | D. TITLE | VERIPTION SCRIPTION |
|--|--|---|----------------------|---|--|
| GENERAL | ARCHITECTURAL | ARCHITECTURAL (CONT.) | STRUCT | URAL | |
| 00 G-001 COVER SHEET AND LOCUS PLAN | 00 A-001 LEGEND, ABBREVIATIONS AND GENERAL NOTES | 85 A-101 ELECTRICAL BUILDING PLANS AND SECTIONS | 00 S-001 | STRUCTURAL NOTES & ABBREVIATIONS | |
| 00 G-002 INDEX OF DRAWINGS I | 00 A-002 CODE SUMMARY I | 99 A-501 TYPICAL ROOF DETAILS | 00 S-002 | STRUCTURAL NOTES II | 1 ₂ (7) |
| 00 G-003 INDEX OF DRAWINGS II 00 G-004 INDEX OF DRAWINGS III | 00 A-003 CODE SUMMARY II | 99 A-601 DOOR SCHEDULE & TYPES | 00 S-003 | STRUCTURAL NOTES III | |
| 00 G-005 OVERALL SITE PLAN | 00 A-004 CODE SUMMARY III 00 A-005 CODE SUMMARY IV | 99 A-602 WINDOW AND LOUVER SCHEDULES AND TYPES 99 A-603 FINISH SCHEDULE & TYPES | 10 S-101 10 S-102 | HEADWORKS FOUNDATION PLAN HEADWORKS FLOOR PLAN | |
| 00 G-006 HYDRAULIC PROFILE | 00 A-006 CODE SUMMARY V | 99 A-701 DOOR DETAILS I | 10 S-102 | HEADWORKS ROOF PLAN | |
| 00 G-007 DESIGN CRITERIA | 10 A-101 HEADWORKS FLOOR PLAN | 99 A-702 DOOR DETAILS II | 10 S-301 | HEADWORKS SECTIONS I | + |
| CIVIL | 10 A-102 HEADWORKS ROOF PLAN | 99 A-703 WINDOW DETAILS I | 20 S-101 | GRIT BUILDING MODIFICATIONS BASEMENT PLAN | |
| | 10 A-201 HEADWORKS EXTERIOR ELEVATIONS 10 A-301 HEADWORKS WALL SECTIONS I | 99 A-704 WINDOW DETAILS II 99 A-705 LOUVER DETAILS | 20 S-102 20 S-103 | GRIT BUILDING MODIFICATIONS GROUND FLOOR PLAN GRIT BUILDING MODIFICATIONS LINTEL LEVEL PLAN | |
| 00 C-001 LEGEND, ABBREVIATIONS AND GENERAL NOTES 00 C-002 YARD PIPING SCHEDULE | 10 A-302 HEADWORKS WALL SECTIONS II | 99 A-705 EGOVER BETAILS 99 A-706 PARTITION TYPES I | 20 S-301 | GRIT BUILDING MODIFICATIONS SECTIONS I | |
| 00 C-101 EXIST. CONDITIONS, EROSION CONTROL AND BORING LOCATION PLAN I | 10 A-501 HEADWORKS EXTERIOR DETAILS | 99 A-801 STANDARD STAIR DETAILS I | 20 S-302 | GRIT BUILDING MODIFICATIONS SECTIONS II | |
| 00 C-102 EXIST. CONDITIONS, EROSION CONTROL AND BORING LOCATION PLAN II | 10 A-502 HEADWORKS EXTERIOR DETAILS | 99 A-802 STANDARD STAIR DETAILS II | 40 S-101 | PRIMARY CLARIFIER EFFLUENT DIST. BOX MODIFICATION PLAN & SECTION | |
| 00 C-103 CONTRACTOR ACCESS AND STAGING AREA - KEY PLAN | 20 AD 103 CRIT BUILDING BASEMENT LEVEL DEMOLITION PLAN | 99 A-803 STANDARD RAILING DETAILS | 50 S-101 | SOLIDS BUILDING FOUNDATION PLAN | |
| 00 C-104 CONSTRUCTION STAGING AREA - ENLARGED PLAN I 00 C-105 CONSTRUCTION STAGING AREA - ENLARGED PLAN II | 20 AD-102 GRIT BUILDING GROUND LEVEL DEMOLITION PLAN 20 A-101 GRIT BUILDING BASEMENT LEVEL PLAN | 99 A-804 STANDARD LADDER DETAILS 99 A-805 MISCELLANEOUS METALS DETAILS | 50 S-102 50 S-103 | SOLIDS BUILDING FLOOR PLAN @ EL. 20.58 SOLIDS BUILDING FLOOR PLAN @ EL. 29.25 | MAR |
| 00 C-105 CONSTRUCTION STAGING AREA - ENLARGED PLAN III | 20 A-102 GRIT BUILDING GROUND LEVEL PLAN | Wildelia William Bennie | 50 S-104 | SOLIDS BUILDING ROOF PLAN | Ö <u>Z</u> |
| 00 C-107 NOT USED | 20 A-103 GRIT BUILDING ROOF PLAN | | 50 S-301 | SOLIDS BUILDING SECTIONS I | VICES, |
| 00 C-108 DEMOLITION PLAN I | 20 A-301 GRIT BUILDING EXTERIOR ELEVATIONS AND WALL SECTIONS | | 50 S-302 | SOLIDS BUILDING SECTIONS II | AL SER'NE NVE A 0182 05-210 |
| 00 C-109 DEMOLITION PLAN II | 20 A-501 GRIT BUILDING EXTERIOR DETAILS 50 A-101 SOLIDS BUILDING LOWER LEVEL PLAN | | 50 S-303 53 S-101 | SOLIDS BUILDING SECTIONS III GRAVITY THICKENER NO. 2 FOUNDATION PLAN | ECHNICAL LO DRIV, DRD, MA 178) 90: m.com |
| 00 C-110 DEMOLITION PLAN III 00 C-111 SITE LAYOUT, PAVING, GRADING AND DRAINAGE PLAN I | 50 A-101 SOLIDS BUILDING TRUCK BAY LEVEL PLAN | | 53 S-102 | GRAVITY THICKENER NO. 2 TOP PLAN | COM TE O APOIL ELMSFC W. geco |
| 00 C-112 SITE LAYOUT, PAVING, GRADING AND DRAINAGE PLAN II | 50 A-103 SOLIDS BUILDING UPPER LEVEL PLAN | | 60 S-101 | BAF FACILITY FOUNDATION PLAN I | AECC 250 CHEL PHON WWW. |
| 00 C-113 SITE LAYOUT, PAVING, GRADING AND DRAINAGE PLAN III | 50 A-104 SOLIDS BUILDING ROOF PLAN | | 60 S-102 | BAF FACILITY FOUNDATION PLAN II | |
| 00 C-114 SITE LAYOUT, PAVING, GRADING AND DRAINAGE PLAN IV | 50 A-201 SOLIDS BUILDING ELEVATIONS I 50 A-202 SOLIDS BUILDING ELEVATIONS II | | 60 S-103 60 S-104 | BAF FACILITY BAF BOTTOM LEVEL PLAN I BAF FACILITY BAF BOTTOM LEVEL PLAN II | Z |
| 00 C-115 YARD PIPING PLAN I 00 C-116 YARD PIPING PLAN II | 50 A-301 SOLIDS BUILDING WALL SECTIONS I | | 60 S-104 | BAF FACILITY DN EFFLUENT CHANNEL LEVEL PLAN I | |
| 00 C-117 YARD PIPING PLAN III | 50 A-302 SOLIDS BUILDING WALL SECTIONS II | | 60 S-106 | BAF FACILITY DN EFFLUENT CHANNEL LEVEL PLAN II | |
| 00 C-118 YARD PIPING PLAN IV | 50 A-303 SOLIDS BUILDING WALL SECTIONS III | | 60 S-107 | BAF FACILITY ROOF PLAN I | M |
| 00 C-119 YARD PIPING - ENLARGED PLANS | 50 A-401 SOLIDS BUILDING ENLARGED PLANS & ELEVATIONS | | 60 S-108 | BAF FACILITY ROOF PLAN II | " |
| 00 C-120 LANDSCAPE PLAN I 00 C-121 LANDSCAPE PLAN II | 50 A-402 SOLIDS BUILDING STAIR PLANS AND SECTION I 50 A-403 SOLIDS BUILDING STAIR PLANS AND SECTION II | | 60 S-109 60 S-301 | BAF FACILITY PARTIAL PLANS BAF FACILITY SECTIONS I | |
| 00 C-121 LANDSCAPE PLAN II 00 C-122 LANDSCAPE PLAN III | 50 A-501 SOLIDS BUILDING SECTION DETAILS I | | 60 S-302 | BAF FACILITY SECTIONS II | |
| 00 C-123 PIPING PROFILES I | 50 A-502 SOLIDS BUILDING SECTION DETAILS II | | 60 S-303 | BAF FACILITY SECTIONS III | |
| 00 C-124 PIPING PROFILES II | 53 AT-101 GRAVITY THICKENER NO. 2 TEMPORARY PUMP RELOCATION | _ | 60 S-304 | BAF FACILITY SECTIONS IV | HILLIAM CONTROL OF THE CONTROL OF TH |
| 00 C-125 PIPING PROFILES III | 53 AT-501 GRAVITY THICKENER NO. 2 TEMPORARY SECTION & FRAMING DETAILS 60 A-101 BAF FACILITY GALLERY LEVEL PLAN | S | 60 S-305 60 S-306 | BAF FACILITY SECTIONS V BAF FACILITY SECTIONS VI | 3.0 |
| 00 C-126 PIPING PROFILES IV 00 C-127 PIPING PROFILES V | 60 A-101 BAF FACILITY LOWER LEVEL PLAN | | 60 S-307 | BAF FACILITY SECTIONS VII | PARS ARS |
| 00 C-128 PIPING PROFILES VI | 60 A-103 BAF FACILITY UPPER LEVEL PLAN | | 70 S-101 | EFFLUENT DISTRIBUTION BOX MODIFICATION PLAN & SECTIONS | |
| 99 C-501 DETAILS I | 60 A-104 BAF FACILITY ROOF LEVEL PLAN | | 80 SD-101 | OPERATIONS/LAB BUILDING UPPER LEVEL DEMOLITION PLAN | Think Is - S PROMING |
| 99 C-502 DETAILS II | 60 A-201 BAF FACILITY ELEVATIONS 60 A-202 BAF FACILITY ELEVATIONS | | 80 S-101 | OPERATIONS/LAB BUILDING FOUNDATION PLAN | |
| 99 C-503 DETAILS III 99 C-504 DETAILS IV | 60 A-301 BAF FACILITY BUILDING SECTIONS | | 80 S-102 | OPERATIONS/LAB BUILDING UPPER LEVEL PLAN | |
| 99 C-505 DETAILS V | 60 A-302 BAF FACILITY BUILDING SECTIONS | | 80 S-103 | OPERATIONS/LAB BUILDING ROOF PLAN | S |
| 99 C-506 DETAILS VI | 60 A-303 BAF FACILITY WALL SECTIONS | | 80 S-301 80 S-302 | OPERATIONS/LAB BUILDING SECTIONS I OPERATIONS/LAB BUILDING SECTIONS II | ※ |
| 99 C-507 DETAILS VII | 60 A-304 BAF FACILITY WALL SECTIONS 60 A-401 BAF FACILITY STAIR NO. 1 PLANS & SECTION | | 80 S-303 | OPERATIONS/LAB BUILDING SECTIONS III | N N |
| 99 C-508 DETAILS VIII 99 C-509 DETAILS IX | 60 A-401 BAF FACILITY STAIR NO. 1 PLANS & SECTION 60 A-402 BAF FACILITY STAIR NO. 2 PLANS & SECTION | | 80 S-304 | OPERATIONS/LAB BUILDING SECTIONS IV | |
| 99 C-510 DETAILS IX | 60 A-501 BAF FACILITY EXTERIOR DETAILS | | 85 S-101 | ELECTRICAL BUILDING PLAN & SECTIONS | |
| 99 C-511 DETAILS XI - ENLARGED PLANS AND SECTIONS REVETMENT AREAS I | 80 AD-101 OPERATIONS/LAB BUILDING LOWER LEVEL DEMOLITION PLAN | | 99 S-501 | STRUCTURAL STANDARD DETAILS I | OF F |
| 99 C-512 DETAILS XII - ENLARGED PLAN AND SECTIONS REVETMENT AREAS II | 80 AD-102 OPERATIONS/LAB BUILDING UPPER LEVEL DEMOLITION PLAN | | 99 S-502 | STRUCTURAL STANDARD DETAILS II STRUCTURAL STANDARD DETAILS III | MENT O |
| 99 C-513 DETAILS XIII - ENLARGED PLAN AT ELECTRICAL AREA | 80 A-101 OPERATIONS/LAB BUILDING LOWER LEVEL PLAN | | 99 S-503 99 S-504 | STRUCTURAL STANDARD DETAILS IV | |
| 99 C-514 DETAILS XIV | 80 A-102 OPERATIONS/LAB BUILDING UPPER LEVEL PLAN | | 99 S-505 | STRUCTURAL STANDARD DETAILS V | AR M ₹ |
| TRAFFIC MANAGEMENT | 80 A 201 OPERATIONS/LAB BUILDING ROOF PLAN | | 99 S-506 | STRUCTURAL STANDARD DETAILS VI | |
| 00 T-001 TRAFFIC MANAGEMENT PLAN I | 80 A-201 OPERATIONS/LAB BUILDING EXTERIOR ELEVATIONS I 80 A-202 OPERATIONS/LAB BUILDING EXTERIOR ELEVATIONS II | | 99 S-507 | STRUCTURAL STANDARD DETAILS VIII | F N H |
| 00 T-001 TRAFFIC MANAGEMENT PLAN I | 80 A-301 OPERATIONS/LAB BUILDING WALL SECTIONS I | | 99 S-508 | STRUCTURAL STANDARD DETAILS VIII | H, H |
| 00 T-003 TRAFFIC MANAGEMENT PLAN III | 80 A-302 OPERATIONS/LAB BUILDING WALL SECTIONS II | | | | |
| 00 T-004 TRAFFIC MANAGEMENT PLAN IV | 80 A-303 OPERATIONS/LAB BUILDING WALL SECTIONS III | | | | SMOUT PEIRCI NDE |
| 00 T-005 TRAFFIC MANAGEMENT PLAN V | 80 A-304 OPERATIONS/LAB BUILDING WALL SECTIONS IV | | | | |
| 00 T-006 TRAFFIC MANAGEMENT PLAN VI 00 T-007 TRAFFIC MANAGEMENT PLAN VII | 80 A-401 OPERATIONS/LAB BUILDING UPPER LEVEL FURNITURE PLAN | | Γ | STRUCTURE NUMBER LEGEND | <u> </u> |
| 00 T-008 TRAFFIC MANAGEMENT PLAN VIII | 80 A-402 OPERATIONS/LAB BUILDING ENLARGED PLAN AT LABORATORY | | | | Ö |
| | 80 A-403 OPERATIONS/LAB BUILDING INTERIOR ELEVATIONS AT LABORATORY | | | OO GENERAL, LEGENDS, NOTES, SITE WIDE DRAWINGS | CE |
| | 80 A-404 OPERATIONS/LAB BUILDING INTERIOR ELEVATIONS AT LABORATORY | | | 10 HEADWORKS 20 EXISTING GRIT BUILDING | |
| | 80 A-405 OPERATIONS/LAB BUILDING FURNITURE AND EQUIPMENT SCHEDULES 80 A-406 OPERATIONS/LAB BUILDING ENLARGED PLAN LOCKER ROOMS | | | 35 EXISTING GRIT BUILDING 35 EXISTING PRIMARY CLARIFIERS AND PRIMARY CLARIFIER | |
| | 80 A-407 OPERATIONS/LAB BUILDING INTERIOR ELEVATIONS MEN'S LOCKER RO | DOMS | | INFLUENT DISTRIBUTION BOX | PROJECT NO: 60301525 CAD DWG FILE: 00 G-002 |
| | 80 A-408 OPERATIONS/LAB BUILDING INTERIOR ELEVATIONS WOMEN'S & BREAK | | | 40 EXISTING PRIMARY CLARIFIER EFFLUENT DISTRIBUTION BOX | DESIGNED BY: T. WASSELL |
| | 80 A-409 OPERATIONS/LAB BUILDING REFLECTED CEILING PLAN | | | 50 SOLIDS BUILDING | DRAWN BY: N. YEE |
| | 80 A-410 OPERATIONS/LAB BUILDING STAIR AND RAMP I | | | 53 GRAVITY THICKENER No. 2 | DEPT CHECK: C. BENZIGER |
| | 80 A-411 OPERATIONS/LAB BUILDING STAIR AND RAMP II | SHEET DESIGNATION | N LEGEND | 55 EXISTING GRAVITY THICKENER No. 1 | PROJ CHECK: E. MESERVE |
| | 80 A-502 OPERATIONS/LAB BUILDING DETAILS | | | 60 BAF FACILITY 70 EXISTING CHLORINE CONTACT TANK | DATE: DECEMBER 2015 |
| | 80 A-503 OPERATIONS/LAB BUILDING MILLWORK | STRUCTURE NUMBER — STRUCTURE NUMBER — DISCIPLINE | | 80 OPERATIONS/LAB BUILDING | SCALE: AS NOTED |
| | | SHEET NUMBER | | 85 ELECTRICAL BUILDING | 00 G-002 |
| | | 00 G-001 | | 99 STANDARD DETAILS | J 00 G-002 |
| | | | | | 1 |



- 2. HORIZONTAL LOCATIONS SHOWN ARE REFERENCED TO THE NH STATE PLANE COORDINATE SYSTEM, NAD83.
- 3. VERTICAL DATUM IS NAVD 88 AND IS BASED ON NATIONAL GEODETIC SURVEY FIRST ORDER CLASS I BENCHMARKS "V31 USGS" (PID:OCO289) HAVING A PUBLISHED ELEVATION OF 29.19' AND "W31" (PID:OCO413) HAVING A PUBLISHED ELEVATION OF 20.54'. REFER ALSO TO VERTICAL DATUM CONVERSION NOTE BELOW.
- 4. TOPOGRAPHIC INFORMATION SHOWN IS THE RESULT OF A SURVEY MADE IN JULY 2013 BY DOUCET SURVEY, INC., 102 KENT PLACE, NEWMARKET, NH 03857. WETLAND BOUNDARIES AND HIGHEST OBSERVABLE TIDE LINE (HOTL) WERE DELINEATED BY NORMANDEAU ASSOCIATES, INC. ON JULY 3, 2013. EXISTING TREE SURVEY WAS MADE ON NOVEMBER 18, 2013 BY DOUCET SURVEY, INC.
- 5. THE LOCATION OF ANY UNDERGROUND UTILITY INFORMATION SHOWN ON THIS PLAN IS BASED ON RECORD DRAWINGS AND IS APPROXIMATE. THE OWNER DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF UNDERGROUND UTILITIES SHOWN. PRIOR TO ANY EXCAVATION ON SITE THE CONTRACTOR SHALL CONTACT DIG SAFE AT 1-888-344-7233.
- 6. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL EXISTING CONDITIONS AT THE SITE.
- 7. THE CONTRACTOR SHALL ERECT EROSION CONTROL CHECKS PRIOR TO COMMENCING ANY CLEARING, EXCAVATION OR STORAGE OF BACKFILL MATERIAL ON-SITE. REFER TO SPECIFICATION SECTION 01568 AND DETAILS.
- 8. THE ENGINEER MAY DIRECT THE CONTRACTOR TO VARY THE PROPOSED WORK DURING CONSTRUCTION TO MEET EXISTING CONDITIONS.
- 9. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES AND SHALL PROVIDE ALL NECESSARY CONTINUOUS BARRIERS OF SUFFICIENT TYPE, SIZE AND STRENGTH TO PREVENT ACCESS TO ALL OPEN EXCAVATIONS AT THE COMPLETION OF EACH DAYS WORK. REFER TO SPECIFICATION SECTION 01046 FOR ADDITIONAL REQUIREMENTS
- 10. INTERRUPTION TO WATER AND OTHER EXISTING UTILITIES SHALL BE REQUESTED IN WRITING BY THE CONTRACTOR 3 DAYS IN ADVANCE OF THE WORK AND REVIEWED BY THE ENGINEER.
- 11. CONTRACTOR SHALL MAINTAIN FLOW OF SEWAGE IN ACCORDANCE WITH SECTION 01063 AND 02602.
- 12. DISTURBANCE TO SHORELAND AREAS SHALL BE LIMITED AND RESTORED AS INDICATED IN SPECIFICATION 01063.
- 13. EXISTING UTILITIES INTERFERING WITH THE WORK SHALL BE RELOCATED AS DIRECTED BY THE ENGINEER AT NO ADDITIONAL COST TO THE OWNER.
- 14. PIPE SHALL BE AS INDICATED IN THE PIPING SCHEDULE AND SPECIFICATIONS. PROVIDE RESTRAINED MECHANICAL JOINT FITTINGS FOR ALL PRESSURE PIPE BENDS.
- 15. PIPING WHICH IS EXPOSED DURING EXCAVATION, INCLUDING TEE'S, VALVES, AND FITTINGS, AND IS NOT TO BE DEMOLISHED, SHALL BE SUPPORTED, BRACED OR OTHERWISE PROTECTED DURING CONSTRUCTION ACTIVITIES.
- 16. ALL PIPING, EXCEPT FORCE MAINS, SHALL BE CONSTRUCTED WITH A MINIMUM OF 5 FEET OF COVER. FORCE MAINS SHALL BE CONSTRUCTED WITH A MINIMUM OF 5 FEET COVER IN CROSS—COUNTRY AREAS, 6 FEET COVER IN PAVED AREAS.
- 17. ALL PIPES SHALL SLOPE UNIFORMLY BETWEEN ELEVATIONS SHOWN UNLESS OTHERWISE INDICATED ON THE DRAWINGS OR DIRECTED BY THE ENGINEER. NO SAGS OR CRESTS IN PIPING WILL BE PERMITTED.
- 18. WHERE NEW PIPING IS TO BE CONNECTED TO EXISTING PIPING, THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ADAPTERS, FITTINGS, AND ADDITIONAL PIPE WHICH MAY NOT BE SHOWN IN DETAILS (REQUIRED AS A RESULT OF CUTTING THE EXISTING PIPE BACK) IN ORDER TO COMPLETE THE CONNECTION AS REQUIRED.
- 19. ALL WALL AND SLAB PENETRATIONS SHALL BE SEALED WATERTIGHT.
- 20. ALL WALL CASTINGS SHALL HAVE WATER STOPS.
- 21. JOINTS SHALL BE PROVIDED AT THE WALL OF STRUCTURES ON ALL PIPELINES, EXCEPT WHERE SLEEVES ARE INDICATED. THIS SHALL BE ACCOMPLISHED BY CASTING A BELL WALL FITTING, BELL END STUB, OR WALL CASTING INTO THE STRUCTURE.
- 22. ALL LAYOUT DIMENSIONS REFER TO OUTSIDE EDGE OF WALL AT GRADE LINE, UNLESS OTHERWISE INDICATED.
- 23. LOCATION COORDINATES TO PROPOSED STRUCTURES ARE TO EXTERIOR WALLS AND CENTER OF TANKS.
- 24. ALL SIGNAGE, HEADWALLS, GUARD RAILS, GUARD POSTS, FENCES, CURBS, ROADWAYS, SIDEWALKS AND ANY OTHER OBJECTS DISTURBED BY CONTRACTOR ACTIVITIES SHALL BE RETURNED TO PRE-CONSTRUCTION CONDITION OR BETTER AS DIRECTED BY THE ENGINEER AT NO ADDITIONAL COST TO THE OWNER.
- 25. ALL AREAS OF EXCAVATION, BACKFILL, FILL AND GRADING SHALL BE RETURNED TO THE ORIGINAL GRADE UNLESS SHOWN ON THE DRAWINGS.
- 26. ALL UTILITY BOXES, FRAMES, GRATES, ETC. DISTURBED BY CONTRACTOR AND NOT TO BE ABANDONED SHALL BE RESET TO THE PROPER GRADE AT NO ADDITIONAL COST TO THE OWNER.
- 27. UNPAVED AREAS DISTURBED BY THE CONTRACTOR SHALL BE CLEARED AND GRUBBED IF REQUIRED, AND RESTORED WITH LOAM AND SEED.
- 28. FOR BURIED PIPE MATERIALS, SEE PIPING SCHEDULE ON SHEET 00 C-002.
- 29. ALL EXISTING PIPES TO BE ABANDONED SHALL BE PLUGGED AT OPEN ENDS. SEE PIPE PLUGGING DETAIL ON SHEET 99 C-501.
- 30. RECORD DRAWINGS FOR EXISTING FACILITIES CAN BE FOUND IN APPENDIX J OF THE SPECIFICATIONS.

VERTICAL DATUM CONVERSION NOTE:

SURVEY BY DOUCET ASSOCIATES IS BASED ON NAVD 88 DATUM. EXISTING PLANT RECORD DRAWINGS ARE BASED ON NGVD 29 DATUM. TO CONVERT NAVD 88 ELEVATIONS TO NGVD 29, ADD 0.77 FEET. TO CONVERT NGVD ELEVATIONS TO NAVD 88 SUBTRACT 0.77 FEET.

STORMWATER MAINTENANCE SCHEDULE:

- 1. CONTRACTOR SHALL CONDUCT INSPECTION AND MAINTENANCE OF ALL STORMWATER FACILITIES THROUGHOUT THE CONSTRUCTION PERIOD. REFER TO SEDIMENT AND EROSION CONTROL NOTES AND LONG TERM INSPECTION AND MAINTENANCE SCH3EDULE ON SHEET 99 C-507.
- 2. UPON COMPLETION OF CONSTRUCTION, THE OWNER WILL ASSUME RESPONSIBILITY FOR ACTIVITIES LISTED IN THE LONG TERM INSPECTION AND MAINTENANCE SCHEDULE AND APPLICABLE REQUIREMENTS OF USEPA-NPDES MULTI-SECTOR GENERAL PERMIT (MSGP) FOR STORMWATER DISCHARGES WITH INDUSTRIAL ACTIVITY.

GEOTECHNICAL NOTES

1. FOR EARTH EXCAVATION, BACKFILL, FILL AND GRADING SEE SPECIFICATION 02210.

- 2. FOR DEWATERING SEE SPECIFICATION 02140.
- 3. FOR EXCAVATION SUPPORT SYSTEM SEE SPECIFICATION 02160.
- 4. BORING LOCATIONS ARE SHOWN ON THE PLANS AND BORING LOGS ARE BOUND IN THE SPECIFICATIONS.
- 5. BORINGS WERE TAKEN FOR PURPOSES OF DESIGN AND INDICATE SUBSURFACE CONDITIONS AT BORING LOCATION ONLY. SUBSURFACE CONDITIONS MAY VARY FROM THOSE SHOWN IN THE LOG.
- 6. IN ALL AREAS WHERE DEWATERING IS NECESSARY, MEASURES SHALL BE TAKEN TO ENSURE THE PRESERVATION OF WATERCOURSES AND COMPLIANCE WITH ALL REGULATIONS AND LAWS. ALL DEWATERING MUST BE DISCHARGED INTO SEDIMENT TRAPS AS INDICATED IN THE DETAILS AND AS SPECIFIED IN SPECIFICATION SECTION 01568.
- 7. FOR ROCK EXCAVATION AND DISPOSAL, SEE SPECIFICATION SECTION 02211.

ABBREVIATIONS

| ACU | AIR CONDITIONER UNIT | MHW | MEAN HIGH WATER |
|--------------|-----------------------------------|-------|---------------------------------|
| | | | |
| ALP | AIR LOW PRESSURE | MLW | MEAN LOW WATER |
| APPROX. | APPROXIMATE | MJ | MECHANICAL JOINT |
| B&B | BALL AND BURLAP | MSL | MEAN SEA LEVEL |
| BAF | BIOLOGICAL AERATED FILTER | N.C. | NORMALLY CLOSED |
| B.H. | BUILDING HEIGHT | NE | NITRIFIED EFFLUENT |
| BLDG. | BUILDING | PCW | PROTECTED CITY WATER |
| BPF | BELT PRESS FEED | OC | ODOR CONTROL |
| BW | BACKWASH OR BARBED WIRE | OV | OVERFLOW |
| CA | COMPRESSED AIR | PBS | PRINTED BOTH SIDES |
| СВ | CATCH BASIN | PCE | PRIMARY CLARIFIER EFFLUENT |
| CD | CHEMICAL DRAIN | PCI | PRIMARY CLARIFIER INFLUENT |
| CONC. | CONCRETE | PCW | PROTECTED CITY WATER |
| C.I. | CAST IRON | PD | PLANT DRAIN |
| CLF | CHAIN LINK FENCE | POL | POLYMER |
| C.O. OR CO | CLEANOUT | PP | POTASSIUM PERMANGANATE |
| COV | CHEMICAL OVERFLOW | PR | PRESSATE |
| CS | CAUSTIC SODA | PSL | PRIMARY SLUDGE |
| CV | CHEMICAL VENT | PSNH | PUBLIC SERVICE OF NEW HAMPSHIRE |
| CW | CITY WATER OR CROSS WALK | PVC | POLYVINYL CHLORIDE |
| D | DRAIN | PW | PLANT WATER |
| DI | DUCTILE IRON | RCP | REINFORCED CONCRETE PIPE |
| DIA. | DIAMETER | RED. | REDUCER |
| DIM. | DIMENSION | RET. | RETAIN OR RETAINING |
| DNE | DENITRIFIED EFFLUENT | RU | ROLLUP (DOOR) |
| DMH | DRAIN MANHOLE | RWW | RAW WASTE WATER |
| DWGS | DRAWINGS | SAM | SAMPLE |
| DYL OR DYCL | DOUBLE YELLOW CENTER LINE | SAN | SANITARY DRAIN |
| E | ELECTRICAL | SB | SODIUM BISULFITE |
| ECC. | ECCENTRIC | SC | SCUM |
| EL. OR ELEV. | ELEVATION | | |
| EMERG. | | SD | STORM DRAIN |
| | EMERGENCY EDGE OF DAVIEWENT | SH | SODIUM HYPOCHLORITE |
| EOP | EDGE OF PAVEMENT | SL | SLUDGE OR STOP LINE |
| EXIST. | EXISTING | SMH | SEWER MANHOLE |
| FCL | FERRIC CHLORIDE | SPD | SUMP PUMP DISCHARGE |
| FE | FINAL EFFLUENT | SWL | SINGLE WHITE LINE |
| FES | FLARED END SECTION | SYL | SINGLE YELLOW LINE |
| FF OR F.F.E. | FINISHED FLOOR ELEVATION | TBM | TEMPORARY BENCHMARK |
| FM | FORCE MAIN | TDW | THICKENER DILUTION WATER |
| GAL. | GALLON | TP | TEST PIT |
| GP | GUARD POST | TSD | THICKENED DIGESTED SLUDGE |
| GRAN. | GRANITE | TSL | THICKENED SLUDGE |
| GR | GRIT | TS&V | TAPPING SLEEVE AND VALVE |
| GTO | GRAVITY THICKENER OVERFLOW | TRANS | TRANSFORMER |
| GV | GATE VALVE | TYP. | TYPICAL |
| HOTL | HIGHEST OBSERVABLE TIDE LINE | UE | UNDERGROUND ELECTRIC |
| HWS/R | HOT WATER SUPPLY/RETURN | V | VENT |
| INV. | INVERT | VERT. | VERTICAL |
| LF | LINEAR FOOT | VGC | VERTICAL GRANITE CURB |
| L.O.W. | LIMIT OF WORK | WSO | WATER SHUT OFF |
| LPG | LIQUEFIED PETROLEUM GAS (PROPANE) | WQI | WATER QUALITY INLET |
| MC | MICRO-C | WV | WATER VALVE |
| MECH. | MECHANICAL | ΥH | YARD HYDRANT |
| | | | |

LEGEND

| | LEGEND | | |
|------------------------|---------------------------------|---|--|
| <u>EXIS</u> | <u>TING</u> | PROPOSED | |
| | UTILITY POLE & GUY WIRE | LIMIT OF WORK | |
| ⋛ □ | UTILITY POLE W/ LIGHT | | |
| | SIGN | STRUCTURE | |
| Θ | YARD HYDRANT | PIPE PLUG OR CAP | |
| Ø | UNIDENTIFIED PIPE | * | `````````````````````````````````````` |
| | WOODEN POST | DEMOLITION | |
| WM | FIRE HYDRANT | | |
| WM X WV X | WATER METER WATER GATE VALVE | ABANDON IN PLACE | |
| ₩ | VENT PIPE | // | ////// |
| <i>4</i> ≥0 | WATER SHUTOFF VALVE | TREE REMOVAL | \searrow |
| co | CLEANOUT | | |
| | TRAFFIA DIRECTION APPOW | TEE | |
| | TRAFFIC DIRECTION ARROW | | |
| | ELECTRIC BOX | REDUCER | |
| 0 | CATCH BASIN (ROUND) | BEND | |
| | CATCH BASIN DRAIN MANHOLE | | |
| © © | ELECTRIC MANHOLE | GATE VALVE | H |
| © | CHEMICAL MANHOLE | PIPE $- \le 6$ " DIAM. | |
| (W) | WATER MANHOLE | THE _ O DIAM. | |
| <u>S</u> | SEWER MANHOLE | PIPE - > 6" DIAM. | |
| \bigcirc | UNIDENTIFIED MANHOLE | | |
| 7/17 | JURISDICTIONAL WETLAND SYMBOL | DIRECTION OF FLOW | → |
| ~• | FLAG POLE | MANHOLE | \bigcirc |
| | CONIFEROUS TREE DECIDUOUS TREE | CL FANIOLIT | C.O. •/ |
| | SHRUB | CLEANOUT | 5.0.9 |
| | CONCRETE | GUARD POST OR BOLLARD | • |
| | BOULDER | | |
| | ROW OF BOULDERS | CHAIN LINK FENCE | |
| | LANDSCAPED AREA | TEMPORARY FENCE | |
| | GRAVEL | | |
| | LEDGE OUTCROP BOLLARD | SILT FENCE AND STRAW BALE | |
| \Rightarrow | DRAINAGE FLOW DIRECTION ARROW | EROSION CONTROL | |
| XX | CHAINLINK FENCE | | 0.7 |
| OHW | OVERHEAD WIRES | CONTOUR | 23 |
| D | DRAIN LINE | SPOT ELEVATION | × 23.50 |
| | TREE LINE | TOP OF SLOPE | |
| | SHRUB LINE GUARDRAIL | CRUSHED STONE | |
| — 24 — — | | MOWING STRIP | |
| | EDGE OF JURISDICTIONAL WETLAND | CONCRETE | 4 4 |
| P48 | ROCK PROBE | CONCRETE | 4 |
| ⊕ B13−1 | BORING | CURB === | |
| - MW -1 | MONITORING WELL | | |
| TP#2 | TEST PIT | EXISTING PAVEMENT AREA TO BE REPAVED (RECLAIMED BASE) | |
| | | NEW PAVEMENT AREA (RECLAIMED BASE) | |
| | | POINT OF CONNECTION, NEW WORK TO EXIST. | \$ |
| | | DISCIPLINE INTERFACE | |
| | | | |

APPROVALS (SEE SPECIFICATIONS):

- · CITY OF PORTSMOUTH SITE PLAN APPROVAL, DATED (TBD)
- NHDES WETLANDS PERMITS 2015-01866 AND 2015-01878, DATED OCT. 9, 2015.
- · NHDES ALTERATION OF TERRAIN PERMIT: AoT—(TBD), DATED (TBD)

AECOM TECHN 250 APOLLO I CHELMSFORD, PHONE (978) O

EVIATION (ABBRE

GEND, AND GI

PROJECT NO: **60301525** CAD DWG FILE: 00 C-001 DESIGNED BY: T. WASSELL DRAWN BY: N. YEE

DEPT CHECK: C. BENZIGER PROJ CHECK: E. MESERVE DECEMBER 2015 SCALE: as noted

00 C-001


MANHOLE

| | YAF | RD PIPING SCHEDULE | - - |
|---------|-------------------------------|---|--|
| LEGEND | SYSTEM | MATERIAL | REMARKS |
| BW | BACKWASH | DUCTILE IRON | |
| CS | CAUSTIC SODA | SCHED. 80 PVC | |
| CW | POTABLE WATER | 4" AND LARGER: DUCTILE IRON 3" AND SMALLER: PVC | |
| D | DRAIN | SAME AS SYSTEM | |
| DNE | DENITRIFIED EFFLUENT | DUCTILE IRON PVC C905 (BURIED) | USE LONG RADIUS BENDS |
| FC | FERRIC CHLORIDE | SCHED. 80 PVC | |
| FP | FIRE PROTECTION | 3" AND SMALLER: 4" AND LARGER: DUCTILE IRON | |
| GTO | GRAVITY THICKENER OVERFLOW | DUCTILE IRON PVC C905 (BURIED) | |
| HWS/HWR | HOT WATER SUPPLY/RETURN | DUCTILE IRON | |
| PCE | PRIMARY CLARIFIER EFFLUENT | DUCTILE IRON PVC C905 (BURIED) | |
| PD | PLANT DRAIN | DUCTILE IRON | |
| POL | POLYMER | SCHED. 80 PVC | |
| PR | PRESSATE | DUCTILE IRON | |
| PROPANE | PROPANE | DUCTILE IRON | |
| PSL | PRIMARY SLUDGE | DUCTILE IRON | USE LONG RADIUS BENDS SEE NOTE 11 |
| PW | PLANT WATER | 4" AND LARGER: DUCTILE IRON 3" AND SMALLER: SCHED. 80 PVC | SEE NOTES |
| OC | ODOR CONTROL | FRP (ABOVE GRADE)/ DR 32.5 IPS HDPE (BELOW GRADE) | SEE NOTES |
| RWW | RAW WASTEWATER | DUCTILE IRON PVC C905 (BURIED) | |
| SAM | SAMPLE | TYPE 316L STAINLESS STEEL | |
| SAN | SANITARY | DUCTILE IRON | |
| SAN FM | SANITARY FORCE MAIN | DUCTILE IRON | |
| SB | SODIUM BISULFITE | SCHED. 80 PVC | |
| SC | SCUM | DUCTILE IRON | USE LONG RADIUS BENDS SEE NOTE 11 |
| SD | STORM DRAIN | CORRUGATED POLYETHYLENE DUCTILE IRON RCP SCHED. 40 PVC | REFER TO DRAWINGS FOR PIPE MATERIAL |
| SEC | SECONDARY INFLUENT | DUCTILE IRON | |
| SH | SODIUM HYPOCHLORITE | SCHED. 80 PVC | TITANIUM FASTENERS |
| TDW | THICKENER DILUTION WATER | DUCTILE IRON | |
| TSL | THICKENED SLUDGE | DUCTILE IRON | SEE NOTE 11 |
| V | VENT | SAME AS SYSTEM | |

| YARD | PIPING | NOTES |
|------|--------|-------|

- 1. REFER TO MECHANICAL PROCESS PIPING SCHEDULE AND SPECIFICATIONS FOR INFORMATION RELATED TO SCHEDULE/CLASS OF PIPE LINING/COATING, JOINT TYPE, INSULATION AND TEST REQUIREMENTS.
- 2. TEST VENTS AND DRAINS TO SAME PRESSURE AS SYSTEM.
- 3. FOR OPEN VENTS, FILL VENT WITH WATER AND TEST FOR LEAKS.
- 4. USE TYPE 316L S.S. PIPE FOR DRAINS FROM DUCTILE IRON SERVICE FOR DRAINS 3" AND SMALLER.
- 5. PROVIDE FLANGES AT EQUIPMENT, VALVES AND AS INDICATED ON THE DRAWINGS.
- 6. ALL PIPING THAT IS NOT BURIED SHALL BE CONSIDERED EXPOSED.
- 7. HEAT TRACE AND INSULATE ALL EXTERIOR EXPOSED PIPING CONTAINING LIQUIDS, TO 4 FEET BELOW GRADE AS INDICATED AND SPECIFIED IN SECTION 15370.
- 8. FOR BURIED DUCTILE IRON PROVIDE MECHANICAL JOINT OR PUSH—ON JOINTS AS SPECIFIED IN SECTION 02615. ALL JOINTS IN PRESSURE PIPES TO BE RESTRAINED.
- 9. PROVIDE 3/4" 316 STAINLESS STEEL MESH ON ALL ODOR CONTROL PICKUPS. SANDWICH MESH BETWEEN TWO FLANGES W/316 STAINLESS STEEL FASTENERS.
- 10. PROVIDE 316 STAINLESS STEEL INSECT SCREEN ON ALL GOOSENECK VENTS.
- 11. CLEANOUTS SHALL BE INSTALLED ON ALL 45° AND 90° BENDS FOR GRIT, SCUM AND SLUDGE LINES AND WHERE INDICATED ON THE DRAWINGS.
- 12. MINIMUM COVER OVER CW (CITY WATER) PIPING IS 5 FEET.

| | | | INCITOLIGEORGE | | DESCRIPTION | SINUISINA |
|--|------------------------|--|----------------|-----|----------------------|-----------|
| | N | | | と つ | CHECKED | |
| | | 5 | 」 ⊥ | Ĺ | DATE MADE BY CHECKED | |
| | | | |) | DATE | |
| | | | | | MARK | |
| | CHNICAL SERVICES, INC. | -0 DKIVE RD, MA 01824 78) 905—2100 | com | | | |




SCHEDULE **PIPING**


PROJECT NO: **60301525** CAD DWG FILE: 00 C-002 DESIGNED BY: T. WASSELL DRAWN BY: Z. BANKOVIC


DEPT CHECK: C. BENZIGER PROJ CHECK: E. MESERVE


DECEMBER 2015 SCALE: AS NOTED


00 C-002























































NME: P:\60301525 - PORTSMOUTH WWTF UPGRADE\SHEETS\BP-2\C\
































LATITUDE: 043° 04' 25" N LONGITUDE: 070° 44' 31" W

APPLICANT: CITY OF PORTSMOUTH DEPARTMENT OF PUBLIC WORKS 680 PEVERLY HILL ROAD PORTSMOUTH, NEW HAMPSHIRE

DESCRIPTION

The project consists of improvements and upgrades to the Portsmouth Peirce Island Wastewater Treatment Facility.

DISTURBED AREA

The total area to be disturbed for the development improvements is approximately 352.162 SF (8.085 acres).

PROJECT PHASING

The proposed project will be completed in one phase

NAME OF RECEIVING WATER

The site drains directly to the Piscatagua River (tidal).

NPDES CONSTRUCTION GENERAL PERMIT

Contractor shall prepare a Stormwater Pollution Prevention Plan (SWPPP) is accordance with federal storm water permit requirements. The SWPPP must be prepared in a format acceptable to the Owner and three (3) copies provided to the City at least fourteen (14) days prior to initiating construction. Contractor is responsible for all cost associated with preparation and implementation of SWPPP including any temporary erosion control measures (whether indicated or not on these drawings) as required for the contractor's sequence of

The Contractor and Owner shall each file a Notice of Intent (NOI) with the U.S.E.P.A. under the NPDES Construction General Permit. (U.S.E.P.A., 1200 Pennsylvania Avenue NW, Washington, DC 20460) All work shall be in accordance with NPDES General Permit: NHR120000, including NOI requirements, effluent limitations, standards and management for construction. The Contractor shall be responsible for obtaining a USEPA Construction Dewatering Permit, if required.

SEQUENCE OF MAJOR ACTIVITIES

- Prepare SWPPP and file NPDES Notice of Intent, prior to any construction activities The Contractor and Owner shall each file a Notice of Intent (N.O.I.) to U.S.E.P.A. Install temporary erosion control measures including silt fences, stabilized construction
- control measures shall be maintained in good working condition for the duration of Upon completion of Items 1 through 2, clear and grub wooded areas (some stumps

entrance and inlet sediment filters as noted on the plan. All temporary erosion

- may require grinding). Dispose of stumps in an approved offsite location.
- Strip and stockpile loam. Stockpiles shall be temporarily stabilized with straw bales, mulch and surrounded by a straw bale or silt fence barrier until material is removed and final grading is complete.
- Reclaim/remove existing paved surfaces.
- Perform all required demolition activities.
- Construct ditches, swales and wet pond early in construction sequence; stabilize them
- Ditches and swales shall have sides and bottom reinforced with excelsior matting, Permanent turf reinforcement shall be installed at swale sloped greater than 5%.
- Rough grade site including placement of borrow materials.
- Construct drainage structures, parking area & road base materials. All roadways and parking lots shall be stabilized within 72 hours of achieving finished grade
- Install base course paving, pavers & curbing.
- Install top course paving. Loam (6" min) and seed all disturbed areas not paved or otherwise stabilized within
- 72 hours of achieving finished grade. When all construction activity is complete and site is stabilized, remove all straw bales, storm check dams, silt fences and sediment that has been trapped by these
- 23. File a Notice of Termination (N.O.T.) with U.S.E.P.A.

TEMPORARY EROSION & SEDIMENT CONTROL AND STABILIZATION PRACTICES

All work shall be in accordance with state and local permits. Work shall conform to the practices described in the "New Hampshire Stormwater Manual, Volumes 1 - 3", issued December 2008, as amended. As indicated in the sequence of Major Activities, the silt fences shall be installed prior to commencing any clearing or grading of the site. Structural controls shall be installed concurrently with the applicable activity. Once construction activity ceases permanently in an area, silt fences and any earth/dikes will be removed once permanent measures are established.

During construction, runoff will be diverted around the site with stabilized channels where possible. Sheet runoff from the site shall be filtered through straw bale barriers, stone check dams, and silt fences. All storm drain inlets shall be provided with straw bale filters or stone check dams. Stone rip rap shall be provided at the outlets of drain pipes and culverts where shown on the drawings.

Stabilize all ditches, swales, stormwater ponds, level spreaders and their contributing areas prior to directing flow to them.

Temporary and permanent vegetation and mulching is an integral component of the erosion and sedimentation control plan. All areas shall be inspected and maintained until vegetative cover is established. These control measures are essential to erosion prevention and also reduce costly rework of araded and shaped areas.

remporary vegetation shall be maintained in these areas until permanent seeding is applied. Additionally, erosion and sediment control measures shall be maintained until permanent vegetation is

INSTALLATION, MAINTENANCE AND INSPECTION PROCEDURES FOR TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES

A. GENERAL

- These are general inspection and maintenance practices that shall be used to implement the
- The smallest practical portion of the site shall be denuded at one time, but in no case shall it
- All control measures shall be inspected by the Contractor's Qualified inspector at least once
- each week and following any storm event of 0.25 inches or greater. All measures shall be maintained in good working order; if a repair is necessary, it will be initiated within 24 hours.

- INSTALLATION, MAINTENANCE AND INSPECTION PROCEDURES FOR TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES (CON'T)
- Built-up sediment shall be removed from silt fence or other barriers when it has reached
- one—third the height of the fence or bale, or when "bulges" occur. All diversion dikes shall be inspected and any breaches promptly repaired
- Temporary seeding and planting shall be inspected for bare spots, washouts, and unhealthy
- The owner's authorized engineer shall inspect the site on a periodic basis to review compliance
- All roadways and parking lots shall be stabilized within 72 hours of achieving finished grade. All cut and fill slopes shall be seeded/loamed within 72 hours of achieving finished grade.
- An area shall be considered stable if one of the following has occurred: a. Base coarse gravels have been installed in areas to be paved;
- b. A minimum of 85% vegetated growth as been established; c. A minimum of 3 inches of non-erosive material such as stone of riprap has been
- d. Erosion control blankets have been properly installed. 11. In areas not under active construction, the length of time of exposed soil disturbed during construction is limited to 14 calendar days. For specific stabilization requirements, refer to Section 2.2 stabilization requirements of the 2012 Construction General Permit (CGP) contained

in the Project Manual.

Mulch shall be used on highly erodible soils, on critically eroding areas, on areas where conservation of moisture will facilitate plant establishment, and where shown on the plans.

- Timing In order for mulch to be effective, it must be in place prior to major storm events. There are two (2) types of standards which shall be used to assure this:
 - a. Apply mulch prior to any storm event. This is applicable when working within 100 feet of wetlands. It will be necessary to closely monitor weather predictions, usually by contacting the National Weather Service in Concord, to have adequate warning of significant storms.
 - b. Required Mulching within a specified time period. The time period can range from 21 to 28 days of inactivity on a area, the length of time varying with site conditions. Professional judgment shall be used to evaluate the interaction of site conditions (soil erodibility, season of year, extent of disturbance, proximity to sensitive resources, etc.) and the potential impact of erosion on adjacent areas to choose an appropriate time restriction.
- Guidelines for Winter Mulch Application —

| <u>Type</u> Straw | Rate per 1.000 s.f. 70 to 90 lbs. | <u>Use and Comments</u> Must be dry and free from mold. May be used with plantings. |
|---|---------------------------------------|---|
| Wood Chips or Bark Mulch | 460 to 920 lbs. | Used mostly with trees and shrub plantings. |
| Jute and Fibrous Matting (Erosion Blanket | As per manufacturer Specifications | Used in slope areas, water courses and other Control areas. |
| Crushed Stone 1/4" to 1-1/2" dia. | Spread more than 1/2" thick | Effective in controlling wind and water erosion. |
| Erosion Control Mix | 2" thick (min) | * The organic matter content is between 80 and 100%, dry weight basis. * Particle size by weight is 100% passing a 6"screen and a minimum of 70 %, maximum of 85%, passing a 0.75" screen. * The organic portion needs to be fibrous and elongated. * Large portions of silts, clays or fine sands are not acceptable in the mix. * Soluble salts content is less than 4.0 mmhos/cm. * The pH should fall between 5.0 and 8.0. |

- Maintenance All mulches must be inspected periodically, in particular after rainstorms, to check for rill erosion. If less than 90% of the soil surface is covered by mulch, additional
- C. TEMPORARY GRASS COVER

Seedbed Preparation -

Apply fertilizer at the rate of 600 pounds per acre of 10-10-10. Apply limestone (equivalent to 50 percent calcium plus magnesium oxide) at a rate of three (3) tons per acre.

- a. Utilize annual rye grass at a rate of 40 lbs/acre.
- b. Where the soil has been compacted by construction operations, loosen soil to a depth of two (2) inches before applying fertilizer, lime and seed.
- c. Apply seed uniformly by hand, cyclone seeder, or hydroseeder (slurry including seed and fertilizer). Hydroseedings, which include mulch, may be left on soil surface. Seeding rates must be increased 10% when hydroseeding.
- 3. Maintenance -

Temporary seedings shall be periodically inspected. At a minimum, 95% of the soil surface should be covered by vegetation. If any evidence of erosion or sedimentation is apparent, repairs shall be made and other temporary measures used in the interim (mulch, filter barriers, check dams, etc.).

D. FILTERS

a. Synthetic filter fabric shall be a pervious sheet of propylene, nylon, polyester or ethylene varn and shall be certified by the manufacturer or supplier as conforming to the following requirements:

| Physical Property Filtering Efficiency | <u>Test</u> VTM-51 | Requirements 75% minimum |
|---|-----------------------|--|
| Tensile Strength at 20% Maximum Elongation* | VTM-52 | Extra Strength 50 lb/lin in (min) Standard Strength 30 lb/lin in (min) |
| Flow Rate | VTM-51 | 0.3 gal/sf/min (min) |

* Requirements reduced by 50 percent after six (6) months of installation.

Synthetic filter fabric shall contain ultraviolet ray inhibitors and stabilizer to provide a minimum of six (6) months of expected usable construction life at a temperature range of 0 degrees F to 120° F.

- b. Posts shall be spaced a maximum of ten (10) feet apart at the barrier location or as recommended by the manufacturer and driven securely into the ground (minimum of 16
- c. A trench shall be excavated approximately six (6) inches wide and eight (8) inches deep along the line of posts and upslope from the barrier.
- d. When standard strength filter fabric is used, a wire mesh support fence shall be fastened securely to the upslope side of the posts using heavy duty wire staples at least one (1) inch long, tie wires or hog rings. The wire shall extend no more than 36 inches above the original ground surfaces.

e. The "standard strength" filter fabric shall be stapled or wired to the fence, and eight (8) inches of the fabric shall be extended into the trench. The fabric shall not extend more than 36 inches above the original ground surface. Filter fabric shall not be stapled to existing trees.

INSTALLATION, MAINTENANCE AND INSPECTION PROCEDURES FOR TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES (CON'T)

- f. When extra strength filter fabric and closer post spacing are used, the wire mesh support fence may be eliminated. In such a case, the filter fabric is stapled or wired directly to the posts with all other provisions of item (q) applying.
- g. The trench shall be backfilled and the soil compacted over the filter fabric.
- h. Silt fences shall be removed when they have served their useful purpose but not before the upslope areas has been permanently stabilized.
- Sequence of Installation -

Sediment barriers shall be installed prior to any soil disturbance of the contributing upslope drainage area.

- Maintenance
 - a. Silt fence barriers shall be inspected immediately after each rainfall and at least daily during prolonged rainfall. They shall be repaired if there are any signs of erosion or sedimentation below them. Any required repairs shall be made immediately. If there are signs of undercutting at the center or the edges, or impounding of large volumes of water, the sediment barriers shall be replaced with a temporary stone check dam.
 - b. Should the fabric on a silt fence or filter barrier decompose or become ineffective prior to the end of the expected usable life and the barrier still is necessary, the fabric shall be replaced promptly.
 - c. Sediment deposits must be removed when deposits reach approximately one—third (1/3) the height of the barrier.
 - d. Any sediment deposits remaining in place after the silt fence or other barrier is no longer required shall be removed. The area shall be prepared and seeded.
 - e. Additional stone may have to be added to the construction entrance, rock barrier and riprap lined swales, etc., periodically to maintain proper function of the erosion control

Filtrexx Siltsoxx or approved equal - install per manufacturer specifications.

- PERMANENT SEEDING -
- Bedding stones larger than $1\frac{1}{2}$, trash, roots, and other debris that will interfere with seeding and future maintenance of the area should be removed. Where feasible, the soil should be tilled to a depth of 5" to prepare a seedbed and mix fertilizer into the soil.
- Fertilizer lime and fertilizer should be applied evenly over the area prior to or at the time of seeding and incorporated into the soil. Kinds and amounts of lime and fertilizer should be based on an evaluation of soil tests. When a soil test is not available, the following minimum amounts should be applied:
 - Agricultural Limestone @ 100 lbs. per 1,000 s.f. 10-20-20 fertilizer @ 12 lbs. per 1,000 s.f.
- 3. Seed Mixture (recommended):
 - SEE LANDSCAPE PLANS
- Sodding sodding is done where it is desirable to rapidly establish cover on a disturbed area. Sodding an area may be substituted for permanent seeding procedures anywhere on site. Bed preparation, fertilizing, and placement of sod shall be performed according to the S.C.S. Handbook. Sodding is recommended for steep sloped areas, areas immediately adjacent to sensitive water courses, easily erodible soils (fine sand/silt), etc.

WINTER CONSTRUCTION NOTES

- All proposed vegetated areas which do not exhibit a minimum of 85% vegetative growth by October 15th, or which are disturbed after October 15th, shall be stabilized by seeding and installing erosion control blankets on slopes greater than 3:1, and elsewhere seeding and placing 3 to 4 tons of mulch per acre, secured with anchored netting. The installation of erosion control blankets or mulch and netting shall not occur over accumulated snow or on frozen ground and shall be completed in advance of that or spring melt events:
- All ditches or swales which do not exhibit a minimum of 85% vegetative growth by October 15th, or which are disturbed after October 15th, shall be stabilized temporarily with stone or erosion control blankets appropriate for the design flow conditions: and
- After November 15th, incomplete road or parking surfaces where work has stopped for the winter season shall be protected with a minimum of 3 inches of crushed gravel per NHDOT

BEST MANAGEMENT PRACTICES FOR BLASTING

All activities related to blasting shall follow Best Management Practices (BMPs) to prevent contamination of groundwater including preparing, reviewing and following an approved blasting plan; proper drilling, explosive handling and loading procedures; observing the entire blasting procedures; evaluating blasting performance; and handling and storage of blasting rock.

- 1) LOADING PRACTICES. The following blasthole loading practices to minimize environmental effects
- a) Drillings logs shall be maintained by the driller and communicated directly to the blaster. The logs shall indicate depths and lengths of voids, cavities, and fault zones or other weak zones encountered as well as groundwater conditions.
- b) Explosive products shall be managed on-site so that they are either used in the borehole, returned to the delivery vehicle, or placed in secure containers for off-site disposal. c) Spillage around the borehole shall either be placed in the borehole or cleaned up and
- returned to an appropriate vehicle for handling or placement in secured containers for off-site disposal. d) Loaded explosives shall be detonated as soon as possible and shall not be left in the blastholes overnight, unless weather or other safety concerns reasonably dictate that
- detonation should be postponed. e) Loadina equipment shall be cleaned in an area where wastewater can be properly contained and handled in a manner that prevents release of contaminants to the environment.
- f) Explosives shall be loaded to maintain good continuity in the column load to promote complete detonation. Industry accepted loading practices for priming, stemming, decking and column rise need to be attended to.
- 2) EXPLOSIVE SELECTION. The following BMPs shall be followed to reduce the potential for groundwater contamination when explosives are used:
- a) Explosive products shall be selected that are appropriate for site conditions and safe blast b) Explosive products shall be selected that have the appropriate water resistance for the site
- conditions present to minimize the potential for hazardous effect of the product upon the groundwater. 3) PREVENTION OF MISFIRES. Appropriate practices shall be developed and implemented to prevent
- 4) MUCK PILE MANAGEMENT. Muck piles (the blasted pieces of rock) and rock piles shall be manages in a manner to reduce the potential for contamination by implementing the following
 - a) Remove the muck piles from the blast area as soon as reasonably possible.

b) Manage the interaction of blasted rock piles and stormwater to prevent contamination of water supply wells or surface water

BEST MANAGEMENT PRACTICES FOR BLASTING (CONT.)

- 5) SPILL PREVENTION MEASURES AND SPILL MITIGATION. Spill prevention and spill mitigation measures shall be implemented to prevent the release of fuel and other related substances to the environment. The measures shall be included at a minimum:
 - a) The storage requirements shall include: Storage of regulated substances on an impervious surface.
 - ii. Secure storage areas against unauthorized entry.
 - iii. Label regulated containers clearly and visibly.
 - iv. Inspect stage areas weekly.
 - v. Cover regulated containers in outside storage areas. vi. Whenever possible, keep regulated containers that are stored outside more than 50 feet
 - vii. Secondary containment is required for containers containing regulated substances stored outside, except for on premise use fuel tanks or aboveground or underground storage tanks otherwise regulated.

from surface water and storm drains, 75 feet from private wells, and 400 feet from

- b) The fuel handling requirements shall include:
- Except when in use, keep containers containing regulated substances closed and sealed. ii. Place drip pans under spigots, valves, and pumps. iii. Have spill control and containment equipment readily available in all work areas.
- iv. Use funnel and drip pans when transferring regulated substances.
- v. Perform transfers of regulated substances over an impervious surface. c) The training of on-site employees and on-site posting of release response information describing what to do in the event of regulated substances.
- d) Fuelina and maintenance of excavation, earthmoving and other construction related equipment will comply with regulation of New Hampshire Department of Environmental Services (see WD-DWGB-22-6 Best management Practices for Fueling and Maintenance of
- Excavation and Earthmoving Equipment. http://des.nh.gov/organization/ommissioner/pip/factsheets/dwgb/documents/dwgb-22-6.pdf

| | nnce Schedule Spring Fall or After | | |
|---|------------------------------------|----------|----------------|
| | Spring | Yearly | Major Storm |
| Vegetated Areas | | | |
| Inspect all slopes and embankments | X | | X |
| Replant bare areas or areas with sparse growth | X | | X |
| Armor areas with rill erosion with an appropriate lining or divert the erosive flows to on-site areas able to withstand concentrated flows. | X | | х |
| Stormwater Channels | | | |
| Inspect ditches, swales and other open stormwater channels | x | X | X |
| Remove any obstructions and accumulated sediments or debris | X | X | |
| Control vegetated growth and woody vegetation | | X | |
| Repair any erosion of the ditch lining | | X | |
| Mow vegetated ditches | | X | |
| Remove woody vegetation growing through riprap | | X | |
| Repair any slumping side slopes | | X | |
| Replace riprap where underlying filter fabric or underdrain gravel is exposed or where stones have been dislodged | | X | |
| Culverts | | | |
| Remove accumulated sediments and debris at inlet, outlet and within the conduit | X | X | X |
| Repair any erosion damage at the culvert's inlet and outlet | X | X | X |
| Remove woody vegetation growing through riprap | | X | |
| Catch Basins and Water Quality Inlet | | | |
| Remove accumulated floatable, sediments and debris | | X | |
| Inspect internal pipes and screens | | X | |
| Roadways and Parking Surfaces | | | |
| Remove accumulated winter sand along roadways | X | | |
| Sweep pavement to remove sediment | X | | |
| Grade road shoulders and remove excess sand either manually or by a front-end loader | X | | |
| Grade gravel roads and gravel shoulders | v | | + |
| Clean out sediment contained in water bars or open-top | X | | |
| culverts | ^ | | |
| Ensure that stormwater is not impeded by accumulations of material or false ditches in the | X | | |
| roadway shoulder | | | |
| Rain Garden | | T | |
| "Harvesting" – Removal of dead vegetation and Any accumulated sediment (normally at the drain entrance to the garden) to allow for new growth | X | | |
| The same of the barden, to allow for the blown | <u> </u> | <u> </u> | |

ALL FACILITIES SHOULD BE INSPECTED ON AN ANNUAL BASIS AT A MINIMUM. IN ADDITION, ALL FACILITIES SHOULD BE INSPECTED AFTER A SIGNIFICANT PRECIPITATION EVENT TO ENSURE THE FACILITY IS DRAINING APPROPRIATELY AND TO IDENTIFY ANY DAMAGE THAT OCCURRED AS A RESULT OF THE INCREASED RUNOFF. FOR THE PURPOSE OF THIS STORMWATER MANAGEMENT PROGRAM, A SIGNIFICANT RAINFALL EVENT IS CONSIDERED AN EVENT OF THREE (3) INCHES IN A 24-HOUR PERIOD OR 0.5 INCHES IN A ONE-HOUR PERIOD. IT IS ANTICIPATED THAT A SHORT, INTENSE EVENT IS LIKELY TO HAVE A HIGHER POTENTIAL OF EROSION FOR THIS SITE THAN A LONGER, HIGH VOLUME EVENT.

NO ≥ Ť STR 2 ZO C O

CAL MA 905 AECOM TECHN
250 APOLLO [
CHELMSFORD,
PHONE (978)

≡COM ALTUS



S

PROJECT NO: **60301525** CAD DWG FILE: 99 C-507 DESIGNED BY: R. BEAL DRAWN BY: R. BEAL

99 C-507


SCALE: AS NOTED


DEPT CHECK: J. CLIFFORD PROJ CHECK: E. MESERVE DECEMBER 2015

NOTES:

- 1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.
- 2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH WITH APPROXIMATELY 12" OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE BLANKET.
- 3. ROLL THE BLANKETS (A) DOWN OR (B) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING OPTIONAL DOT SYSTEMTM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
- 4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2"-5" OVERLAP DEPENDING ON BLANKET TYPE. TO ENSURE PROPER SEAM ALIGNMENT, PLACE THE EDGE OF THE OVERLAPPING BLANKET (BLANKET BEING INSTALLED ON TOP) EVEN WITH THE COLORED SEAM STITCH ON THE PREVIOUSLY
- 5. CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART ACROSS ENTIRE BLANKET WIDTH. NOTE: IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.

EROSION CONTROL BLANKET SLOPE INSTALLATION







CONSTRUCTION SPECIFICATIONS

- 1. <u>STONE SIZE</u> NHDOT STANDARD STONE SIZE #4 SECTION 703 OF NHDOT STANDARD.
- <u>LENGTH</u> DETAILED ON PLANS (50 FOOT MINIMUM).
- THICKNESS SIX (6) INCHES (MINIMUM).
- WIDTH FULL DRIVE WIDTH UNLESS OTHERWISE SPECIFIED.
- FILTER FABRIC MIRAFI 600X OR EQUAL APPROVED BY ENGINEER.
- SURFACE WATER CONTROL ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE.
- MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS WILL REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE OR ADDITIONAL LENGTH AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
- WHEELS SHALL BE CLEANED TO REMOVE MUD PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- STABILIZED CONSTRUCTION EXITS SHALL BE INSTALLED AT ALL ENTRANCES TO PUBLIC RIGHTS-OF-WAY, AT LOCATIONS SHOWN ON THE PLANS, AND/OR WHERE AS DIRECTED BY THE ENGINEER.

STABILIZED CONSTRUCTION EXIT NOT TO SCALE




NOTE: FOR LOCATION OF SWALE, SEE SHEET 00 C-112.



NOTES:

- 1. SILTSOXX MAY BY USED IN PLACE OF SILT FENCE OR OTHER SEDIMENT BARRIERS FOR AREAS OF REVETMENT CONSTRUCTION.
- 2. ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
- 3. SILTSOXX COMPOST/SOIL/ROCK/SEED FILL MATERIAL SHALL BE ADJUSTED AS NECESSARY TO MEET THE REQUIREMENTS OF THE SPECIFIC APPLICATION.
- 4. ALL SEDIMENT TRAPPED BY SILTSOXX SHALL BE DISPOSED OF PROPERLY.

FILTREXX STAKING DETAIL



INSTALLATION AND MAINTENANCE:

INSTALLATION: REMOVE THE GRATE FROM CATCH BASIN. IF USING OPTIONAL OIL ABSORBENTS; PLACE ABSORBENT PILLOW IN UNIT. STAND GRATE ON END. MOVE THE TOP LIFTING STRAPS OUT OF THE WAY AND PLACE THE GRATE INTO CATCH BASIN INSERT SO THE GRATE IS BELOW THE TOP STRAPS AND ABOVE THE LOWER STRAPS. HOLDING THE LIFTING DEVICES, INSERT THE GRATE INTO THE INLET.


MAINTENANCE: REMOVE ALL ACCUMULATED SEDIMENT AND DEBRIS FROM VICINITY OF THE UNIT AFTER EACH STORM EVENT. AFTER EACH STORM EVENT AND AT REGULAR INTERVALS, LOOK INTO THE CATCH BASIN INSERT. IF THE CONTAINMENT AREA IS MORE THAN 1/3 FULL OF SEDIMENT, THE UNIT MUST BE EMPTIED. TO EMPTY THE UNIT, LIFT THE UNIT OUT OF THE INLET USING THE LIFTING STRAPS AND REMOVE THE GRATE. IF USING OPTIONAL ABSORBENTS; REPLACE ABSORBENT WHEN NEAR SATURATION.


UNACCEPTABLE INLET PROTECTION METHOD:

A SIMPLE SHEET OF GEOTEXTILE UNDER THE GRATE IS NOT ACCEPTABLE.

STORM DRAIN INLET PROTECTION

NOT TO SCALE






TO BE USED IN LOCATION WHERE THE EXISTING GROUND SLOPES IN TOWARD THE TOE OF THE EMBANKMENT.

STRAW BALE EROSION CONTROL

2-1.60.4 (REV. 09-29-95)



SILT FENCE/STRAWBALE DETAIL

NOT TO SCALE

99 C-508

≡COM

STRUC


ZO

O

S

PROJECT NO: **60301525** CAD DWG FILE: 99 C-508 DESIGNED BY: R. BEAL DRAWN BY: R. BEAL DEPT CHECK: J. CLIFFORD PROJ CHECK: E. MESERVE

DECEMBER 2015 SCALE: as noted



GRADE INSTALL TEMPORARY SEEDING OR STONE CHANNEL

> SWALE SHALL BE FREE OF IRREGULARITIES WHICH MAY CAUSE PONDING. COMPACT FILLS AS NECESSARY TO STABILIZE MATERIAL.

MAINTENANCE

PROTECTION IMMEDIATELY AFTER GRADING ----

EXISTING

DIVERSIONS SHALL BE INSPECTED AFTER MAJOR RAINFALL. SEDIMENT AND DEBRIS SHALL BE REMOVED FROM THE CHANNEL AND REPAIRS MADE AS NECESSARY. VEGETATION THAT HAS DAMAGED SHALL BE RESEEDED AS NECESSARY.

6' MIN.

-SLOPE SWALE 1% TO


5% TO TEMPORARY SEDIMENTATION TRAP

CONSTRUCTION SPECIFICATIONS

FLOW

- 1. THE FOUNDATION AREA OF THE DIVERSION SHALL BE CLEARED AND GRUBBED OF ALL TREES, BRUSH, STUMPS, AND OTHER OBJECTIONABLE MATERIALS. 2. MATERIALS REMOVED FROM THE FOUNDATION AREA SHALL BE DISPOSED OF SO THEY WILL NOT
- INTERFERE WITH THE CONSTRUCTION OF OR THE PROPER FUNCTIONING OF THE DIVERSION. 3. THE DIVERSION SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE AND CROSS-SECTION AS REQUIRED TO MEET THE DESIGN CRITERIA. THE DIVERSION SHALL BE FREE OF IRREGULARITIES WHICH MAY CAUSE PONDING OR IMPEDE NORMAL FLOW.
- 4. ALL FILLS SHALL BE COMPACTED AS NECESSARY TO PREVENT UNEQUAL SETTLEMENT IN THE
- 5. ALL EARTH EXCAVATED AND NOT USED FOR THE CONSTRUCTION OF THE DIVERSION SHALL BE SPREAD OR DISPOSED OF SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE
- 6. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER AS TO MINIMIZE EROSION AND AIR AND WATER POLLUTION. ALL APPROPRIATE STATE AND LOCAL LAWS AND
- REGULATIONS SHALL BE COMPLIED WITH DURING CONSTRUCTION. 7. ALL DISTURBED AREAS SHALL BE STABILIZED ACCORDING TO APPROPRIATE BMPS FOR VEGETATION AND MULCHING.

TEMPORARY DIVERSION SWALE



PATH/FILENAME: P:\60301525 - PORTSMOUTH WWTF UPGRADE\SHEETS\BP-2\C\

