

City of Portsmouth
Department of Public Works
Bid#55-15 Harborwalk Park Pier
Addendum #2

Date Issued: April 6, 2015

This Addendum forms part of the original document marked: BID#55-15 Harborwalk Park Pier.

The following questions have been asked and answered:

1. Q: IPE DECKING: What is the minimal length of decking the City will accept?

A: Target a minimum length of 6 feet interior and 5 feet near edges, no more than one per plank run of decking (along a line of decking). The deck varies in width with angle cuts and has the curved outer end, so we will consider unavoidable shorter minimum lengths within the constraints.

2. Q: CITY PROVIDED UNIT PAVERS: What are the dimensions (LxWxThickness) of the city supplied pavers? What is the address where the pavers are located?

A: Per the approved shop drawings the seawall cap granite pavers should be 18" wide, 2" thick and 5 feet long, quantity 16 (may need end cuts to fit actual length). Pavers are stored at Portsmouth DPW, 680 Peeverly Hill Road, Portsmouth.

3. Q: BENT 6B: Does bent number 6B receive any bracing, either Cross or Horizontal?

A: No, Bent 6 (and 6B pony bent) do not have bracing as the overlook is connected to the adjacent seawall.

4. Q: RANGER LENGTHS: Sheets WF-4 & WF-7 of the drawings show the Ranger on the West & East side of the pier. Total length of the Rangers appear to be 130' +/- . Item number 9 "Deck rangers" on the Bid Proposal states an estimated quantity of 270' What is the correct LF of the Deck rangers?

A: **A revised page 11 bid form is issued (see attached)**, changing the bid item 9 quantity estimate to 163 LF based on centerline distance along one edge, around the curved out end, and along the other edge for the finished installed length. With the angled end and curve transition cuts it is expected that the total lumber requirement for fabrication will be somewhat greater depending on off cuts and splice staggers.

All else remains unchanged from original bid document.

Please acknowledge this addendum within your proposal, failure to do so may subject a bidder to disqualification.

END OF ADDENDUM #2

PROPOSAL FORM (continued)

ITEM #	EST. QTY.	UNITS	ITEM DESCRIPTION & UNIT PRICE IN WORDS	UNIT PRICE IN FIGURES	ITEM TOTAL IN FIGURES
1	39	Ea	Support piles (CCA timber SYP)	\$ _____	\$ _____
2	242	Lf	Timber pile caps (CCA timber SYP)	\$ _____	\$ _____
3	33	Lf	Glu-Lam curved pile cap	\$ _____	\$ _____
4	1	Ls	Pile cap hardware	\$ _____	\$ _____
5	1400	Sf	Membrane (Ice & Water Shield)	\$ _____	\$ _____
6	384	Lf	4X8 cross bracing (CCA timber SYP)	\$ _____	\$ _____
7	156	Lf	4X8 horizontal bracing (CCA timber SYP)	\$ _____	\$ _____
8	57	Ea	Bracing hardware (HDG)	\$ _____	\$ _____
9	163	Lf	Deck rangers (Built out of CCA timbers SYP)	\$ _____	\$ _____
10	1344	Lf	3X12 Stringers (CCA timber SYP)	\$ _____	\$ _____
11	1	Ls	Stringer and Ranger Hardware	\$ _____	\$ _____
12	2400	Sf	Ipe Decking (2X6) with hardware	\$ _____	\$ _____
13	1	Ls	Remove, modify and/or salvage existing fencing according to plans	\$ _____	\$ _____